

This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines


Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:


- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + Refrain from automated querying Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search


Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at http://books.google.com/







•			
•			
	•		
		•	
		•	



HANDBOOK FOR TRAVELLERS

IX

YORKSHIRE,

AND

FOR RESIDENTS IN THE COUNTY.

THIRD EDITION, THOROUGHLY REVISED.

WITH MAP AND PLANS.

LONDON:

JOHN MURRAY, ALBEMARLE STREET.

1882.

is right of Translation is reserved

Yorkel

LONDON:

PRINTED BY WILLIAM CLOWES AND SONS, LINITED, STANFORD STREET
AND CHARING CROSS.




PREFACE.

An earnest endeavour has been made to render this Edition more perfect and accurate than its predecessors, so that it may be found more useful to the stranger and traveller, and more reliable to the resident or native of Yorkshire than before. For this purpose most of the Routes have been tested and verified on the spot.

Curtailments have been made in some of the very minute archaeological details, which seemed out of place in a popular guide, so as to make room for more modern and practical information. The Routes also have been adjusted according to the new Lines of Railway opened since the last Edition went to press. But since changes occur so rapidly in every part of England, some errors may still have escaped notice in describing a district of so great extent, and in which the objects of interest are so numerous and so varied; it is therefore requested that notices of such faults or omissions may be sent to the Editor, care of Mr. Murray, 50A, Albemarle Street.

The Editor desires to acknowledge the great courtesy and readiness with which all his inquiries, made in person or by letter, have been received and answered in every part of Yorkshire.

June, 1882.



CONTENTS.

•	
ISTRODUCTION	vii
ROU	TES.
*." The names of places are printed in <i>itali</i> descr	ics only in those routes where the places are ibed.
DUTE PAGE	ROUTE PAGE
1. London to York, by Don-	14. York to Whitby, by Malton
custer and Selby.—(Great	and Pickering 190
Northern Railway) 2	15. Whitby to Stockton-upon-
la. London to York, by Luton,	Tees, by Stokesley (Guis-
Bedford, Leicester, Lough-	borough, Roseberry Topping) 208
borough, and Trent Junc- tion.—(Midland Railway), 76	15A. Whitby to Guisborough and Middlesbrough 216
	Middlesbrough 216 16. York to Darlington, by
2. Doncaster to York, by Knot- tingley.—Bolton Percy 78	Thirsk and North Allerton 218
3. London to Hull, by Don-	17. Stockton to Saltburn, by
caster, Thorne, and Goole,	Middlesbrough and Redcar 230
- Hatfield Chase 85	18. Thirsk to Malton, by Coxuold,
4. Knottingley to Goole, by	Byland Abbey, and Gilling 236
Snaith	18A. Gilling to Pickering, by
5. Milford Junction to Hull,	Helmsley (Rievaulx Abbey),
by Selby and Howden 104	Kirkby Moorside, and Last-
6. Hull, by Hedon and Pa-	ingham—Rail 242 19. York to Boroughbridge and
trington to Withernsea.	19. York to Boroughbridge and
(Spurn Head.) The Hol-	Aldborough 252
derness Coast to Hornsea . 108	20. York to Anaresocrough and
7. Hull to Hornsea and Skipsea 120	Harrogate (Marston Moor) 256
8. York to Beverley and Hull,	21. Harrogate to Pateley Bridge
by Market Weighton.—Also	(Brimham Craggs), Nid-
to Selby 125	derdale
9. Hull to Bridlington, by Be-	22. Harrogate to Northallerton,
verley and Driffield 147	by Ripon, Fountains Abbey, Hackfall, and Tanfield 274
10. Beverley to Bridlington—	Hackfall, and Tanfield 274 23. Northallerton to Leyburn, by
Road 150	Bedale (Middleham, Jer-
Wolds) 152	vaulx Abbey, Hornby Castle) 301
12. York to Scarborough, by	24. Wensleydale. — Leyburn to
Castle Howard and Malton 156	Hawes Junction and Sed-
13. Scarborough to Filey, Flam-	bergh, by Bolton Castle,
borough Head, and Brid-	Ayegarth, Askrigg, Hawes,
lington 181	(Hardrano Force) 312

EOUTE PAGE	ROUTE
24A. Hawes to Muker 322	34. Leeds to Skipton, by Bingley
25. York to Richmond, Swaledale,	and Keighley (Saltaire, Ha-
Reeth, Muker, and Barnard	worth) 442
Castle, by Dalton Junction	85. Leeds to Bradford (Low Moor
and Catteriok Bridge 323	Ironworks) 430
26. Darlington to Barnard Castle	86. Leeds to Bradford and Hali-
(Rokeby), Bowes Castle, and	fax, by Laister Dyke,
Egglestone Abbey 336	Queensbury and Thornton . 437
27. Barnard Castle to Middleton-	37. Leeds to Manchester, by
in-Teesdale, High Force.—	Devisbury and Huddersfield 447
Micklefell 348	38. Leeds to Wakefield (Nostel
28. London to Leeds, (1) by Don-	Priory, Walton Hall) 457
caster and Wakefield; (2)	39. Wakefield to Halifax (Lan-
by Pontefract and Wake-	cashire and Yorkshire Rly.) 466
Solds (2) by Pontation	40. Wakefield to Doncaster, by
field; (3) by Pontefract and Castleford 352	
	Barnsley and Mexborough
29. Leeds to Harrogate (Kirk-	(Coningsborough) 471
stall, Harewood) 372	41. London to Leeds.—(N. Mid-
30. Leeds to Skipton: A. By	land Railway) 479 42. Leeds to Selby, by Milford
Otley and Ilkley (Bolton	42. Leeds to Selby, by Milford
Priory, Wharfedale) 378	Junction 481
31. Skipton to Kettlewell (Upper	43. London to Harrogate, by
Wharfedale) 897	Tadoaster and Wetherby . 484
32. Skipton to Ingleton, by Settle	44. Huddersfield to Sheffield, by
(Malham, Gordale, Victoria	Penistone and Wortley 490
Cave). — (Midland Rail-	45. Sheffield to Doncaster, by
way) 402	Masborough (Rotherham,
32A. Skipton to Clapham, Ingle-	
ton, Kirkby Lonedale.—	46. Sheffield to Barnsley (Eccles- field)
The Yorkshire Caves 413	field) 514
33. Settle to Chatburn (Gisburne,	47. Rotherham to Bawtry, by
Sawley Abbey) 419	Tickhill (Rocks Abbey) 516
* • • • • • • • • • • • • • • • • • • •	•
INDEX	519
	
PLA	NS.
1 12	
CITY OF YORK	to face 18
YORK MINSTER	21
RIPON CATHEDRAL	276
FOUNTAINS ARREY	
	28/

INTRODUCTION.

EXTENT AND	GENE	BAL	Сна	BACTI	ER	••	••	••	.,	••	Page Vii
GEULOGY	••	••	••	••	••	••	••		••	••	ix
HISTORY	••	••	••	••	••	••	••	••	••	••	xiii
ANTIQUITIES	••	••	••	••		••	••			••	xxiv
RESOURCES AN	ND MA	NUF.	ACTU	RES	••	••	••	••	••	••	xxxi
Travklieb's	Vikw	AND	Scr	ENERY		••	••	••	••	x	xxviii
SKELETON TO	URS	••	••	••	••	••	••	••	••	••	xlix

[In the following Introduction reference is made to the Routes in which the places mentioned are described. The reader will find the exact page by turning to the Index.]

EXTENT AND GENERAL CHARACTER.

§ I.—Yorkshire—

"A kingdom that doth seem, a province at the least,
To them that think themselves no simple shires to be"—

Drayton, 'Polyolbion,' Song 28—

is, it need hardly be said, the largest shire in England. It contains nearly two million of statute acres more than either Lincolnshire or Devonshire, the two English counties of next importance. It is about the size of the entire Peloponnesus; is half as large as Holland; and very nearly half as large as modern Belgium. "One may call and justify this," says Fuller, "to be the best shire of England."

§ II.—The size and population of Yorkshire (as gathered from the census of 1871) are as follows:—

Area in aquare miles.
5961

Area in statute acres. 8,882,851

Population. 2,886,309.

Lincolnshire contains 2611 square miles, or 1,739,812 statute acres, wi ha population of 404,143; Devonshire 2585 square miles, or 1,657,180 statute acres, with a population of 584,873. Taken according to the Ridings, the population of Yorkshire is—

			1881.			1871.			1861.
East Riding		••	365,028	••	••	268,466	••	••	274,425
North Riding	••	••	346,147	••	••	293,278	••	••	211,109
West Riding		••	2,175,134	••	••	1,874,611		••	1,530,007

§ III.—The county, which is nearly conterminous with the ancient Deira (see post, History) was no doubt known as "Yorkshire" before the Conquest, taking its name of course from the great city which, from the days of the Romans, had been the capital of the north, and which itself, seems to have been named from the river on whose banks it etands. (See York, Rte. 1.) "Eoferwic-scire" occurs in a charter of the Confessor's.—Kemble, vi. 203. At what period the division into the three ridings was made, whether by Anglians or Danes, is not certain. In its present form, the word is a corruption of "Trithing," a third part or division. ("Thridjungar"—thirdings—occur as land divisions in South Norway, where are also found "halfur," halvings, and "florhjungar," quarterings.) The three ridings, very unequal in size, meet at the city of York. The West Riding, one of the great centres of English manufacture, is by far the largest and most populous; but it can hardly be said to be more full of interest for the tourist than the two others. The vast surface of Yorkshire, with its great extent of seaboard, is in effect an epitome of England, whatever is excellent in the whole land being to be found there.

§ IV.—To the east, and partly on the north, Yorkshire is bounded by the sea. The Tees, from its mouth nearly to its sources, forms the rest of the northern boundary, and separates Yorkshire from Durham. The western boundaries, beyond which lie Westmoreland and Lancashire, run for the most part along the mountain ridges; and the lines are continued S.W. and S. along similar high ground, dividing Yorkshire from Lancashire and Derbyshire. Part of Nottinghamshire succeeds on the S.E.; and the north of Lincolnshire is separated from Yorkshire by the Humber. The natural divisions of the county are sufficiently marked. A broad valley, or rather a broad tract of rich level, generally known as the Vale of York,-pronounced by M. Bunsen "the most beautiful and most romantic vale in the world, the vale of Normandy excepted,"-runs through it from S. to N. Two very distinct districts may be traced on either side of this great vale, which is bounded by their high ground. East of the Vale of York, are, S. the group of chalk hills called the Wolds, and N. the Hambledon Hills and the Moors of Clevelands. The Vale of Pickering divides the Wolds from the northern hills. W. of the Vale of York are, N. the group of northwestern hills, of which Mickle Fell is the highest summit, and which are pierced by the most beautiful and interesting of the dales—Wenaley-dale, Swaledale, and others; and S. the group of south-western hills, forming the district of Craven, the Moors of Halifax, and the Yorkshire border as far as Stanedge. Ribblesdale, a comparatively low region, sufficiently marked, though not so decidedly as the Vale of Pickering, may be regarded as separating these western districts, the mountains of which form a portion of what is known as the "Backbone of England," the so-called Pennine chain, which extends nearly from the Scottish border to the Peak of Derbyshire.

§ V.—The lands of Yorkshire, as Professor Phillips has pointed out, rise in masses toward the west. Hence its many rivers find their way, almost without exception, to the German Ocean; the Ribble, on its western border, being the single stream of importance which falls into the Irish Sea. (The Lune, which receives some Yorkshire tributaries, rises in Westmoreland.) The great rivers—the Tees, the Swale, the Ouse, the Wharfe, the Derwent, the Aire, the Calder, and the Don-have been, at all periods, the centres of Yorkshire life and civilization. The most important Roman stations were formed on their banks and at their fords; the strongest baronial castles rose near them: Augustinians and Cistercians took possession of, and brought into cultivation, the most secluded and most beautiful portions of their valleys; and in more recent periods the "labours of the loom," and the tall chimneys and ceaseless clang of every kind of factory have established themselves in the same river-valleys. The same advantages have induced the population to gather, age after age, about the same centres; and the result, especially in the manufacturing districts, is such a singular mixture of the present and the past as perhaps no other part of England can show.

GEOLOGY.

- § VI.—The geology of Yorkshire has been so exhaustively treated by Professor Phillips, both in his larger work ('Geology of Yorkshire') and in his 'Rivers, Mountains, and Sea Coast of Yorkshire,' that it is only now possible to describe it by condensing Mr. Phillips's descriptions. Those who wish for more information than can be given here must refer to the works mentioned above.
- § VII.—The great Vale of York, stretching directly through the centre of the county, is occupied entirely by the red sandstone series of rock, resting, along its western border, from the southern limit of York-

shire to a point between the rivers Ure and Swale, on a much narrower belt of magnesian limestone. The red sandstones are overlaid, east, by the lias, which extends down the valley of the Esk nearly as far as Whitby, and appears also in patches along the coast and inland. On the lias, and forming the mass of the north-eastern hills, rest the series of Bath and Oxford colites, the latter being confined to a district extending from Helmsley to the sea at Filey, and again in a south-easterly direction from Helmsley to the lower course of the Derwent. A patch of Kimmeridge day intervenes between these Oxford colites and the chalk, which forms the Wolds. Holderness, marked by a line drawn from Bridlington to Hull, a little W. of the Hull river, is entirely cainozoic, a district of submarine forest and of rolled fragments brought from various and distant regions. The marshes through which the Ouse, the Derwent, and the Don flow in their lower courses towards the Humber are of still more recent growth.

The coal formation underlies the magnesian limestone from the border of the county as far as Leeds, then turns W. to a point beyond Bradford, and, winding round S.E. by Huddersfield and Penistone, again reaches the Yorkshire border S. of Sheffield. It is bordered W. by the millstone grit series, which extends irregularly quite across the county, and is pierced by large masses of Yordale and Scar limestone. The grits and limestones form the mountainous and picturesque districts of the S.W. and N.W. A small patch of Silurian rock extends from Westmoreland into Yorkshire by Sedbergh and Dent, and thence round to Settle. The upper valley of the Tees is of volcanic trap, and a remarkable basaltic dyke extends from Cockfield Fell in Durham across the N. of Yorkshire.

nearly as far as Whitby.

- § VIII.—To these various formations are due the very distinct character of the great natural divisions of Yorkshire already noticed. "The mineral qualities and position of rocks, with the accidents to which they have been subjected, give us the clue to the forms of mountains and valleys, the aspect of waterfalls and rocks, the prevalent herbage, and the agricultural appropriation. Even surface colour and pictorial effect are not fully understood without geological inquiry. While limestone 'scars' support a sweet green turf, and slopes of shale give a stunted growth of bluish sedge, gritstone 'edges' are often deeply covered by brown heath, and abandoned to grouse, the sportsman, or the peat cutter. In a word, geological distinctions are nowhere more boldly marked than in Yorkshire, or more constantly in harmony with the other leading facts of physical geography."—Phillips.
- § IX.—Excellent collections, illustrating the geological history of Yorkshire, with the fossil remains characteristic of the various formations, exist at York, at Leeds, at Scarborough, and at Whitby. The chalk is rich in sponges, marsupites, apiccrinites, echinides, and belemnites. "Its

couthern coal formations.

numerous bands of flint modules are in a lower part of the mass than in other parts of England. Sponges are not usually found in these nodules, but lie in the chalk itself (the upper part), and are remarkably distinct in appearance and character, because their tissue is silicious."—Phillips. The isas, besides pentacrimites and star-fishes of great beauty (as at Staithes), abounds in its great characteristic reptiles,—Ichthycsaurus, Plesicsaurus, and Teleosaurus. The coal-measures (described more fully, post, among the 'Resources and Manufactures of Yorkshire, * xxxvi, pest, in plants, and are characterised by a few shells,"—Aviculo-pecter pappyruceus, Goniatites Listeri, Nastilus Rauvsoni, and Orthocorus Stein-

Accept,—which are either rare, or are altogether wanting, in the more

§ X.—The Trap Dyke, which runs across N.E. Yorkshire, and the great displacement in the mountain limestone known as the Craven Fault. are marked features in the geology of the county. The trap, or basaltic duke, of dark-coloured rock, nearly vertical in position, and generally about 60 ft. in horizontal thickness, although it is not in some places exposed at the surface, may with tolerable certainty be presumed to extend continuously from Cockfield Fell in Durham, across the Tees, by way of Stainton and Great Ayton, to Eskdale and Gothlanddale, terminating within four miles of the sea a short distance W. of Whitby. "Its total length is about 60 miles. The strata which it penetrates are, in Durham, the mountain limestone, the millstone grit, and the coalmeasures; in N. Yorkshire, the new red sandstone, the lias, and the lower colite. By some geologists it is supposed to be connected with the Tecadale whinsill; but though it is quite possible that it may owe its orgin to the same centre of igneous disturbance, it is quite evident that the Cleveland dyke is much later in the date of its protrusion than the Teesdale mass. Generally its sides are not quite perpendicular, and the beds on the N. of it are somewhat depressed. In some places a tendency towards the prismatic type of structure is observable in its masses. In the neighbourhood of the Tees it is quite overlaid by the glacial diluvium. In the Ayton tract it forms a conspicuous ridge, and st Language and in Kildale it is extensively quarried for roadstone. From this last-mentioned dale its course lies along the dale of the Eak for some distance in a line not far from the river. At Egton Bridge it forms a steep scar in Limber Hill, on the S. side of the Esk, and from thence turns S.E. to the head of Iburndale, and at last, after becoming considerably reduced in thickness, it is lost amongst the thick sandstones of the moorland mass not far from the point where the main branch of the Derwent takes its rise,"-J. G. Baker, 'North Yorkshire,' p. 29.

§ XI.—The Crowen Fault, "one of the most magnificent dislocations in England," writes Professor Phillips, is a vast displacement of the mountain limestone, which has produced the cliffs of Malham and of Gordale, and to which Craven is indebted for the most striking and picturesque features of its scenery. The southern boundary passes from Threshfield on the Wharfe to Malham, and is continued thence N. to

Settle. It then borders the river Ribble as far as Stainforth, where the slate makes a great indentation. Beyond, it again runs parallel to the river, and fills the valley above Horton; thence it winds round by Ingleborough. Another line of dislocation runs from Settle by Giggleswick Scar, Feizor, Austwick, and Newby, to Ingleton. Both lines of fault are marked by great scars of limestone, produced by the violent dislocation and drop of the rock.

"With regard to the extent of the dislocations caused by the Craven Faults, it is found that the northern drop is about 300 ft., whilst the total depression under Ingleborough is not less than 3000 ft., about Settle 1000 ft., and it diminishes toward Grassington, where numerous other dislocations confuse but do not destroy its effects. The limestone beds are usually removed from the axis of disturbance; enough, however, can be seen to assure us that, while the elevated beds rise slightly to the fault, the depressed beds fall steeply to the S.; they are nowhere vertical, and the angle of their inclination continually diminishes eastwards."—W. Houson.

§ XII.—A remarkable peculiarity of the Wolds and of the Cleveland moorlands is the steep escarpment, towards the N., of the hill ranges. This is very conspicuous on the northern and western borders of the chalk, where it rises from the Vale of Pickering and sweeps round toward the Vale of York; and on the northern border of the Cleveland hills, as well as in the calcareous hills on their southern border, ranging from Scarborough to Hambleton End. (See Pickering, Rte. 14.) The view of this latter range, from the Cawthorne Camps, near Pickering, or from any one of the adjoining heights, precisely resembles the view from a sea-cliff, with a long line of bluffs projecting into the water. Professor Phillips and other geologists have looked on these escarpments as having at one time been true cliffs, long washed by a primæval ocean, and worn into their present forms by its waves. There is now, however, considerable doubt as to the truth of this explanation; and Mr. William Topley, in a paper on the Physical Geography of East Yorkshire (Geological Magazine, October, 1866), suggests that the "origin of the present scenery of Yorkshire is due, in the main. to sub-aërial denudation, and not to marine action." The ground on which he builds his theory is briefly as follows:- The Yorkshire escarpments. "in common with all analogous hills in England, have this striking character. The same bed, or its representative, crops out at about the same height of the escarpment all along its course. Thus, in the N. Cleveland hills, the 'ironstone and marlstone series' crop out some way down the side, and the hills are capped by the same bed of sandstone (inf. colite). In other words, these escarpments run along the strike, and their scarped sides face the dip. Thus, if the beds are dipping to the south, the scarped side will face the north, and the escarpment will run east and west. Now, how can this fact be accounted for if these escarpments are old sea-cliffs? To learn what a lias sea-cliff is like, we have only to examine the present coast-line of Cleveland. Here the beds are seen to dip in the cliff section, and therefore the cliff is not

formed along the strike. Moreover, beds are seen to dip one under the other and disappear, so that a cliff section at one place may give a set of beds quite different from another section taken a few miles off. Thus, on the Yorkshire coast we pass in the same line of cliffs from lias in the N. through all the colite series in succession, to chalk in the S. Such is never the case with an inland escarpment. This presents the same set of beds throughout its entire length. Now, since escarpments run along the strike, whilst the present sea-cliffs rarely or never do, it would seem that we must no longer look to marine action as the mode of formation of these escarpments. They are assuredly not 'river cliffs,' since rivers by no means always run parallel to them or even near them. There remain then only pure sub-aërial agencies to account for them.

HISTORY.

- § XIII.—Although modern researches into the contents of Yorkshire "houes" and tumuli, especially of those on the Wolds and the Cleveland moors, have rendered it certain that the country was occupied, perhaps at successive periods, by at least two very distinct races, the Romans seem to have included the whole native population under the general name of Brigantes. They are first mentioned by Tacitus (Ann. xii.), and the word has been explained as signifying "mountaineers—highlanders." Braighe (Gaelic) signifies "high grounds;" Brigant (Cymric) is a mountaineer. It is uncertain whether the Brigantes belonged to the Gaelic or Cymric division of the Celts.
- § XIV.—About a.p. 50, more than a century after the first landing of Cessar in Kent (B.C. 55), and after the greater part of S. Britain had been subdued, the Roman legionaries appeared for the first time among the Brigantes. Ostorius Scapula is then said by Tacitus to have marched into their territory to "suppress internal discord." But they continued independent until about A.D. 70. Cartismandua, their powerful queen, is infamous for the betrayal to Rome of her relative Caractacus (circ. a.p. 51), and was afterwards driven away by the Brigantes themselves, headed by her husband Venutius. It is possible that their country was left unattacked by the Romans until, between A.D. 70-78, great part of it was conquered by Petilius Cercalis. In the following year, 78-79, the conquest of the whole district was confirmed and completed by Agricola. For the history of all this period, see Merivale's 'History of the Romans under the Empire,' vol. vi. chap. li., and vol. vii. chap. lxi.

The Brigantian territory stretched from sea to sea, including, besides Yorkshire, the northern parts of Lancashire, and possibly a portion of Derbyshire. But their most important towns and stations were in Yorkshire; and after the Roman conquest and occupation the whole of that district was speedily covered with roads, permanent camps, and cities, in which the refinements and civilization of Rome were not less conspicuous than in any other portion of the empire. It appears certain that throughout the Roman period the province which comprised

the country of the Brigantes was the most flourishing, the most important, and, in relation to the Government, the most central portion of Britain. York, "Altera Roma," was the great resting-place of the emperors on their visits to this island; and at the time of the compilation of the Notitia the 6th Legion had held that city uninterruptedly for three centuries, and still sent its troops thence to garrison the lesser stations in Valentia and along the line of the great North Wall. (See Eburacum, York, Rtc. 1.)

- § XV.—The history of North Britain, after the departure of the legions, is altogether obscure; and the beginning and early progress of no Anglo-Saxon kingdom is so difficult to trace as that of Northumbria. Ida is said to have "assumed the kingdom" (Sax. Chron. sub anno) in 547, nearly a century after the arrival of Hengist (A.D. 449). Matthew of Westminster (or the compilation made at St. Alban's under the direction of Matthew Paris which passes by his name) asserts that Ida was chosen by the "process Anglorum;" and it would appear that the Anglians had made good their footing in Northumbria some time before. His 12 sons followed him, according to the same authority, with 40 ships, and landed at Flamborough Head (apud Flemesburg applicuerunt, p. 193, ed. 1578), and, though not without a severe struggle, the Britons of Cumbria and Bernicia were gradually compelled to retire or to submit themselves to the new comers. The little kingdom of Loidis or Elmete (see Rts. 28) was not incorporated in that of Northumbria until about the year 616. At what time the northern and southern portions of the Northumbrian kingdom became known as Bernicia and Deira is not evident. In the 'Gododin' of Aneurin (see Catterick, Rte. 25), and in other Welsh poems, they are called "Deivyr and Bryneich;" but whether these names are Celtic or Teutonic is uncertain. Bernicia possibly represents the Celtic name of the district; Deira is more probably the "country of wild animals,"—the "hunting-ground,"—from the A.-S. deor. The boundaries of these divisions no doubt varied at different times, although the Humber was always the southern border of Deira, and the Tyne seems to have been the usual line of division between Deira and Bernicia. the absence of any light from Dr. Guest through this most obscure period of Northumbrian history, some assistance will be found in the Tables of Anglo-Saxon History' appended by Sir Francis Palgrave to his 'History of the English Constitution.'
- § XVI.—The Northumbrian kingdom, of which the capital, as in the Roman times, was York, was the most powerful in England for a period of 50 years (620-670), throughout the reigns of Edwin, Oswald, and Oswi, 3 of the 7 Bretwaldas enumerated by Bede. Under the first of these, Edwin, Christianity was introduced among the heathen Anglians by Paulinus. The history of the mission of St. Paulinus and of the royal conversion, followed as usual by that of the king's principal followers and the great mass of his subjects, can hardly be traced so minutely as the story of St. Augustine in Kent; but the sites connected with the foundation and gradual establishment of the new faith retain some very interesting memorials of their early days, and are well worth

visiting. (See especially York, Rts. 1; Goodmanham, Rts. 8; Hackness, Rts. 12; Lastingham, Rts. 14; Whitby, Rts. 14; and Catterick, Rts. 25. Bede (Hist. Eccles.) is of course the chief authority for all this period.) The Anglians, who peopled East Anglia and Northumbria, from whatever part of Europe they may have come, were more akin to the Danes in character and in language than the Saxons who settled in S. Britain; and the Danes accordingly found more inducement, and probably found it easier, to establish permanent colonies among them than in other parts of England. The first ships of these "heathens" arrived, according to the Sax. Chron., on the coast of Wessex in 788. In 793 Lindisfarne was destroyed by them; and from that time they appeared more and more frequently in the Humber, plundering the country on both sides, until in 867 their army attacked York, and entirely routed the host of the Northumbrians. In 875 Northumbria is said to have been "conquered" by the great Danish leader Halfdan; and in the following year he divided the Northumbrians' lands among his followers. " who from that time were ploughing and tilling them (Sax. Chron., s. a. 876). Henceforth the Danish settlements in Northumbria were permanent; and the termination by, marking a Danish house or village, is more frequent along the rivers that flow into the Humber than in any other part of England. "Kirk,"as in "Kirkby Moorside,"—is another Danish indication, of which 19 instances occur in Yorkshire. It is not always, however, easy to distinquish between the Anglian of the first colonists and the Danish of the new comers; and, in further complication, the Norwegians, who established themselves on the western coasts, spread over Cumberland and Westmoreland, and descended thence into the Yorkshire dales, where, besides many personal names, the waterfalls, as in Norway, are still called "forces" or "fosses," and the mountains "fells." Norwegians may also have settled in other parts of Yorkshire, since many of the northern kings who ruled for a time in York,—Olaf, for example, and Eric Blodsex, the son of Harald,—came from Norway, and must have brought with them numerous followers. An accurate distinction between the 3 tongues-Anglian, Danish, and Norwegian-and the assigning to each its proper share in the naming of Yorkshire places, is a task which has still to be performed by local etymologists. Worsase ('The Danes in England') probably gives far more to the Danes than is really due to them. Assistance of the highest value has been furnished by a 'Glossary of the Cleveland Dialect, by the Rev. J. C. Atkinson. long vicar of Danby, near Castleton, in the centre of the district to which he has given so much careful attention. An excellent and exhaustive 'History of Cleveland' has been also published by him. The author is a sound northern scholar, and his knowledge of Danish in all its forms has enabled him to illustrate the cognate dialect of Cleveland in a very remarkable manner.

The Danish "kingdom" of Northumbria gave "fealty oaths" to Alfred and to Athelstane, and afterwards to Eadmund and to Eadred.

When the Danes had become uppermost in England, Cnut assigned the kingdom to a certain Eric, and thenceforward the country formed one of those great earldoms which arose as the power of the king became less evident. Tostig, the brother of Harold, was Earl of Northumbria under the Confessor, and a remarkable record of him still exists at Kirkdale (Rte. 18a). In 1065 he was expelled, and "Morkere, son of Earl Ælfgar," was chosen earl. Tostig afterwards fell at Stamford Bridge fighting on the side of Harald of Norway (Rte. 8); and Morkere and his brother Eadwine, the two most powerful earls in the north, after submitting to the Conqueror, "fled away from him" in 1072. Eadwine was killed by his own men. Morkere joined Hereward in Ely, but finally again submitted to the "alien king."

& XVII.—It was not until the summer of 1068 that William led his army to York and built his castle there. In October of the following year the associated Northmen and Northumbrians came up the Humber. attacked and took York, and burnt the city. (See York, Castle, Rte. 1.) The famous devastation of Northumbria by the Conqueror's army followed. It continued throughout the whole winter ("per totam hyemem devastare, hominesque trucidare, et multa alia non cessabat agere," says Hoveden, of the Conqueror), and was succeeded by a terrible famine which continued for 9 years. "Terra cultore destituta, lata ubique solitudo patebat per novem annos. Inter Eboracum et Dunelmum, nusquam villa inhabitata; bestiarum tantum et latronum latibula magno itinerantibus fuere timori."—Hoveden. From this time the name of Northumbria, or "Northumberland," is confined to the country beyond the Tyne, the ancient Bernicia; and Yorkshire is henceforth known by its present name,—in Domesday "Everwicscyra." (For a full history of the Conqueror's proceedings in the north, see Freeman's Norman Conquest, vol. iv.)

§ XVIII.—The most powerful Norman houses established in Yorkshire after the Conquest, or within the next half-century, were those of Percy, of Lacy, of Mowbray, of Clifford, and of Alan of Brittany at Richmond. At a later period appear the Scropes of Upsall and Bol-William de Perci is said to have married a daughter of the great Saxon Earl Gospatric, of whose lands at Seamer, near Scarborough, he had taken possession. He received from the Conqueror 86 lordships in Yorkshire, including Topcliffe (Rte. 22) and Spofforth (Rte. 43), where were the chief Percy strongholds, until, in 1309, Antony Bek, the great Bishop of Durham, granted and sold the barony of Alnwick to Lord Henry Percy. Henceforth they are truly "Percies owte of Northumberlande," although they still retained their Yorkshire lordships and influence. The Lacy fee extended for the most part round Pontefract (Rte. 28); but eventually their lands stretched across the country almost without a break, as far as Clitheroe Castle, their Lancashire stronghold; the great Mowbray Castle was at Thirsk (Rte. 16); and the northern portion of the so-called plain of York—the comparative level or valley between the hill-ranges E. and W.—was almost entirely in their hands. The Cliffords from Skipton Castle (Rte. 30) ruled much of Craven and the adjoining country, and the "Honour" of Richmond (Rte. 25) was supreme in the N.W. For Bolton and the Scropes see Rte. 24.

& XIX.—These great Norman lords, and their sub-infeudatories, seem to have been active in church-building after Yorkshire had somewhat recovered from the Conqueror's devastation. To them are due the many small Norman churches noticed in the following division (Antiquities, -- ecclesiastical section). Every religious house in the county (Beverley, Rtc. 8, which William is said to have spared, was a college of secular canons) had fallen during the troubles preceding and following the Conquest. St. Mary's at York (Rte. 1) and Whitby (Rte. 14) were refounded by certain Benedictines who came from Evesham. For the very curious story of the foundation of Selby, see Rte. 1; but it was not until the 12th century that Yorkshire became rich in those great monastic houses which from that time formed one of the chief testures of the county. Thurstan Abp. of York (1119-1140), the friend and correspondent of St. Bernard, was a most powerful patron of the Cistercians, whose first Yorkshire house, Rievaulx, was founded in 1131. It it scarcely too much to assert, as Mr. Raine ('Lives of the Archbishops of York') has done, that, after St. Bernard, Thurstan was at this time the most active supporter and reformer of monachism in Europe. For the history of foundations influenced or assisted by him, see especially Rievaula (Rte. 18A) and Fountains (Rte. 22). (See also, for the general history of monarchism in Yorkshire. Raine's Lives of the Archbishops' and the 'Memorials of Fountains Abbey,' edited, with most valuable notes and introductions, by Mr. J. R. Walbran, for the Surtees Society.) The Cistercians had in Yorkshire 8 houses for men-Rievanix, Fountains, Byland, Sawley, Roche, Meaux, Kirkstall, and Jorevaulx-besides 11 for women (none of which were of great wealth or importance). The 3 great Benedictine houses were St. Mary's at York, Whitby, and Selby. They had also 13 priories or lesser houses, some of which were for women. The Cluniacs had only 2 houses in Yorkshire—at Pontefract and Monk Bretton. The Carthusians also had but 2-st Hull and at Mount Grace. There were 11 houses of Augustimians, the most important of which were Guisborough, Nostel, Bridlington, Bolton, Kirkham, and Newburgh. The Premonstratensians were established at Easby near Richmond, at Coverham, and at Eggleston. There were 4 houses of Gilbertines in the county, of which Malton was the most important. The Dominicans, Franciscans, and other friers were well represented in the principal towns, and had altozether 28 houses.

The only mitred abbots N. of the Trent were those of St. Mary's, York, and of Selby. St. Mary's was the wealthiest abbey in Yorkshire, its rental at the Dissolution being 1650%. Fountains, with a rental of 998%, came next; then Selby, 729%; and then Guisborough, 712%. The power and resources of a great monastery, however, can hardly be judged from rental alone, especially from rental as computed by Henry VIIL's commissioners; and it is probable that, if St. Mary's received a larger apparent income, Fountains, from the vast extent of its lands and [Yorkshire.]

its enormous property in stock, was of scarcely less weight and importance. All the Cistercian houses were rich; and although the Augustinians possessed stately priories and were very wealthy, it would seem that the former order was, on the whole, the most powerful in the

county.

The creation of a second metropolitical see at York formed part of Pope Gregory's original plan for the ecclesiastical rule of England. (Beds, H. E., l. i. c. 29.) For the subsequent disputes and arrangements between York and Canterbury, see Rte. 1, York (Minster, § I.). Mr. Raine's 'Lives of the Archbishops of York' contains a great mass of information on this subject.

§ XX.—The most important events in the history of Yorkshire after the Conquest have been noticed at length in describing the different places with which they are connected. It is sufficient to mention here the battle of the Standard, A.D. 1138 (Rte. 16); the Scottish forays under the Black Douglas in 1322, when the Earl of Richmond was taken prisoner in a skirmish among the hills near Byland, and Edward II. was compelled to escape in haste from the neighbourhood (see Rtes. 18 and 18A, Byland, Rievaulx); the rising in the same year, 1322, of the Earls of Lancaster and Hereford against Edward II.; the battle of Boroughbridge (Rte. 19), and the execution of the great Earl of Lancaster at Pontefract (Rte. 28); the landing of Henry of Bolingbroke (Hen. IV.) at Ravenser or Ravenspurne (Rte. 6); the rising of the northern earls and of Archbishop Scrope against Henry IV. (Rte. 1, York, Minster, § XX., and Bishopthorpe); the battle of Wakefield (Rte. 38); the skirmish at Ferrybridge (Rte. 2); and the subsequent Battle of Towton (Rte. 43). The close connection of Richard III, with Yorkshire has been referred to under Middleham (Rte. 23).

The Reformation, and events connected with it, gave rise to two most serious disturbances in the northern counties—the "Pilgrimage of

Grace" in 1536, and the "Rising of the North" in 1569.

§ XXI.—The rising called the "Pilgrimage of Grace" was due mainly to the disaffected condition of the northern monks and clergy, who, always violently opposed to the changes in religion, had (1536) been greatly excited by the commission for suppressing the lesser monasteries; but it also owed much of its strength to the discontent of the commons in consequence of enclosures and of alterations in their old system of life, and to the jealousy and dislike of the old nobility to the rise of new men, like Cromwell, which had followed in the train of the Reformation. The first outbreak occurred (October, 1536) at Louth and at Lincoln, and the Duke of Suffolk was sent to suppress it; but it had been premature and without organization, and the men who had gathered dispersed within a fortnight. In Yorkshire it was different. Almost by accident, as it appears, Robert Aske, the second son of Aske of Augnton on the Derwent (see Rte. 8), was taken by the rebels as he attempted to pass through Lincolnshire during the insurrection, and compelled to take the oath which bound him to their cause. After a few days, and still, as he declared, undecided, he returned into Yorkshire,

only to find the whole county in movement. His own name was the watchword; and in his absence, a letter bearing his signature had been sent throughout Yorkshire calling on the commons to rise in defence of the Church. Lord Darcy, to whom the King had written, and who was at this time the feudal superior of the E. Riding, was in reality favourable to the cause of the insurgents, but played into their hands without so declaring himself. He shut himself up in Pontefract Castle with only 12 followers, and without provisions. Meanwhile the great body of insurgents met on Market Weighton Common. Aske was acknowledged as the commander of the entire force. Sir Thomas Percy, brother of the Earl of Northumberland, joined them, and they moved direct on York, which at once surrendered. Thence they marched to Pontefract, where they compelled Lord Darcy to surrender the castle, and he, with the Archbishop of York, who had joined him there, and all others within the walls, took the popular oath. The Earl of Shrewsbury was advancing with the king's troops; but the passes of the Don were secured, and he was compelled to remain at Doncaster. Hull was taken by the insurgents; who, in the W., were laying siege to Skipton Castle, (For a story connected with this siege, see Skipton, Rte. 30.) In the mean time an enormous gathering of the great northern families had taken place at Pontefract. The Cliffords, the Dacres, the Musgraves, and the dving Earl of Northumberland (his brother had joined it), alone were absent; and from Pontefract they marched in three divisions upon Doncaster, where the Duke of Norfolk had joined Shrewsbury. intended, as Aske told Lancaster Herald, whom Shrewsbury had sent to Pontefract, "to go to London of pilgrimage to the King's Highness, and there to have all the vile blood of his council put from him and all the noble blood set up again, and also the faith of Christ and his laws to be kept, and full restitution of Christ's Church of all wrongs done unto it; and also the commonalty to be used as they should be." They had with them the banner of St. Cuthbert, and another displaying, among other devices, the 5 wounds of Christ. Each of the insurgents were a badge also crossed with the 5 wounds.

At Doncaster they found the river heavily swollen; and after some discussion a conference (Oct. 26, 1536) took place on the bridge between certain of the leaders on both sides. The insurgents seem to have been deceived by their great strength; and instead of forcing the passage of the Don, they agreed that Sir Robert Bowes and Sir Ralph Ellerkar should carry their demands to the king, whilst Norfolk undertook to escort them in person. In the mean time the musters on either side were to be disbanded. Henry received the messengers graciously, but detained them a fortnight, gained them over to himself, and sent back by them letters to others of the rebel leaders, which were meant to produce a similar result. Meanwhile disturbances continued in many parts of Yorkshire. The monks were replaced in their abbeys; and it began to be feared that Aske, Lord Darcy, and Sir Robert Constable, the 3 principal leaders, would cross the Humber and advance southward. The king's delay in replying to the representations made by the mes-

sengers greatly excited the insurgents. Aske again collected his army (Nov. 27); and a council of notables and convocation of the clergy was assembled at Pontefract. Aske, with 34 peers and knights, and others of the leaders, sate in the castle hall; the Archbishop of York and his clergy in the church below the castle. (See Rte. 28.) The archbishop, however, who had taken the popular oath under constraint, declared in his opening sermon that the assembly was unlawful and the insurrection traitorous. He was dragged out of the pulpit and nearly killed; and after he had been carried off by a party of his friends, the clergy drew up a list of articles pronouncing successively against every step of the Reformation. The king's commissioners had in the mean time arrived at Doncaster, and brought with them what Aske and the rebel leaders seem to have understood as the grant of their entire petition. A conference again took place; and at its close, Aske and the others pulled off their badges and declared that "henceforth they would wear no badge but that of their sovereign lord." All that Henry had really granted, however, was a general pardon, and the promise of a parliament at York in the following summer. The great Council of the North was also to be established at York, with the Duke of Norfolk as its first

president.

Aske had been sent for to London by the king, who desired to see the man who had almost shaken his throne. He was well received, and gave a full account of the rising to Henry; but on his return northward he found the counties he passed through full of angry excitement at the doubts which everywhere prevailed as to the intentions of the king; and he wrote to Henry stating plainly what he himself thought, that a second outbreak was imminent. It occurred accordingly; and Sir Francis Bigot, of Mulgrave Castle, made himself its leader for the short time it lasted. Nothing was effected by it, except the affording of an excuse to the king for withdrawing his concessions. Norfolk arrived at York with orders to punish all offences committed after the Doncaster conference. Fresh disturbances took place. Martial law was proclaimed in northern Yorkshire and the neighbouring counties. Seventy-four persons, including many clergy and monks, were hanged in various towns of Cumberland and Westmoreland, and the rebellion was finally extinguished. Aske, Darcy, and Constable were arrested and taken to the Tower—how far having compromised themselves in the later rising. or with Reginald Pole, who was now at Liège, is quite uncertain. They were tried and executed - Darcy in London, Constable in Hull, and Aske at York. Whatever may be thought of other leaders, there can be little doubt that Aske himself was, in Mr. Froude's words, "a brave, simple, noble-minded man," and perhaps as little that he was judicially murdered. There is no better or more complete narrative of this great insurrection than will be found in Froude, 'History of England,' vol. iii., chaps. 13 and 14.

§ XXII.—After the suppression of this insurrection the so-called "Council of the North" was established by Henry VIII., with its head-quarters at York. It had a criminal jurisdiction in Yorkshire and the

4 more northern counties as to riots, conspiracies, and acts of violence. It had also a certain civil jurisdiction, which Lord Wentworth, afterwards Earl of Strafford, after his appointment as President of the Council in 1628, spared no pains to enlarge, and procured for this purpose a special commission, the effect of which was to deprive all these northern counties of the privileges of the common law. The Long Parliament, when it abolished the Star Chamber (1641), annihilated, by the same act, the arbitrary jurisdiction of this Northern Council, together with that of the Council of Wales. The best lawyers, including Sir Edward Coke, had always looked on the legality of such tribunals as, to say the least, extremely problematical. (See Hallam, 'Constitutional History,' ii. 43, 99.)

§ XXIII.—Of the rebellion in 1569, generally known as the Rising in the North, the best and fullest accounts will be found in Froude's 'History of England,' vol. ix., and in 'Memorials of the Rebellion,' edited by Sir Cuthbert Sharp. The proposal for a marriage between Mary Stuart and the Duke of Norfolk, which had been first broached during the sitting of the commission at York in October, 1568, had led to fresh combinations and conspiracies. Preparations had been made for a general rising in the eastern counties, where Norfolk was supreme, and in the N. of England, where the great lords were nearly all Catholics. The objects were the liberation of Mary and her recognition as next heir to the crown, the deposition and probably the death of Cecil, and the restoration of the "old religion." But Norfolk, wavering and incanable. allowed himself to be detached by Cecil from the other conspirators; and after playing for a short time a double game, was safely lodged in the Tower. This was in October, 1569; when the northern lords—the Earls of Northumberland and Westmoreland, Leonard Dacres. of Naworth, the Nortons of Norton Convers, and a number of gentlemen, were assembled at Topcliffe, the Earl of Northumberland's house, waiting for news that the eastern counties had risen. Instead came a messenger from the duke, begging them "not to stir, or he would lose his head." But their preparations were too complete to allow of concealment. Nearly the whole of Yorkshire was in their favour; and after some hesitation at Topcliffe and at Raby, the earls (mainly by the persuasion of their countesses, who seem to have been made of "sterner stuff") refused to obey the queen's summons to London, and the rising commenced, the declared object being the restoration of religion. Bodies of armed men from all points assembled at Raby; thence they marched to Darham, where (November 14) Northumberland, Westmoreland, Sir Christopher and Sir Cuthbert Neville, and old Richard Norton, strode into the cathedral, "with 60 followers armed to the teeth behind them; Norton with a massive gold crucifix hanging from his neck, and carrying the old banner of the Pilgrimage of Grace, the cross and streamers and the 5 wounds." They overthrew the "Communion board," tore the English Bible and Prayerbook to pieces, replaced the ancient altar, and caused mass to be sung with all solemnity. From Durham they moved 8. to Darlington, gathering force as they went, and making everywhere proclamation of their intention to restore the "ancient and Catholio

faith." They were not opposed by the Earl of Sussex, who was then at York, as Lord President of the Council, but who had no regular troops at command. They passed from Darlington to Ripon (where mass was sung in the minster), to Knaresborough, and Tadcaster, intending to make first for Tutbury, where the Queen of Scots then was, and, after releasing her, to march on London. But when they were within 50 miles of Tutbury, Mary was hastily removed to Coventry, and so placed beyond their reach. With her removal the earls lost the game. Alva, with whom they had been in correspondence, would not stir until Mary was free; and others who favoured their cause in England waited for Alva. After waiting for some days near Tadcaster the earls retreated northward, hoping to hold N. Yorkshire, Northumberland, and Durham. But the Court had been thoroughly alarmed. A southern force was on the move, and by the 30th of November the rebel army was broken up. Northumberland went back to Durham. Westmoreland. paused before Barnard Castle, where Sir George Bowes had entrenched himself with a few followers. He was compelled to surrender after a few days' siege, and Westmoreland went on to Raby. Dacres was at Carlisle with Lord Scrope, and had withdrawn himself from his old companions. The queen's army was advancing, and (December 20) the two earls, their ladies, the Nortons, Markenfield, and a few others who still held together, having rested the night before at Naworth, succeeded in crossing the Border. There they found at first a refuge among the outlaws and mosstroopers, and afterwards (Westmoreland and the Nortons) at Fernihurst, the stronghold of the Kers, 2 miles above Jedburgh. Northumberland was taken by stratagem, delivered to the Regent Murray, and confined in the same rooms in Lochleven Castle which had been occupied by Mary. There he remained until May, 1572, when he was given over to Elizabeth; and, after having been carried along the line of the rebellion to Durham, to Raby, and to his own house at Topcliffe, he was beheaded (August 22) in the Pavement at York. The Earl and Countess of Westmoreland, the Countess of Northumberland, old Norton and 2 of his sons, escaped from Scotland to Flanders.

The punishment which followed the rebellion in Yorkshire and Durham was beyond example cruel. No blow had been struck, and hardly a life had been lost; but a general seizure of all persons implicated was made on a certain night, and from them 600 or 700 artizans, labourers, or poor tenant farmers, were picked out for summary execution. They were hanged in the different towns through which the insurgents had passed. Those who had property were afterwards tried at York. Eleven were found guilty, 4 of whom were at once put to death. The lands of the others were escheated.

The ballad of the 'Rising of the North' will be found in Percy's

*Relics' and in Ingledew's 'Yorkshire Ballads.'

§ XXIV.—The events before and immediately following the outbreak of the civil war are closely connected with York. The details will be found in every History of the period. In 1640 Charles I. was at York

with his army preparing to invade Scotland, which country had broken into open war after Laud's appointment of bishops and the imposition of the English liturgy. The Scottish army crossed the Tweed Aug. 20, and soon made themselves masters of Northumberland and Durham. On the 24th of September the king summoned a great council of peers to assemble at York. By their advice a Parliament (the famous Long Parliament) was proclaimed to meet on the 3rd of November. Sixteen peers then went to Ripon to negotiate with the Scots, but the commissioners soon withdrew thence to London.

Toward the latter end of March, 1642 (the attempt to arrest the 5 members had been made in January, and Charles left Whitehall on the 10th of that month), the king was again in York. The civil war was on the point of breaking out. Many of the peers and some of the commens withdrew from London to York; and during his stay here Charles. who was lodged in the palace built out of the ruins of St. Mary's (it is now known as the Manor-house, see Rte. 1), issued numerous important state papers and proclamations in answer to the demands and assertions of the Parliament. From York he rode to Hull (April 23. 1642) to demand the submission of Sir John Hotham (Rte. 3), and afterwards to besiege the town; and from York he set out to raise his standard at Nottingham (August 22). Yorkshire was for the most part royalist; and at the end of 1643 a line drawn from Hull to Southampton would suggest no very incorrect idea of the two parties, considered as to their military occupation of the kingdom."—Hallam. The Fairfaxes, however, were active and powerful on the side of the Parliament, and inflicted some serious losses on the king's troops under Newcastle before they retreated into Hull in July 1643. Newcastle then besieged Hull, but was compelled to abandon his position. The siege of York by the Fairfaxes, Manchester, and Leven followed (June, 1644); and in July was fought the battle of Marston Moor (Rte. 20). York afterwards surrendered on honourable conditions to the Parliamentarians; but Yorkshire claims the honour of possessing the 2 strongholds which held out last for the king-Scarborough (surrendered July, 1645, and again held for Charles from August to December, 1648, see Rte. 12), and Postefract (Rts. 28), which did not surrender until after the death of Charles, and was the first place in England in which his successor was proclaimed.

§ XXV.—But little public history has since been connected with Yorkshire. The county was vigorously Hanoverian in 1745, when large sums were subscribed throughout it for its due protection against the Jacobite invaders. A curious list of the subscribers was printed, showing, from such insertions as "the young gentlemen of Beverley school," "the young ladies of Pontefract," and many similar, how warm and general was the feeling for the Government. Archbishop Herring was most active on this occasion; and it was no doubt owing to his exertions that Yorkshire made so decided a display of opinion, mainly influencing the struggle.

§ XXVI.—Throughout the last century York was the centre of society

in the N. of England; and many of the county gentry had houses here in which they passed the winter. The city had been noted for its life and hospitality from the days of Elizabeth :—

"Yorke, Yorke for my monie,
Of all the citties that ever I see,
For merry pestime and companie,
Except the cittie of London."

With the present century the importance of York in this respect began slowly to decline, partly owing to better roads and to greater security of travelling, which rendered the journey to London less formidable. If York declined, however, the great manufacturing towns of Yorkshire were rising to an importance such as the chief city of the county had scarcely ever possessed. During the half-century between 1800 and 1850, Leeds, Bradford, Halifax, Huddersfield, and Sheffield, with their numerous dependencies, have become great centres of English wealth and enterprise. They had before been places of much censequence; but it is since the beginning of the present century that their manufactures have so largely increased, and that that vast pepulation has grown up in and around them which has made the W. Riding so great a power in political questions, and has caused its representation in Parliament to be so eagerly sought.

ANTIQUITIES.

& XXVII. Primaval and British.—Yorkshire is in reality richer than most English counties in memorials of the ancient races by whom her soil has been occupied at different times. But these are for the most part below the surface, and are contained in the innumerable "houes" (the word is connected with the Icelandic "hoie" = a grave-mound, and with the S. Saxon heah = high) and tumuli which dot the surface of the wolds, and of the moors of Cleveland and the N.E. district. Many of these graves have been systematically explored under the direction of the Rev. J. C. Atkinson (on the moors) and of the Rev. William Greenwell of Durham. The contents of the house on the northern moors seems to indicate that they are of greater antiquity than those on the wolds. (See them figured and described in Atkinson's 'Hist, of Cleveland'). On the wolds, two distinct types of skull have been found; and proofs of interment both after cremation and by simple inhumation. In both cases. however (as is proved by cases in which the body was burnt on the spot. and the bones have been found only partially calcined), the body was contracted, with the knees drawn up on the breast, and the hands placed over the face. Numbers of urns, some of very good workmanship, and flint weapons, occasionally very fine and perfect, are found in these Metal is very rare, and has only been discovered in such graves as are evidently of later date. In some of the mounds remains of bodies which had been broken and divided were found, generally on the side of the houe, and at some little distance from the principal interment. It is uncertain whether these are relies of the funeral feast, incicating that some of the ancient tribes were cannibals, or whether they were bodies of slaves sacrificed and mutilated on their master's death. It is probable that the greater part of these graves are of far earlier date than the Roman occupation; but farther examination and comparison are necessary before their age, or the ethnological character of the races whose remains are found in them, can be determined with certainty. Urns, flint implements, and various antiquities from these and other primitive graves in Yorkshire, may be seen in the museums at York, Leeds, Whitby, and Scarborough. (The results of Mr. Greenwell's researches will be published in his 'Decade of Northumbrian Skulls.' Brief accounts have appeared in the 'Times' and elsewhere. For some interesting notices of Yorkshire graves, see Phillips's 'Rivers, &c., of Yorkshire,' and Journal of the Archæol. Institute, York vol.)

Numerous foundations of primitive houses and villages exist on the N.E. moors, probably in far greater numbers than have been hitherto examined or described. These foundations are circular pits, 8 or 4 ft. deep, paved in many instances with small stones, and sometimes with a raised border of earth. They are sometimes (as at Danby) in parallel lines; sometimes (as at Egton Grange) irregularly ecstiered over the ground, with each pit separated by a ridge sufficiently wide for a man to pass. The most remarkable of these villages are on Danby Moor (Rte. 15), at Egton Grange (Rte. 14), the "Killing Pits" near Goathland (Rte. 14), in Harwood Dale, near the Falcon Inn, between Scarborough and Whitby (Rte. 12), and below Roseberry Topping (Rte. 15). A conical or beehive-shaped hut, such as might be seen but a short time since in some of the Hebrides, and may perhaps still exist there, was constructed of turfs, or of branches of trees, on these foundations, which, there can be little doubt, were those of Brigantian villages existing before and during the Roman occupation. "This must have been a scattered population of shepherds, who have left traces of long, but not altogether peaceful occupation."-Phillips. The Roman camp at Cawthorne (Rte. 14) probably held them in some There was no large Roman town in the district.

Some hut foundations of different character—being excavated pits with the earth thrown inward so as slightly to raise the centre—are said to exist on Skipwith Common in the W. Riding (see Rte. 1, Exc. from York); but these are doubtful and but slightly marked. On the summit of Ingleborough (Rte. 32A) are stone foundations of circular huts, somewhat resembling those at Greavesash in Northumberland, and on Dartmoor in Devonshire. It is somewhat remarkable that neither in the dales of western Yorkshire, nor on the moors of its southern border, have any similar remains been noticed, although from other indications it is clear that these portions of the county were far from

un peopled.

In stone monuments—such as the circles, cromlechs, and tolmens of Wales and Cornwall—Yorkshire is not rich. Many single stones, or stones placed in groups of 3 or 4 together (and called on the N.E. moors bridestones, a name which has not been explained), are found here and there in different parts of the county; but the absence of larger monu-

ments is noticeable, and is certainly not owing to want of durable and easily-worked stone. A few stone circles (of small size and of little importance) also occur (especially on the hills about Settle). Many isolated blocks have received the name of "rocking-stones," for the most part without reason, and have been assigned, as usual, to the Druids. They are in almost all cases ice-drifts, and their original beds, as well as the line of their "migration," can often be traced. (See Rte. 32a.) The rocks at Brimham (Rte. 21), with which the name of the Druids has also been connected, are equally natural.

The most striking stone monuments in Yorkshire are, however, the "Menhir," or single shaft, called the Rudstone (Rte. 18), and the Devil's Arrows, near Boroughbridge (Rte. 19). The latter may possibly

be Roman.

Large earthen mounds, generally circular, are found in different parts of Yorkshire (for the most part on the wolds, on the Cleveland Moors, and in the old district of Elmete), and generally in connection with British villages. There is one near the huts on Danby Moor (Rte. 15), others at Lofthouse (Rte. 14), at Cropton near Pickering (Rte. 14), at Kippax (Rte. 42), and elsewhere. The finest and most remarkable examples are at Barwick in Elmete (Rte. 42) and at Laughton-en-le Morthen (Rte. 47). These mounds have been called "raths" by Professor Phillips ('Rivers, &c., of Yorkshire'), a name which is not local; and although similar green mounds are known as "raths" in Ireland, it seems undesirable to transfer it elsewhere. Mr. G. T. Clark regards them as of Saxon or English construction, and considers that they always mark the site of an English "strength" or defended mansion. They were palisaded, and the structure raised on them was never of stone in the first instance. But when Norman lords succeeded to these English strongholds, they often built a shell keep on the mound, and converted the ancient earthworks into a portion of the defences of a Norman castle. The best examples of this treatment are at Pontefract (Rte. 28) and at Tickhill (Rte. 47). Coningsborough (Rte. 40) has a keep of a different character, but the earthworks are of the same early date. Yorkshire is especially rich in such mounds and earthworks.

Some very remarkable circular earthworks exist in the neighbourhood of Ripon, at Blois Hall, and at Thornborough (see Rte. 22). There are others of similar character near Penistone (Rte. 44), and from their peculiar character it has been suggested that they are rather temples than places for defence. They are surrounded by a mound and an inner trench. The arrangement in the great circle at Abury is the same; and many stone circles in Scotland (especially in Aberdeenshire—see Col. Forbes Leslie's 'Early Races of Scotland') are placed within similar mounds. In most of these cases the trench is on the inner side of the mound. There are no upright stones and no traces of their former existence within the Yorkshire circles.

Of British camps the most remarkable is perhaps Almondbury, near Huddersfield (Rte. 37), which, however, shows evident marks of Roman cccupation. It is perhaps noticeable that very few traces of strong

British camps exist in Yorkshire, except on the south-eastern border, -as at Wincobank, Rte. 45; Mexborough, Rte. 40; and perhaps Coninesborough, Rte. 40. (It must be remembered that many a British camp may have been adopted as an English stronghold, just as these latter were adopted by the Normans.) On the other hand, few parts of England contain such numerous and extensive dukes and earthworks. The wolds and the skirts of the hills on the N. side of the Vale of Pickering are covered with these entrenchments. (See Rte. 11.) The most extensive works of this class are between Sheffield and Mexborough, on the ridge of hills I, of the Don (Rte. 45), and between Catterick on the Swale and Gainford on the Tees. (Rte. 25. These latter have been most carefully examined and planned by Mr. Maclachlan, at the cost of the late Duke of Northumberland. See his paper in the Journal of the Archeol. Institute, vol. vi.) The Wold Dykes are hardly less important. The Danes' Dyke, at Flamborough (Rte. 13), cuts off the entire promontory. It is evident that all these entrenchments were constructed for defence, and that they formed at different times the boundary-lines of the races who raised them. But their date is by no means so clear; and perhaps all that can be said with certainty is that they are pre-Roman.

§ XXVIII.—Roman and Anglian. The most important Roman remains in Yorkshire are the Multangular Tovoer at York (Rte. 1), and the numerous relics at Aldborough, the ancient Isurium (Rte. 19). At Catterick Bridge (Rte. 25) are traces of the station of Cataractonium; and some remains, found on the site, are preserved in the neighbouring Brough Hall. The outline of the Roman station is traceable at Old Multon (Rte. 12), and a (probably) Roman bridge exists near Tudcaster (Calcaria, Rte. 43). Yorkshire was covered with Roman roads. Many Roman relics—altars, inscribed stones, sepulchral urns, personal ornaments, and weapons—will be found in the museums at York, Leeds, Scarborough, and Whitby. (A map of British and Roman Yorkshire, in which the sites of British villages, earthworks and stone monuments, Roman stations, and the lines of Roman road are carefully marked, was prepared by Mr. Newton for the meeting of the Archæological Institute at York in 1846. It is to be had at the office of the Institute.)

Of the Anglian and Danish period the most evident relies are the names of places and the local dialects. Fine and interesting remains have been found in tombs of this period, as well heathen as Christian. Some of these are preserved in the public museums, and need not be particularly described here. Parts of churches, apparently of earlier

date than the Conquest, are noticed in the following section.

§ XXIX.—Mediæval. Yorkshire is especially rich in both ecclesiastical and military architecture. Other counties can perhaps show more important domestic buildings, but some of the Yorkshire castles are of high interest, and no part of England contains more important monastic remains. Those of the great Cistercian abbeys are indeed unequalled in Europe.

§ XXX.—Of the churches the following deserve notice. The most important are marked by an asterisk.

Saxon.—*Kirkdale, portal with inscription, Rte. 18a; *Kirk Hamerton, tower, S. side and E. end, Rte. 20; Skipwith, lower part of tower, Rte. 1; *Aldborough, inscription and fragments from earlier church, Rte. 6. There are also fragments and sculptured crosses, all of which are probably more ancient than the Conquest and all of great interest, in the crypt at Lastingham, Rte. 18a; at Hauxwell, Rte. 28; at Wensley, Rte. 24; at Hackness, Rte. 12; at Ilkley, Rte. 30; at Bedale,

Rte. 23; and at Dewsbury, Rte. 37.

Norman.—Campsall, portions, Rte. 2; *Birkin, Rte. 2; St. Denis, Walmgate, York, rich portal, Rte. 1; St. Margaret's, Walmgate, York, portal, Rte. 1; Fishlake, portal, Rte. 8; *Selby, parts of nave, Rte. 1; Brayton, Rte. 1; Goodmanham, portions, Rte. 8; Bubwith, chancel arch, Rte. 8; Hackness, portions, Rte. 12; Rudstone, tower, Rte. 13; Pickering, portions, Rte. 14; *Lastingham, crypt, Rte. 18a; Whorlton, portions, Rte. 15; Alne, portal, Rte. 16; Feliskirk (rebuilt), Rte. 16; Northallerton, parts, Rte. 16; Hornby, Rte. 23; *Spennithorne, parts, Rte. 23; *Adel, Rte. 28; Leathley, E. Norm. tower, Rte. 30; Coniston, Rte. 31; Coningsborough, Rte. 40; *Bardsey, Rte. 43; Thorpe Salvin, late Norm. portal, Rte. 47.

Transition.—Arksey, portions, Rte. 1; *Kirkburn, Rte. 8; St. Mary, Scarborough, parts, Rte. 12; *Filey, portions, Rte. 13; Raskelf, parts, Rte. 16; *Ripon Minster, transepts and part of choir, Rte. 22; Wragby,

Rte. 38.

It is evident that church-building must have been very general in Yorkshire throughout the century that followed the devastation of the country by the Conqueror. The character of the Yorkshire-Norman agrees rather with that found in the great churches of eastern England,—Ely, Peterborough, and Norwich,—than with that in the W., as seen either at Gloucester or at Hereford. It is plain and massive; sometimes with enriched portals, but generally with little elaborate ornament. The small churches which retain their original ground-plan deserve especial notice. Such are Adel and Kirkburn, both more ornamented than usual. Birkin is hardly less interesting, though it has had some additions of later date.

Early English.—*York Minster, transepts, Rte. 1; *Skelton, Rte. 1; *Nun Monkton, Rte. 1; *Snaith, W. front, Rte. 4; Hemingborough, portions, Rte. 5; *Hedon, choir and transepts, Rte. 6; *Beverley Minster, eastern portions, Rte. 8; Bubwith, nave arcade, Rte. 8; *Old Malton, Priory church, Rte. 12; Hackness, parts, Rte. 12; Scalby, Rte. 12; Filey, parts, Rte. 13; Hunmanby, nave arcade, Rte. 13; *Bridlington, parts, Rte. 13; Lastingham, Rte. 18a; Northallerton, parts, Rte. 16; Ampleforth, parts, Rte. 18; Helmsley, parts, Rte. 18a; Kirkdale, parts, Rte. 18a; Slingsby, Rte. 18; Goldsborough, Rte. 20; *Krichaller, W. front, Rte. 22; Wath, Rte. 22; Hauxwell, portions, Rte. 23; Wensley, choir, Rte. 24; Almondbury, chancel, Rte. 37; Towton, parts, Rte. 43.

The E. E. of York, Ripon, and Beverley ranks with the finest in the kingdom. The churches of Skelton and Nun Monkton are especially interesting, and the latter has some unusual design. As a rule, the

E. E. of Yorkshire is distinguished by no marked peculiarities.

Decorated.—*York Minster, nave and chapter-house, Rte. 1; Fish-lake, parts, Rte. 3; *Selby, choir, Early, Rte. 5; *Howden (all but tower and chapter-house), Rte. 5; *Holy Trinity, Hull, transepts and choir, Rte. 5; *Hedon, nave, Early, Rte. 6; *Petrington, Rte. 6; *Beverley Minster, nave, Rte. 8; *St. Mary's, Beverley, chancel, Rte. 8; *Sheriff Hutton, Rte. 12; Flamborough, Rte. 13; *Bridlington, parts, Rte. 13; Rudstone, Rte. 13; Pickering, parts, Rte. 14; Whorlton, parts, Rte. 15; Aldborough, Rte. 19; Whitley, tower and nave, Rte. 20; Ripley, Rte. 21; *Ripon Minster, E. front, Rte. 22; Well, Rte. 22; *Bedale. Rte. 23; Spennithorns, portions, Rte. 23; Middleham, Rte. 23; Richrond, parts, Rte. 25; Wycliffe, Rte. 26; Methley (of no great interest but for the Waterton chantry, which is Perp.), Rte. 28; Otley, Rte. 30; Ikkley, Rte. 30; Wakefield, tower and spire, Rte. 38; *Thornhill, chancel and aisles, Rte. 39; *Darton (late), Rte. 40; *Darfield (very Silkstone (late), Rte. 41; *Royston (late), Rte. 41; Penistone (late), Rte. 44; *Silkstone (late), Rte. 44;

Of Decorated work, Howden, Hedon, Patrington, the choir of Selby, parts of Beverley Minster, and of St. Mary's, Beverley, are very fine examples. The use of a peculiar pointed ornament (a form of ball-flower) may be noted as unusual in the S. of England; and there is a tendency in the smaller churches to use the discontinuous impost, in which the srch-mouldings die into the pier. The group of Late Dec. churches in S. Yorkshire—Darton, Darfield, Royston, Penistone, and Silkstone—

deserves special notice.

Perpendicular.—Campsall (with Perp. roodloft and inscription), Rte. 2; *Bolton Percy, Rte. 2; *York Minster, choir and presbytery, Rte. 1; St. Michael le Belfry, York, Rte. 1; St. Martin's, Coney Street, York, Rte. 1; Hemingborough, portions, Rte. 5; *Howden, tower and chapter-bouse, Rte. 5; *Holy Trinity, Hull, nave, Rte. 5; Winestead, Rte. 6; Aldborough, Rte. 6; *Beverley Minster, N. porch and W. front, Rte. 8; St. Mary's, Beverley, nave, Rte. 8; *South Skirlaugh chapel, Rte. 10; Bridlington, W. front, Rte. 13; *Thirsk, Rte. 16; *Coxwold, Rte. 18; Brafferton, Rte. 19; Ripon Minster, nave, Rte. 22; Tanfield (portions), Rte. 22; Wensley, nave, Rte. 24; *Catterick, Rte. 25; Richmond, Rte. 25; *Methley, Waterton chantry, Rte. 28; Whitkirk, Rte. 28; *Harewood, Rte. 29; Skipton, Rte. 30; Kirkby Malham, Rte. 32; Giggleswick, Rte. 32; *Bolton-by-Bolland, Rte. 33; Kildwick, Rte. 34; Bradford, Rte. 35; *Halifax (parish ch.), Rte. 36; Almondbury, nave with nacription, Rte. 37; Wakefield, Rte. 38; Tadcaster, Rte. 43; *Spofforth, Rte. 43; *Sheffield, St. Peter's, Rte. 44; *Rotherham, Rte. 46; *Tickhill, Rte. 47.

The choir and presbytery of York Minster were probably among the carliest Perpendicular works of importance completed in England. They greatly influenced subsequent building and design in Yorkshire. The great breadth of the chancel and the squared eastern end, with aisles terminating parallel with the retrochoir, are marked features of York, and recur on a smaller scale in many parish churches.

Of Modern churches it will be proper to mention St. Peter's, at Leeds (Rte. 28); St. George's, Doncaster (Rte. 1), and All Souls, Haley Hill,

Halifax (Rte. 36), both ranking among the finest works of Sir G. G. Scott; Baldersby, a very striking church by Mr. Butterfield (Rte. 22), Escrick, F. C. Penrose, architect (Rte. 1), and Dalton Holme (Rte. 8.)

§ XXXI.—The *Monastic Remains* of Yorkshire must of course be studied in connection with the churches, the architecture of which they in many cases influenced. Those here mentioned are in ruins. The churches of such monasteries as were retained are included in the former section.

Benedictine.—St. Mary's, York (Rte. 1), E. E.; Whitby (Rte. 14).

E. E. and Dec.

Cistercian.—Kirkham (Rtc. 12), E. E. and Dec. (fragments); Byland (Rtc. 18), Tr.-Norm and E. E.; Rievaulx; (Rtc. 18a), Norm. and E. E.; Fountains (Rtc. 22), Tr.-Norm. and E. E. (the most perfect in ground-plan and in actual remains); Jervaulx (Rtc. 23), Tr.-Norm. and E. E.; Kirkstall (Rtc. 29), Tr.-Norm.; Sawley (Rtc. 33), little but ground-plan and foundations, 12th cent.; Roche (Rtc. 47), Tr.-Norm. and Dec.

Augustinian Canons.—Guisborough (Rts. 15), E. Dec., little except E. window of church remaining; Bolton (Rts. 30), Dec. and E. E.

Premonstratensian Canons.—Coverham (Rte. 23), Dec. and Perp.; Easby (Rte. 25), Tr.-Norm. and E. E.; Eggleston (Rte. 26), E. E. and Dec. Carthusian.—Mount Grace (Rte. 16), Perp.

Cluniac.—Monk Bretton (Rte. 40), E. E. and Dec.

The remains of St. Leonard's Hospital, York (Norm. and E. E.), and St. Anthony's Hospital, York (Perp.), should also be mentioned. The various monastic remains have been described so fully in their different routes, that nothing need be added here. The ground-plans of Fountains, of Jervaulx, and of Sawley, have at different times been carefully examined. The original design for Fountains, and perhaps for Kirkstall, was no doubt brought from Clairvaux; and some foreign peculiarities are traceable, especially in the W. porch and front of the church at Fountains.

§ XXXII.—The Castles of Yorkshire deserve more complete study and examination than they have hitherto received. They are—

Clifford's Tower, York (Rte. 1), Edwardian, with earlier portions; Wressel (Rte. 5), Perp.; Sheriff Hutton (Rte. 12), Perp.; Keep of Scarborough (Rte. 12), late Norm.; Pickering (Rte. 14), Edwardian; Danby (Rte. 15), Perp.; Gatehouse of Whorlton (Rte. 15), Perp.; Gilling (Rte. 18), now chiefly domestic, but with Edwardian portions; Helmsley (Rte. 18A), E. E. and Edw. II.; Knaresborough (Rte. 20), Edw. III.; Snape (Rte. 22),—now domestic,—late Perp. and Eliz.; Tanfield (Rte. 22), Perp. fragment; Middlebam (Rte. 23), Norm. with Perp. outer walls; Bolton (Rte. 24), Rich. II.; Richmond (Rte. 25), Norm.; Barnard Castle (Rte. 26), Edwardian; Bowes (Rte. 26), late Norm.; Pontefract (Rte. 28), Norm. and Edwardian; Harewood (Rte. 29), Edwardian; Barden Tower (Rte. 30), late Perp.; Skipton (Rte. 30), Edwardian and Hen. VIII.; Coningsborough (Rte. 40), Norm.; Spofforth (Rte. 43), Tr.-Norm. ranging to 15th cent.; Tickhill (Rte. 47), Perp.

Of these the Norman keeps of Scarborough, Richmond, and Coningstorough are of great interest; and nearly all retain portions which deserve attention. The Gatehouse of Whorlton is an excellent and most perfect example, temp. Rich. II. Some of the Yorkshire castles have been described by Mr. G. T. Clark in the 'Builder.'

§ XXXIII.—Yorkshire is not so rich in *Domestic Architecture* as might be expected from the great size of the county, though it contains

some important examples. The best are—

Burton Agnes (Rte. 9), Jas. I.; Burton Constable (Rte. 7), various dates, chiefly Jas. I. and Chas. I.; Howsham Hall (Rte. 12), Elizabethan; Campsall Vicarage (Rte. 2), late E. E. or E. Dec.; Slingsby (Rte. 18), Chas. I. (in ruins); Ripley Castle (Rte. 21), Philip and Mary; Temple Newsam (Rte. 28), Chas. I.; Markenfield (Rte. 22), Dec., with 15th and 16th cent. additions; Bolton-by-Bolland (Rte. 33), Edwardian in parts; Browsholme (Rte. 34), Hen. VII.; Bowling Hall (Rte. 35), Eliz. with earlier towers; Woodsome Hall (Rte. 37), Hen. VIII., re-ironted 17th cent.; Ledstone Hall (Rte. 42), Jas. I.

Castle Howard (Rte. 12), by Vanbrugh; Duncombe Park (Rte. 18A), built from Vanbrugh's designs; and Harewood (Rte. 29), by Carr of

York, must also be mentioned here.

RESOURCES AND MANUFACTURES.

§ XXXIV.—Of the natural productions of Yorkshire, the extent and importance of which have assisted so largely in raising the county to its resent position, the chief are iron and coal. These require a longer notice. Others which may here be briefly mentioned are lead, worked very extensively in Swaledale (Rte. 25) and in Nidderdale (Rte. 21); where it was certainly worked by the Romaus, and where the lead-mines have probably never since been entirely neglected; jet, procured in considerable quantities from the cliffs near Whitby (Rte. 14); alum, the raw material for which is found in the same district; the excellent building-stone from the Tadcaster (Rte. 43) and Huddlestone (Rte. 42) quarries; and the black and grey marble, found in such vast quantities throughout Nidderdale and Dentdale.

The staple manufactures of Yorkshire are woollen and worsted. Cf

these a longer account must be given.

§ XXXV.—Iron. The ironstones of the coal-measures have been worked in Yorkshire from a very early period. There is evidence that the Romans had discovered their value and had smelted them. The working of these beds—the black-band and clay-band ironstones of the coal-measures, which occur in thin layers associated with coal-seams, shales, clays, and sandstones—has never been altogether neglected, and until very recently the chief supply of English iron was derived from them. The most important works in connection with these ironstones are in the neighbourhood of Bradford,—at Low Moor and at Bowling. (See Rte. 35.)

These ironstones, which "partake more or less of the laminated or

bedded structure of the strata with which they are associated "(E. Hell), are of course not so rich as the homatites of Lancashire, Cumberland, the Mendip Hills, and elsewhere. But the largest supply is afforded by the clay ironstones; and about the year 1850, when many of the principal beds in the coal measures were found to be rapidly exhausting, and some anxiety was felt in consequence (since the demand for iron was every year increasing), an enormous addition was made to our resources by the discovery of the "New Iron-fields of England," which occupy a broad belt of country almost from the shores of the English Channel to those of the German Ocean. The Cleveland Hills in the N.E. corner of Yorkshire form the most important portion of this helt, see Rta 17 (Middleshrough)

belt, see Rte. 17 (Middlesbrough).

The ironstone of the Cleveland Hills, like that of the Yorkshire coalmeasures, was not unknown to the Romans, and had been worked by them in several places. The monks of Rievaulx and of Whitby had also worked it; and it had also been quarried and smelted in Rosedale in the 12th cent. (see Rte. 14); but it had been entirely neglected in modern times, and the vast extent of it was altogether unknown, when Mr. Vaughan, in 1850, made the discovery of the seam of ironstone lying under Eston Moor. (See Rte. 17.) From that time the ironstone has been worked in different parts of the district with increasing profit and importance. Smelting-houses have been erected in great numbers on either side of the Tees; the town of Middlesbrough has arisen as the "metropolis" of the trade.

Ironstones in the same formation are being worked in Lincolnshire, in Oxfordshire, and elsewhere. The quality of iron "is confessedly inferior to that derived from the coal-measures, still more to that from the hæmatites of Ulverstone and Furness; but for ordinary purposes and for mixing with the finer classes it is of great value. It is, moreover, supplying the enormous demand of the present generation; and looking to the future, the Middlesbrough district is likely to have few rivals

in any part of the world."

The processes of iron manufacture have been briefly noticed under Middlesbrough (Rts. 17) and Low Moor (Rts. 35), and call for no further description here.

(Dr. Percy's volumes on 'The Metallurgy of Iron and other Metals'

contain the best and fullest information on the subject.)

The process of converting iron into steel, and the steel manufacture, fully described Rte. 44—Sheffield—need not be again noticed here.

§ XXXVI.—Coal. There were in Yorkshire, in 1857, 347 collieries, producing annually 8,875,440 tons of coal. In 1870 this had increased to 10,606,604 tons, and now exceeds 12 millions. The Yorkshire coalfield is, however, only a portion of a great field extending over parts of the shires of Nottingham and Derby, and forming altogether the largest coal-field in England. (That of S. Wales is 153 square miles larger in area.) The whole field produces annually about 20 millions of tons.

The greatest length of the coal-field from S. to N. is 66 miles, and its breadth varies from 5 to 20 miles. Though the general dip of the strata is eastward, there generally occurs along the centre of the field

a gentle undulation which for a certain distance produces a westerly dip;; but the strats always roll over when approaching the base of the Permian rocks. The coal-seams are only occasionally broken by faults.

The Yorkshire coal-beds abound in fossil ferns, lepidodrenda, and sigillarise; and among the deposits of this period are sandstone strate in which the stems of trees stand erect. Roots of trees also are extended m their natural positions beneath several of the coal-seams. "The coal-heds are certainly composed of terrestrial plants, probably accumulated round the trees and above their roots, often by the agency of water, which has left part of its living tenants even in the substance of the coal, as the defensive fin-bones of cartilaginous fishes (Gyracanthus), and estuary shells (Unionidæ)."-Phillips. 17 species of fish (placed and ganoid), 5 cephalopods, 17 conchifers and brachiopods, and I of the crustaces-Cythere (cypris)—have been reckaned in the Yorkshire coal-measures. Fish-remains occur plentifully in the roofing shale of some of the coal-beds; so plentifully at Middleton, that the miners call it "fish-coal." There are very good collections of fossils from the coal-measures in the museums at York, at Leeds, at Scartorough, and at Whitby.

The Yorkshire coal-field contains many courses of ironstone, which are worked in different places,—most extensively in the neighbourhood

of Bradford, at Low Moor, and Bowling.

Estimating the area of the entire coal-field (not including the portion under the magnesian limestone) at 760 square miles, Mr. Hull concludes that at the present rate of consumption the coal it contains will

last about 700 years.

\$ XXXVII.—As Lancashire is the great seat of the cotton manufacture, Yorkshire is the centre of the woollen trade. Some cotton-mills (especially in the Todmorden valley), and more silk and flax factories are to be found in parts of the W. Riding (flax and linen factories are very numerous at Leeds and at Barnsley); but wool in its various forms is still the main source of the wealth of manufacturing Yorkshire. The woollen trade has two grand divisions: cloth or woollen properly so called, and consted. Leeds is the capital of the cloth manufacture, which is carried on for the most part in that town and in the surrounding district. Bradford is the great worsted mart of the county. Cloth or woollens are made from short wool, worsted from long wool.

It has been thought that the wool of the sheep in its natural and primitive state was more properly long than short, and therefore that the most ancient woollen fabrics had rather the character of worsted than of cloth. However this may be, it is certain that the fabrication of wool into clothing is one of the most ancient of human arts; and not less certain that in Yorkshire cloth manufacture long preceded the making of worsted fabrics, which was not introduced into the county until the middle of the 17th cent. The name "worsted" is probably derived from the town of Worsted, in Norfolk, which certainly existed before the Conquest, and in which, at an early period, Flemish weavers settled and introduced the manufacture. (Comp. similar derivations from Cambria (cambric), Arras, Calicut (calico), and others.)

A 'History of the Worsted and Woollen Manufactures,' in 2 vols., by Mr. James Bischoff, was published in 1842; and in 1857, Mr. James published an excellent and exhaustive 'History of the Worsted Manufacture.' These are the chief authorities on the subject.

§ XXXVIII.—Wool was exported from this island during the later Roman period: and woollen fabrics were no doubt manufactured here long before colonies of Flemings, driven from their own country by a destructive inundation, were settled by the Conqueror and afterwards by Hen. I. in parts of England and of S. Wales (Pembrokeshire). But these Flemings were the first great "clothiers" in England, and their trade was largely increased by Edw. III., who induced fresh bodies of Flemish weavers to settle in this country. "Happy," says Fuller, who breaks off his 'Church History' to commemorate the arrival of these strangers. "the veoman's house into which one of these Dutchmen did enter, bringing industry and wealth along with them. Such who came in strangers, within doors, soon after went out bridegrooms and returned sons-in-law, having married the daughters of their landlords who first entertained them; yea, those yeomen in whose houses they harboured soon proceeded gentlemen, gaining them estates to themselves, arms and worship to their estates." Under the teaching of these profitable strangers, the cloth trade spread extensively throughout the southern and western counties of England. Bristol and its neighbourhood was one very important centre: Norwich and the eastern counties was another; and there was a third in Devonshire, of which Exeter and Crediton were the chief towns. A good specimen of the wealthy English clothier was "Jack of Newberry,"-John Winchcomb of Newberry, in Berkshire—who kept 100 looms in his house, and marched 100 of his own men to Flodden Field, armed and clothed at his own expense. Long before this the woollen manufacture had extended into Yorkshire; and in the reign of Hen. VII. had become of some importance in that county, especially at Wakefield, Leeds, and Halifax. But as yet it was only the coarser kind of cloth that was made in the north; and the manufacture of the various kinds of worsted fabrics, the great centre of which had from the beginning been Norwich and the eastern counties. was not introduced into Yorkshire until the end of the 17th cent. From that time, however, both woollen and worsted manufactures increased steadily in the W. Riding, and (chiefly from the end of the last cent.) have been developed there to such an extent as to leave all other parts of England far behind. The worsted trade of Norwich is still important; and there are still considerable factories of cloth in Gloucestershire and elsewhere, but there is no competition with Yorkshire. "The S.W. portion of Yorkshire," says Mr. James, "possesses, beyond all rivalry, more natural advantages as a manufacturing district than any other in the kingdom, having in abundance, and of the best quality, those three grand requisites -water, coal, and ironstone. Intersected by small valleys, it abounds in rills, brooks, and rivers, excellently adapted either for the working of mills by water-power, or for the use of the 'great iron servant of nations,'-the steam-engine. . . . Add to these essentials that the rivers could easily be made navigable,

and canals formed for the transit of goods; that the district is central, and, what is of paramount importance, that the people are industrious and persevering, of indomitable energy of character, delighting in business, neither shunning labour nor fearing difficulties in the prosecution of their enterprises, and one may comprehend how the manufacture has obtained in such a spot, among such a people, a mighty growth, and become one of the wonders of this progressive age."—History of the Wersted Manufacture.

- § XXXIX.—It was about the middle of the last cent that skill and science began to develop the great resources of south-western Yorkshire, and that that long series of inventions commenced which has been carried to such admirable perfection, and has entirely changed the character of the trade. Dyer's poem of 'The Fleece' was published in 1757, and in it he describes the first factory (as it would seem) in which the different processes of the woollen manufacture were brought into one building. This factory, in the Vale of Calder, had been built for a parish workhouse.
 - Behold in Calder's vale, where wide around Unnumber'd villas creep the shrubby hills, A spacious dome for this fair purpose rise. High o'er the open gates with gracious air Riliza's image stands. By gentle steps Upraised, from room to room we slowly walk, And view with wonder and with silent joy The sprightly scene; where many of busy hand, Where spoles, cards, wheels, and looms, with motion quick And ever-murmuring sound, the unwonted sense Wrap in surprise,"

The whole district was at this time alive with the cloth manufacture. Dyer proceeds—

Take we now an eastward course
To the rich fields of Birstal. Wide around
Hillock and valley, farm and village smile;
And ruddy roofs and chimney-tops appear
Of-busy Leeds, upwafting to the clouds
The incense of thanksgiving; all is joy,
And trade and business guide the living scene,
Roll the full cars adown the winding Aire,
Load the slow-sailing barges, pile the pack
On the long tinkling train of the slow-paced steeds."

Factories, however, did not become general until the end of the cent.; and it was some time before the first spinning-machines, used originally for spinning cotton, were applied to spinning wool. Before they were brought into use the wool was spun in different parts of the country, especially in Craven and in the dales between Skipton and Richmond. "The W. Riding (worsted) manufacturer had not only to visit the villages in the immediate neighbourhood of Halifax, Bradford, &c., but used periodically to traverse the romantic hills and dales of Craven. Here at each village he had his agents, who received the wool,

distributed it among the peasantry, and received it back as yarn. The machine employed was still the old one-thread wheel; and in summer weather, on many a village green or hill-side, might be seen the house-wives plying their busy trade and furnishing to the poet the vision of "Contentment spinning at his cottage-door." Returning in safety with his yarn, the manufacturer had now to seek out his weavers, who ultimately delivered to him his camblets, or russels, or serges, or tammies, or calimancoes (such were then the names of the leading fabrics), ready for sale to the merchant or delivery to the dyer."—James, History of the Worsted Manufacture.

The development of the factory system has, it need hardly be said, entirely changed all this. Resources of all kinds—in the material employed as well as in the most complicated and admirable machinery—have, since the beginning of the present cent., been brought to bear on the worsted and woollen trades; and there are probably no establishments in the world where the means are more nicely proportioned to the ends, where the arrangements are more perfect, or where the whole process of manufacture may be more advantageously studied, than the great factories of Leeds, Bradford, and Halifax, or the wonderful manufacturing "palace" of Saltaire. Some description of these, and especially of Saltaire, will be found in the routes to which they belong. A short general notice of the various processes used in the manufacture of woollens and worsteds may however be useful.

§ XL.—In the manufacture of cloths or woollens the processes are

(those marked with an asterisk are performed by machinery)-

1. Sorting; 2. Scouring or washing; 3. Dyeing (when wool-dyed);
4. *Willying or twilling; 5. Picking or moating, 6. Oiling; 7. Scribbling; 8. *Carding; 9. *Slubbing; 10. *Spinning; 11. *Reeling;
12. Warping; 13. *Sizing; 14. *Weaving; 15. Scouring; 16. Dyeing (when piece-dyed); 17. Burling; 18. *Fulling or felting; 19. Scouring; 20. Tenter-drying; 21. *Raising or teazling; 22. Shearing; 23. *Brushing; 24. Picking-drawing; *25. Pressing; 26. Packing. (The extracts are from Bischoff's 'History of Wool and Woollens,' where they are quoted from an article in the latest edition of

the Encyc. Britann.)

After the wool has been sorted and scoured, first in ley and afterwards in running water, so as to cleanse it from grease and all impurity, it is dyed—if intended for the making of wool-dyed cloth. (All cloth, except white, is either wool or piece-dyed.) It is then placed in the willying machine (the name is said to be a corruption of "winnow" are winnowing," since this is the office it performs). This is "a revolving cone, armed with 4 rows of iron spikes, strongly fixed in 4 longitudinal bars fastened to 3 concentric wheels of different diameters. This cone revolves at the rate of from 300 to 500 revolutions per minute, within a casing cylinder, armed with several spikes, but placed so as to alternate with the spikes on the cone. The machine is fed by means of an endless apron, the wool entering at the smaller end, so that when most entangled it is subjected to the least motion By the revolutions of the cylinder the wool is torn,

disentangled, and cleaned, and by the gradually increasing centrifugal force it is impelled forwards toward the large end of the cone. When the wool thus reaches the base of the cone it is tossed into a chamber, where it is received upon another endless apron, moving in a direction from the machine instead of towards it. Over this apron is a cylindrical wire cage, . . . and immediately over it is a revolving fan. Both these are covered and protected by sheet-iron casings, but communicate with the chamber which receives the wool from the cone. The fan, drawing the dust out of the chamber, blows it through a chimney or pipe connected with the machine for the purpose. The cage pre-

vents the escape of the wool with the dust, and by its passage over the asson it lave down the wool in a continuous fleece."

The wool is then picked or "moated," in order to remove any dirt which may not have been separated by the willy, and is afterwards eded. 8 or 4 lbs. of oil being well mingled with 20 lbs. of wool. It is then ready for scribbling and carding,—processes which resemble each other, the only difference being that the scribbling machine is coarser. The object of both is farther to separate and open out the fibre of the wool. "The wool-carding engine consists of one large cylinder or and-dram, surmounted by 3 pairs of smaller cylinders called urchins. all of them covered with card-cloths armed with carding-wires. At one end is an endless feeding apron, upon which equal portions, by weight, of the oiled wool are evenly spread by hand." The wool is distributed upon the eard-drum, from which it is stripped by the smaller cylinders, and is at last removed by a larger cylinder called a "doffer." from which the whole is scraped off by a "doffing" knife. In the acribbling process the wool is wound round a revolving roller in an endless fleece, having the appearance of a fine blanket. The carding engine delivers it in narrow bands or slivers.

The wool is now ready to be spun into yarn by machines. The first of them is the slubbing machine or "slubbing billy," in which about 60 spindles are arranged on a moveable carriage. By this machine the carded wool is joined, elongated, and slightly twisted. The slubbing thus produced has the appearance of a soft and weak thread, and is ready for the spinning jenny or the "nulle," which is fast superseding it. The yarn is finally prepared for weaving by the operations of

reding, warping, and sizing.

The weaving itself is performed either by the hand-loom or by the power-loom, the latter being chiefly used for weaving the finest and

broadest cloths,—such as are 12 quarters wide in the loom.

"After the cloth comes from the loom, and before it can undergo any other process, it is necessary to scour it, in order to get rid of the oil and size to which the wool and yarn have been subjected in the preparatory process. This is performed at the mill in a somewhat rude machine called the stocks, consisting of a pair of wooden mallets, worked alternately by a cog-wheel. The cloth is exposed to the stroke of the mallet on an inclined trough, the end of which is curved, so that the tendency of the stroke is to turn the cloth round and round, and different portions are alternately exposed to the operation of the hammers.

At first soap or some other detergent is used, but at last a stream of pure water is let in upon it." The cloth is then dried and dyed (if dyed in the piece), and is afterwards handed over to the burlers, who pick out all irregular threads, hairs, or dirt which may remain in the fabric. In order to effect this thoroughly, the cloth is examined both on the surface and through the web against a strong light. It is then ready for fulling or felting, a process in which, "by the united operations of beating, heat, and moisture, the minutely-jagged surfaces of the fibres of the wool are made intimately to cohere, and form not a mere woven tissue, like cotton, flax, or silk, but a felted homogeneous mass. If a piece of cloth be cut it will not unravel; the tissue is almost lost under the thick fulled surface raised upon it, and the weaving seems less to give a character to the fabric than to impart the requisite degree of strength." The cloth is afterwards scoured with fuller's earth, rinsed in pure water, and hung upon tenters till it is completely dry.

Then follows the operation of teazling, "by which the loose fibres of the wool are raised to the surface, so as to form, when duly cut and sheared, the pile or nap." The teazles are fastened into a cylinder. A piece of cloth of 40 yards consumes 3000. Teazles are grown in Yorkshire (chiefly in the neighbourhood of Leeds) and in Somersetshire, and are sold in packs of about 20,000 at (in average years) 61. a pack. Wire has been tried instead of teazles, but has not been found to answer. The superiority of the plant arises from its tendency to break off when

it meets with a knot or inequality, which wire would tear out.

The pile raised by teazling is afterwards cropped or sheared. This is done by ingenious machinery, which has replaced the old hand-work. It is then brushed by cylinders fixed in a machine, is picked over to remove all defects, and is finally packed in bales for the market.

§ XLI.—The processes of the worsted manufacture so nearly resemble those of cloth-making that they need not be described here at any length. There is, however, one important addition. It has before been said that a long-stapled wool is used for making worsted stuffs, while short wool is manufactured into cloth. This long wool, after it has been washed, is combed, a process which was formerly performed by hand labour. It is now almost entirely done by machinery, and somewery ingenious machines have been invented for the purpose.

TRAVELLER'S VIEW AND SCENERY.

§ XLII.—The special objects of interest for the traveller in Yorkshire are the manufactures, the geology, the antiquities (including the various historical sites), and the scenery of the county. The manufactures are confined for the most part to the West Riding; and whoever may visit Yorkshire with the intention of studying them must provide himself with introductions to the heads of the principal firms. Otherwise he will not readily, if at all, obtain admission to the factories. Tours (see post, 'Skeleton Tours') which will take the traveller

through the most beautiful and interesting scenery in Yorkshire, will introduce him at the same time to the most important fields of geological study, and to some of the most remarkable antiquities. The wanderer in search of the picturesque must not be sent either to the flat of Holderness or to the bare chalk hills of the Wolds; although neither district is without beauty for the true lover of nature; and the views from the border hills of the Wolds, across the great plain of York, are very fine. But the geologist will not neglect Holderness (Rtes, 6 & 7), with its lacustrine deposits, -its accumulations of drift and gravel, relics of the glaciers and ice agencies that deposited here rock fragments from Norway and from the Cumbrian Alps,-and its rapidly crumbling seachiffs. Some very fine churches (especially Patrington and Hedon-Rte. 6) are also to be found here; and the antiquities scattered over the whole district (nowhere very picturesque) which lies east of the Great Northern Railway from Doncaster to Milford Junction (Rtes. 1, 2, 3). thence on either side of the line by Selby to Hull (Rte. 5), and thence throughout Holderness (Rtes. 6, 7), will amply repay examination. On the Wolds the antiquary will find few churches worth attention; but the primeval remains, the Rudstone pillar, the numerous and important dykes and earthworks, and the houes and tumuli that dot the hills in all directions (Rtes. 10, 11, 14), are among the most striking in Yorkshire.

- § XLIII.—The great extent of Yorkshire, and the various geological formations that appear on the surface of the county, afford a greater variety of natural scenery than is to be found elsewhere in England; and the only county which can at all rival it in this respect is Devon-Much very pleasant country is to be found in the comparatively level districts of the Vale of York; the ancient Barnsdale (Rte. 2), stretching between Doncaster and Pontefract; and the rich circuit of the old forest of Elmete (Rte. 42); but the chief scenery of Yorkshire is comprised in four divisions—(1) The sea-coast; (2) The hills and moors of Cleveland and the N.E.; (3) The western mountains, extending from Barnard Castle to Skipton in Craven, and thence round to Clitheroe in Lancashire; and (4) The remains of the old forest of Sherwood in the neighbourhood of Sheffield, of which Wharncliffe Chase is the finest and most remarkable portion. Each of these districts has its subdivisions and its special points of interest: and the tourist with time at his command will find that some weeks may well be given to the thorough examination and enjoyment of each. For those whose days of travel are more limited, the most striking scenes in the county, and the best manner of visiting them within a short time, are described in the 'Skeleton Tours' (post).
- § XLIV.—The sea-coast of Yorkshire is the finest and most picturesque in England, with the exception of that of Devon and Cornwall. These western shores—especially in N. Devon the bold heights and the wooded glens opening to the sea, and in Cornwall the towering cliffs and precipices of granite and serpentine—far exceed even the finest

portions of the Yorkshire coast. But on the other hand, the sea-air of the north-is more bracing; and even Torquey cannot boest the many resources and amusements which Scarborough offers to the ordinary visitor.

The Yorkshire watering-places, reckoning them according to their size and importance, are - Scarborough, Whithy, Bridlington, Filey, Redcar, Saltburn, Hornsea, and Withernsea. Scarborough and Whitby have the finest cliff scenery in their immediate neighbourhoods, and the inland country accessible from them is very pleasant and picturesque. Whithy especially has within easy reach, for drives, or for days' excursions by railway or on foot, the fine wild scenery of the Cleveland Moors (Rtes. 14, 15). The great size of Scarborough makes it more of a "London by the sea" than most other watering-places; though in this respect it is as yet far from equalling Brighton; and it is infinitely superior to Brighton in the beauty and interest of the surrounding country, and in the case and readiness with which the true country is reached from the outskirts of the town. It is well provided with good hotels, at which the charges generally are very moderate, especially to visitors who avail themselves of the prevailing Scarborough custom of residing en pension as a fixed weekly tariff for board, lodging and attendance. Whitby is far quieter and more staid; a very great recommendation to many visitors. It has long been a favourite resort of the clergy.

Bridlington has no good coast seenery close at hand; but the sands are firm and level; and the grand chalk cliffs of Flamborough head are within an easy day's walk or excursion. The Priory Church is an attraction for the antiquary; and there are a few places of interest accessible inland. Filey is quieter and more aristocratio; its broad. open bay is very beautiful; and you may ride or drive for at least five miles along the hard, firm sands. The sands, which extend from Huntcliff rocks to the mouth of the Tees, are the main, if not the only attraction at Redcar; although there are some points of interest inland. Saltburn is (at present) a small, but a very pleasant, watering-place. Very fine cliff scenery stretches away from it E.; and the wooded ravines, which here descend to the sea, are picturesque. The coast at Hornsea is flat, and the place is otherwise not very attractive. It is. however, quiet, and conveniently situated as a watering-place for the S.E. of Yorkshire. The same may be said of Withernsea, which has

still fewer recommendations.

in all these places the hotel accommodation is good and comfortable; and lodgings are readily found.

§ XLV.—The most striking and picturesque points on the Yorkshire coast are (beginning from the S.)-Flamborough Head (Rte. 13), the extreme eastern point of the chalk in England, with the fine sea-caves in its neighbourhood. This is easily reached either from Bridlington or from Filey. Filey Brig, and the grand sweep of its bay; probably the "well-havened bay" or the "bay of the Gabrantovici" (Гавраитонком o an levoureros Euliperos rolaros) of Ptolemy .- (The word "Gabrantovioi" has puzzled commentators. No such tribe is known, or at least

is nowhere else mentioned; and it has been suggested that it may be an error for "Brigantovici,")-From the hill above Filey Brig the view is very fine, both towards Scarborough and towards Flamborough Head. Scarborough Castle. Staintondale Cliff, a range extending from Haiburn Wyke to the "Old Peak," a distance of nearly 41 m. The sea-views are magnificent, and there is a singular underoliff, interesting to geologists. The High Peak, 585 ft. above the sea, and forming the S. extremity of Robin Hood's Boy. Robin Hood's Boy itself, very striking and well worth the artist's attention, with wild, high ground behind it; and next. Whithy, with its ruined abbey. This coast between Scarborough and Whitby is accessible from either place, and the pedestrian will do well to explore it at leisure, resting perhaps at Robin Hood's Bay, where the village inn will be found passable. Beyond Whitby the sliffs become grander and more picturesque: the chief points are-Kettleness, 875 ft.; Runswick Bay, with its caverns, nearly destroyed, however, by jet-workers; Staithes, a very curious and old-fashioned fishing village, well deserving a visit, since it remains unchanged, whilst Whitby, Filey, and other ancient settlements along the coast have adopted modern improvements, and have greatly lost their original character: Boulby Cliff (660 ft.), the loftiest precipice on the English coast; Huntcliff Nab (360 ft.); and Saltburn, with the wooded glens passing inland behind it. These long, narrow valleys, through which streams find their way to the sea from the high moors of Cleveland, are very characteristic of this part of the coast. Whitby or Saltburn are the points from which this northern coast is to be examined. Only the pedestrian, however, will be able to enjoy it thoroughly.

§ XLVI. (2.)—Cleveland and the North-Eastern Moors. This, which is entirely a mountainous district, full of the most picturesque scenery, is contained within boundary-lines which extend from Pickering nearly to the sea, north of Scarborough, thence to Whitby, thence along the base of the hills from Whitby to Guisborough (the country between the hills and the sea is also part of Cleveland; but this, though occasionally not unpicturesque, is very distinct); from Guisborough by Stokesley, round the western bases of the Cleveland and Hambleton Hills, to the neighbourhood of Thirsk; and thence by Coxwold and Byland, round again to the neighbourhood of Pickering.

The character of this great moorland district is, owing to its different geology, very distinct from that of the western mountains. It is evered in parts by thick and deep heather, which is almost entirely wanting on the limestone of the west. The ridges of high, rough moor are divided by long, narrow, winding dales, each of which has its own streamlet, and is marked by a line of bright green pasture, and some wood. Broken crags of gritstone rise here and there from the dale sides; and the contrast of their greensward and sprinkled farms, with the barren upper moors, is very striking and pleasant. The most important of these dales are (beginning from the west) Bilsdale, Bransdale, Farndale, Rosedale, and the series of dales (Newtondale and others) through which the railway is carried from Pickering to Whitby.

The boundary of Cleveland proper (the "cliff" or "cleft" land—it is the "Kliffond" of the Northmen) runs across the moors, eastward, nearly in a line with Osmotherley; and the highest point of the entire district (Burton Howe, 1419 ft.) is in this division, a little S.E. of Ingleby Greenhow. The Hambleton hills continue the moorland S. of the Clevelands; but there is scarcely any true division between the ranges. The Hambletons represent, however, the range of upper colitic or calcareous hills which rest on the lower colitic of Cleveland (see Rte. 14, Pickering); and from their calcareous nature they have less heather than the others. The western ridges of both Clevelands and Hambletons command magnificent views over the great plain of York, with the hills of its western border in the distance. These vast prospects, extending over an enormous extent of the richest and most cultivated country, and seen, as they often may be, with a foreground of wild mountain, or of broken and most picturesque woodland, are almost peculiar to Yorkshire. There are views from the ridges of the Sussex Downs, and from the opposite hills of Surrey, which somewhat recall them; but they are not so extensive, and the mountainous foreground is far less grand. Some of the Dartmoor hills (especially Cawsand) command stretches of country equally vast, and the views from these more nearly resemble those in Yorkshire; which, it should be added, are of the same general character as seen from the hills E. or W. of the plain of York.

- § XLVII.—The great Cleveland district may, for tourist's purposes, be subdivided as follows:—(a.) The dales between Pickering and Whitby, with the adjoining moors on either side. (b.) The northern portion of the Cleveland hills, or Cleveland proper. (c.) The western slopes of the Clevelands and the Hambletons, from Stokesley to Thirsk. (d.) Ryedale and the southern slopes of the Hambletons; the country accessible from the line of the Thirsk and Malton railway. (c.) The mass of central moors, with their dales. The tourist who cares for thoroughly wild scenery, much of which has been but little explored, cannot do better than devote a month or six weeks to this portion of Yorkshire.
- (a.) The dales between Pickering and Whitby (Rte. 14) may be explored from the stations on the railway; and either Pickering or Whitby may serve as head-quarters. The most interesting points are fully noticed in Rte. 12. The Cawthorn Camps and Lastingham (Rte. 18A) may best be visited from Pickering or Helmsley. The moors W. of the Railway are finer and more picturesque than those E.; although the latter should not be neglected. The woods and moors of Egton, Iburndale, and the moors in its neighbourhood, are easily reached from Whitby.

(b.) For exploring the northern portion of the Cleveland hills, the best stations are Whitby (Rte. 14); Castleton (Rte. 15); Guisborough (Rte. 15); and Stokesley (Rte. 15). The walk from Whitby by Glaisedale End to Castleton (Rte. 14, Exc. b, 2) is especially to be recommended. The chief points of interest in this division are—the

moors above Castleton and Westerdale, from which very fine views are commanded; Danby Beacon, with the British village near it; Danby Castle, Roseberry Topping, and Burton Howe above Ingleby Greenhow. All these places are described in Rte. 15, which embraces this northern border of the hills.

(c.) The western slopes of the Cleveland and Hambleton hills are very picturesque, with a kind of wooded "undercliff"—a mass of tumbled hills and valleys—extending along their bases, and giving scope for the most delightful wanderings. The best centres for exploration are Stokesley; Whorlton (the Black Horse Inn); Osmotherley (Queen Catherine Inn); Northallerton and Thirsk. The most noticeable points of interest are Whorlton Church and Castle (Rte. 15); Mount Grace Priory (Rte. 16), with the grand view from the hills above it; and Whitestone Cliff, and Gormire, near Thirsk (Rte. 16).

(d.) Ryedale, which the railway traverses from Thirak to Malton, is full of interest; and there is scarcely a place noticed in Rts. 18 which will not repay a visit. The best centres are Coxwold, Helmsley, and Hovingham. From Coxwold, the tourist may visit Byland Abbey and the hills above it; at the Gilling station he will be within reach of Gilling Castle and Ampleforth; and may proceed thence to Helmsley, where Duncombe Park and Rievaulx Abbey are close at hand. This country is also to be reached from Hovingham, where is a "spa" of

saline water.

- (e.) The central moors and the dales which pierce them cannot be visited without some abandonment of the "comforts o' the Sant Market." Kirkby Moorside, Helmsley, and the country inns in Rosedale and Bilsdale, will be the tourist's best centres; but he should remember that the remoter inns, such as those in Rosedale and Bilsdale. are apt to be engaged beforehand, and to be well filled, in the shooting season. Bilsdale is most easily accessible from Helmsley (Rte. 18A): Bransdale and Farndale (both noticed in Rte. 18A) from Kirkby Moorside, or (if entered from the N.) from Castleton or Ingleby Greenhow. Rosedale (Rts. 14) may be reached either from Kirkby Moorside, or across the moors from Pickering or Whitby. The finest views in these moors are from the high ground about Blakey Cross, between the Rosedale ironworks and Ingleby; but all the dales afford delightful lingering ground, where the tourist may wander day after day with great enjoyment. The scenery is not so grand as that of the western mountains: but it has a charm of its own, which will be felt at once by all true lovers of the moorland and the heather.
 - § XLVIII. (3.)—The Western Mountains. This division embraces the whole western portion of the county, and contains some very fine mountain masses, dales which are only inferior (if at all) to those of Cumberland and Westmoreland, and some of the grandest rock scenery in England. It has already been said (§ IV.) that the comparatively low region of Ribblesdale divides this group of hills into two portions,—the north-western and the south-western. It may be further subdivided as follows, including the picturesque districts which form the containts of the higher land:—(a.) Upper Teesdale, the extreme north—

western corner of Yorkshire, with Rokeby and the neighbourhood of Barnard Castle; (b.) Richmond and its neighbourhood—Swaledale and Arkengarthdale; (c.) Leyburn and its neighbourhood—Masham and Hackfall, Wensleydale and Garadale to Sedbergh; (d.) Upper Wharfedale, and the hills forming Langstrothdale Chase; (e.) Nidderdale; (f.) Skipton and its neighbourhood—N.E. Craven, Lower Wharfedale, and Bolton Priory; (g.) Ilkley and its neighbourhood; (h.) Settle and its neighbourhood—Ribblesdale, Upper Airedale; (k.) Ingleton and its neighbourhood—Clapham Cave; (l.) S.W. Craven, Lower Ribblesdale, Forest of Bowland.

The tourist who proposes to explore all this side of Yorkshire will find that his best centres are—for the N., Barnard Castle, Richmond, Leyburn, and Hawes in Wensleydale; Pateley Bridge, for Nidderdale; and for the S., Skipton, Settle, Clapham (there is no tolerable inn at Ingleton), and perhaps Gisburne. (Other inns in each subdivision are mentioned post.) The principal scenes may be visited in a tour extending over ten days or a fortnight (or even less); but a month or six weeks will not be too much for any one who desires thoroughly to enjoy the country; and indeed, a whole summer may be spent here with advantage. The pedestrian, as usual in mountainous districts, will see most, and will find, on the whole, fewer difficulties to encounter than those who depend on horses or carriages; but all who leave the main track must be prepared for some roughing. A skaleton tour (No. IV.), embracing the whole district, points out the chief scenes and places of interest, which all should visit.

heather; and are covered for the most part with a fine, short turf, excellent for walking. Scars of rook constantly enring the hills, and are specially characteristic. Other great features of these mountains are the caves and "pots" by which the limestone is pierced; the waterfalls, here, as in Norway, called "forces" or "fosses," one of many proofs that Norwegian settlers penetrated into Yorkshire from Westmoreland; and the great rock dislocations produced by the "Craven Fault" (§ XI.), and forming the magnificent scenery of Gordale, Malham, Attermyre, and Giggleewick. Of the caves, the two most remarkable are the stalactic cavern at Clapham, and Weatheroote Cave, near ingleton (for both see Rte. 32A); the most striking waterfalls are High Force, in Upper Teesdale (Rte. 27), one of the finest and most picturesque in England, and Hardraw Force (Rte. 24), near

The general character of the district has been sufficiently indicated in the various routes which describe it. The limestone hills show little

his best subjects in the falls and streamlets that are least known. The mountains which most deserve to be scaled are Ingleborough (Rte. 82a), and Micklefell (Rte. 27), the highest in Yorkshire; the finest and most characteristic of the dales is Wensleydale (Rte. 24).

Hawes in Wensleydale. But every stream has its "forces"—all beautiful, and all full of attraction for the artist, who will often find

§ XLIX.—The various subdivisions of this great district are described at length in their several routes; but each one may here be briefly noticed.

(a.) At Barnard Castle the tourist is within reach of the beautiful scenery on the Greta and the upper course of the Tees. (See Rtes. 26, 27.) He may take up his quarters at Middleton in Teesdale or at the High Force Inn, in order to explore Upper Teesdale. The points to be visited are Rokeby and the Greta, Eggleston Abbey, Wycliffe, Bowes, the High Force, the waterfall of Caldron Snout, and Micklefell. This range of country is very varied in its scenery and is full of interest.

(b.) The Richmond district is fully described in Rts. 25. Richmond itself is one of the most picturesquely placed towns in England. Swaledale is not so striking as Wensleydale; but both it and Arkengarthdale deserve exploration. There is a tolerable inn at Reeth in Swaledale; and others (very small and humble) at Muker and at

Thwaite.

(a) The whole of Rte. 24 (Leyburn and its neighbourhood) may safely be recommended for adoption by the tourist who desires to enjoy some fine mountain scenery, and to make himself acquainted with the most characteristic of Yorkshire dales. From Leyburn, Middleham (church and castle), Jervaulx Abbey, and Bolton Castle, may be visited. (Hackfall (Rte. 22), a most picturesque scene of wood and water, may also be visited from Leyburn; but, perhaps, more readily accessible from Ripon.) At Aysgarth and at Askrigg, which stand in the centre of Wensleydale, are comfortable inns. In Wensleydale itself the scenes and places to be noticed are fully described in Rte. 24.

(d.) For Upper Wharfedale and Langstrothdale, the tourist will find his best centres at Kilnsey, at Kettlewell, and at Buckden (Rte. 31); but here he must expect to rough it. The inns are generally clean, and tolerably comfortable, but they are thoroughly rustic hostelries; and no one should venture into this district who cannot find his full reward in the wild scenery which will surround him. The country is described in Rte. 31.

(c.) Nidderdale may be reached by railway from Harrogate (Rtc. 21). Brimham Crags lie off the railway in the lower part of the dale. Pateley Bridge is the centre from which all the upper dale may be explored. There is some good scenery near the village; and Upper Nidderdale is quite worth exploration. The lead-mines at Greenhow, and the stalactite cavern at Stump Cross, are also to be reached from Pateley Bridge.

(f.) There is a very good inn at Skipton (Rte. 30), from which place Rylstone (Rte. 31), Barden, Bolton Priory, and the lower Wharfe, may be explored. Skipton itself is interesting for its old castle of

the Cliffords.

(g.) Ilkley (Rte. 30) abounds in hotel accommodation; and its many

advantages as a centre are fully noticed in the route.

(h.) Settle (Rte. 32) contains an excellent old-fashioned inn, and is, perhaps, the best point from which to visit Gordale and Malham Cove (Rte. 32)—scenes which no tourist should leave Yorkshire without seeing. There is a small inn at Horton, in Ribblesdale, from which the

ascent of Penyghent (Rte. 32) may be made. Either Penyghent or Ingleborough may, however, be climbed in a long day's excursion from Settle.

(k.) The neighbourhood of *Ingleton* (Rte. 32A) is very interesting and there is now good accommodation for tourists. There is also a good inn at Clapham (Rte. 32A), whence Ingleton is easily reached by railway. Weathercote Cave, Thornton Force, Kingsdale, and Yordas Cave, are all within reach of Ingleton, and are all scenes of very great

beauty and interest.

(1.) South-West Craven (Rte. 33) may be explored from either Settle or Skipton. The accommodation at Gisburne is good, and that place is nearer to the more interesting parts of the district. This contains much picturesque scenery, although the hills of the forest of Bowland, which form its western border, are by no means so fine as those farther north. Bolton Hall and Sawley Abbey will repay the antiquary for his visit. The interest of the latter is principally confined to its well-made-out ground-plan.

- § L. (4.)—The Forest district in the neighbourhood of Sheffield. This corner of Yorkshire, over which the great forest of Sherwood once extended, is very distinct in character, and should on no account be neglected by the tourist. Sheffield, Barnsley, and Rotherham are the best centres. The chief places to be visited are Wharncliffe Chase (Rts. 44), one of the finest scenes of wood and broken rock in the county; Wentworth Castle and park (Rts. 40); and Wentworth Woodhouse (Rts. 45). In these routes the district is fully described.
- § LI.—The most important collections of pictures in Yorkshire are at—Castle Howard (Earl of Carlisle, Rte. 12); Duncombe Park (Lord Feversham, Rte. 18A); Hornby Castle (Duke of Leeds, Rte. 23); Temple Newsam (Mrs. Meynell Ingram, Rte. 28); Gisburne Park (Lord Ribblesdale, Rte. 33); Nostel Priory (Charles Winn, Esq., Rte. 38); Wentworth Castle (F. Vernon Wentworth, Esq., Rte. 40); and Wentworth Woodhouse (Earl Fitzwilliam, Rte. 45). There are less extensive but valuable and interesting collections at Escrick Park (Lord Wenlock, Rte. 1); at Hovingham Park (Sir W. Worsley, Rte. 18); at Thornton-le-Street Hall (Earl Cathcart, Rte. 16); and at Brough Hall (Sir John Lawson, Rte. 25). Some portraits worth notice are at Bolton Hall (Lord Bolton, Rte. 24); at Harewood (Earl of Harewood, Rte. 29); at Bolton Priory (Duke of Devonshire, Rte. 30); and at Wortley Hall (Lord Wharncliffe, Rte. 44).

At Newby Hall (Lady Mary Vyner, Rte. 22) is a fine collection of ancient statuary. There is some very important statuary at Castle

Howard, and at Duncombe Park.

§ LII.—The traveller in Yorkshire will generally find that the people, especially in the more remote districts, are, if rough, very hospitable, and very ready to assist him in any difficulty. The population of the great towns differs, of course, very greatly from that of the open country; but, here too, civility will always bring civility; and the tourist who shows a real desire to examine and to under-

stand the various manufacturing processes will have (if he bring proper introductions) all possible assistance readily afforded to him. Both in town and country the dialects will often puzzle a Southerner -(that of Cleveland is very peculiar, and is old Norse in accent, even when the words are English). These differ greatly in different parts of the country; and although glossaries have been published for many separate districts, a general survey of the Yorkshire "speech" still awaits the leisure and the learning of some competent northern archæologist. Some valuable observations on this Northumbrian English, which Higden, writing about 1850, describes as "so harsh and rude that we Southern men can hardly understand it" ('Polychronicon, ap. Gale'), will be found in an essay by the late Mr. Garnett, in the 'Quarterly Review' for February, 1836 ('English Dialects'); but the differences between the many local dialects in the county deserve to be carefully examined and compared. The general foundation of the Yorkshire speech is no doubt Anglian, which remains most pure in the Craven district; but this has been overlaid at different times and in different places by Danish and Norse, and perhaps by Flemish or other Low Dutch dialects. Besides Yorkshire, Northumbrian English prevails throughout Northumberland and Durham; and (with some variation) in Cumberland, Westmoreland, and Lancashire to the north of the Ribble. "It is, as might be expected, more like English to the south of the Tees, and more like Scotch as we approach the Tweed, but its essential peculiarities are everywhere preserved. It is unquestionably, 'pace Ranulphi Higdeni dixerimus,' the most pleasing of our provincial forms of speech. especially as spoken in the North and East Ridings of Yorkshire. The Durham pronunciation, though soft, is monotonous and drawling; and that of Northumberland is disfigured by the burr and an exaggerated Scotch accent."—Garnett. It is not every one who will agree with Mr. Garnett in this matter; but the difference between southern English and the harder northern is so marked, that the ear which has from youth been accustomed to one will hardly be able to appreciate fairly the merits of the other.

Anglian, of which Northumbrian English forms one division, embraces two others—the East Anglian of Norfolk and Suffolk; and the Middle Anglian of Lincolnshire, Nottinghamshire, and East Derbyshire. The Northumbrian of Yorkshire, in its medieval stages, is well illustrated by the works of Richard Rolle, the "Hermit of Hampole," who died in 1349. (See a short notice of him and of his books in Rte. 1); and by the very remarkable religious verses containing the Creed and the Ten Commandments, translated from the Latin, under the direction of Archbishop Thoresby (1352-1373), by John de Taystek (John of Tavistock?), a monk of St. Mary's, York, to be distributed among the people for their better instruction. The Ten Commandments and the preamble are printed in Mr. Raine's 'Lives of the Archbishops of York,' i. p. 471 seq. All the verses will be found in Mr. Halliwell's 'Yorkshire Anthology' (printed for

private circulation in 1851). This volume contains some good examples of the modern dialects, including 'Marjory Moorpoot and Gulwell,' illustrating the speech round Roseberry Topping:—"Ah's Yorkshire," says Marjory, "by ma truly! Ah wor bred and boorn at canny Yattan, aside o' Roseberry Toppin;"—and a 'Yorkshire dialogue in the pure natural dialect as it is now commonly spoken in the north parts of Yorkshire, 1697.'—(This is by Giles Merrington, a native of Northallerton, and was published by him in the same volume with a poem "in praise of Yorkshire ale,") For some remarks on Chaucer's use of the Craven dialect see Rte. 31, Langstrothdule.

The most important published glossaries are- The Hallamshire Glossary, by the Rev. Joseph Hunter, 1829; 'The Dialect of Craven,' by a Native (the Rev. W. Carr, of Bolton Abbey), 2 vols. 8vo., 1830; 'A Glossary of Provincial Words used in Teesdale,' 1849: 'The Sheffield Dialect,' by Abel Bywater, 1854; 'The Dialect of Leeds and its Neighbourhood, London, J. R. Smith, 1862; 'A Specimen of the Bilsdale Dialect,' Northallerton, 1832; 'A Glossary of Words and Phrases collected in Whitby and its Neighbourhood, 1855; 'A Glossary of the Cleveland Dialect,' by the Rev. J. C. Atkinson, London, 1868. 'The Bairnsla Folks Annual, by Tom Treddlehoyle,' is an almanae in the local dialect, published regularly at Barnsley. Others are published at Leeds. Bradford, and elsewhere. A 'List of Words used in the Mountainous District of the West Riding, by Rebert Willan, M.D., will be found in the 'Archeologia' for 1811. Versions of the 'Song of Solomon,' in the Craven dislect, in that of Sheffield, and in those of W. and N. Yorkshire, were compiled and published under the direction of Prince The story of the 'Terrible Knitters e' Dent,' in L. Napoleon. Southey's 'Doctor,' is a very good illustration of the dialect of that nert of Yorkshire which borders on Westmoreland.

- § LIII.—There is no lack of good cheer in Yorkshire; but local "plats" are not numerous. Yorkshire pie, however, in which game of all sorts is imprisoned within huge standing walls of crust, is a universal favourite at Christmas time. Yorkshire hams are excellent, and generally of enormous size. The western dairies are celebrated for their cream cheeses: and a very good cheese—sometimes as good as Stilton—is made at Cotherstone and the villages round, in the neighbourhood of Barnard Castle. Wensleydale cheese has also a wide reputation, which it has maintained from an early period. The menks of Jervaulx, at the eastern opening of the dale, were famous for their cheese, their singing, and their white horses.
- § LIV.—The Botanist should provide himself with Mr. J. G. Baker's 'North Yorkshire; Studies of its Botany, Geology, Climate, and Physical Geography,' London, 1863. Baker and Nowell's 'Yorkshire Flora' contains a complete list of the flowering plants, ferns, and mosses, with the localities of many of the rarer species. The publisher was Pamplin, 45, Frith Street, Soho.

SKELETON TOURS.

No. I .- A GENERAL TOUR OF YORKSHIRE,

Embracing the chief points of interest throughout the county (Scenery, Antiquities, and Manufactures). The more important are marked with an asterisk. This Tour is of ten weeks; but many places described in the Routes are necessarily omitted.

Dava

1. London to Doncaster.

2. See *Doncaster church and the race-course in the morning. In the afternoon visit (by rail) *Coningsborough Castle.

3. By rail to Selby. See *Selby church. Thence by rail to Hull,

visiting *Howden church on the way.

4. See the docks and the church of the Holy Trinity at Hull. In the afternoon visit (by rail) the churches of *Hedon and *Patrington.

5. From Hull by rail to Beverley. See the Minster, and St. Mary's

church.

6. Beverley by Market Weighton to York, visiting by the way Goodmanham and Londesborough.

7. Sunday at York.

8. At York. See the *Minster; *St. Mary's Abbey and the gardens of the Philosophical Society; some of the parish churches (see Route 1 for the most interesting); and walk round the *walls.

9. From York to Castle Howard, Visit by the way Sheriff Hutton (church and castle) and Kirkham (abbey ruins). No inn at Castle

Howard.

- 10. See the *house at Castle Howard. Proceed to Malton. See the church and Roman station at Old Malton. Thence by rail to Scarborough.
- 11. At Scarborough. In the morning see the *Castle and the parish church. In the afternoon climb Oliver's Mount, and afterwards visit,

while the band is playing, the *Spa and Promenade.

12. By rail to Filey. See the *church and the *sanda. Walk along

*Filey Brig. Thence by rail to Bridlington.

13. Visit *Flamborough Head and the Caves on the way to Bridlington.

14. Sunday at Bridlington. See the *Priory Church.

15. Drive to Rudstone. See the church and *upright stone; and thence over the Wolds (so as to get some idea of that district), either to Hummanby or Filey. Thence by rail to Scarborough.

16. Drive in the morning through the Forge Valley to *Hackness, and thence round by Scalby. In the evening proceed by rail to Pickering.

[Yorkshire,]

Dave.

17. See Pickering *Church and *Castle. Then drive to Lastingham, visiting the *Cawthorn Camps on the way. Return to Pickering, and proceed by rail to Whitby.

18. At Whitby. See the old town and the *Abbey ruins. In the afternoon walk or drive to the Park of Mulgrave and old Castle, and

if time allows, walk to Sandsend and see the site of the alum-works.

19. From Whitby the *Egton Woods; and either walk or drive thence to Rosedale. If possible, sleep at the Crown Inn in Rosedale village.

20. See the Rosedale iron-works; and walk or drive (the road is but indifferent for wheels) by Ralph Cross, along the ridge between Westerdale and Danbydale to Castleton. Return by rail to Whitby. [The route planned for these two days will give an excellent idea of the Cleveland Moors; but, at any rate, two days should be given to excursions among the moors round Whitby.]

21. Sunday at Whitby.

22. The coast-road from Whitby to Saltburn.

- 23. Saltburn by rail to *Middlesbrough. See one of the great *iron-works. Thence by rail to Guisborough, See the *Priory ruins.
- 24. Guisborough to *Roseberry Topping. Thence to Stokesley and Whorlton. See *Whorlton church and Castle. Sleep at the Black Horse at Whorlton.

25. Visit *Mount Grace Priory and Osmotherley. Thence to North

Allerton. See the church there.

26. To Thirsk by train. See the *church at Thirsk. Drive from Thirsk to Helmsley; visiting *Gormire and *Whitestone Cliff by the way.

27. See Helmsley church, *Castle, and *Duncombe Park in the morn-

ing; Rievaulx Abbey in the afternoon.

28. Sunday at Helmsley.

29. Helmsley to Gilling. See *Gilling Castle. By rail to Boroughbridge, visiting *Coxwold on the way. See the *Devil's Arrowa, at Boroughbridge.

30. See the Roman remains at *Aldborough. Drive to Knaresborough. See the *church, castle, Dropping Well, and St. Robert's

Cave. Thence by rail to Harrogate.

31. At Harrogate. In the afternoon to the *Brimham Rocks.

82. By rail to Ripon. See the *Minster in the morning. In the afternoon *Fountains Abbey.

33. Drive from Ripon by *Hack Fall to Tanfield. Thence to Leyburn, visiting *Jervaulx Abbey and *Middleham Castle on the way.

34. Leyburn to Hawes; visiting *Wensley church; *Bolton Castle; Aysgarth church and *Force; and the Waterfalls near Askrigg.

35. Sunday at Hawes, or try the Dragon at Hardraw; visit *Hardraw Force.

36. Hawes to Sedbergh. See Sedbergh church, and climb the mound above the town. Thence by rail to Barnard Castle.

37. See the *Castle. Drive to *Bokeby, and thence round by Brignall to Bowes, taking care to walk by the Greta at Brignall, as recommended in Rts. 26. Return to Barnard Castle.

Dava.

38. Drive to the *High Force, by Cotherstone, Romaldkirk, and Middleton in Teesdale. See the High Force, and sleep either at Middleton or at the High Force Inn.

39. Visit the *Caldron Snout; and if the day is fine, ascend *Mickle-fell. Return to Middleton.

- 40. Return to Barnard Castle, and drive thence to Richmond,
- 41. See Richmond *Castle and church. Walk to *Easby Abbey. Drive to the *Racecourse.

42. Sunday at Richmond.

43. Drive from Richmond to Bedale,—seeing by the way the Roman station at Catterick; *Brough Hall (pictures), if possible; and *Hornby Castle (pictures). At Bedale see the *ohurch.

44. From Bedale by rail to Ilkley. Stop at Otley and ascend the

*Chevin.

45. See the church at Ilkley. Drive to *Bolton Priory; and walk through the woods to *Barden Tower, where the carriage should be in waiting. Drive thence to Skipton.

46. Excursion from Skipton by Rylston to Kilnsey Crag.

47. Drive from Skipton to Settle (or order a carriage from Malham to meet you at Bell Busk station); visiting *Gordale and *Malham Cove by the way.

48. Excursion from Settle to Horton and Selside. If fine, ascend

Penyghent.

49. Sunday at Settle.

50. By raif to Clapham. See the *Cavern. Thence a good pedestrian should (if the weather is fine) walk across *Ingleborough, and, descending upon *Chapel-le-Dale, regain the railway at Ingleton, returning thence to Settle. Otherwise drive from Clapham to Ingleton, and thence to *Chapel-le-Dale. Return to Settle.

51. Rail from Settle to *Bolton-in-Bolland, and *Sawley Abbey.

Thence by rail to Skipton.

52. Skipton by rail to Bradford—stopping at Keighley to visit *Haworth.

53. See Bradford church, and *the view from the cemetery. In the afternoon to *Saltaire.

- 54. Visit the *Low Moor Ironworks; and proceed thence by rail to Halifax. See the *parish church, and the *church of All Saints, Haley Hill.
- 55. Halifax to Leeds. See the *parish church, *St. John's church, and the *Museum of the Institute. Afterwards *Kirkstall Abbey.

56. Sunday at Leeds.

57. If introductions have been procured, give the day to the factories of Leeds. Or make an excursion to *Adel church, and thence to *Harewood church and Castle. (The house and gardens are open on Thursdays only.)

58. Visit *Temple Newsam (pictures). Return to Leeds, and proceed thence by rail to Wakefield. See *Wakefield church, and the

*chantry on the bridge.

Days.

59. Excursion to Nostel Priory (pictures); thence by rail to Ponte-

fract. See the *Castle and church. Return to Wakefield.

60. Wakefield by rail to Huddersfield; stopping at the Thornton Lees station for visits to Dewsbury *church and *Thornhill church. Batley, the great seat of shoddy manufacture, may also be visited on the way.

61. Visit *Almondbury Camp and church; and *Woodsome Hall.

Return to Huddersfield.

62. Huddersfield, by Penistone, to Barnsley. See Penistone church and *Silkstone church. Make an excursion to Monk Bretton Priory.

63. Sunday at Barnsley.

64. Drive to Wentworth Castle. Returning to Barnsley, proceed to Sheffield by rail.

65. See St. Peter's church at Sheffield, and visit a steel factory and

warehouse also the park and cemetery. 66. Excursion to Wharncliffe Chase.

67. Sheffield to Rotherham *church; and *Wentworth Woodhouse

(pictures). Return to Rotherham.

68. Drive from Rotherham by *Roche Abbey and Tickhill (Castle and church), to Bawtry, where the Great Northern Railway is gained.

No. IL.-A MONTH'S WALKING TOUR.

This is the route followed and described in Mr. White's 'Month in Yorkshire.' The longest day's walk is 26 miles; the next 22; and all the rest from 14 to 18. Many of the resting-places are necessarily small country inns, where the accommodation, though generally clean, is otherwise, of course, but indifferent.

Loudon to Hull by steamer.

Days.

1. Excursion by rail to Patrington. Thence walk to Spurn Head and back. Return by rail to Hull.

2. To Beverley by rail. Walk to Hornsea.

3, Rail to Bridlington. Thence by Flamborough Head to the village of Flamborough.

4. Walk to Filey. Thence through Scarborough to Cloughton.

5. Walk by Robin Hood's Bay to Whitby.

- 6. At Whitby. Excursions to Egton Bridge or to Mulgrave Park. Return to Whitby.
- 7. Along the coast by the old alum-works at Sandsend, to Runswick and Staithes.
 - 8. Along the coast to Redear. Thence by Kirkleatham to Guisborough.

9. Climb Roseberry Topping. Thence to Marton and Stockton. By rail from Stockton to Darlington.

Dave.

10. By rail to Barnard Castle. Walk to Rokeby and Wycliffe. Return to Barnard Castle in time for the omnibus to Middleton in Teesdale. (It starts about 5.30 P.M.) Sleep either there, or 5 m. further, at the High Force Inn.

11. See the High Force. Walk to Caldron Snout. Thence climb

Mickle Fell; and descend on Brough.

12. From Brough to Thwaite in Swaledale. Thence over the Buttertube Pass to Hawes.

13. Hawes to Bainbridge. Thence visit the "forces"-Mill Gill and

Whitfield, near Askrigg. Sleep at Bainbridge.

14. Climb Addleborough. Descend on Simmer Water, walk thence through Widdle to the inn at Newby Head.

15. By the Gearstones inn and Chapel-le-Dale to Clapham. In fine

weather cross Ingleborough from Chapel-le-Dale,

16. By rail to Skipton. Thence to Bolton Priory. Thence by Burden to the Angler's Inn at Kilnsey.

17. By Kettlewell and Buckden; down Bishopdale to Avsgarth.

18. By Carperby and Bolton Castle. Thence by the "Scarth Nick" read to Richmond. Visit Easby. View from Race-course.

19. By rail to Ripon. Walk to Fountains Abbey. By rail from

Ripon to Thirsk.

20. Walk from Thirsk, by Gormire and the Hambletons, to Rievaulx Abbey. Themee to Helmsley through Duncombe Park. By rail to Gilling. Thence by train to York.

21. At York.

22. By rail to Leeds. Walk to Kirkstall Abbey. By rail to Settle.

23. Walk to Gordale and Malham. Back to Settle. By train to Keighley.

24. Walk to Haworth (?) and back. By train to Shipley. Thence to

Saltaire. Rail to Bradford.

25. By rail to Mirfield and Batley. Thence to Wakefield.

26. Rail to Sheffield.

No. III.—CLEVELAND AND THE COAST.

The inns marked * will not afford extensive accommodation, but are excellent centres for pedestrians.

Routes and Resting-places,

Places to be visited.

YORK TO MALTON

.. Between York and Malton see Sheriff Hutton Castle; Kirkham Priory; and Castle Howard.

MALTON TO SCARBOBOUGH

.. From Scarborough visit Hackness, and the coast N. and S.

Routes and Resting-places.	Places to be visited.
Filey	Filey Brig and the coast to Flamborough.
Bridlington	Flamborough Head and the Caves.
*Johnstone Arms Inn, at Hack- ness	Troutdale, the upper valley of the Der- went, and the neighbouring moors.
	This is the best centre for exploring
borough.	the moors between Scarborough and Robin Hood's Bay.
Pickering	Cawthorn Camps. Lastingham. New-tondale. The moors E. of the railway.
WHITBY	The coast N. and S. Egton Bridge. Glaisdale, and all Eskdale between
	Egton and Castleton. Iburndale,
	and the moors E. of the railway. Gothlandale and Wheeldale.
*Rosedale (Crown Inn)	Lower part of Rosedale. Farndale.
	The moors between Rosedale and Castleton.
*Castleton	Danby Dale, Castle, and Moors. Free- borough Hill. Westerdale. Base- dale.
Ingleby Greenhow	Upper parts of Bransdale and Bils-dale.
Guisborough	Roseberry Topping. The valleys toward Saltburn.
SALTBURN-BY-THE-SEA	Marske; Redcar. The valleys inland. The coast eastward.
STAITHES	Boulby Cliffs. Runswick.
*BLACK HORSE INN, WHORLTON.	Cleveland Hills, between Whorlton and Ingleby Greenhow.
*Queen Catherine Inn, Os- motherley.	Mount Grace Priory. Walk down Ryedale to Rievaulx.
THIRSK	Hambleton Hills. Whitestone Cliff.
	Gormire.
Coxwold	Byland Abbey. Walk over the hills to Rievaulx.
	Castle.
HELMSLEY	Rievaulx. Duncombe. Lower part of Bilsdale.
*INN AT CHOP GATE IN BILE- DALE, near Biledale Church.	Upper parts of Bilsdale and Brans- dale.
	Bransdale. Lower part of Farndale.
	₹

No. IV.—THE WESTERN MOUNTAINS.

(Inns marked * are only fitted for pedestrians.)

•					• •
Routes and	Restin	g-place	16.		Places to be visited.
LEEDS TO SKIP	TON	••	••	••	Between Leeds and Skipton, Haworth and the surrounding Moors should be visited from Keighley.
SEIPTON	••	••	••	••	Moors between Skipton and Bolton; and between Skipton and Thresh- field.
DEVORBHIRE A	BMS,	Bora	COM	••	Bolton Priory. The Wharfe and hills overlooking the river here.
ILELEY					Rombald Moor. Otley Chevin.
KIRKBY MAL	UAW.	••	••	••	Malham Cove, Gordale, and surround-
TIMES! MAIL		••	••	••	ing moors.
Angler's Arm	s, K	LNSE	¥		Wharfe and neighbouring moors. Skifare, and Littondale.
Kepplewell	••	••	••	••	All Upper Wharfedale. Great Whern-side.
*Buckden	••		••	••	Bishopdale. Waldendale. Parts of Langstrothdale.
SETTLE	••	••	••	••	Ribbledale. Penyghent, and all the neighbouring moors. Forest of Bow- land, S.W.
GIEBURNE	••	••	••	••	Lower Ribbledale. Bolton Hall. Saw- ley Abbey.
CLAPHAM					The Caves. Ingleborough.
LIGLETON	••	••	••		Kingsdale. Chapel-le-Dale. Whern-
	••	••	••	••	side. Yordas Cave, and Easgill.
	Inn,	near	Ribb	le-	Ingleton Fells. Cam Fell. Parts of
Head.	TT.				Langstrothdale.
INN AT NEWS	у пі	EAD	••	••	Widdale Fell, and surrounding moors.
HAWES	••	••	••	••	Hardraw Force. The Buttertubs Pass, between Hardraw and Thwaite. Hawes may serve as a centre for
					much of the country between it and Ingleton; and from it the hills
					may best be explored which lie between Hawes and Sedbergh,
Sedbergh	••	••	••	•• :	How Gill. The Calf. Baugh Fell. Dent Dale; and all the country on the Westmoreland border.
Askrigg	••	••	••	••	Semmer Water. Bainbridge. Aysgarth. The hills between Wensleydale and Swaledale.
AYSGARTH	••	••	••	••	Bishopdale. Waldendale. Pen Hill.

Routes and Resting-places.	Paces to be visited.
LEYBURN	All Wensleydale may be explored from here. Middleham. Jervaulx. Country between Leyburn and Richmond. Swaledale.
*MUKER OR *THWAITE	Buttertubs Pass. Upper part of Swaledale.
Reern	Swaledale. Arkengarthdale.
RICHMOND	
Barnard Castle	Rokeby. Eggleston Abbey. The Greta. Wycliffe. Bowes. Country between Barnard Castle and Mid- dleton. Stainmore.
MIDDLETON IN TEESDALE, High Force Inn.	or Upper Valley of Tees. Lunedale. High Force, Caldron Snout. Mickle Fell, and surrounding moors.

ROUTES.

a The names of places are printed in italics only in those routes where the places are described.

BOUTE PAG	E ROUTE PAGE
1. London to York, by Don-	15. Whitby to Stockton-upon-
caster and Selby.—(Great	Tees, by Stokesley (Guis-
Northern Railway)	Tees, by Stokesley (Guisborough, Roseberry Top-
1 a. London to York, by Luton,	ping) 208
Bedford, Leicester, Lough-	15 A. Whitby to Guisborough
borough, and Trent Junc-	and Middlesbrough 216
	6 16. York to Darlington, by
2. Doncaster to York, by Knot-	Thirsk and North Allerton 218
tingley.—Bolton Percy 7	3 17. Stockton to Saltburn, by
3. London to Hull, by Don-	Middlesbrough and Redcar 230
caster, Thorne, and Goole.	18. Thirsk to Malton by Cox-
—Hatfield Chase 8	
4. Knottingley to Goole, by	Gilling 236
4. Knottingley to Goole, by Snaith 10	Gilling 236 2 18 A. Gilling to Pickering, by
5. Milford Junction to Hull,	Helmsley (Rievaula Abbey).
by Selby and Howden 10	Kirkby Moorside, and Las-
6. Hull, by Hedon and Pa-	tingham—Rail 242
trington to Withernsea.	19. York to Boroughbridge and
(Spurn Head.) The Hol-	19. York to Boroughbridge and Aldborough 252
derness Coast to Hornsea 10	3 20. York to Knaresborough and
7 Hull to Hornsea and Skipsea 12	Harrogate (Marston Moor) 256
8. York to Beverley and Hull,	21. Harrogate to Pateley Bridge
by Market Weighton.—	(Brimham Craggs), Nid-
Also to Selby 124	derdale
9. Hull to Bridlington, by Be-	22. Harrogate to Northallerton,
verley and Driffield 147	
10. Beverley to Bridlington-	Hackfall, and Tanfield 274
Road 150	23. Northallerton to Leyburn, by
11. Malton to Driffield. (The	Bedale (Middleham, Jer-
Wolds) 152	l vaulx Abbey, Hornby
12. York to Scarborough, by	Castle)
Castle Howard and Malton 156	1 24. Wensleydale. — Leyburn to
13. Scarborough to Filey, Flam-	Hawes Junction and Sed-
borough Head, and Brid-	bergh, by Bolton Castle,
lington	Aysgarth, Askrigg, Hawes,
14. York to Whitby, by Malton	(Hardraw Force) 812
and Pickering 190	24 A. Hawes to Muker 322
[Vorkshire]	В.

Routes and Resting-places.	Paces to be visited.
LEYBURN	All Wensleydale may be explored from here. Middleham. Jervaulx. Country between Leyburn and Richmond, Swaledale.
*MUKER OR *THWAITE	Buttertubs Pass. Upper part of Swaledale.
Rеети	Swaledale. Arkengarthdale.
RICHMOND	Swaledale. Easby Abbey. Catter-
	ick, Hornby Castle. Country between Richmond and Barnard Castle.
BARNARD CASTLE	Rokeby. Eggleston Abbey. The Greta. Wycliffe. Bowes. Country between Barnard Castle and Mid- dleton. Stainmore.
MIDDLETON IN TEESDALE, High Force Inn.	or Upper Valley of Tees. Lunedale. High Force. Caldron Snout. Mickle Fell, and surrounding moors.

ROUTES.

• The names of places are printed in italics only in those routes where the places are described.

BOUTE PAGE	ROUTE PAGE
1. London to York, by Don-	15. Whitby to Stockton-upon-
caster and Selby.—(Great	Tees, by Stokesley (Guisborough, Roseberry Top-
Northern Railway) 2	borough, Roseberry Top-
1 a. London to York, by Luton,	ping) 208
Bedford, Leicester, Lough-	15 A. Whitby to Guisborough
borough, and Trent Junc-	and Middlesbrough 216
tion.—(Midland Railway). 76	16. York to Darlington, by
2. Doncaster to York, by Knot-	Thirsk and North Allerton 218
tingley.—Bolton Percy 78	17. Stockton to Saltburn, by
3. London to Hull, by Don-	Middlesbrough and Redcar 230
caster, Thorne, and Goole.	18. Thirsk to Malton by Cox-
—Hatfield Chase 85	wold, Byland Abbey, and
4. Knottingley to Goole, by	Gilling 236
Snaith 102	18 A. Gilling to Pickering, by
5. Milford Junction to Hull,	Helmsley (Rievaulx Abbey),
by Selby and Howden 104	Kirkby Moorside, and Las-
6. Hull, by Hedon and Pa-	tingham—Rail 242
trington to Withernsea.	19. York to Boroughbridge and Aldborough 252
(Spurn Head.) The Hol-	Aldborough 252
derness Coast to Hornsea 108	20. York to Knaresborough and
7 Hull to Hornsea and Skipsea 120	Harrogate (Marston Moor) 256
8. York to Beverley and Hull,	21. Harrogate to Pateley Bridge
by Market Weighton.—	(Brimham Craggs), Nid-
Also to Selby 125	derdale
9. Hull to Bridlington, by Be-	22. Harrogate to Northallerton,
verley and Driffield 147	by Ripon, Fountains Abbey,
10. Beverley to Bridlington-	Hackfall, and Tanfield 274
Road	23. Northallerton to Leyburn, by
11. Malton to Driffield. (The	Bedale (Middleham, Jer-
Wolds)	vaula Abbey, Hornby
12. York to Scarborough, by	Castle) 301
Castle Howard and Malton 156	24. Wensleydale. — Leyburn to
13. Scarborough to Filey, Flam-	Hawes Junction and Sed-
borough Head, and Brid-	bergh, by Bolton Castle,
lington 181	Aysgarth, Askrigg, Hawes,
14. York to Whilby, by Malton and Pickering 190	(Hardran Force) 512
and Pickering 1901	
[Yorkshire.]	В

Routes and Resting-places.	Places to be visited.
LEYBURN	All Wensleydale may be explored from here. Middleham. Jervaulx. Country between Leyburn and Richmond, Swaledale.
*Muker or *Thwaite	Buttertubs Pass. Upper part of Swaledale.
Rеети	Swaledale. Arkengarthdale.
RICHMOND	Swaledale. Easby Abbey. Catter-
	ick. Hornby Castle. Country between Richmond and Barnard Castle.
BARNARD CASTLE	Rokeby. Eggleston Abbey. The
	Greta. Wycliffe. Bowes. Country between Barnard Castle and Mid- dleton. Stainmore.
MIDDLETON IN TEESDALE, High Force Inn.	or Upper Valley of Tees. Lunedale. High Force. Caldron Snout. Mickle Fell, and surrounding moors.

ROUTES.

• The names of places are printed in *italics* only in those routes where the places are described.

BOUTE PAGE	ROUTE PAGE
1. London to York, by Don-	15. Whitby to Stockton-upon-
	Tees, by Stokesley (Guis-
Northern Railway) 2	Tees, by Stokesley (Guis- borough, Roseberry Top-
1 a. London to York, by Luton,	ping) 208
Bedford, Leicester, Lough-	15 A. Whitby to Guisborough
borough, and Trent Junc-	and Middlesbrough 216
tion (Midland Railway). 76	
2. Doncaster to York, by Knot-	Thirsk and North Allerton 218
tingley.—Bolton Percy 78	
3. London to Hull, by Don-	Middlesbrough and Redcar 230
caster, Thorne, and Gools.	18. Thirsk to Malton by Cox-
—Hatfield Chase 85	
4. Knottingley to Goole, by	Gilling 236
4. Knottingley to Goole, by Snotth 102	18 A. Gilling to Pickering, by
5. Milford Junction to Hull,	Helmsley (Rievaula Abbey),
by Selby and Howden 104	
6. Hull, by Hedon and Pa-	tingham—Rail 242
trington to Withernsea.	19. York to Boroughbridge and
(Speern Head.) The Hol-	19. York to Boroughbridge and Aldborough 252
derness Coast to Hornsea 108	20. York to Knaresborough and
7 Hull to Hornsea and Skipsea 120	Harrogate (Marston Moor) 256
8. York to Beverley and Hull,	21. Harrogate to Pateley Bridge
by Market Weighton.—	(Brimham Craggs), Nid-
Also to Selby 125	derdale 268
9. Hull to Bridlington, by Be-	22. Harrogate to Northallerton,
verley and <i>Driffield</i> 147	by Ripon, Fountains Abbey,
10. Beverley to Bridlington—	Hackfall, and Tanfield 274
Road	23. Northallerton to Leyburn, by
11. Malton to Driffield. (The	Bedale (Middleham, Jer-
Wolds) 152	vaulx Abbey, Hornby
12. York to Scarborough, by	Castle) 301
Castle Howard and Malton 156	24. Wensleydale. — Leyburn to
13. Scarborough to Filey, Flam-	Hawes Junction and Sed-
borough Head, and Brid-	bergh, by Bolton Castle,
lington	Aysgarth, Askrigg, Hawes,
14. York to Whitby, by Malton and Pickering 190	(Hardraw Force)
and Pickering 190	24 A. Hawes to Muker 322
[Yorkshire.]	В

Routes and Resting-places.	Places to be visited.
LEYBURN	All Wensleydale may be explored from here. Middleham. Jervaulx. Country between Leyburn and Richmond. Swaledale.
*MUKER OR *THWAITE	Buttertubs Pass. Upper part of Swaledale.
Rеетн	Swaledale. Arkengarthdale.
RICHMOND	Swaledale, Easby Abbey. Catter-
	ick. Hornby Castle. Country
•	between Richmond and Barnard
D	Castle.
BARNARD CASTLE	Rokeby. Eggleston Abbey. The
	Greta. Wycliffe. Bowes. Country
	between Barnard Castle and Mid-
	dleton. Stainmore.
	or Upper Valley of Tees. Lunedale.
High Force Inn.	High Force, Caldron Snout.
	Mickle Fell, and surrounding
	moors.

ROUTES.

*a The names of places are printed in *italics* only in those routes where the *places* are described.

PAGE PAGE	
1. London to York, by Don-	15. Whitby to Stockton-upon-
caster and Selby.—(Great	Tees, by Stokesley (Guis- borough, Roseberry Top-
Northern Railway) 2	borough, Roseberry Top-
1 A. London to York, by Luton,	ping) 208
Bedford, Leicester, Lough-	15 A. Whitby to Guisborough
borough, and Trent Junc-	and Middlesbrough 216
tion.—(Midland Railway). 76	
2. Doncaster to York, by Knot-	Thirsk and North Allerton 218
tingley.—Bolton Percy 78	
3. London to Hull, by Don-	Middlesbrough and Redcar 230
caster, Thorne, and Goole.	18. Thirsk to Malton by Cox-
Hatfield Chase 85	
4. Knottingley to Goole, by	Gilling 236
Snaith 102	18 A. Gilling to Pickering, by
5. Milford Junction to Hull,	Helmsley (Rievaula Abbey),
by Selby and Howden 104	Helmsley (Rievaula Abbey), Kirkby Moorside, and Las- tingham—Rail 242
6. Hull, by Hedon and Pa-	tingham—Rail 242
trington to Withernsea.	19. York to Boroughbridge and
(Spurn Head.) The Hol-	19. York to Boroughbridge and Aldborough 252
derness Coast to Hornsea 108	20. York to Knaresborough and
7 Hull to Hornsea and Skipsea 120	Harrogate (Marston Moor) 256
8. York to Beverley and Hull,	21. Harrogate to Pateley Bridge
by Market Weighton	(Brimham Craggs), Nid-
Also to Selby 125	derdale
9. Hull to Bridlington, by Be-	22. Harrogate to Northallerton,
verley and Driffield 147	by Ripon, Fountains Abbey,
10. Beverley to Bridlington-	Hackfall, and Tanfield 274
Road 150 11. Malton to Driffield. (The	23. Northallerton to Leyburn, by
11. Malton to Driffield. (The	Bedale (Middleham, Jer-
Wolds) 152	vaulx Abbey, Hornby
12. York to Scarborough, by	Castle)
Castle Howard and Malton 156	24. Wensleydale. — Leyburn to
13. Scarborough to Filey, Flam-	Hawes Junction and Sed-
borough Head, and Brid-	bergh, by Bolton Castle,
lington 181	Ausgarth, Askrigg, Hawes,
14. York to Whitby, by Malton	(Hardraw Force) 312 24 A. Hawes to Muker 322
and Pickering 190	24 A. Hawes to Muker 322
[Voebshins]	В

Routes and Resting-places.	Paces to be visited.
LEYBURN	All Wensleydale may be explored from here. Middleham. Jervaulx. Country between Leyburn and Richmond. Swaledale.
*MUKER OR *THWAITE	Buttertubs Pass. Upper part of Swaledale.
Rеети	Swaledale. Arkengarthdale.
RICHMOND	Swaledale. Easby Abbey. Catter-
	ick. Hornby Castle. Country between Richmond and Barnard Castle.
BARNARD CASTLE	Rokeby. Eggleston Abbey. The
	Greta. Wycliffe. Bowes. Country
	between Barnard Castle and Mid-
	dleton. Stainmore.
MIDDLETON IN TEESDALE, High Force Inn.	or Upper Valley of Tees. Lunedale. High Force, Caldron Snout. Mickle Fell, and surrounding moors.

BOUTES.

°° The names of places are printed in *italics* only in those routes where the *places* are described.

BOU	TE P	AGE	ROUTE PAGE
1.	London to York, by Don-		15. Whitby to Stockton-upon-
	caster and Selby.—(Great		Tees, by Stokesley (Guis- borough, Roseberry Top-
	Northern Railway)	2	borough, Roseberry Top-
la.	London to York, by Luton,		ping) 208
	Bedford, Leicester, Lough-		15 A. Whitby to Guisborough
	borough, and Trent June-		and Middlesbrough 216
	tion (Midland Railway) .	76	
2.	Doncaster to York, by Knot-		Thirsk and North Allerton 218
	tingley.—Bolton Percy	78	17. Stockton to Saltburn, by
3.	London to Hull, by Don-		Middlesbrough and Redcar 230
	caster, Thorne, and Goole.		18. Thirsk to Malton by Cox-
	—Hatfield Chase	85	wold, Byland Abbey, and
4.	Knottingley to Goole, by		Gilling 236
	Snaith	102	18 A. Gilling to Pickering, by
5.	Milford Junction to Hull,		Helmsley (Rievaulz Abbey), Kirkby Mooreide, and Las-
	by Selby and Howden	104	Kirkby Moorside, and Las-
6.	Hull, by Hedon and Pa-		tingham—Rail 242
	trington to Withernsea.	1	19. York to Boroughbridge and Aldborough 252
	(Spurn Head.) The Hol-		Aldborough 252
	derness Coast to Hornsea	108	20. York to Knaresborough and
7	Hull to Hornsea and Skipsea	120	Harrogate (Marston Moor) 256
8.	York to Beverley and Hull,	- 1	21. Harrogate to Pateley Bridge
	by Market Weighton.—	ļ	(Brimham Craggs), Nid-
	Also to Selby	125	derdale 268
9.	Hull to Bridlington, by Be-		22. Harrogate to Northallerton,
	verley and Driffield	147	by Ripon, Fountains Abbey,
10.	Beverley to Bridlington-	1	Hackfall, and Tanfield 274
	Boad	150	23. Northallerton to Leyburn, by
11.	Malton to Driffield. (The	ı	Bedale (Middleham, Jer-
	Wolds)	152	vaulx Abbey, Hornby
12,	York to Scarborough, by	- 1	Castle)
_	Castle Howard and Malton	156	24. Wensleyaate. — Leyourn to
13.	Scarborough to Filey, Flam-	- 1	Hawes Junction and Sed-
	borough Head, and Brid-	- 1	bergh, by Bolton Castle,
	lington	181	Aysgarth, Askrigg, Hawes,
14.	York to Whitby, by Malton	i	(Hardraw Force) 312 24 A. Hawes to Muker 322
	and Pickering	190	24 A. Hawes to Muker 322
- [Yorkshire.]		В

BOUTE PAGE	BOUTE PAGE
25. York to Richmond, Swaledale,	35. Leeds to Bradford (Low
Reeth, Muker, and Barnard	Moor Ironworks) 430
Castle, by Dalton Junction	36. Leeds to Bradford and Hali-
and Catterick Bridge 323	
26. Darlington to Barnard Castle	Queensbury and Thorn-
(Rokeby), Bowes Castle, and	ton 437
Egglestone Abbey 336	37. Leeds to Manchester, by
27. Barnard Castle to Middleton-	Dewsbury and Hudders-
in-Teesdale, High Force.	field
Micklefell 348	field
28. London to Leeds, (1) by	Priory, Walton Hall) 457
Doncaster and Wakefield;	39. Wakefield to Halifax.—
(2) by Pontefract and	(Lancashire and Yorkshire
Wakefield; (3) by Ponts-	Rly.) 466
fract and Castleford 352	40. Wakefield to Doncaster, by
29. Leeds to Harrogate (Kirk-	Barnsley and Mexborough
stall, Harewood) 372	(Coningsborough) 471
30. Leeds to Skipton: A. By	41. London to Leeds.—(N. Mid-
Otley and Ilkley (Bolton	land Railway) 479
Priory, Wharfedale) 878	42. Leeds to Selby, by Milford
81. Skipton to Kettlewell (Upper	Junction 481
Wharfedale) 897 82. Skipton to Ingleton, by Settle	48. London to Harrogate, by
32. Skipton to Ingleton, by Settle	Tadcaster and Wetherby . 484
(Malham, Gordale, Victo-	44. Huddersfield to Sheffield, by
ria Cave).—(Midland Rly.) 402	
32 A. Skipton to Clapham, Ingle-	45. Sheffield to Doncaster, by
ton, Kirkby Lonedale	Masborough (Rotherham,
The Yorkshire Caves 413	
88. Settle to Chatburn (Gis-	46. Sheffield to Barnsley (Eccles-
burne, Sawley Abbey) 419	field)
34. Leeds to Skipton, by Bingley	47. Rotherham to Bawtry, by
and Keighley (Saltaire,	Tickhill (Roche Abbey) . 516
Haworth) 442	:

ROUTE 1.

LONDON TO YORK, BY DONCASTER AND SELBY.

(Great Northern Railway, King's Cross Stat.)

Distance from London to York, 189 m. 9 trains daily; the express in 4 hrs. 15 min., ordinary trains in 5 hrs. 15 min. (For Rte. by Midland Rly, see Route 1 A.)

(The "great North road" in the days of posting, was chiefly remarkable for the absence of scenery or places of interest along its course. The Great Northern Railway follows nearly the same line. The riy, passes through much rich and fertile country; but it opens no picturesque scenery, and the only places:

of importance between London and the border of Yorkshire are—Peterborough, where the tourist should look out for a fine view of the west front of the cathedral; Grantkom, with its noble church and almost unrivalled spire; and Newark, where the castle reminds us of the death of King John, which occurred within its walls. The Great Northern does not follow the line of a Roman read from London; but at Bawtry it meets an ancient cross-road from Lindum (Lincoln), and proceeds in a line with it to Doncaster and Castleford.)

At 148 m. from London,

Basery Stat., we enter Yorkshire. Bawtry is a village of about 1000 Inhab., containing little or nothing to attract the tourist. The ch. has some Norm, portions; but the tower is modern. There is a hospital, with this neighbourhood, especially about a chapel, founded by the Morton the time of Doncaster races, they family, who were long resident here. Bawkry is on the great North road; and it was here that the Sheriff of Yorkshire anciently met royal personages and conducted them over the border of the county. When Hen. VIII. visited Yorkshire in 1541. after the rising known as the "Pilgrimage of Grace," he was met at Bawtry by "200 gentlemen of the county in velvet, and 4000 tall yeomen and servingmen well horsed, who on their knees made a submission by the mouth of Sir Robert Bowes. and presented the king with 9001."-(Hall.)

There is a Boman camp near the village of Austerfield (1 m. N.E.); and the ch. has Norman portions. At Tickkill (4 m. W.) are a fine Perp. ch. and the remains of a castle. Rte. 47.7

1511 m. Rossington. The small ch here, which has a Norm, chancel arch and S. doos, was probably erected by the Foreste, lords of Doncaster and the surrounding district from the Conquest to the reign of Richard I. In the churchyard is the grave of Charles Bosvile-died 1709. Like Bampfield Moore Carew in the South, Bosvile made himself the chief of the Northern gipsies, and his word among them was law. "He was a gentleman with an estate of about 200% a-year, and is described by De la Pryme, of Hatfield, as 'a med spark, mighty fine and brisk, and keeps company with a great many gentlemen, knights, and esquires, yet runs about the country.' . . No gipsy for many years

passed near Rusington without going to pay respect to the grave of him whom they called their king; and I am informed that even now, if the question were asked of any of the people who still haunt the lanes in the Race-course, and, for those who

the time of Doncaster faces, they would answer that they were Bosvile's people."-(Hunter's S. Yorkakire.)

[In the ch. of Wadworth, 4 m. W., is an effigy (14th cent.), which is probably that of a forester. The dress, as Mr. Bloxam has pointed out, exactly agrees with that of Chancer's "Yeoman Forester:"-

" And he was clad in cote and hode of grene, And by his side a sword and a bokeler : An horne he bare; the bawdricke was of grene : A forester was he sothely as I gesse."

The effigy of Jenkin Wyrral in Newland churchyard, Gloucestershire, should be compared. Few similar memorials exist.

From Rossington the line proceeds through a level district to

1561 m. Donoaster Stat.

Hotels: Pye's, Angel Hotel (very good and comfortable); Reindeer.
Railways: To York (Great Northern), 9 trains daily. To Wakefielt and Leeds (Great Northern), 10 trains daily (Rte. 28). To Sheffield (Midland, 19 m., wid Swinton and Masborough) (Rte. 45), 5 trains daily. To Manchester and Liverpool (S. Yorkshire and Manchester line, wid Barmsley and Penistone) (Rte. 46), 4 trains daily. To Sheffield (S. Yorkshire, wid Wombwell and Chapeltown, 27 m.) (Rte. 46), 4 trains daily. 27 m.) (Rte. 46), 4 trains daily.

Doncaster (Pop. in 1881, 21,130), one of the cleanest and pleasantest towns in Yorkshire, occupies the site of a Roman station on the great road from Lindum (Lincoln) to There was a Eboracum (York). ferry here across the river Don (which rises near Penistone, and flows into the Humber near Goole, see Rte. 44).

The chief points of interest in Doncaster are the Churches (all modern), the Great Northern Railway.

Except during the race-week (in September), when the town is thronged with visitors, and enormous sums are demanded for lodgings, Doncaster is quiet and attractive. The movement of the place is chiefly due to the weekly corn-market, which is one of the most important in the North. There are few agricultural districts in England richer or more productive than that of which Doncaster is the centre.

*St. George's, the parish church of Doncaster, whose bells sounded so pleasantly in the ears of Dr. Dove. was completely burnt down (Feb. 28, 1853); the cause being, as usual, a neglected flue. The old church had nothing remarkable in its architectural character except the central tower, which was finished about 1425, and was inferior to none in the kingdom for accurate proportion and grace of outline. It was the celebrity of this tower that caused the restoration of the ch. to be taken up as a matter of more than local interest. Nearly 30,000l. were subscribed at once, and The work 10.000L more afterwards. was placed in the hands of Sir G. G. Scott, whose reputation with posterity may safely rest on this noble building. The general character of the ch. is Dec. The greatest defect is perhaps the apparent shortness of the nave and transepts for their height; for although the ch. is in both those portions considerably longer than the old one, it looks shorter, in consequence of the roofs being 75 ft. high, whilst those of the former building were flat. This great height of the nave and chancel roof, produces within (as in St. John's Chapel at Cambridge, also the work of Sir G. G. Scott) an effect of real grandeur.

The present church may be shortly described as a large cross ch., with an internal area of 12,600 feet; the length of the whole inside is 169, of

care for machinery, the "plant" of | ft.; the width of the nave and aisles 65, and of the nave proper and of the transepts and chancel 27 ft. There is on each side of the chancel a chapel 25 feet wide, one of which, formerly called the Seaton Chapel, was rebuilt in a more decorated style than the rest of the ch. at the sole cost of Mr. Forman, of Pipbrook House, Dorking, the representative of an old Doncaster family. It is also the baptistery of the ch., containing a large and handsome font of serpentine marble, the gift of Professor Selwyn. The tower is 170 ft. high, and (except that of Boston, Lincolnshire) is the highest central tower of a parish ch. in England (it is exceeded by some cathedral towers). Being 34 ft. square outside, it is proportionately wide.

The E. window is one of the largest in England, being 48 ft. high and 221 wide. It has 8 lights and a wheel above them 15 ft. in diameter. It is filled with painted glass by Hardman (representing the Passion of our Lord, and the events before it, beginning with the Entry into Jerusalem), in memory of the Rev. Dr. Sharpe, who was vicar and curate, and a schoolmaster of great reputation at Doncaster. (His coped tombstone, of very good design, should be remarked, in the church-yd.). decoration of the chancel, including an elaborate reredos, gilt and coloured, altar rails, and gas standards, was in 1869 'the grateful and loving gift of 88 of those graduates of Oxford and Cambridge who here prepared themselves for holy orders under the instruction and guidance of the very Rev. Dean Vaughan, D.D., former vicar of Doncaster.' Almost all the windows in the church (except those of the clerestory) have been filled with stained glass; but as various artists. have been employed, the effect, as is usually the case under such circumstances, is anything but satisfactory. The West window, representing a 'tree of Jesse,' is by Ward and the transepts 92, and of the nave 91 Hughes. The window of the N.

Transcept (the Transfiguration and of the organ, apart from the screen or the curing of the demonisc below) is a wonderfel production by O'Connor,—Raffaelle's picture having suggested some of the details. The window of the S. Transept is by Clayton and Bell. The glass in the Seston chapel is by Wailes; and at the end of each nave sisle is a window by Capronnier of Brussels. whose opeque glass has much the effect of a coloured blind. The pulpit would appear enormous in a ch. of ordinary size, being part of a circular arcade of 8 ft. diameter, consisting of 10 arches with marble shafts, on a round base, ornamented with iron bands, like a piece of a Norman pillar The general design of it 5 ft. thick. and of the pulpit itself was given by Sir. E. B. Denison Beckett, Bt., who suggested various other features in the ch., and especially the sinking of the windows deeper from the outside than had been previously done in any modern ch. The tower contains a fine peal of 8 bells, also designed by him on the scale of the Westminster clock bells (as described in the 4th edition of his 'Rudimentary Treatise on Clocks and Bells'). The medallions and sculpture throughout the ch. are by Phillips of London.

The organ of the old ch. had been celebrated in its time; and the new one promises to be still more famous. It is built by M. Schultze, of Paulinzelle, near Erfurt, and is said to be the largest ch. organ in England, except that of York Minster; containing 96 stops and above 6000 pipes, and covering a space of about 900 square ft. in the N. chapel. It has 12 bellows, not worked by hands, as usual, but by feet, in which way a man can exert nearly double the power with less fatigue. Three men can blow the full organ. But the sweetness of the tone is a far more valuable quality of this organ than its size, and it is so voiced as not to be town, which was founded by the too load for the ch. The whole cost late Mr. Jarratt, a retired iron-

case, was 2500l., for which a separate subscription was raised.

"The whole cost of this noble ch. with all its appendages, is stated to be within 45,000L, for its size and architectural character a singularly cheap building, a fact which is not without importance in these days, when there is a growing disposition to regard mere height and ornamentation as the only sources of architectural effect."-E. B. D.

*St. James's was (through the influence of the late chairman of the Great Northern Railway Company) built by the subscriptions of some of the shareholders for the families of their workmen, who have increased the population of the town by about 4000. This ch. consists of two nearly equal naves 113 ft. long and 52 ft. wide, together with what is only a bell-turret in architectural design, but in most modern chs. would pass for a tower and spire,in height 120 ft.—rising out of the roof of the minor nave. The roof is 53 ft. high, and the walls are 32 ft., and none of them less than 3 ft. thick. This ch. is remarkable for the boldness and massiveness of all its parts, and the deep setting and thick mullions of the windows. The general design of St. James's ch., and many of the details of construction, were supplied by Sir E. B. Denison Beckett, who undertook the management of the building, with G. Gilbert Scott as architect, at the request of the Great Northern Railway Board. The whole cost of this ch., previous to an alteration of the spire made by Sir Ed. Beckett at his own expense, was only 5000l. It is built of Ancaster stone.

The third ch. in Doncaster is Christ Church, at the S. end of the master, in 1829. It was built by a | "plant," of which (for the Gt. local architect, and is not inferior to the average of so-called Gothie chs. of that period. The E. window is filled with stained glass Capronnier.

Doncaster is best known to the world from its Races, which take place annually in September, and last 4 days. They are among the most celebrated in England, attracting a vast assemblage of persons, and contributing not a little to the prosperity of the town. At what time races were first established here is quite uncertain, but they had probably been in existence for some time in 1708, when the first mention of them occurs. They did not become famous, however, until the St. Leger stakes were established in 1778. These were named after their principal founder, Col. St. Leger, who lived near the town; and the race for them is at Doncaster what that for the Derby is at Epsom, or that for the Queen's Plate at Ascot. The first winner of the St. Leger was a horse of the Marquis of Rockingham's, rejoicing in the incomprehensible name of " Allabaculia." The Racecourse is about a mile from the town, on the old London road. There is no view from it, but the scene from the Grand Stand is worth a visit, and during the races it is wonderfully fine and animated. The Stand was built in 1826 at the expense of the Corporation, who contribute 3801. yearly in stakes and plates to be run for, and draw from the stand a rental of 2000l. per ann. The celebrated achievements of Eclipse were performed on this course, which is 2 m. in circuit. The St. Leger Race is run on a Wednesday, and attracts thousands of visitors from all parts of the United Kingdom: 100 trains and engines crowd the Rlv. station.

Northern) this is the principal depôt. There are others (secondary) at Boston and Peterborough. All the carriages used on the Great Northern Rly, are made here, besides the engines. A great central engine of 80-horse power is the chief motive force: and Nasmyth's hammer, circular saws, &c., may be seen in full operation. A small saw used for cutting breaks is especially curious. About 1500 workmen are employed here.

On Hobeross Hill, a little S. of the town, are the remains of an ancient cross (removed here from the town in 1793), with the inscription-

"Icest est la cruice Ote D Tilli A ki alme Deli en face merci.

Otho de Tilli was seneschal of Conisborough in the reigns of Stephen and Henry IL

"The whole town of Doncaster," says Leland, writing in Henry VIII's time, "is built of wood, and the houses be slated; yet there is great plenty of stone thereabout." There are now few old houses—and little even which can be assigned to the time of Dr. Dove of the 'the Doctor.' The Town-hall was built in 1744, by Paine, arch., and improved in 1800.

The Grammar School, near Christ Ch., though founded 1553, had fallen into disuse, until resuscitated by Rev. Dr. Vanghan and the Town Council. The donations of private benefactors have endowed it with numerous exhibitions at the universities, and supplied funds for the erection of the handsome School Buildings.

The Rev. Mr. Cartwright, inventor of the power-loom, finding no one at Manchester willing to give a trial to his discovery, established at his On the left of the station extend own cost (1786) a manufactory and the sheds and factories of the rly. a weaving-mill at Doncaster, the machinery in which was at first | Don (whose successor still occupies

moved by a bull.

The profits of the town mills, near the bridge over the Don, were anciently assigned for the special expenses of the mayor; hence the old

"The Doncaster Mayor, he sits in his chair, His mills they merrily go: His nose doth shine with drinking of wine, And the gout is in his great toe."

History.

Roman antiquities have been found from time to time at Doncaster. It is supposed to occupy the site of the Roman "Danum." The Northumbrian kings had a "villa" here.

The position of Doncaster on the line of the great North road has rendered it more than once a place of historical importance. The Northmen frequently plundered it. Malcolm of Scotland did homage here for Cumberland to Henry II. in 1157. Thomas Earl of Lancaster, the great baron of Pontefract, assembled his adherents here in the winter of 1321-2. before the rising which ended in the hattle of Boroughbridge (see Rte. 19). In 1470 occurred the remarkable rising in Lincolnshire, the object of which was to place Clarence on the throne instead of his brother, Edward IV. Sir Robert Welles and Sir Thomas Delalaunde headed the insurgents, who were defeated at Erpingham, in Rutland. The king (who in spite of his promise had beheaded Lord Welles, father of Sir Robert) then returned to Doncaster, where he caused Sir Robert Welles and Sir Ralph Grey to be beheaded in the Market-place. During the " Pilgrimage of Grace" in 1536, Doncaster was the scene of two remarkable interviews between the insurgent leaders and the heads of the royal army. This army, under Lord Shrewsbury and the Duke of Norfolk, was in Doncaster, and the bridge across the

the same place, on the N. side of the town) had been fortified. Aske and the insurgents had advanced from Pontefract to Scawsby Lees, about 3 m. N. of the river A battle seemed imminent : but, after some discussion. a conference between certain of the leaders on either side took place on the bridge (Oct. 26, 1536), Robert Aske himself remaining on the bank of the Don, "the whole host standing with him in perfect array." It was then agreed that the petition of the insurgents should be carried to the king, and that the musters on either side should be dishanded. A second meeting between Aske and the king's commissioners took place in December. when Norfolk announced the king's pardon to the insurgents; and Aske, "in the presence of all the lords, pulled off his badge, crossed with the five wounds, and in a semblable manner did all the lords there. and all others there present, saying all these words: 'We will wear no badge nor figure but the badge of our sovereign lord." - (Froude, Hist. Eng. iii. ch. 13. For a general sketch of the rising see Introd.)

During the civil war Charles I. was frequently at Doncaster, and the Puritan Earl of Manchester made it his head-quarters after Marston Moor. In Oct. 1648, when Pontefract Castle was the only royal garrison in the North, a small party from it attacked and killed the Parliamentarian General Rainsborough, in the midst of his troops at Doncaster. Sir Marmaduke Langdale was a prisoner at Nottingham, and the object of the royalists was to get possession of Rainsborough, so as to effect an exchange. They were nearly successful; but in the struggle Rainsborough was severely wounded, and fell dead; his assailants got safely back to Pontefract. house opposite to the shambles is still pointed out as the scene of the attempt.

made from Doncaster to Coningsborough Castle (51 m. S.W., where is a station on the Midland Rlv.). The castle itself is of great interest, and the scenery on the Don is very pleasing (see Rte. 40). A drive of about 10 m. from Doncaster, along the great Northern road, will bring the tourist to Barnsdale, the ancient haunt of Robin Hood. Rte. 2.)

[Carr House, 1 m. from Doncaster, on the northern edge of Pottery Carr, was for many generations the residence of the Childers family. Here the famous horse called Bay Childers, or the Flying Childers-in his day, and long after, the fleetest racer known in England -was bred by Leonard Childers, who died in 1748. Pottery Carr is an extensive level, of about 4000 acres, lying S. of the racecourse. It was formerly a complete morass, as the name "Carr" indicates; but toward the end of the last cent. an Act was obtained for draining and allotting it, and it is now valuable ground.]

For several years the main line followed by G. N. R. trains to York was by Knottingley Junction and The rail from Knot-Sherburn. tingley belonged to the York and N. Midland Company, but the Gt. Northern had the right of passing over it. However a shorter line has been opened by the N. Eastern Company, but really for the convenience of the Gt. Northern, which has the privilege of using it, passing to York by Selby. This considerably shortens the distance, and is now used as the direct route from London to York. (For the line by Knottingley, see Rte. 2.)

Leaving Doncaster by the railway, Cusworth House (R. H. Wrightson, Esq.) is seen 1. The river Don (which was made navigable to Fishlake in name marks its position, close to

A very pleasant excursion may be the reign of George II.) is then crossed; and we soon reach-

> (Near Shaftholme the N. Eastern Rlv. turns out of Gt. Northern)

1581 m. Arksey Stat. The Ch. (seen rt. of the stat.) is interesting, and has been restored at a cost of 30001.. under Sir G. G. Scott (reopened July, 1870). It is for the most part late Trans., with traces of an earlier (Norm.) building. The central tower (Trans.) has a low spire above it, which may possibly be of the same date. The parapet and pinnacles of the tower have been added. mouldings of the tower arches and their piers, with double shafts and capitals, are very good, and the view of the group from the W. end excellent. Remark a curious pierced panel of stone on the S. side of the chancel. It now opens through the thickness of the wall to the vestry; but the wall was originally external. On the N. side, low down, is a square hollow in the exterior wall. The pulpit dates 1634, and the font-cover 1662. font was once attached to last pier on the S. side of the nave. There are some remains of good heraldic glass in the windows. The arms in the W. window are apparently those of Henry Duke of Lancaster, died 1361. The ancient lords of Arksey were the Newmarches, the Tibetots, the Scropes, and the In 1654 the manor Windhams. was sold to Bryan Cooke of Doncaster, who left by will money for the erection of a hospital for 12 poor persons, each of whom receives 51. a year. This hospital, with a rather picturesque gateway, stands opposite the ch.

l. of the stat. is Arksey Pool. a deep hollow in the magnesian limestone, well stored with fish.

[The ch. of Adwick-le-Street (the

the great North road, here a branch i ci the ancient Ermyn Street), 21 m. N.W. of Arksey (and on the line of the Great Northern Rly, between Doncaster and Wakefield; see Rte. 23), is E. E. and early Dec., and 25, is as. a. tastored. The tower is open to the nave. A singular half-arch connects the E. E. chancel with the Dec. nave. In the Washington Chapel (N. of the chancel) are some incised slabs (16th cent.) a alter-tombs. The Washingtons were lords of the manor from the middle of the 16th cent. to the eginning of the 18th; but although radition has connected the American family with one of the northern counties, there is no proof whatever of its relation to the Washingtons of Adwick. In the reign of Henry II. the ch. at Adwick was granted to the nuns of Hampole, who possessed it till the Dissolution, when all their interest passed to the Saviles of Methley. On the publication of Spelman's 'De non Temerandis Ecclesiis,' Mrs. Anne Savile, daughter of the then proprietor, was so much struck by it, that she purchased the "rectory" from her father (at a cost of 900l.), and settled it on the cure for ever.

2 m. N.W. of Adwick-le-Street. and on the road from Doncaster to Wakefield, is Hampole, where was a priory for Cistercian nuns, founded by William de Clarefai, about 1170. At this place lived Richard Rolle, the "hermit of Hampole," one of the most popular "divines" of the 14th cent. His books, written in rhyme, for the "unlered and lewed," afford remarkable examples of the Northumbrian dialect. One of the most important, the "Pricke of Conscience," was edited by Mr. Morris, in 1863, for the Philolog. Soc. that is really known about Richard Rolle will be found in the preface to certain of his English Prose Treatises, edited (1866) for the Early Eng. Text Soc. by the Rev. G. Perry. He was born at Thornton, near Thirsk; and instead of having been an Augustinian friar, or a Doctor of Divinity, as is generally asserted, he was not in holy orders, but entirely an irregular teacher, and in a great measure self-instructed. He died in 1949, and was buried in the Priory at Hampole.]

From Arksey the railway traverses a level district of dykes and drains, in which are two small stations at Moss and Balne—(Balne was an ancient name of this whole district, comprising all the low-lying lands between the Aire and the Don)then crossing the Knottingley and Goole Canal it reaches the little station of Heck. Beyond this it encounters the river Aire, winding through the marshes toward junction with the Ouse, N. Goole; and on the 1 bank of the river is the station of Templehurst. Here was a small preceptory of the Templars, the site of which is now occupied by a modern farmhouse. Templehurst was granted by Ed. III. to Sir John Darcy; and here lived his descendant, Lord Darcy, at the time of the Pilgrimage of Grace, 1536 - 37. He sympathised with Aske, and played into his hands. (See Froude, vol. iii.) (For the church of Birkin, probably built by the Templars of Hurst, see Rte. 2. It is best reached from Knottingley The or Burton Salmon station.) line then passes through a somewhat more wooded, but still level, district; and crossing the Selby Canal, it reaches station of Selby. No objects of interest to the tourist are passed between Doncaster and Selby.

1741 m. Selby Junct. Stat. (Inn: Londesborough Arms, near the ch.). Selby (Selebi, the "seal's house," according to the chronicler of the

A very pleasant excursion may be the reign of George II.) is then made from Doncaster to Coningsborough Castle (51 m. S.W., where is a station on the Midland Rlv.). The castle itself is of great interest, and the scenery on the Don is very pleasing (see Rte. 40). A drive of about 10 m. from Doncaster, along the great Northern road, will bring the tourist to Barnsdale, the ancient haunt of Robin Hood. Rte. 2.)

[Carr House, 1 m. from Doncaster, on the northern edge of Pottery Carr, was for many generations the residence of the Childers family. Here the famous horse called Bay Childers, or the Flying Childers-in his day, and long after. the fleetest racer known in England -was bred by Leonard Childers, who died in 1748. Pottery Carr is an extensive level, of about 4000 acres, lying S. of the racecourse. It was formerly a complete morass. as the name "Carr" indicates: but toward the end of the last cent. an Act was obtained for draining and allotting it, and it is now valuable ground.]

For several years the main line followed by G. N. R. trains to York was by Knottingley Junction and Sherburn. The rail from Knottingley belonged to the York and N. Midland Company, but the Gt. Northern had the right of passing over it. However a shorter line has been opened by the N. Eastern Company, but really for the convenience of the Gt. Northern, which has the privilege of using it, passing to York by Selby. This considerably shortens the distance, and is now used as the direct route from London to York. (For the line by Knottingley, see Rte. 2.)

Leaving Doncaster by the railway, Cusworth House (R. H. Wrightson, Esq.) is seen 1. The river Don (which crossed: and we soon reach-

(Near Shaftholme the N. Eastern Rly. turns out of Gt. Northern)

1581 m. Arksey Stat. The Ch. (seen rt. of the stat.) is interesting, and has been restored at a cost of 3000L, under Sir G. G. Scott (reopened July, 1870). It is for the most part late Trans., with traces of an earlier (Norm.) building. The central tower (Trans.) has a low spire above it, which may possibly be of the same date. The parapet and pinnacles of the tower have been added. mouldings of the tower arches and their piers, with double shafts and capitals, are very good, and the view of the group from the W. end excellent. Remark a curious pierced panel of stone on the S. side of the chancel. It now opens through the thickness of the wall to the vestry; but the wall was originally external. On the N. side, low down, is a square hollow in the exterior wall. The pulpit dates 1634, and the font-cover 1662. The font was once attached to last pier on the S. side of the nave. There are some remains of good heraldic glass in the windows. The arms in the W. window are apparently those of Henry Duke of Lancaster, died 1361. The ancient lords of Arksev were the Newmarches, the Tibetots, the Scropes, and the Windhams. In 1654 the manor was sold to Bryan Cooke of Doncaster, who left by will money for the erection of a hospital for 12 poor persons, each of whom receives 51. a year. This hospital, with a rather picturesque gateway, stands opposite the ch.

l. of the stat. is Arksey Pool, a deep hollow in the magnesian limestone, well stored with fish.

The ch. of Advick-le-Street (the was made navigable to Fishlake in name marks its position, close to

the great North road, here a branch ! of the ancient Ermyn Street), 21 m. N.W. of Arksey (and on the line of the Great Northern Rly. between Doncaster and Wakefield; see Rte. 28), is E. E. and early Dec., and 28), is b. E. and has been well restored. The tower A singular half-arch connects the E. E. chancel with the Dec. nave. In the Washington Chapel (N. of the chancel) are some incised slabs (16th cent.) on alter-tombs. The Washingtons were lords of the manor from the middle of the 16th cent, to the beginning of the 18th; but although tradition has connected the American family with one of the northern counties, there is no proof whatever of its relation to the Washingtons of Adwick. In the reign of Henry II. the ch. at Adwick was granted to the nuns of Hampole, who possessed it till the Dissolution. when all their interest passed to the Saviles of Methley. On the publication of Spelman's 'De non Temerandis Ecclesiis,' Mrs. Anne Savile, daughter of the then proprietor, was so much struck by it, that she purchased the "rectory" from her father (at a cost of 900l.). and settled it on the cure for ever.

2 m. N.W. of Adwick-le-Street, and on the road from Doncaster to Wakefield, is Hampole, where was a priory for Cistercian nuns, founded by William de Clarefai, about 1170. At this place lived Richard Rolle, the "hermit of Hampole," one of the most popular "divines" of the 14th cent. His books, written in rhyme, for the "unlered and lewed," afford remarkable examples of the Northumbrian dialect. One of the most important, the "Pricke of Conscience," was edited by Mr. Morris, in 1863, for the Philolog. Soc. All that is really known about Richard Rolle will be found in the preface to certain of his English Prose Treatises, edited (1866) for the Early according to the chronicler of

Eng. Text Soc. by the Rev. G. Perry. He was born at Thornton, near Thirsk: and instead of having been an Augustinian friar, Doctor of Divinity, as is generally asserted, he was not in holy orders, but entirely an irregular teacher, and in a great measure self-instructed. He died in 1349, and was buried in the Priory at Hampole.]

From Arksey the railway traverses a level district of dykes and drains, in which are two small stations at Moss and Balne—(Balne was an ancient name of this whole district. comprising all the low-lying lands between the Aire and the Don)then crossing the Knottingley and Goole Canal it reaches the little station of Heck. Beyond this it encounters the river Aire, winding through the marshes toward its junction with the Ouse, N. Goole; and on the 1 bank of the river is the station of Templehurst. Here was a small preceptory of the Templars, the site of which is now occupied by a modern farmhouse. Templehurst was granted by Ed. III. to Sir John Darcy; and here lived his descendant, Lord Darcy, at the time of the Pilgrimage of Grace, He sympathised with 1536 - 37. Aske, and played into his hands. (See Froude, vol. iii.) (For the church of Birkin, probably built by the Templars of Hurst, see Rtc. 2. It is best reached from Knottingley or Burton Salmon station.) line then passes through a somewhat more wooded, but still level, district; and crossing the Selby Canal, it reaches station of Selby. No objects of interest to the tourist are passed between Doncaster and Selby.

1741 m. Selby Junct. Stat. (Inn: Londesborough Arms, near the ch.). Selby (Selebi, the "seal's house,

of seals which were formerly taken here) is a town of some size (Pop. 6033), on the rt. bank of the Ouse, here a broad and deep river, navigable for steamers and other craft; crossed by two bridges, and connected by a canal with the Aire. The town has flax scutchingmills, rope-works, and a boat and barge building-yard. Many hands are employed in making of twine and shoemaker's thread. Selby, besides being on the direct line between London and York (from which latter place it is distant about & hr. by railway), has lines connecting it with Leeds (Rte. 42) on one hand, with Hull (Rte. 5) on the other, and again with Market Weighton (Rte. 8) on the rly, between York and Beverley. The canal which connects Selby with that between Knottingley and Goole, passes from Haddlesey on the latter canal to Selby, but it is now little used.

The Ouse at Selby is crossed by a railway bridge of cast iron, founded on piers driven through a quicksand into a bed of clay. weighs 590 tons, and has an opening arch in the centre, allowing masted vessels to pass. The river is navigable for steamers hence to York. The town bridge, a little above the railway-bridge, was built early in the present century. is of wood, for the proper selection of which the engineer and one of the principal promoters of visited 13 counties bridge The ancient in England. -crossed about 50 yds. higher up the

Ouse.~ Selby is not mentioned, except incidentally, in the Domesday Survey: but the foundation charter granted by the Conqueror apparently refers to it as a royal manor. According to an ancient traddition, Matilda was delivered here of ther youngest son, Henry the Beauclero, the only one of

Abbey (see post), from the numbers | his acquisition of the English crown. toward September 1068, shortly after the first submission of York (see post) Freeman, Norm. Cong. iv. 231. suggests the bare possibility that "William may have brought his wife into Northumberland, as Edward brought his wife into Wales, in order that the expected Atheling might be not only an Englishman but a native of that part of England which had cost his father most pains to win." As in many similar cases, a room was long pointed out at Selby as that in which Henry was born, but an inscription on a beam indicated that this chamber had been built by Abbot Deeping, early in the 16th century. (This room has disap-There is, moreover, no menpeared.) tion of the birth in the remarkable 'History' of the monastery (printed in Labbe, 'Nova Bibliotheca Manuscriptorum,' vol. i.). This was written by a monk of Selby, circ. 1184. The foundation of the Benedictine monastery, about which the town of Selby grew up, and the church of which is still its great glory, is there told as follows:-

A certain monk of Auxerre, named Benedict, warned in vision by St. Germanus, fled from his convent by night, carrying with him the finger of the saint. At Salisbury he was received by an Englishman, who provided him with a golden reliquary (afterwards shown at Selby) for his treasure. He then took ship at "Luma" (Lyme Regis?) and sailed thence, entering the Humber and passing up the Ouse till he recognised the spot St. Germanus had shown him in the vision. This was Selby, where he landed, set up a cross on the river bank, and then constructed a small abode for himself, under an oak of vast size, "que a patriotis strihac vocabatur" (perhaps a misreading for shirhac = shire oak). This was in 1068 (?), when, says the chronicler. not a single monk was to be found the Conqueror's children born after throughout all Yorkshire, owing to and of the Conqueror. Hugh, the Sheriff (Vicecomes) Norman Yorkshire, passing in a boat on the Ouse, saw the cross, and sought Benedict, whom he found in prayer before the relic. He looked graciously on the monk, and left his tent as a temporary shelter for the -glorious digitus," sending afterwards carpenters to build a chapel. Hugh's suggestion. Benedict then went to the Conqueror, and obtained a grant of that portion of the royal manor on which he had Wooden cells were built, and many brethren assembled. Benedict was abbot for 27 years. All the buildings up to this time had been of wood. The second abbot, Hugh, who ruled 26 years (1097-1123) began a church and monastic buildings of stone, somewhat farther from the "The monastery," says its chronicler, "stands fairly there; is everywhere visible from the roads; and the river brings the commerce of all parts past it." . The 'History' ends in 1184, and no building is mentioned in it after this of Hugh's. Many English kings, however, and a long string of benefactors, enriched the new convent greatly; and Pope Alexander II. (1076) erected Selby into a mitred abbey. (The only other mitred abbey N. of the Trent was St. Mary's York.) The annual value, at the Dissolution, was 7291. making Selby the monastic house of the third importance in Yorkshire, the two which exceeded it in revenue being Fountains and St Mary's of The site, with much of the property of the convent, was then granted to Sir Ralph Sadier, and has since persod through many hands. It is now the property of Lord Londesborough.

The Abbey Church, made the parockial church of Selby by James I. in church remaining in Yorkshire, and smaller arches with a central pier-

the devastations of the Northmen | one of which any county might well be proud. The plan comprises nave, choir, and Lady-chapel, a central tower between nave and choir, and a north transept with eastern aisle. (The S. transent was destroyed by the fall of the central tower in 1690.) The length of the entire church is 296 ft.: the width (which is the same in both nave and choir) is 50 ft. The aisles have square terminations eastward. parallel with the eastern termination of the Lady-chapel. The nave is late Norm. and E. E. The choir and Lady-chapel are Dec. The Norman portions, no doubt, belong to the ch. began by Abbot Hugh, as we have seen, between 1097 and 1123. They are thus of the same date as Durham (1093-1128) and Norwich (1091-1119).

The W. front is divided into 3 parts by narrow E. E. buttresses. The lower part of each division is Norm.; the upper late E. E. (circ. The side divisions are, in fact, flanking towers, which rise above the level of the aisle roof, but were, perhaps, never completed The Norm. portal recedes in orders, with enriched arches. composition of the E. E. windows above is unusual (rather foreign than English), and deserves special notice. The central window has filled with been Perp. tracery. Within, the nave opens very finelylofty, massive, and solemn. part of the church has been restored, 1872-78, under the care of Sir Gilbert Scott.) The first four bays (from the central tower) are Norm.; the four western, Transition, passing into decided E. E. in the upper portions. The Norm. nave alternated with massive piers in long parallelograms, and circular colums; one of which is covered with a latticework pattern, recembling Durham. The arches are much enriched with zigzag. The Norman triforium—a 1618, is the most perfect monastic broad circular arch, including 2

remains in the two last bays eastward, N. and S. (see post). The rest of the triforium and all the clerestory is E. E. In the western portion of the nave the main arches are circular, marking their transitional character. The triforium and clerestory here deserve special attention. On the N. side the low, massive pier dividing one bay of the triforium (which extends back over the aisles, forming in fact, an upper story, as was usual in Norm, work of this period) is set round with two rows of shafts, one within the other, giving an effect of great enrichment. clerestory on the S. side is of 8 arches in each bay, that in the centre pierced for light. Clustered shafts, with dogtooth in the angles, divide them. the spandrils above, the wall is pierced The corbels from with a trefoil. which the so-called vaulting-shafts spring should be especially noticed. The triforium and clerestory on the S. side differ from those N., and are more purely E. E. On the N. side the clerestory has 2 arches, both pierced for light. Remark also the slender vaulting-shafts which in front of each central triforium pier, and are attached to it by a projecting ring of stone. The arrangement of the west end should be noticed from within. A narrowpointed arch, pierced in two places with a quatrefoil, rises on either side of the window, along the sill of which there is a wall-passage.

A settlement of the great tower piers seems to have taken place at an early period, and the adjoining bay of the nave was crushed in consequence. The main arch, the triforium, and the clerestory in this bay, on either side, are much bent and twisted. The triforium was at first open with a central shaft, as in the bay westward of it; but after the displacement, in order to strengthen the work, the central shaft was removed, cut in two, and the pieces used as attached side shafts for a wall, and 2 late Dec. windows in the

single arch, which was then filled That this was done has been proved during the restoration in 1873. The clerestory was also walled up.

The ceiling of the nave, flat and of wood, is ancient (temp. Hen. VII.), with very good carved bosses. The roof, which was much lower than that of the choir, remains over this ceiling, and above again has been constructed an entirely new roof, of the ancient pitch (as shown by the mouldings on the tower)—a very great improvement to the exterior of the church.

The flooring of the nave has been lowered to its original level, and the bases of the great piers are now well disclosed—very massive, squared, and

of unusual height.

The wall of the south nave aisle had been thrown much out of the perpendicular, either by the fall of the transept in 1690, or the removal of the cloister which adjoined it. The vaulting of the aisle had consequently been almost destroyed. The wall has been rebuilt, and it was found that it had been raised entirely on balks of timber—great squared trunks of oak trees. The vaulting has been carefully restored, and the old stones have been worked in wherever it was possible. The windows are restored after the old type. and are of late Dec. character. Three of them have been filled with stained glass by Hardman.

The glass in the great west win-

dow is by Heaton and Butler.

In the N. aisle the original vaulting remains; and here is a plain circular Norm. font, of dark marble, with a lofty oak canopy. The windows are Dec. Two contain stained glass by Wailes, and Clayton and Bell. In this aisle are the effigies of an unknown knight (cross-legged) and lady, temp. Henry III.

The 4 lofty tower-arches are late Norman. The N. transept is Norm., with a Norm. window in the W.

clerestory. (The apridal eastern termination of this transept has been traced.) The large N. window is Perp., and three curious figures have been placed on the sill.—Moses (with borns), an Angel, and the Virgin. These were removed from the clerestory of the choir.) The eastern aisle is of two bays, and is apparently Dec., of the same period as the adjoining portion of the choir. On the wall of the transcot is a curious inscription, recording the gift, by Robert Anby, "pannicularius, atq. de repub. hujus oppidi optime meritus," of the peal of bells in 1614.

It would appear (although there is no record of it) that the original Norman nave was partly destroyed, from some unknown cause (probably a fire), towards the end of the 12th century; that the rebuilding was commenced on the N. side, toward the W.; that the S. side was finished somewhat later; and that the W. front (which is not exactly square with the nave) was completed last of all, some remaining portions of the Norman front being worked into it.

The Choir (of 6 bays beyond the tower) was apparently built under the rule of Abbot John of Heslyngton (1335-1341) and of his successor, Gilfred of Gatesby (1841-1367). The work is throughout Decorated with a mixture of flowing and geometrical tracery, such as is found also in the church of St. Mary, Beverley. Nothing can have exceeded the beauty of the sculpture throughout the choir when perfect; but it has suffered greatly from neglect and wilful injury. The pier shafts and brackets, the arcade under the aisle windows, and the foliage of the altar-screen are all more or less rained. The clustered piers have capitals of leafage; and at the intersection of the arches are brackets of very good work, some of them curiously grotesque, with very rich canopies above them. From the canopies spring vaulting-shafts, terminating in capitals of leafage. be noticed. In the E. window is

The clerestory has a single window in each bay, filled with flowing Dec. tracery. The high sill of the window serves for the triforium passage; the parapet in front of which, and the canopies above the wall openings. should be noticed. The vaulting is of wood, Dec. (except that of the first bay, which was destroyed when the transept fell), and of the same date as the choir; but that a stone vault was at first intended is evident from the projecting side ribs. Some of the original stall-work also remains. The aisle windows are pure geometrical, with a stone bench and arcade beneath them.

A very rich stone altar-screen (Dec.) divides the choir from the The frieze and en-Lady-chapel. richment on the E. front deserve special notice. On the S. side are four sedilia of unusual design and equal height. The rest of the screen has been lined (about 1790) with dark wood.

The E. window of the Lady-chapel is flambovant. Under it is a tomb with a shattered effigy (temp. Edw. II. (?), and on the sill is placed a piece of sculpture, representing Samson with the lion (from the clerestory like that in the transept). fragments of old glass remain in the windows; and there are 3 windows of modern glass by Wailes. slabs (incised), of Abbot Sherburns (1368-1407); of Abbot Pygot (1407-1429); of Abbot Cave (1429-1436); of Abbot Langrence Selby (1486-1504), with effigy; and of Abbot John Barwick (1522-1526), remain in the choir, but are partially hidden under seats.

From the S. choir aisle an early Dec. chapel (circ. 1250)—it has been also called the chapter-house—of 2 It is stone-vaulted; bays opens. and in the S. wall is a remarkable lavatory, with projecting trough and B triangular recesses above it. The double portal of this chapel should some good old heraldic glass, re- | the width 29 ft. The eastern pormoved from other parts of the ch. The ch. was especially righ in stained glass at the beginning of the last century, according to Burton; but little now remains.

The effect of the whole choir is singularly fine and impressive. It is greatly to be wished that modern abominations—the screens or walls separating the choir and its aisles from the nave, the pews, and all coated whitewash --- should be removed. But the "restoration" of the much-shattered sculpture would be doubtful benefit.

On the exterior, remark the traces of the cloister on the S. side. The upper part of the central tower fell in 1690, as has already been said. The chapel or chapter-house on the S. side of the choir has a room over it, now used as the grammar-school. The composition (which may be compared with the "Flemish chapel" at S. Mary's Beverley) should be especially noticed. Here and at the E, end are pierced pinnacles, recembling those at Howden (see Route 5). The parapets on the exterior of the choir, with small stone figures rising above them, and the graceful pinnacled buttresses dividing each bay, should be remarked. On the N. side of the nave is a fine Norman portal, with a porch of Transition This has been restored. character. together with the whole exterior of the nave.

There are few remains of the monastic buildings. A "painted chamber" in the vicar's house was long pointed out as that in which Hen. I. was born; but an inscription on a beam proved (the chamber no longer exists) that it was built by Abbot Deeping at the beginning of the 16th cent. The great barn or "spicarium" remains, with beams and pillars of massive oak, and is probably Dec. The walls are 3 ft.

tion is still used as a barn, the western as a brewhouse. The principal gateway, with the porter's lodge and vaulted chambers above it. were standing in Burton's time (1758), but have since been pulled down. arms of the Abbey, and now of the town, were sa. 3 swans as.

The Cross in the market-place, a short distance W. of the Abbey church, is modern, and was raised by the Petres, 1790. It is of unusually good design for that date.

Among modern churches in Selby of some importance are St. James's, built and endowed by J. Audus, Esq., 1866; and a Romanist church, built 1856 (Hanson of Bath, archit.) by the widow of the Hon. E. R. Petre, after whose death the Selby estates were bought by Lord Londesborough. Church Hill, on the rt. bank of the Ouse, close above the town bridge, is the site of the first monastic settlement; and a chapel ded. to S. German long remained here. An ancient cemetery was discovered here in 1857. in which the coffins had been trunks of oak, hollowed.

Selby was the scene of some skirmishing and of important military operations during the Yorkshire campaigns of 1643 and 1644. It was held for the Parliament by Lord Fairfax (father of the famous Sir Thomas) early in 1643, but was placed in a critical position after the landing of the Queen at Burlington and the subsequent Royalist proceedings. The Fairfaxes left it accordingly, and made a successful flank march to Leeds, in presence of the hostile army. In July 1643, after he taking of Bradford by the Earl of Newcastle, Lord Fairfax made a rapid march from Leeds to Selby, his son, Sir Thomas, following in thick; the length, before the middle his rear, and there was a cavalry part was pulled down, was 318 ft. skirmish in the town of Selby be-

tween 8 troops of Royalist horse, who! ralloped from Cawood, and were encountered by Sir Thomas Fairfax and his soldiers, drawn up before the Abbey gateway. The Royalists were routed, and the Fairfaxes duly reached Hull, which at this time was the single stronghold of the Parliament in Yorkshire. Sir Thoma: Fairfax was afterwards employed in the ismous siege of Lathom; but in April 1644, Lord Bellasis, the governor of York, occupied Selby; Lord Fairax marched out of Hull and met Sir Thomas at Ferrybridge, and the two then advanced against Selby. The town was attacked at three points, and the Fairfaxes took it with a complete victory. Lord Belasis, with many other officers of mak, and 1600 men were made prisoners; and guns, arms, horses, and baggage were captured. "The victory at Selby was the immediate cause of the battle of Marston Moor, and the destruction of the Royalist power m the North. It at once raised Sir Thomas Fairfax to the first rank amongst the generals of the Parliament . . . and 'the two Houses marked their sense of the importance of his services by ordering a public thanksgiving for the victory, on April 23."—Markhom's 'Fairfax,' p. 138.

The rich level round Selby produces much corn, flax, wood, and tessel. It is a perfect 'plat pays' with the exception of 2 isolated hills, 140 ft. high (rounded, and of diluvial drift), about 2 or 8 m. S.W., talled Brayton Barf and Hambleton Hough. The latter is covered with trees. Bishop Wood, 3 m. W. of Selby, is said to be the largest in Yorkshire, covering about 1000 acres. Bragion Church, 11 m. S., is worth a visit. It belonged to Selby Abbey, and is partly Norman (lower part of tower, chancel arch, and S. portal). The chancel is Dec. with Perp. insertions, and the W. tower is capped by | " A venerable chestnut, fish-ponds,

a Perp. octagonal lantern and spire. The Norman work, especially the portal, is very rich, with beak-head mouldings and medallions. In the ch. is the mont. of George, Lord Darcy (d. 1558) and his wife-son of the Lord Darcy concerned in the Pilgrimage of Grace.

Leaving Selby, the rly. proceeds through the level plain, and crossing the Ouse, reaches the station at

180 m. Riccall; a small village with a ch. (restored 1865) which contains some Norman portions. At Riccall the fleet of Harald Hardrada was moored before (1066) the main body of his troops, landing here, advanced on York. The bed and the whole aspect of the river have no doubt been greatly changed: but the position was central, and the Norwegian fleet moored there, at once barred the ascent of the Ouse, and the descent of the Wharfe (which falls into the Ouse a little above Riccall) where the English fleet had retired. (Freeman, iii. 348.)

131 m. W. of Riccall is Cawood, a small market-town on the Ouse, here crossed by a ferry, in the midst of a fertile district, noted for the growth of flax and teasels. Here, long before the Conquest, the Abps. of York possessed a palace, which was castellated in the reign of Hen. IV. Wolsey made it his summer resi-He was arrested here for high-treason, just before his death, by the Earl of Northumberland. The palace was demolished during the great Rebellion; and all that remains is a large chapel built of brick, and the gatehouse, the work of Abp. and Chancellor Kempe (1426–1452), through which the proud Lord Cardinal passed in the hour In the room of his humiliation. over the gateway the Abp.'s courtsleet for the manor are still held.

extensive marks of old foundations, I assist in carrying back the mind to one of the most remarkable periods of English history." Several adjacent houses have been built out of the ruins. Abp. Matthew died here March 29, 1628; and his successor, Abp. Monteigne, who had been Br. successively of Lincoln, London, and Durham, also died at Cawood, on the 6th Nov. in the same year. There is a monument for Abp. Monteigne in the ch. of Cawood, which is Perp. and of some interest. He was a native of the place, and founded a charity here which still exists.1

Skirting the park of Escrick the rly, proceeds to the Stat, at the village of the same name.

Escrick seems to be equivalent to the southern "Ashridge," and is a good example of the harder "Northern English." It is so named from a low ridge of land which stretches between the rivers Ouse and Derwent, the village of Wheldrake "Quell (Spring) ridge") marking its termination above the latter. The ch. of Escrick, which formerly stood in the garden of Escrick Park (Lord Wenlock), was removed to its present site in 1769, and was again taken down and rebuilt in 1854 at the cost principally of the late Rector the Hon. and Rev. Stephen Lawley. The existing church (F. C. Penrose, arch.) is late Dec. in general character, and is very picturesque. It consists of nave, N. aisle, eastern polygonal apse, with a tower 100 ft. high on the N.E. side, making a fine group from the road; and at the W. end a second apse or multangular chanel, which serves at once as baptistery and memorial chapel (it is over the family vault). On the S. side of the nave is a porch, with parvise chamber used as a vestry, and a turret with spiral staircase projecting into the

The nave pillars are of Plymouth marble - those of the baptistery of marble from Ipplepen, also in Devonshire. The ch. (ded. to St. Helen) is built of stone lined with brick. rose-window above the baptistery arch is filled with Hardman's glass, as are the E. windows. The font in the baptistery is by Tognoli, master of drawing to Canova. There are also here a fine bas-relief by Thorwaldsen to the memory of Lady Lawley, grandmother of the 2nd Lord Wenlock, and one by Wyatt for Richard Thompson, Esq.

Escrick Park closely adjoins the village. It is large and welf-wooded. but, like all this part of Yorkshire, is nearly level. The house stands on the low rise of the "Ash ridge." The hall, originally Elizabethan, was enlarged by Beilby Thompson, Esq., great-uncle of the present owner. On the S. side is a large and well-laid-out Italian garden. The house contains a few good pictures. In the drawingroom are - a landscape, with the Prodigal Son, S. Rosa; Job and his wife, Guercino; the Flight into Egypt, Baroccio; and Hagar and Ishmael. Carlo Dolos. In Lady Wenlock's sitting-room are—a Virgin and Child, by Andrea del Sarto; and St. Domenic and St. Francis, a small but most striking picture, by Fra Bartolomeo. On the staircase are-Sir Thos. and Lady Lawley, 1632, Vandyck (?); and two portraits of Lady Anne Luttrel, afterwards Duchess of Cumberland. (It was the marriage of the Duke with this lady which partly caused the passing of the Royal Marriage Act in 1772.) The best portrait is by Gainsborough, and is one of his masterpieces. second, also a fine picture, is by Romney; but is perhaps unfinished. In the hall is a marble group by Wyatt (1827), 'Boys returning from the Chase.' The "boys" are portraits of 2nd Lord Wenlock and his interior and making a good feature. brother, Here are also a nymph,

· Dirce.' Canova's last work, finished i by a pupil; and two superb cinerary urns of Oriental alabaster, from the Theatre of Augustus at Rome. One is said to have contained the ashes of Marcellus; the other was prepared for those of Augustus. The Library is rich in foreign topography, especially Italian. Here are also a fine collection of Homers, including the 'Editio Princeps; 'Napoleon's 'Bodoni; 'Porson's copy of the large-paper 'Grenville Homer: 'a collection of ornithological books; and part of the theological library of Sir William Dawes, Abp. of York (died 1724). Over the chimneypieces are two very rich old Venetian mirror-frames, carved in Turkish boxwood, by Brustolo, the master of Grinling Gibbons.

[A drive of 3] m. from Escrick, through a level but pleasantly-wooded country brings us to Skipwith. (With seems here to be the Danish word. signifying a forest.) Its ancient Church. ded. to St. Helen, happily remains unrestored, and the evidences of its ancient history have not as yet been swept away. The tower, at the W. end, is of three stages. The two lower, if not Saxon, are very early Norman; the uppermost is Perp. The two westernmost bays of the nave are Trans.-Norm., with octagonal piers, ziozag round the outer arch mouldings, and bunches of foliage, E. E. in character, at the intersections. eastern bay is E. E. The squareheaded clerestory windows are perhaps early Perp., of the same period as the chancel, which was entirely rebuilt in the 14th cent. On either side are two high square-headed windows, of three lights each, with Perp. tracery in the headings. The E. window, which resembles them, is of 5 lights, with brackets for figures on There are some remains either side. of good stained glass, with excellent borders, in the upper lights; and within the present cent. the windows [Yorkshire.]

was carried off by one of the rectors. The saltire of the Nevilles remains in one of these windows. There is no chancel arch. Chancel and nave have a plain open roof. The arch from the nave into the tower is very remarkable. The ornament is the same on either side, but is most perfect within the tower. The arch is round-headed, with a plain soffit; and at some little distance from the main arch is first a round and then a square moulding, slightly projecting from the wall. A round stringcourse cuts both these mouldings, and passes round at the spring of the main arch. The second story of the tower has had a square fireplace, which may be a later addition. The window openings, rude and narrow, are splayed outside and in. The S. porch has the zigzag moulding round a square-headed doorway. The ironwork on this door-interlacing, with bosses-may be Norm., and should be noticed.

Skipwith Common, which stretches away beyond the ch., is one of the largest tract of unenclosed (reclaimable) land in England. Among the heath which covers it, the lovely Gentiana pneumonanthe grows in profusion, flowering in autumn, when its bright blue is conspicuous among the heather. "On Skipwith Common are many tumuli, old banks, and the slightly-marked foundations of ancient (turf or log?) houses or wigwams. These, by some error of tradition, are called 'Danes' Hills; ' but on opening the tumuli, no confirms. tion of so modern a date appeared. The tumuli are set in square fosse: the sides of the fosse range N. and S. and E. and W. (true). Similar facts (?) appear in connection with tumuli on Thorganby Common adjacent. Burnt ashes and bones occur in the mounds -facts which suffice to overthrow the supposition of these hills being funeral heaps of the Danes of the 11th cent., for then they buried their were entirely filled with glass, which dead. No instruments of metal, bone,

stone, or	pottery	were	found."
Phillips's			
Hills," are			
with the b			
A piece of			
the "King			nd a way
near it is "	Olave's re	med."	

There is a station at

Nabura, a small village on the east bank of the Ouse; and then, again crossing the river, the towers of the great Minster come into view, and through a breach in the old city walls, barbarously made to admit the rly... we enter

189 m. York Station, perhaps the finest and most commodious of the provincial stations in England.

There is an especially good refresh-

ment room at the stat.

GENERAL INDEX-YORK. Page 67 Backhous's Gardens Ball Hill 62 Bridges-Lendal 63 Castle and Clifford's Tower 64 53 All Saints, Pavement 52 Holy Trinity, Colliergate 51 Goodramgate 51 86 Micklegate 8. Cuthbert's . 51 8. Crux 52 8. Denis, Walmgate . . . 8. Helen's-on-Walls (site) 51 51 8, Helen's, Stonegatel. 62 S. John's, Micklegate 53 S. Lawrence 52 S. Margaret's, Walmgate 52 S. Martin's, Coney St. 53 S. Martin's - cum - Gregory, Micklegate . . . 8. Mary, Castlegate 85 53 S. Mary the Elder, Bishop Hill \$4 Younger, 55 S. Michael le Belfry 51 B. Michael's, Spurrier Gate 53 8. Olave's . 57 8. Sampson's 52 8. Seviour's 61 Excursions 72 Gulldhall History of York

1 .									P	age
Hotels .										Ĭ.
Minster .										11
Multangule	r To	Wee	•							55
Old Houses			_	-		-	-	Ī	Ī	67
Railways		•	•	-	•	•	•	•	•	18
S. Anthony	, u	<u></u>	Ŀ١	•	•	•	•	•	•	67
S. Leonard	- A	ooht		•	•	•	•	•	•	
		99		•	•	•	•	٠	•	56
S. Mary's	rope	7.	•	٠	٠	•	•	•	•	55
8. William	S CO	begr	•	•		•	٠	٠	٠	67
The King's	Mai	30E	•	•		•				57
York Race										68
Yorkshire l	Philo	gon)	hia	18	locte	etv				55
(ard	ne.	•						-	55
	Hosp			en	a i	N .	•	m.	οŧ	
		tiqu						_	~	58
l,	W			-	•	•	٠	•	•	60
Walls and	O-A-	ш	•	•	•	•	•	•	•	
Wanta and	Jake.	•	•	•	•	•	٠	•	•	61

Hotels: *Royal Station Hotel, entered from the station, best; very comfortable and reasonable. North-Kastern Railway Hotel, opposite the stat. Scawin's Family Hotel, also near the station. York Hotel, central. Black Swan, Coney-street; central and tolerably good.

The Ratheay Station and Hotel, in connection with the lines belonging to the North Eastern Rly. Company; and the Great Northern trains, running from Donesser to York, passing into it. The stat. is outside the city wall, on the rt. bank of the Ouse, and nearly opposite the grounds of St. Mary's

Abbey.

RAILWAYS: To the north, Newark, Berwick, and Edinburgh, via Darlington (9 trains daily, Re. 16); to Knaresborough and Harrogate, in 1 hr. (Bte. 20).

To Harrowgate, via Church Fenton and

Tadcaster, in about 14 hr. (Rte. 43).


To Hull, by Market Weighton and Beverley (Rie. 6); to Scarborough (2 hrs., Rie. 12) and Whithy (2 hrs., Rie. 14, 8 trains dealer)


Whithy (8 hrs., Rte. 14; 8 trains daily).


The Station is within 10 minutes walk of the Minster; in proceeding to which, over the Lendal Bridge, you pass I, the entrance to the grounds and museum of the Yorkshire Philosophical Society. In the grounds are the ruins of St. Mary's Abbey. These are the principal points of interest in York. And about 300 yards from the stat. (in an opposite direction) is Micklegate Bar, the most perfect and most historic of the city gates. The distances from the new stat. will be somewhat less to the Minster, and more to Micklegate.

Yerk (Pop. of municipal borough in 1881, 54,198), the capital of a county which surpasses in extent and wealth many principalities and kingdoms in Europe, is placed at the junction of the three Ridings (see Introd.). It was the British Case









Eurouc, a name of uncertain etymo-| seum of the Yorkshire Philosophical logy, but probably referring to the situation of the town on the river Ouse. (The Ouse is formed by the function of the Swale and the Ure. which latter name may enter into the composition of Evr-auc.) Evraue, Romanised, became Horacum (Mr. Wellbeloved and most English scholars make it Eboracum: some continental writers Eboracum—there is no direct authority for either); and afterwards, under the Saxons, Efermie, The Danish settlers made it Jorvik; from which last form, according to Worsaac, the present York is immediately descended. The form in Domesday is Exercic.

From the 17th century until very recently York, although it was the winter residence of the neighbouring gentry, remained stationary and life-less, without commerce, and with little trade. Railways, however, have done much to change this, although the ancient prophecy-

" Lincoln was, London is, but York shall be The greatest city of the three "-

will hardly be realised until, as Fuller suggests, the "river of Thames run under the great arch of Ouse bridge." This bridge gave place (1810-1820) to the present 8-arched The Lendal bridge is a structure. light and ornamental iron arch. leading direct from the railway stations to the Minster. The Foss is crossed by 3 small bridges, and there is a toll bridge over the Ouse from Skeldergate to the Castle. It is of 3 arches, the central 90 ft. span. The city still retains an antique and venerable aspect; and its network of narrow streets, without apparent plan or regularity, covers the same wide area as in the days of York's greatest prosperity.

The great points of interest in *St. Mary's Abbey, with the Mu-small wooden church, hastily built

Society: the * City walls and gates; and some of the parish churches. The visitor will, of course, first find his way either across the new bridge. or through Conev-street and the still narrower pass of Stonegate, to the MINSTER.

YORK MINSTER—CONTENTS.


						P	age
History and (Jeneral C	harac	er				19
S. Transept.	Exterior						23
, .	Interior				-		24
1	Stained	or lease	_				25
	Monum	ente		•	•	•	25
Narrow arch	a in Tra	nsenta	•	•	•	•	26
N. Transept.	Interior	- C	•	•	•	•	27
		olean	•	•	:	•	27
"	Monum	en te		•	:	•	28
Nava		0116	•	•	•	•	28
Nave Stained glass	in Nava	• •	•	•	•	:	
Chapter-hous Glass in Chap Choir and Pro- Shrine of St.	TO 11810		•	•	•	٠,	32
Class to Char	was born	• •	•	•	•	•	32
Choir and Da	NOTATORE	•	•	•	•	•	34
Chaire of St	TIVIII I	• •	•	•	•	•	35
Chain Airlan	AA TITREETIT	• •	•	•	• .	•	37
Choir Aiales . East Window Monuments i		• •	•	•	•	•	38
Pare Window	* * *.	:		•	•	•	39
wonamenes :	л. П. Сво	IT AIS.	le	•	•	٠	40
, ,,	Presby	tery	•	•	•	•	40
Stained glass	S. Choir	r Alsk	١.	٠	٠	•	42
stained glass	. East V	Vindo	W.	•			43
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	N. Cho	oir Ais	ije.	•	•		43
	B. Cho	ir Ais	le	•			44
Crypt			•	•			44
Central Towe	т			•			45
Choir Screen.							46
Organ .							46
Record Room	, Vestry,	and T	`rea	sur	y		46
Exterior of	Hinster.	S. sid	e of	'N	ĀVE		47
West Fre	ont						47
N. side o	f Nave			-	-	-	48
N. Trans	ept .	. :	-		-		48
West From N. side of N. Trans Chapter-East End Chapter Libra	bouse .	: :	-	-	•	•	49
East End	of Choir		-	•	•	•	49
Chapter Libra	LTV.	•	•	•	•	:	50
			•	•	•	•	30

I. Although the Roman Eboracum can hardly have been without a Christian church, all recollection of such a building seems to have passed away when St. Paulinus visited Northumbria at the beginning of the 7th cent. The king, Edwin, who then embraced Christianity, was bap-York are the * Minster; the ruins of tized (Easter-day, A.D. 627) in a

whilst he was receiving instruction it as well as he could, and afterwards as a catechumen, and dedicated to St. Peter. This was the first church built on the site of the existing Minster. After his baptism, in the words of Bede, the king "set about to construct in the same place, at the suggestion of Paulinus, a larger and more noble basilica of stone, in the midst of which the oratory which he had first built was to be included. Accordingly, having laid his foundations, he began to build his basilica in a square form around the original oratory; but, before the walls were completed, the king was slain, and it was left to his successor Oswald to complete the work." The head of Edwin, after his death in the battle of Heathfield (A.D. 633), was brought to York and deposited in this basilica, in the "porticus of St. Gregory the Pope, from whose disciples he had received the word of life." Archbishop Wilfrid, in 669, found this building in great decay. He repaired its roofs and its walls, "rendering them whiter than snow by means of white lime." and filled the windows with glass. the year 741 the "monasterium" or "minster" in York was burnt, according to Roger Hoveden; and Archbishop Albert, who came to the see in 767, is recorded by Alcuin as having been the builder of a most magnificent basilica in his metropolitan city. We may fairly conclude that Albert rebuilt the ch. founded by Edwin and restored by This ch. remained until the year 1069, when it was destroyed, in its turn, by fire in the course of the Conqueror's devastation of Yorkshire. The central wall of the crypt, below the choir of the existing Minster, is the only relic which can possibly be assigned to the Saxon cathedral of York.

Thomas of Bayeux, the first Norman abp., was consecrated to the see in 1170. He found his cathedral in ruins, and is said first to have repaired | ch. of Paulinus, the vast minster was

(before the end of his episcopate in 1100) to have built a new ch. from the foundations. This ch. remained entire until Abp. Roger (1154-1181) pulled down the choir with its crypts and reconstructed them on a considerably larger scale. Abp. Gray (1215-1255) pulled down the S. transept of Thomas of Bayeux's ch., and built that which now exists. John Romanus. sub-dean and treasurer of York (1228-1256) and Archdeacon of Richmond, built, according to Stubbes, the N. transept and a central bell-tower at his own expense. The early Norman nave of Abp. Thomas still remained: but its removal commenced in 1291. when Abp. Romanus (1285-1296), son of the treasurer, laid the first stone of the existing nave, which was completed, after some intermissions. about the year 1345; although its wooden ceiling was not added until 1355. The chapter-house was in progress at the same time as the nave. Abp. Roger's Norman choir was standing at the completion of the nave, but it was plainly out of character with the increased size and magnificence of the new building; and in 1361 Abp. Thoresby (1852-1873) began the existing Lady-chapel and Presbytery, which were, no doubt, completed at the time of his death. Between the years 1373 and 1400 the Norman choir was entirely taken down, and was replaced by that which now exists. The central bell-tower, which had been the work of the treasurer, John Romanus, was recased about 1405, and the works of the present tower extended over the succeeding years. The S.W. tower was begun about 1432, whilst John Berningham was treasurer; the northwestern was completed about 1470; and on the 3rd July, 1472, the ch., which had thus been completely rebuilt, was reconsecrated, and the day was afterwards observed as the feast of dedication. Like the first wooden



St. Peter the Apostle.

The dates and architectural character of the different portions of the cathedral may be thus recapitulated :---

Saxon, of uncertain date.—Inner wall of crypt,

Norman (temp. Abp. Thomas, 1070-1100).—Remains at western end of crypt.

Late Norman (temp. Abp. Roger, 1154-1181). -- Eastern portion of

crypt.

Early English (1215-1256).--North

and south transents.

Decorated (1285-1345).—Nave and chapter-house.

Early Perpendicular (1861–1373). -Lady-chapel and presbytery.

Perpendicular (1373 - 1400). Choir.

Late Perpendicular (1405-1470).-Central and two western towers.

The Minster is built of magnesian limestone from quarries near Tadcaster; from the Huddleston quarries near Sherburn; and from quarries near Stapleton (Pontefract). A body of workmen (not so large as that which the Fabric Rolls show to have been in the constant service of the chapter) is kept for the execution of repairs, on which considerable sums are spent yearly.

II. York Minster has, perhaps, a more widely-extended reputation than any other English cathedral. Until the rise of the great manufacturing towns within the present century, York, like the Roman Eboracum which it replaced, was by far the most important city in the North of England. It was centre from which Christianity had been dispersed throughout the country north of the Humber, and the ch. in which Paulinus baptised King Edwin was, as we have seen, long preserved within the walls of the existing cathedral. The wealth and

dedicated in the name of God and of the memory of the great change of faith in Northumbria, found their most permanent representative in the Minster, which, as the metropolitan church of the Northern Province, gathered about it the recollections, often of deep historical interest, connected with its long series of archbishops. These causes sufficiently explain the early fame of the cathedral; and after the completion of the long series of works which have just been recorded, the sise and grandeur of the building itself rapidly extended its reputation. Mineas Sylvius, afterwards Pope Pius II. who passed through York about the year 1430, soon after the central tower had been finished, describes the ch. as "worthy to be noted throughout the world (toto orbe memorandum) for its size and architecture; with a very light chapel (sacellum lucidissimum)—the Chapter-house?) whose glass walls" (the large windows) "rise between very slender clustered columns." The shrine of St. William, the great treasure of the Minster, although no doubt rich and stately, was exceeded in importance by that of St. Cuthbert at Durham, and probably by those of St. John at Beverley and St. Wilfrid at Ripon: but the cathedral itself was always the great centre of the northern counties, and it still remains a bond of union between the many sects, parties, and classes scattered over the three Ridings. Whatever touches the Minster touches the heart of Yorkshire.

Although other English cathedrals can show portions and details of better design and of more delicate beauty, it must be admitted that few exceed York Minster in dignity and massive grandeur. These are especially the characteristics of the exterior. From the walk on the walls the cathedral is well seen, towering above the ancient city. Of the nearer views the best are—that of the W. front, from the importance of the ancient city, and end of the space before it, which has

been elegred of many cottages and ! decaying buildings; and that of the whole N. side, from the lawn in front of the Desmery. In the height of its roofs (994 ft. in the nave, 102 ft. in the choir) York exceeds every other English cathedral. This great height is evident on the exterior, where, to some extent, it dwarfs the apparent dimensions of the central and western towers: and it is the main cause of the first powerful impression on entering the building. The great breadth of the nave (104) ft., with its aisles) is ill-supported by the comparatively slender piers of the main arcade, which want the grandeur of the Norman piers at Edy or Peterborough, or of the more massive Perpendicular arcades in the naves of Winchester and The breadth of the Canterbury. choir (991 ft.) is somewhat less; but it combines with the square eastern end, filled with one of the largest windows in the world - a literal "wall of glass"-and with the lines of the aisle-walls, unbroken by chantries or side-chapels to produce an impressive effect. The view across the great transcot takes its place, without question, among the finest architectural views in Europe.

The transept aisles are vaulted with The original roofs of both neve and choir were of wood, probably on account of the unusual breadth of the space to be covered. In the night of February 1st, 1829, the choir was set on fire by a certain Jonathan Martin, who had hidden himself after the evening service of the previous day behind Archbishop Greenfield's tomb in the N. transept. After destroying the carved stalls and the organ, the flames reached the roof. which was entirely consumed. Considerable damage was done to the stonework of the choir; and the great E. window was not saved without difficulty. Martin himself (who was a brother of the well-known artist) escaped through a window of the

a few days afterwards, and tried at the York assizes, when he was pronounced insane. He was confined in a lunstic asylum, and died in 1838. The cost of restoration after the fire was estimated at 65,000L, which sum was raised by public subscription: 5000L worth of teak timber was granted from the National Dockvards: and Sir Edward Vavasour, like his ancestors in the 14th cent., gave the necessary stone from the Huddlestone quarries (near Ferry Bridge), the same which had been worked in the time of Archbishop Thoresby. The restoration, which was completed in 1832, was entrusted to Sir Robert Smirke. The roof of the nave was destroyed on the 20th of May, 1840, by a fire which broke out in the S.W. (the bell) tower, where some workmen had been repairing the clock. The tower was reduced to a shell; the bells were destroyed; and the flames rapidly spread to the roof of the nave, the whole of which was burnt: 28,000L was raised, chiefly by subscription, for the restoration. which was completed in the following year, under the care of Sidney Smirke.

The dimensions of the principal parts of the Cathedral are as follow :-

Length. Breadth, Height. Ft. Ft. Ft. Nave . 264 991 1044 Choir and Presbytery 223 994 102 Transepts . Lady-chapel . Central Tower 223 93‡ 99 101 ٠, 64 100 216 Western Tower .

The South Transept, owing to the great weight and pressure of the roof and cak-groined ceiling, of which the latter is carried high above the top of the walls, was found to be in so dangerous a condition that in 1872 the work of reconstructing it was entrusted to Mr. G. E. Street. He found it necessary to take down the wall as far as the base of the clerestory, and to rebuild it, with the old materials, and precisely as before. It would appear, also, that the retranscopt, but was taken at Hexham casing of the tower piers (see § xxiv.),

had much injured the transept.

The cathedral is usually entered from the S. Transent, the great portal of which fronts the visitor as he enters the Minster-yard from Stonegate. The transept is, as we have seen, the earliest portion of the existing church; and by commencing here. each part of the cathedral may be described in due architectural succession. (The architecture, the monuments, and the stained glass of each division are described separately and successively. The numbered sections will assist reference.)

Leaving the rest of the exterior for the present, the visitor before entering should remark that of the S. transept. This transept was erected, in all probability, during the archiepiscopate of Walter de Gray (1215-1255), and is pure E. E. There is little difference in general design between the two transepts, both of which must have been completed during the lifetime of Archbishop Gray. Both have E. and W. aisles. The main distinction between them is in the composition of their gables, or N. and S. ends, which differ entirely, that of the N. transept being infinitely the finer.

In the S. transept the main or central portion is divided from the fronts of the aisles by enriched buttresses. Two flights of steps ascend to the portal, "set in a shallow porch of very meagre composition and execution," the upper part of which is flanked on either side by a lancetwindow. In the story above are three lofty pointed windows, much decorated with brackets and shafts, and with the dogtooth in their mouldings; and the actual gable is filled with a very rich rose-window, with narrow pointed openings below and a triangular light above it. The whole of this front was admirably restored by Edward Street, R.A., 1880.

while strengthening the tower itself, to the visitor on entering is without doubt the finest in the cathedral. great height (99 ft.), breadth (934 ft.), and length (2281 ft.) of the whole transept; the majesty of the fine lofty lancets which nearly fill the N. gable: the solemn light struggling through their ancient dispered glass; the great central tower with its unrivalled lantern, combine to produce an impression fully sustaining the great reputation of the Minster.

In the S. transept the piers of the main arcades have clustered shafts, of local stone and Purbeck marble alternately. In the central piers all the shafts are ringed. In those at the ends (except that in the angles adjoining the nave, afterwards to be mentioned) only the Purbeck shafts have rings. The capitals are foliaged. The outer moulding of the main arches on the E. side is enriched by a small double dogtooth ornament. The effect with a billet between. thus produced is very rich. The dogtooth occurs again on each side of the soffit; one row only being visible when the arch is looked at in front. The triforium in each bay is formed by a wide circular arch enriched with the dogtooth, enclosing two pointed arches, each of which is again subdivided into two. In each bay of the clerestory is a group of five pointed arches, of equal height: the shafts between which are Yorkshire stone and Purbeck marble The arches have many alternately. mouldings, among which appears the dogtooth. At the back of the clerestory passage are three lancets in each bay, corresponding to the central arches of the arcade. vaulting-shafts, in groups of three, with dogtooth ornament between them, spring from brackets of leafage between the main arches. They rise, ringed by the base moulding of the triforium, and again somewhat higher, to the crowns of the pointed triforium arches, where they terminate in capi-IV. The view which is presented tals of leafage. On these capitals

rest bases, from which triple shafts! Blessed Virgin and St. John in the rise to the base of the clerestory, which enrings them, and forms their capitals.

In the gable is the rose or wheel window, the best and most striking feature of this end of the transent. It is only necessary to turn toward the N. transept to perceive at once how far that gable end exceeds the S.

The wall of the W. aisle is lined below the windows with a foliated arcade, having bosses of leafage at the intersections of the arches. rose-window in this transept, and the five smaller lancets in that opposite. were long cut off by the groinings of the roof. The line of it was raised before the restoration under Mr. Street (1873), so as to bring back both these to the interior. Mr. Street, as has been said, found it necessary to take down the walls as far as the base of the clerestory. In rebuilding them, he has given much greater strength by making the piers solid. Since the erection of the central tower, the passage through them had led to nothing. The whole weight of the roof and groined ceiling is now carried on timber from the floor.

V. The stained glass in this transept is of no great importance. That in the rose-window is modern and In the windows below are: in the centre, St. Peter and St. Paul; with St. William of York E., and St. Wilfrid W. The four lower lights are filled with glass by Peckett of York, given to the cathedral in 1793. The figures are Abraham, Solomon, Moses, and St. Peter. The colour of this glass is fine; Peckett's ruby was especially famous; but the background and accessories are thoroughly bad. In the eastern aisle is some Perp. glass, with the figures of St. Michael, St. Gabriel, and St. William, toward the N., in the chantry of St. Michael the Archangel, founded by Abp. Gray in 1241; and with those of the soulding propensities of Archbp. Gray, that the W. front of Ripon was in all probability his work. (See that Cathedral, Rtc. 22.)

chapel founded in their honour, in 1273, by Thomas de Ludham, Canon of York. In the W. aisle is some ancient Perp. glass, with modern borders. The yellow glass here used for the head of our Lord deserves notice.

VI. In the E. aisle, S. transept, is the finest monument in the cathedral. the magnificent Tomb, with effigy and canopy, of Abp. Gray (1215-1255). There is no direct evidence for assigning the foundation of the entire transept to this Archbp.; • but it is certain that the transept must have been complete (or nearly so) 1241, when he founded the chantry in which he lies interred; and it was the usual custom to bury the founder in the midst of his own [Gray, who was one of the work. greatest English prelates of his century, was the friend and favourite of King John, and has at least the merit of entire fidelity to his patron. He was Chancellor from 1205 to 1214, and was not less valued by Henry III., who twice left him Regent of the kingdom. At Christmas. 1252, the Abp. married Alexander of Scotland, and Margaret, daughter of Henry III. Both Courts were at York for some weeks, and the feasting was prodigious. Gray was an excellent economist in his diocese. and was the purchaser (for the see) of Bishopthorpe, and of York Place in London (afterwards Whitehall). See Raine's 'Lives of the Abps. of York.'

The pier arch under which the

* The tradition however, has always run to this effect. The antiquary Gent, writing in 1731, "mounted on his courser" to visit the little church of Skelton, near York, "because it is affirmed 'twas built with the stones that remained after the S. cross of the

tomb stands is made wider than the others, apparently to give it importance. The effigy of the Abp. (who "seems to have been a man of small stature and slight frame"), vested in cope, tunic, dalmatic, and alb, has an enriched arch above the head, on either side of which are censing angels. One hand is raised in benediction; with the other the pastoral staff is held, the end of which pierces the dragon, trampled on by the feet. Over the effigy rises a lofty canopy, resting on four shafts on either side, and another at the head. shafts have capitals of leafage, and support foliated arches, the spandrels between which are ornamented with leafage. Above, again, rises a second, smaller canopy, with three foliated arches on each side, resting on short piers with enriched capitals. canopy is crested by gables, with heads at the intersections; and from the gables rise finials of foliage crowned by two thrushes resting upon woolpacks. The sides of the gables, and the central ridge of the canopy, have crockets of foliage.

All the details of this monument deserve very careful attention. It was retouched during the time of Abp. Markham (1777-1807) by an Italian named Bernasconi; and the finials with their thrushes are merely of plaster. These are an addition, and had no existence in the original monument. Their introduction, therefore, cannot be defended, notwithstanding their grace and beauty. The bronzed screen which surrounds the tomb was presented by Abp. Markham, and was designed by De Corte,

an artist of Antwerp.

N. of the tomb is a plain marble slab, charged with a floriated cross, and elevated on low pillars. It marks the resting-place of Abp. Sewal de Bovill (1256-1258); a man of "modesty, piety, and learning." A gold ring, taken from the Abp.'s grave about 1735, is preserved in the vestry. It is of plain workmanship.

VII. The narrow, walled-up arches, adjoining those which open to the aisles of nave and choir, have still to be described and accounted for. must be remembered that the Norman nave and choir remained after the erection of the E. E. transepts, and that they were considerably narrower than the present ones. "It is true that the central aisle of the Norman nave was very nearly of the same width as the new one; but its sideaisles were exceedingly narrow in proportion. Each side of each transept, in accordance with the then existing arrangements, was provided with one narrow pier-arch, opposite to the side-aisle of the nave or choir, and with three other pier-arches of When the present greater width. nave was built, its wide and spacious side-aisles opened to each transept immediately against the narrow pierarch, which had been adjusted to the narrow sisle of the preceding nave; and its pier was now found to be in the very centre of the passage from the side-aisle of the nave to the transept. As this arrangement was evidently intolerable, the pier was taken away, and a Dec. pier erected, at a greater distance from the tower-piers, so as to leave a proper space for the passage from the sideaisles to the transepts. Instead. however, of constructing Dec. arches above the new pier, the E. E. arches were simply shifted, and their archstones reset, so that at present the narrow arch which originally occupied the position nearest to each tower-pier, and corresponded to the side-aisles of the nave, is shifted to the second place; and the wide pier-arch, which originally held the second place in order from the tower-pier, has become the first in order, and serves to open the way to the side-aisles. To strengthen the building, it was also found necessary to wall up the space between these new Dec. piers and the central pier of the transept, on each side. When the choir was built, similer recents compelled a similar to the tower-pier, is also Dec. The change, and thus the two sides of each transent became assimilated. The triforiums, however, remained unaltered, and to this day preserve their original arrangement. Thev each have three wide and equal arches extending from their respective gables; and after these one narrow compartment in connection with the tower-pier; and the clerestories, in like manner, present three equal compartments, and one narrow one; but below, reckoning from the gable, we find two wide arches, then one narrow arch, and, lastly, one wide one."-Wilks, Archit, Hist. of York Cathedral.

It will be seen, therefore, that the piers opposite to the tower-piers. E. and W., are of the same dates as the nave and chair respectively. Much dislocation is apparent in the pier adjoining the nave, and is still more visible in the opposite transept. This was caused, not by the shifting of the E. E. arches, which seems to have been entirely successful, and which is accordingly characterised by Professor Willis as a "very remarkable exsample of the bold engineering work of the Middle Ages," but by the erection of the central tower, the great mass of which caused the piers on which it is raised to sink "bodily into the ground, to a depth of about eight inches," dragging with them the adjoining masonry and arches.

VIII. In its general arrangement the N. Transopt resembles the S.; but there are some differences of detail. It is, according to Stubbes, the work of John le Romain, subdean and treasurer of York 1228-1256; and its erection must have immediately followed the transept of Abp. Gray. On the W. side of this transept, the first pier from the gable end is Dec., the original R. E. pier having no doubt been removed when the narrow arch which opened to the nave was shifted. The pier of this arch, next know not,"-Gent's York Cathedral.

chief points of difference between this and the corresponding side of the S. transept are—the character of the foliage, which is here more advanced and natural; the smaller vaultingshafts: and the use of a large-leafed ornament (like half a dogtooth) in the base of the triforium, and in the cornice above the clerestory. At the intersection of the main-arch moulding is an animal creeping downwards, well rendered; and above is a small figure of a saint under a Dec. canopy. On the E. side the piers have capitals of very rich leafage, among which (in the capitals of the central pier) birds with human heads, and other grotesques, are perched. The grand and simple composition of the N. end has been already noticed. The chief space is entirely filled by five very lofty (about 50 ft. high) and narrow lancets, best known as "the Five Sisters."* These are of equal height. In the gable above them are five small lancets, declining from the centre. The five front windows are divided by groups of shafts, ringed in three places, and of stone and Purbeck marble alternately. The shafts, which have capitals of foliage, are detached, and there is a passage along the sill of the windows. The arch mouldings are enriched with dogtooth. Below, the wall is covered with a foliated arcade, resting on clustered shafts.

The "Five Sisters" are filled with their original early English glass, consisting of diapered patterns, varying in each window, and of very great The narrow white border which surrounds each window was inserted in 1715. The glass in the five upper lancets is modern.

* This name no doubt arose from the equal dimensions of the 5 windows, "There is a tradition that 5 maiden sisters were at the expense of these lights; the painted glass in them, representing a kind of embroidery or needlework, might perhaps give occasion for this story. This window has also been called the Jewish window, but for what reason we At the N. end of this aisle a very rich decorated portal, opening to the vestibule of the Chapter-house, has been cut through the E. E. work. An original E. E. entrance remains at the

N.E. angle.

The monuments in this transent are-in the eastern aisle, the tomb, with canopy, of Archbp. Greenfield (1306-1315), Chancellor of England at the time of his election, and employed on many public services by Edward I. and II.; he presided at the Council which condemned the Templars of the northern province. and was afterwards present Vienne when (1312) the order was dissolved. The very rich canopy. which deserves notice, is crowned by a figure of the Abp. bearing his cross, and with his hand raised in benediction. This is modern, and the work of a late master-mason of the cathedral. A portion of a brass (one of the earliest existing brasses of English ecclesiastics) remains on the tomb. ("The only earlier brass of an ecclesiastic which is known is that of Richard de Hakebourne, circa 1311, in the chapel of Merton College, Oxford."—Haine's Manual of Brasses.) The lower part was stolen about the year 1829. The Abp. is represented fully vested, and wearing the pall. A gold ring, with a ruby, taken from the tomb in 1735, is pre-E. of the tomb served in the vestry. E. of the tomb stood the altar of St. Nicholas, on whose festival the death of Abp. Greenfield occurred. It was at the back of this monument that the incendiary Martin hid himself on the night of the fire.

In this aisle is also the monument, with effigy, of Dr. Beckwith, who died in 1843, leaving to his native city the benefactions here recorded, amounting

to nearly 50,000l.

In the W. aisle is the cenotaph, with effigy, of Abp. Vernon-Harcourt (1808-1847). The effigy, the hands of which are clasped on a book resting on the breast, is by Noble.

IX. The Norman Nave remained after the completion of the E. E. transepts. About 40 years after the death of the treasurer John Romanus, the constructor of the N. transept, the foundation-stone of the existing nave was laid (April 6, 1291) by his son, Abp. Romanus or le Romain. The work seems to have proceeded slowly. and with interruptions; and it was not until 1338 that the windows (including the great W. window) were glazed. In 1345 the stonework seems to have been entirely complete; but the ceiling of wood was not added for 10 years. Abp. Thoresby granted the timber for it in 1355. The cost of the general work was defrayed by offerings at the shrine of St. William, whose relics had been translated with great magnificence in 1284; by indulgences and briefs issued on behalf of the fabric by Abps. Corbridge, Greenfield, and Melton; by large contributions from the Abps. themselves; and by grants of stone and wood from the quarries and forests of the great Northern houses, especially those of Vavasour and Percy. Abp. Romanus commenced the work at the S.E. angle of the nave aisle; and although a petition, in 1298, shows that the Norman nave had then either been pulled down or had fallen, it is probable that it was allowed to remain untouched as long as possible. The much greater width of the existing side-aisles would admit of the Norman walls standing within those of the new nave.

The nave of York Minster was thus in progress throughout the Decorated period. It can hardly be said, however, that the work, either in design or in detail, is among the best examples of English Dec.; and, in spite of its vast dimensions, the nave of York is unquestionably inferior to those (later in date) of Winchester or Canterbury. Yet the long roofs of nave and choir, stretching away at nearly the same great height; the tower

arches which support the lantern; the enormous east window of the choir.-the "wall of glass" closing in the vista, and showing its upper portion above the organ-screen; and the solemn effect of the stained class filling the windows of nave, aisles, and clerestory-all aid in producing an impression of grandeur. Looking westward, the great feature is the western window, with its stately rows of saints and archbishops. The view across the nave, through the arch opening from the nave aisle to the transept, is fine and unusual, owing to the great width of the aisle, and consequently of the arch.

The design of the piers of the nave is octagonal, with attached shaftslarge at the four main points, with smaller between them. Toward the neve itself the large shaft, with a smaller one on either side, rise to the spring of the vaulting, somewhat above the base of the clerestory. These shafts, the effect of which, unbroken by ring or stringcourse, is very fine, terminate in capitals of leafage. The capitals of the pier-shafts are also enriched with leafage, and the outer moulding of the arches (which are very acute) has projecting busts

at its angles. The nave has " but two great divisions; of which the lower one, containmg the pier-arches, is 51 ft. high; the upper one, 43 ft. high, is occupied by a large clerestory window of five lights, with geometrical tracery, and a transom across the middle. lights above the transom are glazed, and constitute the real window; but the lights below the transom (if the phrase can be applied to openings so perfectly dark) are open, and, as the roof of the side-aisle abuts against the transom, the space behind them, and to which they communicate, is the interval between the stone vault of the sisles and its wooden roof; they thus serve the purpose of a triforium. -Willie. The rich and peculiar headbe noticed. The triforium passage, in their high sills, is formed by a double line of tracery, with 5 openings in each bay. In the central opening of each bay was originally the figure of a saint. The entire series is said to have represented the patron saints of the different nations of Christendom: but nearly all have now disappeared, and the only remaining figure which can be identified with any probability is that of St. George, in the fourth bay from the W., on the S. side. From the N. bay, opposite, projects a stone beam, the head of which is carved to represent that of a dragon, This formerly supported the canopy of the front.

It will be seen that the design of the nave differs altogether from that of the transepts, and that "the latter has not exercised the slightest influence upon the composition of the former, although the reverse has been frequently the case when a Decorated building has been added to an E. E. one, as may be seen at Ely, Westminster, and St. Albans."—Willis. The transepts have three very distinct divisions—pier-arches, triforium, and clerestory. The nave has but two.

In the spandrels of the pier-arches is a series of shields, the bearings on which are those of benefactors to the fabric.

X. The great width (30 ft.) of the nave aisles at once excites attention. The actual nave, or central aisle, was the same width in the Norman ch. as in that which now exists; but the side-aisles of the Norman nave were at least 10 ft. narrower. The aisle windows should be compared with the clerestory. In both, "the tracery is geometrical; but in the side-aisles the pattern is much simpler than in the clerestory. The former, and of course the earlier, as being lower in the building, is in 3 lights, without subordination or mouldings; but the latter is in 5 lights, with a rich head, ings of the clerestory windows should | and a complex subordination of mould-

runs a very rich arcade, with gables and pinnacles; and blind arches, with similar rich headings, line the walls between the windows. The carved heads and small figures at the termination of the outer mouldings of these upper arches should be noticed.

XL The windows at the W. end of the nave aisles have geometrical tracery, of the same design as the others. The great W. window of the nave itself is filled with the most exquisite flowing tracery, and in its original state was probably the work of Archbishop Melton (1317-1340), who gave a sum of 500 marks toward the completion of the W. front. and who is recorded as the donor of the glass which still remains in this window. There is, however, not one old stone in it, as it was restored (precisely on the original The only model) many years since. window in England which can be considered as at all rivalling this one is the E. window of Carlisle Cathedral, nearly of the same date and character. The Carlisle window (which is the larger of the two) has been pronounced by Mr. Fergusson "without a single exception the most beautiful design for window tracery in the world." It is not easy, however, to determine which of these windows is the finer; and many competent judges of architecture give the preference to York. "Although not the largest Decorated window in the kingdom." say Messrs. Poole and Hugall, "it is undoubtedly by far the finest, even taken without its accessories. great beauties are variety of design and fulness of tracery, without confusion as a whole, and without poverty of separate parts.

The great W. door, below the window, displays on either side a series of niches once filled with figures. The gable was perhaps crowned by a

ings."-Willis. Below the windows and blind arcading line the splays of the window. The side openings give light to the staircase of the tower.

> Over the aisle doors is some curious sculpture, which deserves notice. the N. aisle is, in the centre, a woman setting her dog (which is muzzled) at two beasts, behind which is a man blowing a horn. In quatrefoils at the sides are—a man drinking, and attacked by another, and a man driving another out of his house. In the S. aisle is-in the centre, a man, with sword and round shield, fighting a lizard-shaped monster; and in the quatrefoils. Samson with the lion, and Delilah cutting his hair; and a man and woman fighting. The sculpture over the door of this aisle is modern. although an exact reproduction of the old, which was greatly injured by the fire of 1840, that destroyed the roof of the nave, and began in the S.W. tower.

The aisle roofs are of stone, and of the same date as the aisles themselves. The vaulting of the nave is of wood. like that destroyed in 1840.

In 1868 the whole of the vast nave was fitted, for congregational purposes, with movable benches, choir seats, and an organ by Messrs. Hill and Son. The lighting of the nave is effected by jets of gas which form coronals round the capitals of the great piers. In the choir a string of jets runs along at the base of the triforium. The Minster. thus lighted, is singularly picturesque and impressive.

XII. More than one archbishop and many other great personages were interred in the nave; but their monuments and brasses were entirely destroyed by the Puritans, with the exception of a recessed tomb in the N. aisle, generally assigned to Abp. Roger (1154-81. He was with Becket in the family or "court" of Theobald, Abp. of Canterbury, and was on the King's side after the signing statue of the Saviour. On either side of the Constitutions of Clarendon. are kneeling figures. Rows of niches This was the "York" who, in

asserting the precedence of his see, | Edw. III. and Philippa of Hainault sat down in "Canterbury's" lap at a council in Westminster, and was half killed in consequence. At his death Hen. II. seised all his great treasure, and Foxe in consequence gives him a place among his martyrs: a compliment which the Abp. would scarcely have appreciated). This monument is, however, of a much later date; although it is possible that the remains of Abp. Roger may have been transferred to it from the choir, where he was originally buried. Some bones and fragments of vestments were found in the tomb when it was examined before its restoration in 1862. though the work is good, this restoration is not to be commended: and "two hirds holding scrolls, on either nde of the central figure of the Virgin, have been metamorphosed into eagles, with cars of wheat in their mouths."

The sainted Abp. William of York, who died in 1154, was then interred in the nave of the Minster, " near the S.W. piller of the lantern." His remains were translated in 1284; but a tomb or cenotaph still remained in the nave, and offerings were duly made at it. This tomb was destroyed at the Reformation (no doubt by Dean Layton), and the relics of the saint were replaced beneath the pavement of the nave. Here they were discovered in 1782. (See post, | xvi.)

Abp. Melton, who contributed so largely toward the completion of the mye, was interred near the font. His coffin in which was found a silvergilt chalice and paten, was examined during the laying down of the new pavement in 1786. This pavement is of marble and Huddlestone stone, and was designed by Kent. (Melton, 1317-1340, one of the most distinguished prelates who has ever filled the see, was involved throughout his episcopate in Scottish affairs, and in the great struggle between Edw. II.

in the Minster in 1328.)

XIII. The stained glass in the nave demands special examination and description. The glass throughout the Minster was little injured at the Reformation; and York surrendered to Fairfax in 1644 with the express stipulation that neither churches nor other buildings should be defaced. Hence the extraordinary quantity of stained glass remaining in the city.

With the exception of some E. E. glass in the tracery and other parts of the clerestory windows, and of some modern in that of the aisle windows, the nave retains its original glazing—the most perfect, and perhaps the most extensive remains of painted glass of the early part of the 14th cent., of which this country can boast. Two windows in the aisles, and two in the clerestory, are alone without stained glass.

The E. E. glass was possibly removed from the windows of the Norman nave when that was demolished at the beginning of the 14th cent The earliest of this glass is a portion of a Jesse in the second window from the west, on the north side of the clerestory. "The date of the glass is about 1200. It is therefore much older than the greater part of the E. E. glass at Canterbury Cathedral, to which I do not think a date can be assigned much earlier than the middle of the 18th cent. . . Much E. E. glass, varying in date from the beginning to the middle of the 13th cent., has been employed to fill the wheel of tracery in the head of the last-mentioned window, as well as the wheels in the tracery of the five next clerestory windows. The upper tier of subjects in the lower lights of the fifth and seventh windows, counting from the west, on the north side of the clerestory, are also E. E. An E. E. subject is inserted in one of and the Bruce. It was he who married | the lower lights of the sixth clerestory

window, counting from the west. The | contains many shields of arms; and wheels in the tracery of all but three of the clerestory windows, on the south side of the nave, are likewise filled with E. E. glass; and E. E. glass paintings are also to be found amongst the subjects in their lower lights."-C. Winston.

The rest of the glass in the clerestory, and that in the aisles (except some modern headings), is Decorated. "The general arrangement and execution of the designs throughout this part of the building are well worthy of notice, as evincing the attention paid by our ancestors to general effects in these matters. The west windows of the nave and aisles, of which distant views may be obtained, have their lower lights filled with large figures and canopies; while the windows of the aisles, with one exception, are adorned with paintings of a more complicated character, and on a smaller scale, and which are therefore better calculated for a near inspection. Much of the plain geometrical glazing in the clerestory windows is original, and, like that in a similar position in Cologne cathedral, affords a proof that the ancient glass-painters did not consider themselves bound to finish patterns destined to occupy a distant position as highly as those placed nearer the eye."-Winston.

Much of the Decorated glass in a clerestory is heraldic. The aisle the clerestory is heraldic. windows are for the most part white pattern windows enriched with coloured pictures and ornaments. The only windows of a different character are the two westernmost in the south aisle, one of which is a Jesse, having below it the date 1789, when it was probably restored by Peckett; the other has three large and very fine figures with canopies-St. Christopher, St. Lawrence, and another saint. The earliest of the Decorated windows is probably the first (from the east) in the north aisle. This, the subject of

from a comparison of them with a halfeffaced legend across the lower part of the window, Messrs. Winston and Walford, who examined it very minutely, conclude that it was the gift of Peter de Dene, a canon of York, during the first years of the 14th cent. All the windows were in all probability special gifts to the fabric; and the bellfounders are said to have presented that adjoining Peter de Dene's.

The small figures of saints in the quatrefoils of the tracery in the south aisle are very fine and should be noticed. In the west window of this aisle are figures of the Virgin. St. Catherine, and another saint. west window of the north aisle has a Crucifixion, with the Virgin and St. John. Both these windows, the latter of which is especially striking, should be seen from the eastern end of the aisles.

The great west window was no doubt the last to be filled with stained glass. This was done in 1338, at the expense of Archbp, Melton, who gave 100 marks for the purpose. contains three distinct rows of figures: below, eight Archbishops, unnamed; above, eight saints, among whom St. Peter, St. Paul, St. James, and St. Catherine are conspicuous; and above again is a series of smaller figures. The rich and solemn colouring of this window, the fine arrangement of figures and canopies, and the manner in which the glass is adapted to the graceful lines of the tracery, render it worthy of all possible study and attention. It should be mentioned, however, that many of the heads of the figures are modern—the work of Peckett, who was employed to restore this window about the year 1747.

XIV. Taking the Minster in chronological order, we pass from the nave into the Chapter-house. The erection of this, the most beautiful of English Chapter-houses, has not been recorded. and the series of Fabric Rolls does which is the story of St. Catherine, not commence until long after its com-

pletion. It is certain, however, that | it was in progress at the same time as the nave; and hardly less certain, from the character of its architecture, and of the stained glass which fills its windows, that it was completed before the nave—at all events, before the west front of the nave, with its curvilinear tracery.* The form of the Chapter-house, like those of Wells, Salisbury, and Westminster, is octagonal: but unlike those, and unlike any, except the earlier Chapter-rooms, in the form of a long parallelogram (as at Exeter, Oxford, and Chester), it has no central pillar. The vestibule opens from the north end of the transept aisle. and turns at right angles to the portal of the Chapter-house itself. It is clear, however, that both the north transept and the Chapter-house were completed before this vestibule was commenced. "This is demonstrable from the fact that parts of the north transept are cut away to admit of the addition of the vestibule, and that the very parapet mouldings of the Chapter-house itself appear within the vestibule, which has been built against it."-Pools and Hugall.

The solemn effect of the stained glass with which the windows of the vestibule are filled, at once impresses the visitor who passes into it from the transept. The portal has two trifoliated arches with square headings. The wall above is covered with blind tracery, resembling that of the windows. Part of the E. E. buttress of the

e Various dates have been assigned to the Chapter-house. Mr. Browne thinks it was begun about 1280, though not completed until far into the next century. Professor Willis is of opinion that this date "is too soon by fifty years for the beginning"—**arch. **Hist.* of York.* p. 30; and his judgment is sustained by that of the Rev. James Raine, editor of the 'York Fabric Rolls,' Preface, p. xiv. On the other hand, Messrs. Poole and Hugali assert that the Chapter-house "does not seem more advanced than the crosses of Queen more advanced than the crosses of Queen the Bleanor," and suppose "that both Chapter-house and vestibule were concluded very early in the fourteenth century,"—**Tork Cathedral, p. 58.

[Yorkshire.]

transept, a window arch, and a cornice of dogtooth above it are here visible. Below the lofty windows of the vestibule (which resemble those of the Chapter-house—see post) runs a wall arcade, formed by a pointed archemistrate trafficial archemistrates.

enclosing trefoiled arches. The portal of the Chapter-house is formed by two trefoiled arches, divided by a central shaft. These arches are circumscribed by a main arch with a quatrefoil in the tympanum, containing two brackets for figures. a niche against the central shaft is a mutilated figure of the Virgin and Child of extreme beauty. (The Purbeck marble of the shafts is fast decaving, whilst the Yorkshire stone is still perfectly sound.) The Chapterhouse retains its original oaken door, covered on the interior with a kind of trellis-work of wood, and on the exterior with scrolled ironwork, deserving the closest attention. The scrolls, which are cut into leafage and flowers, are admirable in design, and terminate at the top of the doors in dragons and lizard-like monsters. They should be compared with the ironwork of the cope-chest in the choir aisle, which is of the same date. said that four of these chests stood originally in the centre of the Chapterhouse.

3000L of the sum left to the Minster by the late Dr. Beckwith, whose monument is in the transept, were appropriated by him to the restoration of this Chapter-house. was accordingly commenced in 1844. Much of the Purbeck marble was then renewed. The vault was restored and decorated by Willement, and the floor was laid with Minton's tiles. All traces of the ancient painting and gilding were then unhappily obliterated; but no amount of restoration has as yet deprived this building of its right to stand at the head of English Chapter-houses. It is still fully entitled to the distinction implied in the ancient verse painted on the left side of the entrance,-" Ut

Rosa flos florum sic est domus ista other sculpture of this period, either domorum."

Each bay of the Chapter-house contains a lofty window, with magnificent geometrical tracery of somewhat late character. Each circle in the headings has nine cusped foliations. Below, runs an arcade of wonderful beauty. There are six arches in each bay; and each arch contains a recessed semi-octagonal seat, with attached shafts of Purbeck marble at the angles and at the back. In front of each angle rises an entirely detached shaft of the same marble. Each seat is groined, with a boss of hollow worked leafage in the centre, and the capitals of the Purbeck shafts are worked in varied leafage of ivy, maple, oak, and other trees. overhanging canopy has two pendants of leafage in front of each recess. The canopy, which is gabled, is enriched with finials of oak-leaves; and a cornice of vine-leaves and grapes bends round above it, following the line of the recesses. The effect of this superb mass of enrichment is perhaps unique. The arrangement is unlike that of any other English Chapter-house, especially in the form of the seats, and in that of the cornice above the canopy.

At the intersections of the gables, and at the angle between each stall, are grotesque heads and figures of wonderful spirit and variety. Besides animals and birds there occur human heads, men fighting with monsters and with each other, besides several monastic figures, full of the satire in which the secular clergy were always ready to indulge. Birds and small animals are perched among the leaves of some of the pendent bosses. The whole of this sculpture will repay the very closest examination. It is distinguished by that careful imitation of nature which belongs to the work of the early part of the 14th cent.: and in the spirit of the heads and grotesques, and the graceful arrangement of leafage, it is exceeded by no and consist chiefly of single figures

in England or on the Continent.

The entrance portal should be examined from the interior. it is a wall arcade of very beautiful design, with thirteen brackets for figures of the Saviour (or the Virgin and Child) and the Apostles. Thesewhich are traditionally said to have been of silver gilt-have disappeared. Two angels remain at the sides above. A wall-passage, with square-headed openings in the splays, runs round below the windows of the Chapterhouse. Between each bay, clustered vaulting shafts run to the roof, which is of wood. The vaulting ribs pass to a central boss, on which is the Lamb bearing a flag with a cross. The roof, before This is modern. the restoration in 1845, was "richly painted with the efficies of kings. bishops, &c., and large silver knots of carved wood at the uniting of the timbers, all much defaced and sullied by time."—Gent.

The stained glass with which the windows are filled adds not a little to the solemnity of the building. They are white windows with coloured medallions, and shields in the tracery, some of which are modern. glass " is of the time of Edward II, and commencement of the reign of Edward III., and is an extremely beautiful specimen of early Decorated work."-Winston. The E. window is alone modern, and the work of Messrs. Barnett, of York. "If it does not produce so satisfactory an effect as the original windows, this arises not from the fault of the artist, but from the impossibility of procuring at the present day a material similar in texture to the glass of the 14th cent."—Winston. The subjects in this window are from the life of our Lord. The borders of the ancient windows, and all the details of the glass, afford admirable studies and examples, and should be carefully examined. The windows in the vestibule are of the same date, under canopies. Some E. E. glass, of the same character and date as that in the "Five Sisters" (in the N. transept), has been inserted in the tracery of the second window from the door, in the vestibule.

XV. Leaving for the present the central tower and the rood-screen. we pass into the Choir. After the completion of the nave, it was determined to replace Archbishop Roger's late Norman choir with one of greater size and magnificence: and, whilst so doing, to provide a place "where the mass of the Blessed Virgin might be fittingly celebrated." Archbishop Roger's choir had short eastern transepts, and terminated, eastward, two bays beyond them. The design for the new work extended it three bays towards the east, and widened the whole choir and presbytery by making the aisle walls run in a line, east and west, with the outer walls of the short The presbytery Norman transepts. and Lady-chapel, forming the four easternmost bays of the existing building, were first completed.* and it is probable that until their completion the Norman choir was not interfered with, and was still available for service. Afterwards this choir was entirely removed, and that which now exists was continued from the new presbytery, until it joined the E. E. transepts and the central tower.

The first stone of the new pres-

* The term "Presbytery" is here used, as it has been by Professor Willis and others who have written on the Minster, to denote the four easternmost bays of the building, including the Lady-chapel. But strictly speaking, no part of this was ever included in the true presbytery, which is the part of the church between the "Chorus cantorum" and the high after, set apart for the clergy who are ministering at the latter. At York, before the Reformation, and indeed long afterwards, the high altar stood at the eastern end of the #72a bay; so that what is here called the presbytery was behind it, and formed the retrochofr with its alsies.

bytery was laid on the 30th of July, 1361, by Archbishop Thoresby (1352-1373), who had already granted timber for the completion of the ceiling of the nave, and had been otherwise a considerable benefactor to the fabric. The presbytery is, however, his especial memorial. ward its construction he gave the stone of his manor-house at Sherburn, which had fallen into decay, besides a yearly sum of 2001, during the remainder of his life. amount of Archbishop Thoresby's contribution towards this part of the Minster cannot be estimated, "in the money of the present day, at a lower sum than 37,000l., and this in all probability, is considerably under the mark."-Raine. Large additional sums were raised by grants of indulgence to all benefactors, by taxes laid on the Chapter clergy, and by subsidies levied on the Church property throughout the diocese. Brief-bearers (brevigeri) were also sent through the country to beg for the fabric. The presbytery was accordingly completed before the death of Thoresby in 1373, within twelve years from its commencement. After his death the work remained for some time at a standstill, owing apparently to the loss of the Archbishop's large donations, and to the troubles of his successor, Alexander Neville (1374-1388), who died an exile from York. The choir seems to have been commenced about the year 1380, and in 1385 the Chapter obtained a lease of the quarry of Huddlestone for 80 years, showing that they were in want of stone, and that the work was in progress. The walls were completed about 1400, and the roof and wooden vaulting were finished at the beginning of 1405.

The choir and presbytery thus completed were perhaps the most magnificent works which, up to this date, had been attempted in England; and it is quite possible, as has been suggested by Mr. Raine, that William

1404), and Walter Skirlaw, at Durham (1388-1405), both of whom were connected with the ch. of York, and were intimate friends of Archbishop Thoresby, were encouraged to undertake similar works in their own cathedrals by the beautiful structure "they would gaze upon as it rose from the ground at York." visitor, on entering the choir, is first struck by the great eastern window, the largest in England, the lower part of which is seen through the pierced altar-screen. The vast height (102 ft.) and width (991 ft.) of the choir, impress the mind with a sense of grandeur, which steadily increases as the building becomes better known. Other English choirs are more picturesque; none is more majestic than this of York.

The general design of both choir and presbytery repeats that of the nave. There are two great divisions, the lower containing the pier arches, the upper the clerestory, the high sills of which form the triforium passage. The 4 easternmost bays (3 of them beyond the present altar-screen), forming the presbytery and Lady-chapel, completed during Thoresby's episcopate, although they agree in general character with the actual choir, exhibit in their details very distinct evidence of their earlier date. Standing toward the upper end of the choir, where the clerestory of both choir and presbytery may be seen at once, the contrast pointed out by Professor Willis will be at once clear. The clerestory windows were no doubt intended to match. "The number of lights are the same in each, and so is the system of subordination, by which two lights on each side are cut off, and included in a separate arch. (This, indeed, is also derived from the nave.) But in the presbytery a transom crosses the tracery, and connects these arches. In the choir, on the contrary, the two

of Wykeham, at Winchester (1367-| Perp. character to meet the window arch. In the presbytery these monials run up, but in the subordinate order of mouldings only, so as not to be prominent. The head of the presbytery window is occupied by a series of compartments that recline right and left fan-wise, and have many flowing lines in them, strangely mixed with others of decided Perp. But in the choir the character. whole of the filling up is of the most decided Perp. character; and shows that, when this part of the building had been reached, the Perp. style had become fully established."—Willis. the presbytery the clerestory passage runs outside the windows: in the choir, within the glass.

> The small heads which terminate the outer mouldings of the pier arches. and the general design of capitals and foliage, are imitated from the nave. On the north side of the choir, however, the capitals of the piers have some figures inserted among the foliage which deserve notice. Mr. Browne has found in them "the principal events of the tragedy which ended in the death of Abp. Scrope." But the choir was no doubt completed before his death in 1405; and there is no authority whatever for the appropriation.

Against each pier of the presbytery is a bracket and enriched canopy. These do not appear in the choir proper; but two of them, happily unrestored, remain on the piers adjoining the altar-screen. In the spandrels of the main arches of both choir and presbytery are shields of arms, slung from turbaned heads. They are chiefly those of benefactors, and of other persons connected with the Cathedral.

XVI. The fire of 1829 destroyed. as has already been mentioned, all the woodwork of the choir, including the roof, which was of wood, like that of the nave. central monials run up with decided sent vault is an exact reproduction

of that which formerly existed, and | is a very rich lierne. The stalls are also close copies of the old ones; and considering that the restoration under Sir R. Smirke was effected before the revival of Gothic architecture, it The original is highly creditable. stone altar-screen was destroyed by the fall of heavy beams, and by the general effect of the fire; but that which has replaced it is of very great beauty, and "so perfect a restoration that it may be treated as a study of Perp. screen-work." The altar now stands immediately in front of Until the year 1726, this screen. however, it stood one bay further westward; and at its back was a wooden reredos, rising very high, so as to obstruct the view of the east window, "handsomely painted and gilt, with a door at each end "opening into the space between it and the stone screen. On the top of the reredos was a music gallery. The space behind it is said to have served as a vestry "where the archbishops used to robe themselves at the time of their enthronization;" but it seems to have been so prepared for the enthronization alone of Abp. Kempe in 1427: and Professor Willis suggests that it was in all probability the place where the portable feretrum or shrine of St. William was kept. On the removal of the wooden reredos by Dean Finch in 1726, the altar was placed in its present position.

The sainted Abp. William of York (1143-1154) was a son of Count Herbert, whose wife, Emma, was sister of King Stephen. His election in 1143 incurred the violent opposition of the clergy (and especially of the Cistercians), who complained that it had been effected by court influence. After some struggles, and after his consecration by his uncle Henry of Blois, Bp. of Winchester, William was formally deposed in 1147 by the Cistercian Pope, Eugenius III.; and Abbot of Fountains. Henry Murdac, was consecrated to the see.

On Murdac's death in 1153, William was re-elected, and the new Pope Anastasius granted him the pall. went at once to York, but died there 30 days after his entry. The sufferings and gentle character of the Abp. won for him general sympathy; and as the Church of York had no saint peculiar to itself, it was anxious to procure his canoniza-tion. This was not effected till 1227. (On his entry into York the wooden bridge over the Ouse gave way, owing to the multitudes which thronged it. William is said to have saved them by a miracle; and a chapel ded. to him was afterwards erected on the site.) Abp. William was interred at first in the nave of the Minster; but on the 8th of January, 1283-4, his remains were translated by Archbishop Wickwaine, in the presence of Edward I., his Queen Eleanor, and a great company of prelates and nobles. The cost of translation was defrayed by Antony Bek, "le plus vaillant clerk de roisume," who on the same day was consecrated to the see of Durham. The relics were borne into what was still the Norman choir of Abp. Roger; and on the completion of the existing choir they no doubt found a resting-place in the position assigned to the shrine by Mr. Willis. shrine itself was richly decorated; and the head of the saint was kept by itself in a reliquary of silver, gilt, and covered with jewels. Layton, Henry VIII.'s commissioner, who was Dean of York, obtained a special grant of this reliquary for the use of the cathe-The relics of Sir William seem to have been interred at this time near their ancient resting-place in the nave; where, in May, 1732, Drake, the historian of York, found a leaden box containing "a number of bones huddled carelessly together without any order or arrangement." Until the Reformation this original place of sepulture seems to have been marked by a cenotaph at which offerings were made, as well as at the the transeptal towers of Abp. Roger's shrine itself.

The eagle lectern in the choir was the gift of Dr. Calcraft in 1686. For the stained glass in the clerestory windows, see post, § xxii.

XVII. The aisles exhibit the same differences as the choir and presbytery; the 4 easternmost bays being of the earlier date; the transeptal bay. with those westward of it, of the later. The windows of the eastern bays are more acutely pointed than the others; and their tracery is less distinctly Perp. The windows are of three lights each; and the slender shafts with enriched capitals, dividing the lights, should be noticed, as adding to the effect. The wall-spaces between the windows are divided by a group of vaulting shafts, on either side of which are two ranges of broad, canopied niches, with pedestals for statues. Below runs a plain arcade lining the wall. The vaulting shafts, which terminate above in capitals of foliage, have lower capitals, or rings of leafage, at the top of the arcade stringcourse. The vaulting itself (of stone) is plain, with small leaf bosses at the intersections.

The easternmost bay of each aisle is narrower than the others, and the side windows have only two lights. The eastern windows are of three, and in no way differ from the rest. At the angles (N.E. and S.E.) are doors opening to staircases which lead upwards to a passage through the base of the eastern aisle windows, and thence ascend to the galleries in front of the great east window of the presbytery. At the east end of the north aisle was the altar of St. Stephen; at the end of the south, the altar of All Saints.

The lesser or eastern transepts (which do not project beyond the aisles, and should rather be called transeptal bays) belong to the second period—that in which the choir was erected. They represent, in effect,

the transeptal towers of Abp. Roger's Norman choir;* and may be reckoned among the most original features of the Minster. "The exquisite and unique effect of the tall windows, rising almost off the floor into the roof, and occupying the whole width of the transept, is beyond all praise; it is one of those felicitous efforts of architectural skill in which the creative genius of a master-hand is recognised."—Poole and Hugall. For

the glass, see § xxii. The lower part of the window (like the great east window) has a double plane of tracery; the inner or open lights being exactly similar to those in which the glass is fixed. At each side of the window are, above, three rich canopies and brackets; and below, two lesser ones, like those of the aisle windows. A lofty arch opens from the transept E. and W.; and another of the same height opens to the choir. Above this arch the triforium gallery A second arch, with side passes. shafts, level with the clerestory windows, rises from the gallery to the roof, and through it the upper part of the transept window is visible from the choir. Above the arches. E. and W., is a window of the same height as the clerestory.

At the spandrels of the arches are shields of arms.

XVIII. The general character of the so-called presbytery, or retro-

* The choir of York Minster, as restored or rebuilt by the first Norman Archbp. Thomas (1070-1100), was short and apsidal. Archbp. Roger (1154-1181) took it down, and rebuilt it of much greater size, and on a different plan. This late Norman choir had a square eastern end, and short eastern transcptal towers, the foundations of which remain in the crypt. Before his elevation to the see of York, Roger had been Archdeacon of Canterbury; and many peculiarities of the "glorious choir of Conrad" in that cathedral (completed 1130, destroyed by fire 1174) were imitated at York. Among them was the double transept. Canterbury, however, had towers flanking the choir, N. and S., as well as a second or eastern transept. At York the flanking towers were made to perform the part of transepts also.

choir. has been already described. The canopies against the piers, and those under the east window, should be remarked and compared. stone carving in this part of the cathedral was greatly injured by the fire of 1829; and five of the canopies against the piers "were renewed by John Scott, the Minster mason; when changes were very inindiciously admitted into them. wanton alteration, even of a minute feature, must always be deprecated in such instances. . . . There is less difference between the two ends of the choir, at an interval of nearly fifty years from one another, than has been wantonly produced between canopies on adjoining pillars, whose place in the history of the church is identical? The original —Poole and Hugall. canopies, unrestored, remain on the piers adjoining the altar-screen.

The areat East window—the largest window in the kingdom that retains its original glazing *- is one of the chief glories of the Minster, and is best examined here. It is impossible to look up at it without feelings of increasing wonder and admiration. In itself the design is fine and unusual. Almost filling the entire bay, the window rises quite to the roof, in three lofty stages, the two lower having an inner plane of open arches, through which, at the base, runs a passage, with doors at the angles opening to a staircase in the buttress turrets of the window, by which access is gained to a second gallery, with a parapet in front, running across at the foot of the highest stage. The elaborate tracery which fills the upper part of the window is of the same undecided character (Perp. with some flowing details) which already been noticed in the windows

• The R. window of Gloucester Cathedral is somewhat larger, but is partially (in the lower part) unglazed. The Gloucester window is about 72 ft. high, and 38 wide. The York window, which is entirely glazed, about 78 ft. high and 33 wide.

of the clerestory and aisles. jambs of the window, in each stage (within the plane of open arches) were enriched with figures, for which the brackets and canopies remain. The under-part of the gallery is covered with panelled tracery. Above, in the window-jambs, are heads of saints, with canopies, arranged at intervals; and small canopied brackets, with figures of angels, form a continuous outer moulding. (See & xxii. for the glass.)

The narrow wall-space on each side of the window has a double row of brackets, with canopies, ascending in four tiers. Under the window the wall is lined with a plain arcade nearly hidden by monuments. the centre, above the place of the altar, are three canopied niches. the base are figures of angels, kings, and bishops; all deserving examina-

tion.

The view from the upper gallery of this window is very striking. The west window of the nave, especially,

is best seen from this place.

Beneath this window was the altar of the Lady-chapel, founded by Abp. Thoresby, and before which he was himself interred, in the midst of the magnificent building he had so largely assisted in raising. Thoresby (1352-1373), one of the best and greatest prelates of his age, had been employed by Edward III. on various public matters before his elevation to the see of York. He was chancellor from 1349 to 1356. His services to the state were great, and those to his diocese greater. He was indefatigable in reforming and instructing it. his time, and greatly by his influence, the long contention between the northern and southern primates was happily ended, and the Pope named one "Primate of England," and the other "Primate of all England." The remains of several of the Abp.'s predecessors, removed from the Norman choir, were re-interred here, under monuments which were made for formed a series of brasses, the greater part of which were destroyed during the civil war; and the rest (with the stones containing the matrices) disappeared when the choir was newly paved.

XIX. Of the monuments in the north aisle of the choir and presbytery, the most remarkable is the following: In the last bay of the aisle, westward, and against the wall of the transept aisle, is a high tomb, recessed, with the effigy of William de Hatfield, second son of Edw. III., born 1336, died 1344, aged 8. The effigy is finely wrought. The prince wears a short tunic, covered with a rich leaf ornament, and a mantle, the border of which is foliated. The shoes are diapered; the flowing hair is bound with a small coronet. face is much broken. In the front of the high tomb are two panels of pecu-The canopy above and liar tracery. behind the figure has been powdered with the plantagenista. The fact that one of Queen Philippa's children was interred in the Minster probably accounts for the gift of a richly embroidered bed belonging to her, which was made to the chapter either by the Queen herself or by Archbishop Thoresby.

On the S. side of the aisle is the monument, with effigy, of Abp. Savage (1501-1507)—a great builder at Cawood and at Scrooby, a courtier, and a passionate lover of field sports. The very rich mitre deserves notice. The frieze with angels bearing shields, and the hollowed recesses at the sides, indicate the lateness of the work. the next bay is the entrance to the crypt. In front stand two large copechests, said to have been brought from the Chapter-house. They are of the 14th cent., and the flowing ironwork with which they are covered should be compared with that of the Chapterhouse doors.

Beyond the transept, the arcade aisle and the Lady-chapel, Arch-

them at Thoresby's expense. These | lining the wall below the windows is nearly hidden by frightful monuments of the 17th and 18th cents. The first is that of Sir Henry Bellasis, without a date, but about 1630. Beyond are -Margaretta Byng, "Londoniensis; ter vidua, pia, honesta, proba," in very rich ruff and dress, kneeling before a desk: 1600. Sir William Ingram and wife, 1625; half figures, under a canopy, gilt and coloured. Sir William was "of the King's Council in the North." Charles Howard, Earl of Carlisle, died 1684; ambassador (1663-4) to Russia, Sweden, and Denmark. Admiral Medley, died 1757; with bust and weeping cherubs. Dr. Dealtry, died 1773, with a figure of Hygeia lamenting, and some edifying verses below. Sir George Savile, died 1784: a full-length by Fisher of York. Sir George represented the county of York in Parliament for 25 years, and this statue was erected by public subscription. Dr. Breary, Prebendary of York, died 1735, with an inscription recording his descent and connections; and Lionel Ingram, a boy of 2 vears old, son of Sir Arthur Ingram, with a remarkable Latin epitaph—a very good example of a small Jacobæan monument. At the end of the aisle, under the window, is the monument of Abp. Sterne (1664-1683). The Abp., robed and mitred, is under a canopy, looped up at the sides; very ugly cherubs support him. Sterne had been the chaplain of Abp. Laud, and attended him on the scaffold. He assisted Walton in the Polyglot Bible (published in 1657); and is one of those to whom the authorship of the 'Whole Duty of Man' has been attri-The Abp. was the greatgrandfather of Laurence Sterne, the novelist.

Adjoining is the plain tomb of Frances Cecil. Countess of Cumberland; died 1643.

XX. In the presbytery the monuments are—In the bay between the bishop Scrope (1398; beheaded, 1404. Scrope is the "Abp. of June 8. York " of Shakspeare's 'Henry IV.,' Parts I. and II. He had been indebted to Richard II. for all his preferments, and joined the Mowbravs, Percys, and others of great northern barons who rose in arms against Henry IV. in 1405. They were led to disband their forces by a stratagem of the Earl of Westmoreland; but the Abp. was seized and taken to the king at Pontefract. whence he was brought to Bishopthorpe, condemned in his own hall, and at once beheaded. See post, Bishopthorpe). This is a plain tomb, restored after the fire of 1829. was the indignation felt throughout Yorkshire at Scrope's "legalised murder." that his virtues (which were in truth not small—he was a man of letters, and of a "holy life") became magnified, in popular estimation, to an extraordinary degree, and his tomb here was sought by thousands as that of a saint. Offerings were made at it; and miracles were said to have occurred The offerings were forbidden by an order from the king, Henry IV.: and the officers of the Cathedral were directed to pull down the screen (clausure de charpenterie) which surrounded the monument, and to pile wood and stone over the tomb (between the pier and the E. wall), so as to prevent the access of the The order was not, however, people. strictly obeyed. Offerings continued to be made; and at the Reformation the treasures of St. Stephen's Chapel (adjoining the tomb on the N. side), in which they were deposited, were among the richest in the cathedral. The Scropes had their chantry there, and many of the Archbishop's ancestors had been interred in this chapel. At the same time with Archbishop Scrope were buried in the Minster (where is not known) Thomas Mowbray, Duke of Norfolk, and Sir John Lamplugh, both of whom were beheaded on the same charges.

Under the next bay, between the presbytery and the aisle, is the Cenotaph of Archbishop Markham (1777-1807), buried in the cloisters of Westminster Abbey. The top is a slab of black marble, inlaid with a cross and the inscription, "Equidem ego novi redemptorem meum vivere." At the sides are shields of arms.

The altar platform of the Ladychapel is raised on two steps. Under the E. window are:—(1.) Towards the N., Archbishop Accepted Frewen (1660-1664, the first Abp. after the Restoration. He was a member of a Sussex family, rejoicing in such puritanical names as "Thankful" and "Accepted"), in cap, rochet, and black gown. (2.) Against the wall, Frances Matthew, wife of Abp. Matthew, died 1629. She was the daughter of William Barlow, Bishop of Chichester; and one of four sisters, all of whom married bishops. (3.) Archbishop Sharpe (1691-1714), reclining, with a book in his left hand; below is a long inscription. In front, and projecting over the steps, are:-(1.) towards the N., Archbishop Rotherham (1480-1500), a perpendicular high tomb, with quatrefoils at the sides, and white marble drapery spread over the top. The tomb was restored after the fire by Lincoln College, Oxford, of which Archbishop Rotherham was the second founder. He had been translated to York from Lincoln, and died of the plague at his palace of Cawood. This Abp. was chancellor at the death of Edward IV., and was imprisoned by Richard III. for his devotion to the widowed queen and her children. He was afterwards restored to favour. (2.) The effigy of Abp. Tobias Matthew (died 1628), formerly on his tomb, which is under the second arch from the east, on the S. side of the presbytery. (3.) A monument with a floriated cross, and the bases of pillars which once supported a canopy. It has been attributed to Archbishop Sewal de Bovill (died 1258), but his tomb, there can be little doubt, remains in | on his side, in cap, rochet, and black

the great S. transent.

The most easterly bay, between the Lady-chapel and the S. aisle, is filled with the tomb and canopy of Archbishop Bowet (1407-1423-a great lover of hospitality. 80 tuns of claret were annually used in his household). Above the elliptical arch of the canopy, the sides of which are panelled, are three very rich tabernacles, with figures. The whole deserves attention, but has been much shattered.

In the next bay to the W. is the high tomb of Archbishop Tobias Matthew (1606-1628), with shields in the panels, and a black marble top, restored after the fire. Archbishop, who was famous for his wit and "cheerful sharpness" in discourse, was a special favourite with Elizabeth and James. Between this mont, and that of Abp. Markham is an altar-tomb, with the effigy, by Noble, of Abp. Musgrave (1847-1860).

XXI. In the south aisle, the monuments are: -At the east end, under the window, that of the Hon. Thos. Watson Wentworth (d. 1723), by Guelfi, of Rome. It displays figures of his son and widow. Against the S. wall is a grand and stately monument of William Wentworth, Earl of Strafford (b. 1626, d. 1695), son of the great Earl beheaded in 1641. Earl and his second wife. Henrietta de la Rochefoucauld, stand on either side of an altar. Below is Abp. Lamplugh (1688-1691); an upright figure in a niche, bearing the crosier. Lamplugh, the then Bp. of Exeter, hastened from that city to Whitehall on the news of the landing of William, after exhorting his clergy to remain faithful to King James. He was rewarded with the see of York, which had been two years vacant; but his loyalty to the Stuarts did not prevent him from officiating at the coronation of William. Abp.

gown. He was the second Matthew Hutton who became Abp. of York; both were members of the family of Hutton of Marske, near Richmond. The monument of Sir William Gee (1611), who is kneeling, with his two wives, is a good example of its time. Sir William was secretary to James I .. and one of his privy council.

On the choir side of the aisle, against one of the arches of the crypt. is the monument of Abp. Dolben (1683-1686); a reclining figure, robed and mitred. Before his ordination, in 1656, the future Abp. was active in arms on the side of the Royalists. He was standard-bearer at Marston Moor, and was severely wounded there, and afterwards during the defence of York.

W. of the iron grille, which crosses the aisle, are some very striking modern memorial tablets. (1.) For Major Oldfield, 5th Bengal Cavalry; Lieut.-Colonel Willoughby 6th Inniskillings; and those who perished with them in the Europa transport, burnt at sea, June 1, 1854. This displays a fine sculpture (part of the scene on board) in high relief, well arranged, and very striking. Executed by Phillip, from a design by G. G. Scott (2.) A monument to "perpetuate the remembrance of two members of this cathedral ch. departed to the mercy of God-William Mason, canon residentiary, and Vicar of Aston, whose poetry will be his most enduring monument: and his nephew, William H. Dixon, canon resid., and rector of Bishopthorpe (b. 1783, d. 1854)." monument, which is much enriched. is of worked brass, with knobs and fruitage of cornelians. On the top of the gable, supported by double shafts, is a figure of the Good Shepherd: at the sides are female figures, one with a cup, the other with a book. Exec. by Skidmore, of Coventry, from Scott's design. (3, 4, and 5.) Tablets Matthew Hutton (1747-1757) reclines | to the officers and men of the 33rd

Regt. who fell during the Russian war, 1854-56—to those of the 84th Regt. (York and Lancaster) who fell during the Indian Mutiny; and to those of the 51st who fell in the war with Burmah, 1852-53. (6.) A very good brass to the officers and men of the 19th Regt. (1st York N. Riding) who fell in the Crimean war. At the top is a figure of the Saviour with hands raised in benediction; at the sides are St. Michael, St George, Gideon, Joshua, Judas Maccabæus, and the Centurion. Exec. by Hardman, from Scott's design. The great superiority of these military memorials over most others of their class descrives especial notice.

XXII. The stained glass in the choir and its aisles is throughout Perpendicular. Before noticing the windows in detail it will be well to quote Mr. Winston's general observations.

"The earliest Perpendicular glass in the Cathedral is contained in the third window from the E. in the S. aisle of the choir; in the 3rd and 4th windows from the E., in the N. clerestory of the choir; and in the 4th clerestory window from the E., on the opposite side of the choir. These windows are of the close of the 14th cent. There is also an early Perpendicular Jesse in the 3rd window from the W. in the S. aisle of the The date of the E. window of the choir is well known; a contract for glazing it in 3 years was made in 1405. This window is one of the best executed that I have ever seen; the beauty of the figures, however, cannot be fully appreciated without inspecting them closely from the gallery near the window. The other windows of the choir aisles, eastward of the small eastern transepts, as well as the glass in the lancet windows on the E. side of the great Western transepts, appear to be likewise of the time of Henry IV. Some of these windows may probably be a few years earlier than the E. window.

All the rest of the glass in the choir is of the reigns of Henry V. and Henry VI.; the greater part belonging to the latter reign. The chief peculiarity that I have observed in these windows is that the white glass, which enters so largely into their composition, is, generally speaking, less green in tint than usual, especially in the western and southern parts of England. Mr. Browne has informed me that it clearly appears, from the Fabric Bolls, that this white glass is of English manufacture; which circumstance may perhaps serve to account for it whiteness."

The contract for glazing the great E. viudow, between the Dean and Chapter, and John Thornton, of Coventry, glazier, is dated Dec. 10, 1405.

The subjects in the upper division of the window, above the gallery, are from the Old Testament; beginning with the Creation, and ending with the death of Absalom. All below are from the book of Revelation: except those in the last or lowest tier, which are representations of kings The tracery lights are and bishops. filled with figures of prophets, kings, and saints, with angels in the uppermost divisions, below a small figure of the Saviour in judgment, at the apex of the window.

It has already been shown that the tracery of this superb window might have been completed long before 1405, when Thornton commenced his glazing. "The plan pursued in the carrying on of works of this description seems to have been to fill the windows with linen cloth, which gives a sufficient light, or with plain glass, until some benefactor could be found to furnish the glazing, or until it was convenient to employ funds for the purpose."—Willis.

The stained glass in the North aisle, E. of the small transept, is of the time of Henry IV. The E. window of the aisle has, in the upper part, the Crucifixion, with St. John and the Blessed Virgin, and a figure of St.

James below, with other subjects at | fine figure of Edward III. the sides. The St. James seems to have belonged originally to another window. The magnificent window of the small transept dates probably from the reign of Henry V. (1413-1422). It contains subjects from the life of St. William of York and representations of miracles attributed to his intercession. The windows westward of this are of somewhat later date. They seem to have been given by Thomas Parker, Canon of York, circ. 1423; in the border of this window are repeated the words Thomas Parker, with a hound collared between them—this must have been his badge; -by Robert Wolveden, Treasurer of York, who d. in 1432-3, leaving 201. to the fabric,—his name is repeated in the borders;—and by Abp. Bowet (d. 1423), whose name and arms occur

repeatedly in the glass. In the South aisle, the E. window is temp. Henry IV. The subjects (from the life of a saint) are not easily interpreted. In the upper part of the central light is the figure of an Apostle, apparently of the same date and character as the figure of St. James in the opposite window. The window adjoining this, S., has been filled with * "a very beautiful glasspainting, of the last half of the 16th century. It was presented to the cathedral by Lord Carlisle in 1804, and was brought from a ch. at Rouen" (the ch. of St. Nicholas). "The design (the Salutation of Mary and Elisabeth) is evidently taken from a painting, I believe by Baroccio (who d. in 1612, aged 84), but the colouring and execution have been varied to suit the nature of the material employed. I infer from the columnlike arrangement of the groups, as well as the actual division lines of the glass, that this work was originally painted for a four-light window."-The superb colouring of Winston. this window deserves especial notice. The third window from the E. in this

The transept window was probably the gift of the executors of Thomas Longley, Bp. of Durham (d. 1437). It displays subjects from the life and miracles of St. Cuthbert, and figures of the principal members of the House of Lancaster. The next window (with a tree of Jesse) is earlier, and no doubt dates from before the end of the 14th cent. The two remaining windows, one with designs from the life of the Virgin, the other with grand single figures under canopies, are perhaps temp. Henry VI.

In the clerestory windows of the choir, the earliest glass is in the 3rd and 4th from the E., on the N. side, and in the 4th from the E., opposite. This is of the end of the 14th century.

The rest is later.

XXIII. The Crypt is entered from the upper part of the choir aisles. Before the fire of 1829 the only crypt that was known to exist occupied one compartment and a half of the middle aisle, under the high altar. This was apparently Norm., with some Perp. restorations and additions. The repairs consequent on the fire showed that "the pillars and lower parts of the walls of another crypt exof the tended under the whole western part of the choir and its side Also that the crypt above mentioned, which had been so long known, was in fact a mere piece of patchwork, made up during the fitting up of the choir in the 14th cent., out of the old materials, to support a platform for the altar, and provide chapels and altar-rooms beneath it."-

This original crypt had been filled up with earth, which was removed, so that the whole may now be examined. It is of late Norm. character, and seems to have formed 4 aisles, the outer ones resting on low cylinder piers, grooved in spirals, like those of Durham, and 2 smaller piers inside. aisle is of earlier date, and contains a Toward the E. it opens N. and S. into a projecting building, "a kind of eastern | transept, but which from the greater thickness of its walls was evidently a tower." This crypt was no doubt the work of Abp. Roger (1154-1181), who built the Norm. choir, which was pulled down when that which now exists was constructed. As at Canterbury. the general design of which cathedral seems to have been closely imitated by Roger, this crypt was entered from its aisles, at the western end of which appears a portion of a vestibule, and of an enriched Norm. portal. joining this portal is a low arch, and a portion of an apse; both of earlier date than Roger's work, and belonging to the first Norm. cathedral of Abp. Thomas (1071-1100). The apse proves that the transents of the first Norm. ch. terminated in this form eastward.

The central part of the extreme western portion of this crypt had apparently been filled with earth ever since its first construction by Abp. Roger. It is enclosed by a massive wall, 3 ft. 6 in. in thickness. This is of Roger's time. Within it is a wall, "apparently of great antiquity, 4 ft. 8 in. thick; and on the inner side a third wall, which lines the latter, and is 2 ft. thick. The middle wall is faced with herring-bone work, and of course workmanship, and has evidently belonged to one of the early structures, possibly to the Sax. ch.... The inner thin wall is partly constructed of old materials, apparently derived from some part of the ch. that was pulled down to make way for the new crypt."-Willis. It probably served as a foundation for the timber-work of the stalls in the choir above. The middle wall will be regarded with very great interest, if, as is not impossible, it formed part of the stone ch. built by King Edwin. At any rate it marks the exact site of this ch., even if we admit that the work of Edwin was replaced by a more elaborate structure by Abp. Albert in the 10th cent.

The earth which filled the enclosure

made by these walls was removed after 1829. The workmen left, however, a slab of stone, about 5 ft. higher than the level of the pavement of the crypt, and 3 steps, which they found a little to the E. of this slab. These have been regarded as an altar and the ascent to it. But Professor Willis conjectures that "this was the stair which led to the small crypt or 'confession' of the Saxon chancel."

XXIV. The Central Tower of the first Norm, cathedral seems to have remained in its original state, at least as high as the roof, after the construction of the E. E. transepts. treasurer, John le Romain, who built the N. transept, is said also to have built the campanile, or bell-tower. This no doubt refers to the central tower: but Le Romain's work was in all probability above the roof. The core of the existing piers is Norm.; and Norm. ashlaring remains on the N.W. pier, in the parts above the vault of the nave aisle. These Norm. piers were cased with Decorated or Perp. masonry as the works of the nave and choir advanced to them; the western faces of the piers toward the nave first receiving their casing, and the eastern of those toward the choir. After the completion of both nave and choir, the casing of the piers was also completed; and in 1409 Thomas de Haxey was appointed supervisor of the work of the fourth pier; a proof that the three others had already been finished. The lantern or upper part of the tower above the piers was still in progress in 1421, when a temporary roof was set up, and the stonework was not completed in 1447. In 1471 the permanent roof was preparing, and was complete in 1472, when the charges for painting it are recorded.

The four great arches of the tower, with their huge piers and capitals of leafage, are magnificent. Above them runs a stringcourse with projecting angel brackets. An enriched wall arcade, with a parapet, intervenes between the main arches and the lofty Perp. windows, two in each face. The vault of the lantern, 180 ft. from the pavement, is a rich lierne. The effect of the whole, it has been well said, is "beyond all praise."

In the windows of the lantern are some portions of the original glass, displaying, among other devices, the

cross keys of the chapter.

The tower should be ascended for the sake of the riew, which is very fine and extensive. A large part of the country is commanded, and the dome of Castle Howard is a marked feature in the landscape; whilst the streams that unite to form the Ouse may be traced almost to their sources in Craven.

The completion of the central tower terminated the great series of works which had replaced the Norm. cathedral by the gigantic building which now exists. The church was accordingly reconsecrated, July 3, 1472.

XXV. A work of no small importance, however, was completed after this date. This was the Rood or Choir screen, the construction of which may be safely placed between the years 1475 and 1505. "William Hyndeley was the master-mason, having two others under him. Six carpenters were employed, and received 11l. 16s. 4d. The sum of 27s. 81d. was paid to the sawyers, and 96s. 4d. to the labourers, of whom there were but three."—Raine's Fabric Rolls. Among the decorations of the screen occurs Hyndeley's device—a hind lodged, or lying.

The screen consists of 15 compartments, 7 on the N. and 8 on the S. of the central portal. The compartments are divided by buttresses, and in each is a lofty pedestal, supporting a lifesized statue of a king of England, the series ending with Henry VI. Above is a superb mass of tabernacle work, enriched with small figures; and the

screen is finished by a very rich parapet. The portal is in 4 orders, surmounted by an ogeed pediment.

The fine statues of the kings deserve

special notice.

The screen, rich and beautiful as it is, is perhaps too massive, and certainly does not improve the effect of the transept. Its removal, however, which was threatened during the repairs after the fire of 1829, is entirely to be deprecated.

XXVI. The ancient Organ was destroyed in 1829. In 1832 an organ built by Elliot and Hill, from the design of Dr. Camidge, the organist, was presented to the Cathedral by the Earl of Scarborough, who was one of the Prebendaries of York. This organ cost 3000l. In 1859 it underwent considerable alteration, at a cost of more than 1300l., by Messrs. Hill and Son. It has now 69 stops and 4260 pipes.

XXVII. On the south side of the choir are the Record Room, Vestry, and Treasury. The Record Room, which is fitted with presses, and contains the valuable series of Registers, Fabric Rolls, and other documents relating to the Cathedral, formed part of a chantry founded by Archbishop Zouch about 1350; but rebuilt about the year 1396, so as to bring it into uniformity with the new choir. At its S.W. angle is a draw-well, called "St. Peter's well."

The vestry and treasury were rebuilt twenty years before Archbp. Zouch's chantry. In the vestry are preserved some antiquities of very great interest: they include the Horn of Ulphus, made of an elephant's tusk, and dating from a period shortly before the Conquest: when Ulph, the son of Thorald, the lord of great part of eastern Yorkshire, laid this horn on the altar in token that he bestowed certain lands on the church of St. Peter. Among these lands was Godmundham, near Market Weighton, the site of

the great pagan temple which was I profaned by Coifi, the high priest, after his conversion by St. Paulinus. The horn is encircled about the mouth by a belt of carving, representing griffins, a unicorn, a lion devouring a doe, and dogs wearing collars. The griffins stand on either side of a tree. which at once recalls the conventional sacred tree of Assyrian sculpture. This famous horn disappeared during the civil war; but came into the hands of the Lords Fairfax, one of whom restored it to the church. Its golden ornaments had been removed; but a silver-gilt chain and bands were attached to it by the Chapter in 1675. -A magnificent oak chest, carved with the story of St. George, dating early in the 15th century.—A silver pastoral staff, six feet long, taken, in 1688, from James Smith, titular Bishop of Callipolis, by the Earl of Danby. - The Pope had made Smith his Vicar Apostolic for the northern district, and he was soon pounced upon." The staff is said to have been wrested from the hand of Bishop Smith, when walking in procession to his "Cathedral Church."-The Mazer bowl, or "Indulgence Cup of Abp. Scrope." This is a bowl of dark brown wood, with a silver rim, and three silver cherubs' heads, serving as feet. Round the rim is the inscription, "Recharde arche beschope Scrope grantis on to alle the that drinkis of this cope xl dayis to pardune, Robart Gubsune Beschope musm grantis in same forme afore saide xl dayis to pardune, Robart Strensalle." The cup seems to have originally been given by Agnes Wyman, wife of Henry Wyman, Mayor of York, to the Corpus Christi No similar instance of an episcopal consecration of such a cup is known. The Corpus Christi Guild of York was dissolved in 1547; and the cup passed afterwards to the Cordwainers, whose arms appear at the bottom of it. Their association was dissolved in 1808; and the bowl was presented to the Minster by Mr.

Hornby, who had become its proprietor. The word "musm" (musin?) perhaps refers to Richard Messing (Latinised Mesinus), Bp. of Dromore in 1408, and for some time suffragan of York.—Three silver chalices with patens, taken from the tombs of abps.—The rings of Abps. Greenfield, Sewall, and Bowet, from their tombs.—An ancient "coronation chair," apparently of the 15th cent.

At the S.E. angle of the nave is an apartment called the Record Room, and used as a Will Office.

XXVIII. Passing out of the Minster by the south transept, the exterior of which has already been described, we proceed along the south side of the nave. The bays are separated by lofty buttresses, rising high above the aisle roof. The buttresses rise above the aisle roof in three stages. In the lowest is a canopied niche containing a figure; and from the second, terminating in three gables, rises the lofty pinnacle of the third.

The enriched buttresses produce the chief effect on this side of the Minster. It may here be said that the fantastic gurgoyles which are so conspicuous, are more numerous in the later work of York Cathedral than in any other English church of the same rank, and form one of the special characteristics of its exterior.

The Central Tower, the date of the completion of which has already been given, is well seen from this side. It is 65 ft. square, and the largest in England—Winchester, which comes next, being only 62. The gurgoyles projecting from its buttresses,—winged bat-shaped demons.—seem as if expelled from the holy building by the sounds of the choir below.

XXIX. The West Front admits of being well seen from the open space in front of it, happily cleared of small buildings.

This famous façade fully deserves its reputation. It may truly be said

that the west front of York is more architecturally perfect, as a composition and in its details, than that of any other English cathedral. It consists of a centre, flanked by two lofty towers, forming the terminations of the aisles. The towers are divided from the nave by very deep buttresses, which occur again at the exterior angles. The lower part of this front, including the three portals, and the two lower windows in the towers, which light the aisles, is of early Decorated character. All above, as high as the roof, is later curvilinear. and is probably of the time of Abp. Melton (1317-1340). The towers, above the roof, are Perp. The S.W. tower had been begun in 1433, and was still unfinished in 1447. It was probably completed before the death, in 1457, of John Bernyngham, treasurer of York for 25 years, whose name appears on it, and by whose exertions it was erected. The N.W. tower was not carried on until about 1470.

The central doorway has an outer arch of many orders, greatly enriched, and subdivided by a central shaft into two lesser, foliated arches, in the tympanum above which is a circle filled with tracery. The history of Adam and Eve appears in the mouldings of the principal arch, and the minute foliage of its ornamentation deserves special notice. A crocketed pediment rises above the sill of the great west window; and the space between the portal and the buttresses has a double series of enriched niches. In a niche within the pediment is the figure of an archbishop, either that of John Romanus, who commenced the nave, or of William de Melton, under whom the west front was completed. either side, in niches beyond the pediment, are the mailed figures of Percy and Vavasour, the traditional donors of the wood and stone for the Minster, with their shields of arms adjoining. One of these figures bears a block of wrought stone—the other, what may be either an unwrought stone or a block of timber. Over the portal is the great west window, with an enriched pediment above it, rising into the gable. The gable itself is battlemented, and is crowned with a rich finial.

The buttresses are much enriched with niches and panelling. Figures of saints remain in the upper niches: and in the two lowest, N. and S., is some sculpture which has so nearly perished, that the subjects are not easily decipherable. That of one appears to be the Flight into Egypt. The great depth of these buttresses is

especially striking.

The towers are 201 ft, from the ground. Their windows, above the roof, are completely Perp. Each tower is crowned by a rich battlement, with The fire of 1840 greatly pinnacles. injured the S.W. tower, in which it commenced; and some of the delicate stonework of the exterior has been renewed in consequence. The bells in this tower were destroyed. A new peal, 12 in number, was placed in it in 1843, when Dr. Beckwith bequeathed 2000l. for this purpose. A monster bell, the largest at present in England. was hung in the N.W. tower in 1845. Its height is 7 ft. 2 in., its diameter 8 ft. 4 in., and its weight 10 tons 15 cwt. It was cast by Messrs. Mears, of London, at a cost of 2000l., raised by the inhabitants of York. Like other great bells, it is not rung, but struck with a hammer.

XXX. The N. side of the nave is far less enriched than the S.; and the plain buttresses do not rise above the parapet of the aisle. This side was concealed by the Abp.'s palace. Towards the W. end was the chapel of the Holy Sepulchre, founded by Abp. Roger.

The exterior of the N. transept should be especially noticed. Its N. front is one of the most remarkable features of the Minster; and has been pronounced, with some justice, "the most noble E. E. composition in the kingdom." An arcade covers the wall below the "Five Sisters;" and on either side of the five lancets above, is a blind arch, filling up the gable. The vestibule of the Chapter-house covers the E. transept aisle, and thereby deprives the composition of its proper balance; but the grand simple lines of the front call for the highest admiration.

The Chapter-house, with its vestibule, projects beyond the transent. Each bay of the former is divided by a short flying buttress which deserves attention. It is solid to the height of 49 ft.; then has an arch of a flying buttress, and is again joined towards the top by a flat panelling. The buttress terminates above the wall in a spire, with finial of leafage. these details, and the windows, are of early Decorated character. But among the many grotesque gurgoyles which project from the buttresses and from the vestibule, occur several bears, which have been regarded as the device of Francis Fitzurse, who became treasurer of the Minster in 1335. If this supposition be correct, it must have been some time after this date that the Chapter-house was completed.

The view E. of the Chapter-house is a very fine one. The choir with its short transept, the central tower, and the Chapter-house, full of varied lines and intersections, produce a most picturesque and striking group. The four bays E. of the small transept belong to the earlier period (1361-1373); the transept itself and the four western bays, to the later (1380-1405). The most marked difference between these portions is in the arrangement of the triforium passage, which, in the presbytery (E. of the transepts), is outside instead of, as usual, inside the building. The passage is between the clerestory windows and a remarkable open screen, "in composition a square-headed window

of three lights, cinquefoiled in the head, and once transomed." The lofty transept window should also be noticed. Many gurgoyles—apes, dragons, and bat-like demons—project from the main buttresses. The buttresses at the sides of the transept terminate in straight shafts pierced by projecting gurgoyles; the straight line repeating the character of the outer screen of the clerestory.

XXXI. The E. end of the choir is only second, as a composition, to the W. front. The great Eastern window forms the centre, crowned by an ogeed dripstone, rising into a lofty finial far above the parapet. Between the dripstone and the apex of the window is the figure of an Abp., probably Thoresby, under whom the presbytery was completed. massive buttresses on either side are enriched with niches and panel-work, and rise into lofty pinnacles of great beauty. The panelling is continued along the space between the window and the buttresses, and rises above the roof so as to form an open parapet, much enriched. The buttresses which flank the aisles are also capped with lofty pinnacles. Under the sill of the great window is a row of sculptured busts, representing the Saviour with his Apostles; a crowned head (Edw. III.) at the N.; and a bishop (Thoresby) at the S. end.

The best point for examining the E. front is about halfway down the opening before it, near the gateway of St. William's College.

The S. side of the choir resembles the N. The two parapets, however, with the finials of the aisle windows, were not added until 1743, when they were supplied chiefly by the liberality of the Dean, Richard Andrew.

XXXII. Abp. Roger (1154-1181), besides rebuilding the choir of his cathedral, erected the archiepiscopal palace on the N. side, of which the only remaining portions are—the

Yorkshire.

fragment of a cloister on the N. side of the precincts, in which a wide circular arch encloses two smaller, with trefoil headings; and the building now used as the Chapter Library, but originally, in all probability, the chapel of the Abp.'s palace. At the W. end are five lancets under a circular arch, showing the transitional character of Roger's work.

The Library of the Chapter is, two days in the week, open to the public. who may take books from it on payment of a small annual subscription. There are about 8000 vols.; some of which are of great rarity and interest. Among the MSS, are—two York Breviaries:- 'Tractatus Varii Patrum,' with Ailred of Rievaulx 'de Bello Standardi' at the end-the book. which is of the 13th cent., belonged to Rievaulx: 'Speculum Spiritualium' —from the Carthusian Priory of Mount Grace, near Arncliffe; the 'Sentences' of Peter Lombard (14th cent.), from St. Mary's of York; Book of Psalms, with Glossary (13th cent.); some Bibles, one of great beauty, temp. Edw. I., with small miniatured capitals; MSS. of Cicero (11th and 12th cents.); and a MS. vol. by Gray the poet, containing poems and notes on the history of English poetry, &c. Among the printed books are many Caxtons, Wynkyn de Wordes, and Pynsons. The historical collections are good, embracing Bouquet, Pertz, Muratori, and a complete set of English printed chronicles, including the Master of the Rolls' series. Some books and MSS. of special interest are arranged in glazed cases. A case of autographs includes one assigned to Tasso, and (it consists of 4 Latin verses) is written in a book (Discorso della virtù heroica) given by him to the 'ornatissimus Doctor Matthæus,' afterwards (1606-1628) Archbp. of York. There is a case of very fine stamped bindings, and another of early printed books and MSS .- in which is perhaps the finest book in England—a copy

on vellum of Erasmus's New Testament, 2 vols. 1518, probably that prepared by Frobenius the printer for Erasmus himself. Here is also John Eliot's Indian Bible, printed in Cambridge; and among the MSS. a very remarkable book of the Gospels of the later (?) Saxon period, on which the various officers of York Cathedral took their oaths from the Conquest to the reign of Elizabeth.

Near the W. front of the Minster, is the R. C. "Pro-Cathedral," ded. to St. Wilfrid (Goldie, architect). It was completed in 1864, and contains some elaborate carving and good stained glass. The tower groups at a distance with those of the Minster.

The Churches in York, which may best be described here (although the tourist who is pressed for time should make his way direct from the Minster to St. Mary's Abbey, see post), although none are of great size, are nearly all interesting, and present some architectural peculiarities. Before the Reformation their number was 45: there are now only 24. Light and space were not easily procured within the closely-packed city, and the greater part of these churches are small, with large windows, high in the walls or in the clerestories, so as to catch the light above the surrounding houses. Many, like the Cathedral, are wonderfully rich in stained glass. Of these the most important are-All Saints', North Street; St. Denis, Walmgate; Holy Trinity, Goodram-gate; St. Martin-le-Grand, Coney Street; and St. Michael-le-Belfry, in the Minster Yard. None of these churches should be missed by the archæologist; who should also visit St. margaret, Walmgate; St. Mary, Bishop Hill, Junior; and St. Mary, Castlegate. Starting from the Cathedral, the churches may be briefly described in order. The most important are marked with an asterisk.

* St. Michael-le-Belfry, late Perp., begun 1525, finished about 1536. (See Fabric Rolls of Minster.) The old ch. was pulled down by order of the Chapter, and the present built most probably from the spare stores of the Minster. There is no separation of the chancel. The bell-cot on the W. gable, boldly corbelled out, should be noticed. The buttresses are pierced by gurgoyles, like those of the Minster eastern transepts. The stained glass is temp. Henry VIII., but is much confused and mutilated. In the E. window are the Annunciation, Nativity, and Resurrection of our Lord. The other windows contain figures of saints. At the end of the S. side is a wonderful monument for Robert Squire and Priscilla his wife, full-length figures, standing by alters from which flames are rising. Thomas Gent, the printer and historian, who d. in 1778, was buried in this ch., but has no monument.

* Holy Trinity, Goodramgate. Dec. with Perp. portions, and a plain Perp. tower. The aisle windows are squareheaded. Dec. On the S. side is a Dec. The E. window contains chantry. some fine Perp. glass (circ. 1470). The larger subjects are—St. George, St. John the Baptist, the Holy Trinity, St. John the Evangelist, and St. The smaller are—the Christopher. Holy Family, St. Joachim, St. Anne, the Virgin and Child, 3 crowned kings, for the Holy Trinity, the Virgin seated in front, St. Zachary, St. Elisabeth and the Baptist, and St. Ursula and her companions. There are some good fragments of Perp. glass in the other windows. On the E. side of Goodramgate is a small Dec. chapel, belonging to the "College of Vicars Choral," but of little interest. Close to the city wall, between Monk Bar and Merchant Taylors' Hall, is the site of St. Helen's on the Walls, one of the churches abandoned at the Reformation. In a vault beneath it the tomb of Constantius Chlorus (father of Constantine the Great) was said to have been found; and an urn, supposed to contain his ashes, was preserved in the ch. The small ch. of St. Maurice, beyond Monk Bar, has a Trans. W. window, well showing the approaching change from Norm. to E. E. Holy Trinity, or Christ Church, at the end of Collier Gate, may perhaps mark the site of the first Christian ch. in York. It stands in what is called "King's Court," a name which has been thought to indicate the position of the Imperial Palace within Roman Eboracum. York had no doubt possessed a Christian ch. before the arrival of Paulinus; and it was probably within the enclosure of The present ch. (almost the Palace. entirely rebuilt) is of little interest. The S. door is Dec. with a niche on each side, "a very elegant composition."

St. Saviour's, in St. Saviour's Gate has been restored. It is mainly Perp Some Perp. glass remains in the E. window.

St. Cuthbert's, Peaseholm Green, is late Perp. with a good open timber roof.

* St. Denis, Walmgate, consists of chancel and aisles; the nave was The S. doorway destroyed in 1798. is rich Norm., removed from the nave, and built up without the shafts in its present situation. The tower arches are Norm. (the tower itself modern). The N. aisle is Trans. Norm., the S. arch Perp., and the E. window Dec., "with very uncommon tracery of flowing character, which seems to be an imitation of the great W. window of the cathedral."—J. H. P. other windows in this aisle are Dec. The S. aisle has a Perp. E. window, the rest Dec. The great E. window is Perp. The stained glass in the E. window is Perp., with two shields of the Scropes, and figures of saints. In the E. window of the N. aisle is

part of a tree of Jesse (Dec.). The I tached to it by a chain. In this ch. two adjoining windows contain "some fine specimens of early Dec. glass." In the first, Christ in the Garden, and St. Thomas. There are also some curious quarrels painted with butter-In the second, St. Margaret, and the Virgin and Child. The glass in the third window has Dec. portions mixed with Perp. The rest of the glass here is entirely Perp. In the N. aisle many of the Percys were interred; and a large blue stone is said to mark the resting-place of Henry Percy, the Earl of Northumberland, who fell in the battle of Towton. March 29, 1460. (See Rte. 43.) "Percy's Inn," the old palace of the Earls, stood nearly opposite this church.

* St. Margaret's, Walmgate, deserves a visit for the sake of its very rich Norm. porch and doorway. "Round the arch of the doorway are the 12 signs of the Zodiac, with an ornament supposed to be a thirteenth month, according to the Saxon Calendar, which continued in general use in England long after the Norm. Conquest. Between the signs are small groups of figures in panels, representing some characteristic emblem for each month."—J. H. P.

St. Lawrence, beyond Walmgate Bar, has also an enriched Norm. doorway, and the Norm. plinth remains all round the church except in the tower. The ch. above the plinth was rebuilt in the Perp. period.

Returning up Walmgate, we pass through Fossgate to the Pavement. St. Crux, Pavement, is Dec. and Perp., with a tower built of brick by Sir Christopher Wren in 1697. The windows are Perp., the piers Dec. without caps; "and the section being different from that of the arches, the impost offers a curious example of the crossing or interpenetration of mouldings." In the chancel is an early Perp.

is buried Sir Thomas Herbert, who was in close attendance on Charles I. during the last two years of his life. and was with him on the scaffold. Herbert's account of the king's last days is the most minute and interesting we possess. He was b. in York. and d. here, March 1, 1681-2. Before the breaking out of the rebellion he had travelled much in Asia and parts Percy, Earl of Northof Africa. umberland, who was beheaded in the Pavement (1572) for his share in the rebellion against Elizabeth, known as the "Rising in the North," is also interred here.

* All Saint's, Pavement, a Perp. ch., which has been much injured. the chancel destroyed, and the other walls rebuilt, is remarkable for its very graceful octagonal lantern at the W. end, which has been also rebuilt, but after the old design. It greatly resembles the lantern on the ch. of St. Maclou at Rouen. Camden asserts that a beacon (cresset) was lighted nightly on this ch. to guide travellers through the forest of Galtres, which anciently closed up round the walls of York. The pulpit dates 1634, and there is a very good scutcheon on the N. door.

The little ch. of St. Sampson, in St. Sampson's Square, has been rebuilt, but is interesting from its dedi-St. Sampson, according to Matthew of Westminster, was the first Abp. of York, to which see he was appointed by King Lucius. and Abp. are alike shadowy.

*St. Helen's, Stonegate, is dedicated to the Empress Helena, mother of Constantine the Great, who, according to one tradition (see ante), was born in Eboracum. The ch., chiefly Dec., has been restored. octagon lantern at the W. end is very striking. The arches spring from octagonal pillars, which, "instead of wooden lectern, with the Bible at- the usual moulded caps, have corbels

on the N. and S. sides, carrying the outer arch. This practice of using corbels instead of caps is unusual, but seems to be a provincialism, as it recurs in several other churches in York."—J. H. P. The font is Norm. on a Dec. base. Some original Dec. glass remains in the E. window.

* St. Martin's, Coney Street, is late Perp., and has been restored. Robert Semar, vicar of this ch., left by will (1443) a large portion of his estate to the fabric, if the parishioners would build it anew within 7 years. buttresses, slender, and pierced with gurgoyles, are characteristic of York Perp. work, and resemble those of the Minster (lesser transepts), St. Michaelle-Belfry, and All Saints, Pavement. Within, the bosses of the painted roof, and the large clerestory window, should be noticed, but the chief feature is the stained glass, which is The W. window, dated very rich. 1447, is a memorial of Robert Semar, and much of his legacy must have been used for it. It contains events from the life of St. Martin, with the heavenly hierarchy in the tracery. The other windows of the S. aisle and the clerestory contain figures of saints, shields of arms, &c., all Perp. (circ. 1450) and all worth notice. In the third window of the S. clerestory are the 4 doctors of the Church, St. Ambrose, St. Augustine, St. Jerome, and St. Gregory. The great E. window, long plainly glazed, now contains stained glass by Heaton and Butler.

St. Michael's, Spurrier Gate, is plain Perp., with some good Perp. glass in the windows. The altar-covering is of stamped leather, temp. Charles II.

*St. Mary, Castlegate (restored by the Dean of York, 1870), has a fine Perp. tower and spire; the lower story square, the second, on which rests the spire, octagonal. The N. side of the nave is Trans.-Norm.; the piers on the S. side were rebuilt in the Perp.

period. Within, the tower has arches opening to the aisles N. and S., as well as that E. to the nave. This is a peculiarity frequent in Yorkshire The S. doorway is E. E. churches. The windows are Dec. and Perp. (One in the N. aisle has floriated tracery.) Under the windows of the N. aisle are some arches which, it has been suggested, may have been places of sepulture for benefactors. the chancel pier of the N. aisle, and protected by glass, is a stone with an inscription, partly Latin, partly A. Saxon, recording the dedication of a ch. on this site. There is no date; but the inscription must be of the period between 1000-1040. The choir is Perp., with narrow arches on each side opening to the ends of the aisles: under the arches are flat Perp. tombs. There is some old glass in the E. window of the S. aisle. The E. window of the chancel was given by the parishioners in 1870. The glass is parishioners in 1870. Hardman's—the principal subject the Nativity. The colour is rich and fine, and the window adds greatly to the effect of the view from the W. end The font is temp. Charles II. The altar-covering is of stamped leather, red and gold flock, and is possibly Flemish work of the 17th cent.

Crossing the river, we first reach St. John's, Micklegate; a poor Perp. church (the arches may be E. E.) of little interest. There is some stained glass, late Dec. and Perp.

* All Saints', North Street, is one of the most interesting churches in York. The outer walls and windows are chiefly Perp. The pillars, arches, S. doorway, and font, are E. E. The tower, which is octagonal, with buttresses up the alternate flat faces instead of at the angles, and a lofty spire, is Perp. The E. windows of chancel and aisles are Dec. The E. E. pillars on the N. side are alternately round and octagonal; and many of the latter have a peculiar capital,

which seems a Yorkshire provincialism. The stained glass in this church is of great beauty, in spite of restoration and addition. The E. window (15th cent.) has, above, the Virgin and St. Anne, the Baptist, and St. Christopher. Beneath, in the centre, is the Holy Trinity. On the S. side is Nicholas Blakeburn, Mayor of York in 1413, and wife. On the N., Nicholas Blakeburn, the younger, sheriff of York in 1428, and mayor in 1429, with his wife. These figures are kneeling, and have labels with passages from the penitential psalins; below are shields with the letter B. The Blakeburns were no doubt the donors of this window. The glass in The E. winthe tracery is modern. dow of the N. aisle is earlier, but still of the 15th cent. The subjects are from the life of our Lord, with the This glass Coronation of the Virgin. has been much "renovated." The E. window of the S. aisle has much modern glass inserted, but there are some good Dec. fragments. The subjects are-the Virgin, Christ in the Garden, the Crucifixion, and figures of saints. The first window from the E., in the N. aisle, is known as the "Bede" window, not because it represents the events of the fifteen days preceding the Last Judgment-which St. Jerome describes, but Bede does not-but because the window itself was an offering, and contained a prayer (bede) for the donors. In the tracery is the reception of the blessed into heaven, and the dismission of the wicked. The 15 divisions below, with their legends, are as follows:-(1st day) An extraordinary inundation of the sea—legend gone; (2nd) The sea ebbs-"The seconde day ye see sall be so lowe as all men sall yt see;" (3rd) It returns to its ordinary level -"Ye iii daye yt sall be playne and stande as yt was agayne;" (4th) Fishes and sea monsters come upon the earth—"Ye iv. daye ye fisches sall "—the rest obliterated; (5th) The

bryn, and all ye waters y' may ryn;' (6th) Trees on fire; fruit dropping off-legend nearly gone; (7th) Earthquake-" Ye sevent daye howses mon fall, Castels and towres and ilka wall;" (8th) Rocks consumed-" Ye viii daye ye rockes and stanes sall bryn togedyr all at anes;" (9th) Men hide in holes of the earth-legend nearly gone; (10th) Only earth and sky to be seen-"Ye tende daye for (before) even Erthe sall be playne and even;" (11th) Men and women. and a priest, looking out of holes in prayer-"Ye xi. daye sall men come owte of their holes and wende about;" (12th) Three coffins full of bones-"Ye xii dave sall banes dede in (?) Be somen sett, and at anes ryse all: (13th) Stars fell from heaven—"Ye thirtende daye suth sall sterres and ye heven fall;" (14th) A bed with a man and woman dead, Death at the foot with a spear, mourners at the side-" Ye xiv. daye all yat lives you (then), sall dy, bathe childe, man, and woman;" (15th) End of all things-"Ye xv. day yat sall betyde ye werlde sal bryn on ilka syde." (All these lines are taken from the 'Prick of Conscience,' an English poem by Richard of Hampole, sæc. xiv. For this "Hermit of Hampole" see p. 9.) At the bottom of the window are figures in prayer, probably the donors. The glass was "restored" in 1861. The next window westward has Dec. glass, representing six works of mercy: and the third Perp. glass, with three large figures. In the S. aisle, the first window westward has St. John the Evangelist and an archbishop. This glass is Perp., as is that in the adjoining window, showing the remains of a stately procession. The 3rd window is also Perp. There are many Roman bricks in the wall of this church; and let into its S. wall is a Roman sepulchral tablet of no great importance.

sall "—the rest obliterated; (5th) The | St. Mary, Bishop Hill, the elder, see on fire—"Ye fift daye ye see sall has some good E. E. and Dec. work;

but it is of no special interest. *St. Mary, Bishop Hill, the younger, has a remarkable tower, which is probably Saxon. There is herring-bone work among the masonry, and the belfry windows are rude, with circular arches. a central shaft, and long and short work in the jambs. It is probably a Saxon tower, built of Roman stones, but patched in more recent times, and has been knocked about a good deal. Stones with Norm, sculpture on them are used as old materials in the interior: "and on the exterior, but built into the walls, are many bricks of the shape of the modern or Flemish bricks, a form not used before the 13th cent."--J. H. P. "The two arches on the S. side of the nave are very curious. They are nearly straightsided, with bold Dec. mouldings, and of very wide span, while the two responds and central pillar are Norm. On the N. side are two Norm. arches." -J. H. P. The chancel has been rebuilt of old materials. The E. and several of the side windows are Dec. The name "Bishop Hill" is of uncertain origin. It is the highest ground within the city; and it has been suggested that it may have been the hill on which the first bishop who visited Eboracum set up his tent, and which was afterwards crowned by a Christian temple. *St. Martin's cum Gregory, Micklegate, has an E. E. nave with Perp. clerestory, a Perp. chancel, and some Dec. windows. Some very fine Dec. glass (mutilated) remains in the windows of the S. aisle, and in the E. window of the "There are some singular N. aisle. and beautiful borders and quarries in this church."—J. B. There are traces of a crypt; and in the W. wall is a rude piece of Roman sculpture. In the N. wall is built in a child's gravestone of the 16th cent. with an incised cross. Holy Trinity in Micklegate has some E. E portions; but the aisles and chancel have been destroyed. It is chiefly interesting as having been the church of a Benedictine Priory, attached to the great abbey of Marmoutier (majus monasterium) near Tours. There had been a church of secular canons on this site before the Conquest; and Ralph Paganel gave it to Marmoutier in 1089. (The history of the priory has been traced in a most elaborate paper by Mr. Stapleton, in the York vol. of the Institute.) An E. E. gateway, the only fragment of the priory remaining, has been removed.

The second point of interest in York is St. Mary's Abbey, in the garden and grounds of the Yorkshire Philosophical Society, on the l. bank of the Ouse, about 5 min.'s walk from the Minster, and a little further from the rly. stat. Entrance l. after crossing Lendal Bridge. If not introduced by a member, the charge for admission is 1s. The very pleasant and well-kept gardens include not only the remains of **ST. MARY'S ABBEY. but those of the small hospital of St. Leonard; the Multangular Tower. the most perfect relic of the Roman city; and the Museums of Antiquities and Natural History belonging to the A feast of no ordinary excellence is thus provided for the visitor.

The remains should be visited in due order. The hospital of St. Leonard is seen rt. on entering the grounds; but the visitor should first examine the Multangular Tower, a short distance beyond it. A portion of the ancient wall is connected with The lower part of the tower alone is Roman, the upper part being a mediaval addition. "The masonry of the exterior surface of the Roman wall, and of the whole breadth of the wall of the tower, consists of regular courses of small ashlar stones, with a string of large Roman tiles, five in depth, inserted between the 19th and 20th courses of the stones from the foundation. The masonry of the interior of the tower, reaching very nearly, it is probable, to its original

height, is remarkably fresh and perfect, owing to its having been concealed during many ages by an accumulation of soil. The tower has evidently been divided by a wall. a small part of which is still remaining, into two equal portions. At the height of about 5 ft. there seems to have been originally a timber floor; and above this, at the height of about 9 ft., another floor. The stone coffins now in the tower are from different Roman burial-places in the neighbourhood of York.

This tower stood at the S.W. angle of the Roman city, which was rectangular, about 650 yds. by 550, enclosed by a wall with a rampart mound of earth on the inner side of the wall, and perhaps with a fosse without. (For this earthen mound see post, the City Walls.) The S.W. wall ran from the Multangular Tower to Jubbergate; the S.E. terminated near Aldwark; the N.W. probably terminated at the angle of the present city wall in the Deanery Garden. The date of these Roman walls is uncertain; but most probably they were raised during the 3rd century, perhaps by the legions under Severus.

Rt., opposite the lodge at the entrance of the Abbey grounds, are the remains of St. Leonard's Hospital, said to have been founded by Athelstane, re-established by the Conqueror, and rebuilt by Stephen. It was one of the largest and best endowed foundations of its class in the north of England. Ninety persons were con-stantly maintained in it, including a warden, 13 brethren, 8 sisters, 26 bedemen, and 8 servitors. Its rental at the Dissolution was 362l. The principal remains are those of the ambulatory or cloister, and of the chapel of the infirmary. The ambulatory consisted of 5 or 6 aisles, in two of which was a large fireplace. Above were the wards of the infirmary, opening at the E. end to a small chapel; so that the sick persons, present at the services. The chapel of St. Leonard's is of the early part of the 13th cent.: the cloister is earlier, and may, perhaps, have been part of the building raised by Stephen. Some Roman remains found near York (including a tomb formed of ten large slabs of gritstone, and enclosing a coffin of wood) are preserved here. Here are also many sarcophagi and other relics found in the Roman cemetery discovered (1873) in excavating for the N. E. Rly. stat., on the rt. hank of the Ouse.

Passing the Grecian portico of the Museum of the Society (described further on), we come to the ruins of St. Mary's Abbey, one of the first monastic establishments founded in Yorkshire after the Conquest, and always one of the most important in the county. In 1074, three Benedictines, Ealdwin, Prior of Winchcombe, and two brethren from the neighbouring house of Evesham made a pilgrimage into the North to visit the holy shrines of which they had read in the history of Bede. many adventures, they became at last the re-founders of two famous Benedictine houses-Jarrow and Whitbyand the founders of this of St. Mary's. They were protected here by the first Norman Abp., Thomas of Bayeux; and the ch. of St. Olave was given to them (temp. Wm. II.) by Alan of Brittany, Earl of Richmond, to whose lot it had fallen. Numerous grants were made to the new foundation. which became not only the richest in Yorkshire, but one of the richest in the North, its annual rental at the time of its surrender in 1540 being 1650l. The site was retained by the Crown; and a portion of the buildings, extending from the S. transept of the ch. to the wall of the Abbev Close, was converted into a royal palace. The Abbot of St. Mary was the only mitred Abbot N. of the Trent besides the Abbot of Selby, remaining in their beds, might be and was called to Parliament. From

this monastery, in 1132, a company of monks, wishing to adopt the reformed and stricter rule of the Cistercians, set forth, after a violent struggle with their Abbot, found a restingplace at Fountains, and founded the great abbey there. (See Rte. 22.)

The remains of the monastic buildings were greatly shattered when, in 1827, the Yorkshire Philosophical Society (established 1822) obtained a grant from the Crown of great part of the ancient precincts, including the abbey ch., with the exception of the choir. In the reigns of William III. and Queen Anne, who granted permission for the removal of the materials to repair other buildings, part was used to construct the city gaol, and part of the stone was sent in the reign of George I. to Beverley, to repair the Minster there. The ruins are now carefully protected and cared for: and an exploration of the ground has brought to light many interesting foundations and fragments.

The principal existing remains are those of the Abbey Church. After the burning of an earlier ch., Abbot Simon of Warwick (1259-1299) laid the foundation of a new and larger choir, which he lived to see completed: and the rebuilding of the rest of the ch. no doubt followed in order. existing remains are very late E. E., or early Dec.; and, although much weather-worn, are of considerable beauty. The ch. consisted of nave and choir (of equal length-8 bays in each), a transept with E. aisle, and a central tower. (This tower was blown up during the siege of York in 1643.) It will be seen that the lights and tracery of the windows varied alternately. The W. front must have been fine; and the leafage, which rises between the shafts, and is twisted round the top of each, so as to form a foliated capital, is especially graceful. Foundations of eastern apses have been discovered in the transept, N. and S., and of a larger apse a short | the purposes of that body and for the

distance within the choir. were, no doubt, the eastern terminations of the Norm. ch., commenced by the first abbot during the episcopate of Thomas of Bayeux.

The monastic buildings were arranged in accordance with the usual plan. The cloister was on the S. side of the nave. East of the cloister, and projecting beyond the transept, was the chapter-house, of which one of the piers of the portal-arch remains. of late Norm, character.

N. of the ch. is the arch of the principal entrance to the precincts. This is Norm.; but the building attached to it, the lower part of which seems to have been the prison of the Abbey, and the upper part the Abbot's court-room, is late Perp. The Abbey stood without the city walls; and the entire close, or precincts, were surrounded by a wall of stone, with towers at intervals, by Abbot Simon. the rebuilder of the choir. This protection was necessary, not only against the citizens, between whom and the monks there were frequent skirmishes. but against occasional forays of the Scots. Outside the precincts, and N. of the gateway, is St. Olave's Church, of no architectural interest; but in the ch.-yd. Etty the painter (d. 1849) is buried. His plain sarcophagus is seen through an arch on the N. side of the ruined nave of the Abbev Church.

E. of the Abbey Church, and seen from the grounds, is a large irregular pile of building, known as the King's Manor, and occupied partly by the Wilberforce School for the Indigent Blind (established by subscription in 1833 as a memorial of William Wilberforce) and partly by the National School for Boys. This stands on the site of the Abbot's House, which, after the "Pilgrimage of Grace" in 1536 and the subsequent establishment of the Great Council of the North (see Introd.), was assigned for

residence of the Lord President of the Council. So it was inhabited until the abolition of the Great Council in 1641. The most distinguished Presidents who occasionally abode here were Radcliff, Earl of Sussex, and Henry Hastings, Earl of Huntingdon, both temp. Elizabeth; Lord Burleigh, who received here James I. on his entry into England; Lord Sheffield; and Lord Wentworth, afterwards Earl of Strafford. Charles I. was here for a month in the spring of 1639; but on his later visits, in Nov. 1641, and during his long stay in 1642, the King remained in Sir Arthur Ingram's house in the Minster Yard. Of the Abbot's House, built by Abbot Siever towards the end of the 15th cent., the only remains are a staircase in the N.W. corner and a wall or two. large brick buildings forming the N. wing of the Manor were raised by Lord Huntingdon, and one ornamented room (the dormitory for blind girls) is worth notice. The principal front of the Manor, facing E., was built by Lord Sheffield; and Lord Wentworth built a gallery and chapel. These have disappeared, but their position is marked by the heraldic achievement over the doorway on the W. side of the quadrangle. Strafford was charged with unbecoming arrogance for thus putting up his own arms in one of the King's palaces, but this did not form, as is often asserted, one of the articles of impeachment against him.

In the lower part of the grounds, near the river, is the ancient Hospitium, or guest-hall, of the monastery, the lower part of which (of stone) is of the 14th cent., the upper (of wood) of the 15th. In both of these (which have been restored) some interesting antiquities are arranged, the greater part having been found in York or the neighbourhood. In the lower room the most important are—a fine Roman pavement, with heads representing the 4 seasons, found in 1853 near Micklegate Bar; Roman altars, chiefly

from York, two of which are dedicated or bear inscriptions to the Deæ Matres (the three female deities whose worship is supposed to have been introduced in Britain by the Tungrian cohort from the banks of the Rhine), and one inscribed to a local deity. "Arciacon," whose name occurs nowhere else; Roman sepulchral monuments (one of them showing the funeral feast for a child, who stands in front), coffins (the inscription on No. 12 deserves notice), fragments of sculpture and tablets. The broken tablet (No. 14), which dates circa A.D. 108, and records the performance of some unknown work by the 9th legion in the reign of Trajan, was found in 1854 near Goodramgate, and is one of the most ancient inscribed tablets of the Roman period in the kingdom. Here is also a coffin found (1873) in the Roman cemetery opposite the Society's grounds, with an inscription for a "Decurio" of York, who "vixit annis xxviiii." This is the only, but a distinct, proof that Eboracum was a "colonia" of Rome, and had its local magistracy. Remark also fragments of Saxon sculpture. including two coffin-lids, the larger and more perfect of which was found within the nave of St. Dionis' Church. Walmgate; and some curious and interesting sculpture, chiefly of the Dec. period, from the ruins of the Abbey. In the upper room are, on the floor, some Roman pavements; the largest was removed in 1857 from Oulsten, near Easingwold, belonging to Sir George Wombwell. In cases round the room are British and Romano-British cinerary urns and potterv. In the case rt. of the stove is a very graceful small vase of Greek character, but of the local pale-coloured pottery; 3 cups of red ware, belonging to a lady's toilet, and found in the new cemetery; and a remarkable urn, from the same place, found full of bones, over which oils and gums had been poured. The scent of the unguents in the cups and of these gums

was still powerful when the discoveries ! were made.

The local antiquities in the Hospitium have been largely increased by the very interesting discoveries made on the site of the rly, stat, and hotel, on the L bank of the Ouse, which turns out to have been a Roman cemetery outside the walls. Among these observe coffins of stone (and wood), in which the bodies were laid in their clothes, and plaster poured over The plaster still retains in part the form of the body, and the marks of the folds of the clothes. one coffin, lined with lead, the skeleton of a woman was found, with the hair of the scalp quite perfect. It is here still preserved, with a jet hair-pin sticking in it. The collection of pottery is very extensive, and part of it, Samian ware of bright red colour, is very good, in classical shapes and ornaments. This fine ware was imported from Gaul and other countries, but a large quantity is of inferior British make, and includes some of the potter's moulds in which it was formed. The Roman glass is copiously represented-many vessels, bottles of good shape, glass beads. Personal ornaments and jewels; rings of gold, fibulæ, armlets, bracelets, beads of iet and amber; needles, hair-pins, ivory knitting-needles; toys for children, a ball, &c.; clay moulds and crucibles; a bronze pitcher on 4 legs for cooking, spindle-whorls of lead and stone; figures in bronze of birds, cock, peacock, eagle, ostrich (?); tiles stamped with inscription of Roman legions. "Leg. ix. Hisp;" a funereal jar full of burned bones; mosaic pavements, from Toft Green and Oulston: a bronze boss of a shield, engraved and inlaid with figures and patterns; besides many tombs and sarcophagi of various materials, several instances of interments made with curved tiles laid over the body, with ridge tiles along the top. Not only many lamps, but candlesticks of terra-cotta and dried clay; a gold amulet, with Gnostic | interest—a magnificent bowl of copper

inscription in Greek and Coptic; & coin (? obolus) found in a woman's mouth; a monumental stone inscribed of Lucius Rufinus, standard-bearer to the 8th legion, with his effigy in relief: the furnace of a bath, and the leaden pipes which conveyed water to it. Among other relics from the new cemetery are a curious small cup of pottery, thin as egg-shell china; a gold plate (a false palate?), found within the skull of a young woman (gold was one of the few substances which by the laws of the Twelve Tables might be buried with the body); and a small bone tablet, with the inscription, "Domine victor vincas felix," which may be either Christian or Mithraic. These antiquities are for the most part local, and deserve careful examination with the help of the detailed catalogue drawn up by the curators. At the head of the room, in a separate case, is the "Cook" collection of antiquities found in York. These are chiefly Roman. and comprise some fine pottery and glass. There are also some remarkable Danish (?) combs, in bone and wood, and what seem to be bone skates-long bones polished and flattened on one side. A small leaden ossuary (Roman) retains its contents. The case against the wall at the N. end of the room contains the finest collection of mediæval pottery out of London, all, or nearly all, found in There are some pitchers of Norman date, many interesting tiles, besides fragments and figures, all deserving attention. Of relics other than Roman, especially remark the sepulchral remains from tumuli at Arras, near Market Weighton, in a case opposite the door. The chieftain, whoever he may have been, seems to have been buried in his war-chariot, of which the wheel-tires and other portions are to be seen here, besides the horses' bridal-bits. In other cases are some fine Anglian bronze brooches and ornaments, and—of the highest

gilt and jewelled, found at Ormskirk, in Westmoreland. The ornaments on this bowl are very peculiar, and among them occurs a bird or monster, with a tail ending in a dart, and pecking at grapes. This occurs also on a fragment of stone sculpture at Otlev (Rte. 30), and apparently belongs to a post-Roman period. In this room are also an ancient British canoe. found in the bed of the Calder, near Wakefield, in 1838; and "the remains of an ancient British or Saxon fisherman, found in excavating for the foundations of Salem Chapel, S. Saviourgate." A small botanical garden is laid out between the Hospitium and the river.

The Roman Cemetery, where so many of the relics here preserved were found, was discovered (1873) in preparing the site for the N. E. Railway stat. This lies on the rt. bank of the Ouse, immediately opposite the grounds of the Philosophical Society, and covers a very considerable space. The whole was outside the wall of Roman York. and lay at a short distance rt. of the road from Eboracum to Calcaria (Tadcaster). It must have been used as a cemetery for a long period, and was apparently the burial-place of a poorer class than that which raised its monuments nearer to the great road, and for some distance along its course. In some parts of the ground Roman carters had been in the habit of "shooting" rubbish from the neighbouring city. There were thick strata of Roman bricks, mortar, and pottery, mingled with fragments of wallplaster, on which coloured patterns were distinct. Adjoining this rougher portion of the cemetery two or three deep pits, or "putei," were found, into which, as was usual, the bodies of slaves had been thrown carelessly and pell-mell, as was evident from the confused mass of bones in all possible positions. No similar "putei" have been found elsewhere in Britain, and the remarkable headstone-like blocks (in St. Leonard's Hospital, ante) are equally confined to this cemetery. The large coffins were found in groups, seven or eight together, and possibly mark the graves of a family. The gravel below the cemetery-bed was excavated in places to a considerable depth, and was full of glacial blocks—some boulders from Shapfell and other masses of greenstone from some unknown source.

The Natural History Museum of the Society is in the centre of the gardens. It is a Grecian building, designed by Wilkins, and contains a lecture room, with apartments occupied by interesting and well-arranged collections in natural history, antiquities, &c., chiefly local, the arrangements of the whole being highly creditable to the original curator. Professor Phillips, the distinguished geologist. It possesses one of the best geological collections, and most instructive from its good arrangement, that is to be found out of London. It is rich in Yorkshire specimens,elephants' teeth from the coast; freshwater fossils from the lake deposits of Holderness: fossil bones from Kirkdale (water-rat, ox, deer, besides hyænas, and carnivora); a choice collection of crag fossils; an extensive series from the chalk; colitic (opossum from Stonesfield, lower jaw); lias (ammonites from Whitby); and brown coal formation, &c. Remark especially an Ichthyosaurus crassimanus, 30 ft. long; and Plesiosaurus zetlandicus, the only specimen known. The British birds are good and tolerably complete. The foreign birds are numerous, and were arranged and named by Mr. Gould. In a case in the first room rt. is the skeleton of the (extinct) New Zealand Moa (Dinornia robustus), found, with the eggs about it, under a sand hillock, as it now appears. The mother-bird, refusing to leave her nest, must have been overwhelmed in a sand-storm. case of stone implements from the

local antiquities, are also in this Museum. In the hall are - some Egyptian antiquities: a Mithraic tablet, found, in 1747, under a house in Micklegate; and the Mortar of the Infirmary of St. Mary's Abbey, which, after undergoing various fortunes, was restored to its ancient resting-place in 1835. It is of bell-metal, weighing 76 lbs. On the upper rim is the inscription. "Mortariu Sci Johis Evangel de Ifirmaria Be. Mariæ Ebor." On the lower, "Fr. Wills de Touthorp me fecit. A.D. MCCCVIII." On the walls of the theatre are 3 tapestry maps, originally from Weston in Warwickshire, where lived William Sheldon, who first introduced tapestry-weaving into England. These maps (which contain some of the midland counties of England) were executed in 1579, and are said to be the first pieces of rapestry manufactured in this country. They were given by Horace Walpole to Lord Harcourt, and presented by Dr. Vernon Harcourt, Abp. of York, to the Society, in 1827. They are parts of 3 great maps of the midland counties, formerly at Mr. Sheldon's house at Weston, Long Compton, Warwickshire. The art of tapestry weaving was introduced by Sheldon, who died in 1570. Some fragments, said by Gough to be parts of these maps, are preserved in the Bodleian. In the Council-room is a large collection of Coins (to be seen only by special application to the curator). Among them is a series of Northumbrian stycas (about 4000 of the hoard found in St. Leonard's Place, York, in 1842, and about 2000 of that found in 1847 near Bolton Percy). Here is also a portrait of Francis Drake the antiquary, - author of · Eboracum.'

*The City Walls, perfect nearly throughout their whole extent, have twen built and repaired at many different periods.

Bridlington wolds, and some other | most part Dec. (temp. Edw. III.) They were much battered during the siege of York by the Parliamentarians in 1644; and the repairs lasted throughout the three years following. Thev were restored as a promenade towards the beginning of the last cent.; but again became dilapidated, and were put into their present condition in the year 1833, at a cost of nearly 3000%. The walk round them (22 m.) may be continued by the bridges across the Ouse. Some of the best general views of the Minster are to be obtained from the walls: the walk on which is carried for the most part on the ridge of the high rampart. The whole scene is picturesque, and with its gardens, trees, red roofs, and ancient churches, recalls that from the boulevards of some old Flemish city, or perhaps still more that from the walls of Nuremberg. The Clifford Tower, within the Castle (see post), a true relic of old York, is well seen from the walls.

The Gates, here called Bars (the streets leading to them being styled gales, the A.-S. "geat" signifying a road), are remarkable features of the city, dating for the most part from the time of Edward III., though the lower arches and foundations may be older. They have suffered serious improvements from modern innovators; and their very curious barbicans or outworks, scarcely to be met with elsewhere, have been, except in one instance, removed. The wall may be ascended close to any one of the gates or bars, and the visitor who has time should make the entire circuit. far as the mediæval wall follows the line of the Roman (N. and W.), and in some other portions, it is built on or adjoining an earthwork, which in places has been very strong. Roman city did not extend to the rt. bank of the Ouse. This earthwork is certainly later than the true Roman They retain Norm. | period, since close to Micklegate Bar and E. Eng. portions, but are for the | it overlays a large Roman pavement.

It remains uncertain, however, whether the work is British after the departure of the Romans, Anglian, or Danish. The mediæval wall has in places little or no foundation, as was distinctly evident where the wall and mound were cut through for the rly. Where the ancient earthen mound would not support it, it is carried on arches, or rather on piers with arches between them, and the whole was then banked up with earth. Outside the whole range was a deep and wide ditch, and probably a palisade: thus the comparative lowness of the wall, as seen from without, is accounted for. one side, opposite the Foss Island. there was no wall. Here the River Foss itself served as a protection, and the ground in front was a deep morass, not passable for an army.

Taking the circuit of the walls and the bars together, we begin at Bootham Bar, where the city is entered from the N.W. This lost its barbican in 1831. The main arch of the gateway seems Norm., the superstructure is Edwardian. From Bootham Bar to a little beyond Monk Bar the wall follows the two sides of the Roman Monk Bar, at the end of Goodram Gate (so called, perhaps, from a Danish "Gudrun"), opens on the road to Malton and Scarborough. Here the bar deserves careful atten-The archway itself is probably Norm.; the superstructure is good Dec., with a sustaining arch carrying a gallery between the flanking turrets, on the outside, and one at a lower level within. They were intended for pageants and procla-The machinery for the mations. portcullis remains in the chamber above, and the portcullis chamber is here one of the most perfect in England (the only one indeed which at all equals it is in the gateway of the Bishop's Palace at Wells). Inside Monk Bar (and on the rt. facing it) is a portion of the Roman wall, a little outside which the mediæval

wall has been built. Shortly beyond Monk Bar the wall leaves the square of the Roman city, and in the angle before reaching Laverthorpe Bridge is some stonework which may be At Laverthorpe the vall Norman. ceases, and, crossing the bridge, the visitor should take the outer road. beyond the Foss River, until he reaches the Red Tower, where the wall begins again. A glance at the outer country here will show him how completely the city must have been defended here by the Foss and the morass beyond it. The Red Torrer is so named from the brick of which it is built, and the wall between it and Walmgate may be Norm, or E. E.

Attached to Walmgate Bar, where the road opens to Beverley and Hull, the barbican, or outwork remains. It was rebuilt, however, in 1648; since, during the siege of York, by the army of the Parliament (1644), which lasted 18 weeks, this gate was nearly demolished by a battery on Lamel Hill. From Walmgate the wall proceeds to the Fishergate Postern (one of 5 postern gates formerly existing), adjoining the Foss and the castle. Here, in the angle of the wall, is a tower which is no doubt of E. E. date.

In St. George's ch.-vd., near Fishergate, the highwayman Turpin was buried, after his execution here in 1739. Crossing the Foss by a bridge. and passing under the outer walls of the castle, which, with their round towers, may be temp. Hen. III. (see post), the Ouse is reached, and a swivel Bridge leads to the Skeldergate Postern. (The New Walk along the banks of the Ouse, here shaded with elms, was laid out in 1734.) Immediately within the Skeldergate is the Bail Hill, the site of the second castle built by the Conqueror. This is a great earthen mound, at least 60 ft. high, and the wall itself is here carried on a very lofty embankment. There can be no doubt that these

carthworks, both mound and em-llimbs of his father (the Duke of bankment, belong to a period before the Norman Conquest. The castle was built here during the King's sojourn of 8 days (see ante), and no newly-raised earthen mound would have been capable of sustaining even a wooden superstructure. long dyke here crosses towards the wall, beyond the House of Correction, and marks what was apparently the limit of the Bishop's ancient jurisdiction. (Bishopgate - street is here outside the wall.)

The Victoria Bar is a portal, built in the days of Mr. Hudson, of railway celebrity. Then, passing along a good portion of the wall, whence the ancient tower of St. Mary the Younger is conspicuous, we reach Micklegate Bar, the largest and most important of all, through which passes the old road to London and the South.

The archway of Micklegate may be Norm., the rest is, perhaps, temp. Edward III. Above the arch are carved shields bearing the arms of old France and England quartered between those of the city of York. The gateway is flanked on either hand with turrets or bartizans, pierced with cross loopholes, and surmounted by battlements, on which stone figures of menat-arms are perched. The two side arches are not ancient. These gates have too often borne other and more ghastly decorations;—limbs and skulls of tra tors, patriots, and princes have been in turn exposed upon them to bleach in the sun-Llewelyn, last native Prince of Wales; ambitious York with his paper crown -"that York might overlook the town of York;" and those unfortunate followers of the Stuarts executed in the '45. The heads of the last were stolen in 1754 by a tailor of York

York); which so incensed him that he ordered Courtenay Earl of Devon, and 3 others of his prisoners, to be instantly beheaded, that their heads might replace that of his parent.

Just outside it and seen from the walls, is the Nunnery of St. Mary, a plain brick building, with extensive grounds. It is a great educational resort for the R. C. gentry of the north. Beyond Micklegate the wall is pierced for access from the new North-Eastern station, the ground occupied by which is the site of the great Roman cemetery (see ante, the Museum).

Quitting the station we then reach the Lendal Bridge over the Ouse, where the river was formerly protected by strong chains drawn across from postern to postern. (The openings for these chains are evident in the tower on the rt. bank of the river.) Then follows the multangular tower (see p. 55), the S.W. angle of the Roman city, and the round is completed at the neighbouring Bootham Bar.

Near the S.E. extremity of the city, on a tongue of land between the Ouse and the Foss, close to their junction, stands the Castle, to be seen only by direct application to the Governor, or by a magistrate's order (Admission is readily given by sending a card to the Governor, except on Saturdays.) There was a ditch round the whole outer walls of the castle, besides a second surrounding the keep or Clifford's Tower. could at any time be filled with water from the Foss. The position is thus naturally strong; and it is probable that the mound of the keep. like the Baill hill across the Ouse and his journeymen. Edward IV., (see ante), had been raised long on his triumphant entry into York as before the Conqueror built his first victor from Towton field was here castle on it. The whole fortress met by the sight of the head and suffered much during the siege in

1644; and was afterwards dis- that day and the following night. mantled by the Parliamentarians. It has ever since served as the County Prison. Within an area of 4 acres, enclosed by a massive wall 1100 yards in circuit and 35 ft. high, finished in 1836, and which cost with some other erections not less than 200,000l., stand the County Gaol, for felons and debtors: the County Courts, where the assizes for the N. and E. Ridings are held; and that fragment of the old castle called Clifford's Tower, from the Cliffords who were anciently the castellans. This was the keep or citadel of the fortress, and crowns a lofty mound. Its form is remarkable (unique, certainly, in this country, and apparently unknown elsewhere), consisting of parts of 4 cylinders running into one another. From its architecture the greater part of this tower cannot date farther back than the reign of Edward I., but it undoubtedly occupies the site, and possibly includes portions, of the stronghold erected by William the Conqueror. Its gateway is grooved for a portcullis, and over it is a small chapel (E. Eng.) with tooth-moulding. This keep (but not the existing structure) was the scene of the terrible Massacre of the Jews in 1190, which repeated in England the scarcely more fearful story of the siege of Masada. (Josephus, Bell. Jud. viii,

Henry II. had shown the Jews marked favour; but the hatred and jealousy with which they had always been regarded were only increased by the King's good-will. On the day of Richard I.'s coronation at Westminster (Sept. 3, 1189), some Jews ventured to enter the Hall during the feast, bearing presents in Eastern fashion. One of them was struck at the door. It was said, and gladly believed, that Richard, in atonement for his father's concessions, had ordered the extermination of the infidels; and a general attack on the Jews of

"The great crusade came; and Richard, before starting, laid down express law to guard 'his Jews' from outrage; vet, even before he left England, frightful massacres had taken place at Lincoln, Stamford, and Lynn. But the men of York waited till the King was beyond seas. The Jews of York lived, we are told, in the centre of the town, in splendid houses"-(their district was Jubber or Jewbergate, now Market-street, extending from Coney-street, across Parliamentstreet, to the Shambles)-"and appeared in public with the luxury and pomp of kings (cultu fastuque pæne regio procedentes .- William of Newburgh). It had been a terrible thing for insolvent debtors to fall into their hands. A body of armed men, nobles and citizens who had pawned their estates, crusaders soon to be out of reach of law, and within reach of absolution, attacked (March 16, 1190) the house of Benet, the chief Jew of York, with crowbars, plundered it, and slew his wife and children. Warned in time, 500 flew to York Castle, carrying their gold with them. It was the King's gold, they cried, and entrance was granted. All who were left behind were massacred. Soon the Warden of the Castle, returning from a journey, unaware of what had taken place, demanded entrance; and the Jews, either not knowing or not trusting him, refused it. He complained to the Sheriff, and the Sheriff shared his indignation. It was treason to seize the royal castle-treason not of Christians, but of Jewish dogs. The fatal word of permission escaped his lips; in a moment he would have recalled it; but, in that moment, armed masses from the city and from the country were thronging to the castle. But armed men were not their only leaders; for priests had joined their ranks, and, far in advance, robed in white, strode a hermit of the neigh-London commenced, which lasted all bourhood, famed for zeal and holiness, with passionate voice and gesture | to us, affliction has taught wisdom: goading them to the onset. Every morning, for the siege lasted several days, he performed mass, and reminded his audience that they were doing God's work, and sweeping from the earth the rebellious foes of Christ. At length, in his foolbardy fury, blind to the stones that were showered from the walls, he fell, the first and the last; for battering rams had now been made, and the besiegers, certain of victory, spent that night in merri-The Jews, meanwhile, were ment. perishing with hunger: and, as they sat down that evening, silent or muttering prayers, face to face with death, an old Rabbi who had come from beyond seas to spread the knowledge of the law among his brethren of England, who received him as a prophet, spoke thus: 'God, to whom none may say, Why dost Thou so? has now laid it before us to die for His law. Death, as ye see, stands at the door; unless ye rather choose for this short life to desert God's law, and live on the alms of the wicked in the deep shame of apostasy. Let us, then, like men, choose death; and death not at the hands of a laughing enemy, but in its most honourable and painless shape—a free surrender of life to Him that gave it. Let those stand apart who will not follow my counsel.' Many stood apart. Many were true to their name and faith; they set fire to the castle, casting their splendid Restern robes into the flames, hiding such wealth as could not be destroyed. A Jew, named Jocen, then killed his wife Amia and her sons. Then, when all the women and children had fallen at the feet of their husbands and brothers, and the last and boldest of them had turned his hand upon himself, the wretches who were afraid to die appeared on the walls at dawn, shrinking from the flames behind them, told the tale, and dropped down some of the corpses in proof. 'These wicked men,' they said, have ended witnesses of the story. The rebuild-their wicked lives in self-alaughter; ing of the keep was probably ren-[Yorkshire.]

we long for baptism, and for the faith and peace of Christ.' The crowd pitied, but Richard Malabeste and his crew were not to be cheated of their prey. All was promised, if they would open the gates; but, as soon as the threshold was crossed, they found themselves hemmed in by These proceeded to the murderers. Minster, wrested from the vergers the keys of the Jewish chest" (in which the register of money lent by the Jews was kept), "and burnt the documents in the nave. This done, they fled as soon as might be, some to Scotland, some to the crusades. The tale reached Richard in France: furious at the loss of revenues, and stirred perhaps by nobler feeling also, he ordered William des Longchamps to hold a court of inquiry in the city. Fines were laid upon the wealthier citizens; but to no single man was guilt brought home."—(J. H. Bridges, in 'Oxford Essays for 1857.' The narrative is from William of Newburgh, a contemporary, and a native of Yorkshire.)

The entrance to Clifford's Tower is through a portal erected by Francis Clifford, Earl of Cumberland, who was governor for Charles I., and put the castle into a state of defence at the beginning of the civil wars. arms of the Cliffords are still visible on this portal. Over the old entrance is the small and interesting E. Eng. chapel already noticed. This keep was burnt or blown up in 1684, on the night of St. George's festival. having been set on fire wilfully, it is supposed, by the soldiers posted (The marks of fire on the in it. stonework are, of course, referred by the warder to the time of the Jewish massacre and conflagration. But little of the existing keep is so ancient. The site, and a well in the court, down which, says tradition, the Jews flung many bodies, are the chief then underwent.) The interior is of the Reform Bill. now overgrown with trees, one of which, a walnut, is said to have been planted by George Fox, the founder of the Quakers, who was for some time imprisoned here. There is a fine view from the ramparts, with the Bail hill opposite.

There is in a small room adjoining the house of the governor of the prison a remarkable Collection. Here are preserved the coining apparatus used by David Hartley; the razor with which Jonathan Martin, the incendiary, struck a light to burn the Minster: the bell-rope by which he let himself down from the window; a part of the skull of Daniel Clark, the victim of Eugene Aram, dug up at Knaresborough; the strap with which one Holroyd hung his father on a cherry-tree; the knife and fork with which the rebels were quartered, 1745; the fetters (24 lbs.) which confined Dick Turpin's legs, and the belt which went round his waist, while in prison here; a rusty knife and a bent poker with which husbands murdered their wives : a sledge hammer and a razor with which a wife destroyed her husband; a wig and pistol, by means of which Peter Buck, a Quaker, robbed a banker of Knaresborough of 1500l.; and many other articles which would do substantial duty in a sensation novel, but which ordinary visitors will hardly care to examine.

Within the Courtyard of the castle county and election meetings are held. Here the youthful and diminutive Wilberforce poured forth his eloquence in the cause of Pitt upon the dense crowd assembled-when, to use the words of Boswell, "I saw what seemed a shrimp mount on the table. but, as I listened, he grew, and grew, till the shrimp became a whale." Here, in 1831, Henry Brougham fulminated that speech which set the title:-

dered necessary by the destruction it | country on fire, and led to the passing

In the small opening called Helen'ssquare, at the end of Conev-street (Conyng-cyning, or king's street), stands the Mansion-house, a large modern building, not particularly remarkable; but behind it, reaching down to the river, is the Guildhall, having a stately Perp. Gothic hall, erected 1446, by the Guild of St. Christopher, and divided into a nave and aisles by 2 rows of piers, with a council-room at its further end. The windows were restored temp. Queen Anne. The Great Council of the North, which was established by Henry VIII., and continued until the reign of Charles I., held its sittings in the Justice-room at the back of the Hall, overlooking the Ouse; and here the Scots were paid 200,000l. for assisting the Parliament against Charles I. A great banquet (Oct. 26, 1850) was given in the Guildhall by the Mayors of different English Corporations to Prince Albert and the Lord Mayor of York, in return for the banquet which the Lord Mayor had given here, in support of the Great Exhibition. (The second festival is commemorated in a stainedglass window by Hardman at the end of the hall.) York is the only city in England, besides London, which boasts of a LORD Mayor, the dignity having been conferred by Richard II., when he granted to the city its first corporate charter. With it he bestowed on the mayor, William of Selby, his own sword, adding afterwards a mace, and a cap of maintenance for the swordbearer. The sword and cap of maintenance still exist, and are displayed on state occasions. corporation plate is fine, and the "loving cup," passed round special occasions, holds a gallon. According to the old rhyme, the Lady Mayoress always retained her

"He is a lord for a year and a day, But she is a lady for ever and aye."

The same monarch made York a distinct county, comprising 35 towns and villages; and Henry IV. annexed to it the district called the Ainsty; but by the Municipal Corporations Bill (1835) this has been transferred to the West Riding. A long vaulted passage on the W. side of the Guildhall leads to the river, opening on a river gate which seems earlier than the hall above, and was probably defended. Within the passage (I. in ascending from the Ouse) is a boat chamber.

St. Anthony's Hall or Hospital, now the Blue-coat School, in Peaseholm Green, will reward the archæologist for his visit. Modern floors have been introduced throughout building, which consisted originally of a hall, 81 ft. long by 27 wide, and an aisle on either side. The Perp. open timber roof of the main hall (now used as the schoolroom) well deserves study. The aisles, serving as dormitories. have also good roofs. The hospital was founded about 1340, for brethren of the Mendicant Order of St. Anthony, by Sir John Langton, Mayor of York.

St. William's College, opposite the E. front of the Minster, was founded in 1460, "for the parsons and chantry priests of the Cathedral," by the Nevilles (George, then Bishop of Exeter, afterwards Archbishop of York, and Richard, Earlof Warwick). Of the original college little remains except the entrance doorway, Perp., with carved brackets on each side. In a niche above it is a mutilated figure, probably St. William. The building within is chiefly Jacobean. The staircase deserves notice, and in one of the apartments the royal printing-presses were set up in 1642, during

the residence of Charles I. in York. Many important state papers and political pamphlets were printed here.

Few old houses now remain in York; though the overhanging porches and carved brackets of those which still exist show how picturesque the streets must once have been. A large timber house at the end of the Pavement (14th cent.?) deserves notice, especially for the brackets which carry the overhanging story. "A house called Newgate, in a narrow street of the same name, near the Shambles, is also a curious specimen of the 14th cent.; the lower part is of stone, and has an original doorway and 2 The upper part curious windows. is of timber, of early character, but plain."-J. H. P.

The lover of trees and flowers should on no account leave unvisited Messrs. Backhous's Gardens. about 11 m. from York, on the road to Acomb. They cover about 75 acres, and are among the largest and most important nursery gardens in this country. They are famous for their alpine garden, their ferneries, and orchid houses. The chief fernery is under glass, and is so extensive and so well-managed, that its limits are quite unseen. alpine ground is an artificially formed dell, with rockwork, lofty and broken, of most natural appearance, and covered in spring with the loveliest alpine flowers from all parts of the world. In front of the offices are two dwarf palms-Chamerops Fortuni, - which have survived, unprotected, many winters.

above it is a mutilated figure, probably St. William. The building within is chiefly Jacobean. The staircase deserves notice, and in one of the apartments the royal printing-presses were set up in 1642, during having been the projectors. It was

established on those principles of kindness and firmness toward the insane which are now universally recognised; but the benefits of this system were here first practically demonstrated in England.

Severus' Hills, 3 slight eminences near Holgate, west of York, were supposed by some antiquaries to have been raised on the spot where the body of the Emperor Severus was buried or burned. It is possible that the body may have been burned here; but the hills, as Professor Phillips has clearly proved, are natural elevations, part of a deposit of clay and gravel belonging most probably to the glacial period.

York races, which are of some celebrity, take place annually in August on Knavesmire, about 2 m. from the city. The course is one of the best in England. The races were first established in 1709, on Clifton Ings; but they were soon afterwards removed to the present course. Horse-races, however-probably the first in England - are recorded by Camden as taking place in his time, in the forest of "It is Galtres, close to York. scarce credible," he says, "what a concourse of people flock to these races from all parts, and what great bettings there are upon the horses." The prize for the winning horse was a little golden bell, "which was tied on his forehead, and he was led about in triumph; --- whence the saying, when a person is winner or most expert at any sport, 'He bears the bell.' " - Gough. The Northmen were great lovers of horse-fights (between the small Icelandic ponies) and of horse-races; so that the Galtres races may possibly have been first set on foot by some Egils or Guntrun who had established himself within the walls of Danish York.

History.

The position of York, nearly at that point of the river Ouse where it ceases to be navigable, resembled that of most other British towns. became Romanised, in all probability, during the second campaign of Agricola (A.D. 79), and after the conquest of the Brigantes (see Introd.). "The Romans knew well how wise it was, in a strange and savage country, to take possession of a place of antiquity and note, where, probably, there was the only market in the district, and towards which all the forest paths converged." - Raine. The first certain evidence of the existence of Eboracum is given us by Ptolemy, who mentions it as the headquarters of the 6th Legion, with monuments of which York and the neighbourhood abound. Severus, with his sons Caracalla and Geta, arrived in York early in A.D. 208. It was then, no doubt, the chief city of the whole province of Britain-" the seat of the prefect with his official staff and the ministers of his luxury; while Londinium was still a mere resort of traders." It occupied a comparatively small part of the space included within the existing mediaval walls. It was confined to the l. bank of the Ouse. forming nearly a square; one side of which ran parallel to the river-ending at the multangular tower.

at the multangular tower.

Bootham Bar marks the centre of W.
wall and Monk bar of the N. (these
two bars are probably on the sites of
Roman gates). The line of the fourth
wall is not ascertained, but it probably
extended in a direction opposite to
Ouse gate and bridge, and Monk bar
may stand about the centre of them.

Geta was left to administer justice in York during the absence of Severus in his campaign against the Metae, and he was assisted here by the famous lawyer Papinian. Severus died at York, Feb. 4, A.D. 211. His body was burned here, but the ashes were conveyed to Rome. His memory

Hills (see ante). In 305 Diocletian and Maximinian resigned the empire to Galerius and Constantius Chlorus. Britain fell to the share of the latter, who came over at once and fixed his residence in York, where he died in the following year. The ceremony of his apotheosis may have been performed in York: but his ashes were probably conveyed to Rome, in spite of a tradition that his tomb was found (temp. Hen. VIII.) in a vault beneath the Church of St. Helen's on the walls (see ante, Churches of York). His son, CONSTANTINE THE GREAT, WAS Proclaimed Emperor at York. Whether he was born here is uncertain. the councils of Constance and Basle the English ecclesiastics endeavoured to found a claim of precedency on the assertion that Constantine, the first Christian Emperor, had been "a born Englishman." His mother Helena, who is sometimes said to have been a British princess, was in reality born at Drepanum, in Bithynia, where she died.) Constantine, on his father's death, proceeded at There is no later once to Gaul. distinct notice of York during the Roman period. According to Richard of Cirencester, Eburacum and Verulamium were the only Roman "municipia" in Britain. The city was full of stately buildings-" Decus imperii, terrorque hostilibus armis," according to Alcuin. It lay entirely on the left bank of the Ouse. short notice of it will best be read under the walls of its most important remaining fragment, the multangular tower now in the Botanic Gardens (see St. Mary's Abbey).

The importance of York continued during the Saxon period, when St. Paulinus baptized Edwin of Northumbria here and founded the Minster (see ante). From the time of Abp. Egbert (735-766) until the the chief places of education, not wards Hastings, Northumbria re-

is preserved by the name of Severus' only in England, but in Europe. Egbert was himself the "moderator" of the school, and his successor in the see, Albert, the "vice-dominus" or "Abbas." Among their scholars was the great Alcuin, himself one of the teachers and friends of Charlemagne, and the most learned man of his age. Alcuin became "magister scholarum" of York when Albert was raised to the see; and he assisted both Egbert and Albert in collecting a library which was one of the best in Europe, and which he has himself described in some wellknown Latin hexameters. the end of the 8th century the Northmen appeared in Northumbria, and, after ravaging the whole district, established themselves permanently within it in large colonies. Athelstane reduced them to submission; but York, in the mean time, had become almost completely a Danish settlement, and wandering Vikings found their way to it from all parts of the North. It is described, about 990, as thronged with Danish merchants, and having a population of at least 30,000. was the chief city of the old Northkingdom, and of great earldom, still almost as independent, which followed it. It was the capital of the Danish Siward (see St. Olave's Church). and of Earl Tostig, the brother of Harold. Morkere, whom the Northumbrians of Deira chose for their Earl after the exile of Tostig, issued from York to fight the battle of Gate Fulford (Sept. 20, 1066), before Harold of England arrived, too late to prevent the surrender of the city to the Norwegians, but in time to redeem it by the great victory at Stamford Bridge (see Rte. 8). was while feasting at York after the battle that Harold first heard of the landing of William at Pevensey. Here he held a council of leaders, end of the century, York was one of and then marched southward to-

until the summer of 1068. Morkere. who had become the Conqueror's "man" and had been confirmed in his earldom, then revolted with his brother Eadwine. York was the centre of resistance; in the city were gathered Eadgar the Ætheling, his mother and sisters, Gospatric, Earl of Bernicia, and all the powerful thegas of Northumbria. The Conqueror at once marched toward York. Eadwine and Morkere met him near Warwick, submitted without a blow, and were again received into favour. Some of the Northern leaders fled to Durham, and Eadgar the Ætheling, Gospatric and others took refuge with Malcolm of Scotland. William entered York as its master and conqueror, and now built his first castle there, between the Ouse and the Foss (see the He left this new strong-Castle). hold in the charge of three commanders : Robert Fitz - Richard, William of Ghent, and William Malet. (It was on his return southward that Prince Henry was born at Selby—see that place ante—if that event really occurred there.) In the following year Northumbria again The citizens of York revolted. attacked the newly-built castle; William again appeared on the scene, took fearful vengeance on the besiegers, and caused a second castle to be constructed on the right bank of the Ouse, on the mound which still bears the name of the Bail Tower (see Index). In the autumn of 1069 occurred the last great struggle of the North for independence. In September a Danish fleet, commanded by Osbeorn, brother of King Swend, and by the king's sons, Harold and Cnut, entered the Humber and was joined by Eadgar the Ætheling and the English exiles. They advanced to York; and the

mained unsubdued by the Normans [for filling up the ditches during the assault, set them on fire. The flames spread, and the greater part of the city, including the Minster (and the famous library collected by Abp. Egbert—see the Minster), was destroyed. While the city was still burning the Danish fleet came up, the castles were attacked and taken. and two of the castellans, William Malet and Gilbert of Ghent, carried off prisoners. The castles were broken down, and the Danes returned to their ships with vast booty. Again William, who had been suppressing the revolts Western England and elsewhere, hastened northward, crossed Aire above Pontefract (see Ponte-fract, Rte. 28), entered the ruined city of York, repaired the castles. and then set on foot that deliberate harrying of the whole of Northumberland which reduced the country to a desert, and effectually prevented any future risings of the few remaining inhabitants. (See Introd., and for the whole of this period, Freeman's 'Norman Conquest,' vol. iv.) The importance of these events has rendered it necessary to notice them at some length; but to detail all the great events of which York has been the witness from the 11th to the middle of the 17th cent. would be to write the history, not only of Northern England, but in a great degree that of the whole kingdom. The conquest of the city by William I. is described above (the Castle of York). The Edwards and Henrys were constantly here. Henry II. and his son (already crowned king) received in York Cathedral (Aug. 10, 1175) an homage of William the Lion, of Scotland, and his brother David. Many Scottish bps. and abbots were present. (Ben. Abbas. i. 95.) Alexander of Scotland here married Norman governors of the castles, (Christmas day 1251) Margaret, fearing that the houses adjoining daughter of Henry III., — bride them would be used by the Danes and bridegroom being not quite

Philippa of Hainault (1328) at York: and here King David of Scotland was solemnly delivered to that queen by Sir John Copland, who had taken him in the battle of Neville's Cross (1346). Richard II. was often here, and gave a sword of state to the mayor, which is still carried before him (see ante). Henry VI. and Queen Margaret were constantly at York during the wars of the Roses. Here they received the fatal news of Towton (1461), and hence they fled to Scotland. Edward IV. was crowned here (1464) with the royal cap called "Abacot," which had been found in Henry's baggage at Hexham. Charles I. was at York in 1639, before his armed interference in Scotland; and in 1642 he was for some months in the city. When the Parliament had openly declared war and had begun to arm, the Commission of Array—the prelude to the Civil war-was issued from York. Thirty-six of the Peers, quitting the Parliament, devoted themselves and their fortunes to the service of their sovereign; and in August Charles finally left York, and proceeded to Nottingham, where the royal standard was set up. After the raising of the siege of Hull (1643) York was besieged by the Parliamentarians under Fairfax, Manchester, and Leven. On this occasion Fairfax did his utmost to protect the Minster, and the safety of the stained glass is probably due to his exertions. But the tower of St. Mary's Abbey was blown up by a mine worked under it by the troops under Lord Manchester, and a vast collection of documents stored there was thus destroyed. (For a full account of the siege see Markham's 'Life of Fairfax, ch. xIV.) The siege was raised on the arrival of Prince Rupert. Marston Moor immediately followed, and the remains of the Royalist army

11 years old. Edward III. married! dered to the Parliament after that battle, July 16, 1644.

> Many parliaments were held at York under Edward II. and Edward III., and in 1354 the staple of wool was removed to this place from Bruges.

Among the most remarkable "illustrations" of York are Sir Thos. Herbert (see ante, St. Crux Church). Guy Faux, born 1570, of a good old family, in the parish of St. Michael le Belfry. He removed, when young, with his mother, to Scotton, near Knaresborough, where he is said to have been converted to Romanism. He afterwards served in the Spanish army in the Netherlands, under the Archduke Albert, and came back to England in 1604, when he was fixed upon by the conspirators as the best person to execute their purpose. Marmaduke Fothergill (born 1652), whose books formed the nucleus of the Minster Library; Bp. Porteus (b. 1731); John Flaxman, the sculptor (b. 1755); and William Etty, R.A. (b. 1787). Throughout his life Etty's fondness for his birthplace was marked. In 1828 there was a project for taking down the old walls, which raised his highest in-"Is it possible," dignation. writes, "that such barbarians exist in the 19th century at York?-York, that gave birth to Flaxman, the glory of his country, and the admiration of foreigners?" In 1846 Etty bought a house in Coney-st. (somewhat back from the street, and close to St. Martin's Church), where he painted his 'Joan of Arc,' and where he died, 1849. There is no great picture of Etty's in York. Thos. Gent, the printer, an Irishman, settled here, where he wrote and printed most of his books. (An amusing sketch of his life will be found in Southey's 'Doctor.') retreated to York. But they could died at his house in Petergate, 1778. hold it no longer, and the city surren- Lindley Murray, a native of Pennsylvania, came to England in 1784, and settled at York. He died (a Quaker) in 1826. The house in which Hudson (the Railway King) first set up as a linendraper in York is in College-st. (near St. William's College). Finally, let us not forget in York that Robinson Crusoe was "of York, mariner. I was born," he says, "in the year 1632, in the city of York, of a good family, though not of that country."

Excursions by Railway.—Knaresborough (\$\frac{1}{2}\$ hr.) and Harrogate (1 hr.) with the intermediate stations, may easily be visited from York. (For all these places see Rte. 20.) Boroughbridge (1 hr. 5 min.) and Aldborough, with its Roman relics (see Rte. 19), may also be the objects of a day's excursion.

Sheriff Hutton Castle (see Rte. 12) may be reached by a pleasant walk of 2 m. from the Flaxton stat. (25 min. from York), on the Whitby and Scarborough rly.; and Castle Howard (44 min. from York, on the same rlv., see Rte. 12) is also accessible. Gilling Castle (Rte. 18), Rievaulx Abbey (Rte. 18A), and Selby Abbey Church (see the present route, ante), may be visited in one day from York. Selby is reached in hr. by rly., and Howden Church (Rte. 5) may easily be seen in the same day. For Gilling and Rievaulx the distances are considerable, and the trains are inconveniently timed for tourists.

Shorter Days' Excursions; walks or drives.

The country in the immediate neighbourhood of York is flat and unpicturesque; but there are some interesting churches to be visited, and the antiquary may find his way to the battle-fields of Stamford Bridge and Marston Moor.

The great forest of Galires anciently extended from the north wall of York as far as Easingwold and Craik. It comprised nearly the whole of the wapentake of Bulmer: about 60 townships, and nearly 100,000 acres of land; and continued a royal forest until 1670, when an Act of Parliament was obtained for its division and enclosure. Leland (temp. Henry VIII.) describes that portion of the forest between York and Sheriff Hutton as "in the first part" (nearer York) "moorish and low ground, and having very little wood; in other higher, and reasonably wooded." It abounded in "wild deer." Galtres is the 'Calaterium Nemus' Geoffry of Monmouth, who makes it the scene of his story of Arthegal and Elidure.]

a. Heslington Hall (2 m. S.W. of York, long the residence of the Yarburgh family) is an Elizabethan mansion (restored and partly rebuilt by G. J. Yarburgh, Esq.), with a fine hall, containing some portraits of interest. Among them are:—Queen Elizabeth, Charles I., Vandyck; James II., Wissing; Charles II., Henry Prince of Wales, Prince Charles Edward, Duchess of Orleans, Lely; Duchess of Grafton, Kneller. In the gardens are clipped hollies and yew-trees, well harmonizing with the house.

The Church was rebuilt in 1858. In the park, I of the road, not far from the house, is Sevent's Mount, about 50 ft. in diam. at the top and about 15 ft. in direct height. There is no sign of outworks about it, and it is uncertain whether the name preserves that of the great Earl Siward.

There are striking views of York from the Heslington road, which give some idea of what the approach must have been to the city in ancient days, with its Minster, Castle, great Abbey, many churches,

and encircling walls. A windmill, which stood rt. of the road from York, marked the spot where Archbp. Scrope was beheaded.

b. *Bishopthorpe (2½ m.), the palace of the Archbishops of York since it was purchased and attached to the see by Archbishop Gray (1216-1255), is on the rt. bank of the Ouse. Its ancient name was

St. Andrewthorpe.

The vaulted foundations of the existing palace and part of the wall next the river, its lancet windows and buttresses, are of E. E. character, and are the only remaining portions of the palace that was built here by Abp de Gray. present building is of various dates; but bears for the most part the stamp of Abp. Drummond (1761-1776), who built the gatehouse and the principal front in Strawberry hill style. The chapel is a mere squaresided room. In the dining-room are portraits of the Archbishops, of considerable interest. Markham, by Reynolds; Herring, by Hogarth; also George III. in robes, and Earl Harcourt, with a Beefeater, by Benj. West. The palace, though large and well arranged, is of little architectural importance. In the hall of Bishopthorpe (no longer existing-although the present dining-room may occupy its site) Abp. Scrope and the Earl Marshal were condemned (June, 1405) by a certain knight named Fulthorpe; the King (Henry IV.), who was present, having first commanded Chief Justice Gascoigne to pronounce sentence on them. Gascoigne firmly refused, on the plea that the laws gave him no jurisdiction over the life of the prelate. The archbishop was beheaded, protesting that "he never intended evil against the person of King Henry," on Bishops' Hill, between York and Bishopthorpe. The windmill which marked the spot was taken down 1881. (See gate, for his grave in the Minster.)

The gardens of Bishopthorpe are large, abound in fine trees, and are flanked by two stately avenues. It was long the custom for passing trading-vessels to fire three guns—a signal which was answered by a supply of ale from the palace. The church of Bishopthorpe was rebuilt by Abp. Drummond in 1766, and is of the same nondescript Gothic as the rest of his work. He is buried in the chancel.

c. * Two very interesting churches -Skelton and Nun Monkton, and a third, Overton, worth a visit-lie within a short distance of each other, N.W. of York. By road Skelton is 4 m. from York, Overton 1 m. from Skelton, and Nun Monkton 2 m. from Overton. The pedestrian may, if he prefers it, proceed to the Shipton stat. (52 m.) on the York and Darlington Rly.; walk thence to Nun Monkton (21 m.), to Overton (2 m.), and to Skelton (1 m.). From Skelton he can either return to York (4 m.) or to the Shipton stat. (2 m.), but he should be told that every train does not stop at Shipton.

The little Church of All Saints, Skelton, a conspicuous mark, since it stands high above the village, is throughout E. E., and is traditionally said to have been built with the stones that remained after the completion of the S. transept of York Minster. It is without a tower, and the nave and aisles are The S. porch, under one roof. with a deeply-splayed doorway, is original, but the shafts are modern. The windows are single lancets, except at the E. end, where are three lancets of equal height, with "vesica" in the gable. stringcourse runs round the buttresses and over the windows, and is a pearshaped moulding, with the nail-head ornament on both sides (the same string is used

throughout the interior). elegant bell-cot for bells rises over the chancel arch within; the E. window is much enriched with banded detached shafts. and the tooth-moulding. There is an E. E. piscins on the S. side of the altar, and an aumbrie, with bracket, on the N. The font is unusual. The ornamentation of the windows deserves special notice. The vaulting is modern. Overton, the least important of the three churches, was chiefly Trans.-Norm., with Dec. windows inserted; but the walls having become dilapidated from burials close to them, were rebuilt 1854, at the cost of Hon. L. F. C. Dawnay. small priory of Gilbertine Canons was founded here by Alan de Wilton in the reign of John. St. Mary's, Nun Monkton (restored 1873), archit. J. W. Walton, is E. E., and very beautiful. The village was known as Monkton at the time of the Domesday Survey -probably indicating the site of a Saxon monastery. In the reign of Stephen, William de Arches, and Ivetta his wife, founded here a priory of Benedictine nuns. The church, which was the chapel of the nuns. stands at the end of a noble avenue of elm-trees, and close to Nun Monkton Hall (J. Crawhall, Esq.), which occupies the site of the priory. Before the late (1869-1873) restoration, only the nave and W. front with the belfry The chancel had tower remained. been entirely destroyed. The W. front -"of very singular design, perhaps unique, and remarkably elegant"-J. H. P.—consists of a Trans.-Norm. doorway, with a gabled pediment, and three E. E. lancets above it, of which that in the centre rises into the tower. The tower windows, square-headed and trefoiled, should be noticed, as well as the corbel table above them. The lancets are much enriched with the dog-tooth. On either side of the portal (and of the same date) are round-headed niches.

A lated figure of a king. The aisle windows (high in the wall) are lancets; and on the S. side are three The westernmost (the doorways. nuns' door) is rich Trans.-Norm.; the central doorway is walled up, and was perhaps the prioress's door; the easternmost, or priests' door, has been faithfully restored, one jamb and a portion of the arch having guided the work. These doors probably opened from a cloister. The interior, very striking before, is now rendered still more so by the modern chancel. The windows of the nave, which are plain externally, are rich within, having shafts with well-moulded caps, bases, and bands. "Between these windows are lancet-shaped arches, with trefoil-headed niches above them, opening into a triforium or passage in the wall; the whole range forming a sort of rich triforium arcade."-J. H. P. The east end has a triplet filled with stained glass by Morris and Co., representing various scenes from the life of the B. Virgin, the central subject being the Adoration of the Shepherds. The reredos below is of Caen stone, with shafts of serpentine.—the figures by Forsyth. The manner in which the three walls of the tower within the church are supported by arches is peculiar, and is an early instance of an arrangement (the tower opening to aisles as well as nave) almost confined to Yorkshire. Two coffinshaped gravestones with found under the flooring during the restoration, are cramped to the wall in the N.W. angle. The font is E. E.

and three E. E. lancets above it, of which that in the centre rises into the tower. The tower windows, square-headed and trefoiled, should be noticed, as well as the corbel table above them. The lancets are much enriched with the dog-tooth. The abbot of St. Mary's, York, had on either side of the portal (and of the same date) are round-headed niches, in one of which remains the muti-

ch. of which (3 m. N.W. from Shipton | the gardens of Red House, where it stat.) was rebuilt in 1849 (except the lower part of the tower, which is Norm.), at the cost of the Hon. Lydia Dawnay. The spire (150 ft.) is a good landmark. The E. window is by Willement. There is a modern brass in the chancel (with effigies) for the 6th Lord Downe, rector of Sessay and Thormanby, died 1846and his wife. Overton and Skelton are on the l. bank of the Ouse.

Red House, on the Ouse, 11 m. below Nun Monkton, was an ancient seat of the Slingsbys. It is now a farmhouse, but the chapel remains. built by the father of Sir Henry Slingsby the Cavalier, whose 'Memoirs' were partly edited by Sir Walter Scott; and the whole by the Rev. D. Parsons. The house itself was built by Sir Henry; and the room still remains in which King Charles slept, in 1633, on his way into Scotland. The canopy of the royal bed (of blue damask) is also preserved. At the W. end of the chapel is a gallery and staircase, removed from the house, where they had been erected by Sir Henry himself. "Upon every post of the staircase," he says, "a crest is set of some of my especial friends and my brothers-in law; and upon that post that bears up the halfpace that leads into the painted chamber there sits a blackamoor (cast in lead by Andrew Karne), with a candlestick in each hand to set a candle in to give light to the staircase." This "blackamoor" has lost his hands. Some stained glass remains in the E. window of the chapel, which was consecrated by Thomas Merton, Bp. of Lichfield, after Abp. Neale had refused to consecrate it, "lest it may be occasion of conventicles." Charles I. whilst here in 1633 was present at a race on Acomb Moor when a favourite horse of Sir Henry Slingsby's won the plate. The effigy of this victorious steed was placed in

still remains, much mutilated. Henry was an active Royalist, and after many troubles was sacrificed by Cromwell in 1658, when fears of a rising of the King's party were apprehended. He was beheaded on Tower-hill, and buried in Slingsby chantry attached to Knaresborough Ch. (see Rte. 20).

- d. Escrick and Skipwith may be visited from the Escrick Stat. (See the present Rte. ante.)
- e. The battle-field of Stamford Bridge (94 m. N.E.) will be reached by the York and Market Weighton Rly., and is described in Rte. 8. Both here and at Marston Moor the imagination must see more than the eye. Marston Moor is 7 m. W. from York, on the Wetherby road, but is quickly reached from the Marston Stat. on the rly. between York and Knaresborough. (For it see Rte. 20.) The battle-field of Towton is 2 m. W. of Church Fenton Stat. (Rte. 2 and Rte. 43), and may be made the object of a day's excursion from York.

ROUTE 1A.

LONDON TO YORK, BY LUTON, BED-FORD, LEICESTER, LOUGHBOROUGH, AND TRENT JUNCTION.

(Midland Railway.)

From St. Pancras or Moorgatestreet and other Metropolitan stations. 9 trains daily; 5½ to 6 hours from St. Pancras.

This route, though rather longer than that by the Great Northern, is preferred by many. It passes through more picturesque scenery, especially in the Trent Valley, whether the train goes vid Derby, or directly from Trent to Chesterfield. The large map of the Company's Time Table is a useful companion on this route.

A number of suburban stations are rapidly passed, and several short tunnels. After passing the great "Welsh Harp" reservoir between Cricklewood and Hendon, the train enters the open country, and runs in a direct course for many miles. To the left of the line, and nearly parallel with it, is the old Roman Road to St. Albans. Presently the train enters the Elstree tunnel, 1060 yards, which cuts through Woodcock Hill, the summit line of which separates Middlesex from Herts. Thus the fourist passes from ne country to the

other in this tunnel. The Colne is crossed beyond

Radlett Station, and on the l. is Parkbury Lodge. Running on in a nearly straight line the train comes in sight of the town and old abbey of St. Albans, to the left of which are seen the wooded hills of Gorhambury, where Lord Bacon had a residence. After passing Harpenden, the line crosses the Lea and enters Bedfordshire, and proceeds to

Luton Stat., looking down upon the beautiful park of Luton Hoo. The northern outcrop of the chalk that underlies the London basin is well seen in the cuttings hereabouts.

Passing four small stations,

Bedford is reached, and thence the line proceeds, crossing the Ouse several times, into Northamptonshire, which it enters at about a mile before reaching

Irchester Stat. The Ise is crossed just before reaching

Wellingborough Stat., 65 m., where the Midland Company has a locomotive establishment and goods depot. The branch line to the left goes to Northampton. The ironworks passed on the rt. show that we have now entered a different geological region from that which immediately surrounds the metropolis. After passing Kettering and some minor stations, Leicestershire is entered on crossing the Welland at

Market Harborough, with its fine Church, said to have been founded by John of Gaunt, and where Charles rested on the night before the battle of Naseby, the field of which is 7 m. distant. Passing Kibworth Beauchamp, the birthplace of Dr. Aitken, on 1.,

Middlesex from Herts. Thus the Leicester is soon reached; its spires tourist passes from one county to the and factories are seen from the line.

The railway ascends the valley of the the other. The line runs nearly Soar, and crosses the Wreke near to its junction with the Soar, and the windings of both rivers are seen; passing the quarries and kilns which produce the hydraulic lime of Barrowon-Soar, and the granite quarries of Mount Sorrel, a huge granitic rock described by Sedgwick as "an outlying boulder" resting on the clay. The line crosses the Soar a little beyond Barrow-on-Soar, and the foxhunting village of Quorndon on 1. The Charnwood hills are finely seen on 1.,

Loughborough Stat. is passed. train then runs on an embankment over Loughborough Moors, recrosses the Soar, and enters Nottinghamshire. After passing Hathern and

Kemporth Stat., with its fine spire on rt., and Kingston Hall, the residence of Lord Belper, also on rt., we approach the ridge of Red Hill, running E. and W. Here the line from Leicester is doubled, for passengers and goods. The Red Hill tunnel is 170 yards long, the N. end of the arch is flanked by towers and battlements of stone. On emerging from the tunnel the Trent is crossed. The scenery heareabouts is very fine, and continues so as we proceed to the

Trent Junct. Stat., from which there are two routes to Chesterfield, the most picturesque being that vid Derby and the beautiful valley of the Derwent, passing Ambergate, where the Amber joins the Derwent, and the Matlock valley opens very finely, and the line forks to right and left round Crich Hill, which blocks its due N. The more direct rte, of the course. express trains is up the Erewash valley, the beauty of which is by no means improved by its numerous coalpits and ironworks. The Erewash separates Derbyshire from Nottinghamshire, and the line frequently crosses the river from one county to

parallel to the Erewash canal for some miles, in some parts between it and the winding river. Several stations are passed, including that of Alfreton. or Alfred Town, said to have been founded by Alfred the Great, and presently after passing the smoky region of Clay Cross, Chesterfield is reached, and a good view is obtained of its paradoxical spire, concerning the inclination of which the the tourist may form his own opinion. The train now follows the direct line between Chesterfield and Sheffield. through varied rural, sylvan, and metallurgical scenery, passing Sheepbridge and Dronfield with their wellknown colleries, and through the Bradway tunnel; leaving Beauchief Abbey and Hall on the rt., the line runs parallel to the boundary line between Derbyshire and Yorkshire. and crosses it near the station of Heeley, a residential suburb of

SHEFFIELD Stat. (see Rtc. 44).

From Sheffield to Masborough. Rotherham and Swinton Junction, see Rte. 45.

From Swinton Junct. the Midland now runs directly to York in nearly a straight line. After leaving the Junct., the Don is followed for a short distance, and the train then suddenly emerges from the dark regions of coal pits, coke ovens, and ironworks to a pastoral plain, which continues to

Bolton-upon-Deane Stat., a bright clean agricultural village, contrasting curiously with those left behind. Similar thinly peopled district to

Clayton Stat. Wooded hills on rt., and pretty scenery on l.

Moorthorpe Stat. Undulating country of similar character to

Acknoorth Stat. (see Rte. 28). The

college is on L, but hidden by the! trees of the Park. The next stat, is

Pontefract (Rte. 28). Proceeding through pleasant country, and passing many liquorice plantations and some sections showing the remarkable depth of soil which favours this curious agricultural product, the train reaches

Burton Salmon Stat., and there going Rte. 2, and proceeds by it to York (Rte. 1).

ROUTE 2.

DONCASTER TO YORK, BY KNOTT-INGLEY.

Great Northern Rly. to Knottinglev. Thence the line to York is Yorkshire and N. Midland.

This was the main line of the Great Northern Rly. from London to York before the opening of the shorter line by Selby, described in Rte. 1. From Doncaster to.

1581 m. from London, Arksey (see Rte. 1), the lines are the same. Soon after leaving Arksey the present line curves westward. I, is passed Outston Church, E. E. (tower and chancel), with Perp. additions. A canopied tomb of the 14th cent., with fine

is now the exterior wall. The ch. contains a monument by Chantrey, for Mrs. Cooke (d. 1818), and some Munich glass. Remark, also, the bruss of Robert de Haitfield (1417) and wife (1409), both wearing collars of S.S. Adjoining is Owston Hall (P. B. Davies-Cooke, Esq.). Here, among other treasures, is preserved the original MS. of the Liber Landavensis, a book of documents relating to the Ch. of Llandsff, and compiled about 1131.

1624 m. Askerne. (The rly. from this stat. to Knottingley is the Lancashire and Yorkshire, with a right of passing over it for the Great Northern.) Here is a Spa of some local reputation. There is a small new ch., a tolerable Inn (the Swan), and lodgings are numerous. water is sulphureous, and is said to be useful in cases of gout and rheumatism, and in some forms of There is little cutaneous disorder. to attract the ordinary tourist, although the charms of the pumproom, and of Askerne Pool with its pleasure-boats, draw large occasional parties from Doncaster. The "Pool," covering about 6 acres, resembles that at Arksey, and has been considered the crater of an extinct volcano. Such hollows are, however, produced by water charged with carbonic acid gas, which dissolves the limestone. At the back of the village stretches the "Mount," a ridge of magnesian limestone, from which a good view is obtained, chiefly over the low country, eastward.

[The ch. of Campsall (2 m. W.) has a good Norm tower, the arches supporting which formerly opened into the nave-aisles, as well as into the nave itself. There are some Norm. portions in the transepts, and the chancel is E. E., but has perhaps been rebuilt with old materials. The nave is Perp., with fragments of earlier oak-leaf crocketing, remains in what work in it On the S. side of the

with a priest's room above it. The Pero. Rood-loft remains, and is remarkable for the inscription which runs along at the top of the panelling under the open arches. In the roundels above are the letters I.H.S. and M. The inscription is as follows:-

"Let fal downe thy ne and lift up thy hart; Behold thy Maker on yond Cros al to torn; Remember his wondis that for the did

Gotten without syn, and on a virgin born: Al his hed percid with a crown of thorn. Alas! man, thy hart ought to brest in too. Bewar of the devyl when he blawis his horn, And pray thy gode aungel convey the."

The "devil's horn" frequently appears in early paintings; and the 'Shepherd's Kalendar' has a poem headed. 'How every Man Woman ought to cease of their sins at the sounding of a dreadful horn. An inscription, nearly of the same date as this, and somewhat similar, runs round the nave of Almonbury ch., near Huddersfield-see Rte. 87.) In the chancel are some incised slabs (15th cent.); and in the S. aisle a curious inscription for Thomas Cleworth, vicar (died 1754), the donor of a library, which remains in the vestry. The books are chiefly theological, and of no great importance. Among them is an early copy of Sir P. Sidney's 'Arcadia.' The vicarage, adjoining, has been formed from a house dating early in the 14th cent.

In the parish are Campsall Hall (F.B. Frank, Esq.) and Camps Mount (G. C. Yarborough, Esq.). The grounds of Camps Mount contain same very large and fine cedars of Lebanon

The old North road, following the line of the Roman way (the Ermyn, or, as it was here generally called, the Watling Street—a good fragment of which may be seen close to the turnpike called "Barnsdale Bar"), runs, about 2 m. W. of Campsall, through

tower was a vaulted chapel (Dec.), lancient possessor), one of the favourite haunts of Robin Hood. The whole of this tract (now for the most part enclosed, and offering little that is picturesque) was anciently covered with forest, and afforded an excellent retreat to bands of outlaws and broken men, who "took their prev" from the passengers along Watling Street. (All the learning about Robin Hood will be found in the 2 volumes of ballads relating to him, edited by Mr. Gutch (London, 1847): in Mr. Hunter's pamphlet on Robin Hood; and in papers, by Mr. Gutch and Mr. Halliwell, in the 8th vol of the 'Journ. of the Archseol. Assoc.') The historical character of Robin is at least doubtful. The first writer who mentions him is Fordun, who, in the 'Scotichronicon,' dating from the latter part of the 14th cent., connects "that most famous cut-throat," Robin Hood, with this forest of Barnsdale, where he is said to have been hearing mass when word was brought him that his enemies were at hand. He would not stir until mass was concluded: but then easily put his foes to flight; and afterwards, says Fordun, held masses and the clergy in greater veneration than before—a fact, however, which did not prevent him from sundry attacks "on wealthy abbots' chests and churls' abundant store." Mr Hunter discovered the names of Simon and Robyn Hode among the "vadlets" or "porteurs de la chambre" of Edward II.: and considered the latter to have been the famous outlaw. Mr. Wright, with great probability, has suggested that Robin represents some mythical personage—a "Robin o' the wood," who was not distantly related to Robin Goodfellow; and this view is much strengthened by the fact that numerous mounds. stones, and wells are assigned to him throughout the whole kingdom. In another fashion he is no doubt the representative of the "salvage" men the district of Barnedale (probably (silvatici), who, as the chroniclers Beorns-dale, from the name of an tell us, abounded in the great English

Conquest, harassing the Normans in many ways; and the shape which this "gentlest of thieves" has taken in popular tradition was probably the slow growth of later centuries. Here in "merry Barnysdale," however, Robin is for us an actual personage. It was here, according to the ballad. that he caught the Bishop of Hereford and made him dance in his boots, after paying a heavy ransom. (This scene probably suggested that between Locksley and the Prior of Jorvaulx, in 'Ivanhoe.') Here Robin fought Guy of Gisborne, and killed him :-

"I dwell by dale and downe, quoth he, And Robyn to take I'm sworne, And when I am called by my right name I am Guy of good Gisborne.

My dwelling is in this wood sayes Robyn; By thee I set right nought; I am Robyn Hood of Barnésdale Whom thou so long hast sought."

Sir Richard of the Lee, whom the proud Abbot of St. Mary's, at York, would have spoiled of his inheritance, met Robin in the wood here, and was supplied by him with the 400l, needful to ransom his land :---

"When he looked on Bernysdale, He blys ed Robyn Hode. And when he thought on Bernysdale, On Scathelock, Much and Johan, He blyssed them for the best companye That ever he in come."

Robin himself, after he had been long detained in the King's court, sighed for the merry greenwood of Barnsdale:-

> " Me longeth sore to Bernysdale; I may not be therfro."

The only existing relic of the outlaw in this district (it was no doubt within the ancient Barnsdale, though not in the small tract now so called) is Robin Hood's Well, on the roadside, where the parishes of Kirkby-Smeaton and Burghwallis join. It is close to the highway; and may have been one of the springs at which, as

forests during the period after the hung brazen cups for the use of travellers. It was formerly the fashion for passengers by the coaches to alight here and drink of the water. "Drunken Barnaby" himself tasted it:-

> " Nescit sitis artem modi. Puteum Roberti Hoodi Veni, et liquente venâ Vincta catino catena Tollens sitim, parcum odi, Solvens obulum custodi."

"We all alighted at the highway," says Evelyn (1654), "to drink at a crystal spring, which they call Robin Hood's Well; neere it is a stone chaire, and an iron ladle to drink out of, chained to the seat." The building which now covers the well was erected at the beginning of last cent. by the Earl of Carlisle, from a design by Vanbrugh. It is cut all over with names and dates, the earliest being 1711. In the park of Skelbrook, opposite the well, is a spot called the "Bishop's Tree Root," marking the site of the oak round which the bishop performed his in-voluntary dance. The tree itself has quite disappeared.

The church (ded. to St. Helen) of Burgh Wallis (2 m. S. of Campsall) is chiefly E. E. and is remarkable for the entire absence of windows on the N. side of the nave. In the nave is a portion of a brass knightly effigy (circ. Hen. V.). There is no inscription; but it probably represents one of the Gascoigns, who were long lords of the manor. The little ch. of Skelbrook (on the Skel "burn," about 1 m. from Robin Hood's Well) is very rude E. E., and, like Burgh Wallis, has no window on the N.

side of its nave.]

1644 m. Norton Stat. [2 m. W. is Kirk Smeaton, where a small E. E. ch. with Perp. tower has been indifferently restored. The valley of the Went (Gwent, Brit., fair-the stream rises on the high ground S. of Wake-Bede tells us. Edwin of Northumbria field, and runs westward to the Don

turesque scenery in the neighbourhood. Smeaton ch. stands on the edge of the valley, the green sides of which are broken by "Smeaton Crage," projecting masses of magnesian limestone. Between Smeaton and Went-bridge (an old posting station on the great N. road), for a distance of about 2 m, the valley is called Brockudale (the "brock's" or badger's dale), and is narrowed to a glen. On the l. bank it adjoins Stapleton Park (- Barton, Esq.); and plantations have been made on this side of the glen, with green roads, and seats at the best point of view, above the crags of limestone. Patches of meadow open here and there along the sides of the sparkling Went; and a steep rough hill (on which are traces of entrenchments) rises opposite. The Brockadale drives are entered from the Went-bridge side; and in ascending from the bridge towards the entrance, wide views open over the wooded country S. W. 2 m. from Went-bridge, toward Ackworth, are the kennels of the Bedsworth Hunt.1

1661 m. Womersley Stat. spire of the fine Dec. ch. is seen l. It has been restored, and during the operations a very interesting crucifix, 16 in. by 10 in., was found under the chancel floor. Adjoining is Womersley Park (Lady Hawke).

The rly., beyond Womersley, is bordered by large quarries, worked in the magnesian limestone, here of great value for building-stone, as well as for burning. The smoke of many kilns sweep round the train as it reaches

171 m. Knottingley Junction, in the midst of a deep cutting. (Here the Gt. Northern and Lancashire and Yorkshire railways join. Our route follows as far as Milford Junction; rt. a branch line (Gt. Northern) passes to Snaith and Goole, Rte. 4; l. lines | after a fire, 1876, contains a very ex-[Yorkshire.]

at Goole) here offers the most pic-1 (L. and Y. and Gt. Northern) pass to Leeds by Pontefract, and to Normanton—the centre of a network of rlys.—see Rtes. 28 and 41.)

There is nothing to detain the tourist at Knottingley. The Aire and Goole canal (see Rte. 4) passes close to the town, and, together with the rly., offers great facilities for the convevance of lime from extensive Limekilns, building-stone, &c. Chemical works, roperies, &c., have been established here; and there are four ship-building yards.

A short distance beyond Knottingley the rly, crosses the river Aire, a little above Ferrybridge. This was the principal pass on the river. present bridge dates from the last cent.: but Leland describes a more ancient one of 7 arches, which was perhaps existing when, March 28, 1461 (the day before the decisive battle of Towton), a fight took place here between Lord Fitzwalter, who had advanced from Pontefract where Edward IV. was present, and the Lancastrians, under Lord Clifford (the traditional murderer of the young Earl of Rutland at Wakefield; see Rte. 38). Early on the morning of the 28th Fitzwalter heard the noise of a sudden attack, and rose out of his bed, taking a pole-axe in his hand: but, before he knew what was the matter, he was slain. himself, a few hours later, met, not far from the same spot, with a similar fate from a chance arrow. Fitzwalter, according to Monstrelet, was uncle to the Earl of Warwick, who, when he took the news of his death to Edward, is said to have stabbed his horse in the king's presence (in token that he would "do or die"), and then, kissing the cross-hilt of his sword, to have sworn vengeance.

1 m. N. from Ferrybridge is Fryston Hall (Lord Houghton), in a wellwooded park. The house, restored tensive Library; some interesting family portraits by Gainsborough, Lawrence, Wright of Derby, Romney, -the 2 dogs by Landseer.

Rt. of the rly. is Brotherton, where Margaret of France, second queen of Edward I., "by chaunce laboring as she went on hunting," brought into the world (June 1, 1300) her first child, the prince known as Thomas of Brotherton, afterwards Earl of Norfolk and Grand Marshal of England. She had invoked St. Thomas of Canterbury in her trouble. Hence the name. The house in which the prince is said to have been born, stood, says tradition, not far from the church, which is of some interest.

174 m. Burton Salmon.

[4 m. E. of Burton Salmon is the ch. of Birkin, which the antiquary should by no means leave unvisited. The manor of Hurst (afterwards Temple-Hurst, 5 m. E., near Snaith, see Rte. 1) was granted to the Templars in 1152, by Ralph de Hastings; and it was under their influence that the existing church of Birkin seems to have been built. It is Norman, with the exception of the S. aisle and the upper part of the tower. The S. aisle is late Dec., temp. Edw. III.; and the original Norm. S. portal has been removed and rebuilt in it. This is much enriched with different mouldings; the devices in the outermost (the pellet) moulding being much varied. Similar mouldings ornament the exterior or the windows of the eastern apse, which, with the short choir, form the chief feature of the interior. Both are Norm. The arch into the choir is more enriched than that opening to the apse. On either side of the choir is a round-headed window, with shafts at the angles. The apse has three Norm. windows, of which that in the centre is filled with Dec. tra-

rise between the windows, and support the groining. In the N. wall of the nave is a remarkable monument. "It is a recumbent figure, cross-legged, but unarmed, with the hands closed in prayer, bare-headed, and habited in a loose robe, bearing no insignia of rank or order, and tempting the suspicion that it is a penitential garment."-G. A. Pools. Birkin ch. must date soon after the establishment of the Templars here: and differs, in the arrangement of its choir and apse, from the many small Norm. churches, existing wholly or in parts on this side of Yorkshire.

There are no remains at Templehurst. 7

The rly, proceeds through the rich vale of York-a level and wooded district, here without much interest for the tourist. It reaches at

176 m. Milford Junct. Stat., where the rlv. between Leeds and Selby (Rte. 42) crosses the Great Northern. (2 m. W. is Steeton Hall, a 14th cent. manor-house (now a farmhouse), remarkable for the numerous shields of arms on the gateway, and for an E. Eng. chapel, now divided into ordinary apartments. In that used as a dining-room the piscina remains.)

1772 m. is Sherburn Stat. The ch. (restored), with a plain and massive Norm. nave, worth notice, is seen 1. The S. doorway is also Norm., but has been removed from its original position and rebuilt. The arch is now pointed instead of circular, and shields of arms have been introduced instead of the original caps of the The ch. is said to have shafts. been partly built from the ruins of a palace which the Abps. of York had here, the foundations of which exist in a field called the Hall Garth. According to a local tradition Edward IV. ascended the tower of Sherburn Ch. the day before the battle of Towton. There was a sharp cery. Piers with enriched capitals skirmish at Sherburn (Oct. 15, 1645)

between the King's forces and those Parker, rector, between 1411-1423. of the Parliament: in which Sir Richard Hutton and many others on the king's side were killed. Lord Digby's "coach" is said to have been taken on this occasion at Milford: and the slain were interred there. The Royalists had the same morning taken 800 Parliamentarians, "laying their arms in a great heap in the street of Sherburn." These were now recovered, with " much rich pillage." Sherburn and its neighbourhood are famous for a plum called the "wine-sour," which makes an excellent preserve. Passing Church Fenton ch. rt., we reach

180 m. Church Fenton Junct. Stat. (Saxton, the scene of the so-called battle of Towton (Rtc. 43), is 2 m. W. and is best visited from this stat.) Here a line branches I. to Harrogate, by Tadcaster (see Rte. 43). Passing

182 m. Ulleskelf Stat.—[1 m. rt. is the E. E. ch. of Kirby Wharfe, restored as a memorial of the late Lord Londesborough of Grimstone Park1-

1831 m. Bolton Percy Stat. is Here the ch. deserves especial notice. It is fine Perp., with a noble 15th cent. window of stained glass.

Bolton Percy was one of the manors granted by the Conqueror to William de Percy, founder of the great house The ch. was of Northumberland. granted by one of his descendants to Nostell Priory; but was transferred at the Dissolution to the Abp. of York, in whose patronage it remains. (A wood at Bolton Percy is recorded in the Domesday Survey, and it was from it that, according to tradition, the Percys made their principal grant of timber for the building of York Minster.) The living is worth 1540L a year, and is the best in the gift of the Abp. The existing fine On the monument is a long and pom-Perp. Church was built by Thomas pous inscription, in which Lord Fair-

The whole is of this date, with the exception of the upper part of the tower and the wooden porch. The chancel is especially good; and is remarkable for the "excellence of its workmanship and the grace of its proportions." The original open roof, simple but very graceful, remains. The sedilia and piscina, S, of the altar. should be noticed. The matrix of a brass representing the Crucifixion. with a kneeling figure at the side, remains at the back of the central sedile. Thomas Lamplugh, who became rector in 1715, repaired the church, and collected into the chancel much of the stained glass scattered through different windows in the edifice. This remained untouched until Archdeacon Creyke, in 1866, restored the figures in the great E. window, which had been more or less shattered. This window, of five lights, is unbroken by a transom, although it is 23 ft. in height and 14. broad. It contains 5 full-length and life-sized figs. of Abps. Scrope, Bowet, Kempe, Booth, and Neville. are their shields of arms; and above are life-sized figs. of St. Peter, St. Anna, Mother of the B. Virgin, the Virgin Mary, Elis., mother of John the Baptist, and St. John the Evangelist.

The chancel has been reseated at the cost of the same rector, who has also filled the six side windows with modern stained glass. The nave, unusually for a Perp. church, has no clerestory. One of the chancel piers has been cut away to make room for the ponderous Monument of Ferdinando, Lord Fairfax, who died at Denton 1647, who commanded the Parliament's centre at Marston Moor. and was father of the more famous Sir Thomas Fairfax, afterwards Lord Fairfax—the "Black Tom Fairfax" of Yorkshire tradition and General-in-Chief of the Parliamentary forces.

fax is called "humanitatis repumicator." In this church, Sept. 15, 1657, George Villiers, Duke of Buckingham (the hero of Dryden's famous verses), married Mary, daughter of Sir Thomas (then Lord) Fairfax. Cowley the poet was the Duke's best man, and wrote a sonnet in honour of the occasion. The original seat of the Fairfaxes in Yorkshire was at Walton, near Thorp Arch.

Nun Appleton Hall (Sir Fred. Milner, Bart.), in this parish, was the seat of General Lord Fairfax, the hero of Milton's sonnet,

——"Whose name in arms through Europe rings, Filling each mouth with envy or with praise, And all her jealous monarchs with amase, And rumours loud, that daunt remotest kings."

A nunnery was founded here by Adeliza St. Quintin in the reign of Stephen, and on the Dissolution the site was granted to Fairfax of Steeton. His eldest son inherited it, and it became the favourite abode of the great general, who completed the house here which had been begun by his grandfather. This was a mansion of red brick, with a centre and two wings at right angles. There was a large park with fine caks and 300 head of deer. Here Lord Fairfax, after his retirement, amused himself with his library, and a large collection of coins, medals, and engravings. Hence he opened communications with Monk for the restoration of Charles II. Here he entertained that general and his officers at a banquet in the gallery, and from the splendid stud which he maintained here he provided the horse on which Charles rode at his From this place he coronation. married his daughter (described by Madame de Longueville as "a little round crumpled woman very fond of finery") to the Duke of Buckingham. Here his wife, daughter of

Horatio Lord Vere, died, 1665the heroic lady who interrupted the court at the trial of Charles I.; and here he died himself, Nov. 1, 1671. He was buried in Bilborough church (l. of the rly., but not seen from it), where the altar-tomb of himself and his wife, enriched with shields of arms and bearing a simple inscription, remains on the S. side of the chancel. Andrew Marvell, the poet, was for some time a resident at Nun Appleton, whilst giving "some instructions in the languages" to the future Duchess. He has a poem entitled 'Appleton House,' and another Before the hill and grove at Bilborough.' Lord Fairfax, according to Marvell, laid out his gardens in the figure of a fort,-

"The sight does from their bastions ply The invisible artillery; And at proud Cawood Castle seems To point the battery of its beams, As if it quarrelled in the seat The ambition of its prelate great."

Nun Appleton passed to the Duchess of Buckingham after her father's death, and at her death it was sold to Alderman Milner of Leeds, whose descendant now possesses it. The house has been much altered, the wings pulled down, and large additions made, but the old north front is yet standing.

(At Appleton Roebuck, in this parish, a good modern church has been built.)

The same rich level country extends on each side of us as we pass

187 m. Copmanthorpe Stat. (The name, "kaup-manna" thorpe, signifies "the merchants' village," and marks a settlement of Danish traders.) Soon the towers of the great Minster come into view; and through a breach in the old city walls we enter

191 m. York Stat. (See Rte. 1.)

ROUTE 3.

LONDON TO HULL, BY DONCASTER, THORNE, AND GOOLE.—HATFIELD CHASE.

For the line from London to Doncaster see Rte. 1. From Doncaster a branch of the North-Eastern Rly. is followed. There are 7 trains daily. The journey is performed in about 1½ hr.

The rly., leaving Doncaster and proceeding through a rich, level country, follows nearly the line of the river Don, which has here been canalised, to

Barnby-on-Don Stat., where is a ch. of some interest, restored. At

Kirk Bramoith (13 m.), the church has a Norm. S. door, with a very fine example of beak-moulding. The chancel arch is Norm., the tower early Dec.

Stainforth Stat. Here a canal stretches across by Thorne and Crowle to Keadby on the river Trent. It is still extensively used, although the rly. follows nearly the same course. All this country is thoroughly Flemish in character; and the canals, with their steep green banks and still waters, reflecting every tree and quaint building, are the precise

counterparts of those which stretch away from the gates of Bruges or of Ypres.

[2] m. S. of the Stainforth stat. is the little town of Hatfield (Pop. about 2000) lying in the W. part of Hatfield Chase, about 6 m. (by high road) from Doncaster. The ch. ded. to St. Lawrence-is large, and occupies the site of one which existed here at the Domesday Survey. contains some Trans. Norm. portions (at the W. end), and has a large E. Eng. S. porch, but is for the most part Perp. The tower is central; and on it is the shield of Sir Edward Savage, who was keeper of the park at Hatfield under Henry VII. There are no monuments of importance.

Thomas of Hatfield, Bp. of Durham (1345-1381), was a native of this place.]

Hatfield Chase is a portion of the district called "the Levels," extending into Lincolnshire and Nottinghamshire. The "Level of Hatfield Chase," of which the boundaries are roughly marked by the courses of the rivers Idle, Torne, and Don, contains about 70,000 acres, the greater part of which, before the drainage of the district by Cornelius Vermuyden in the reign of Charles I., was constantly under water. Large tracts of the level, however, were, and still are, covered with turf-several yards in depth in some places, in others only a few inches. "When the turf is removed, a natural mould is discovered, like that of the surrounding country; and a native of these regions, who had often watched the labourers on the moors, avers that he has seen the land beneath the turf lying in rig and furrow; as if, before the turf collected upon it, it had been submitted to the higher operations of husbandry."-Hunter. This turf, before the drainage, was so soft that a pole might easily be thrust into it; and oaks and fir-trees of large size are

and the Myrica gale (bog-myrtle), besides heath and fern, grow thickly over these moors; which, since the drainage, have been diminished by enclosures and plantations, and by "warping" portions of them. (For the process of warping see post, Thorne.)

Hatfield Chase is no doubt the "Hethfelth" of Bede - the scene (A.D. 633) of the battle between Edwin the first Christian King of Northumbria and the fierce heathen Penda of Mercia. "There is an obscure tradition that the battle was fought near the present town of Hatfield, and that the blood of the slain flowed from the place called 'Sleybur-hill Slack' to the thresholds of the inhabitants."—Hunter. Edwin was killed in this battle; and his head was afterwards brought to York. and placed in the "basilica" he was building there at the time of his death. (See Rte. 1, York, Minster.) After the Conquest, the great Earl of Warrene (whose remains have been found at Lewes in Sussex), received Hatfield and Conisborough, both of which had been part of the lands of Harold; and his successors held them till the reign of Edward III. Hatfield then came to the Crown; and the Chase remained Crown land until it was granted to Vermuyden. The Earls of Warrene, and the English kings after them, had a hunting-lodge with a park of 500 acres close to the town of Hatfield; and it was here that William of Hatfield, 2nd son of Edward III. by Philippa, was born, 1336. (He died young, and was buried in York Minster: see his monument there.) Here also was born Henry, eldest son of Richard Duke of York, in 1441. Edward Balliol, after surrendering (1355) his rights as King of Scotland to Edw. III., lived for some time at Hatfield; and (either at that time or when he was in England

frequently found in it. Cotton-grass | hunted and fished without liberty in the park and ponds, for which he was afterwards pardoned by Edward. -Rymer, iii. 341. The Lodge or Palace was, says Leland, "meanly builded of timber," and there are still some scanty remains of it. Henry VIII. remained here a day or two during his progress in Yorkshire in 1541, and hunted in the park: and De la Pryme gives a curious description of a day's hunting here in 1609, in the presence of Henry Prince of Wales, when 500 deer took to the water, and were pursued by "a little royal navy" of 100 boats, which "ventured among them, and, feeling such and such that were fattest, drew them to land and killed them." Before the drainage, deer are said to have been as plentiful in Hatfield Chase as "sheep upon a hill;" and the fisheries, including those of eels, were most valuable and productive.

The Drainage of Hatfield Chase was undertaken in 1626 by Cornelius Vermuyden, a Dutch engineer of eminence, who had already been very successful in his operations at Dagenham on the Thames, and in draining Windsor Park. Vermuyden and his partners in the adventure obtained a grant of one entire third of the lands to be recovered from the waters. Many Dutch capitalists joined him; and he was enabled to engage a great number of Dutch and Flemish workmen, some of whom were exiles in England; French Protestants from Picardy, and Walloons from Flanders.

About 24,000 acres were recovered by Vermuyden and his foreign labourers, but not without serious opposition during the progress of the works from the people of the country, gentle as well as simple, who beat, wounded, and even killed some of the workmen, broke down the embankments, demolished the floodgates, and checked the works. before the capture of David Bruce) For a long while it was found necesspot to protect the enclosures and the houses of the Dutch settlers, who lived for the most part in isolated dwellings, dispersed through the newly-recovered country. 1642, in consequence of a rumour that Sir Relph Humby, the Royalist, was about to cross the Don and to merch into the Isle of Axeholm. the Parliamentarian Committee at Lincoln gave orders for breaking through the dykes in the Hatfield This was done; to the delight of the neighbouring population, whose great cause of complaint was that the foreign settlers had robbed them of their rights of common. Damage amounting to no less than 20,000L was inflicted on the strangers in a single night. The people who carried out the orders of the Committee "levelled the houses of the settlers. destroyed their growing corn, and broke down the fences; and when some of them tried to stop the destruction of the sluices the rioters stood by with loaded guns, and swore they would stay until the whole levels were drowned again, and the foreigners forced to swim away like ducks."-(Smiles' 'Lives of the Engineers,' i. ch. 3, where will be found an excellent account of the whole undertaking.) Even when the drainage was effectually finished, it gave rise to so plentiful a crop of lawsuits and to such long-continued litigation that the projector and ingenious executor is said (after having also completed the drainage of the Great Level of the Fens in Norfolk and Cambridgeshire) to have died ruined and in gaol. levels brought into cultivation now produce as abundant crops as any part of the Fens of Lincolnshire, though parts of this district are as much as 8 feet below high-water mark.

Many Dutch and Flemish names still remain in this district. Among

sary to station a military force on the spot to protect the enclosures and the houses of the Dutch settlers, who fied from Ypres before the Duke of Alva; and whose descendant made collections for a lated dwellings, dispersed through the newly-recovered country. In value. (See post, Thorne.)

In the centre of the great turf moor, S.E. of Hatfield, is Lindholme, an arable tract of about 60 acres, slightly raised above the level. It is still a perfect solitude; and before the drainage was one of the keepers' stations. Here a certain William of Lindholme, half giant, half hermit, is traditionally said to have lived; and to have brought here two large boulder - stones known as the "Thumb Stone," and the "Little Finger Stone"-which lie near the only house on the holme. This house is modern; but it has replaced a remarkable cottage, framed in timber ("stud-bound"), with a raised space at the E. end, on which stood an altar. Toward the west was a large flat stone, under which remains of a human body, some hemp-seed, and a small defaced coin, were found in 1727. There can be little doubt that the place had been the abode of recluse, who, like St. Robert of Knaresborough, had been buried within the enclosure of his cell.

Drayton thus notices the supposed rising and falling of the marsh-land with the rise and fall of the neighbouring rivers:—

"Whose soil, as some reports, that be her borderers, note,

With water under earth undoubtedly doth float; For when the waters rise it risen doth re-

For when the waters rise it risen doth remain, High while the floods are high, and when

High while the floods are high, and when they fall again It falleth."

The swelling and bursting of a peat-bog in wet weather is a well-known and very serious occurrence.

[1 m. N. of the Stainforth stat.,

which there is a ferry, is

The fine ch. of Fishlake (which ecclesiologist should by no means leave unvisited). Fishlake is so called from a deep hollow in the marsh-land, extending into what was once a lake which abounded in fish. It is said to have been one of the places at which the body of St. Cuthbert rested during its wandering; and for this reason the church may have been ded, to that It was originally erected saint. about the beginning of the 12th cent. by the powerful family of Warrene, who were lords of Conisborough and of Hatfield Chase from the Conquest until 1346 (20th Edward III.). The ch. in the village of Hatfield was the only one within the limits of the Chase until the Warrenes built others at Fishlake and Thorne. The ch. at Fishlake, with that part of the Chase which lay N. of the Don, and was assigned to it as its "parochia," was granted by the Warrenes to their priory at Lewes; and continued in possession of that house until 1372; when, together with other churches, it was resigned to the Crown in compensation for the "naturalisation" of Lewes Priory, had which hitherto been alien, and dependent on Clugny. In 1387, Richard II., at the instance of Thomas of Hatfield, Bp. of Durham, who had died in 1381, settled Fishlake on the new college (then "Durham," now Trinity College) at Oxford, which the prior and convent of Durham had just founded. At the Reformation. Fishlake reverted to the Crown. and was given by Henry VIII. to the Dean and Chapter of Durham, who still hold it.

The size and beauty of the ch. sufficiently prove the wealth and resources of its several possessors. It is built throughout of stone, which must have been brought up | (This, however, can hardly refer

on the l. bank of the Don, across the River Don at no small cost. The S. portal, very fine enriched Norman, of about the same date as that at Iffley, is of course part of the Warrenes' ch. It is of four The outer circle of ornaorders. ment has been thought (but this is very uncertain) to represent the session of the righteous in glory; the figures are arranged in pairs, within oval compartments. inner circles contain animals and leaf-like ornaments. The capitals of the shafts have grotesques and other subjects not easily interpreted. The nave piers and arches are Transition (E. E. to Dec.), with a fine and lofty Perp. clerestory above them. The Western Tower (Perp.), with a noble W. window of 5 lights. has arches opening N. and S. to the nave aisles, and closed halfway up with solid stone screens. The Roodacreen, dating about 1500, remains in its original position, and has been repaired by the Dean and Chapter of Durham, the restorers of the The lower part of the chancel. chancel seems to be Dec.; but the clerestory has been copied from that of the nave, and is of the time of Henry VII., as are also the chantries at the E. end of the nave aisles. The font (Perp.) is octagonal, with niches containing figures of saints (among them St. Cuthbert), of Pope Gregory the Great, and of two archbishops, St. William of York and St. Wilfrid, distinguished by the The bosses underneath the pall. bowl represent each an angel bearing an infant in his arms.

In the chancel is the altar-tomb of Richard Marshall, vicar (1496-1505). The brasses have been removed; but Dodsworth served the inscription, part of which ran-

" The VI. vicar of this church, of good fame without rage.

In whose time this chancell and vestry bildite was."

almost certainly older.) The un- for the history of this district, was usual ornaments of the tomb deserve notice. In the front are the symbols of St. Anthony (a tau cross and two bells), between the words " Jesu Mercy," " Lady Help."

In a niche on the W. side of the lofty Perp. tower appears St. Cuthbert, carrying in his right hand the head of St. Oswald. (The 2 natron saints of Durham were frequently thus represented.) Remark the fine pinnacled buttresses marking the division between the nave aisles and their eastern chantries: and the north porch in the nave opening through the broadened base of a buttress.

The ch. of Fishlake rises grandly over the Level, of which it is one of the great landmarks.]

11 m. Thorne Junct. Stat. Inns: Red Lion; White Hart. An active market-town, carrying on considerable trade in corn, coal, and timber. The Don runs about a mile to the N.W. of the town, and on it is situated the Quay called the Waterside, resorted to by sailing vessels, and, when the tide permits, by steamers from Hull. This is the steamers from Hull. port of Thorne. Ships are built here, and at Hangman's Hill (about 1 m. from the town, so called because some of the men who destroyed Vermuyden's sluices were executed here). Part of Vermuytown of Thorne. The ch., founded like that of Fishlake by the Warrenes, is small, very late Dec., and of no great interest. There was a small peel or castalet at Thorne, which was used as the prison for offenders in the Chase. This has disappeared; but the mound on which it stood still remains, planted with ash-trees. De collections (preserved among the Barnetby to Great Grimsby. For

to the piers and arches, which are | Lansdowne MSS. in the Brit. Mus.) (1701 - 1704) perpetual curate of Thorne. To the E. of the town extends a wide Turbary or turf-moor. occupying an area of 6800 acres: large quantities of peat are cut from it and exported in barges along the canals and drains to York and Hull. The bog encloses the remains of a buried forest; and large trees, oak, ash, beech, &c., from 60 to 120 ft. long, have been dug up here, and from the excellent preservation of the timber have been sold for 5l. or even 15L each.

Extensive tracts lying between the Ouse and the Trent have, since 1825. been converted from heath and morass into profitable pasture and arable land by the process of warping (A.-S. weorpan - to turn aside, and it is still going on with success to the E. of Thorne, on the borders of the Trent, near Keadby. The contents of these rivers are apparently "half mud, half water, and turbid enough to suffocate the fishes." The earthy matter is washed down from the high grounds. When the waters are most heavily laden the landowners on the banks open the sluices, let in the flood, and retain it until it has left behind its fertilizing ooze. From 3 to 6 or more feet of rich black vegetable mould thus deposited, so fine that the whole might pass through a sieve. Three years of warping generally suffice to convert the most barren den's house is still standing in the lands into fields teeming with fertility, clothed with clover, or growing the richest crops of wheat, beans, potatoes, and flax. A similar process, known as "colmate," has been for some time used with great advantage in the Tuscan Maremma, and in other districts of Italy.

(From Thorne another line of Railway (S. Yorksh. and M. S. and L.), Abraham runs by Crowle to Keadby where it la Pryme, who made large crosses the Trent; and thence by

Lincolnshire.)

Leaving Thorne, and skirting Thorne Waste, the train, in 1 hr., reaches

Gools (Inn: the Lowther Hotel), on the Ouse, a port of increasing importance, situated a little above the point where the Ouse and the Trent unite to form the Humber (Pop. in 1881, 10,339). A pier and docks have been constructed here by the Aire and Calder Navigation Company, the proprietors of the Knottingley and Goole Canal, which, however, since the formation of this railway and of that from Knottingley (see Rte. 4), is but little used. Fruit and vegetables in great plenty are imported here from Antwerp and Rotterdam, and find their way from Goole into the centre of Yorkshire. Iron and cloth are the chief exports; and much Yorkshire building-stone is conveyed hence to different parts of England and the Continent. A large ch., more pretentious than good, with a lofty spire, has been built here by the Company.

The canal terminates in a basin and 2 capacious Docks, one of them capable of admitting vessels of 300 tons burthen, communicating locks with the Ouse; finished in 1838. The New Dock, calculated for steamers, 6 or 8 of which ply between Goole and Hull, is entered by a lock 200 feet long and 58 broad. Large warehouses and a timber-pond have erected contiguous to the Docks. The sum expended by the Company on these and other works connected with the navigation exceeds

one million sterling.

Steamers run daily from Goole to Hull in 2 hours. There are also small steamers to Antwerp and Rotterdam (twice a week), and one to Dunkirk weekly.

these places see the Handbook for | and on the left bank of the old Don, are successively situated the three parishes of Swinefleet, Whitgift, and Adlinfleet, nearly every acre of which has been converted by the process of warping (see ante) from a black, goose-feeding marsh to a land rich in corn and grain crops. In the last parish, which appears to the eve of the unfrequent stranger like the Ultima Thule of Yorkshire, has been established an excellent commercial school by the charity of Madame Mary Ramsden; the head-mastership being in the gift of the Master and Fellows of Catherine College, Cambridge.]

> Crossing the Ouse at Goole, the rly. enters the East Riding. the bank of the river, surrounded by trees, is Saltmarshe Hall (Philip Saltmarshe, Esq.). This is one of the most ancient families in Yorkshire, and has been settled at Saltmarshe probably from a period before the Conquest.

There is a station near the village of

Saltmarshe (which is in the parish of Laxton: the church is a bad modern building); and at the next station,

Staddlethorpe, the line of the Selby and Hull rly. is joined.

The railway crosses the Warping Drain and the Market Weighton Canal, which falls into the Humber opposite the confluence of the Trent, before reaching

Brough Stat.

The ferry here, over the Humber, to Winteringham and Ferriby Sluice in Lincolnshire, is as old as the time of the Romans, being on the line of their great highway, the Ermin-street.

The antiquary will find it worth while to drive from Brough across [Below Goole, in a district lying the country to Market Weighton, between the rivers Ouse and Trent, 12 m. (or 14 by N. Cave). The churches of North Cave and North; mattress. In the window of the Newbold are of great interest. The landscape is not very picturesque. Low chalk hills lie rt. of the road.

The Church of Elloughton, seen rt., is modern, rebuilt, except the tower in 1846. Ellerker, l., is interesting as the place at which Robert Aske was visiting his cousins when the news reached them of the rising (the Pilgrimage of Grace) Lincolnshire, and Aske was chosen here as the leader of the Yorkshire insurgents. On the hill rt. is Thorpe Hall (C. Sykes, Esq.), a large Elizabethan mansion. South Cave, 3 m. from Brough, is a long straggling village, with a church of some interest and of various dates -Trans., Norm. (chancel arch); E. Eng. (arch opening to a transeptal chapel, S. side of nave), Dec. (chancel and arches into N. chancel arch, now closed), and Perp. (arcade of nave, and tower). The church has been restored, and there is some modern stained glass. Close by is Cave Castle (Mrs. Barnard), a turreted mansion, with some ancient portions. The legend that the family of Washington was established here, and that the great-grandfather of the famous general was born here, has been entirely disproved. The church of North Cave, 11 m. W., is more important. This is throughout E. Eng., of remarkable size and uniformity, consisting of W. tower, nave, and aisles, transepts opening from aisles, and chancel. The nave piers are circ. with plain caps, and above is a 3-light clerestory. At the end of the nave proper is a high arch opening to the crossing, and beyond again is a second arch opening to the chancel, which is perhaps of a little later The lower part of the tower is E. Eng., the upper Perp. All the ceilings are modern. On the N. side of the transept is the monument of Sir Thos. Metham, temp. Eliz.—the effigy is in armour on a rolled of Sir Philip Monckton, the Boyalist,

S. side is the alabaster effigy (Jacobean), of a lady, also a Metham; and on the floor is a curious inscription :---

> "My Father a North Briton, My Mother Rutlandshire; From Dublin I their son. Hugh Montgomery, Esqr, When my race is run, Shall rest me in this choire. In hope, as he began, God will raise me higher." ÆT. 68. A.D. 1748.

The hall of the Methams, who formerly held the manor, was close to the church, but has disappeared.

Hotham Hall (Col. Clitherow) lies N. of the village. There is some curious Norm, work in the tower of Hotham Church. (Here was born John of Hotham, Bp. of Ely (1316-1337) and Chancellor-who founded a chapel in this his native place.) On the side of a steep hill at Drewton, in the par. of N. Cave, is a huge boulder-stone 12 ft. high, which is known as St. Augustine's pulpitand of course the Druids have been found in the name "Drewton." At North Newbald (2 m.) we regain the direct road from Brough. Here is a very remarkable Late Norman church, with some unusual features. It has nave, central tower, transept, and chancel, and is without aisles. The tower rests on 4 lofty and wide arches, with attached shafts and scolloped capitals. The E. and W. arches are ornamented with zigzag, and have a roll-moulding in the The transept windows (East) are wide-arched, with zigzag, and have Perp. tracery inserted. In the S. trans. (South) is an E. Eng. triplet. The chancel has been restored, and has Perp. windows. On the N. side is a small Early Perp. chantry, with the base of the altar remaining under the East window. Against the chancel wall is a tablet to the memory

born at Heck, near Howden, present at Marston Moor and at Naseby, and active in all ways for the king. He was arrested and confined by Cromwell; died in 1678, and was buried at South Newbald, where he was lord of the manor. The Norm, windows of the nave are high in the wall, with wide splay. The font is almost E. Eng. On the exterior the church is much enriched. The transepts have portals with zigzags. The portal of the S. porch has much rich moulding, and above in a vesica is our Lord in Majesty, all covered with whitewash. There are curious corbel tables in nave and chancel, with heads and grotesques, one being a fox covering his eyes with his paws. The tower is very massive, with an E. Eng. stage. N. Newbald was attached to York Minster from an early period. Between N. New-bald and Market Weighton the road passes through the village of Sancton, in a rather pretty valley. is a small ch., rebuilt, except the tower, in 1869-70. The Perp. tower is good. Separated by a low wall from the churchyard is a R. C. burying-ground, with a small open shrine or chapel at the end, with a Pieta-(the Virgin supporting the body of our Lord)-and a small lamp burning before it. Near is Houghton Hall, (C. Langdale, Eq.) with a R. C. chapel. For Market Weighton, see Rte. 8.]

Leaving the station at Brough, we pass, 1., under the chalk hills, Mellon, where, towards the end of the 13th cent. William of Melton, Archbp. of York (1317-1340) was born. The church of Melton, seen 1., is E. Eng., and has been restored.

The estuary of the Humber, backed by the Lincolnshire hills on the S., now begins to open to view; while on the N. the elevated outline of the Yorkshire Wolds is seen stretching down to the river, near

294 m. Ferriby Stat. (The church of North Ferriby was rebuilt in 1848. It is of Early Dec. character, and has many stained-glass windows.)

The railway, passing to the S. of Hesslewood House (J. W. Pease, Esq.), reaches the water-side, and is carried for a considerable distance along its margin. The river here bears the aspect of a large lake, its surface occasionally enlivened by the smoke of a steamer, or a passing sail. All view is for a time intercepted by a deep cutting through Hessle Cliff, a chalk hill, the extreme limit of the Wolds, at

321 m. Hessle Stat. The church has E. Eng. (N. and S. portals), Dec. (S. aisle with good windows), and Early Perp. portions. (Steamers 4 times daily to Barton, Lincolnshire.)

[Barton Church, 3 m. beyond the ferry, has a remarkable Saxon tower. The rest of the ch. is Perp. and of little interest. See Handbook for Lincolnshire.]

Near this are several neat villas, together with chalk-pits, limekilns,

and whiting-mills.

The rly. is carried along the margin of the Humber, here more than 2 m. broad, upon an embankment of chalk, nearly a mile long, and soon comes in sight of Hull and its forest of masts. The fields and garden-gates on the approach are not unfrequently decorated with huge jaw-bones of whales, trophies of the whale-fishery, of which Hull was long the principal seat.

The railway is joined 1. by that from Beverley (Rte. 8), near the Lunatic Asylum, and soon enters

Hull Junct. Stat. (Paragon Stat.)

[There are two radicons stations at Hull. The Paragon Stat., near the W. entrance of the town, whence trains leave for loncaster and toole (the present route). Selby litt.

1), York, by Beverley and Market Weighten

(Rtc. 8), Bridlington, Filey, and Scarborough by Driffield (Rtc. 9), and Malton by Driffield. From this station also trains leave Hull for Withernsea (Rtc. 6) and Hornsea (Rtc. 7). The Victoria D de station is at the east end of Hull, and is used for the railways which connect Hull with London and the Eastern Counties through Lincolnshire. It is also in connection with the Hornsea and Withernsea riys. (All trains, however, on these two rlys. start from the Paragon Stat., and the connection from the Victoris Stat. is at South-coustes.)

Hotels.—Royal Station (best), entered from the Paragon Stat. (good and comfortable). Victoria, close to docks and pier. Minerva also near the pier.

Stemmers.—To Aberdeen in 27 hrs.; to Amsterdam; to Antwerp (Wed. and Sat.); to Bremen; to Christiansund and Christiania; to Chymhagen; to Dundee; to Dunder; to Bamburg (Turs. Thurs. Sat.); to Londom; to Lynn; to Newcastle; to Rotterdam; to Steltam; to St. Petersburg (weekly); to Yarmouth. There are also steamers to Gaine-barough, in 3½ hrs.; to Goole in 2 hrs.; to Grimaby in 1½ hr.; and to York, in 6½ hrs. The starting-places and times of sailing of all these steamers are duly advertised, and may generally be found in Bradshaw.

There are Ferries over the Humber 4 times a day to Barton, and 6 or 7 times to New Holland and back, from Victoria Pier.

The chief objects of interest in Hull are— the Docks and the two Churches of Holy Trinity and St. Mary's. These may be essily seen in a long morning's walk from the Rly. Hotel. Turning into Carr Lane, the visitor will proceed through St. John St., at the end of which is the Wilberforce Memorial, and crossing the bridge between Queen's Dock and Prince's Duck should take the south side of Queen's Dock as far as the opening of Lowgate. Descending Lowgate, rt. is the Town Hall, and a little below, l., St. Mary's Church. The Market Place opens from Lowgate, and rt. is Holy Trinity Church. (A lane on the N. side of the ch. leads to Trinity House Lane, in which is the Trinity House.) Passing down the Market Place, the visitor who has time at his disposal may cross the South Bridge, near the mouth of the Hull River, and proceeding along South Bridge Road, visit the Victoria Dock. At any rate he should pass down Queen St. (in a line with the Market Place), and see the view of the Humber from the Pler. Here he will find himself close to the Humber Dock, the Rly. Dock, and the great Albert Dock, to each of which he may give as much time as he pleases. Cogan St., near the east end of the Albert Deck, and Upper Union St., opening from its, will lead him into Osborne St.; and

Midland St., at the W. end of Ceborne St., opens directly in front of the Rly. Stat. and the Hotel. (The places here mentioned are described at length post.) This route will take the stranger through the oldest and most interesting part of Hull. The best and newest streets lie N. of the docks and the rly.]

The town of Hull, or KINGSTON-UPON-HULL, ranking third in commercial importance and extent of shipping among the seaports of Great Britain (it is only surpassed by Liverpool and London), is situated on the N. bank of the broad Humber, at the junction of a small and sluggish stream, the Hull, which gives its name to the town. The Population, including the suburbs, Sculcoates, Drypool, and Lutton, was in 1871, 121,892; in 1881, 154, 250.

It cannot be said that Hull possesses much attraction for the ordinary tourist; but it is the great packet station for the North of Europe; and the larger part of the imports from Holland, Denmark, Norway, Sweden, Russia, and the Baltic, finds its way to this port. It is therefore a place of extreme bustle and activity; and the prospects from the sides of the docks, crowded as they are with shipping, are sometimes, under good effects of light, singularly picturesque and interesting The town first appears under the Scandinavian name of Wyke, which here probably had reference to its position on the river (vic = an inlet or bay); it was first called Hull temp. Rich. I.; and at length received the name of "King's Town" from Edw. I., who visited it in 1299, and must be looked upon as its real founder.

The ground-plan of the original "Kingstown" corresponds very nearly (making allowance for the irregular form of the ground) with that of the numerous "English town," called "Bastides," or "Free towns," "Villes franches," founded

by Edward I. in Guienne and l Aquitaine — a long parallelogram, crossed and recrossed by parallel streets, with a large open marketplace, adjoining which is the principal ch. New Winchelsea, also founded by Edw. I., was another English town of this class; and the situation of Hull closely resembles that of Leyburn or "Liborne," in Guienne, at the junction of the small river Isle with the Dordogne. said, like that of Hull, to have been expressly chosen by Edw. I. That town was named from its chief founder under the King, Roger de Leyburn (of the great Kentish family, and not of Leyburn in Yorkshire). King Edward is said to have been at Baynard Castle, near Cottingham (see Rte. 8), on his return from Scotland after the battle of Dunbar, when, whilst hunting, he was accidentally led to the hamlet of Wyke or Hull, and was struck with the advantage of its position. He at once purchased the site from the Abbot of Meaux (see Rte. 7), to whom it belonged, caused the new town to be laid out declared it free (that is, the tenure of the inhabitants was made direct from the Crown), and offered great privileges and immunities to all who would build and inhabit there. (See, for the free towns of Edw. I. in England and France, Parker's 'Domestic Architecture,' xiv. cent.)

Hull, however, did not become of great importance until after the decav of Ravenser and Hedon (see Rte. 6), which, owing to the waste caused by the sea, was already advancing when Edward I. visited the "King's town." Sixty years after, Hull had so far increased in prosperity as to be able to furnish Edward III. with 16 ships and 460 men, when the complement of London itself was only 25 ships and 662 men. The chief intercourse was always

use of brick in H. Trinity Ch. and in the ancient town walls, introduced from the Low Countries.

That the jurisdiction here was anciently somewhat strict, is evident from the traditional "thieves' litany,"---

> "From Hull, Hell, and Halifax, Good Lord deliver us.'

The Hull, on the rt. bank of which the town was founded, was at first its only harbour: on its margin are to be found the oldest houses and the most ancient streets. The extent boundary of the old town are pretty nearly marked by the course of the Hull, and the direction of the older docks (the Queen's, the Prince's, and the Humber), which occupy the site of the old walls. The space thus enclosed by the docks and the Hull, and converted by them into an island of nearly triangular shape, includes the most bustling part of the town and the best shops; outside extend long and monotonous lines of nest dwelling-houses of more recent The places to be noticed in Hull are the *Docks; the Churches of *H. Trinity and *St. Mary; the Trinity House; the Museum; the Town Hall; and the Dock Offices.

The most important features in the town are the Docks, which, though far inferior in extent to those of Liverpool, yet well deserve attention. The Hull river itself forms a natural dock, narrow, but thronged with vessels and lined with warehouses for a distance of 11 m. It is crossed by the South Bridge near its mouth, and about 1 m. higher by the North Bridge. A cut from the Hull leads E. into the new Victoria Dock. Another on the W. communicates with three other docks extending from the Hull to the Humber, and covering an area of 23 acres. Albert Dock opens from the basin of with the Hanse Towns and Flanders; the Humber Dock, and thus is in and the antiquary will note the early | direct communication with the Humr

ber itself. The visitor who desires across the Humber to the Lincolnto make a thorough examination of these docks had better proceed at once to the most eastern-the Victoria Dock-and so work westwards. No dock existed here until 1778. when what is now called the Queen's Dock was completed. The Humber Dock was opened in 1809, and the Prince's Dock, connecting these, in 1829. The Railway Dock was opened in 1846, the Victoria Dock in 1850, and the Albert Dock in 1869.

The Victoria Dock (opened 1850), on the E. side of the River Hull, occupies about 30 acres, and two large timber ponds are connected with it. It is almost entirely used by ships importing timber from the The patent slips belonging to this dock, used for raising and inspecting vessels, deserve special attention. In excavating the Dock, remains of a large submerged forest were discovered.

The Queen's Dock, on the W. side of the Hull, is, as has been said, the oldest of the docks; and when opened, in 1778, it was the largest in England. It covers nearly 10 acres: and is used on the N. side chiefly for timber, on the S. for general merchandise. The Junction Dock, uniting the Queen's and the Humber Docks, covers 6 acres. The Humber Dock (opened 1809—engineer, John Rennie) covers more than 7 acres. This is used chiefly by trading-vessels from Antwerp, Rotterdam, and the Dutch ports. The Railway Dock, opening W. from the Humber Dock, is small, and was formed chiefly to aid the transfer of goods from ship It is now mainly freto railway. quented by ships from Sweden and Norway.

with the Humber by a basin, pro- the imports. tected by piers. Between this basin and the Hull is the Ferry Boat Pier, land which engaged in the Green-

shire coast is here well seen.

The Albert Dock (opened in 1869. J. Hawkshaw, engineer) covers 24 acres: and the largest steamers can enter with case.

The passage across the docks is maintained by means of drawbridges, the leaves of which, though about 9 yards long, and weighing 40 tons, are raised and lowered with great celerity; a necessary arrangement, as these bridges are in the main thoroughfares of the population. Steam dredging-machines are constantly at work in clearing away the mud, which, owing to the copious deposits brought down by the waters of the Humber, would otherwise soon choke the docks. From 80.000 to 100.000 tons are thus removed annually.

A walk along the Queen's or the Humber Docks will give the tourist, who will hear many northern languages spoken round him, some insight into the nature of the commerce of the town. He will see woolpacks and barrels of yeast from Germany, raw hides, hemp, and tallow from Russia, corn from Dantzic and other Baltic ports (an immense annual importation), and thin iron bars from Sweden: this metal is imported to be converted into steel at Sheffield (see Rte. 44). Elsewhere, hugh bales of cotton twist, and of cotton and woollen cloth, are waiting to be embarked, since Hull is the port from which the cottons of Manchester, the woollens and linens of Yorkshire, and the lace and net of Nottingham, are exported to France, Germany, and the N. of Salt is also an export. Europe. On the W. side of the dock rise lofty piles of timber from the Baltic. The Humber Dock communicates forming a very important article in

Hull was the first place in Engwhich should be visited. The view land fishery. Its merchants fitted

out ships for that purpose as early as 1598. They discovered the island of Jan Mayen, and established a fishery there; and the whalers of Hull continued to be numerous and of great importance until the present cent., but have now altogether disappeared. It was a whaler of Hull Isabella, Capt. Humphries) which, in 1833, saved the lives of Sir John Ross and his companions, who had been 4 yrs. in the Arctic regions. They were brought to Hull. general fishing trade is still of very great importance here; but Hull can no longer be described as "memorable for mud and train oil," in which words Etty the painter, who was an apprentice here for seven years, used always to sum up the chief features of the town.

The Quay, extending along the Humber from the Victoria Hotel to the mouth of the docks, at most hours of the day presents a lively scene, not only from ships, steamers, and small coasting craft, but from the keels and barges from the interior approaching or quitting the roadstead, and the numerous steam-ferries and packets crossing and recrossing. crowd collected on shore, especially on the arrival or departure of a packet, contributes to enliven the scene.

From Victoria Pier Ferry steamers cross the Humber in 1 hour to New Holland Rlv. stat. and to Barton, many times a day.

The Trinity House (one of three in England, the others being at London and Newcastle) is an establishment for the relief of decayed and distressed seamen of the merchant service, their widows and children. A religious guild of the H. Trinity was founded in 1369, and in 1457 was incorporated with a brotherhood called the Shipman's Guild. The Trinity House belonged to this united society, and has continued There are more than ever since.

mariners or their widows; and upwards of 1000 pensioners receive annual relief, in amount from 21. to 16l., from its funds, which are furnished partly from property bequeathed for the purpose, partly from a levy of a shilling per month from the wages of seamen belonging to the port. The guild or corporation enjoys great wealth, privileges, and influence in Hull. It has the charge of buoys and beacons along the Yorkshire coast and up the Humber, with the appointment of pilots for navigating it. The Trinity House itself was re-erected in 1753. and is built round two courts, with a chapel (opened 1843) between them. The whole place is kept as clean and neat as the decks of a man-of-war. It contains some pictures and plate of interest, and is shown on application to the housekeeper. In the hall, hung from the ceiling is a Greenland 'Kayak,' taken up at sea with a man in it, in 1613. figure now in the boat wears the clothes, &c., of the man thus taken, who refused to eat, and died in a few days. Of the pictures, remark-on staircase—Capt. Cook, by Webber; the Battle of the Nile, Smirke and Anderson; and the Landing of William III. at Brixham. In the Council-room (which, like the other apartments, is kept strewn with rushes, after the old fashion) are portraits of Alderman Ferres, d. 1631 —one of the principal benefactors to the House; Andrew Marrell, the poet, born at Winestead (Rte. 6), and educated at Hull, for which place he sat in 2 Parliaments, 1660 and 1661 (this is a copy from the Brit. Mus. picture); Sir George Saville, by Hudson; and a full-length of Queen Victoria, by Sant. In the diningroom is a full-length of George III., by Sir G. Chalmers: and a very finely painted portrait of William, Prince of Orange, by C. Netscher. (This is a portrait of the Prince as a 30 inmates in the house itself, either young man, and is in a magnificent

frame of carved oak.) Among the plate are some curious devices, such as old sailors may have delighted in-a cup with a floating ball :-- a silver milkmaid with her pail, given by Sir Cecil Wray, 1726. On this is an inscription "to the glorious and immortal memory of King William and Queen Mary;"-on the pail, "Tyburn to the Pretender and all his adherents;" and on her kerchief, "no warming-pan." In the museum are a model of Queen Anne's vacht, a chair which belonged to Capt. Cook, and some Arctic curiosities.

Among numerous other hospitals here may be mentioned that of the Charterhouse (outside the ancient walks, near the Hull River), 28 poor men and women, founded (together with a Carthusian monastery for 13 monks) by Michael de la Pole, Earl of Suffolk, 1384 (rebuilt of brick, 1780). This great and powerful family sprang from a rich merchant of Hull (by birth of Ravenspur), Wm. de la Pole, knighted and created first mayor of Hull by Edw. III. His descendants rose in a short time to the highest ranks of the nobility, became Earls and Dukes of Suffolk, and furnished two ministers and favourites to Richard II. and Henry VI. After having flourished 120 years, and having conferred great benefits on their native town, the family became extinct in the reign of Henry VIII., who caused Edmund de la Pole, Earl of Suffolk, to be beheaded after a 7 years' imprisonment in the Tower.

Near the angle at which the Junction and Old Docks meet, rises the Wilberforce Monument (completed 1835), a Doric pillar of sandstone, 72 ft. high, surmounted by the statue of William Wilberforce. This eminent philanthropist was born, Aug. 24, 1759, in High Street (see post). In 1780 he was returned to Parliament as member for Hull.

[Yorkshire.]

Near this monument, and bordering the Queen's Dock, is the New Dock Office (archit. C. G. Wray), an elaborate structure of Renaissance type, with 3 miniature domes of St. Paul's. It is much ornamented with sculptured friezes, small figures of boys with nets, ropes, &c., and above the main entrance, Commerce, Prosperity, and the River Humber.

The most important of the Hull Churches is that of the *Holy Trinity in the market-place (where is a gilt statue of William III., by Scheemaker), which will amply repay a visit. This church was commenced in 1312 - Edw. II., who was then at York, contributed liberally to the work. It consists of nave, choir, and transepts, of which the nave alone was used for congregational purposes until the restoration (1873) of the choir. The transepts and central tower are early Dec.; the choir, Dec. of later character; and the nave, Perp. Much of the choir is built of brick—an almost unique instance of the employment of that material in England at so early a The restoration of this noble church, under the care of Sir G. G. Scott, was begun in 1860. The choir and transepts have been recased, the exterior brickwork cleared from cement, and where new bricks were wanted, they have been cast in direct copy of the old. The windows have been repaired and restored, and new flat panelled roofs of oak have been constructed for the choir and its aieles. and the transcots. The stone flooring is new. Under the central tower a new vaulted ceiling of English oak, gilt and coloured, has been raised, strengthening the tower, which showed a crack on its W. side, besides adding much to the general effect. In the transepts (the central portion) remark the S. and N. windows, the tracery of which "is after geometrical but before flowing. It is a fine specimen."—J. L. Petit. Opening

chapel (now belonging to the Broadleys of Melton), restored by Sir G. G. Scott. It contains a Dec. tomb. with a vaulted canopy, of nearly the same date as the Percy shrine at Beverley. The choir, which is fine and large, is of 5 bays. Its lofty arches and slender piers, with very high bases, should be The aisles terminate even noticed. with the choir itself. This arrangement, and the broad spacing of choir and aisles, is a Yorkshire characteristic, and was probably imitated from the Minster. The windows of both aisles and clerestory are Dec.: and the form of the E. window is unusual. Some bad modern stained glass remains here in spite of the restoration. Under a canopied recess in the S. aiales are the effigies of a merchant (probably Robert of Selby, the effigy has been assigned, without reason, to Sir William de la Pole) and wife, temp. Edw. III. They have been cleared from the black paint with which they were long The merchant holds a book between his clasped hands. Some monuments in the transept may be noticed, chiefly for their bad taste. There is a good example of 17th cent. design in the S. transept,—a mont. erected by the Trinity House to Thos. Ferres (died 1631), who left the mass of his property to the poor, in connection with the Trinity Guild. In the ch. also is a mont. for the Rev. Joseph Milner, author of a 'History of the Church,' who was vicar of this parish, and died in 1797.

The Perp. Nave is fine and striking. There is a lofty clerestory; and the peculiar tracery of the windows should be noticed. The W. window of nine lights has been filled with stained glass by Hardman, the subjects referring to the H. Trinity. The bowl of the font is, perhaps, earlier than its support. There is a good general external view from the S.W. angle of the yard. The peculiar squared outline of the

from the S. transept is a sepulchral | pinnacles rising above the parapets, which entirely conceal the roofs. are here well seen. The E. end is seen from the market-place.

The poet Mason was born at the vicarage of Holv Trinity in 1725.

(On the S. side of H. Trin, Ch. is the Grammar School, founded in 1486 by John Alcock, Bp. of Ely, who was born at Beverley. school was rebuilt in 1583, chiefly by the aid of Wm. Gee, Alderman of Hull, whose initials and merchant's mark are between the windows of the lower story, and whose portrait is in the schoolroom. Andrew Marvell, father of the poet, and Joseph Milner. author of a Hist, of the Church, were masters of this school; and among the more eminent scholars have been Marvell, the poet; Thomas Watson, Bp. of St. David's, Wm. Wilberforce, Isaac Milner, Dean of Carlisle, and Archdeacon Wrangham.)

St. Mary's Church, in Lowgate. was restored (and almost rebuilt) by Sir G. G. Scott in 1863. It is Pero... with the main arches almost triangular, and with a large Perp. K. window, of which the tracery deserves notice. There is a double S. aisle. The modern gallery projects from the tower-arch, an excellent and picturesque arrangement. In the N. aisle is a mural mont., with bust of Wm. Dobson (temp. Chas. II.):-" hujus emporii . . . præfectus, purpură, cæterisq. imperii insignibus donatus." The organ, by Schnetzler, is famed for its trumpetstop. The great E. window of this ch. and many others, are filled with stained glass, by Clayton and Bell, which is well worthy of notice. Much silvery white and yellow glass is used, in conformity with the date of the ch.; and St. Mary's may boast of possessing some of the very finest modern stained glass in this country. The general effect of the interior is W. end, the lofty buttresses and very striking. The existing building

is only the choir of the original ch., of which the W. end is said to have fallen in 1518, and the nave and steeple to have been pulled down by order of Henry VIII. It was of this church that Andrew Marvell's father was minister.

(Opposite St. Mary's Ch. was the Manor House, built in 1387 by Sir Michael de la Pole, and tenanted by Henry VIII., on his visit to Hull in 1540. There are no remains.)

Of other churches in Hull, the only one that claims notice is All Saints. in the Beverley Road (G. E. Street, archit.), consecrated in 1869. This ch. is not large, but the design and details are especially good. It is of red brick with stone dressings.

(In Osborne St. is the Lutheran chapel of St. Nicolai, built for the use of Danish residents and seamen, and consecrated by Archdescon Rothe of Copenhagen in 1871.)

The Town-hall (opened in January, 1866-architect, Cuthbert Brodrick who also designed the Townhall of Leeds) is no doubt the finest The style modern building in Hull. is Italian, with a clock-tower or campanile. The railings of exterior balconies are gilt, adding much to the effect produced by the varied colour of the stone. the staircase is a niche, with a statue of Edw. I. (Earle, Sculptor), founder of the town. There are also statues of Andrew Marvell (see ante) and of Sir Michael de la Pole, Earl of Suffolk, 1st Mayor of Hull, 1376, d 1389. These are by Keyworth, of Hull. On the ground-floor are sessions and county courts, offices of the corporation, and those of various public bodies connected with Hull. The cost of the building was 28,000l.

street in ancient Hull, now a nar- the river-bed, and petrified by some

row and inconvenient lane, follows the rt. bank of the Hull; and openings pass from it to the staiths or landing-places on the river. Here were the houses of the great Hull merchants. About halfway down the street (1. in descending) is Wilberforce House or Buildings, in which Wm. Wilberforce was born in 1759. The house is of brick with stone dressings. In it Charles I. lodged when he visited Hull in 1639. It then belonged to Sir John Lister. On the rt. side of the street is the George Yard, connecting High St. and Lowgate, with some 15th cent. portions. It seems to have been connected with a large ancient hostelry. Another ancient Inn was the King's Head, also in High Street, and apparently of the end of the 14th cent. It is of framed oak. Taylor, the Water Poet, was entertained here in 1662.

In the newer part of Hull, N. of the Docks, the chief place to be visited is the Royal Institution in Albion Street. The building, which is classical and good, was opened in 1854 (archit. Cuthbert Brodrick), and contains under the same roof the Hull Subscription Library and the Museum of the Literary and Philosophical Society. The library contains about 40.000 vols., and there is a good reading-room, to which strangers are admitted on the introduction of a member. A member's order is also required for admission to the Museum, which is interesting. Among the curiosities worth noticing are the head and skeleton of a whale, showing well the arrangement of the fringe pendent from the roof of the mouth, called whalebone - the whale was washed ashore at the mouth of the Humber, in 1835;—some fossil bones from Kirkdale; elephants' grinders, and other bones, found near the coast of Holderness; a joiner's High Street, the most important bag filled with tools, dredged up from

a polar hare and fox, and an Esquimaux canoe from the North Pole, presented by Sir John Ross, together with a pair of boots made and worn by himself on his last expedition: the jack-boots worn by Sir Edward Varney, the royal standard-bearer at the battle of Edgehill, where he was killed; and (by far the most interesting of the antiquities) a group of figures carved in wood, found in 1836 at Roos, in Holderness, in a bed of blue clay, which may have been at one time the bed of a creek or haven connected with the Humber. The group consists of 8 human figures, the feet of which are inserted in the back of a serpent, which is bent, in the form of a boat. The eves of the scruent and of the human figures are of small pieces of quartz. Each figure is armed with a club, and carries two round shields. The date and meaning of this curious relic are uncertain; but it is not impossibly connected, as has generally been supposed, with the "dragons" or long ships of the Northmen, frequent visitors to the Humber. Many other figures were found at the same time, but are said to have been too decayed for removal. Here is also a collection of fiint implements and bronze weapons from the wolds, and some good examples of Arctic fauna. birds and animals, collected by Sir John Ross. The skeletons of the Finner whale (Balænoptera Sibbaldii), of the tunny, and of Wallace, the famous lion, are worth attention.

The first walls of Hull were apparently of brick, and were entirely on the l. bank of the Hull. (In l 1321 Wm. de la Pole had a brickvard outside the N. gate.) Fortifications on the rt. bank were begun by Henry VIII. in 1529, and some additions were made in the reign of Charles II. All, however, have now

natural process beneath the water; I the ancient citadel was between the Hull and the Victoria Dock.

[Hull played a conspicuous part in the eventful history of the civil wars. When the breach between Charles I. and his Parliament left no alternative but a recourse to arms, the king, finding that his opponents had got possession of his chief arsenal, the Tower of London, endeavoured to make himself master of Hull; which, besides its importance as a fortress and seaport, open on the side of Holland, whence his supplies came, also contained a store of arms and ammunition, provided and purchased by himself. With this view, sending on the prince, he marched from York with a small force, inadequate to surprise or overawe the town; but Charles seems to have relied on the good disposition of the governor of Hull, Sir John Hotham. He, however, either from vacillation, treachery, or intimidated by the townspeople, closed the gates, raised the drawbridges in the king's face, and refused him admittance; protesting at the same time on his knees, from the walls, his loyalty to Charles (April 23, 1642). This proceeding of the governor of Hull may be regarded as the first act of hostility in the civil wars. He was proclaimed traitor to his face by the king. Shortly afterwards, however, Hotham became aware of, and concealed, a plot for giving up the town to the king; for which he and his son were removed to London by the Parliament and there beheaded. Before this came to pass, the king, irritated by his failure, collected a force of 3000 men from York, and laid siege to Hull. He was again baffled, by the cutting of the banks, which laid the country 2 m. round the town under water. Within 2 months after the removal of Hotham (Sept. 1643), another and more formidable armament, under the Marquis of Newcastle, laid siege to the completely disappeared. The site of town, throwing up numerous batteries

against it; from one of which red-hot shot were discharged. If the assaults were plied vigorously, the defence was not less obstinate, and was far more skilfully carried on by the new governor. Lord Fairfax: he repulsed all attacks, directed successful sorties, and drove the Royalists from most of their batteries, by again cutting the dvkes on the Hull and Humber, and laying the country under water. In addition to this, the fleet of the Parliament, being masters of the Humber. threw in constant supplies, so that Newcastle, finding little hope of success, raised the siege, which had lasted six weeks, leaving the townspeople impoverished by military exactions, their town damaged, and their trade ruined.

By a more skilfully contrived and more ably executed piece of treachery than that of the Hothams, the fortress was seized (1688) by some of the Protestant officers of James II., belonging to the garrison, and delivered over to William of Orange, in spite of James's precautions; who, expecting that William would land here. had garrisoned Hull with well-affected troops, officered for the most part by Roman Catholics, under a governor (Lord Langdale) appointed for the These officers, with the occasion. governor, were secured in their quarters and at their posts by the malcontents, who had concerted measures with the magistrates of Hull, and who, as soon as they were sure of the citadel and town, set their prisoners at liberty.

The estuary of the Humber, on which Hull stands, is formed by the union of the Ouse and the Trent, at Flaxfleet, about 20 m. above Hull. The etymology is quite uncertain. The name of the Italian river Umbro may possibly be cognate. The local tradition assigned it to a certain King Humber—

"—for my princely name,
From Humber, King of Huns, as anciently it
came:
So still I stick to him.

Than Humber that is heard more horribly to roar? [shore For when my Higre comes, I make my either Even tremble with the sound that I afar do

DRAYTON, Polyolbion.

And so Milton-

"Or Humber loud, that keeps the Scythian's name."

The traditional King, Humber, is said to have been drowned in the estuary, and some earthworks called the Castles, in the Barrow marshes on the Lincolnshire shore, are known as "Humber's work." The "bore" or "Higre" (the name is that of the Northern sea-god (Egfr)—the tidal wave that rushes up the Humber in the same way as it occurs in the Severn—gives the epithet "loud."

"Trent draws from the heart of England the drainage of 4500 square miles; Ouse collects from Yorkshire alone supplies from 4100 square miles. Ouse brings more water, because it is fed by higher mountains and more rainy countries."-Phillips. By these rivers an immense amount of raw and manufactured produce from the most wealthy and industrious counties of England-Yorkshire, Nottinghamshire, and part of Lancashire —is conveyed to the sea. It is not surprising, therefore, that Hull, most advantageously situated on the recipient of these great waterways, should maintain an extensive and flourishing commerce. Besides the vast amount of goods poured into this port by sea, it is calculated that it receives the value of 5 millions sterling annually from the W. Riding alone.

The Humber is between 2 and 3 m. broad at Hull;—the opposite shore of Lincolnshire appearing as a broad grey streak beyond it.

An ironclad lies in the Humber, off Hull, as part of the new system

of defence. There is also a new fort ! at Paul (on the river, below the town), and one on the opposite coast, thus commanding the ascent of the Hum-The Mayor of Hull, since 1445, has been "Admiral of the Humber," with jurisdiction as far as the mouth of the estuary.

Excursions may be made from Hull to Beverley (Rte. 8), 20 minutes by rly.—where the Minster and St. Mary's Ch. are the objects of attraction (Cottingham Ch., Rte. 8, should be seen on the way); to Burton Constable by the rly. to Hornsea (Rte. 7), which place may also be visited; and to all the places mentioned in the the following route, the Churches of Hedon and Patrington being of especial interest.

ROUTE 4.

KNOTTINGLEY TO GOOLE, BY SNAITH. (Lancashire and Yorkshire Railway.)

[16 m. 6 trains daily in 30 min. It runs from Knottingley Junction (Rte. 2) to Goole, a little above the point at which the Ouse and Trent unite to form the Humber. The line runs somewhat north of the Knottingley and Goole Canal (from the Aire to the Ouse), which it crosses soon after leaving Knottingley. The single point of interest on this line is the fine ch. of Snaith.]

At Whitley Bridge (Stat.) is a good modern ch. (arch. Wilson of Bath). At Hensall, the next station, is one of

Downe (arch. Butterfield). All are of brick, with stone dressings, unusual and picturesque in design. others are at Pollington and Cowick. (The E. E. tower of Kellington is seen N. before reaching Hensall.)

Snaith Stat. ("Esneid" in Domesday; the word (A.-S.) signifies a piece "cut off," Kemble), is a small decaying town, with many signs of past wealth and importance. Its population has declined from 4196 in 1871 to 3970 in 1881. manor was long part of the Duchy of Lancaster. The parish was a "peculiar"-out of episcopal jurisdiction; and the church was appropriated, about 1100, by Gerard, Archbishop of York, to the Abbey of Selby. Snaith Church, which well deserves a visit, is chiefly E. E. and Perp. The Western Tower is E. E. as high as the battlements and pinnacles. which date about 1598. It is in 4 stages, receding slightly, with a fine E. E. doorway, of 4 orders, in the lowest stage; an E. E. window above it; and 3 lancets in each face immediately under the battlement. Between the nave and chancel is a pierced gable for the "sancte" bell. The nave (except the westernmost bay, which is E. E.) is Perp., with a clerestory of triple lights; the chancel retains E. E. and Dec. portions, but has been much altered in the Perp. period. The E. window is Dec. Remark the junction of the E. E. with the Perp. work at the W. end of the nave. The tower was originally open to the nave, and had chapels on either side, open to the nave aisles. The chapel on the N. side served as the consistory court of the "peculiar." Traces of colour (red lines) remain on the E. E. arch E. of this chapel. the easternmost bay of the S. aisle is a niche with "Sca Sitha" over it. was no doubt once filled by a figure of St. Osyth (St. Sythe). Beyond is a projecting turret, carrying the rood-8 churches built at the cost of Lord loft stair. On the S. side is the Dawnay Chapel, with some frag-lare some remains of a hunting-tower ments of stained glass exhibiting the Dawnay arms and quarterings in its E. window. (The 3 rings in the Dawnay shield represent a ring given by Richard Cœur de Lion to Sir William Dawnay, in 1193. It is of silver, set with a toad-stone, and still remains in the possession of Lord Downe, the representative of the Dawnays.) Of the 2 altar-tombs, the westernmost is that of Ralph Acloume, whose wife was Margaret Dawnay (d. 1436); the other is that of Sir John Dawnay (d. 1493). The surcoat, spur, and gauntlet, which hang above, are those of Sir Thomas Dawnav (d. 1642). the N. side is the Stapleton Chapel (Lord Beaumont of Carleton), with a monument of Lady Elizabeth Stapleton (d. 1683).

At the N.W. angle of the chancel is a fine life-like statue (entirely out of place) of Lord Downe (d. 1832)the last Baron Dawnay-by Chantrey. Within the altar-rails is the matrix of a brass, representing a mitred abbot-no doubt an abbot of Selby

who was buried here.

A cell for 2 monks (from Selby) was attached to this ch.; and there are some traces of conventual buildings adjoining the ch.-yd. N. a field called the "Priory Garth" a skeleton of unusual size (Roman?) was found in 1853. Tiles were laid ridgewise above it.

2 m. N. of Spaith is Carlton Hall (Lord Beaumont). A good new ch.. Dec. in character (Atkinson, arch.). was consecrated here in Dec. 1863. This ch., of which the interior fittings are very elaborate, was rebuilt at the cost of Lady Beaumont on the site of the old one, pulled down in 1861.

1 m. S.E. of Snaith is Cowick Hall (Lord Downe, but uninhabited: the family pictures, &c., have been removed to Beldersby). In the park

built here by John of Gaunt.

Beyond the next stat. (Rawcliffe) the line runs parallel for some distance with the Goole Canal. of this is the so-called Dutch River. a wide and deep channel, cut by Cornelius Vermuyden about 1630. After Vermuyden had proceeded far with the drainage of Hatfield Chase (see Rte. 3 for a notice of Vermuyden and his undertaking), which he commenced in 1626, it was found that the blocking out of the Don from the levels which it used to cover rendered the northern channel of the river (which joined the Aire near Snaith) insufficient for the discharge of its waters. Floodings of the lands about Fishlake, Sykehouse, Snaith took place; and the people, already indignant with the Flemish adventurers, whom they "foreigners and marauders." broke into open riot. After much difficulty and delay, Vermuyden succeeded in cutting the "Dutch River," from a point near the junction of the Went with the Don, to Goole; and the floods were effectually stopped. old channel of the river is yet traceable, though much filled up.

For Goole, see Rte. 3.

ROUTE 5.

MILFORD JUNCTION TO HULL, BY SELBY.

(North - Eastern Railway, Leeds, Selby, and Hull Branch.)

[For the line from London to Milford Junction see Rtes. 1 and 2. The chief points of interest between Milford and Hull are the churches of Selby, Hemingborough, and Howden.]

31 m. Hambleton Stat. There is nothing to attract the tourist until he reaches

81 m. Selby. (This place and its immediate neighbourhood are fully described in Rte. 1.)

94 m. Cliffe Stat. the tall spire of the Church of Hemingborough (distant 11 m. S.E.) is conspicuous. This church will repay the archeologist for his visit.

The royal manor of Hemingborough, with the town and church, were granted by the Conqueror to Walchere, Bp. of Durham, who in his turn made over the church to the prior and convent of St. Cuthbert's, In 1426 the prior and convent, by licence from Henry VI.,

with a provost, 3 prebendaries, 6 vicars, and 6 clerks. It was dissolved, with other collegiate churches, temp. Edw. VI.

The existing building is a large cross-church, with central tower, nave, chancel (with a chantry or second chancel opening from it S.), and transept. It is of various dates, Norman, E. E., and Perp., the latter portions consisting of alterations and additions, made apparently when the church became collegiate. two western arches of the nave are Trans.-Norm., with remarkable outer mouldings, terminating in snakes' The lofty tower arches are heads. E. E. The transepts, originally E. E., were much altered in the Perp. period, when very fine windows were inserted, S. and N. East of the N. transept is a Perp. chantry (called St. Nicholas's or Babthorpe's chantry, from a family long resident here), in which is a "cadaver" monument. The stone altar remains here, and what is apparently a credence-shelf, adjoining. In the S. transept of the E. E. windows remain. In the S. transept some chantry opening from it is Perp.; and is separated from the actual chancel by four bays of four-cenarches, with clustered piers and foliaged capitals. The font is The church retains some Norman. ancient woodwork, which is well worth notice. There is some screenwork in the choir; and the original stalls remain, with misereres, some of which are E. E., and of great interest, since they are of the same date as the E. E. misereres in Exeter Cathedral, usually considered the earliest in the kingdom. A door in the S. aisle of the nave (Dec.) should also be noticed, with its massive There is some fine carved oaken bar. wood also in the N. aisle. brasses or monuments of interest remain, unless the visitor can find attraction in some curious rhymes placed against a seat on the N. side of erected it into a collegiate church, the nave. On the exterior the chancel

buttresses (Perp.), with monster gurgoyles and rich pinnacles, should be noticed. Over the S. door of the chancel is a niche for a figure of the Virgin (to whom the church was ded.), with an inscription (scarcely legible): "Ave gratia plena, Das tecum. Ecce ancilla Dni." tower and spire are apparently E. E.; the latter is of considerable height. and is a landmark over all this flat country.

The church stands on the rt. bank of an old channel of the Ouse (long since deserted by the river), and is traditionally said to occupy the site of a Roman fort. The stone at the W. end and in part of the N. side differs from the rest, and is said to have been taken from the Roman building. Of this, however, there is no certain evidence.

"Miss Graham, of Woodal, in this parish, preserves the right arm of the famous Marquis of Montrose, cut off below the elbow; and the sword wherewith he wrote on Leith sands."---

Gough's Camden (1789).

[2 m. S.W. of Hemingborough, on the rt. bank of the Ouse (from which it is distant \(\frac{1}{2} \) m.), is the site of Draz Priory, a house of Augustinian canons, founded by William Paganel temp. Hen. II. (1178). At the Dissolution it was valued at 121l. ann. rental. There are no remains.]

The rly, is carried over the river Derwent by an iron bridge, a short distance W. of

123 m. Wressel Stat.

Rt. the ruins of Wressel Castle, king a residence of the Earls of Northumberland, are visible, rising on a slight eminence on the E. bank of the Derwent (the navigation of which it must have commanded), about a mile above its confluence the Ouse. The castle was founded by Thomas Percy, Earl of same length as the nave), and

Worcester (uncle of Hotspur — the Worcester of Shakspeare's 'Henry IV,' Pt. I.), who was beheaded after the battle of Shrewsbury, 1403; and in 1650 the Parliament demolished 3 sides of it; although its owner, Algernon Percy, Earl of Northumberland, had espoused their cause. The 4th side was injured by fire in 1796, and was reduced to This, however, mere naked walls. There are square is worth notice. towers at the angles; and in the central portion was the hall, with kitchens under it. Leland, writing in the reign of Henry VIII., styles Wressel one of the finest houses N. of Trent; and especially dwells on the delights of a study called "Paradise," in one of the towers. The state here kept up by the Percys was little less than regal, as appears from their "Household Book." In the enumeration of clerks, grooms, yeomen, officers, and gentlemen, not less than 229 persons are stated to have been employed about the house and person of the lords of Wressel. (For a general notice of the Percys, as connected with Yorkshire, see Introd.)

The tower of Howden Church is for some time visible rt. as we ap-

proach

151 m. Howden Stat. (from which the town is distant 11 m. An omnibus meets the trains). Inns: Half-moon, Wellington, Bowman's. Pop. 5800.

The *Church of St. Cuthbert at Howden (the single object of interest in the place; it belonged, from the Conquest, to the Bps. of Durham,the 'shire' of Howden was given by the Conqueror to Bp. William of St. Carilef,—and was made collegiate in the reign of Hen. III.) is very interesting and important, and should on no account be missed by the ecclesiologist. The plan embraces nave, transepts with eastern chantries, central tower, choir (of the

chapter-house on the S. side. The | fore, in spite of its geometrical chachoir and chapter-house are, however, in ruin; and the nave alone serves as the parish church. choir fell in 1696; but it had been gradually decaying since the dissolution of the collegiate church (when the revenues were alienated which should have kept it in repair). and had become altogether unsafe in 1630, when, says Gent, "the inner part was miserably rent to pieces, and the comely, tuneful, and melodious organ was pulled down."

The greater portion of the building is Dec., but of different dates, and offering The some peculiarities. history seems to be as follows. fore and perhaps for a short time after the endowment of the collegiate establishment, the church consisted of a nave with aisles, but no clerestory, a low plain central tower, transepts with eastern aisles or chapels, and a chancel, without aisles. Except the chancel, all the several parts of this church still The transepts show decided exist. Early Eng. work. Then follow (in date) the arcades of the nave, then the tower piers and arches, and the lower stage of the tower itself. After the church became collegiate it was apparently thought that an edifice of greater size and dignity would be appropriate, and a larger choir - that now in ruins - was erected. In order to bring the rest of the building into harmony with this, first the nave clerestory was added, and the west front followed. The nave aisles also were increased in height, and the south porch is of this time. Finally Bp. Skirlaw built the chapter-house, circa 1390; and the central stage of the tower was built from funds left by his will for the purpose. The topmost stage is of still later date.

The *West front is a very beautiful composition, and has been pronounced nave with a clerestory, and is there- figures in the niches were removed

racter, of the same date as the clerestory added to the old nave toward the middle of the 14th cent. The central window is of Geom. character, and the spaces between it and the buttresses are delicately panelled. Between the W. front and the S. porch is a Perp. building, now used as a school. The S. porch, of 2 bays, with a parvise over it, contains a head supposed to be that of Edw. II.. and thus marking its date. porch and the aisle windows are Dec. They belong to the time when the aisles were raised; and a flowing line in the west windows is an indication of lateness of style.

The fine and lofty nave arcades belong to the earlier period of the church, and are earliest Dec. There are small heads and grotesques, much shattered, at the intersections. The clerestory is a later addition very light and elegant, and not intended to bear a vault. It retains so much of Geom. character as to keep it in harmony with the rest of

the church.

Two windows in the N. aisle retain some portions of ancient glass. The rest were filled with very bad modern glass about 1840. The glass in the W. window, representing the Nativity, is by Capronnier of Brussels, and was erected in 1863 as a memorial for members of the Scholfield family of Sand Hall. The glass is rich in colour, but has the same faults as that by the same artist in the par. ch. of Doncaster (Rte. 1). The nave was new-roofed and seated in 1850.

The lofty piers and arches of the central tower are somewhat later in date than the arcades of the nave. The transepts retain Early Eng. portions, the doors, the windows are pure Geom., and among the earliest specimens of bar tracery. The rood-screen, now the reredos, is probably nearly unique. It is adapted to a part of Bp. Skirlaw's work; and the

here from the east front of the choir. The stained window is by Wailes. All the details deserve attention. Close to the portal which formerly opened to the S. aisle is an altar-tomb (16th cent.) with heraldic shields, among which occurs that of Saltmarshe. The chantry opening from the adjoining transept belonged to the Saltmarshe family, and contains a cross-legged effigy (temp. Edw. I.) with their arms on the shield; and a knight and lady, temp. Hen. III. On the knight's shield are the arms of Methuen. On the floor is an incised slab, with the figure of a knight in plate-armour.

The roofless and shattered choir. weather-worn as it is, retains enough of its detail to show how fine it must have originally been. It is Dec. (circ. 1300? at any rate it dates from the beginning of the 14th cent.). On the S. side is the Chapter-House, the work of Bp. Skirlaw. This is singularly picturesque, with short ferns and grasses on its ruined walls, and a large elder-tree nearly filling the opening of one of its windows. The design is so graceful, and the remaining details so excellent, as to make it very desirable that some steps should be taken to preserve this building from further injury, although this would be difficult without destroying the picturesque character which it displays at present. The design is octagonal, with a lofty Perp. window in each bay. Below each window are four canopied seats or niches, the backs of which are richly lined with blank quatrefoil tracery. The portal opening to the choir should be especially noticed. The lower part of the window above it retains the brackets and rich canopies of six figures, which have disappeared. A chamber existed over the vestibule of the chapter-house, between the window and the choiraisle.

The E. end of the choir, and the fer distinction on Howden.

amined from without. The composition of the former is especially fine and is a good example of the Dec. period.

The Tower, 130 ft. high, is (above the roof) Perp., the work of Bp. Skirlaw, who left 40l. by his will (dated 1403) toward its completion. It is one of the finest in Yorkshire; and there is a wide view over all this level district from its summit. The bishop is said to have made this bell-tower of a great size (" summæmagnitudinis"), that it might afford a place of refuge to the people in the event of a great inundation. uppermost stage of this tower is of much later date than Bp. Skirlaw's episcopate.

The ancient Manor House (adjoining the church, E.) was rebuilt by Bp. Skirlaw. There had been such a 'palace' here from an early period. Hugh Pudsey, Bp. of Durham, died here in 1195; Bp. Walter of Kirkham in 1260; and Bp. Skirlaw, the rebuilder, in 1405. Bp. Longley, Skirlaw's successor, put up the great stone gates which still remain. palace was large and built round an open court, but little now remains. One bay of a vaulted substructure · serves as a dairy, and has Bp. Skirlaw's arms upon it; and an ancient fruit-house stands above a little bridge crossing a moat, which bounds the orchard. It should here be said that many parts of the church and of the ruins form admirable subjects for the pencil. The church should by all means be viewed from the garden of the old hall. (A valuable memoir on Howden Ch. by the Rev. J. L. Petit will be found in the 25th vol. of the Archseol. Journal. Bp.'s palace has been described by Canon Raine in the Trans. of the Yorksh. Archit. Soc. 1866.)

Two very different celebrities con-Roger chapter-house itself, should be ex- of Hoveden (whose name should pro-

perly be written Houeden) was one was studded over with the seats of of the early rectors, and lived beyond His annals, which are of great value, begin in 731, and are continued to the third year of King John. They were first published in Savile's 'Sc. Rer. Anglic.' 1595, and afterwards at Frankfort, 1601. They are now included in the Rolls series. A statue of Roger of Howden has been placed in front of the new market hall.

Ward, the well-known minister of the Duke of Parma, was born here in 1810, and, after working for some time as a stableboy in Howden, went to London, where he had the good luck to come to the Duke's assistance after a fall from his horse in Rotten Row. Duke carried him back to Lucca as his groom. Ward at once reduced the ducal stable expenses, and made the stud the envy of all Italy. soon rose to a higher position, and became the Minister and confidential friend of his master, with whom he escaped in 1848 to Dresden, and for whom he succeeded in recovering Parma and Piacenza. Ward was on one occasion sent as an envoy to Vienna, where he delighted his brother diplomatists by supplying them with hams from Yorkshire. "He was," said Lord Palmerston, "one of the most remarkable men I ever met with."

Howden is celebrated for its horse fair, said to be the largest in the world. It begins every year on the 25th of September, and lasts 14 days. The fenny country around Howden, extending to the Ouse and Humber, and formerly called the 'Lowths' or low country, as distinguished from the wolds, remained till the end of the last century an unhealthy and almost unprofitable marsh; but since the drainage of Bishop's Soil and Walling Fen, the district has become highly cultivated and is eminently

numerous ancient families, many of which are either ruined or converted into farmhouses.

2 m. S.W. of Howden is Booth Ferry (Inn), over the Ouse, leading to Goole and Snaith. (Rte. 4.)

174 m. Eastrington Stat.

193 m. Staddlethorpe Stat.

Here the railway joins that from Goole and Doncaster, and the further route to

HULL Terminus is the same as in

ROUTE 6.

HULL, BY HEDON AND PATRINGTON, TO WITHERNSEA. (SPURN HEAD.) -THE HOLDERNESS COAST TO HORNSEA.

[Hull and Withernsea Railway (Paragon St. Stat.). 6 trains daily, in 40 min. to 1 hr. The district through which the tourist passes is very level and unpicturesque; but the churches of Hedon and Patrington will amply repay a visit.]

Leaving the Paragon Stat. at Hull, the rly. winds round the town, passing stations at the Cemetery Gates (the general cemetery, l., pleasantly laid out, was opened in 1847) at Stepney (close to Pearson Park, a fertile. Yet even in early times it public park given to the town of

son, Eq., in 1860), Sculcoates (where the muddy Hull river is crossed),

Wilmington Junct. Stat. (where the rly. to Hornsea breaks off, l.), and Southcoates (whence there is connection with the Victoria Stat.). So far the region passed through is one of factories, cement works, and dismal drains. We now enter the "seignory" of Holderness, rich in grain and in families of extreme antiquity. (For a general description see Rte. 7.) There is nothing to delay us at

21 m. Marfleet, where the church dates from 1793; and we speedily reach

51 m. Hedon Stat. (The ch. is seen rt. The tower of Preston Ch. (see post) is seen 1 m.l.) This is now a decayed town (Pop. 2030), consisting, for the most part, of one long street, with the noble church of St. Augustine at the head of it. Hedon is now 2 m. from the Humber; but a creek, which is now meadow-land, once served as its haven, and before the rise of Hull it was a place of considerable importance. "Treuth is," says Leland (temp. Hen. VIII.), "that when Hull began to flourish, Hedon decaied. The town hath yet great privileges, with a mair and bailives: but wher it had in Edward the 3 dayes many good shippes and riche marchauntes, now there be but a few botes and no marchauntes of any estimation." The first charter was granted by Edw. III., and Hedon sent members to Parliament until it was disfranchised under the Reform Bill.

The sole relic of the former importance of Hedon is the Church (ded. to St. Augustine), known as the "King of Holderness," as that of Patrington (see post) is the "Queen." It consists of nave and aisles, chancel, transepts, and central tower. The South Transept has been re-

Hull by the then mayor, Z. C. Pear- | stored under the direction of Mr. G. E. Street. For what else has been done a local builder is responsible; and under the circumstances it is satisfactory to be assured that no funds are forthcoming for "restoration." The choir and transepts are E. E., the nave Dec. (geometrical), and the central tower Perp. windows have also been inserted in different parts of the ch. The church of Patrington is throughout Dec. (curvilinear); the Dec. portion of Hedon is of earlier character (geometrical).

The ch. is entered through the transept. The N. transept retains its original character more completely than the S. (restored). Both have had eastern aisles, which have disappeared, the piers and arches remaining built up in the wall. A triforium, serving also as a clerestory, with lancets at the back, runs round both transepts, and was approached by staircases in the angles. In the S. transept it had been removed to make room for a large Perp. S. window. This has been replaced by two tiers of triplets, and a rose window above, from the designs of Street. The roof also is new. In the N. Trans. are 3 tiers of triplets, with enriched crosses in the spandrels of the lowest. (Remark a very graceful Dec. niche, with sculptured foliage at the back, inserted in the E. wall, N. of the walledup arches.) The S. transept is probably somewhat earlier than the N. The piers and trans. and the choir. arches supporting the tower are Perp. The choir is of the same character and time (E. E.) as the transept with a similar triforium, which was continued round the E. end before the insertion of the existing Perp. window of 5 lights. The sedilia, and the door now opening into the vestry, should be noticed. On the same (the S.) side are 2 arches, how walled up, which were originally open to the socalled Chantry of St. Mary (the Lady Chapel?), some portions of which are seen within the vestry. Arches (now

the transept aisles. The nave is throughout Dec. (circ. 1310?), although traces of the E. E. nave, which was removed when that which now exists was built, may be seen at the E. end of both nave-aisles. The piers of the nave are clustered, with plain caps, and on a small scale recall those of Exeter cathedral. The clerestorywindows are of 2 lights, with a quatrefoil in the tympanum. aisle-windows have rich geometrical tracery, with the exception of those in the westernmost bays, the tracery of which is flowing and of later date. In the second bay from the W. in each aisle is a doorway, above which is a small lozenge-shaped window with 4 quatrefoils, somewhat resembling one at the W. end of St. Hilda's Abbey at Whitby. A large Perp. window has been inserted at the W. end of the nave. In restoring this part of the church the pews and galferies have been swept away, and plain open roofs placed above nave and aisles. (Stone brackets springers of the old roof remain in the aisle walls.) The flooring of the nave has been brought to its original level, and the bases of the piers exposed. The font (of granite) is Dec., and deserves notice. At the end of the S. sisle are some monuments-an early, much shattered effigy, a slab with richly floriated cross, and a stone coffin-brought here from different parts of church.

The great western portal, and the aisle portals, N. and S., should be examined on the exterior. The very graceful Perp. tower, with its 3-light windows and openwork parapet, is 129 ft. in height to the top of the pinnacles. The transept fronts should especially be noticed (that N. is the better). The foiled ornaments in the spandrels both there and in the windows N. of the choir, suggest Bever-

walled up) opened on either side to of the choir (within) has the 2 animals' heads joining in the centre, characteristic of Beverley. The E. Eng. church here was probably erected at the same time, and by the same builders.

> Hedon still possesses a mayor; and some ancient corporation plate is in his keeping.

> In Mr. Watson's garden is an ancient cross, removed in 1818 to Burton Constable from Kilnsea (see post), where it was in danger of being destroyed by the sea. (The ch.-yard in which it stood was washed away soon after its removal.) It was afterwards brought here from Burton Con-It is said to have been originally erected to commemorate the landing of Henry Bolingbroke at Ravenser, near Kilnsea. It is a tall slender shaft, with much worn figures. and is raised on steps.

I m. to the l. of the station, is the Church of Preston, with a fine Perp. tower, having large double windows in the upper story. A figure remains in a niche above the W. window. The Church is E. Eng. (S. side of nave) with Dec. (N. side) and Perp. (clerestory) additions. The chancel was rebuilt in 1870. The bells, "in 4th Eliz., were taken out of this church and exported . . . When the ship, wherein they were. was clear off Humbre and launched into the sea, being under sail, she, yet within sight, was seen to sink down into the sea, like that of Arthur Prulkley, 38th Bp. of Bangor, who, for the like sacrilege, was struck blind" (Poulson, from an old memorandum). In the parish was the hospital of St. Sepulchre, founded for lepers by Alan FitzOsbern in the reign of John. No remains exist.]

[2 m. S. of Hedon, close to the Humber, is Paghill or Paul. The ley; and one capital on the N. side ch., without interest, is some distance

from the village; -hence the local | Mary's Chapel (Perp.), S. of the rhyme--

"High Paul, and Low Paul, Paul, and Paul Holme; There was never a fair maid married in Paul

There is a lighthouse here, about 40 ft. high, built in 1836 by the Trinity House of Hull, and a dismantled fort has been rebuilt (20 men under a lieut. are stationed here) as part of the system of defence for the Humber. At Paul Holme, possessed by the Holme family from a very early period, is a single brick tower of the old house, dating, perhaps, from the reign of Henry VII.

There is a small chapel at Thorngumbald, in the parish of Paul, which has Norm. portions, but is hardly

worth a visit.

73 m. Burstwick Stat. (The low ch. tower is seen l.) This place, for a considerable time, was the "Caput Baronise," or " Head of the Seignory " of Holderness. The Earls of Albemerle had their chief castle here, and the records preserve many notices of Burstwick at such times as the seignory escheated to the Crown, and was in the possession of the Kings of England. After the defeat of Bruce by Edward I. at Methven (June. 1306), his Queen the "Countess of Carrick," who had fallen into the hands of the English, was consigned, by letters of privy seal, to Richard Ovsel, steward of the royal manor of Burtwick, to be detained in safe custody. She was removed to Windsor Castle in the first year of Edward II. Both kings, Edward I. and IL, were frequently at Burstwick. No trace of the castle remains. said to have stood in "South Park," about 1 mile W. of the village.

The Church of Burstwick is late Dec., but of no great interest. It was

restored in 1853.

The Church of Burton Pideca (8 m. N.E.) is Dec. and Perp. St. has some E. Eng. portions, but it is

chancel, now serves as a schoolroom It will hardly repay a visit. The ch. has been restored.

91 m. Keyingham Stat. The ch. here has a plain broach spire-one of three in Holderness-the others being at Ottringham and Patrington. three serve as guides in the navigation of the Humber. Keyingham Ch. seems originally Dec., but is now rich in "debased" work. There is, however, a good Dec. E. window. The Chartulary of Meaux Abbey records a great storm of wind and lightning (June 24, 1392), which threw down 30 ft. of this spire, tore stones from the walls, and split all the oaken doors in the ch. The tomb of Philip de Ingleberd, rector from 1306 to 1325, was untouched, and "oozed out a sweet-scented oil." Master Philip was accounted "the most subtle Aristotelian in Oxford," and seems also to have been held in some regard as a saint.

In Halsham Church (11 m. N.)which is late Dec. in character, with perhaps Trans. - Norman piers and arches dividing the N. aisle from the nave-there is an unusual arrangement of the sedilia, which are enclosed under a single crocketed arch, the head of which is filled with flowing tracery. The ch. has been restored at the cost of the rector, the Rev. P. M. Shipton. On the N. side of the chancel is the Chapel of St. John of Beverley, in which the family of Constable were buried until 1802. In it is an alabaster effigy of a knight, temp. Richard II. (?) He wears a collar of SS., and his armour affords a good study. Since 1802 the Constables have been buried in a circular mausoleum, E. of the ch.]

102 m. Ottringham. The ch. here (of which the spire is conspicuous) of little interest. It was restored in 1860. At the next stat.,

131 m. Winestead, there is more to attract the antiquary. The family of Hildyard have been settled here since the reign of Henry VI., and the ch. contains some interesting memorials of them. The building itself, without a tower, is Perp. In a chantry, S. of the chancel, is the altar-tomb, with efflgy, of Sir Christopher Hildyard (died 1602)—a very fine example of this period. At the foot of this monument is the effigy of an unknown ecclesiastic (15th cent.). chancel is the brass of a knight and lady, with small figures of children at their feet. This is supposed to be the brass of Sir Robert Hildvard (died 5th Hen. VII.), who, under the name of "Robin of Redesdale," headed a rising in Yorkshire in 1469 (8th Edw. IV.) in favour of the Lancastrians, and together with Sir John Conyers, advanced to Edgcote near Banbury, where they defeated and took prisoner the Earl of Pembroke. This earl, with his brother and Richard Woodville, Earl Rivers, were beheaded at Northampton. "Robin." however, seems afterwards to have become a firm partisan of the house of York, since (if this Sir Robert was he) he was employed to conduct 5000 men from the North to support the coronation of Richard III.; when he received the honour of knighthood. But the real history of Robin of Redesdale has yet to be ascertained. picture drawn of him in Bulwer's Last of the Barons' is perhaps more striking than truthful.

Winestead was the birthplace of Andrew Marvell, the poet and "patriot." His father was for some time rector here, and the birth of his better-known son is recorded in the register. He removed to Hull in

1624.

Winestead Hall, the present mansion of the Hildyards, dates from same time with the nave of York

1710, when it was erected on the site of an older building. Its woods are seen 1. On the rt. of the stat. is White Hall (W. Bailey, Esq.). There is a large and important flax factory here (belonging to Mesers. Garth and Marshall, of Leeds), of which the chimney is conspicuous. Much flax is grown in the neighbourhood; and is here prepared for the spinner by means of hot-water steeping, and 'scutching' from flax straw.

14 m. Patrington Stat. (the village and ch. are 1 m. rt. of station), so named from its church, which is dedicated to St. Patrick. The little town (Pop. 8748) is without interest, but the *Church, which has been called "the glory of Holderness" is, in truth, not only one of the glories of Yorkshire but of England. It would be difficult to mention a more perfectly beautiful church. The admiration of the visitor "grows insensibly from the moment that he first sees the taper spire against the sky, to that of the last inspection which he gives to the elaborate details of the finished structure."-G. A. Poole. In grace of composition and beauty of detail Patrington Ch. is hardly exceeded anywhere; and in portions,—as the arcade of the spire and the hooded porch of the N. transept,—there is evidence of great originality of design. Patrington is said to be the "Queen" of Holderness churches, as Hedon is the "King;" the extreme grace of the former ch. distinguishing it from the dignity of Hedon.

The manor of Patrington was in the hands of the Archbishops of York from a period before the Conquest to the year 1545, when it was seized by the Crown. It has since passed through many hands. The existing ch. (with the exception of the great E. window) is throughout Dec., and probably dates early in the reign of Edward III. (circ. 1330?). It must have been in course of erection at the same time with the nave of York

Minster; and Archbishop William of Melton (1317-1342) may fairly be supposed to have aided the work here, as well as in his own cathedral. Robert of Patrington, a native of this place, was master-mason at the Minster from 1368 to 1371, during the building of the Presbytery (see York, Rte. 1), and had, perhaps, assisted in the construction of this noble ch.

Patrington Church consists of nave, chancel, transept with E. and W. aisles, and central tower and spire. On the exterior, remark the W. window, flowing in its general character, but transomed and showing signs of approaching Perp. in the lines of tracery at the head. The tracery of the aisle windows is completely The N. and S. porches, above the latter of which is a parvise: the buttresses which divide each bay of nave, chancel, and transepts, and terminate in foliated pinnacles; and the very grotesque gurgovles, which project from the buttresses at the base of the parapet, should all be The N. and S. gables of the transepts resemble the W. front, but the windows are without Perp. lines in their tracery. The doorway in the N. transept deserves especial notice for the bold relief of the corbels, -a lion and an eagle,-which support the hooded canopy, and for the figure of our Lord at the point of the arch, "holding up His hands, as if to say to those who enter, I am the door." From the S. transept projects the small Lady-chapel. The chancel windows are richer than those in the nave, and the great E. window is a Perp. insertion; not impossibly the work of Robert of Patrington. The roofs retain their original pitch, a fact to which the ch. is mainly indebted for its graceful out-The design of the tower and spire is singularly graceful and original, although the massiveness of Hedon gives perhaps greater dignity. Round the third story of the [Yorkehire.]

an arcade of four arches on each side. of which two are pierced with squareheaded windows. From the tower rises an octagon, supported by flying buttresses at the angles, and finished at the top with a parapet and 16 crocketed pinnacles, from within which the octangular spire rises to the height of 180 ft. from the ground. Within the ch. the nave is separated from its aisles, and the transepts from their aisles, by very graceful clustered columns, with richly foliated capitals, and corbel-heads at the intersections of the outer arch-mouldings. The tower is supported by four massive piers, each containing 20 shafts. The fine bases of the piers should be noticed. The great (and for a parish church unusual) development of the transepts somewhat dwarf both nave and choir. "The Ladychapel in the S. transept (the eastern aisle of which is groined throughout) forms a three-sided apse, two sides of which are pierced for windows, whilst that in the centre shows an oblong tablet above the altar site, with tabernacle work in three divisions above it. The arrangement of the central boss in the groining of this chapel is perhaps unique; it is formed into a pendant, open on the eastern side, so as to contain a taper which would throw its light down upon the altar. The three closed sides are niches, within pointed pinnacles, containing sculptures of the Annunciation, St. John Evangelist, and St. Catherine." The under-surface forms a rose. In the S. transept is an unfinished triforium (?), approached by open steps from a door opening into the tower. Here is also the font, a single block of granite, 12-sided without and circular within, and much enriched. In the N. transept, the eastern arch is raised on two steps, and projecting piscinas remain in each bay. the N.E. corner remark a bracket with a pig-the place, possibly, of St. Anthony's light.' The whole

covered with a vellow wash. The chancel has been restored, and is separated from the nave by an open screen of wood, also restored. On the S. side are three very graceful sedilia, with a piscina; and on the N. side of the altar, one of the most perfect Easter Sepulchres remaining in England. It is of four compartments, one above another. In the lowest are the three soldiers, the keepers of the sepulchre. The next compartment is vacant, and was probably that in which the crucifix was solemnly deposited on the night of Good Friday, and where it remained until Easter morning. In the third the Saviour is represented rising from the tomb, with censing angels on either side. The fourth is vacant.

From the summit of the tower there is a wide view over the whole level district-one sheet of rich grain in the autumn—with the estuary of the Humber and Sunk Island in front: but the ascent is not to be recommended to persons of weak nerves. A staircase leads to the exterior roof of the N. Transept, and thence, by a gallery close under the ridge of the roof, access is gained to the tower.

Sunk Island, between Patrington and the Humber, containing a cultivated tract of more than 6000 acres, has been entirely formed by the " warp" or sand and salt deposited by the Humber. It first appeared as a sandbank at low water, and gradually increased, until in 1666 it was given by Charles II. to Col. Gilby, Governor of Hull. It afterwards reverted to the Crown, in the possession of which it still remains, but is of course in the hands of lessees. It has been embanked from time to time, as new portions were formed, and it is now connected with the mainland, so as no longer to deserve the name of In 1831 it was erected into a parish by Act of Parliament, and a chapel, which had been built pebbles found on the shore.

of the nave and transepts remains in 1802, became the parish ch. The cultivated portion of the island is among the richest ground in York-

> From Patrington the tourist may make an excursion to Spurn Head, (13 m.), the extreme S.E. point of the Yorkshire coast. There is, however, little to reward him, especially if he has been sufficiently strongheaded to climb to the roof of Patrington tower, where he would see the general character of the district.

At Welwick (2 m. S.E. from Patrington) is a ch. of some interest. which in 1361 was appropriated by the Abp. of York to Beverley Minster. It is dedicated to the Virgin, of whom a headless statue remains in a niche over the S. porch. Under the E. window of the S. aisle is a remarkable monument, which has evidently been removed from elsewhere to its present position. It is traditionally said to have been brought here from Burstall Priory; but this is quite uncertain. The monument consists of a low-arched recess, with a rich mass of tabernacle work above it. The effigy, which is that of a priest in alb and cope, is, very unusually, laid within the recess in a sort of sunk coffin, the side of which has flowing tracery, and medallions with the emblems of the Evangelists. It dates apparently about 1350. The mass of enriched work above the recess has been imperfectly put together after the re-moval of the monument from its original position. At the E. end of the N. aisle is a brass for William Wright of Plewland and his wife (1620).John and Christopher Wright, of "Plewland" or Ploughland in this parish, were concerned in the Gunpowder Plot.

The greater part of the Holderness churches, especially those on the coast, are built with "cobble"-large fonts are nearly all of granite, and of I with the cliff on which it stood. course were brought by sea.

At Skeffling (2 m. S.E. from Welwick) the ch. has E. Eng. portions, and belonged to the Priory of Burstall, an alien house, dependent on the monastery of S. Martin, of Albemarle. in Normandy. In the reign of Richard IL this priory was made over by the convent of S. Martin to Kirkstall Abbev. and remained in the hands of that house till the Dissolution. site of the Priory (S. of Skeffling) has been entirely swept away by the sea.

Dimlington Hill, on the coast, 2 m. from Skeffling, is the highest point (146 ft. above high water) between Spurn Point and Flamborough Head. It is a cliff of boulder clay and pebbles.

Easington Church (2 m. E. from Skeffling, is partly E. Eng., and deserves notice. There is a large and fine Perp. E. window. Beyond Easington (or Skeffling) the pedestrian may walk along the great embankment on the margin of the flats to Kilnsea. The view is singular, "the bank stretching as far as eve can see in a straight line to the E. and W., covered with coarse grass and patches of sea holly (Erynge maritima). Its outer slope is loose sand, falling away to the damp line left by the tide, beyond which all is mud-a great brown expanse, overspread for miles. . . . Fishermen wade across it in huge boots from their boats to the firm beach, and dig down through it two or three feet to find firm holding-ground for their anchors. From Spurn to Sunk Island this whole northern shore is of the same brown, monotonous aspect -a desert, where the only living things are a few sea-birds, wheeling and darting rapidly, their white wings flashing by contrast with the sadcoloured shore."-W. White. The succent Church of Kilnsea disappeared others having been destroyed by the

half fell into the sea in 1826, and the remainder in 1831. The old font is preserved in the parsonage garden at Skeffling. A new ch., of red brick, with white string-courses and arches. was built here in 1865. Population of town and district, 41,102.

A narrow natural causeway of sand and pebbles, between 2 and 3 miles long, connects Kilnsea with the Spurn Head, the northern limit of Humber. This " is a mass of pebbles and sand, movable by wind and tide; yet so balanced are the forces by which it is assailed from the river and the sea. that it has long supported Smeaton's lighthouses, and is one of the least unstable parts of this variable line of coast. It is not, properly speaking, a part of the old land, but a long curved bank, thrown up by the sea, on the place of a tract of land which has been destroyed. It is subject to continual waste by the action of the currents setting along the shore southward; but this waste is continually repaired by new materials which these currents bring from the cliffs, which undergo destruction farther north. It is out of the ruins of Holderness that the Spurn is constituted and maintained."—Phillips. On the highest point of the Spurn stands the lighthouse, built by Smeaton in 1776, with a second and lower tower at the foot of the inner slope, where its base is covered by every tide. Smeaton's Lighthouse is 90 ft. high, and there is a wide view from its gallery, embracing the low coast of Holderness on one side, and the shore of the estuary on the other. The sands (or mud) seen between the inner bank of the Spurn and the shore towards Patrington are known as the "Trinity Dry Sands," and are reclaimable by proper barriers. The lesser tower is 50 ft. high, and is appreached by a long wooden bridge, above reach of the water. It is the third tower which has been built here -- two

sea. Landward of the lighthouses is | oratory, and, as Henry IV., confirmed a row of cottages, inhabited by the crew of a lifeboat, which has often been of great service on this wild coast.

In 1817 the extent of ground about the Spurn (comprising the sandbank by which it is approached) was 100 acres. In 1833 it was only about 58. The coast is constantly changing, and its waste not only repairs the Spurn Head, but enlarges the Trinity Sands, the Sunk Island, and the whole shore of the estuary. But the shore of the Humber in its turn has been not less liable to change. One of its most ancient ports was Ravenser, Ravenspurne, or Ravensburgh, with an island adjoining called Ravenser-odd, Ravenser was within or Ravensrode. and near the Spurn Head. traces of it, however, had nearly disappeared at the end of the 14th cent.: "and it seems possible that the Spurn Point itself may have been since driven inward, as the clay cliffs of Kilnsea, on the north, decayed."-Phillips. Ravenser was of sufficient importance to be summoned to send members to Parliament in 1305; and in 1298 its merchant burgesses offered 300 marks to Edward I. for a confirmation of privileges, whilst those of Hull only presented 100. about 1340 the sea had done great mischief at Ravenser. The merchants began to remove to Hull; the dead were transferred to Easington; the town was at last abandoned, and swept away by the floods. It was here, however, that Bolingbroke landed in 1399-

"The banished Bolingbroke repeals himself, And with uplifted arms is saie arrived AtRavenspurg "-Richard II., act ii.sc. 2-

(a cross, said to have been set up to commemorate his landing, is now at Hedon-see ante); and here that Edward IV. landed from Flanders in 1471, before the battle of Barnet. Bolingbroke found a "hermit-priest"

him in possession. In 1428 another hermit, Richard Reedbarowe, built a "bekentower"—the predecessor of Smeaton's lighthouse—at Ravenser. The place is last mentioned by Leland in 1538, and it is probable that Sunk Island (the formation of which began in the reign of Charles I.) is due in great part to the wash of the land from the ancient coast of Ravenser. Many villages on Humber side, whose names appear in ancient maps, have, like the more important burgh, disappeared entirely.

(For a general notice of the Hum-

ber see Rte. 3, Hull.)

From Patrington the rly. turns N.E. toward

18 m. Withernsea Terminus. (Inn: the Queen's Hotel, near the stat., belonging to the Hull and Holderness Rly. Company. It is comfortable, and well placed, overlooking the sea. and surrounded by its private grounds. The ch. is close by.) Withernsea is a small and somewhat dreary watering-place, frequented by the inhabitants of Hull, but of little general attraction. The coast, like all that between Spurn Point and Flam-borough Head, is low and bare, without rocks, and even without seaplants, although it has its interest for the geologist. "Destruction of land. once fertile and populous, is the melancholy characteristic of the whole coast from Spurn northward to Bridlington. Through all the reach of history, and probably for longer periods before, the sea has here been gaining on the land. The rate at which the cliffs recede from the insatiable waves has been measured of late years, and found to equal 21 yards in a year on an average; which. upon 36 miles of coast, amounts to about 30 acres. At this rate, which may be less than formerly, when the at Ravenser engaged in building an coast was less protected by Flam-

borough Head, one mile in breadth | 1788, by his two nieces and a servant has been lost since the Norman Conquest, and more than two miles since the Roman occupation of Eboracum." -Phillips. Upon the land thus eaten away by the sea stood the ancient ch. of Withernsea, which is known to have existed before the present edifice was consecrated in 1488. This, which was long a ruined shell of late Perp. character, has been restored, and is now in very good order. Withernsea is a township in the par. of Hollym, the ch. of which, 2 m. S., was rebuilt in 1816.

In a depressed part of the cliff between Withernsea and the site of Owthorne (1 m. N.) is a remarkable fresh-water deposit, indicating the site of an ancient lake. "There is a blue lacustrine clay, with Anodonta; above, a layer of peat, with many roots and branches of trees, hazelnuts. leaves, and, less commonly, horns and bones of the red deer. A canoe. made of the trunk of a tree, was also found here, like others of early British date which have been found in the sediments of the Aire and the Calder. in the fens of Lincolnshire, and many other places."-Phillips. The branches of trees found here are locally known as " Noah's wood." On the clay, when exposed, marks of birds' feet, especially swans, sometimes appear.

The ancient ch. and churchyard of Owthorne have disappeared since 1816, when the E. end of the ch. fell, strewing the shore with ruin and with shattered coffins. The last fragment of the churchyard was undermined about 1838. The churches of Owthorne and Withernsea were known as the "Sister Churches," and were said to have been built by two sisters, who at first agreed that a single ch. would be sufficient for the adjoining manors; but they quarrelled as to the respective merits of a tower or a spire, and each sister at last built her own ch. In the Vicarage of Owthorne the Rev. Enoch Sinclair was murdered in sea and Tunstall) is an old lake, of

named Alvin. Alvin afterwards married the elder niece. Her sister, four years afterwards, confessed the crime on her deathbed. Alvin was taken and condemned: but, during the preaching of the "condemned" sermon at York, he protested his innocence aloud. The shock proved fatal to the preacher, a Mr. Mace, who fell dead in the pulpit. The murderer declared that the hand of God was evident, and the "vox populi" supported him; but he confessed his guilt the next day on the scaffold.

34 m. W. of Withernsea is South Frothingham Hall, long the residence of the Frothinghams, who were established here from the 12th cent. to the 17th. The house, which stands low and is surrounded by dark wood, dates from the 16th and 17th cents.

From Withernsea the tourist may proceed along the coast to Hornsea (15 m.), or, if he pleases, to Burlington (30 m.). He will not choose this route if he is in search of the picturesque - although the changing lights over the sea and the low coast have their own beauty: but it offers some points of interest for the geologist and the antiquary. The country is not altogether flat, but undulating rich ground, the "valleys" or "hol-lows" being in some parts rather deep. The villages are generally on the highest points, so that their ch. towers are conspicuous. The spire of Patrington and the tower of Aldborough are great landmarks. The natural richness of the soil was probably one of the principal inducements for the early and numerous settlements in this part of Yorkshire. There must anciently have been much wood; but whole tracts of land lay ready for cultivation with very little trouble.

At Sandley Mere (between Withern-

the same character as that already i noticed between Withernsea and Owthorne, "not quite destroyed by the sea, on a level as low as that of Owthorne, and vielding similar remains of quadrupeds. Washed out from the cliff of boulder clay immediately beyond, teeth of elephants have been found."—Phillips.

The Church of Tunstall (4 m. N. of Withernsea) is Perp. (with an E. Eng. chancel) and of little interest. In it is preserved an ancient quern or mill of some size. The ch. was restored in 1873.

[Roos (Rhos, Celt., a moor?), 2 m. S.W. of Tunstall, was the lordship of the powerful family of Roos or Ross from the reign of Henry L to the beginning of the 16th cent. In the first half of the 18th it became the property of the Sykes of Sledmere, in whose hands it still remains. There are no remains of the Castle of The Church, approached by Roos. an avenue of yews, is early Dec. (nave arcades) and Perp. (nave, clerestory, chancel, and tower); and was entirely restored in 1842 by the Rev. Charles Hotham. There is an east window by Clayton and Bell; and another containing shields of the Barons of Roos and of the seignory of Holderness. It was in Roos Carrs, in this parish, that the singular carving now in the Hull Museum (see Rtc. 3) was found.]

Along all this low coast whales are occasionally stranded. "The possessor of Burton Constable, the Lord Paramount of Holderness, claims such spoils of the sea, and in one instance a fine spermaceti whale was carried off to the Hall, where its huge skeleton remains."-Phillips. Another is in the Museum at Hull (Rte. 3).

At Hilston (2 m. N. from Tunstall) is a small and very good new church (Pearson archit.) built as a memorial

an ancient Norm, building, one portal of which is retained (S. side) in the existing church. The reredos, the pulpit, and the font are inlaid with coloured marbles, representing subjects from Scripture. That of the reredos is the supper at Emmaus with the words "He was known of them in breaking of bread." The tower is crowned with a broach spire. Hilston is on the highest point of the cliff on this coast, which here rises to 80 ft. On Hilston Mount, N. of the village, is an octagonal tower of brick, which serves as a landmark, and was built in 1750 by one of the Storr family. whose mansion has disappeared. From the upper room of this tower there is a wide prospect over the German Ocean. The woods of Grimston Hall (Major M. J. Grimston) are passed rt. between Hilston and Garton. house dates from the end of the 18th cent. The older house of the Grimstons, where they are said to have been settled before the Conquest, was Grimston Garth, nearer the sea. The moat only remains.

Garton Church (11 m. from Hilston) is chiefly Perp. with an E. E. tower. [At Humbleton, 3 m. W. of Garton, is a late Perp. ch. of some interest. Danthorpe Hall (W. Marsdin, Esq.) in this par. is of brick, and ancient. At Elsternwick is a chapel consecrated temp. Hen. VIII.]

Aldborough (Pop. 1469), 3 m. N.W. of Garton, is well known to the antiquary from its ch., which contains a Saxon inscription. The ch., dedicated to St. Bartholomew, has (except the chancel) been entirely rebuilt, apparently in exact reproduction of its predecessor, which was built between 1353 and 1377; but large portions of an earlier building were preserved and worked up in it. This first ch. was no doubt destroyed by the sea, and was that of which the Saxon inscription records the foundation. This is to the late Lady Sykes, on the site of | in the S. aisle. It is circular, and

surrounds what has possibly been a ment. Adjoining this tomb is another, dial, marked by lines into eight hour- bearing the effigy of a lady, whose spaces; within one of which is a robe displays the six griffins volant of cross-lined figure, the meaning of Meaux, and who is probably Maude which is not clear. The words are, "Ulf het aræran curice for Hanum and for Gunthard saula." ordered this ch. to be built for the souls of Hanum and Gunthard." stone projects about an inch from the wall, and immediately below it is the pointed top of what seems to have been a pediment above a portal. The Ulf here commemorated is the great Danish "Jarl" of Deira, who bestowed so many manors on the ch. of York. and whose carved horn, which he laid on the altar in confirmation of his gifts, is still preserved in the Minster. (See York, Rte. 1.) Ulf is recorded in the Doomsday survey as lord of Aldborough in the days of the Confessor, and his "house" was represented by the Barons of Greystock in Cumberland, where he is said to have died, and where his grave was long shown. (There is a dial, divided, like this, into eight spaces, with a Saxon inscription of the same date, over the porch of Kirkdale church. and another, resembling it, in the neighbouring ch. of Edstone. both, see Rtc. 18a.) Against the first pier is a rude, bare-footed figure, wearing a sort of petticoat or kilt in long strips.

At the E. end of the N. aisle is the fine monument, with effigy, of Sir John de Meaux (de Melsa—see Rte. 7), died 1377 (1st Richard II.). John de Meaux, temp. Stephen, exchanged lands in Meaux for Bewick in this parish, where his descendants remained until the house became extinct in the male line with the knight here figured, who is locally known as "Giant Morrell," and is said to have been a man of vast strength and stature. This tradition has perhaps arisen from the unusual size of the effigy, which is 6 ft. 6 in. long, and 2 ft. across the shoulders. A helmet (of later date) hangs above the monu-

de Meaux, wife of Sir John. Both tombs and effigies have been sadly mutilated by the boys of the parish school, which was long kept in this part of the aisle, the arches N. and W. being boarded up. In those happily past days the helmet now hanging on the wall was used as a coalscuttle. The position of the church, on high ground, and on one side of a hollow sweep, is noticeable. An ancient stronghold here (the "ald" borough), like the church of Ulf, was nearer the sea.

The Church of Mapleton (31 m from Aldborough) stands high (60 ft.) for this coast, and there is a good view from the churchyard. The ch. has E. E. and Dec. portions, and has been entirely restored. As a proof of the manner in which the sea is gaining on this coast, it may be noted that in 1786 Mapleton ch. was 28 chains 76 links distant from the cliff. In 1858 it was 21 ch. 62 l., and in June, 1871, 19 ch. 30 l. Hall, N. of the ch., was the residence of William Brough, Esq. (died 1783), who, as Marshal of the Admiralty, superintended the execution of Admiral Byng. The pirate Paul Jones, who had an especial grudge against the Marshal, used always to pay him the compliment of a shot in passing his house, which is a good sea-mark. One of these shot is still preserved at the hall.

3 m. N. of Mapleton we reach Hornsea. (Hotel, The Marine. See Rte. 7.)

ROUTE 7.

HULL TO HORNSEA AND SKIPSEA.

(North-Eastern Railway—Hull and Hornsea Branch.)

[7 trains daily in 50 min.]

This line, of 16 m., takes us across the centre of the district known as "Holderness," a short notice of which is here given.

As a natural division, Holderness includes the whole country between the Wold hills, the German Ocean, and the Humber. The boundaries of the existing "seignory" or wapentake (which is in 3 divisions) run from Barmston to Spurn Point, from Spurn Point to Hull, and from Hull along the Hull river, and by a line from thence N. to Barmston.

"Lordings, there is in Yorkshire, as I gesse, A mersh contree yealled Holdernesse,"

writes Chaucer: and the whole district is one of "extensive marshes and silt lands,—ramified among low hills of gravel, sand, and clay,—materials drifted from the N. and N.W. parts of England, and enclosing some rocks derived from Scotland and Norway, or more distant regions. In the hollows of these masses occur small lacustrine

deposits, with bones of elk, stag. boar. &c.: while in them and in the drift. and in the flinty covering of the chalk, elephant's bones sometimes occur."—Phillips. There is much planted, but no natural wood: although oak, yew, and fir are found abundantly in the ancient deposits. The land is for the most part of extreme richness, and the crops of grain are magnificent. There is no picturesque scenery. The district is drained (so far as any natural drainage is found in it) by the Hull river, the name of which possibly enters into that of Holderness—Hol-deira-ness the "ness" or projecting headland of the hollow (hol) of Deira? An extensive and complicated system of drainage, however, has been introduced about Hull and throughout Holderness since the end of the last century: and the result has been that large districts, which were formerly either marsh lands or altogether under water, have been brought into the highest state of cultivation.

In the days of the Confessor, Holderness was divided among many over-lords,-the great Earls Morcar and Tostig, besides Ulf, famous for his grant to York Minster (see Aldborough, Rte. 6) among them. Conqueror gave the greater part of the territory to Drogo de Beurere (so the name is given in Domesday-Beveren), a Flemish adventurer who had joined his host. He built a castle at Skipsea, as "caput baronise," of which the only traces are the keep, the mound, and some outworks (see present route, post). On the death or flight of Drogo, William gave Holderness to Odo, a son of Stephen Count of Champagne, who married Adeliza, the Conqueror's niece. (Odo, it is said, found Holderness a barren country, bearing nothing but oats; and the king, on his complaint, gave him Bytham in Lincolnshire, "to feed his infant son with wheaten bread.") Odo was also Earl of Albemarle (Aumale, on the Bresle river,

N. of Rouen). The seignory con- | Stat., and passing the small stations tinued in the hands of the powerful house of Albemarle until the reign of Edward I., when it reverted to the Crown for want of heirs. (Among the lords of Albemarle, succeeding either directly or as husbands of heiresses, had been-William le Gros, one of the English leaders at the battle of the Standard (Rte. 16), after which he was created Earl of Yorkshire-he was the builder of Scarborough Castle (Rte. 12); Baldwin de Betun, the friend and favourite of Cœur de Lion: and three Williams de Fortibus. The last heiress, Aveline, was married to Edmund Earl of Lancaster, son of Henry III. died without issue, and her vast inheritance passed to the Crown.) Edward I. retained Holderness in his own hands; Edward II. gave it to Piers Gaveston. It then reverted to the Crown; and after grants to various persons (among them Thomas of Woodstock, 6th son of Edward III.: and Thomas Duke of Clarence, 2nd son of Henry IV.), Holderness was bestowed by Philip and Mary on Henry Neville, 5th Earl of Westmoreland, who gave it to his son-in-law, Sir John Constable, of Burton Constable. The Constables still hold the "seignory, liberty, and manor" of Holderness; but the present lord is not in direct descent from the first. Cuthbert Tunstall of Wycliffe, the Sheldons, and finally Sir Thomas Clifford, all connected with the ancient Constables, have succeeded to the lordship, and taken the name of Constable. (For an ample account of the descent of the seignory, see Poulson's 'History of Holderness.') From a very early period until the grant to the Constables, the "caput baronize" was at Burstwick, where was a castle and a park (see Rte. 6). Burton Constable has since been the head of the seignory.

Leaving Hull from the Paragon Holderness. The first abbot, Adam,

at Stepney and Wilmington (see Rte. 6), we reach

5 m. Sutton Stat. The ch., Dec. and Perp., has been restored, and contains the tomb, with effigy, of Sir John de Sutton, died 12th Edw. III. The father and mother of the poet Mason are buried here.

[2] m. N. is the ch. of Wanhen (pron. Wawne), chiefly Perp., but hardly worth a visit. In the parish, 11 m. farther, are the very scanty remains of Meaux Abbey, founded 1150, by William le Gros, Earl of Albemarle, in order to obtain absolution for the non-fulfilment of his vow to join the Crusade. The abbey was Cistercian, and was peopled from Fountains. Like the rest of their order, the monks of Meaux suffered much during the reign of John, and were at one time sheltered by Baldwin de Betun, in his castle at Burstwick. The abbot and 22 monks died of the black plague in 1349. At the Dissolution the clear revenue of the abbey was 298l. The site has passed through many hands (one of its owners was Elizabeth's Earl of Leicester): but the buildings, which are said to have been very stately and extensive, were soon pulled down, and little now remains beyond a small fragment of wall, and a gateway. The mosts which surrounded the abbev, and the site of the ch., are still traceable. Some tesselated pavement (of very good design), and the tomb-slabs of a lady, and of an abbot of the monastery, may be seen in the garden of the farmhouse. There is much fine old wood; and the ground, which is rather elevated, affords views towards Beverley and the Wolds. Baldwin de Betun was buried here. The name Meaux had been given to this place by a certain Gamel, of Meaux, in France, who had accompanied the Conqueror to England, and settled in

called it "Melsa." The chronicle of I Meaux (de Melsa) from 1150 to 1400. has been edited, in the Rolls series, by E. A. Bond.

71 m. Swine. (The name may, perhaps, refer to a creek which anciently reached as far as the village, and "Swynhumbr," mentioned as a port in the reign of Ed. I., probably represents this place. So the "Zwyn" was the arm of the sea which once stretched inland to Bruges, and Swine is the name of the passage between the islands of Wollin and Usedom, at the mouth of the Oder. Swinemunds is the town at the sea entrance of this passage.) The ch. here, formerly that of St. Mary's Priory, has been restored, and is worth a visit. priory, founded by Robert de Verli, in the reign of Stephen, was for Cistercian nuns. The church was originally cruciform, with a central tower; but the ancient nave has entirely disappeared, and the present tower dates from 1787. The rest of the ch. shows late Norm. (Trans.) work (piers, arches, and clerestory), with later additions. The nuns' seats, with misereres (Dec.), remain. the end of the N. aisle is the Hilton chapel, containing some monuments of the Hiltons, Lords of the Manor of Swine from the beginning of the 13th cent. to the reign of Henry VI. The oaken screen, through which the chapel is entered, was added by Lord Darcy (the then Lord of Swine) in There are monts. with effigies 1531. for Sir Robert Hilton (circ. Henry V.); and two others, for knights and ladies of the same family, and of earlier date (Hen. IV., Edw. III.). In the wall of the S. aisle are two Hilton effigies, circ. Rich. II. are much shattered and defaced. About 1 m. N.W. of the ch. was a Roman camp, all trace of which has nearly disappeared. An urn, containing nearly 1500 copper coins (the earliest, of Constantine the Great), was found here 1826. Near the ch. | Clifford Constable), one of the largest

is a mound surrounded by trees, which local tradition asserts to be the grave mound of Swegen or Sweyne, the Danish king of England, who died at Gainsborough, A.D. 870. Swegen was really buried in his own church of Roskild in Denmark, and his name is in no way connected with that of Swyne.

81 m. Skirlaugh Stat. is still in the par. of Swine.

South Skirlaugh (Pop. 2246), on the S. bank of astream called Skirlaugh Beck, is remarkable as the birthplace of Walter Skirlaugh, the munificent Bp. of Durham (1388-1405), who is said to have been the son of a sieve-makera parentage very probably invented from his armorial bearings, six osier wands interlaced in cross. Bp. Skirlaugh became the proprietor of an estate here, on which he built the beautiful chapel which still remains. and is an excellent example of early Perp. It consists of a western tower. crowned by a parapet of great elegance; and of nave and chancel, of which the division was only marked by the screen, no longer existing. There are six bays on either side, divided by pinnacled buttresses. The details deserve attention; and the grace of the little building amply justifies Pugin's selection of it for his 'Contrasts,' where it appears on the same plate with St. Pancras, London. It was probably unfinished at the time of Bp. Skirlaugh's death, since his will provides 200 marks for its completion.

The school adjoining was endowed with 20% a year by Marmaduke Langdale, by will dated 1609.

101 m. Burton Constable Stat. From this station the tourist (having ascertained that the house is shown, which is not always the case) may visit the stately park and mansion of Burton Constable (Sir F. A. Talbot houses of its class in Yorkshire, though I some of which are fine. The grand scarcely one of the most interest-The manor began to be called Burton Constable (say the heralds) after the marriage of Ulbert, son of the "Constable" who fought on the side of the Conqueror at Hastings, to Erenburch. (?) heiress of Burton. From that time the Constables held it in direct succession, until, at the beginning of the last century, it passed, for want of heirs, to Cuthbert Tunstall, nephew of the last William Constable. The Sheldons and Cliffords, who have since held it, were all connected with the Constables, and have assumed the name. Sir Henry Constable was created Viscount Dunbar by James I. : that title became extinct on the failure of the direct line.

The Park of Burton Constable is about 51 m. in circuit; flat towards the E. and S. E., but it rises gradually westward towards "Roe Hill,"-no very great height, but commanding wide views over the flat country, toward the Humber and the Wolds. The park is well wooded, and contains a lake of 16 acres. The fallow deer are numerous: and there are two "paddocks" for red deer, which are regularly hunted. A herd of wild cattle (Bos Urus), resembling those of Chillingham and of Chartley, was long preserved here; but they were destroyed by distemper toward the middle of last century.

The house is of various dates; but the two principal fronts (E. and W.) may be temp. James or Charles I., although they have been altered ;the W. front apparently by Cuthbert Constable (Tunstall), whose monogram runs along the parapet. mass of the house is said to be of Henry VIII.'s reign. In the entrancehall are some family portraits, including that of the first Lord Dunbar. Many other pictures (none, perhaps, of great interest or importance) are scattered throughout the apartments,

staircase, and the library (110 ft. long), are especially worth notice. Many important documents connected with the history of Holderness (includings Dade's collections, on which Poulson's history is founded) are preserved here; and the MS. library includes all the collections of Dr. Burton, editor of the 'Monasticon Eboracense,' besides the monastic charters rescued from the ruins of St. Mary's Tower, York, in 1644. The house contains a R. C. chapel.

Crossing the little stream of the Lamwith, which rises near the E. coast, and runs across Holderness to fall into the Hull river, and passing 111 m. Whitedale Stat., the wooded park of Rise Hall (R. Bethell, Esq.) is seen l. The house dates from 1820. The Bethells have been here since the reign of James I. The ch. of E. Eng. character was rebuilt in Rise Bush, a plantation of ash-trees on a rising ground, is visible from a great distance, and is one of the landmarks of Holderness. The church of Long Riston, 11 m. W. of Rise, on the road from Hull to Bridlington, is Perp., with a modern chancel, but of little interest.

121 m. Hatfield Stat. The single object of interest here is the fragment of an ancient cross, of somewhat unusual character, which stands at the junction of three narrow roads. On the shaft of the cross is a vine springing from a vase or chalice. The vase rests on four couchant lions.

Passing rt. Goxhill, where the ch. was rebuilt in 1840, and 151 m. Hornsea Bridge Stat. (over the beck that runs into the sea from Hornsea Mere), half a mile farther we reach

16 m. Hornsea Terminus. (Hotel, The Marine, but inquiry should be made at Hull whether it is open. It is closed in winter. It stands on a rising ground, looking to Flamborough Head N., and over a wide extent of low coast.)

Hornsea (Pop. 3233), like Withernsea, has some pretensions as a watering-place. Only those, however, who wish for entire quiet, and who can find interest in the peculiarities of this unpicturesque coast, should seek it, although there are some pleasant walks in the neighbourhood of the Mere. Hornsea now stands on the cliff, but there is a local rhyme which runs—

"Hornsea steeple, when I built thee Thou wert ten miles off Burlington, Ten miles off Beverley, And ten miles from the sea."

The Church, which stands high, is Dec. and Perp.; the portions of the latter period (clerestory and chancel) very good. There has been a chantry on the S. side, the traces of which remain; and under the chancel is a crypt, occasionally used in former days by smugglers. The church has been restored under the care of Sir G. G. Scott, at a cost of more than 3000l. In the market-place are the remains of a Perp. cross.

The point of greatest interest at Hornsea, however, is the Mere, which closely adjoins the town, and is the largest in the county-nearly 2 m. long, 5 m. in circumference, and 2 m. across at its broadest part. Iŧ is dotted with small wooded islands, and abounds with pike, perch, eel, and roach. Until the Dissolution. Hornsea belonged to St. Mary's Abbey in York; but in 1260 (44th Henry III.) the Abbot of Meaux claimed a right of fishery in the S. part of the mere. Against this claim the Abbot of St. Mary's protested, and it was agreed to decide the matter by combat. Both abbots provided their champions-more than one, apparently, on either side. horse was then made to swim across the mere, and stakes were fixed to mark the boundary of the portion

claimed by the Abbot of Meaux. The fight lasted from morning till night, when the champions of Meaux were beaten, and the undisputed right to the mere remained with the Abbot of St. Mary's. (A remarkable illustration of such a judicial combat occurs on the brass of Bishop Wyvil (died 1375) in Salisbury Cathedral. Below the figure of the bishop, who is represented above the portal of a castle, is that of the champion (in close-fitting jack and battle-axe), who recovered for the see the Castle of Sherborne, which had been alienated since the time of Stephen.)

"Hornsea Mere is now undergoing some of the changes which are traced in the old lakes cut into by the sea at Owthorne, Sandley Mere, and other places. It is slowly filling up by depositions of vegetable matter and earthy sediment round the shores and islands. The sea is advancing steadily to destroy the barrier of the When that happens, a section will be presented like what is seen at many of the old drained lakes in the cliffs of Holderness—a hollow in pebbly clays or sands, covered by fine argillaceous, perhaps shelly sediments, over which peat is spread; and, above all, the sandy, loamy, and argillaceous accumulations which are in daily progress."—Phillips.

(The church of Sigglesthorne, 3½ m. from Hornsea, has an E. Eng. tower of some interest. The church was restored in 1848. Near is Sigglesthorne Hall (Sir W. Wright). The country round is well wooded, and picturesque for this district. Wasand Hall, at the W. end of the mere—which is sometimes called Wasand Mere—is the seat of Henry Strickland Constable, Esq.)

The coast N. of Hornsea is of the same character as that below. "Low cliffs, occasionally diversified by peaty deposits and shelly mark—the

reached, and other lacustrine deposits appear. A fine elephant's tusk was found in the cliff here."-Phillips. Atwick church is uninteresting. Skirlington Hill, farther N., is 60 ft. high-here a great elevation. Skipsea (Pop. 1812, 3 m. from Atwick. and 54 from Hornsea) was the Castle of Drogo de Beurere, the first Norman lord of Holderness (see the present route, ante). What seems to have been the mound of the keep, with portions of a high circular rampart beyond it, are the only traces. is very probable that this mound was the "motte" of a stronghold existing here before the Conquest. The mound is known as "Albemarle Hill," and Mr. Phillips suggests that it may have been a natural gravel mound like the "barf" at Brandsburton, scarped by the Norman (or earlier) builders. (Skipses Brough, the name of the village below, seem also to refer to this mound-brough, like barf, signifying a hill.) Between the mound and the encircling rampart are certain marks in the turf, said to be the footprints of a brace of combatants, who here, at some unknown period, fought a duel for the sake of a lady. The marks are carefully cleared, and with some ceremony, at Martinmas by farm lads on the Castle farm, who hold that their coming year (they come into their places at Martinmas) will be unlucky if they neglect this service. The church at Skipsea is E. Eng. (nave arcades and chancel arch) and Perp. (outer walls, clerestory, and tower). It was completely restored in 1866. "Cliffs, nowhere exceeding 30 ft. in height, continue by Skipsea, broken here and there by freshwater deposits; but for the most part, from hence to Bridlington, these perishing cliffs show at the bottom the amorphous boulder clay, in the middle finer and more laminated sediments, and above all lavers | wegian fleet had been moored at

beds of old lakes—continue to At- of chalk and flint gravel, variously wick, where the height of 40 ft. is inclined, and accompanied by many marks of local agitation and drifting."-Phillips.

> The ch. of Ulrome (1 m. N. of Skipsea) has some very early portions, and is said to date from before the Conquest. The place preserves the name of the Danish Ulf (Ulfreham).

> For Barmston, 11 m. N., see Rte. 10

ROUTE 8.

YORK TO BEVERLEY AND HULL BY MARKET WEIGHTON -- ALSO SELBY.

[5 trains daily in 14 hr. to Hull, 1 hr. to Beverley.]

Passing the stations at Earswick. Warthill and Holtby, there is nothing to call for notice until we reach

92 m. Stamford Bridge Stat., where the line crosses the Derwent. Here we are close to the scene of the great battle (Sept. 23, 1066) between Harold of England and Harold Hardrada of Norway, in which the latter fell. There is not much to be seen here; but the site is of far too great historical interest to be passed without notice. After the great NorRiccall (Rte. 1), Harald of Norway | Senlac, or Hastings (Oct. 13), in and his host advanced inland as far as Gate Fulford, 2 m. S. E. of York, where they were met by Eadwine and Morkere, to whom the care of the North had been committed. The English were overpowered and driven back into York, and the city capitulated 4 days later (Sept. 14, 1066), 150 hostages were given to Harald for the fidelity of the city alone. Hostages for the whole shire were to be given afterwards, and to be delivered at Stamford Bridge - a removal from York having probably been rendered necessary by a want of provisions, since all that the banks of the Ouse could supply must have been exhausted. There the Northmen were encamped on both sides of the Derwent, when Harold of England, who had marched with wonderful rapidity from the South, gathering in recruits from various districts on his way, reached York on the morning of Monday, Sept. 25, and at once pressed onward to Stamford Bridge. He found a portion of the Norwegian host on the right bank of the stream, and quite unprepared for his onslaught. were driven across the stream; and it was at this time that a nameless Northman kept for a time the wooden bridge over the Derwent against the whole English army. Forty men fell beneath his axe, an arrow was shot at him in vain; but at last an Englishman crept under the bridge and pierced him through beneath his corselet. The English host then passed the bridge, the battle raged throughout the rest of the day, Harald of Norway and Tostic, the traitor Earl of Northumbria, brother of the English Harold, both fell, and the great mass of the Northern host at last lay dead on the banks of the Harold of England returned to York, where on the following Thursday the news was brought

little more than a fortnight after Stamford Bridge. For the details and a true history of the battle of Stamford Bridge, see Freeman's 'Norm. Conq.,' III. chapter 14. He has shown that the grand description in the Saga of Harald Hardrada is not to be trusted; and that the famous offer of the English king to his Norwegian namesake, of "seven feet of ground, or as much more as he is taller than other men." is at least doubtful.

The Derwent is now crossed at Stamford by a bridge of stone. This is not on the site of the earlier wooden bridge, which was raised on the stepping-stones giving name to the place (Stane-ford). The true position of this bridge is preserved by local tradition, and by the evidence of the course of the roads converging towards it. The ground is nearly level, and on the left bank of the stream is known as "Battle Flats." The Wolds are visible in the distance. It is said that the famous exploit of the Englishman who killed the hero of the bridge is commemorated at Stamford Feast by certain pies made in the form of a tub or boat, like that which he may have used for getting under the bridge.

[The river Derwent, north Stamford Bridge marks the division between the N. and E. Ridings. About 3 m. above Stamford Bridge is Aldby Park (H. Darley, Esq.), which is possibly (as Camden long since suggested) the site of the Roman Derventio, an old dwellingplace of the Northumbrian kings. It was at this "royal villa on the Derwent" that the faithful thegu Lilla gave his life for the Bretwalda Edwin: and here that Eanfled, the Bretwald's firstborn, was the first of Northumbrian race to be received to him of William's landing; and he into the fold of Christ (Beds, H. E. marched thence to fight the battle of ii. 9). The place is thus of great

interest for the student of early Nor- | his deathbed, his wife kneeling at a thumbrian history; and Freeman suggests that, as a house of the later earls, it may have been the head-quarters of Harald Hardrada before Stamford Bridge. A mound surrounded by a fosse remains in Aldby Park, and probably marks the site of the ancient dwelling (see, however, the present route, post, Londesborough. The site of Derventio has by some been placed there,-by others at Malton, Rte 12.) The park itself is well wooded, and commands views of the Derwent. 1

121 m. Fangfoss Stat. Fangfoss and Wilberfoss (the latter 1 m. S. of the Stat. and on the high road from York to Market Weighton) are villages on a tributary of the Derwent. The latter place is of some interest from having given name to the family of Wilberforce, whose estates here were sold in 1710.

161 m. Pocklington Stat. This is a market town (Pop. 6584. Inn: the Feathers), with a ch. of some interest, of which the tower is conspicuous from the station. The nave is E. Eng., with a Perp. clerestory. The chancel was much altered in the Perp. period. It has a chapel opening from it on the N. side which is E. Eng. or late Transition. Remark in this chapel, and on the S. side of the nave, the beak sculpture at the intersections of archmouldings—an early indication. The W. tower arch is Perp. and very lofty, with sculptures of heads alternating with bold leafage. At the east end of the N. chapel is a monument for Robert Denison of Kilnworth Percy, died 1829, erected by his son, who died in 1862. Above, and under glass, is some very fine Flemish carving. Here is also a curious monument for Thomas Dolman, a J.P. under Elizabeth, "De selectiori illo numero qui vulgo Quorum dicuntur," d. 1589. He is represented on and stained windows.

desk. The monument was restored in 1850. The ch. was restored and some stained windows inserted in the same year. In the ch.-vd. is a lofty cross (the shaft is new) with gabled head, having on one side the Crucifixion, on the other a Trinitythe Holv Father holding the crucified Saviour in his arms. There is an inscription, "Orate pro anima Johannis Soteby." The ch. tower. of 3 stages, is Perp. There is a free grammar school at Pocklington, the property belonging to which was originally left to a guild founded by John Dolman, Archdn. of Suffolk, whose family long held the manor. On the dissolution of guilds, temp. Hen. VIII., the school received this property, and the revenue is now about 1000L a year.

The visitor with time at his disposal may be advised to drive or walk across the country from Pocklington to Malton, or from Pocklington to Fimber, where is a station on the rlv. between Malton and Drif-In this manner he will see something of a very peculiar corner of Yorkshire, the district lying immediately under the Wolds; and if he go to Fimber, may visit a characteristic portion of the Wolds themselves, and inspect some of the churches built or restored by Sir The distance from Tatton Sykes. Pocklington to Fimber is 14 m. From Pocklington by Kirkby Underdale to Malton is at least 18 m. But as the roads are intricate and sometimes bad, and as there may be sundry diversions from them in order to see churches, &c., one whole day should be allowed for the expedition.

Kilnwick Percy lies L of the road on leaving Pocklington. Within the grounds of the Hall is a small Norm, ch., with modern carved oak stalls The road

runs under the Wolds to Bishop's the ch. is in admirable order, and St. Edith) which should be seen. The original building was late Norm., with lofty chancel arch and fine S. door. The aisles, and probably the W. tower, were added by Abp. Zouch (1342-1352). The ch. has been thoroughly restored by J. L. Pearson, at the sole expense of Sir Tatton Sykes. The stained glass is by Clayton and Bell. The roofs are throughout new, and have been most elaborately coloured and decorated. All this work is very good, rich but quiet. The Norm. door deserves special notice. It has a double roll moulding with ornaments cut in the soffit, so that there is apparently no place for the door hinges. Remark among the ornaments on the S. side the Abp.'s cross, with pointed staff. The ch. and village stand picturesquely, in a long valley with wooded hills above. The country here is much broken and varied, and the rich wood which clothes it contrasts sharply with the bare wolds under which it lies. consists of greensand, grits, and Oxford clay, descending into the marks and sandstones of the plain of York.

1 m. beyond Bishop's Wilton the old high road from York to Bridlington is crossed; and a cross road leads through a wooded, park-like district, to Kirby Underdale, 11 m. Here is a small ch. on the slope of the dale, in a tossed and broken The earliest — probably country. pre-Norm.-ch. here was without aisles, and had an apse, the foundations of which have been found. Then came Trans.-Norm. arcades and aisles—the wall of the older ch. showing as a step on the S. side. earlier ch. seem to have been retained and pierced for arches when the

Wilton, where is a Church (ded. to has been carefully restored by Street. at the cost of Lord Halifax, and the rector, the Rev. T. J. Monson.

... Dr. Thirlwall, Bp. of St. David's. was for some time rector of K. Underdale, and here wrote his 'History of Greece.'

(11 m. W. is Bugthorpe, where the ch. has Norm. portions, and is worth a visit.)

(a) Cross-roads leads by Burythorpe to Mallon, about 10 m. from K. Underdale. The views from the high ground over the plain of York are singularly fine, with the great towers of the Minster rising as a landmark in the midst of the scene. The tourist who follows the crossroad should make a point of turning off l. and visiting Acklam Wold, above a village of the same name. This is a famous "meet" of the Wold hunt; and a deep hollow valley suddealy opens to the lower country,one of the steep-sided hollows so characteristic of chalk and of the The scene here is very fine and peculiar, and a vast extent of country is commanded. That from Leavening (pron. Leevening) Brow, a little beyond this point, is described in Rte. 11. The road here descends: rt. is Birdsall (Lord Mid-The village dleton, see Rte. 11). of Burythorpe (ch. modern) is passed through. Langton Hall (Mrs. Norcliffe) lies rt.; and the road, again crossing a rise of wold, enters Malton (Rte. 12).

(b) The Bridlington road will lead from K. Underdale to Fimber Stat. (6 m.), and passes over the Wolds The lower part of the tower has her- through Fridaythorpe, where is a ring-bone work. The walls of the small Norm. ch. of the usual Wold type. It will be better, however, to drive or walk from K. Underdale to Trans. work was done. On the N. Thizendale, where the wold scenery side are traces of a clerestory. All is very characteristic, and where is a small new church (G. E. Street, arch), of Dec. character, built by Sir Tatton Sykes. The view from the ch.-yd. is striking. The road winds through the valley to Fimber. The ch. of Fimber (nave, chancel, and W. tower) is of early Dec. character, and has been restored and elaborately decorated by Street. From the ch.-vd. the woods of Sledmere are seen N. For a general notice of the Wolds see Rte. 11. The high ground passed on this excursion commands wide wold prospects, extending to the sea, and having the memorial tower of Sir Tatton Sykes as a landmark.)]

Beyond Pocklington the country becomes richer and more wooded: L is seen the ridge of the Wolds, extending in a long line towards the The rly. approaches very near these chalk "cliffs" at (19 m.) Nunburnholms, or Burnby Stat. The ch. of Burnby, with Norm. portions, is Nunburnholme is the rectory of the Rev. F. O. Morris, well known for his 'History of British Birds.'

F4 m. N. from Nunburnholme Station is Warter Priory (Lord Muncaster), in one of the prettiest of the The Priory valleys. founded for Augustinian canons in 1132, but no ancient portions exist. The present house has much the character of a French chateau, with steep roofs and lucarnes. The gardens are fine and the valley is well In the village is a good wooded. modern church (Haberfield, archit.), built by the late Lord Muncaster in 1862.] At

21 m. the Shipton and Londesborough Station is reached.

Shipton has a small Norm. Church of some interest. (There is also a Norm. ch., of nearly the same date, and of more importance, "restored" in 1860, at Hayton, 3 m. from Shipton, third Earl of Burlington. Yorkshire.

on the York road. The windows have been filled with stained glass. These early churches indicate the antiquity of the settlements here, on the line of Roman road. See post.) The archeologist should here leave the railway and walk through the park of Londesborough to Goodmanham, whence he may descend to Market Weighton. The round will be between 3 and 4 miles. An avenue of trees, said to have been planted at the suggestion of David Garrick, leads from the hamlet of Thorpe-in-the-Street, close to Shipton (the name indicates the line of a Roman road running from York, under the Wolds, to the Humber), to the site of the former house of Londesborough. This was pulled down by the late Duke of Devonshire, and nothing now remains but the terrace on which it stood, from whence a magnificent view (looking S. to the Humber, and W. towards the Vale of York) is commanded. (There is a small modern house called Londesborough Lodge, toward the N. end of the park.) The estate was long the property of the Cliffords, and passed from them-by the

marriage of the Lady Elizabeth

Clifford, daughter of the last Earl

of Cumberland, 1635, to Richard

Earl of Cork and Burlington—to the Boyles, whence it came to the Dukes

was built by the third Earl of Burlington, the friend of Pope and

Garrick-who also built Burlington

House in London. The estate was

sold by the duke for 470,000L to

George Hudson, and was purchased from him for the same sum by the

late Lord Londesborough (Lord Al-

bert Conyngham), who took his title

Part of the house

of Devonshire.

(1849) from it. Londesborough Church closely adjoins the park. Several of the Clifford's are interred here; besides many Boyles, including Pope's friend, the Thomas Wentworth, afterwards the great Earl | of Strafford, was here married to Lady Henrietta Clifford.

There was probably a Roman villa at or near Londesborough; since Roman coins and other relics have been frequently found in the park and gardens. (This villa was afterwards, perhaps, appropriated by the kings of Northumberland and the conferences of Edwin with Paulinus. may, perhaps, have been held here. See post, and the present route, ante, Aldby.) Many fine old trees are scattered over the park,-through which the tourist should walk to the site of the old house, descend into the vallev below it, and then mount the opposite hill, up which the park extends. From the top of this hill he will look down on the church of Goodmanham, -no doubt the "Godmundingaham" of Bede, and the scene of the conversion of Edwin of Northumbria to Christianity (A.D. 625), one of the most remarkable events in the early history of Yorkshire.

Paulinus—consecrated bishop by Justus, 4th Archbp. of Canterburyhad accompanied into Northumbria Ethelburga, the Christian daughter Ethelbert of Kent, marriage to Edwin of Northumbria (A.D. 625). Edwin was still a pagan. but was not without Christian tendencies. At his royal villa on the Derwent he was suddenly attacked by Eumer, a messenger from Cwichelm of Wessex, and his life was only saved by his thegn Lilla, who interposed his own body between the king and the assassin. On the same night (Easter-eve, 626) Ethelburga bore a daughter, Eanfled. The king, says Bede, returned thanks to his gods; but Paulinus, who was present. gave hanks to Christ, and assured Edwin that the queen's safety was Edwin owing to his intercession. promised that, if Paulinus by his prayers should procure him the victory in the war he was about to

would become a Christian. He was victorious: and on his return received much instruction from Paulinus, but would not consent to be baptized until Paulinus reminded him of a mysterious passage in his former life. A conference was then held, apparently at the villa on the Derwent, in which Coifi, the king's chief priest, declared that, although he had faithfully served his gods, they had been of little help to him, and that he was ready to hear of a more powerful deity. He was followed by another chieftain, whose words, as reported by Bede, have been thus versified by Wordsworth :--

"Man's life is like a sparrow, mighty king!
That, stealing in, while by the fire you sit Housed with rejoicing friends, is seen to flit Safe from the storms, in comfort tarrying. Here it did enter-there, on hasty wing Flies out, and passes on from cold to cold : But whence it came we know not, nor behold

Whither it goes-e'en such that transient

thing The human soul; not utterly unknown While in the body lodged, her warm

But from what world she came, what woe or weal

On her departure waits, no tongue hath This mystery if the stranger can reveal, His be a welcome cordially bestow'd!"

Coifi then desired to hear Paulinus himself: and after he had listened to him for some time, he pronounced himself ready to embrace the new faith, to which the greater part of the king's thegas were evidently inclined, and suggested that the temple and altars should at once be destroyed. Edwin agreed; and Coifi, declaring it was right that he. who had been the chief worshipper of the false gods, should be the first to profane their temples, demanded arms and a horse from the king (for the priests were not allowed to bear weapons, or to ride, except on a mare), and, riding to the temple, shot against it the lance which he carried in his hand. The people, says Bede, undertake against Cwichelm, he thought him mad; but he followed up his deed by ordering the burning of the temple with all its enclosures. The "place of idols" was still shown in Bede's time, at Godmundingaham (probably the "ham" or home of the Godmundings—sons of Godmund). Edwin himself was baptized at York (see York, Rte. 1) on the Easter Day (April 12, 627) following that on which his daughter Eanfied had been born.

It seems probable that the royal villa of Edwin and the heathen temple were at no great distance from each other. Mr. Wright suggests that the first may have been at Londesborough, which was close to the Roman road, and where, as we have seen, there are traces of a Roman villa. (But on the other hand. Bede expressly asserts that the "villa regalis" was "juxta amnem Derventionem" near the Derwent, which Aldby is, and Londesborough is not. See the present route, ante, Aldby.) The temple was certainly at Goodmanham-also near the same Roman road. The site was in all probability that on which the ch. now stands—a rising ground in the middle of the village. There are some traces of a vallum encircling the ch.-vd.; and nothing is more likely than that the site of the great temple should have been Christianized by the erection of a ch. on it. There are some extensive and strange-looking earthworks in a field about 100 yards S. of the ch., on the other side of the rectory, which have sometimes been looked upon as the remains of the temple; but Mr. Roach Smith, who has carefully examined them, pronounces them to have been caused by a modern chalk-pit. Drake (the historian of York) had made excavations on the same spot, and had come to the same conclusion. The Church of Goodmanham has E. Norm. portions. The chancel arch is depressed; and the capitals of its shafts are of somewhat unusual design. The main areade is Trans. Norm.

old font (rude E. Norm.) is certainly not that in which Edwin was baptized. This was Stukeley's suggestion. But the baptism took place at York, and no doubt by immersion. Stone fonts, such as this at Goodmanham (which is hexagonal, plain and rude), could not have come into use until England had been completely Christianized.

The Wolds at the back of Londesborough and Goodmanham are covered with sepulchral tumuli. From Goodmanham the tourist may walk down the hill (about 1 m.) to

(23 m. from York by rly.) Market Weighton Junct. Stat. (the name, possibly marks its position on the Roman road — Wea-tum — the town on the way). Pop. 4835. Inn: Londesborough Arms. The ch., restd. (E. Eng. and Perp. with a Trans. Norm. west tower), is of little interest: and unless the visitor cares to make inquiries as to the exact birthplace of William Bradley, the "Yorkshire Giant" (7 ft. 9 in. high, 27 stone in weight at 19), born in this town in 1792, and died in 1820, aged 33, he need not linger in Market Weighton.

A great sheep fair (at which 60,000 sheep are sometimes collected) is held here in September. A navigable canal (10 m. long) has been made from the Humber, near Flaxfleet, to within 1½ m. of the town, and serves the double purpose of transport and drainage of the fens.

The country round Market Weighton is rich in grave mounds, many of which have been explored by Canon Greenwell. At Arras, 3 m. on the road to Beverley, are many barrows, two of which yielded the remarkable chariot wheels and horse furniture now in the museum of the Yorkshire Philosophical Society (see Rte. 1).

[Market Weighton to Selby Rly. runs S.E. to Selby (17 m.) through a flat country of little interest. The only places on this line that call for notice are Holme and Bubwith.]

Passing the station at Harswell Gate (the small ch. of Harswell was built in 1871) we reach

5 m. Holme on Spalding Moor Stat.; so called to distinguish it from Holme on the Wolds, N.E. of Market Weighton. The estate of Holme belonged to the tried loyalist and faithful general of Charles I., Sir Marmaduke Langdale, in whose family it long remained: the Hall is now the property of H. Stourton, Esq. The ch., a very marked feature in this low country, stands on an eminence commanding extensive views over a tract of land now fat and well cultivated, in consequence of drainage; though in former times a labyrinth of morasses, so that a cell was established by certain members of the great families of Vavasour and Constable, and two monks maintained in it to guide travellers on their way. Not far from the ch. is a tall beacon, with two branching irons near the top, to support fire-grates; it was frequently used to signal alarms during the revolutionary war, and communicated with beacons on 3 other hills, Bainton, Wilton, and Huntley, each giving a name to a division of Harthill Wapentake.

There is a Stat. at Foggathorpe; and

10g m. from Market Weighton the rly. crosses the river Derwent at

Bubwith Stat. The Church here seen rt. (a "mediety" of which belonged to Byland Abbey from 1369 until the Dissolution) is of some interest. The chancel arch is very good late Norm. with enriched shafts and caps. and an unusual arcaded

moulding surrounding the outer order. The piers and arches of the nave are E. E., as are probably the walls of the chancel, in which are inserted 2 Dec. windows (S. side) and a good Perp. E. window. The tower is Perp. and has originally been open to the ch. Some helmets and mantling belonging to the Vavasours of Melbourn hang in the chancel. It is greatly to be wished that a hideous brick school-room, attached to the N. side of the chancel, and blocking up two windows, should be swept away.

Bubwith, Pop. 1748, was the birthplace of Nicholas de Bubwith, Bp. of Wells in the early part of the 15th cent., whose beautiful chantry remains

in the nave of his cathedral.

[A short distance up the Derwent, on the l. bank, is Aughton, remarkable as the home of Robert Aske, leader in the "Pilgrimage of Grace," 1536. (See Froude, H. E., vol. iii., and Introd. to this Handbook.) The ch. has a low Perp. tower, and contains some memorials of the Askes. The ask or newt—the rebus of "Aske"—is on the ch. tower and buttresses; together with their shield of arms (or, 3 bars az.), and the inscription "Christopher, le secound fitz de Robart Ask Chr. oblier ne doy, A.D. 1536."

64 m. from Bubwith the railway reaches

17 m. Selby. (See Rte. 1.)]

[For the road from Market Weighton to Brough (9 m.) on the Selby and Hull rly., see Rtc. 6.]

The Rail to Beverley proceeds through a somewhat uninteresting country, to

interest. The chancel arch is very good late Norm, with enriched shafts tion. (The ch. of Goodmanham is and caps, and an unusual arcaded passed a short distance l. soon after

leaving M. Weighton.) There is again a station at

Cherry Burton Stat., where the rlv. crosses the old high road from Beverlev to Malton. (For this road, and the places of interest on it, see post: exc. from Beverley.) The ch. and village of Cherry Burton lie a short distance below the station, rt. ch. was rebuilt, 1852-3. The famous Bonner was for some time rector here; and at Cherry Burton (then known as North Burton) St. John of Beverley was born (see post). The rly, soon crosses the high road to Driffield: the towers of the Minster come into view; and we reach the station at

Beverley (Inns: Beverley Arms, comfortable; Holderness H.). This is an old-fashioned market town (Pop. 15,507) with a "staid, respectable aspect, as if aware of its claims to consideration." These claims are founded on its noble *Minster. St. Mary's Church is the second object of interest here.

Beverley is no doubt a place of considerable antiquity. It is probable that its later name—Beverley—records (as in similar instances elsewhere in England) a colony of beavers, which had established themselves here on the Hull river. The importance and reputation of Beverley, however, are due entirely to its patron saint, "St. John of Beverley," a short sketch of whose life will best be read here.

The future saint was born in the latter half of the 7th cent., of noble parents, at Cherry Burton, in the East Riding (see the present route, post), and was early intrusted to the care of Abp. Theodore of Canterbury, who educated him, and gave him his name of "John." Oxford has claimed him as her first Master of Arts, and his figure as a "fellow" was in one of the windows of the chapel of University College; but, says Fuller, "see-

There is | ing the solemnity of graduating was then unknown, a judicious Oxonian rejecteth it as a fiction "-not to add that St. John had been dead nearly a cent, before the birth of Alfred, the traditional founder of the university. It is more certain that he was the pupil of St. Hilds at Streonshal (Whitby). In 687 he was consecrated to the bishopric of Hexham. having lived for some time before in a hermitage at Harneshow on the Tyne; and on the death of Bosa. in 705, he was translated from Hexham to York. Amongst other good works in Yorkshire, he established a monastery at "Inderawood," where a little ch., dedicated to St. John, already existed. He enlarged this ch., and settled here a company of religious persons of both sexes, as was then usual. In 718 he resigned the see of York, and retired to this monastery, where he was received by the Abbot Bercthune, who narrated to Bede the many miracles of St. John which the latter has recorded in his history (H. E., v. 2-6). St. John died here May 7, 721, and was buried in St. Peter's Porch, a chapel attached to the ch.

Beverley thus became one of the three religious centres of Yorkshire— (the other two were York and Ripon). The reputation of "li bons Johans... celni ki gist a Beverli" spread widely throughout England. Miracles were performed at his tomb. In 1037 he was solemnly canonized by Pope Benedict IX., and (with the exception perhaps of St. Cuthbert at Durham) no saint was regarded with greater reverence north of the Humber than St. John. He took his place with the great champions of Christendom:—

"Come ye from the east, or come ye from the west.

Or bring relics from over the sea— Or come ye from the shrine of St. James the divine,

Or St. John of Beverley?"

Athelstane, on his way to Scotland,

prayed before the tomb, and promised | the ch. many privileges and gifts if he were successful, leaving behind him his knife (cultellum) as a pledge. He carried with him the banner of St. John, and on his return, victorious, offered his sword-the sword he had wielded in the great battle of Brunanburgh—at the altar; founded here a college of secular canons (if, indeed, it should not rather be said that he confirmed the original foundation), added much land to the endowment, and gave the ch. the right of sanctuary, which it enjoyed until the Reformation (see post). The traditional words of Athelstane's grant are recorded in a tablet in the Minster (see post).

The Confessor was a benefactor to the College. William the Conqueror (see Alured of Beverley, whose statement is of some value, since he wrote early in the following century.—Freeman, however ('Norm. Conquest,' iv. 289), suggests that the story of the preservation of Beverley is a legend. The authentic records of the Conquest give no hint that any exception to the harrying was made in any part of Northumbria) -- and Stephen both refrained (it is said they were miraculously prevented) from ravaging its lands. King John visited the shrine, and Edward I., after "waking a night" before it, carried off the sacred banner to the wars in Scotland, as Athelstane had done before him. (It had before been one of the banners —the other two were those of St. William of York and St. Wilfred of Ripon—which gave name to the battle of the Standard in 1138. See Northallerton, Rte. 16.) Henry IV. visited Beverley; and after the victory of Agincourt (Oct. 25, 1415, the feast of the translation of St. John of Beverley, as well as that of SS. Crispin and Crispinian), Henry V. made a pilgrimage to the shrine (from which, on the day of the battle, holy oil is said to have flowed "like drops the neighbourhood were driven to

of sweat") with his queen; and Abp. Chichele ordered that the day of St. John's death (May 7), as well as that of his translation, should henceforth be observed with increased ceremony. Offerings of considerable value were made at the shrine by these royal visitors, as well as by the host of ordinary pilgrims. (The annual value of the oblations was about 100 marks.) At the Dissolution the revenue of the College was 598L

The town of Beverley received its charter from Abp. Thurstan (1100), and was of some importance as a port (on the Hull river, which was open for navigation before the rise of Kingston. Beverley had many ships). The town was greatly under the influence of the Percys, whose Castle of Leconfield (see post) was 21 m. distant; and numerous offerings are recorded from the "Governors" of Beverley to their powerful neighbours. Charles I. fixed his head-quarters at Beverley (April 23. 1642) before the outbreak of the Civil War, and during the ticklish negotiations for the surrender to him of Hull and the war stores it contained. He returned hither on the night, when the gates of that fortress were shut in his face by Sir John Hotham. remained here watching the siege of Hull and the landing of arms and stores sent to him by his queen up the Humber. One Wm. Cuthbert of Beverley was a chief witness at the King's trial on the charge of levying war. Hotham's subsequent treachery to the Parliament being found out, he fled hither, but was seized by his own nephew, Col. Boynton, and sent to London, where he was executed on Tower-hill. The place had fallen into the hands of the Hothams, and afterwards (1643), when the royalist Marquis of Newcastle advanced against Hull (then held by Sir Thomas Fairfax), Beverley was abandoned as untenable, and was plundered by the King's troops, whilst all the cattle in

York. The plunder is said to have with E. and W. aisles, choir with exceeded 20.000L

Among the "Worthies" of Beverley are Alured, Treasurer of the Church of St. John, whose 'Annals.' ending with the reign of Henry I. were edited by Hearne in 1716, and are of considerable value: John Alcock, Bp. successively of Rochester, Worcester, and Ely (died 1500), in which last cathedral his superb chantry remains; John Fisher, the learned and unfortunate Bp. of Rochester, born here 1459, beheaded 1535; and John Green, Bp. of Ely, born 1706, died 1779. Bns. Alcock. Fisher. and Green, all received their first education in the Grammar School of Beverley.

The first point of interest in Beverlev is of course the *Minster, occupying the site of the church of St. John found here, and enlarged by St. John of Beverley, but now dedicated to the Blessed Virgin. Whatever the nature of St. John's foundation may have been, that which was established by Athelstane (A.D. 938), and which continued to the Reformation, was not monastic although the name "Minster," " Monasterium," was always in use here, as at York. It was a college of secular canons, presided over by a Provost (added by Abp. Thomas of York, 1070). The Provost of Beverley was a personage of great dignity, a fendal lord as well as a spiritual. Among the holders of the office was Thomas Becket, afterwards the sainted Abp. of Canterbury.

The single recorded fact bearing on the architectural history of Beverley Minster is the burning of the ch. on the night following St. Matthew's day (Sept. 21), 1188, the last year of Henry IL Whatever amount of destruction may have been wrought by this fire, it is certain that no part of the existing ch. is of earlier date. The plan comprehends nave, with

aisles, a lesser or eastern transept with eastern aisle, and an eastern Lady-chapel projecting beyond this transept. The whole building eastward of the nave (with the exception of one or two additions and insertions to be afterwards noticed) is E. Eng., dating from the first half of the 19th There seems to have been a considerable interval between the completion of this portion and the commencement of the nave. This is late Dec. (curvilinear), circa 1350. The N. porch and the great W. front are Perp., and date from the latter part of the same century.

The Minster had fallen into an almost ruinous state at the beginning of the last cent. A subscription was then made for its repair. Nicholas Hawkesmoor was appointed architect; and the King, George I., besides a grant of money, gave materials from the ruins of St. Mary's at York. which were brought to Beverley by water.

The ch. is built throughout of Tadcaster stone. The whole Minster, since 1867, has undergone a gradual, but true restoration, at the hands of Sir G. G. Scott. The roofs of both nave and choir have been decorated in gold and colour, the original colouring, some portions of which were found, having been followed as far as possible. Some windows of stained glass by Hardman have been inserted in the nave; and the Minster has recovered an order and rich-

ness well in harmony with its noble

architecture. The visitor should pass at once to the eastern portion of the ch., since it is the earliest in date, and its general design has been followed in the nave. In the great transept, as well as in the choir and parts beyond it, the arrangement is the same, each bay consisting of a main arch, resting on clustered piers; a triforial space above it, without a passage, but enriched by aisles and N. porch, great transept an arcade of trefoiled arches, resting from the wall, which cut an inner arcade of pointed arches supported by short plain shafts,—in the tympanum is a quatrefoil;—and a clerestory, with passage, in which the sharplypointed arches are supported on slender marble shafts. The roof is throughout E. E., and the vaulting shaft rises between each bay from a bracket just above the intersection of the main arches. The shaft is tripled at the string under the triforium.

The piers "exhibit a cluster of eight bold massive columns, suited to the position they occupy, and the weight they have to sustain. For the sake of variety, those which face cardinally are round, the alternate ones being brought to an edge; and many of the round columns have the vertical The triforial space above, with its intersecting arches, may be compared with similar arcades in the choir of Lincoln Cathedral (the work of St. Hugh, 1186-1200, and no doubt the original type, since it is more than probable that St. Hugh's was the first E. E. work in the kingdom). Both triforium and clerestory are much enriched with the dog-tooth moulding; and numerous small shafts of Purbeck marble occur throughout the whole work. All the original windows in the E. E. portion of the Minster are lancets. The doors in the fronts of the transepts have semicircular heads without, and are nearly flat-headed within, each being subdivided into two pointed arches. "The small space which could be allowed to the door, in order to admit of the fine composition of windows above, will satisfactorily account for the use of this form, which is no mark of an early date or imperfectly developed style. It constantly occurs in buildings of advanced E. E. character, especially in the North."-J. L. Petit. From the size of the piers at the intersection of the great transept, it is evident that a central

on slender clustered shafts detached N. front of the transer had an inclination of 4 ft. beyond its base at the beginning of the last cent., when it was restored to its vertical position; "perhaps," says Mr. Petit, "as wonderful an instance of mechanical skill as any we have on record." The restoration was effected by a York carpenter, named Thornton, by means of a huge frame of timber for screwing up the gable end at once. walls of both transents and of choiraisles are lined below the windows with a foliated arcade enriched with dog-tooth, and resting on Purbeck shafts with foliaged capitals.

The choir-screen of oak, carved by a Beverley man, was designed by Scott, and is good of its class. Within the choir, the visitor should remark the singular piers at the intersection of the lesser or eastern transept (adjoining the altar). They are "of a totally different design from those of the principal transept, and, indeed, every other part of the building. Instead of being carried up in continuous lines from the base to the spring of the arch, they are broken by horizontal strings into a series of stages, which project forwards as they ascend, and are terminated by a truncated cluster of columns, having a capital similar in its character to those in the other parts of the edifice."— J. L. Petit.

The stalls of the choir deserve careful attention. They have been much altered, and the lower portion, with the misereres, are probably earlier than the superb mass of tabernacle work which rises above them. The projecting brackets for figures (no longer existing), which form the top of the first stage of the canopy, are unusual. There are very peculiar and expressive heads in the canopy itself, some of which are evidently additions, and represent Georgian divines attired in wig and band. The tabernacle work itself dates from the best period, the tower was originally intended. The beginning of the 16th cent.

Filling the arch between the choir; and the N.E. transept, is the famous *Percu shrine, one of the most beautiful compositions of the Decorated period remaining in England, and (although the monumental effigy has disappeared) wonderfully perfect in all its details. It is generally assigned to Idonea, wife of Henry, 2nd Lord Percy (died 1865). With this date, however, the character of the monument agrees sufficiently well. The canopy is a lofty gable, terminating N. and S. in a magnificent finial of curly kail leafage. An ogee arch rises within this gable, and supports (on the S. side) a bracket, on which is a figure of the Saviour, holding a soul in his robe. The head of this figure is on a level with the point of the gable, below the finial. Springing from the sides of the main canopy grotesque figures supporting brackets, on which are angels with their hands raised in prayer towards our Lord. The gable and the inner arch are crocketed with the richest The inner arch is foliated, with angels at the points of the foliations, and in the spandrels figures in low relief of knights and ladies bearing shields, charged with the Percy arms and quarterings. The details on the N. side of the shrine are nearly the same as on the S. At the top is the Seviour in Majesty, and the angels at the sides seem to have borne the instruments of the Passion, which are mutilated. All these details should be most carefully noticed. The magnificence of the foliage (vine-leaves and clusters on the S. side, and hazel with its nuts on the N.) is extreme; and the sculptured figures, especially the angels, are unusually fine and The vaulting under the solemn. canopy has large bosses of foliage, and angels with musical instruments. the E. end two angels support a coro-Against the E. wall are two net. brackets for figures of saints, one of which has a pair of fighting dragons, very finely rendered; the other, much | designs. The bay over the altar, be-

mutilated, shows the soldiers casting lots for our Lord's coat. A mutilated bracket with the eagle of St. John (?) and a saint, remains W. The spandrels of the arch are filled on the inside with foliage, angels, and a Nativity (N.), and with angels and St. Catherine with her wheel (S.).

This superb monument was constructed at the same time as the nave (see post) of the ch. was building, and its sculpture should be compared with that of the nave-aisles. It may fairly be presumed that the great works at York Minster, where the nave and chapter-house had not long been completed, not only brought able workmen into this part of the kingdom, but assisted in forming a native school of sculptors, to whom we may attribute the Decorated work at Beverley.

The Altar-screen, full of niches and tabernacle work, originally Dec., was entirely restored (or rather rebuilt) by a Mr. Comins in 1826. A staircase turret at the head of the Percy shrine, and of the same date, leads to the broad top of this screen, which probably served as a music gallery, like that formerly in a similar position in York Minster (see Rte. 1). the wall of the staircase is a bracket with a king and bishop (Athelstane and St. John), and near it a musician with a bagpipe. At the back of the screen are three arches on clustered shafts, above which are richly-canopied niches, and a frieze of minstrels with their instruments. The whole screen resembles the Percy shrine in its details, and may possibly have been the gift of that great family. Its eastern side is terribly disfigured by 17th cent. monuments for the Wartons of Beverley Park.

The roof of the choir has been coloured partly from indications of former decoration, partly from Scott's tween the eastern transepts, is covered with scroll patterns, among which are medallions with figures of saints, and of the four Evangelists.

The narrow eastern transept was no doubt imitated from the plan of the choir which Abp. Roger (1154-1191) had constructed in York Minster (see Rte. 1). The Lady Chapel projects E. beyond these transepts, and the beauty of its E. E. work deserves special notice. A narrow and lofty lancet fills the centre of the wall N. and S., and has a lofty blank arch on either side. Below runs the same E. E. arcade which lines the lower walls of aisles and transepts. whole is enriched with dog-tooth moulding and with Purbeck shafts. The E. window is a Perp. insertion, and somewhat resembles (of course on a much smaller scale) the E. window of York Minster. Fragments of very fine stained glass, chiefly full-length figures, of various dates, from E. E. to Perp., which were scattered throughout the Minster, have been collected and arranged in this window, with some modern additions. Under the window is an atrocious Warton monument.

It is probable (judging from the position of other great shrines) that the shrine of St. John of Beverley stood in front of the Lady-chapel, leaving sufficient room before and behind it for the circulation of processions, and for the adoration of pilgrims. The shrine in which the relics were deposited after St. John's canonization in 1037 by Pope Benedict IX. seems to have been destroyed by the fire of 1187. Five years after this the Saint's remains were discovered, and deposited in another When this shrine in its feretory. turn was destroyed at the Reformation, the relics it contained were carefully interred. In 1664, whilst a grave was being dug, they were found in a case of lead, and were reinterred by order of Abp. Frewen. They |

were again brought to light, and again buried, in 1736. They now rest under "the 5th centre square slab of black marble from the tower westward." As in the case of St. William at York, the original tomb of St. John was reverenced as well as the shrine; and in 1448 Abp. Kempe granted an indulgence of 100 days to all who visited the tomb, which distilled a miraculous oil (see post, the nave). Offerings were also made before the banner of St. John, which Athelstane and Edward had taken to Scotland.

On the N. side of the Lady-chapel is the Percy Chantry, containing the tomb of Henry Percy, fourth Earl of Northumberland, killed in his house of Maiden Bower, near Topcliffe, in 1489 (see Topcliffe, Rte. 22). The effigy has disappeared from the altartomb. The window on the N. side is late Perp., with a hollow moulding, in which are laid angels, bearing shields with Percy arms and quarterings. The E. window is considerably earlier, and seems to prove that the chantry existed before it was appropriated for the Earl's tomb.

Near the N. E. transept is the Frith stol (seat of peace), the last and most sacred refuge for those who claimed the privilege of sanctuary here (see post). It is rude and plain, and (unless it has been reworked after injury from the Puritan soldiers) may perhaps be earlier than any part of the existing ch. It stood originally in the N. Porch. Whoever violated the "peace" of this seat, or attempted to seize a criminal who had placed himself in it, was guilty of a "botolos" (bootless) crime, and could free himself by no "bot" or money pay-So says Prior Richard of Hexham, in whose ch. a similar frithstool exists, slightly ornamented with Norman patterns.

[The circuit of the "sanctuary"

of Beverley was marked by four window in this transept is filled with boundary crosses, each of which was about 11 m. distant from the ch. Remains of three of these crosses are still standing. The "Frithmen." or criminals who fled here for sanctuary, were sometimes allowed to take service in the King's "host." lived in the town. Among the Harleian MSS, in the British Museum is the original registry of persons who sought refuge at Beverley, the greater part of them for murder.]

Against the N. wall of the aisle W. of the transept is a remarkable double E. E. Staircass, with foliated arches and slender shafts, having enriched capitals. It probably communicated with an exterior chapterhouse, which no longer exists, or was perhaps never built. There is a similar one at Besulieu, Hants.

In the eastern aisle of the great N. transept is the effigy (14th cent.) of a priest in eucharistic vestments, whose arms appear on the maniple, and on the apparel of the amice. This effigy was long held to be that of a Percy, but from the heraldic evidence more probably represents a Scrope (see Archeol. Æliana, 1860). treatment of the figure, and the arcading round the altar-tomb, are very graceful and good. Here is also a short effigy of a layman (merchant?) in a long dress, with collar and loose sleeves. In the S. transept, close to the entrance, hangs a painted tablet, representing Athelstane making his famous grant to the Church of Beverley. Underneath are the King's traditional words :---

> " Als fre make I the As hert may thynke Or egh may see.

Whatever may be the original date of this picture, it was repainted in the reign of James I., as may be seen by a comparison with the royal arms which hang near it. The great

stained glass by Hardman. transepts and great tower piers have been thoroughly cleaned and restored. and the Purbeck shafts repaired where needful. The vaulting has been tinted to harmonize with the Tadcaster stone, and is a little lighter. The bosses and adjoining portions of the ribs are touched with gold and colour.

The easternmost pier of the Nave. which consists of ten bays (including that under the western towers) is E. E., with the arch on each side of it. This has Purbeck, like the rest of the E. Eng. work. The rest of the nave is late Dec.; and it is evident that a considerable time must have elapsed between the completion of the E. E. work and the commencement of the Dec. ; since no example of early Dec. (geometrical) tracery occurs throughout the ch. The architect of the Dec. nave has closely followed the design of the E. E. portion. The piers, however, "though similar to the others in plan, show a variation of style both in their capitals and bases. Foliage (and grotesques) is introduced in the capitals of the altarnate columns of each pier; the support of the label of the arch is of a richer character, and the mouldings of the architraves are such as to give a greater breadth of effect in the way of lights and shadows."—J. L. P. At the intersection of the main arches are figures of angels bearing musical instruments (the E. E. portion has smaller figures). The triforial arcade only differs from the E. E. in the disuse of marble in the shafts; and its adoption shows that the later architect fully "appreciated its beauty and propriety." The clerestory arcade has three arches instead of five. The ball-flower is used instead of the dogtooth, and the window has three lights with Dec. tracery. The vaulting shafts spring from brackets, with small grotesque heads. The windows

beautiful flowing tracery, recalling the great W. window of York Minster (glazed in 1338), and perhaps modelled on that. The windows in the N. aisle (E. of the N. Porch) are probably later, and are somewhat different. Below the N. porch thev are Perp. Below the aisle windows runs a very rich arcade, as in York Minster. On the S. side the E. E. arcade is closely followed, and its trefoiled arch and toothed ornament are retained. On the N. side the arch is a foliated ogee, with rich crockets and spreading finials, and there is no change under the Perp. windows at the W. end. In the S. aisle, the foliage of the capitals is sometimes carried along the wall itself in a very unusual The grotesque figures at manner. the intersection of the arches on the N. side should be noticed. These beautiful arcades have been carefully restored.

The extreme western bay of the nave (under the W. towers) is Perp. The last two Dec. piers, however, are elongated, and show that the towers were already contemplated, although Perp. portions have been added N. and S. of them. The W. portal and the space below the great W. window are enriched with tabernacle work On the doors are above niches. modern and very bad carvings of the four Evangelists. The window above it is of nine lights, with three orders of tracery, and (like the window of the Lady-chapel) somewhat resembles the E. window of York Minster. is filled with modern stained glass by Hardman—the subjects being: in the upper lights, the four Evangelists, with early kings and arch-Then come the marriage bishops. of Edwin and Ethelburga of Kent, and the baptism of Edwin by Paulinus; below are figures of Paulinus. St. John of Beverley, and Coifi, the priest who desecrated the heathen temple at Godmanham (see the pre-

in the S. aisle are filled with very sent route, ante). Lower again are the Synod of Arles, in which Eborius, Abp. of York, was present, A.D. 314, and the consecration of John of Beverley as Bp. of Hexham. figures are those of Athelstane, and Abps. Thurstan and Neville. glass in the W. windows of the aisles. also by Hardman, represents S., St. Gregory in the slave market, "Non Angli sed Angeli," and N., the arrival of St. Augustine in Thanet. length of the nave is 171 ft., the height 76 ft., the narrow spacing of the piers, the peculiar treatment of the triforial space, by which great height is gained for the main arches and for the clerestory above, produce at once a strong impression of dignity and beauty, which is increased on examination of the graceful details. Round the central boss of the vaulting in the second bay, W. of the central tower, is an inscription which has "Beverlacēsis beati been restored. Johanis subtus in theca ponuntur ossa." It marks the position of the grave of St. John, but whether of the original grave is uncertain. It was in this place that the remains were found in 1644, when they were reinterred here.

> On the S. side of the nave is a very beautiful canopied tomb of late Dec. character, which tradition assigns to two maidens sisters, who gave two common pastures to the town. font is of Purbeck marble, and unusually large.

> On the exterior the fine composition of the N. and S. fronts of the great transept should be especially noticed, as well as that of the slender and buttress-like eastern transcot. The E. front retains its E. E. buttresses and turrets, but was apparently rebuilt from the ground when the Perp. window was inserted. In the buttress on either side of this is a niche, with figures of Athelstane and St John. The nave aisles are con

nected with the clerestory by flying | tration of the power and character of buttresses; and on the S. side the main buttresses, as at York, have The parapet, beautiful open niches. which is carried round the E. E. portion of the Minster as well as the Dec., is of the latter period.

The great features of the exterior, however, are the North Porch, and the West Front with its towers. Both of these are Perp. (The latter is said to have furnished Wren with his l design for the western towers of Westminster.) The North Porch, which is especially graceful, rises higher than the aisle, the upper part forming a parvise. "The door has a fine feathered, straight-sided canopy, over one of the ogee form, both crocketed. It is flanked with niches, buttresses, and pinnacles; the whole front is panelled, and crowned with a lofty central pinnacle, having a niche. The West Front, the general design of which was no doubt suggested by that of York, is as fine an example of a Perp. composition as that is of Dec.: and it is even questionable whether it is not superior in some points. The design, as at York, comprises a gabled centre, in which is the W. window, and a flanking tower on either side. The comparative dimensions are as follows: — Total width of W. front externally: York. 140 ft. 6 in.; Beverley, 89 ft. 9 in. Height of towers: York, 202 ft.; Beverley, 162 ft. 7 in. Width of towers: York, 32 ft. square; Beverlev. 19 ft. 11. in. N. to S., 23 ft. 9. in. E. to W. From the summit of these towers there is a magnificent view over the rich level district through which the Hull river flows; thickly wooded, and bounded westward by the line of the Wolds.

Remark also the buttresses and parapets of the nave aisles (especially the S. side), and the beautiful composition of each transept front. This

the period which produced it, the first half of the 13th cent.

*St. Mary's Church (opposite the "Beverley Arms") is a magnificent structure, almost rivalling the Minster in interest. It is cruciform, with a central tower, and is Dec. (chancel, arches, and aisles) and Perp. (nave and tower), although it retains some portions of earlier character. More than one "restorer" has been at work here; but the building was (1863) happily placed in the hands of G. G. Scott. The West Front, dating late in the reign of Edward III., is a very fine example of transition from Dec. to Perp. The window is true Perp., of seven lights, with a parapet above it. From the centre of the parapet rises a gabled niche, containing a figure of the Virgin. On each side is an octangular turret, with pierced pinnacles and parapets of openwork, rising high above the roof. These are rather late Dec. than Perp., as is the western doorway, which is much enriched. The central tower is massive Perp., with a panelled parapet, and numerous small pinnacles. The circular window-openings in the upper story are unusual, and their peculiar tracery should be noticed. Projecting buttresses give strong character to the tower. The vane on the S.W. pinnacle was the last design of Pugin, who was also the constructor of the flying buttress supporting the S. transept, the wall of which had shown signs of insecurity. The S. doorway, with its porch, displays a curious mixture. The inner arch is semicircular, and has Norm. ornaments. The outer is E. E. Over this is a very fine Perp. porch, with windows, above the door is a Dec. and canopy. The transepts and E. end of the chancel are Perp., and the large clerestory windows in the transepts add greatly to the fine general effect. On the N. side of the chancel Rerly English work is a grand illus- remark the beautiful Flamboyant winrooms above the chantry.

Within the ch., the earliest work is in the chancel and transepts. chancel, of five bays, has early Dec. arches, with a circle enclosing a trefoiled ornament in the spandrels. At the 4th bay on the N. side is a very beautiful niche with canopy. The clerestory and E. window are Perp. The latter is filled with admirable stained glass by Clayton and Bell, the subjects being from the life of The ceiling, of wood, our Lord. panelled, and nearly flat, bears the date 1445, and is painted with figures of English kings, each of which has a label with an inscription. These figures have been carefully restored by William Padget, of Beverley. Portions of an original screen and some Perp. stalls remain in the The S. aisle is Dec., with chancel. a flat ceiling, painted blue, with gold The N. aisle is also Dec., but very much richer. The three eastern bays are divided from the others by an arch, and the vault, eastward, which has exquisite bosses of foliage, differs from that below, although both parts of the aisle are apparently of the same date. A small chantry (traditionally called the Flemish Chapel), with Flamboyant windows, is entered by a low arch from this aisle. (At the entrance remark the figure of a rabbit), with pilgrim staff and scrip.) This chapel, and the N. aisle adjoining, are of the same date and character, and both may have been constructed by Flemish workmen. At the N.E. angle of the chancel (between that and the aisle) a door opens to a staircase leading to two priest's rooms above the N. aisle and the Flemish Chapel. The careful and masterly way in which this staircase is finished (especially the groining at the top) deserves especial notice.

dows of the aisle, and those of a priests | Perp. period, and much of the old material was again worked up. will account for the dog-tooth and zigzag moulding in the arches, which rest on Perp. piers. The S. window has Dec. tracery, with Perp. jambs and hood-moulds. The glass is by The N. is Perp. Hardman. Perp. wooden ceiling of the N. transept, much enriched with bosses and inscriptions, has been restored by Mr. Brodrick, who added the gilt angels with outspread wings as corbels. is a better ceiling than that of the S. transept, which has also been coloured. The S. trans, contains the organ, with a case elaborately decorated. It is by Messrs. Forster and Andrews, of Hull, and contains 2086 pipes. The piers of the tower are Perp.

> In the year 1512 a portion of the ch. fell, most probably the central tower. The fall is recorded by an inscription on one of the pews in the nave, which runs partly,-" Pray God have marce of al the sawllys of the men and wymen and cheldryn whos bodys was slayn at the faulying of thys ccherc "(kirk).... "thys fawl was the 29 day of Aperel 1512." It is remarkable that no other record of this event exists; and it is only from the architectural evidence (and from a local tradition) that the "fawl" is supposed to have been that of the central tower. This of course makes the existing tower later than 1512, and accounts for the patched work already noticed in the transepts.

The nave has been most carefully restored, and the alderman's pew and galleries which disfigured it have happily vanished. It is of six bays, and almost entirely Perp., repeating the general design of the chancel, though not so gracefully. The clerestory is large and lofty, and the roof panelled and nearly flat. The most interesting fact connected with this The transepts were rebuilt in the ch. is that it was built by a subscription. certain families, and individuals | possibly indicates the employment of or guilds contributing, some an arch. some a pier. The date, 1428, occurs on the S. side of the last pier. the N. side, at the terminations of the hood-moulds of the arches, are angels with shields, bearing inscriptions recording the donors. "Thys to (these two) pyllors made god wyffes (good wives), God reward theym." "Thys pyllor made the meynstryls" (round the capitals of this pier are remarkable figures of minstrels—a harper, violinplayer, drummer, lutanist, and piper. "Xlay (Croslay, a merchant of Beverley) and his wyffe made these to pyllors and a halffe."

Below the N.W. tower pier is a modern marble pulpit, designed by Scott. It is of Derbyshire alabaster, with a basement of Mansfield stone and Italian marble, and is a fine work. The W. window of the nave, and two windows in the S. aisle, are filled with glass by Hardman, the former containing figures of our Lord, the Blessed Virgin, and Twelve Apostles. The nave roof is coloured dark blue, with ribs of oak and red, somewhat too dark even for its considerable height. On the nave floor is a stone with incised cross, and an inscription for Robert Burton, 1532—a good example. The inner arches of the W. door (late Dec.) should be noticed, as well as the sculptured lion and dragon above it. Remark also the Norman work on the interior of the S. door-the arch of a lofty doorway. The font has an English inscription, and the date 1530, although it is Dec. in design. It was made by "Wyllm Seyffare, draper, and his wyvis . . of his paper costes."

The rich and remarkable sculpture throughout this ch. calls for especial notice, and should be compared with The difference that in the Minster. is sufficiently marked, especially between the Dec. work of the chancel

a different school of workmen.

On the exterior S. wall of the choir sisie, between the two westernmost windows, is an oval tablet with two swords crossed above; and below the lines—

"Here two young Danish Souldiers lye, The one in quarrell chanc'd to die; The other's Head by their own law, With Sword was sever'd at one Blow." Dec. 23, 1689.

Some Danish troops had been landed at Hull for the service of Wm. III., and marched to Beverley. The par. register records the burial of the soldiers—one beheaded for killing the This is probably the last instance of execution by sword in England; and the record of its occurrence here shows that the Danish troops were exempt from English law, either civil or military.

Of the ancient gateways, North Bar alone remains, and is perhaps temp. Edward III. It is of brick, with 3 small arched recesses, apparently for seats, on either side of the main passage. The portcullis groove exists. N.E. of the Minster are some remains of the Dominican friary (founded here circ. 1321). They are of small interest, and the gateways of moulded brick are of a period after the Dissolution. In the court is an effigy of a lady, temp. Edw. L

The visitor who may chance to pass out of Beverley by the North turning l. will reach the Union Workhouse, an imposing Tudor " mansion;" and beyond is a common pasture of 504 acres called Westwood, and given to the town by Abp. Neville in 1380. A portion of it, called Burton Bushes, is very pleasant; and there are fine views of Beverley and the Minster.

Barracks for the regimental depôt and that in the Minster nave, and of the (so-called) East Riding terriHull.

√ 2½ m. N. of Beverley is the site of Leconfield Castle, a residence of the Percys. Leland describes it as a large house, "and standith withyn a great mote yn one very spacious courte; three partes of the house, saving the meane gate that is made of brike, is al of tymbre. The fore part is fair made of stone and some brike." Of all this the most alone remains. Although the Abps. of York were the feudal lords of Beverley, the Percys were its real protectors; and numerous presents from the governors of the town-herons, "dentrices" (pike?), bream, and wine: swans and pheasants to "my lady the Countess," and oblations to Master William Percy "to celebrate his prime misse"—passed under the great gateway of Leconfield. Occasionally the twelve governors were entertained at the Castle in great state. The Castle gives a title to Col. Wyndham, Lord Leconfield, of Petworth in Sussex, one of the representatives of the Percys. The village of Leconfield is very picturesque.]

A drive from Beverley by the old high road to Malton as far as the Fimber station on the rly. between Malton and Driffield (distance, 16 m. -but there may be some excursions), will show something of the Wolds, and will allow visits to some interesting churches, especially the new ch. of Dalton Holme, and those of Baynton and Kirkburne.

The road passes (2 m) the village of Cherry Burton (see ants); and leaving Etton (where the ch., restored in 1869, has Norm. portions) to the l., reaches (4 m. from Beverley) a cross road, which in about 1 m. gains the village of Dalton Holme (formerly S. Dalton).

torial Regiment have been built 1 m. and Holme on the Wolds, with a E. of the town, on the road to joint population of 427, have been united; and a noble Church (begun 1859, completed 1861) has been erectedi (archit. J. L. Pearson, R.A.) at a cost of at least 26,000%, entirely defrayed by the late Lord Hotham. It consists of nave, transents with eastern chapels, chancel, W. tower and spire. The exterior stone is Steetley; the interior, a very white stone from Hildenley, near Malton. This is laid in black mortar. The general character is E. Dec., but rather French than English. The beautiful tower and spire, together 200 ft. high, are very striking, and perhaps the best portion of the ch. Inside, the effect is entirely pro-duced by proportion and by richness of carving and detail. There is no colour, and even the use of different marbles has been avoided. All the details, however, deserve attention for their finish and excellence. The stained glass is by Clayton and Bell. The chapel E. of the S. transept is that of the Hothams, and contains some monuments removed from the old ch., the principal being that of Sir John Hotham, d. 1689, sculptured in Italy. The four cardinal virtues support a black marble slab, on which is an effigy. The founder of the present ch. is buried in the vault beneath. There is a wonderful view from the top of the tower. One of the bells (removed from the old ch.) dates from the 14th cent. Among the plate is a very fine alms-dish of Nuremberg work of the first half of the 16th cent.

About 1 m. W. of the ch. is Dalton Hall (Lord Hotham), a Georgian house, which was greatly enlarged and improved (1874). Among the pictures here are-Mrs. Siddons as Isabella in the 'Fatal Marriage,' by Sir William Hamilton; George III. by Sir J. Reynolds, given by the king The adjoining parishes of S. Dalton to Sir Charles Hotham; George I., by

Kneller; and (artist unknown) Sirl John Hotham and his son, executed by the Parliament for their design (1642) of abandoning Hull to King Charles. The gardens are large, and good, and the park is extensive, with some good timber. The "lawn" opposite the S. front of the house is about a 1 of a mile in length, and is surrounded, in the formal fashion of last cent., with magnificent beech-trees. About 2 m. W. of South Dalton, at the extremity of the township, is the Kiplingcotes racecourse (said to be the earliest in England), on which stakes have been run for (raised from a sum of 360L subscribed by the then Lord Burlington and others) since 1618. These races take place on the third Thursday in March, and a game of ball on horseback, precisely resem-bling the modern "polo," is always played on the same day.

From Dalton Holme the road is regained at the village of Holme-on-the-Wolds, where the chancel of the old ch. remains, and is used as the chapel of the cemetery. It is a picturesque fragment. At Lund (1 m.) is a mixed ch. (arcade E. E., font Norm., tower Perp.) of no very great interest. There are 2 early female effigies. (Between Lund and Bainton, 11 m. rt. of the road, is Middleton, where is a small early Dec. ch. The village lies on a bed of glacial drift, in which bones of extinct mammals have been found.) The ch. of Bainton (2 m.) is more important. This is late Dec. and the interior is fine, with a lofty arcade (no clerestory), and a broad The font is Norm. The ch. was restored, and some of the walls rebuilt, in 1869. In the chancel is the fine brass of Roger Godeale 1452 (?) rector, with chalice. Here is also (in the N. aisle) a remarkable effigy, temp. Hen. III. of a knight, cross-legged, in chain-mail and the long cyclas or overcoat. He is bareheaded. A toad creeps up the sword ornament, with a billet moulding Yorkshire.

which hangs from his belt, and a lizard stretches by his side, biting the point of his shield. The hands raised in prayer, hold a heart between them. The feet rest on a lion. effigy is said to be that of Peter De Maulay, and the arms of the De Maulays (3 eagles on a bend) are on 3 shields on the wall above the monument. The effigy lies under an enriched arch, of much later date. (In this parish, rt. of the road, is Neswick Hall, J. Grimston, Esq. The house contains some Turner drawings.)

A cross road rt., 1 m. beyond Bainton, leads to the village of Kirkburne (1 m.), where is one of the most interesting churches in Ch. and village stand Yorkshire. picturesquely on the edge of a hollow, through which runs a stream, called the Holburne (hol=hollow; Battleburne, Eastburne and Southburne are other streams which unite near Kirkburne, and flow onward to Great Driffield). There are fine ashtrees round; and near the ch.-vd. a very large elm with knotted roots, called the "village tree." The ch. is late Norman, much enriched, and retains its original plan (nave, W. tower, and square-ended chancel). although it has been throughout restored (1856, Pearson, archit.). On the exterior the nave has broad. flat buttresses; round-headed windowopenings, high in the wall, and much enriched with zigzag; and a corbel table above, with grotesque heads The chancel has been rebuilt; but is a reproduction of the original design, and the Norman sculptures have been retained. The portal on the S. side of the nave has a very rich beak moulding, and beyond it the signs of the Zodiac. On the N. side the door has plain mouldings. The upper part of the tower is Perp. Within, the chancel arch is very rich Norm., having three orders of chevron

beyond. Above the arch are 3 round- | the Wolds, 1.—affording a good notion headed openings; and a rich modern chancel screen of wood crosses it. The abacus of the shaft-caps is continued as a stringcourse along the The tower arch is E. wall. The staircase in the tower is very unusual. It ascends steep and open, first along the face of the S. wall. then turns, and crosses the W. wall in front of a Norm. window (to which there is an ascent of three steps from the staircase), and at the N.W. angle it is continued upward in a spiral form to the belfry. The font is very fine Norm.—a circular basin, with two series of sculptures divided by a twisted band of ornament. sculptures apparently represent, above, the Baptism of Our Lord; the Charge to Peter; and the Ascension (in the latter the aureole (or rainbow?) is held by angels,—a mode of representation occurring in many other places—among the rest, at Newbald in Yorkshire; see Rte. 3). lower range (mostly animals) has thought, without any certainty, to refer to the story of 'Revnard the Fox,' but these sculptures are probably little more than ornamental.

The modern reredos was designed by G. E. Street (Redfern, sculpt.); and represents the Crucifixion. with the Virgin of St. John in the centre, and in small panels, the Annunciation, the Nativity, the Burial and the Resurrection of our The material is very pure alabaster. In the ch.-yd. is a cross on 3 steps, also designed by Street, and very striking. On one side is the Crucifixion, on the other the Annunciation. (Cross and reredos were given by the lord of the manor, Sir Tatton Sykes, who also greatly aided the general (and most necessary) restoration.)

We regain the high road at (1 m.)

of the country-will bring the tourist to Huggate (high gate? the high road?), a large village in a hollow of the Wolds, with a restored (1864) ch. Trans. Norm. arcade and chancel arch, late Dec. tower and spire, the latter hexagonal, with a rounded attached rib, ending halfway down in a small projecting head). ch. was given to St. Mary's Abbey, York, by Philip Paganel. The adjoining wolds are much marked by entrenchments and tumuli.

4 m. beyond Tibthorpe, the road Wetwang, where passes through the ch., chiefly Perp., has Norm. 2 additional m. brings portions. us to Fimber, where is the ch. mentioned above. Here is a station on the Malton and Driffield Rlv. For the road from Fimber to Malton, see ante.

Leaving Beverley, the train in 10 min. reaches

Cottingham Station. A short distance W. of the village are some traces of the moats (outer and inner) of Cottingham Castle, successively the seat of the Stutevilles, and the Wakes. It was built by Robert Stuteville, sheriff of Yorkshire, in 1170, and passed to the Wakes by There is a tradition (quite marriage. unfounded) that the castle was burnt by the Lord Wake of Henry VIII.'s day, who had received intimation that the king, then at Hull, intended to honour him with a visit. Wake, it is said, was very beautiful. and her husband preferred the loss of his house to the risk of the king's admiration. There is probably as much truth in this story as in the assertion that Johanna de Stuteville (1242) was the "inventress" of riding sideways on horseback,—because she is so represented on her seal. Tibliorpe - (a 5-mile drive across Church of Cottingham is Dec., but of more than one period It is chiefly Nicholas de Luda (of Louth in Lincolnshire), rector, and builder of the chancel in 1374. The brass is large, with canopy and super-canopy, the figure in cope. The inscription records that Nicholas founded prebendal stalls at Beverley and at Salisbury. Church and brass have been restored. An Augustinian Priory was founded here by Lord Wake, in 1322: but was removed a vear or two later to Newton or "Haltemprice," about 1 m. S. There are no remains. The intermitting springs, at Keldgate, 1 m. from the village, are sometimes dry for four or five years, and then break out suddenly.

In 1 hr. the train reaches

Hull (see Rte. 8).

ROUTE 9.

HULL TO BRIDLINGTON, BY BEVERLEY AND DRIFFIELD.

(N. E. Rallway. 5 trains daily from Hull. Time to Bridlington 1 hr. 20 m. The trains run on from Bridlington to Scarborough — Rte. 13.)

For the line from Hull to Bevernoticeable for the very fine brass of ley, see the preceding route. Leaving Beverley, at about 3 m., Leconfield (Rte. 8, Exc. from Beverley) is passed l. The village lies about 1 m. from

> Arram Stat., where is a scattered hamlet. The next station is

> Lockington. The village lies 12 m. l. The ch. has Norm. and E. E. portions. (About the same distance from the station, but S. of it, and on the high road from Beverley to Driffield is Scarborough, where the ch. was rebuilt in 1859, at the cost of James Hall, Esq., of Scarborough Hall. The architect, Pearson, also built the ch. of Dalton Holme (Rte. 8), in which he was not allowed to introduce colour. Here colour in marble and in wall painting has been largely used, and with very good result. There is a spire.)

> L. of the line, and on the high road, is Beswick, where (in the Manor House, a fine Jacobsean building of red brick) lived and died the "blameless Bethel" of Pope, his friend and correspondent:-

"Thus Bethel spoke, who always speak his thought, And always thinks the very thing he ought. His equal mind I copy what I can, And, as I love, would imitate the man." Imit. of Horace.

The small ch. was built in 1871. Beswick is in the par. of Kilnwick on the Wolds, where the ch. (1 m. rt.) has a good Norm. portal, with beakhead moulding. It was restored in 1871

A short distance beyond Beswick the rly. crosses a tributary of the Hull river, on the bank of which is Watton Priory, founded for Gilbertines in the reign of Stephen. The building now called the "Abbey" (occupied by a farmer) is a dwelling-house of brick with stone dressings, built from the ruins of the Priory, in the Tudor probably a part of the treasures of style, and containing some old tapestry. It belongs to the Bethels. Some portions of the conventual buildings now serve as stables. The tower is The font, circ, and covered with figures, resembles that at Kirk-There is a station at Hutton Cranswick, where the ch. has Norm. portions. The Perp. ch. is of brick, with stone quoins. (The ch. of Skerne, passed rt., between Hutton and Driffield, contains the remains of some early efficies, and has been restored. There is a Norm. portal and arch.) We soon reach

Driffield Junction, where the rly. from Malton (see Rte. 11) joins the line we are following.

Driffield (Deor or "Deira," feld; the "field," or open space in the midst of the great woods of Deira) is a town of about 5000 Inhab. (Inn: Red Lion) at the foot of the Wolds. having a considerable corn-market. and a communication with the Hull river (and so with the Humber) by means of a small canal, along which much corn and farm produce is con-Driffield, like other towns and villages under the Wolds, has probably claims to a great antiquity. (See for a general notice of the Wolds Rte. 11.) Many tumuli and sepulchral mounds, of various dates, exist in the neighbourhood, one of which (a high tumulus, covering an irregular vault formed of untooled slabs), in a field near Allamanwath Bridge, was opened in 1851, and proved to be British. Bronze, bone, and stone implements were found, but no iron. Early Saxon grave-mounds have also been opened here, and have disclosed amber beads and rock-crystal pebbles, "perforated with a degree of accuracy which implies not only the skilful use of the lathe, but also the possession of emery—a substance not likely to be had except from the island of Naxos. Such beads were

the East, brought to the North of Europe by mercenary soldiers or roving pirates."—Phillips. Some large barrows on the road N. of Driffield are known as "Danes' graves," and perhaps date from the time when the Northmen were ravaging Holderness.

In spite of its antiquity, however, Driffield has little to interest the visitor, unless he be an angler, in which case he may find some good sport in the small trout-streams which rise near, and form the head-

waters of the Hull river.

"The Church is very ancient. In it is a basso-relievo of Paulinus." (Stukeley to Gale, 1740.) This must be the sculptured figure of an ecclesiastic, with a crosier in hand, inserted in wall at W. end of S. aisle The arcade is Norm.: (outside). the N. and S. portals E. E., and the tower fine Perp. At Little Driffield the existing ch. (partly rebuilt 1808, partly Perp.) contains fragments of floriated crosses, &c., in its wallsrelics of an earlier building. Here is the supposed tomb of Alfred King of Northumbria (died circa 727). tradition that he died and was buried here is as old as the time of Leland, who says that a Latin inscription was to be seen on the tomb. This, and the tomb itself, have disappeared, and a modern inscription (in English) now records the interment "within this ch." (See Ebberston, Rte. 12.) (The interesting Norm. ch. of Kirkburne (see Rte. 8) lies about 3 m. S.W. of Driffield, and may easily be visited thence.)

From Driffield the rly. turns N.E., skirting the edge of the Wolds, which

are seen l. At

Nafferton (station) the ch. has been restored, and contains some modern stained glass. More interesting than the parish ch. is one which has been built at the cost of Sir Tatton Sykes in the hamlet of

The architect was G. E. Street. This | Cherry Burton (see Rte. 8). church is remarkable for its stained glass, painted roofs, and very beautiful marble rood-screen and pulpit. The turret at the W. end is carried on arches from the floor. There are also a ch.-yd., cross, lych-gate, and a new parsonage.

Lowthorpe Stat. Here is an old collegiate Church, with the chancel in ruins. It was made collegiate by Sir John de Herbarton in 1333, and the chief part of the building is about that date, but there has been much alteration. It contains the monument, with effigy, of a knight of the Herbarton family (14th cent.). Lowthorpe Lodge is a residence of W. H. St. Quintin, Esq.

11 m. N. of Lowthorpe Stat. is Harpham Church, in which are several fine monuments of the St. Besides altar-tombs, with effigies, there are two excellent brasses-Sir Thomas de St. Quintin (lord of the manor) and wife, 1418. The knight treads on a lion. armour well shows the advance of plate in the early years of the 15th cent. Round the baseinet is a rich "orle" or wreath of feathers and jewels, "intended to lighten the pressure of the tilting helmet." The second brass is for Haines. Thomas de St. Quintin, 1445, and the figure is in complete plate-armour. These fine brasses were probably the work of provincial engravers, who seem to have been first employed (in England) in Yorkshire and Lincolnshire, especially during the 15th See Haines's 'Manual of Monumental Brasses,' i. p. 28. Over the altar is a bas-relief, by Wilton, to the memory of Charlotte, wife of Sir William St. Quintin, 1762. In the village is St. John's Well, a memorial, no doubt, of St. John of

Wansford (11 m. S. of the station). 1 born here, as has been said, but at

The next Station is at

Burton Agnes, where the Church and *Hall are well worth a visit. The Hall (Sir Henry Boynton, Bart.) is a very fine example of James I.'s reign. It is of brick, with stone coigns, and is approached through a very picturesque gatehouse. In the entrance-hall is an elaborately-carved chimneypiece of marble, with figures of the wise and foolish Virgins, and a magnificent screen, rising to the roof, and covered with a mass of minute carving, which was brought here from Barmston, another seat of the family. A very quaint staircase leads to the long gallery, the most remarkable room in the house, having a carved roof, decorated to imitate a trellis-work bower, intertwined with roses and creepers. Among other pictures here (of no very great importance) are some landscapes on panel, said to be by Rubens. hall was added to, and somewhat altered, by Inigo Jones in 1628. It is surrounded by rich wood, very pleasant to the eye after the bare sweeps of the wolds, and is a most picturesque object from whatever side it is viewed, especially from the flowergarden.

The Vicarage of Burton Agnes was long held by Archdeacon Wilberforce, who was the first in this part of Yorkshire to "restore" his Church. The example thus set has been largely followed - not without evil results as well as good-since, in too many instances, "restoration" has really meant destruction. side of the nave shows a fine Trans. Norm. arcade, with low, massive piers and pointed arches. arcade is more decided E. E. arcade on the N. side is much defaced by a partition, which fences off Beverley, who, however, was not the seignorial pew and a chapel

beyond it, in which are some monuments and effigies of the Griffiths lords of Burton Agnes). (former These are Elizabethan, one of them (the monument of Sir Henry Griffith and his wives) being especially won-It is an altar-tomb (the side panels of which are formed of piled-up bones) supporting three There is a fine coffins of stone. Perp. arch opening to the tower. The chancel was entirely restored by Archdescon Wilberforce, and the piers and capitals have been much The moulding above reworked. the credence-table terminates in a small figure with hands raised The head is that of in prayer. William Wilberforce, father of the The font is Trans. Archdeacon. Norm., and was restored to its present place by Archdeacon Wilberforce, who found it doing duty as a flower-vase in the Vicarage Garden. On the exterior of the Perp. tower (in the 3rd story) are niches for figures.

(3 m. N.W. of Burton Agnes is Kilham. The ch. is Perp. and fine, with a rich Norman portal.)

Passing Carnaby Stat. (the village is ½ m. l.; the ch. contains a font worth notice) the noble ch. of Bridlington soon comes into view, and we reach

Bridlington Stat. (For Bridlington, see Rte. 13.)

ROUTE 10.

BEVERLEY TO BRIDLINGTON .- BOAD.

The turnpike road from Beverley to Bridlington (24 m.) crosses the country at some distance E. of the rly. (Rte. 9.) The Hull river is crossed soon after leaving Beverley. It flows through marshy ground "among gravelly hills, which resemble the 'äsars' of Scania, the 'escars' of Mayo, and, in a less degree, the 'moraine' of glacial countries, such as the hills of Kelk and Brandsburton."—Phillips. (See Rte. 7.)

In the ch. of *Routh* (3 m.) is the shattered effigy of a knight, temp. Henry III.; and the good brases of Sir John Routh and his wife Agnes, circ, 1410. Both wear collars of SS.

7 m.; l. of the road, is Leven ch., originally E.E. (the E E. font remains). The ch. was rebuilt 1843–45, and on a different site. Here is preserved the fragment of a fine cross, of late Dec. character (circ. 1860?), found some years since in the ch.-yd. On one side is the Crucifixion, with St. John and the Virgin; on the other the Virgin and Child, St. Catherine, and another saint. At

8 m. the road passes through the village of Brandsburton. The St. Quintins possessed the manor from a very early period until the end of the 14th cent.; and in the ch. (but hidden under seats) are the large and fine brasses of Sir John St. Quintin (1397) and his wife Lora (1379). Sir John, by his will (dated 1397), left 20 marks for a stone, with "images of laton," of himself and 2 wives,—only one of whom now appears. The figures, which are life-size, were probably the work of a local (Yorkshire) artist. The knight's effigy is a good example of armour. He holds a heart between his hands. In the ch. is also a small brass for William Darell, rector of Halsham, 1364. The building itself is of various dates, and not very important. In the village are the remains of a large cross.

A short distance N.W. of the village, is the Barf (local for a small hill) "one of those irregular mounds of gravel and sand which denote the effect of ancient sea currents; for all Holderness was a sea-bed in the glacial period."-Phillips. It is nearly 2 m. long, and varies in height from 20 to 60 yards. Remains of the mammoth, many shells, and tusks of elephants, have been found in it. Some skeletons, which have been disinterred here by the gravel-diggers, show that the hill was used as a place of sepulture at a far later period.

At Numbeeling, 1 m. off the road, rt., was a Priory for Benedictine nuns, founded by Agnes, wife of Herbert de St. Quintin, about 1150. It was small, and its annual value at the Dissolution was only 351. No portion of the building remains, and the present ch dates from 1810. In the chancel are mutilated effigies (14th cent.) of Sir Andrew Fauconberg and his wife, preserved from the old church.

The ch. of Beeford (131 m.) is Perp., but has been much altered at various times. The tower is good, with a graceful open parapet. The figure of the patron saint, St Leonard, remains in a niche over the W. door, and it may be remarked that such figures have been little disturbed throughout this part of Yorkshire. In most churches they will be found still existing. In the chancel is a good brass of Thomas Tonge, rector, 1472. He wears a richly ornamented cope, and holds a book. Crow Garth, in this par., formerly belonged to Meaux Abbey, and was deprived of its ancient trees by a "nativus" resident here. He complained of the noise of the crows; and begged leave of the abbot to get rid of them "by an act." The "act" was to cut down all the trees.

At Lissett (16 m.) is a small chapel, dedicated to St. James, containing some portions of early Norm. work. The S. door, the chancel arch (low and semicirc.), and the font, a plain, rude bowl, are of this character.

Barmston Ch. (18 m.), dedicated to St. James, contains an altar-tomb with fine effigies, said to be that of Sir Martin de la See, who died in 1497. The armour, however (circ. 1415?), is considerably earlier. It is entirely of plate: with a jewelled bawdric, and a fillet encircling the bascinet, on which are the words "Jesu Nazare."

Beyond Barmston, hanging over the sea, is seen the last house of Auburn, a village of which the rest has been washed away by the sea. Hartburn, somewhat S. of it, has disappeared entirely. (For a notice of this coast, and of the manner in which it is gradually devoured by the sea, see Rte. 6.)

The road from Barmston follows.

attention till at

23 m. we reach Bridlington. (See Rte. 13.)

ROUTE 11.

MALTON . TO DRIFFIELD.

(Branch of N. E. Railway. trains. Time 1 hr.)

THE WOLDS.

The tourist in search of the picturesque will find little to care for on this line of rly., unless from one of the intermediate stations he penetrates into the Wolds, through the heart of which the line passes. These wolds—(the word is identical, or nearly so, with "weald," as in the "weald" of Kent, and signifies, in its first sense, a wooded or forest country, but like the word "forest" itself it came to be used for any open. little cultivated district) - form a great crescent of chalk hills, curving round from Flamborough Head to the Humber at Ferriby, cut through by a wide valley, which ranges from Settrington to Bridlington. The hills rise from Flamborough to Wilton Beacon (805 ft.), and thence gradually decline to Hunsley Beacon (531 ft.) and the Humber. Inter-

the coast-line, with little to attract | mitting springs, named Gypseys (see Rte. 13), burst along the valley; and all round the wolds, at the base of the hills, where water-springs occur, is a line of ancient villages, no doubt on the sites of British stttlements. The peculiar character of the chalk, with its deep, dry, steep-sided hollows, is more remarkably developed among the Yorkshire wolds than even on the Southdowns of Sussex; and no one who merely passes through the wolds by the rly. which follows their central valley will obtain the least notion of the singular bits of scenery lying among the hills rt. and l. of him. A sudden depression in the chalk frequently opens a green, precipitous hollow, so deep and so steep as to check even the boldest riders of the wold hunt. In these depths there are few or no sounds, except, it may be, the cawing of rooks and jackdaws which abound all over the wolds; and nothing is to be seen but the enclosing green hills, marked along their sides by the narrowest sheep-tracks, and the cloud-flecked sky, which seems to rest upon them. The broader valleys and depressions (such as Thixendale, Rte. 8) are hardly less striking. The wolds themselves are covered with tumuli, and with very extensive entrenchments, forming places of refuge for men and cattle during the These, which forays of an enemy. cut off large promontories of hill, or front long valleys, are no doubt of British origin, and are most noteworthy along the Northern frontier of the wolds (see Rtes. 12 and 13), and along their western brow, between Malton and Cave. "A good general idea of this class of works may be had by consulting the plan of a part of the wolds" (or the Ordnance map) "above Acklam and Birdsall, where dykes are numerous and of great extent, and are seen in connection with tumuli of unequivocal British character."—Phillips. "Everywhere these hills present

a smooth bold front to the N. and | and intelligence which, together with W.: and from a point like Leavening Brow, which commands views in both directions, the prospect is singular and delightful. An immense vale sweeping round, with the great tower of York Minster for its centre: in the S., the gleaming water of the Humber; on the W., the far off mountains; to the N., purple moorlands; while immediately surrounding us are the green wold hills, crowned with the tumuli and camps of semi-barbarous people, who chased the deer and wild boar through Galtres Forest, watered their flocks at Acklam springs, chipped the flint, or carved the bone, or moulded the rude pottery in their smoky huts, and listened to warriors and priests at the mound of Aldrow, and the temple of Goodmanham."—Phillips. (Leavening Brow is on the W. border of the wolds, about 6 m. from Kirkham Stat., Rtc. 12—see also Rtc. 8, Aldrow is on the hill above Birdsall. see post. For Goodmanham, see Rte. 8.)

Views of this class, however, are not to be found among the wolds themselves,—a mass of low swelling hills, with villages here and there in the hollows. Fifty years ago they formed one unenclosed sheepwalk, of about thirty miles square, over which you might gallop in all directions without being troubled by a fence. The whole district is now enclosed, with such an increase of value, that a farm which was then worth 100% a year, is now worth 1000l. Trees would grow here, but they are not "profitable" enough,-and larches, which are planted in some places, are cut down like a "crop," when at all of useful size. Sledmere and its neighbourhood are the only treesheltered portions of the wolds, although a few trees are generally gathered about a village, or a single These farmhouses are farmhouse. good and substantial, and the wold farmers are distinguished by the skill | the old customs which united them in

ample capital, they bring to bear on their land. Their horses are their pride: and 70l. or 80l. is an ordinary price for a good draught horse (there are no "cart-horses" on the wolds). The waggons are furnished with a pole, and four horses are driven from the saddle, a farm servant acting as The roads, which cross postillion. the district in every direction, are excellent; since care for his horses has led the wold farmer to pay especial attention to them. In each parish, by the side of the principal road, is the public chalk pit, from which "top dressing" is procured, and the botanist will find these places worth examination, since many plants, elsewhere extinct in the country, still linger about them.

There was some cultivation in parts of the wolds at a very early period. Each farmer owned a certain number of "oxgangs" (a word still to be heard now and then from the mouths of old labourers), and lines of ancient balks and plough lands, some straight, some curiously curved, still exist in places. The common pasture meadow was divided into portions, each of which changed hands annually, and each had cut on the turf a distinguishing mark—as an arrow, a triangle, or a circle. At the harvest feast a number of apples, each marked in a corresponding fashion to one of the "dæls" or divisions, were thrown into a tub of water. Each farmer then dived for an apple; and the mark which it carried indicated the "del" which was to be his for the coming year. The Dolemoors in Somersetshire were managed in a similar way, save that the change was for a longer period. It is no doubt a very ancient Teutonic land custom. Sheep, however, must always have been, until the enclosure, the great speciality of the wolds. Shepherds are still employed, but they have lost much of their ancient character, and

away. Before a lad was allowed to join the "order." he was bound to say by heart the shepherd's psalm, as it was called, "The Lord is my Shepherd." The great festival of their vear was "Shepherd Sunday" (2nd after Easter), when the gospel contains our Lord's words, 'I am the Good Shepherd." On this day few shepherds were absent from ch., howvever rarely they might appear at other times.

Roman roads from York ran across the wolds in the direction of Filev and Bridlington. Small square camps occur at intervals, on or near themintended for temporary shelter, and for keeping in awe the British population. (The Ordnance maps, and Mr. Newton's Map of British and Roman Yorkshire, will be found the best assistants in examining the very perplexed lines of ancient works in this district.)

Leaving Malton, the line soon enters the wolds, and the first Stat. is at

Settrington, where the ch. is chiefly Perp. From Settrington Beacon, 1. of the rly., there is a very fine view of the kind described from Leavening, but extending over the Vale of Pickering. At the next Stat.,

North Grimston, the ch. has Norm. and E. E. portions, and the font (of later date) is worth notice.

[Langton Hall (Mrs. Norcliffe) is 2. m. E. Village, church and mansion all stand within a well-defined Roman camp, which extends 1 m. E. to W. on rising ground.

3 m. S. is Birdeall (Lord Middleton), approached by a fine avenue. The Church, which stands within the park, was built in 1825. Some arches and a part of the tower of the

a sort of guild are rapidly passing | has hunted the wold country since the death of the late Sir Tatton Sykes, and the hounds are kept here. On the hill above the house is the mound of Aldrow, one of those remarkable "raths," or green tumuli, of which the finest example is at Barwick in Elmete (Rte. 42, and see Introd.)]

> There is nothing which calls for notice at the stations-Whar-ram-le-Street (the name marks its position on a Roman vicinal way) and Burdale. At the next Stat ...

> Fimber, the ch. may be visited (described in Rte. 8), and the tourist who has time should walk to Thixendale (3 m.), where the wold valley is picturesque. (This is also described in Rte. 8.)

The house of Sledmere (Sir Tatton Sykes, Bart.) is 3 m. from Fimber Stat. It is a fine "Grecian" building, with a noble library running the whole length, 155 ft. The ch., in the park, contains some monuments of Sykeses and Mastermans. The late Sir Tatton Sukes (born 1772, died 1863), so well known on the racecourse and in the hunting-field, was (with his father, Sir Christopher Sykes, to whom a memorial "temple" was erected by Sir Tatton in 1840, opposite the park gates) the great "reformer" of the wolds. He was the first to plant and enclose, "turning bare sheep-walks into rich corngrowing land, averaging from forty to forty-eight bushels of wheat to the His breed of sheep was famous; "and from his training-ground, and its 120 brood mares, came many hundreds of the best hunters in the country, and many of our best racers." Good schools were built by him in the villages; the churches were restored, and new ones built; his last work, a very excellent village ch., close to Sledmere, being a memorial old ch. still exist. Lord Middleton of his wife. "Eigh, well!" said a

Yorkshireman, at his funeral, "there'll | cient church, including maybe a vast o' Sir Tatton Sykeses, and the more the better: but there 'll niver be nobbut one 'Sir Tatton.'" He usually rode to London and back. and as master of hounds was unequalled. "Up every morning with daylight, breakfasting on milk and an apple tart, over at his kennels (15 m. off, at Eddlethorpe) as early as his horse could carry him thither; then a day of cheery hunting, or of hedging and ditching among his tenants; now and then stopping to relieve a parish pauper by breaking a few heaps of stones for him, just for a rest: refreshing (pretty commonly) the pauper, but severely abstemious himself, and then on again for other work: brain and muscle relieving each other, and both made perfect so far as practice could do it—such was the routine of his daily existence; and those who knew him best can best say whether partiality itself can be partial about him."—Saturday Rev., Apr. 1863.

A Gothic tower and observatory 120 ft. high, designed by Gibbs of Oxford, has been raised, as a memorial of Sir Tatton Sykes, on the top of Garton Hill, 14 m. from Malton, and 4 from Driffield. It commands a range of view from Filey to the Humber, and is a most conspicuous object throughout all the country.

The house of Sledmere, which now rises from the midst of extensive woods and plantations, was built toward the end of the last century by the father of Sir Tatton Sykes.

IN. of Sledmere are 4 churches, Kirby Grindalythe, West Lutton, Helperthorpe, and Weaverthorpe, restored or rebuilt at the cost of Sir Tatton Sykes (archit., G. E. Street), and worth a visit. At Kirby the ch. is new; and in pulling down the modern and very bad structure which preceded it, fragments of a fine an-

columns. arches, windows, and a noble old font were found built in as walling. These have all been carefully restored, and it is curious that the remains so discovered were almost identical with the designs for the new ch. furnished by Mr. Street. At West Latton, 2 m. N.W. of Kirby, there is a new ch., with groined porch and chancel. The glass is by Hardman, the triptych on the altar by Burlison and Grylls. The roofs are painted. There is a shingled spire. This ch. has taken the place of a mere barn, which before was used for Divine service. Helperthorpe is 2 m. N.W. of West Lutton. Here also the ch. is new, and built on the site of one which had no old features. It is fitted and decorated very richly. The lych-gate, ch.-yd. cross, and parsonage are also part of the new work. At Weaverthorpe, a mile beyond Helperthorpe, is a fine early Norm. ch., with nave, chancel, and lofty tower. It has been restored completely, and has painted roofs, rich screens to chancel and tower, a painted triptych, and stained glass throughout.]

The next Stat. is at Wetwana. where the ch. has Norm. portions, but is of no very great interest. At the next Stat., Garton - on - the - Wolds, there is a fine Norm. ch. Here the walls have been covered with paintings by Clayton and Bell, from G. E. Street's designs, representing subjects from the Old and New Testaments. the Labours of the Months, and This ch. should be seen. From Garton the train soon reaches

Driffield Junction, where the present line and that from Hull to Bridlington meet. (For Driffield and the line to Bridlington, see Rte. 9.)

ROUTE 12.

YORK TO SCARBOROUGH BY CASTLE HOWARD AND MALTON.

(N.E. Railway. 7 trains daily. The journey, 422 m., is performed by the express train in 11 hr.)

The portion of the line between Barton Hill and Malton, which runs in sight of the Derwent, is very pleasing.

The line to Market Weighton (Rte. 8) branches off rt.; and the rly, proceeds across the great plain of York, passing

42 m. *Hazby* Stat. (small Norm.) ch.), where the river Foss is crossed: and

71 m. Strensall Stat. (ch. rebuilt 1865-6); till it reaches

10 m. Flaxton Stat. About 2 m. N. are the very interesting ruins of Sheriff Hutton Castle. A field-path (as to which the pedestrian should inquire at the station) passes (at about halfway) through an earthwork (square and nearly effaced), with low |

This earthwork is probably of Roman A long entrenchment (?) running across the country beyond it may have been earlier. It then reaches Sheriff Hutton Park (Leonard Thompson, Esq.), where are some fine old oaks; and crosses the ch.-yd. into the village.

The Castle, originally built circ. 1140, by Bertram de Bulmer, Sheriff of Yorkshire (from whom the place gains its distinctive name), passed to Geoffry Neville, who married Bulmer's only daughter and heiress. The Nevilles retained the castle and manor until the death of the great Earl of Warwick, the "King-maker" and the "last of the barons," at the battle of Barnet, in 1471. Edward IV., who seized them, gave them up to his brother Richard, afterwards Richard III., who confined in the castle Elizabeth of York, and his nephew Edward, son of George Duke of Clarence. It was from Sheriff Hutton that the "White Rose of York," as Elizabeth was called, was conducted to London in 1486, to become the wife of Henry The manor afterwards passed through various hands (the Duke of Norfolk, 1490-1500, and Henry Fitzroy, Duke of Richmond, natural son of Henry VIII., both inhabited the castle) until it became the property of the Marquis of Hertford. From him it passed, with much land in the parish, into the hands of the representatives of the late Meynell Ingram, Esq.

Ralph Neville, first Earl of Westmoreland, the "gentle cousin Westmoreland," of Shakspeare's 'Henry IV.'—

"O Westmoreland, thou art a summer bird Which ever in the haunch of winter sings The lifting up of day "-

entirely rebuilt the castle, on a scale so much enlarged, that Leland says he saw "no house in the North so mounds (turnuli?) attached to it. like a princely lodging." All the

existing remains are of this date (circ. | 1410). The walls, which formed a square of considerable size, stood on a lofty mound, and had a great square tower at each angle. These towers, with a portion of wall on the S. side. show great masses of ruin: the towers at the S.W. and N.E. angles being the most perfect. Two large arched window openings in the S.W. tower lighted a great hall. On the S.E. tower are 3 shields, with the saltire of Neville, and the coat of the 1st Earl of Warwick, impaling France and England for his second wife. The principal entrance has been on the E. side; and on the W. some remains of grass-grown outworks may be traced. The inner courts of the castle were surrounded by a deep most, which still exists, and beyond it are remains of a wall enclosing the outer bailey. The plan and arrangement of the castle should be compared with that of Bolton (see Rtc. 24), of somewhat earlier date, built by Lord Scrope, temp. Richard II. Bolton is far more perfect than Sheriff Hutton, but the general plan of both castles seems to have been very similar. From below the S.W. tower there is a striking view over the rich plain towards York, worth the artist's attention. There are great ash-trees on the castle mound, then a wide stretch of woods and meadows, with a blue distance beyond. Flocks of pigeons rest on the grass-grown ledges of the ruined towers. A good general view of the castle is gained from the S.E. angle of the moat, round which the visitor should walk.

The Church of Sheriff Hutton (dedicated to St. Helen) is Dec., with later insertions. In the N. aisle, the windows, nearly square-headed, show a peculiar tracery, which occurs in many churches on the Neville manors, —most conspicuously at Staindrop, adjoining Raby Castle. Here, the windows may have been inserted by the first earl, the rebuilder of the

castle. A door, original and curious. at the end of the aisle, opens to what is now the vestry, of earlier date than the rest of the church, with small square-headed windows S. and N., and a narrow lancet, now closed, which opened to the chancel. The arrangement of the tower at the W. end is very peculiar. The lower part forms a porch, with entrances N. and S., and flights of stone stairs on either side, leading to an upper platform; another flight descends under the W. arch, to the floor of the nave within. The lower walls of the tower are Norm., and show traces of circularheaded windows. The upper part is later. Under the E. window of the N. aisle is the effigy of a knight, circ. 1350? The arms on his shield seem to be those of Thomas Wytham, since they occur also on a brass on the floor, with an inscription, but no date, recording the building of a porch (vestibulum), and the foundation of a chantry by this Thomas and his wife Agnes. The "porch" may, perhaps, mean the arrangement in the tower already noticed. Under the next window is a tomb with a short effigy, in a robe, and wearing a coronet. It is of the 15th cent. and represents a Neville, since the saltire is on the shield at the head,—but has no inscription. This is probably the tomb of the Duke of Bedford, son of John Neville, Marquis of Montacute, a nephew of the King-maker. The dukedom was conferred on him in 1469, when Ed. IV. intended marry him to the Princess Elizabeth (afterwards wife of Hen. VII.). His father's death in 1471, in the battle of Barnet in open rebellion, brought his family into disgrace, and he lost his father's titles and estates under an act of attainder. In 1477 he was degraded from all his honours by Act of Parliament (17 Ed. IV.) on account of his poverty, he being absolutely without any estates. He lived until 1483, and was buried at Sheriff

a prisoner in the castle for part of | dreadful condition. In front of the tomb are shields, that in the centre having a representation of the Holy Father supporting the crucifix. From the ch.-vd. there is a view E. towards the On the S. side are some mounds which have been considered Roman, but which do not seem to have been properly examined.

[Sittenham, 1 m. N.E. of Sheriff Hutton, is said to have been the birthplace (1320) of Sir John Gower, the poet, and the "master" of Chaucer, to whom he is indebted for his title of "moral Gower." The Gowers were settled here from a very early period. The poet succeeded his elder brother in the family estate, which still belongs to the Levison-Gowers, Dukes of Sutherland.

(Sand Hutton, 21 m. S. of Flaxton stat., is the seat of Sir James Walker, Bart.)]

12 m. Barton Hill Stat., 31 m. from Castle Howard. 1 m. l. is Foston - le - Clay, the living which Lord Chancellor Erskine gave to Sydney Smith. There was then no house on it; the living comprised 300 acres of glebe land of the stiffest clay, and there had been no resident clergyman for 150 years. Sydney Smith first settled at Heslington, near York, until he had built his new house at Foston, "the ugliest in the county." he says, "but all admitted it was one of the most comfortable," although it was, as he described it, "20 miles from a lemon." How he built it, and how he furnished it; how Lord and Lady Carlisle arrived in their "gold coach," stuck in the clay, and were ever after among his firmest friends; of Bunch, and of his carriage the "Immortal," we have all read in his daughter Lady Holland's memoir. In 1829 he left Yorkshire for Combe Florey, in Somersetshire. The Church has ancient portions, but is in a a Spanish ship taken by him.

In the vestry remains the newter communion plate.

Soon after leaving Barton Stat. the column on Bulmer Hill (1.) comes This was erected, by into sight. public subscription, in 1869, on the S. edge of the Castle Howard demesne, as a memorial of the 7th Earl of Carlisle, who for 12 years, as Lord Morpeth, represented first Yorkshire and then the West Riding in Parliament, and for 8 years was Viceroy of Ireland. The design of this Grecian column is by F. P. Cockerill. The cost was about 2000L. From its position it is visible far and wide over this part of Yorkshire. In the parish of Bulmer the Castle Howard Reformatory for juvenile offenders from the N. and E. Ridings.

Here the rly, makes a sharp curve. and enters the picturesque vale of the Derwent, passing l. the wooded hills

of Crambe.

On rt. is Howsham, the birthplace of Mr. Hudson of rly. celebrity. On the l. is the village of Whitwell (where is a good Church (G. E. Street, archit.), built, in 1860, at the cost of Sir Edmund and Lady Lechmere), and rt. on a rising ground above the Derwent is Howeham Hall (Sir George Cholmley, Bart.) a very fine specimen of Elizabethan architecture (said to have been built with stones from the Priory of Kirkham). Its front appears almost panelled with glass from the number and size of its square mullioned windows. Its roof is surmounted by a curious vandyked parapet. The house (only to be seen by special permission) is rich in portraits, chiefly of Cholmleys and of Yorkshire families with which they have intermarried. On the staircase is a very remarkable series of paintings on cotton, representing the deeds of Cortez in the New World, and said to have been found by a Cholmley in

dow (Kirk ham = Church Meadow), on the opposite side of the Derwent, l. are the remains of Kirkham Priory, now but scanty, but to be visited by all ecclesiologists for the sake of one exquisite fragment of E. E. date, sufficient to show that the ch. must have been one of the most beautiful in Yorkshire. (The key may be had at the Hall, or Lodge.) The situation of the ruins, in a valley bounded by low wooded hills, is one of great beauty. The priory was founded for Augustinian Canons, in 1121, by Walter l'Espec, the great baron who (1138) led the English army at the battle of the Standard (see North Allerton, Rte. 16), and his wife Ade-Their only son. Walter, is said to have been killed by the fall of his horse at Frithby or Firby, on the Derwent, not far from Kirkham; and his father, resolving by the counsel of his uncle William, rector of Garton, to devote the greater part of his wealth to God, founded three religious houses-this of Kirkham, Rievaulx (Cistercian, founded circ. 1113—see Rte. 18A), and Wardon (Cistercian) in Bedfordshire. The monastic verse ran accordingly-

"Pro reorum veniš Kirkham domus bona Rievallis deinceps, et hec tria, Wardona Est fundata primitius a dicta persona, Pro quorum meritis datur illi trina corona,"

(It is remarkable that no reference whatever is made to the son of Walter Il'Espec in any of the charters of foundation. The story of his death is told in a vol. of collections among the Cotton MSS. (Vitell. F. 4), whence it was copied into the 'Mon. Angl.' The local legend asserts that a wild boar, rushing across the road, startled the horse, which flung its rider against a stone that now forms part of a cross before the gatehouse of Kirkham, and then dragged him by the stirrup to the place where he was found, which was therefore chosen as the site of the high altar. Walter

15# m. Kirkham Stat. In a mea- | l'Espec became a monk in his own abbey of Rievaulx, and died there in 1153. His sister married the heir of the great house of Ros or Roos, in Holderness (see Rte. 6), and afterwards of Helmsley Castle (Rte. 18A): and that family continued to be the patrons of Kirkham until the Many of them were Dissolution. The annual value of buried here. the house at the Dissolution was 2691., nearly the whole of its property having been the gift of the founder, l'Espec. The ruins have been purchased by Lady Fitzwilliam.

> Before the gatehouse, through which the visitor passes into the precincts of the priory, is the base of a cross (the stone against which the heir of l'Espec is traditionally said to have been On a particular day in thrown). autumn, "Kirkham bird fair" is held at this cross,--jackdaws, starlings, and larks being the articles of com-The Gatehouse itself was erected in the latter half of the 12th cent.: and the small apartments E. and W. of the archway are of this The archway itself was rebuilt in the early Dec. period, and is very picturesque. The shields of arms on its outer face, before the cornice, are Clare, Plantagenet, Ros, and Vaux. The niches have been robbed of their figures, with two exceptions—one of which is so defaced as to be unintelligible, the other is St. Bartholomew. Much-defaced sculptures also remain on each side of the archway -representing St. George, and either David and Goliath, or some fight of a Ros with a Scottish foeman. inner face of the gateway has lost all its enrichment.

the horse, which flung its rider against a stone that now forms part of a cross before the gatehouse of Kirkham, and then dragged him by the stirrup to the place where he was found, which was therefore chosen as the site of the high altar. Walter

arrangement and execution as any other work of this period in the county. S. of the choir was probably the prior's house. The Chapter-house (rectangular and E.E., like the choir) was near the S. end of the transept: and between it and the ch. was a small room with a bench on one side -the purpose of which is uncertain. On the S. side of the cloister quadrangle was the Refectory, standing E. and W., contrary to the ordinary rule. The eastern gable remains; and the N. wall, in which is a Trans.-Norm. doorway enriched. (It is engraved in 'Parker's Glossary.') the side of this doorway is a lavatory, of much later (early Dec. ?) character. The Dormitory was on the W. side of the cloister, but only the wall towards the quadrangle remains. In front of the dormitory is a noble ash-treemaking, with the river beyond, the bridge and gatehouse, the meadow and steep banks of wood, a picture for the artist.

An earthen pot, full of bronze chisels, gouges, and celts, found at Weston, near Kirkham, is now in the Yorkshire Museum.

From Kirkham to Malton extends the narrow dale, down which flows the Derwent, draining all the rivers from the vale of Pickering, which, but for this outlet, would be, as at one period it probably was, a great lake, discharging its waters into the sea near Specton, instead of running inland and S. as at present. On the rt. are seen Firby Woods.

16 m. Castle Howard Stat. This station is 3 m. from Castle Howard. There is no longer an Inn at Castle Howard. The Black Bull at Welbourne, 11 m. distant, is the nearest Inn, but poor, and (?) also closed.

Castle Howard, the magnificent seat of the Earl of Carlisle, is one of

capitals of foliage, at least as good in I the grandest and richest country seats in England, and contains a noble collection of works of art. "Lord Strafford alone had told me," writes Walpole to Selwyn (August, 1772), "that I should see one of the finest places in Yorkshire; but nobody had informed me that I should at one view see a palace, a town, a fortified city, temples on high places, woods worthy of being each a metropolis of the Druids, vales connected to hills by other woods, the noblest lawn in the world fenced by half the horizon, and a mausoleum that would tempt one to be buried alive. In short, I have see gigantic places before, but never a sublime one."

> Castle Howard was built about 1702, by Sir John Vanbruah, for Charles, 3rd Earl of Carlisle, by whom the park and grounds were also laid out. These have since been little altered. Formal and stately avenues of lime, beech, and oak converge from four quarters towards an Obelisk, bearing an inscription by the founder, in honour of himself and the great Duke of Marlborough. vast extent of the demesne almost justifies Walpole's raptures; and the Lake, which stretches away before the grand entrance, is striking and picturesque. The ground is much varied and broken; one of the main roads through the park, climbing in a series of steep ascents to the higher level of the so-called "Howardian" hills, which form the southern boundary of Ryedale.

The castle was built on the site of the Castle of Hinderskelf, destroyed by fire about the year 1700. It was erected about the same time as Blenheim (also Vanbrugh's), and is "a far more successful design." "In plan, it is somewhat similar, and looks almost as extensive; but, being only one story high over the greater part, it is in reality much smaller; and its defects arise principally from the fact that Vanbrugh seems to have had no idea of how to ornament a building except by the introduction of an Order. At Castle Howard the whole design is much soberer and simpler than at Blenheim. The cupola in the centre gives dignity to the whole, and breaks the sky line much more pleasingly than the towers of the other palace. The wings and offices are more subdued; and on the whole, with all Vanbrugh's grandeur of conception, it has fewer of his faults than any other of his designs; and, taking it all in all, it would be difficult to point out a more imposing country-house possessed by any nobleman in England, than this palace of the Howards."—Fergusson. The W. wing, it should be said, was added by Robinson, and is unequal to the original design.

Throughout the W., S., and E. fronts, the principal apartments open into each other. They are crowded with pictures, with china, and with various antiques, to such an extent that the house has the character of a museum; and the library is rich in the collections of successive accumu-The collections have been rearranged, and much has been done to the interior of the mansion, since the death of the 7th Earl. Chapel, especially, has been renewed and decorated, and has been rendered more fitting its importance as the domestic chapel of so vast a Of the Pictures, those building. chiefly to be noticed are marked with an asterisk; but two must be especially mentioned: "The Adoration of the Kings," by Mabuse, and the "Three Marys," by Annibale Carracci, The strength of the collection is in important works of the Carracci and their scholars, as well as in Flemish pictures of the time of Rubens. Lord Carlisle was one of the three principal purchasers of the Orleans Gallery in 1798; and works from it are marked "O" in the following notice.

The hall, into which the visitor enters, 35 ft. square and 60 ft. high (100 ft. to the top of the cupols). has its ceiling painted with the "Fall of Phaëton," by Pellegrini. The subiect is curiously unfitted for its position, and "a person standing under feels as if the four horses of the sun were going to tumble on his head." Some antique sculptures, among which the finest is a bust of Bacchus, are arranged here. The apartments l. of the entrance-hall are generally first entered; but as occasional changes are made in the position of the pictures, it will be best to describe them in alphabetical order. As each picture has a number corresponding with the Catalogue, it will be easy to refer to the notice of it. Only the most important are mentioned here, and the principal of these are distinguished by an asterisk :---

*Giovanni Bellini.—The Circumcision. "The real original, marked with the artist's name, of the many copies made at a remote period, of the middle time of the artist."—Waagen.

*Fordinand Bol.—A Boy holding a goblet. Very spirited, and carefully executed in a bright golden tone. The cover of a table is of a deep, glowing red. Whole-length, the size of life.

Paul Brill.—View of the Campagna, from Tivoli.

Canaletti. — A large view of Venice. "In every respect one of the capital works of this master, whose extraordinary merit is not to be appreciated except in England."—W. (The quotations marked "W." are from Waagen's 'Art Tressures in England.') There are more than 20 pictures by Canaletti, some very excellent.

Agostino Carracci.—The Virgin and

Infant Christ present the Cross to St. | of one of which is wanting, this being John.

Annibale Carracci.—2 large landscapes - one representing a very poetical mountainous country. "in which the influence which Brill had on him as a landscape-painter is very evident."-W.

Ann. Carracci.-A Boy and a Girl with a Cat. Very animated and humorous.

Ann. Carracci.—His own portrait, looking earnestly round.

*Ann. Carracci.—The celebrated picture, from the Orleans Gallery. known by the name of THE THREE The Virgin, in the excess of her grief, has fallen back in a faint, with the dead body of Christ on her lap: Salome holds the Virgin's head. In front is the Magdalen, in "her red robe of love," with yellow mantle over it. Mary, the mother of James, is in green, by her side. The expression of intense grief is marvellous. The figures about one-third as large as life. .

*Ludovico Carracci.—The Entombment; figures the size of life. Very noble in the composition and characters. Of the holy women only Mary Magdalene is present. The too dark shadows injure the keeping. (0.)

Domenichino.—St. John the Evangelist looking up in rapture. "This is one of the most indisputable and capital original pictures of Domenichino that exist."-W.

Domenico Feti.-Portrait of a man, possibly himself. "Conceived with great spirit in his natural manner, and producing a striking effect by the glowing lights and the dark shadows."-W.

Giorgione.—Two female heads, part | sesses."—W.

the fragment of a larger picture.

Van Goyen .-- A village on a canal, in a warm evening light. masterpiece of the very unequal master is in force of effect near to A. Cuyp."-W.

Holbein.-Duke of Norfolk. The same as in Windsor Castle; and, like it, an old copy.

Holbein. — Henry VIII. An old copy of the picture in Warwick Castle.

Gerard Honthorst.—The Finding of Moses, figures as large as life, called in the Orleans Gallery a Velasquez: "uncommonly noble in the characters, careful in the execution, and clear in the colouring."—W. (O.)

Gerard Honthorst. - A Concert, figures the size of life.

Francois Clouet, called Janet .-- A collection of more than 300 portraits of the most eminent persons at the courts of Henry II., Francis II., Charles IX., and Henry III., executed with much spirit and animation in black and white chalk, in the manner of Holbein. "It is very singular that the men are almost all handsome, the women, with few exceptions, ugly."-W.

*Janet .- Mary Q. of Scots; Adm. Coligny; Catherine de Medicis, consort of Henry II., with her children, afterwards Francis II., Charles IX., and Henry III., and the Princess Margaret; whole-length figures, the size of life. "Very carefully painted in his pale mode of colouring, and especially delicate in the hands. more important picture of this, the best French portrait painter of that age, than any that the Louvre poswith his name and 1657. "Is a (0.) masterpiece of this kind, and proves how art can lend a charm even to such an indifferent subject."-W.

Lely.-James, Duke of York, afterwards James II. Young, and with the hair in rich curls. A good and carefully painted picture. Josceline. Earl of Northumberland, in armour. Uncommonly spirited, and carefully executed. Duchess of Richmond; whole-length. Sir George Lisle (shot with Sir Chas. Lucas at Colchester, by order of Fairfax, 1648).

* Mabuse. — The Adoration of the KINGS. This celebrated picture was painted before Mabuse went to Italy : and changed his style considerably for the worse. In it he shows himself "by no means inferior to the two most celebrated contemporary painters in the Netherlands-Roger van der Wevde, and Quintin Matsvs. In the nobleness, refinement, and variety of the characters he is superior, and in gravity and energy equal to them." -W. (The date of Mabuse's birth is unknown; it may have been circ. 1470. About 1500 he went to Italy. Died 1533.) This picture, although painted more than 3 cents. and a half ago, is as fresh and in as fine a state of preservation as if finished yesterday. The richness and harmony of colour afford, when the enclosing panels are opened, as delightful a sensation as a burst of sunshine on a gloomy day. Each head should be noticed. Remark especially the wonderful painting of the robe of Balthazar, and the admirable arrangement of the white scarf, in which he holds the thurible. A small head, with hat and feathers, looking in at a window, is said to be that of Mabuse himself. This picture is inscribed with the artist's name "Jan Gossaert." He is generally known by that of his native town, Mabuse, now Maubeuge, in French

Letienberg.—Dead Game. Marked | Flanders, not far from Valenciennes

Pierre Mignard.—The philosopher Descartes: half-length in a circle.

Ant. Moro. - Mary Queen of Eng. land in a splendid dress. The delicacy of the execution, in a clear and warm tone, is worthy of Holbein. Half-length. This is not the picture noticed by Walpole. (See post.)

Frans Pourbus, the Father.—A Knight of St. Michael; half-length. "In energy of conception and force of the clear colouring, one of his best pictures."---W.

Primaticcio.—Penelope relating to Ulysses what has happened to her during his absence. "This is the most important work that I have yet seen of this master, who fills so important a place in the history of painting in France, and whose works, since the ruin of almost all his frescopaintings in the Louvre, are so rarely The characters are very noble, the drawing and rounding of all the parts correct and careful, but the colouring weak."-W.

Sir J. Reynolds.—Portrait of Omai, the "gentle savage," brought to England by Captain Cook from the Sandwich Islands. "In animation and conception, masterly keeping, and solid execution, one of the finest pictures of the master." Frederick, 8th Earl of Carlisle, when young. "Likewise very spirited in the head; only the attitude is rather theatrical." --₩.

Salvator Rosa.—A Man, holding in his right hand a white dove, and with the left pointing downwards. Half-length. "Surprisingly noble in the expression and uncommonly clear and warm in the colour."-W.

Rubens .- The Daughter of Hero-

vant, receives from the executioner the head of St. John: the original of many copies. "A very powerful work of the later period of the master, carefully executed and brilliant in the colouring."-W.

*Rubens.—Thomas Howard, Earl of Arundel. One of the finest portraits that Rubens ever painted. "Nobleness of conception, simplified and decided forms, are combined with a breadth of careful execution. a depth and clearness of the by-nomeans extravagant colouring: one is never tired with looking at it."—W.

Old Stone.—Charles I., with his son the Duke of Gloucester. Copy after Vandyck.

*Tintoretto.-2 young Dukes of Ferrara, whole-length, the size of life, attended by a servant and a page, and kneeling at prayers in a church. "Tintoretto manifests here, as he often does in his portraits, the noblest and purest conception. The brownish lights and the dark shadows produce a deep grave harmony."-W. (0.)

*Tintoretto. - 2 landscapes, one with the Sacrifice of Isaac, the other with the Temptation of Christ. "Extremely poetical, in the manner of Titian, only still bolder in the forms of the mountains, richer in the objects, and producing, by the warm light, a great effect; at the same time very carefully painted and clear for him."---W.

*Tintoretto. — Adoration of the Shepherds. In the landscape the Wise Men. "Highly characteristic of the more elevated feeling of this master. Painted with a light spirited pencil, in a glowing tone, approaching to Titian."-W. Pictures of

dias, attended by a female ser- | rarely seen in England, and deserve the most careful attention.

> Titian.-A Butcher's Dog and 3 Cats; most fearfully animated.

Perino del Vaga. - The Holy Family.

* Vanduck.—Portrait of Frans Snvders, the painter. "Not only one of the very finest portraits of Vandyck, but entitled to rank with the most celebrated portraits of Raphael, Titian, or Holbein."-W. James, 1st Duke of Hamilton, the intimate friend of Charles I., whom he was suspected of betraying when the Scots sold him to the Parliament. He afterwards raised forces and entered England, was defeated by Cromwell at Preston (Aug. 1748), surrendered, was tried before Bradshaw, and executed, Mar. 9, 1649. (Full-length.)

Velasquez.—Two children, in elegant dresses, said to be a young Duke of Parma and his dwarf.

Velasquez.—Portrait of a Man, with features resembling those of a negro. Ennobled by the conception, and at the same time most strikingly true to nature.

Carlo Veneziano. - The Death of the Virgin; figures as large as life. The altarpiece of the chapel. (O.)

Zucchero.—Thomas Howard, 4th Duke of Norfolk, who, after his political intrigue with Mary Queen of Scots, and the "Rising of the North," was tried and executed, June 2, 1572.

Four portraits, which cannot be assigned with certainty to any artist, should also be noticed:—A "delicious whole-length of Queen Mary, with all her folly in her face and hand," mentioned by Walpole; Henry Howard, Earl of Northampthis character, by Tintoretto, are ton, 2nd son of the first Earl of Surrey, author of the 'Dispensation | temple of Apollo at Delphi, many against the Poison of supposed Prophecies,' Constable of Dover under James I., died 1614 (bust, dated 1606); Henry Percy, 9th Earl of Northumberland, imprisoned by Jas. I. for 15 years on suspicion of complicity in the Gunpowder Plot (full-length, in robes as Chancellor of Univ. of Cambridge); and Lord William Hongard, the "Belted Will Howard" of the 'Lay of the Last Minstrel,' from whom the Carlisle branch of the Howards descend.

Since the death of the 7th Earl, the pictures from the town house have been removed to Castle Howard. Among them are-

Tition.—Portrait of a man with falcon.

Giorgione.—Portrait of Gaston de Foix (very fine).

Rubens.—A wooded landscape.

Correggio.—A Virgin and Child, and St. John.

Claude.—Landscape.

Cwwp.—Six Landscapes.

Gainsborough.—Girl feeding pigs a fine picture.

In the Museum is placed a testimonial (cost 1000 guineas) from the West Riding, presented to the 7th Rarl (then Lord Morpeth), after the election of 1841, when he was defeated. It is a wine-cooler in bog oak and silver-gilt, with the shields of Yorkshire towns round it. There are, besides, forty or fifty silver trowels, spades, &c., given to the 7th Earl on various public occasions. Of the Antiquities preserved here, remark especially some fine Greek vases, a circular altar of marble brought by Nelson, says the inscription, from the cinerary urns and small bronzes, and some good ancient sculpture. Some antique statues—as the Gaulish Hercules in armour, dug up on the C.H. estate; a Minerva, of alabaster with bronze insertions, and other sculpture worth attention-are also arranged in a Corridor through which the visitor passes to regain the entrance hall. There is some good tapestry in many of the apartments, and some very fine china.

The Gardens are kept in a state of order and beauty, consistent with the rest of the Domain. Near the house is a copy of the great antique "boar" (at Florence), in Carrara marble, and many other copies from antique statues are scattered over the lawns and terraces. The Park, very fine and extensive as it is, has a certain air of neglect. 1 m. E. of the house is an Ionic temple with porticoes; and at some distance beyond, the Mausoleum in which the Earls of Carlisle have been deposited since the building of Castle Howard. Nicholas Hawksmoor, a scholar of Wren, was associated here with Vanbrugh; and was employed in erecting this mausoleum when he died. "This was the first mausoleum (unconnected with a church) erected in England; and was of course a copy of the Roman tombs and columbaria. The example has since been followed at Brocklesby (Lincolnshire), for Lord Yarborough; at Cobham in Kent (Lord Darnley), and elsewhere."

(The tourist may drive from Castle Howard to the Kirkham Stat., see the ruins there, and so return to York. The drive, about 4 m., is pleasant, and there is an excellent view of Castle Howard just above a small church, built by the late Earl.)

The Rly. follows the winding course

planted by the 6th Earl of Carlisle, and occasional rock-cuttings, blasted in the colitic limestone, to reach

19 m. Hutton Stat. (ch. of Hutton Ambo, built in 1856), beyond which it crosses the river on a timber bridge to

21# m. Malton Junction Stat. on the Derwent, near huge Bone Mills, which are not only seen but smelt from the Stat.

(Branch Railways run from Malton to Driffield across the Wolds (Rte. 11). To Pilmoor Junction on the North-Eastern line, and to Thirsk (Rte. 18), passing through Ryedale, by Helmsley (Rievaulx Abbey) and many points of interest.)

Malton, Inn: the Talbot-with a garden overlooking the Derwent. Malton (Pop. 10,542, 1881) is in effect a junction of three "towns,"-Old and New Malton on the rt. bank of the Derwent, and Norton on the l. situation is agreeable. The number of railways render accessible many places of interest (Castle Howard, Kirkham—all the stations in Ryedale (Rte. 18)—the Wold country, and the watering-places).

Malton was unquestionably an important Roman station, probably Derventio (named from the Derwent), though it was, according to the Itineraries, 7 miles from York. Malton is seventeen Roman miles distant. There may, however, be an error in the numbers. Roman roads led from ·Malton-besides others of less importance-westward to Isurium (Aldborough, Rte. 19), S. to Eburacum, E. to Bridlington, and N. to Dunum Sinus (near Whitby). Modern railways do not follow the exact lines of these roads; but they run in the same directions; and the position of Mal-

of the Derwent, through oak woods those ancient days, near a ford of the river, and at the foot of the Wolds,advantages which had probably rendered Malton an important British settlement before the arrival of the Romans. British tumuli and camps abound in the neighbourhood.

> After the Conquest, Malton passed to a certain Gilbert Tyson; whose descendant, Eustace Fitz-John, succeeded to the lordship temp. Hen. I. A castle had been built by one of the Norman lords on the site of the Roman camp; and Eustace, who on Henry's death took the side of the Empress Matilda, gave it up, together with Alnwick, which he also held, to King David of Scotland, who placed a strong garrison in Malton. Archbp. Thurstan attacked the Scots in Malton, took it, and burnt the town. Eustace fled to Scotland. and was present in the Scottish host at the battle of the Standard in 1136. (See North Allerton, Rte. 16.) He was afterwards reconciled to Stephen, and rebuilt the town of Malton, henceforth known as New Malton. son of Eustace assumed the name of Vesci: and Malton continued in that family until the reign of Henry VIII., when the greater portion of it passed to the family of Eures or Ever.

The Norman castle has entirely disappeared; as, in its turn, has vanished a mansion built on its site. temp. James I., by Ralph Lord Eures. The lodge still remains. The manor and lodge became afterwards the inheritance of the Hon. Thomas Wentworth, created Lord Malton, and better known as the Marquis of Rockingham, the statesman and prime minister. From him they have descended to Earl Fitzwilliam.

Malton is the centre of the corn trade for a wide district; but it has little other trade, and the water traffic ton is as central now as it was in with Hull has nearly ceased since the completion of the railways. The chs. ! of New Malton (St. Michael's and Leonard's) are uninteresting. What is now the cellar of the Cross Keys Inn, in Wheelgate, was the crypt of an hospital attached to the Priory of Old Malton; it is late Norm., and of some interest. The Norman town was walled, but only a fragment of the old walls remain. The Lodge (W. C. Copperthwaite, Esq.), passed rt. on the road to Old Malton, is a good example of Jacobsean architecture. and was connected, as has been already said, with the castellated building behind it, now destroyed. Many British and Roman relics found in the neighbourhood are preserved here: and it marks the site of the This exgreat Roman Castrum. tended S. of the lodge-which is built on its vallum—towards the river. The double vallum on the E. side is still very distinct, as are the defences S. with the Prætorian gate, the form of which resembles that at Cawthorne (see Rte. 14), and is supposed to be peculiar to camps occupied by the 9th Legion. Foundations of the Norm. castle may be traced towards the centre of the camp. A road, leaving the camp by the Prætorian gate, crossed the river at a ford (by the island) and passed towards Londesborough, where it joined another Roman road leading to York. merous Roman remains have been found in the camp and its vicinity; among others, the curious sign of a goldsmith named Serulous, engraved in Wright's ' Celt. Roman, and Sazon.'

Old Malton, 1 m. beyond the Lodge, is only interesting for the remains of the Priory Church, now used as that of the parish. The priory was founded in 1150, by Eustace Fitz-John, for Gilbertine Canons, and was The foundation richly endowed. took place during the lifetime of St. Gilbert of Sempringham, the founder of the order, who died in 1189, and

care of all his religious houses to Roger, Prior of Malton. (Under the Gilbertine rule, monks and nuns occasionally occupied separate divisions of the same convent.)

The priory stood on the rt. bank of the river Derwent, which runs within a few wards of it. Of the Church, the W. front and a portion of the nave alone remain in a perfect state. The original plan embraced a long nave with aisles, a tower between the nave and choir, transepts with square eastern chapels of somewhat unusual plan; choir with aisles; and a square eastern end projecting beyond them. The eastern part of the church, beyond the nave, can only be traced by its foundations; the western piers of the tower, and fragments of the nave aisles, are in complete ruin; the greater part of the aisles has disappeared entirely; and a wall is built up between the nave piers. window in the E. wall (which crosses the nave at the 6th bay from the W.,-there are two ruinous bays of the nave beyond it) was inserted The piers and arches in 1844. (built up) of the nave are Trans.-Norm .- no doubt part of the original circular triforium work. Large arches run above the piers. whole of the W. front appears to be of the latter part of the 12th cent. There were towers N.W. and S.W. The base of that N.W. alone remains; that S.W. is very fine, and should be compared with the later development in the E. E. towers of Ripon. It has lofty pointed window openings, with clustered shafts at the angles; and 2 quatrefoils within circles on each side of the tower at the top.

Foundations of the great cloister may be traced S. of the nave; and under the modern house called "the Abbey" is a crypt (perhaps originally below part of the refectory). was buried here, bequeathing the The ground about the church is

much broken with mounds and hollows,—traces of the many buildings attached to the priory. A building adjoining the ch.-yd. was the schoolhouse of the Free Grammar School, founded by Robert Holgate, Abp. of York (1545-1556). Holgate, whom Fuller calls a "parcel Protestant," had been a master of the Gilbertines, and founded a school at whatever place in Yorkshire there had been a priory of the order.

Norton is the third "member" of Malton, on the l. bank of the river. The ch. is modern and uninteresting. Near Norton is Whitewall, where was the training establishment of the late John Scott. On each stable door, framed in gilt horse-shoes, are miniature portraits of the racers that have been trained within. neath is a record in gilt letters of the horse's performances. In 35 years, 16 winners of the St. Leger were trained in the Whitewall stables. The training-ground was on Langton Since Mr. Scott's death, these famous stables have been empty; and though still cared for. have of course a sadly deserted look. Messrs. I'Anson, Peck, and Shepherd have still training stables near Malton, but not on the scale of Mr. Scott's. An order, or an introduction, is necessary for seeing any of these establishments. On the S. side of the Wold, and N. of a little "beck" that runs toward the Derwent, there is a small British camp; and another at Thornthorpe, I m. lower down, on the same side of the stream; "placed to guard the passage on the road from Acklam Wold to Malton."-Phillips. This road, at first a British trackway, was no doubt adopted by the Romans, -since the "street from the Prætorian gate at Malton led to it. There is a wide view from the top of the Wold.

At Malton the rly. crosses the taken to Driffield, w. Derwent, which, from Stamford (See Driffield, Rte. 9.)

Bridge to its junction near Sherburn with the Hartford Brook (one of its sources), and thence to the rise of this brook near the sea (close to Filey), forms the boundary between the E. and N. Ridings.

Malton to Scarborough,-Rail.

26 m. Rillington Junct. Stat.

Rail to Whitby (Rts. 14) branches l. up the picturesque Vale of Pickering.

Rt. is Scampston Park, seat of the old family of St. Quintin.

28 m. Knapton Stat. 30 m. Heslerton Stat.

33½ m. Sherburn Stat. The Church has a much enriched Norm. chancel arch. All along the rt. of the line rise the Wolds, marked by many barrows, which on being opened yielded bronze ornaments and bead necklaces, intermixed with very rude pottery, flint, and "tynes" of red deer rubbed down into pointed instruments.

35 m. Ganton Stat. Here is the seat of Sir Chas. Legard, Bart.

2 m. farther, on the Old Malton road, is Ebberston; and above the village is, or was, a small cave in a rock called Ilfrid's or Alfred's Hole. Tradition (and one of long standing, since there was formerly an inscription over the cave recording it) asserts that Alfred of Northumbria was wounded in a battle within the entrenchments of Scamridge (long lines on the moors above Ebberston, which are however, in all probability, British works), that he fled, took shelter in this cave, and was on the following day taken to Driffield, where he died. (See Driffield, Rte. 9.)

Between Ganton and Seamer the rly., which has so far kept on the E. Riding side of the river, crosses it (it is here the Hartford Brook) and passes N. to Scarborough. The remarkable course of the Derwent (Dwr-gent (Brit.), fair, or clear water-the Kentish Darent, and the Devonshire Dart, are far-off cousins) should here be noticed. Its chief source is near the Flask Inn, between Scarborough and Whitby; a second is the Hartford Brook, rising on the cliff close to Filey. streams, which rise so near the sea, flow W., S., and E. a distance of 100 miles before reaching it. The Derwent joins the Ouse near Hemingborough, and thence flows into the Humber.

393 Seamer Junct. Stat. Here the railway to Filey and Bridlington (Rtc. 13) turns rt.

A Branch Rly. from Seamer to Pickering shortens considerably the distance by rail between Scarborough and Whitby.

The long range of the Wold hills will have been seen rt. after passing Rillington Stat. The sea, appearing at intervals in the same direction (after the line turns N.), indicates the approach (under Oliver's Mount, the hill rt.) to

424 m. Scarborough Terminus, which lies in a hollow or gully running down to the sea, dividing the town into 2 parts. Hotels: The Grand H., the largest building in the town, on a commanding height above the sea, towards which it presents 13 stories, rising 8 on the land side, has 300 bed-rooms, superb dining and drawing-rooms. 300 people sit down at the table d'hôte, a much frequented and well-managed house.—Royal Hotel.—Crown H., more quiet and select, on the S. cliff just above the Spa; P. of Wales H.; both near the sea.—Pavilion, another huge hotel, close to the Railway Stat.; Victoria H.; Cambridge H.

On the North Cliff, a more modern and less fashionable suburb, stretching along the sea-shore N. of the Castle.

Hotels: Alexandra;—the Queen's;
-the Albion H.

In the town: Talbot; Castle; George, chiefly commercial.

From November 15 to May 15, the terms for visitors to these hotels, remaining more than one week, are reduced to about 8s.; or for married

couples, 15s. a week, board and lodging.

423 m. Scarborough Stat.

[Until the E. winds of spring arrive Scarborough is by no means an undesirable winter residence.

Lodgings are to be had in all directions. The best and pleasantest are on the S. Cliff, but there are excellent houses and very good apartments on the N.

Raileays.—To York and Malton (present Route, ante); to Whitby by Seamer Junct, and Pickering (Rte. 14); by Filey and Bridlington to Driffield (Rte. 13), and thence by Beverley to Hull (Rte. 9).

Post-Office and Telegraph in Huntriss Row.

Staamers during the season run for day's excursions to Filey and Bridlington, round Flamborough Head, and to Whithy.

The most important streets for shopping are Newborough Street and St. Nicholas Street. In the latter is *Theakston's* library.

For day's excursions from Scarborough see the end of the following notice.]

Scarborough (Pop. of borough on April 4th, 1881, 30,484, an increase of 6225 since the census of 1871—the number of summer visitors is legion.)

Scarborough is the most frequented and popular sea-bathing-place in the N. of England, especially resorted to by the wealthier inhabitants of the West Riding, and on a sunny day the display of gay and showily-dressed crowds, pacing along the Esplanade above, and the slopes and terraces under the cliff, to the sounds of a good band of music, is very exhilarating. The situation is singularly fine; and all who like bustle and animation will find them here during the season,

and September. Scarborough is the Brighton of the North. All classes meet and enjoy themselves here; and since the network of railways has extended itself in all directions, excursionists from all parts are constantly pouring into it. Filey and Whitby are quieter, and have a far less mixed assemblage of summer visitors; but no other place offers the resources or the amusement of Scarborough. The air is bracing and pleasant. Sands remarkable for extent and smoothness stretch away under both S. and N. Cliffs. bathing is good. The waters of the Spa (chalybeate) are useful in many cases: and walks inland and along the cliffs are easily accessible and picturesque.

Scarborough is built round the shores of a bay whose sides rise steeply from the water's edge, especially on the N.; where a lofty and precipitous cliff, or scar, is crowned by the ruined castle (burgh); the two giving name to the town. The old town, with narrow, dirty streets, and mean houses, tier above tier, clustered beneath the walls of this feudal for-The new town arose first on the S. Cliff; and has since 1840 extended on the N. From the foot of the castle-hill double piers project forward so as to form an outer and enclosed harbour. Another pier projects from the opposite side of the bay, and forms the larger harbour. The harbour was greatly improved and deepened to an average of 4 ft., and Piers erected between 1879 and 1881. The entrance is marked by a Lighthouse. The outer harbour has an area of 5 acres, the inner of 9 acres.

The history of the town is closely connected with that of the castle (see poet), which must have been at all | which, if it gave protection to the German "Spaws"

which is at its height in August | town, brought also sundry calamities upon it. Scarborough obtained a charter from Henry II.; and a patent for a new port from Henry III. (There is mention of a pier as early as this reign.) It ranks among the most ancient boroughs which sent members of Parliament: since its representatives were present at the parliament of Acton Burnell (11th of Edw. I., 1283), a proof, at all events, that it was then not one of the least important towns in the kingdom Only 18 other boroughs were represented in that parliament. borough still sends its two members. The very ancient seal of the town, displaying a ship and a castle, with a star between them, indicates its early importance as a port; and its great fair or " free mart," held on the sands and in "Merchants' Row" close above them, was attended by Flemings, who brought their clothes of Ghent and of Ypres, and by "Osterling" traders from the coasts of the Baltic. The prosperity of Scarborough seems to have declined as that of Hull rose. The town was burnt by the Black Douglas in 1318, after Bruce had taken Berwick; and it suffered much during the civil war, when the castle was twice besieged. Before that time, however, one source of its modern prosperity had been A certain Dr. Wittie, discovered. author (1667) of a book called 'Scarborough Spaw,' tells us that "Mistress Farrow, a sensible intelligent lady," about the year 1620, sometimes walked along the shore; and in the course of her promenades observed that the stones over which certain water passed received a russet colour. She proceeded to make experiments on the water herself, found it efficacious, and " it became the usual physic of the inhabitants." Its fame soon spread; and during the 18th cent. persons of quality came from a great distance to drink it, preferring it times formidable and important, and before even the Italian, French, and

Sea - bathing, which is now the | evident defence to the harbour, that greatest attraction of Scarborough, did not become fashionable until long after the "spaw" was discovered. But as the smooth sands here allowed the comvenience of a "bathing-chariot," as the machines (of which Smollett, im 'Humphrey Clinker,' gives a long description, they were then novelties) were originally called, the place soon grew into favour on that account. Smollett's novel was written about 1767; and it was at Scarborough that Matthew Bramble, whilst swimming from a machine, was dragged on shore im the midst of all the company by the energetic Clinker, who thought his his master was drowning. Sheridan's amusing comedy 'A Trip to Scar-borough' (it is modelled on Vanbrugh's 'Relapse') shows that the reputation of the place ("Even the boors of this northern spa," says Lord Foppington, "had learnt the respect due to a title") had not diminished at the beginning of the present century. The town on the S. Cliff has since been steadily increasing.

The Cliff Bridge, across the ravine between the old town and the S. Cliff, was completed in 1827; and the spa buildings and promenade in 1858, rebuilt in 1879. Houses and terraces have sprung up in all directions at the back of the spa towards Oliver's Mount, and along the North Cliff, beyond the castle. The town has extended on that side only since 1840, although the sands here are finer and more extensive than those below the S. Cliff.

The chief points of interest in Scarborough are in the old town, the Castle and St. Mary's Church. On the S. Cliff, the Promenade, the Aquarium, the Museum, the Spa Pavilion, and St. Martin's Church.

it was probably converted into a stronghold by the earliest inhabitants. But no traces have been found of Roman or British occupation; and a castle is not mentioned in the 'Heimskringla'-Snorro's chronicle of the Norwegian kings - where the first notice of Scarborough occurs. Harald Hardrada, in 1055, before he passed up the Humber to lose his life at Stamford Bridge, landed in "Kliflönd" (Cleveland), plundered the country, and then "lay-to at Scarborough, and fought there with the burghermen. He ascended the hill which is there, and caused a great pyre to be made there and set on fire. When the fire spread, they took great forks, and threw the brands on the town; and when one house took fire from another, they gave up all the town. The Northmen slew many people, and seized all that they found. Phillips's trans. The Norman castle. according to William of Newburgh was built in the reign of Stephen by William le Gros, Earl of Albemarle and Lord of Holderness, one of the principa leaders of the English in the battle the Standard. "Seeing it to be convenient plot to build a castle upon helping nature forward with a Ver costly work, he closed the whole plane of the rock with a wall, built a tower within the very straigh built a tower within the built a tower with the passage."—(W. Newb. Anglic., l. ii. c. 3.) Scarborough H. Anglic., l. ii. c. 3.) Scarborough H. Anglic., l. ii. c. 3.) one of the principal strongholds of one or the primary who, during Stephen's reign, ruled the country north of the reign, ruled the Humber with more real power than the king himself. Henry II., on his accession in 1154, resumed accession the Crown lands alienated by Stephen; and the Earl of Albemarle was then compelled to resign the castle. great tower had already become ruinous, and the king caused a "great great" (arcem me great runous, and magnamet and noble keep" (arcem magnam et The lofty scar on which the *Castle prescurem, which its place is situated rises so conspicuously from The castellans of Scarborough Place. henceforth appointed by the is situated rises so conspicuously from henceforth appointed by the Crown.

Among them were the most important i of the northern barons—Fitzalans, Dacres, Vescis, and Evers. In 1312, when the confederated barons under the Earl of Lancaster were endeavouring to gain possession of Piers de Gaveston, and had followed the king (Edward II.) to Newcastle, Edward with his favourite fled to Tynemouth, and thence by sea to Scarborough, where he left "Sir Piers" in the castle, and went himself to The Earl of Pembroke laid siege to the castle: many assaults were repulsed; but Gaveston was at compelled to surrender for want of provisions. He was beheaded on Blacklow Hill, near Warwick, immediately afterwards. In 1377 (the year of Richard II.'s accession, when France was directing sundry expeditions against the English coasts) a Scottish "pirate," Andrew Mercer. was taken by certain northern ships, and imprisoned in Scarborough Castle. His son, in revenge, entered the harbour with some Scottish, French, and Spanish ships, and carried off several vessels. Alderman Philpot, a wealthy London citizen, at once equipped (on his own account) an armed fleet, and set out with it in pursuit of Mercer, whom he overtook, encountered, and retook the Scarborough ships, together with 15 Spanish ships richly laden. Philpot was impeached on his return for "raising a navy without the consent of king or council," but was honourably acquitted.

At the time of Wyatt's rebellion (1553), Thomas Stafford, second son of Lord Stafford, got possession of it by stratagem. He disguised his troop as countrymen, and on a market day strolled into the castle with about 30 men, who secured the sentinels, and admitted the rest of their band. This sudden and successful attack is said to have given rise to the saying, "A word and a blow—like a Scarborough warning." The castle was retaken, however, after three

days, by the Earl of Westmoreland; and Stafford, convicted of high treason, was believed in London.

Scarborough Castle, held by Sir Hugh Cholmley, who had gone over from the Parliament to the King's side, was besieged from February. 1644-5, to July 25, 1645, when it surrendered. Sir John Meldrum, the first commander sent by the Parliament against it, took the town by a coup de main, and then erected batteries for playing on the castle, and for intercepting supplies. One of these was on the N. Cliff; and as the approaches were carried nearer, a lodgment of troops was made in St. Mary's Church, and a battery opened from the E. window. But the castle guns destroyed the choir of the church-still in ruin; and Sir John Meldrum, after several ineffectual attempts at storming the castle, died of wounds received in the siege (June 3rd). Sir Matthew Boynton succeeded him; and as the garrison was reduced to extremities, and there was no hope of relief, Sir Hugh surrendered on the most honourable conditions (July, 22, 1645). Commons appointed "a day thanksgiving " for the reduction of Scarborough; and during the siege, square-shaped silver coins (value 5s. and 2s. 6d.) were issued—having on one side a castle, with the words "Obsidium Scarborough, 1645." Lady Cholmley remained in the castle throughout the siege, enduring great privation, and taking care of the sick and wounded. In 1648 Col. Matthew Boynton, then governor of the castle, declared for the King; and there was a second siege from August to December, when it again surrendered.

and admitted the rest of their band.

This sudden and successful attack is said to have given rise to the saysing, "A word and a blow—like a Scarborough warning." The castle "lying much open, the wind drove was retaken, however, after three in the rain so forcibly, that the water

came over his bed, and ran about the ling round, terminated at a gateway, room, so that he was glad to skim it up with a platter." The officers of the garrison declared that he was "stiff as a tree and pure as a bell, for they could never move him." The castle received some little repair by a subscription of the town folk in 1745. when fear of Prince Charles and his Highlanders had stirred all Yorkshire -and in the following year some barracks were erected in it. But, after the injuries received during the civil war, the ancient portions gradually fell into ruin; and the present garrison consists of a couple of artillerymen.

The headland on which the castle stands is so strongly defended by nature that (except the walls and towers of the fortress) its only additional protection is the deep moat, with the ridge beyond it, called the "castle dyke," on the landward side. Toward the sea and the north sands the scar (about 300 ft. high) is precipitous. On the landward or S.W. side it has been scarped, and at its foot are the fosse and dyke. The side of the hill is crowned by a curtain wall, extending from the keep to the precipitous cliff, and completing the defence. The approach to the Castle is a short distance E. of St. Mary's church. The barbican, by which we enter, was repaired in 1645, after the siege. A narrow pass along the ridge which connects the castle cliff with the mainland is walled on either side, and runs between the remains of two strong (Edwardian) towers, noticed Leland, "or ever a man can enter aream castelli." This narrow causeway "is cut through at its deepest, and in the cut is built a lofty pier, which appears to have carried a tower and a gate, from which drawbridges dropped either way to connect the causeway. The causeway, from the bridges, ascends W., and close in front of the keep, and finally, wind- panum. The entrance (now mo-

now destroyed, which entered the inner ward close N. of the keep. From this gate the curtain was continued a few yards northward, until it reached the 'Castle Cliff.' where such defence was unnecessary."-- C. In passing upwards towards the keep, the visitor should remark the view on either side. On the castle wall. rt., is the iron cresset of an ancient beacon.

On emerging from the Gateway, the ground expands into a broad meadow. . The summit of the headland divided by a cross wall into two very unequal spaces. The largest of these is the "outer ward" of the Castle. The smaller is the "inner ward:" and in this is the Keep, placed, as was not unusual with Norman keeps, on what was part of the main outer wall of the castle. For leave to enter this inner ward, and to inspect the ruined keep (so far as it is allowed,--part of it is used as a powder magazine), application must be made to the artillerymen, whose barrack is close by.

The keep is no doubt of the reign of Henry II., when William of Newburgh records its rebuilding. E. side is perfect; about half of the N. and S. sides is standing; the W. is quite gone. (Gunpowder was no doubt used, probably after the siege in 1645, for destroying the keep.) The tower is thus a lofty shell, of 3 stories besides the vaulted crypt, about 50 ft. square, 80 ft. high, and entirely open on one side. A modern wall (enclosing the powder magazine) shuts off part of the lower story. follows, however, the line of a central wall of division, which anciently (as in most Norm. keeps—Rochester for example) rose to the level of the floor of the highest story. The windows are of 2 lights, divided by a central shaft, and enclosed by an outer circ. arch, leaving a plain tymwas covered by a rectangular barbican (as at Rochester, but on the ground level), now destroyed, but the remains of its wall are seen in profile against the keep wall. Within the barbican, on the rt. hand, in the keep wall, "was the inner doorway, 7 ft. opening, with a segmental arch, and in the 9 ft. 6 in. thickness of the wall a flight of steps landing upon the level of the first floor. . . . The barbican ramparts were on the level of the 2nd floor of the keep, and were reached by a small narrow door opening from a mural chamber of that floor.'

The basement of the keep is now filled with earth. On the first floor, perhaps the garrison hall, "the cross wall seems to have been replaced by a bold round-headed arch springing from two wall-piers."—C. There is a round-headed fireplace in the E. wall, and mural chambers in the S. wall, which like the others is about 9 ft. thick. The 2nd floor contained the principal apartments, and had a fireplace in its E. wall, and mural chambers N. and S. The 3rd floor seems to have formed one large undivided apartment. No main stair-case exists at present, but it may have been in one of the angles now destroyed.

The keep of Scarborough is nearly of the same date as Rochester, but it is not so large, and was probably never so magnificent. In size it more nearly approaches the keep of Newcastle, which is, however, much earlier (temp. William II.).

A battlemented wall, with drumtowers at intervals, open at the gorge, runs round the cliff, above the castle dyke, and may perhaps be late Norm. A most, running down to the main dyke, enclosed the keep and a portion of this outer court. A tower (perhaps on the site of the barracks) was in

dernized) was on the W. side. It ! Lodging:" and the chief habitable buildings were in this court.

The outer ward, or "Castle Green." which is always open to the public. contained a well and chapel, of which latter the foundations alone can be traced. The finest sea-view in or near Scarborough is gained from hence. The visitor should walk quite round the edge of the cliff, which here towers 300 ft. above the breakers of the blackened sea-beach. The shore is covered with fragments of wall and of cliff, which is being gradually undermined by the waves. than 70 acres (it is said-but?) were formerly included within the castle walls. There are now only 19. The view extends S. to Flamborough Head, and N. to the Nab. The coast trends away N.W., and is therefore not so far visible as it is southward.

The old *Church of St. Mary, close beneath the castle, is passed on the rt. as you enter it.

This ch., with its chapels, including that within the castle, was given by Richard I., in 1198, to the Abbey of Citeaux in Burgundy, for the purpose of making 3 days' provision for members of the Cistercian order attending the annual Chapter-general there. The existing ch. consists of the nave of the original building. The choir, along with the tower occupied as a battery by the Roundheads in assailing the castle, were demolished by the guns of the garrison. The upper part of the tower, as it now stands, was rebuilt in 1669. At this time. also, the second N. aisle was added. The W. front, lighted by 3 lancets and a wheel window above, flanked by turrets, is Early English, and was well restored with rest of the building in 1850. The ch. is Trans.-Norm. and E. E.; and was perhaps commenced after the grant of Richard I. to the Cistercians. On the N. side all except the two westernmost piers are Trans.; Leland's time called the "Queen's on the S. side only the two eastern-

The others are more purely E. E.: one on the S. side has 6 detached shafts, banded halfway up, round a central pier. There is a clerestory with single E. E. lights. Vaulting shafts—the terminations of which should be noticed-run up between. The S. aisle is also E. E., with chantries opening from each bay. divided from each other by solid walls. In each there is a sepulchral recess and a piscina in the S. wall, The and an aumbrie in the E. present windows (new in 1850) are Dec., except a large Flamboyant one, a rare instance in England. The ribbed vaults of the chantries are transverse to the nave, and are E. E. The W. end of the nave. between the towers, has clustered vaulting shafts rising quite to the roof, perhaps for the support of a great arch. The chancel is formed out of the central tower, and is necessarily short and shallow. A window of Dec. character is inserted at the E. end. On the S. side is a Dec. chapel. with 2 Dec. recesses (in which stone coffins are placed) in the S. wall, and a very fine large Dec. window. Outside the ch. remark the roofing of the chantries adjoining the S. aisle. It is formed of overhanging slabs of stone, and seems original. The ruins of the chancel are too much weatherworn to show any architectural fea-The eastern termination was square. The upper part of the central tower was rebuilt after the siege.

The view from the ch.-yd. over the town, and across to the S. Cliff, is

very picturesque.

That part of the sea-front of Scarborough called the South Cliff is approached from the town by a broad terrace walk running parallel with the sands, carried over the ravine (in the upper part of which lies the Rly. Terminus) on the lofty Cliff Bridge. The steep alope of the cliff is laid out as a garden, planted with trees, and made accessible by shaded zigzag

walks, as well as by a Vertical Tramcoay laid along the face of the hill, which lowers passengers from the esplanade above, to the sands beneath, or lifts them up the ascent.

A *Spa-house was built in 1698, and destroyed by an earthquake in 1737. The whole of the ground about the springs was so convulsed and broken, that some time before they were again elapsed found. A new house was then built, but this (or a successor) was ruined by the rising of the sea during a violent gale in February, 1836. the following year the "Cliff Bridge Company" commenced the excavations, plantings, and buildings, which have been continued from time to time, until the Spa and Promenade were completed (1858). These improvements were planned by Sir Joseph Paxton. The grounds are very pretty, and afford a most agreeable founging-place at all times. All the sloping face of the cliff, below the Esplanade, has been planted with trees, which grow tolerably well in spite of the sea air. There is, at all events, a thick covert, with masses of ferns here and there as undergrowth. Zigzag paths are cut through the wood, and seats are placed at intervals. Below the wood are terraces with flower-beds; and immediately above the sea is the

Spa Pavilion, a large and showy building, in kiosque style, though of stone, with detached tower, surrounded by colonnades, and containing a Concert Hall, a Theatre, Reading and (poor) Refreshment Rooms. It was designed by Mr. Verity, and built after a fire in 1878.

Within or on the terrace in front of the sea an excellent band plays from 11 to 1 A.M. and from 7 to 9 P.M. Day tickets (6d. each) admit to the Spa Building and its grounds; or visitors may pay 2s. 6d. per week.

The effect of this terrace, crowded

with company, either strolling in the sunshine or brilliantly lighted by gas or electric lamps along the front of the buildings, with the sea breaking close under the balustrade (as it does when the tide is up), and the moon rising over the water, is very singular: such a mixture of "nature and art" is altogether uncommon in England.

The Spa, it should here be said, consists of two springs, differing but slightly. They abound in carbonates and sulphates of lime and magnesia, and are said to be of service in many

dyspeptic cases.

Beneath the Cliff Bridge, in the ravine, is the Aquarium, a sumptuous building, which cost 100,000L, in Moorish, Hindoo, and Persepolitan styles of architecture, devoted to an exhibition of living fishes and marine animals, but chiefly to the purposes of a concert and music-hall; admission, 1s.

The well-kept *Museum (6d. entrance), founded in 1828, stands on a rising ground near to the Cliff Bridge. It contains some interesting antiquities, and a most valuable geological collection arranged by Mr. John Williamson, the first curator of the Institution, who also arranged and chiefly accumulated the collections of British birds, insects and shells. the lower room, the chief object (in a case at the upper end) is a hollowed oak-tree, with the skeleton and all else found in it, discovered in a tumulus at Gristhorpe in 1835. There were three tumuli on Gristhorpe Cliff, a short distance N. of Filey. other two contained only urns and some fragments of bone, and seem to have been opened before. The oak trunk (7 ft. 6 in. by 3 ft. 8 in.) which formed the coffin had probably been split by wedges, and then hollowed. When opened it was full of water. A rude face is carved on the outer lid, above the place of the feet of the originally came is unknown.

Bronze and flint spearheads, flint arrow-heads, a horn, probably the handle of a javelin, and fragments of a bark basket, or dish found in the coffin, are arranged at the head of the skeleton. The body had been wrapped in a hide, and laid on a vegetable substance, which after maceration showed long lanceolated leaves, like mistletoe,—and berries. Portions of these are laid at the feet. The interment was evidently that of some great chieftain.—and, from the entire absence of iron, may perhaps, with the caken coffin, be referred to a very early period. Interments in hollowed oak-trees have since been discovered at Great Driffield and at Beverley; and at at Selby 14 coffins were found, made of oaken trunks separated into two pieces, and scooped out. These were on the site of the old parish ch., and were certainly Christian, -- perhaps late Saxon. They afford, as Mr. Wright suggests, a curious proof of the long continuance of this form of interment in eastern Yorkshire. In the same case are some fine urns from tumuli on the moors near Scarborough; flint spear and arrow-heads; stone hammers; and a graceful necklace of jet, from a British tumulus near Egton. In this room remark also some stone querns (for grinding grain); a cross-bow from Sherwood, interesting in a district which still retains its memories of Robin Hood: and a chair—anciently fixed on Scarborough pier, and used for ducking scolds. In a small adjoining room is a very good aquarium; and upstairs is the geological collection, arranged according to the different formations, and well representing all the local features. gallery above are many jaspers and agates from the coast, enabling the finder to classify and arrange his own treasures. The shattered, cross-legged effigy (temp. Henry III.), outside the museum, was brought from the lower part of the town-but whence it valley above the museum has been of ironstone occur, and thin laminge thickly planted, and affords a pleasant of bad coal, and below all is a coarse walk.

A good modern ch. on the S. Cliff
—St. Martin's-on-the-Hill; G. Bodley, archit.; built at the cost of Miss
M. Craven chiefly—was consecrated
in 1863. The style is early Dec.;
and the pulpit and stained glass—by
Messrs. Morris—deserve mention.
The doors of this ch. are always open.

Walks from Scarborough. These will be chiefly along the coast, N. and S., or to Oliver's Mount.

South from Scarborough the visitor may walk partly along the sands, partly above the cliffs to Filey (about 8 m.) and return by rail (care should be taken by those who choose the sands to ascertain the state of the tide, since serious accidents have occurred from neglecting A long detention at the head of a deep bay, with unscalable cliffs behind you, is sufficiently unpleasant, and the misfortune may not be confined to that). The coast is indented by three distinct bays — Cornelian Bay, Cayton Bay, and Gristhorpe. The sea views are wide and striking. The point called White Nab-the N. end of Cornelian Bay-is colitic, bearing above it carbonaceous sandstone, with wood and plants. Cornelian Bay (a short walk from the Spa, along the sands, or by the cliff) jaspers, moss agates, and cornelians may be found among the pebbles. On the cliff above Cayton Bay is a reservoir for the better supply of The cliffs water to Scarborough. here are of calcareous grit and Oxford clay. Red Cliff, the N. termination of Gristhorpe Bay, is 285 ft. above high water. In Gristhorpe Bay itself, the lowest strata of the cliffs, consisting of various shales and sandstones, contain "vast multitudes of beautiful ferns, zamise, lycopodiacese, and much wood . . . Some layers

[Yorkehire.]

of bad coal, and below all is a coarse irony colite full of shells, and covered in some places by Millepora straminea." — Phillips. The northern extremity of the bay is marked by a lofty insulated rock, detached from the main cliff by the action of the sea. On Gristhorpe Cliff, at the S. end of the bay, are the tumuli (still visible), one of which contained the coffin now in Scarborough museum. (See ante.) The cliff itself is formed chiefly of calcareous grit and Oxford clay. Its height is 280 ft. From it you may descend at once upon Filey, between which place and Gristhorpe projects the long rocky promontory of Filey Brig, the northern end of Filey Bay. N.B. The path along its base is accessible only at low tide. (See Filey, Rtc. 13.) All these bays, it may here be remarked, are formed by the action of the sea on comparatively soft cliff, lving between more solid masses of rock.

North of Scarborough, the sands beyond the castle form a noble promenade, and the view of the Castle Cliff from them is very picturesque. The coast is "for several miles irregular and rugged, but rather low, never rising to so much as 135 ft. above the sea, until we reach Cloughton Wyke." The cliffs so far are of gritstone and shales, with (just before Cloughton) calcareous rock. Cloughton Wyke (Wyke is the Norse or Anglian—it is not always easy to distinguish—vig, a bay or sea inlet) is 41 m. from Scarborough. 2 m. farther is Haiburn Wyke, a narrow wooded glen, through which a stream (on which is a waterfall) descends to the sea. The scene is very picturesque, and deserves a visit. menophyllum Tunbridgense and Asplenium marinum have been found here; but such plants are too apt to disappear after the raids of many fern-hunters. Beyond, again, is the long stretch of Staintondale Cliff. extending from Haiburn Wyke to the

41 m. This, the longest range of high cliff on the Yorkshire coast, is far higher than any S. of it. gradually rises to its N. end (the Peak), where it is 585 ft. above the sea. There is a fine view over the moors, inland; and a magnificent one across the German Ocean, with its white sails and passing steamers. Below much of this cliff is "a remarkable undercliff, caused by an ancient seaward slip of the old cliffs. In this strange scene of confusedly aggregated rocks and underwood very curious views are presented; but few besides zealous geologists care to traverse its labyrinthine paths."-Phil-The cliffs themselves display various beds of sandstone, capped by grey limestones. The sandstones are rich in fossil plants (ferns, zamise, equiseta), and at the foot of the cliff at Blea Wyke, near the N. end of the range, the beds are full of shells. The limestones above contain shells and large belemnites. N. of Blea Wyke, the cliffs change, showing a mass of lias shale, generally capped by gritstone. The shale is gradually wasted by the sea, and the gritstone capping then falls. "The permanent effect of these circumstances is a formidable steepness in the whole range of these dark cliffs, which even at low water are margined by only a narrow belt of sands, or a scar of rugged rock—safe only to those who take heedful note of the tide."-J. P. At Ravenshill, on the Peak, an inscribed stone was found in 1774, which seems to record the erection of a "castrum" by a certain Justinianus. High Peak opens the beautiful "Robin Hood's Bay," described as an excursion from Whitby (see Rtc. 14).

Oliver's Mount (so named from a false tradition that Cromwell was present at the siege of Scarborough Castle, and established himself on this hill—the old name of which was Weaponness) is about 11 m. from the town, and is conspicuous in every

"Old Peak"—a distance of nearly | view of it. The hill (of clay. alternating with sandstone, capped by calcareous grit) is 600 ft. high, of a somewhat oval form, and has a road (about 14 m.) running quite round its summit, the views from which are superb. The finest general view of Scarborough is gained from here; with a vast stretch of sea and coast on either side, ranging from the Peak N. to Flamborough Head S., marked by its white chalk cliffs. extends the moorland towards Whitby; and S.W. stretches away the so - called " Vale of Pickering." bounded S. by the line of the Wolds, and N. by high ground rising towards the moors. The steep escarpments on the N. face of the hills result from the action, in some very remote period, of a sea which filled the Vale of Pickering. These hill-sides were then sea-cliffs. On the N. side of the hill, skirted by the rly., is Seamer Mere, once a considerable lake: but it has been drained, and is now little more than a pond.

EXCURSIONS BY RAIL may be made to Filey, Flamborough Head, and Bridlington (Rte. 13); to Pickering (Rte. 14, in about 12 hr.), where the castle and ch. are worth seeing; or to Malton and Castle Howard. the present route, ante). Steamers run almost daily to Whithy and to Bridlington, affording a good view of

the coast.

To Ayton and Hackness.

A very interesting drive, which will take four or five hours (the distance is about 20 m., but the tourist had better arrange to spend some time at Hackness), is by the old Malton road to Ayton; thence up the Forge Valley to Hackness; and thence back to Scarborough by Scalby. Taking this route, the tourist should remark the fine view of Scarborough, as he climbs the hill, above which is a prospect tower built by Lord Londesborough. On the moors near the

tower are some large tumuli. Ayton (on the rt. bank of the Derwent, which the Malton road crosses here) is a tower (late Edwardian, of no very important architectural character, but picturesque, and worth the sketcher's notice), which, with the manor, was part of the inheritance of the Vescis, and thence came to the Eure or Evers family-one of the most powerful in this part of Yorkshire—in the first half of the 16th cent. The road up Forge Valley turns away at Ayton, keeping the I. bank of the river, here but a small stream. The valley itself, narrow and picturesque, winds between steep wooded hills, and, together with the Hackness Vale, to which it leads, affords by far the most beautiful scenery of this class within reach of Scarborough. There is much ash among the woods, giving a special character to the masses of foliage. The colitic hills on either side are covered with tumuli and British earthworks. At the N. end of the valley, and giving name to it, the monks of Hackness, it is said, established an iron-forge; as their brethren did at There was, however, an Rievaulx. iron - foundry at work here when Hinderwell wrote in 1798; but all traces of it, except heaps of cinders, have disappeared. Passing the Middle Road, which winds away rt., through Raincliff Wood, more open ground is entered, and the hills above the river extend N.E. There is a large British camp on the farthest height seen.

Hackness has a pleasant Inn, the Johnstone Arms, which a tourist might very well make his head-quarters for a day or two. The surrounding country, wild and picturesque, is worth exploration.

The village stands at the junction of the Lowdales Beck with the Derwent; but several smaller valleys

unite here-

(" A nest of sister vales, o'erhung with hills Of varied form and foliage"—

At so Mason has described Hackness in his play of 'Argentile and Curan')—ses forming a scene of extreme repose and beauty, in perfect keeping with the recollections of the place, which, connected as it is with the early years of Christianity in Yorkshire, is of starcely less interesting than Lastingham (Rte. 14).

In the year 680 the Abbess Hilds. died, after a lingering illness, at Whitby. (See for a sketch of the life of Hilda, Whitby, Rte. 14.) In the same year she had completed at Hackness (which place seems to have already belonged to the monastic house at Whitby) a "monastery" or cell, in which she placed certain of the Whitby sisterhood. On the night of the "Mother's" death at Whitby, Begu, afterwards known as St. Bees, then a nun of Hackness, saw her in vision carried to heaven by angels; so that, when the messengers from Whitby arrived in the morning, their tidings were already known. (The story is told at length by Beda, H. E. iv. 23.) The cell at Hackness continued to exist apparently until 869, when it is said to have been plundered and destroyed by the At the Conquest, the Northmen. manor, which had belonged to the great Earl Gospatric, passed to William de Percy. Serlo, the brother of this Lord William, became Prior of Whitby, then a house of Benedictine monks; and in 1088, when that monastery had been plundered and greatly injured by pirates and outlawed men from the forests, Serlo obtained leave from his brother to build a "monastery" at Hackness, as Hilda had done before him. he and his monks remained until somewhat quieter times enabled them to return to Whitby; but a cell attached to the larger monastery existed at Hackness until the Dissolution, when four Benedictines were living in it.

There was, however, a church at

was taken. The earliest portion of the existing ch. is the chancel arch, which is very early Norm.; quite plain, with square abaci. The S. side of the nave is later Norm. The N. has S E. E. piers and arches. There is a fine E. E. arch opening to the tower-also E. E. The chancel itself had been originally E. E., but has now a Perp. E. window. the N. wall is an inscription recording the early history of Hackness. On the S. is a good sculptured mont., by Chantrey, for the wife of G. Johnstone, Esq., d. 1819. Above is a tablet with a long inscription (worth reading) for Lady Margaret Hoby, d. 1613. In the chancel are preserved many fragments of crosses (found from time to time in the ch.-yd., and belonging to St Hilda's monastery) with Latin inscriptions, which appear to commemorate Ædilburga and Hwatburga, successively abbesses of Hackness, and daughters of Aldwulf King of the E. Angles, and nephew of St. Hilda; and Canegyth, Bugge, and Treces, correspondents of St. Boniface. On these fragments are other (apparent) inscriptions in a mysterious character, which bears a strong resemblance to the Ogham of Ireland. (Ogham is probably of very ancient origin, but continued occasionally in use in post-Christian times.) These have not been interpreted.

Outside the ch. remark the square buttress-turret, on the S.W. side of the tower, carrying a staircase; and the windows in the top stage of the tower (two lancets, under a circ. The tower is now capped by a spire. The ch.-yd., surrounded by fine trees, is kept with extreme care.

Adjoining the ch. is *Hackness Park* (Sir Harcourt Johnstone, Bart.). The inder the hills, perhaps induced the house was built towards the end of the last cent. The road winds through the park—very picturesque, with and their cattle might take refuge

Hackness when the Domesday survey | much broken ground, low, woodcovered hills, and narrow glens opening rt. and l. to high ground at Suffield-and then descends towards Scalby, affording a fine view of Scar-Scalby Church, which borough. stands pleasantly among wooded hills, is for the most part E. E., and has been restored. The N. aisle has been entirely rebuilt. The E. E. chancel arch deserves notice. ch. was given (circ. 1150) by Eustace Fitz-John to the Prior of Bridlington. in whose hands it remained till the Dissolution. Scalby is 3 m. from Scarborough.

> [Troutedale is a long, narrow valley, a little S.W. of Hackness. The "Black Beck" vale opens from it, and here is Langdale Howe, a conical hill, which has been a British strong-Long, narrow valleys, ali wooded, and all beautiful, run up into the high moors at the back of Hackness. Each has its own streamlet—a tributary of the young Derwent. The moors are covered with tumuli (here often called "houses,"-A.S., a high mound), dykes, pits, and intrenchments, the most important of which are marked in the Ord-nance Map. It is difficult to find any system in the intrenchments, which cross and recross each other curiously. But the longest and most remarkable are (like Givendale Dyke and Scamridge Dvke) near the first ascent of the hills from the vale of Pickering, and must, together, have been good defences against attacks from below. A line of very ancient villages runs along at the foot of these hills, as at the foot of the Wolds on the opposite side of the vale, and intrenchments are found at the entrances of the Wold valleys, in much the same situations as on the northern hills. Water-springs, rising under the hills, perhaps induced the first settlements; and on the approach of danger the inhabitants

behind the intrenchments. For fishing in the Derwent and its tributaries, application must be made to the secretary of the "Derwent Anglers' Club." The Derwent is a fine trout stream.]

[Instead of turning up the Forge Valley at Ayton, the drive may be continued along the Malton road to Hutton Buscel (6 m. from Scarborough—there is a monument in the church, which is uninteresting, for Richard Osbaldeston, Bishop successively of Carlisle and London, 1747-1764), and Wykeham (1 m. farther), where was a priory of Cistercian nuns, founded circ. 1153, by Payne de Wykeham. It was not wealthy, and no remains exist. Wykeham Park, with the site of the priory, is the residence of the Dowr. Lady Downe, and a modern church (by Butterfield) has been built here. Adjoining it is the tower of an older church, apparently E. E. This ch. was taken down when the new one was built: but a tall cross marks the site of the altar. Beyond again, 11 m., is Brompton, interesting as the possible birthplace of John of Brompton, the chronicler, a Benedictine of Whitby, and afterwards Abbot of Jervaulx. In Brompton ch. the poet Wordsworth was married in 1802.

Castle Hill here is said to mark the site of a "villa" of the Northumbrian kings.]

ROUTE 13.

SCARBOROUGH TO FILEY, FLAMBO-ROUGH HEAD, AND BRIDLINGTON.

The Scarborough and Hull branch of the North-Eastern Railway runs by Filey and Bridlington. There are 8 trains daily. The time from Scarborough to Filey is about 25 min.; to Bridlington about 1 hr.

From Scarborough to

Seamer Junction Stat., the rly. is identical with that to Malton. (Rtc. 12.)

The village of Seamer, called by Leland a "great uplandische toune, was a lordship of the Percys (Wm. de Percy, at the Conquest, is said to have married the Saxon heiress of Seamer, daughter of the Earl Gospatric), who had a large manorhouse—now a shapeless mass of ruins -near the ch. There was an important settlement at Seamer in the Saxon times. Some very beautiful personal ornaments of gold and silver, of that period, were found here in a quarry in 1857. Several earthworks will be observed on the moor. Norm. work remains in the Church, and not only the Sanctus

bell-cot, but the bell itself. Seamer diluvium. Attached to it, on the S., is named from the great lake or mere have been built on the top of the cliff a handsome crescent and numer-mount.

Branch Railway to Pickering and Whitby (Route 14), the direct line from Scarborough to Whitby.

14 m. rt. of Cayton Stat. is Folkton. Nose under the Wolds-with a small he. containing Norm. and Trans.clorm. portions. Tombstones in the ch.-yd. record that the family of Mosey has buried its dead here for 500 years, and that of Ombler for 700 years. Folkton is one of a line of very ancient settlements, lying along the skirts of the Wolds. These are covered here with intrenchments, tumuli, and "howes"—which, however, the progress of the plough is rapidly obliterating. (For a general notice of the Wolds see Rte. 11.) The height called Folkton Brow commands a grand view over the valley; it forms the object of frequent drives from Filey.

Between Folkton and the rly. runs (or rather stagnates) the "New Hertford river," a broad trench for draining the "Carrs," as the low, marshy ground of the Vale of Pickering is called. This trench joins the Derwent at Haybridge; and from that point nearly to Yedingham the Derwent itself has been widened (and its old bed altered), so as to receive the drainage.

8 m. Filey stat. Omnibus to the town, ½ m.

Filoy (Inns: Crescent Hotel, on the Cliff overlooking the bay (board and lodging in public room, 9s. a day), very comfortable and reasonable; P. H. 2nd class, Foord's Hotel, Queenstreet. — Pop. 4189) consists of a commonplace fishing-village, of small houses and second-rate shops, on the top and alones of a crumbling cliff of

cliff a handsome crescent and numerous streets of lodging-houses-forming the quiet watering-place, airy and healthy, overlooking the sea, and commanding a fine view across the bay; bounded on the l. by the rock promontory and reef of Filey Brig, and on the rt. by the chalk cliffs of Flamborough Head. The ground in front of the crescent is laid out as a shrubbery and garden, with terrace-walks leading down to the broad smooth sands, extending 8 or 4 miles, dotted over with bathing-machines. As you gaze upon this pleasing prospect the ear is caught by the mysterious tolling of a bell. It comes from the Bell Buoy, set at the end of Filey Brig, moved by the water to warn off vessels from that dangerous spot. At the foot of the cliff a Bath House and reading-room, and several neat villas have been built. There is also a spa

From 25 to 30 fishing-boats are kept here, and give employment to a considerable number of the men and boys. There is a small pier, but the inhabitants live in hope of a grant from Parliament towards the creation of a harbour of refuge.

On the N. side of the village a wooded ravine, accessible by shady walks, leads down to the shore. At its upper end it is crossed by an iron bridge conducting to

The Old Cherch, chiefly Trans. Norm. and E. E., consisting of nave, chancel, and transepts, surmounted by a low tower. It has little that is remarkable, except a semi-circular arched N. doorway (Trans. Norm.) of 4 orders of mouldings, and a rude female effigy in the S. wall within. It has no W. entrance.

street.—Pop. 4189) consists of a Church (St. John's) near the stat., houses and second-rate shops, on the top and alopes of a crumbling cliff of worship. Post Office is in the main

place, free from the crowd, glitter, and excitement of Scarborough, resorted to chiefly by families in search of health. Many pleasant walks and

longer

Excursions may be made from it. Post-horses and carriages are supplied from the Crescent Hotel, and there are numerous Flys to drive along the sands, or to Hunmanby, Reighton, and Scarborough, the last a pleasant drive of 8 miles, commanding views unseen from the Rly.

Railways to Scarborough (8 m.) (Rte. 13) and York. To Bridlington and Hull-by Hunmanby-and Marton (the stat. for Flamborough, 2 m.

distant), see below.

Filey may be the "well-harboured Bay," which Ptolemy places N. of the Ocellum Promontorium (Flamborough Head). The Romans may have had a station here; and the 4 stones, with a hole in the middle of each, now in the Crescent Gardens, dug up on the cliff above Filey Brig, may have been the supports of a beacon.

Filey Brig is a promontory of limestones, colite, coralline, and calcareous grit, projecting in succession from beneath the diluvium, which lines the bay, at first in the shape of a rocky cliff, but prolonged into a reef raised only a little above the surface of the sea at low water. It stretches out from the shore more than a mile. and is reached by traversing a mile of sands. It is a rough walk over the denuded surface of rock, as it is fissured by wide cracks, intersected by high steps, obstructed by huge detached blocks, and crossed by channels. It passes at first under shelter of the cliff and then upon the open reef, from the end of which the view opens up towards Scarborough.

The walk should be commenced when the tide is going out, and should not be prolonged so as to incur and E. E. nave piers. The windows N. risk of being overtaken by the return- are early Dec.; S. flowing.

Filey is a quiet watering-ling waters, which cover it at high tide. A very narrow path runs along the N. side of the cliff, which has here been excavated into a succession of picturesque caves by the waves, the strata beyond their reach projecting like a roof. Explorers should look to the state of the tide, especially at springs, and should be wary in stormy A tablet attached to the weather. rock records the fate of Mr. Paget, a Nottingham gentleman, and his wife, who were washed off by a wave of unusual size 11 hour before low water. Oct. 1873, caused by an unusual heavy ground-swell.

After a storm the shore is often strewn with molluscous animals and other products of the sea; corallines, fucoids, radiata, may be found in the

rocky pools and cavities.

It is possible to walk along the top of the cliffs, but not without trespassing, for there are no paths, and constant interruptions are caused by the slipping down of the loose clay. underwashed by land-springs.

S. of Filey the over-sand walk or drive may be prolonged for 5 m., passing Specton Cliffs, abounding in fossils, as far as the inaccessible chalk cliffs beyond. Those of Flamborough Head are constantly washed by the sea, road

and path alike ceasing.

The low diluvial cliffs which stretch away from Filey to Specton are not picturesque. At Specton the chalk of the Flamborough promontory turns inland; and from beneath it rise cliffs of gravel and dark blue clay, to a height of 200 ft. They abound in fossils: shells, ammonites, crioceratites, crustacea, and belemnites.

Filey to Bridlington.—Rail.

91 m. Hunmanby Stat. The Church (in the village, 11 m. from the stat.) has a Norm, tower and chancel arch

Percy, Constable, Osbaldeston, and others—were painted above the arches in 1869 by W. A. Tissen-Amhurst, Esq. The roof is open. The church was restored (1844) chiefly by the care of the late Admiral Mitford of Hunmanby Hall, a plain mansion of Q. Anne's time adjoining. manby was long the living and the residence of Archdn. Wrangham.

At Reighton, 2 m., is a very early Norm. ch. paved with pebbles from

the sea-shore.

Passing stations at Specton (where flint implements and weapons have been found in great numbers) and Bempton, we reach (about 30 min. from Filey)

Marton Stat., 2 m. from Flamborough village, and 2 m. more from Flamborough Head. Conveyances uncertain, must be bespoken beforehand.

Between Marton and the village of Flamborough the road crosses the Danes' Dyke, a strong double entrenchment, with a ditch (towards the S. end, advantage has been taken of a deep natural valley) and curious projections or "breastworks." crosses the promontory irregularly from one side to the other, converting it into a very secure camp. lands thus defended (though few perhaps on so large a scale—the trench here is 23 m. long) are found on many parts of the English and Scottish coasts once frequented by the Northmen (such as Treryn Dinas, near the Land's End, Bream Down in Somersetshire, and Castle Feather in Wigtonshire), but there is nothing whatever to prove that they are not of far more ancient date than the ravages of the Danes, whose name is frequently connected with them, and who may have availed themselves of strongholds already The headland within the

of the old lords of the manor-Gant, I terminations of the dvke many chalk fossils - spongiade and crinoids may be collected.

> (Col. Lane Fox suggests that this remarkable earthwork was the base of a great system of defensive "dvkes." raised by invaders arriving by sea, and gradually pushing themselves The lines of earthwork inland. crossing the Wolds at different points he regards as successive points of defence, thrown up as the conquering race advanced into the country, which was thus secured in the rear. There are lines of entrenchment at Argam, 5 m. N.W. of Bridlington. which may have been the second station, and thence the invaders passed into the Wolds.)

Close to the dyke, in a commanding position, Mrs. Damer has a handsome residence.

The long straggling fishing-village of Flamborough (Inns are little more than public-houses, where carriages and flys put up) contains nothing of interest but its Church (dedicated to St. Oswald, like many others on the coast; he was the patron of Northumbrian fishermen). It is Dec., and was restored throughout in 1868, and the chancel rebuilt. It belonged to the Priory of Bridling-There is a beautiful screen and roodloft of 16th cent., of carved oak, once richly painted and gilt. loft has been removed to W. end. On the N. side of the altar an inscribed brass for Sir Marmaduke Constable, who fought in France under Edw. IV. and Hen. VII., and at the age of 70 was present, "with his sonnes, brothers, sarvants, and kynsmenne," at Flodden, called " Brankiston feld" in his epitaph, which is worth reading. It ends, "For as ve see him here he lieth under this stone,"—not true at present. Flamborough Dyke is sometimes inscription has been removed from called "Little Denmark." At the the tomb, which is in an adjoining

Constable had been settled here from a very early period. Near the ch. is the ruin of the so-called "Danish tower"—square and vaulted, but with nothing to mark its precise age. There are mounds of ancient foundations about it. It possibly formed part of the Constables' manor-house. Flamborough was the birthplace of Sir John Puckering,—who died Lord Chancellor in 1596.

Passing beyond the village, the tourist will find, at the Inns near the cliff, guides ready to conduct him to the Cares on the N. side of the promontory. When the tide is up, a boat will convev him out of the narrow cleft in the chalk or cove, whose sides are so steep that the Lifeboat is hauled up and let down by a windlass. It is called the "North Landing-place" of the headland (a bay on the opposite side of the promontory is called the S. Landing; "without these landingplaces, the fishermen of Flamborough would have no access to the sea except by ladders down the preciing. They are formed by the action of the sea on the chalk rocks. The finest is Robin Luth's Hole, nearly 50 feet high, and approached by a very narrow entrance on the land side. Robin Lyth, says tradition, was a smuggler, who made this cavern his stronghold. The Kirk Hole extends, according to the lovers of the marvellous, quite under Flamborough church.

The walk may be continued, from the N. Landing, along the cliffs, to the northern extremity of the Danes' Dvke, where the cliffs are 292 ft. high, and about 1 m. farther, to the highest point of the chalk cliffs,here 436 ft. above high water. view from this height is very grand, from the hills above stretching Robin Hood's Bay, across the moorland, to the colitic hills, and then

chapel. A branch of the house of | (Close beyond, the chalk turns inland towards Specton and the Wolds, attaining its greatest height (in York-shire) at Wilton Beacon—805 ft. above the sea.)

> At the N. Landing-place boats may be hired for passing round Flamborough Head—or you may walk along the cliffs, grand and rugged, and opening here and there into small bays, with spires of rock standing forward, worn by sea and weather.

About 400 yards from the edge of the promontory, at the distance of 11 m. E. of the village, and at a height of 250 ft. above the sea, is the Lighthouse, of brick, 80 ft. high, built in 1806, since which time it has been the means of preserving many From hundred vessels. 1770 to 1806, 174 shipwrecks occurred here, but between 1806 and 1813 there was not one within the range of the light. It is a revolving light, exhibiting every two minutes one of its three faces, one of them being red; and is visible in clear weather at a distance of 30 miles. A more ancient beacon stands about 700 yards from the present one, but has fallen to decay. You may climb to the outer gallery of the lighthouse, from whence the view is of course wide, but hardly wider than it is from the extreme point of the headland beyond it.

Flamborough Head, the bold and striking promontory which forms so marked a feature on the map of England, is the extreme eastern termination of the chalk in the island, across which this formation extends masses of greater or less width, till it terminates S.W. in the cliffs of Beer in Devonshire. Flamborough is possibly the "Ocellum Promontorium "of Ptolemy-although this honour has also been claimed for Spurn Point, and it must be remembered that the whole along the S. sweep of the Wolds. of this coast has undergone, and is

undergoing, considerable The present name, Flamborough, perhaps indicates that a great beacon was anciently lighted here within the "burgh" formed by the Danes' Dyke, to guide passing vessels. The seaview from the point of the headland is superb, extending to the "Peak." S. of Whithy, and far along the low coast of Holderness. The cliffs are broken into caverns, arches, and single spires of rock,—the most remarkable of which are "the Matron," and the "King and Queen." On the ledges sit myriads of sea fowl-gulls, auks, cormorants, petrels, grebes --- which have increased rapidly in numbers since the passing of the Act of Parliament that protects them. The birds choose the N. side of the cliff to breed on by preference, because it is that best sheltered from the sun's ravs. "During the season of incubation, boys are" (were formerly) "let down the face of the precipice by ropes, and gather the eggs in bushels for the use of the sugar-houses at Hull, and for domestic purposes."-W. White. Daws, rooks, rock pigeons, and ravens occasionally breed among the sea-birds.

It was off Flamborough Head that the young Earl of Carrick (afterwards James I. of Scotland), son of King Robert III., was taken (1405—King Robert died in the same year) by an armed merchantman belonging to the port of Wye,—in defiance of the existing truce between England and Scotland. The prince was on his way to France, and was detained by Hen. IV. and Hen. V.—only returning to Scotland as king in 1424.

Close off the headland a sea-action was fought, 1779, between two English ships and the pirate Paul Jones, who, with a squadron consisting of the Bonhomme Richard and Alliance, each of 40 guns, the Pallas 32 guns, and the Vengeance armed brig, had spread consternation along our shores,

change. | driving the coasters into port in such numbers, that Bridlington harbour could not hold all which sought shelter in it, and many were glad to obtain security by being chained to the outside of the pier. On Sept. 23rd Paul Jones gave chase to a valuable fleet of merchantmen from the Baltic, sailing under convoy of the Scrapis of 44 guns, Captain Pierson, and the Countess of Scarborough, 22 guns, Captain Percy. The British captains did not hesitate to engage the superior force of the enemy, and by placing themselves between him and the fleet secured for it a safe re-The action. treat into Scarborough. which lasted 2 hours, was fought by moonlight, in full view of the cliffs, which were crowded by spec-The British were at last tators. compelled to strike, but the boldness of their resistance may be best appreciated by the fact that the Bonhomme Richard alone lost 300 men in killed and wounded, and, from the injury she had received, went down the day after the action. with many of the wounded on board. This sea-fight is admirably described by Cooper in 'The Pilot.'

At low water the visitor should scramble down to the beach, "rugged with water-worn lumps of chalk," and most picturesquely broken and hollowed by the action of the sea. It is then possible to walk quite round the "Matron" and the "King and Queen."

It is possible to walk to Bridlington (between 6 and 7 m.) from the village of Flamborough, along the cliff—a pleasant walk. Or you may return to Marton; the station beyond which is

Bridlington Stat., now generally called "Burlington." The great priory ch. is seen rt. (The stat. is about half-way between the old town of Bridlington and Bridlington Quay, the present watering-place, to which an omnibus runs.)

Bridlington Quay (Inns: the Alex- | which she had purchased for her andra Hotel, large and well situated, facing the sea, I m. from the town; in front are gardens; board and lodging in public room, 7s. a day;—the Britannia, in the town, close to the piers).

Bridlington (Pop. 1109) is a commercial town, with a small harbour, originally the landing-place belonging to the great Augustinian Priory of Bridlington, founded in the reign of Henry I. Bridlington Bay, a roadstead, sheltered to the N. by Flamborough Head, affords the best anchorage on the coast, although that is nowhere too good. Eastward, the Smithwick Sand, only just covered when the tide is out, forms a natural breakwater. N. of Bridlington, the chalk rises to form Flamborough Head. S. is the low, flat coast of Holderness. As a watering-place it must rank as second class, though thronged in Aug. and Sept. by provincial visitors, chiefly from Hullchildren in countless number. sands, fine and dry, afford pleasant bathing, and the long Sea wall or terrace is an agreeable promenade.

A long Pier extends on either side of the harbour; that on the S. built in 1849, at a cost of 40,000l. The N. pier affords an agreeable promenade, and commands a fine view of Flamborough The harbour is accessible Head. only at high water; at other times steamers lie off, and receive passengers There is suite of Public in boats. Rooms (cost 8000l.) close by, with a fine view from the roof.

Terraces facing the sea, and streets of lodging-houses extend from the harbour beyond the Alexandra Hotel. 400 or 500 sail of vessels, bound for the N. and detained by contrary winds, may often be seen in the Bay of Bridlington, which is the only moderately safe harbour on this coast.

Oneen Henrietta Maria landed at Bridlington Feb. 20th, 1643, with

husband in Holland, by the sale of the Crown jewels. The admiral of the Parliament, Batten, who had sailed out of Newcastle on a cruise to intercept her, finding that she had eluded his vigilance, entered the bay with two of his ships, and poured into the town a heavy cannonade, most ungallantly directing the shot especially against the house where the queen lay, so that she was driven out of it at night half naked, and obliged to seek shelter in a ditch. "while the balls sung merrily overhead, and a sergeant was killed not 20 paces off from her." Batten was compelled to sheer off by the Dutch Admiral Tromp, who had escorted the queen from Helvoetsluys. The queen reached York on the 8th of March, under an escort from the army of the Earl of Newcastle, carrying with her arms for 10,000 men, with 30 brass and two iron cannon. (After the queen escaped from the ditch she took shelter at Bounton Hall, about 2 m.W. from Bridlington.)

During the season, steamers frequently make day's excursions to Scarborough and Whitby, and occasionally to Hornsea.

Far more interesting than anything at Bridlington Quay, and ranking deservedly among the more important architectural remains in Yorkshire, is the Priory Church, now the parish ch. of the old town, which grew up about the house of the Augustinians, about 1 m. from the quay, but now connected with it by a continuous street.

*Bridlington Priory was founded for Augustinian canons by Walter de Gant, early in the reign of Henry Gifts of manors and of churches were liberally bestowed on the new foundation by the great lords of Yorkshire; and Bridlington become one of the wealthiest religious houses in the the supplies of arms and ammunition county. Its position near the sea

from pirates and other enemies; and by King John to the canons. Richard IL. in 1388 (when the French were active on our coasts), licensed the canons to surround their house with walls and fortifications. The Popes were not less ready to assist the Augustinians in their troubles. When, about 1260, the Archdeacon of Richmond arrived at their Priory on a visitation, claiming food and shelter for himself, his attendants, 97 horses, 20 dogs, and 3 hawks,—so that he consumed more provisions "hora brevi" than would have maintained the house for a long time,-Innocent III., to whom the canons complained, ordered that he should henceforth travel with no more than the 7 horses permitted by the Council of Lateran. An attempt was made to procure the canonization of John of Bridlington, who died Prior in 1379, whose life was one of unusual excellence; and although it does not appear that the attempt was successful, his relics were removed to a shrine at the back of the high altar, and he was known as St. John of Bridlington. (A feast-day was moreover assigned to him in the calendar.) The last Prior, William Wode, was hanged at Tyburn in 1537, for his share in the "Pilgrimage of Grace."

The quiet precincts of the Priory, now turned into a garden, are entered through a picturesque Gothic gatehouse, called the "Bayle Gate"—the only relic of the defences erected temp. Rich. II. The chamber in the upper part was that in which the temporal jurisdiction of the prior was exercised; and on the Dissolution the Bayle Gate passed with the manor, which was bought by the town, and thus this upper chamber became the Town Half. The cells below, called the Kidcote, served as a prison. Three Bs, the ancient arms of the Priory, appear on a shield of

rendered the Priory liable to attacks a fair was held, originally granted

The existing Church of St. Mary is but the grand nave of a very grand Cross church, of which the chancel was pulled down at the Dissolution, weakening thereby the support of the central tower, which, in falling, destroyed the transepts. At the beginning of the 19th cent. even this fragment was a ruin, unroofed and unused. Judicions repairs and a careful renovation, conducted by Sir Gilbert Scott, at a liberal outlay of 17,000l., in 1857, restored this noble edifice in part to its ancient splendour. The W. end consists of a fine window. 55 ft. high, flanked by two towers; that on S.W. Perp. as high as the roof, finished with Dec. upper story and pinnacles from Scott's design: that on the N.W. is of earlier date. with semicircular arched doorway. and is unfinished.

The Nave, 240 ft. long and 80 ft. high (the ch. when perfect was 360 ft. long), consists of 10 bays, resting on piers which on the N. side are E. Eng., those on S. are later Dec., while 3 on S.W. side, along with the windows above, are Perp. On the destruction of the chancel, what is now the E. wall of the ch. was built up with its fragments, as were the eastern The present eastern aisle walls. window (of early Dec. character) is an insertion of Scott's; who also designed the very good roof. window, and the great W. window, have been filled with stained glass by Wailes. The larger piers at the E. end were those of the central tower.

On the S. side, the main eastern piers and arches are very fine early Dec.; the three western seem to be Perp. casings of the original Dec. work, which is untouched in the archmouldings above. The triforium and arms over the gate. In the space clerestory are of somewhat unusual between this gate and the church character. An inner plane of tracery

rises as high as the transom of the I driven on the beach and sunk within large window, and forms the triforium the sight and hearing of a crowd of passage; so that the clerestory and triforium are in effect united—as in the choir of York minster.

In the N. aisle the windows are elegant lancets. The corbel heads of the hood-mouldings, and the sculpture laid into the hollow between the shafts, deserve special notice. Against the E. end of the aigle is laid an altar-slab of very unusual length.

The font, of dark marble, full of madrepores, seems early Dec. It is

circ. on a round shaft.

At the W. end of the S. nave aiale is a most remarkable coffin-lid of dark marble. Below are carved the fox and the crane, with a vase between them; and a cat with formidable Then a building with circ. and pointed arches, and above, two fighting monsters with dragons' tails. It is a curious specimen of Romanesque sculpture, perhaps of the 12th cent.; and had been appropriated as the tombstone of some modern celebrity, who is now happily turned upside down, and consigned to oblivion. Against the S. wall (near the S.W. door) is an iron "joug," or collar, for punishment.

Passing outside the ch., remark the N. porch, very fine E. Eng. the details, ornaments, and leafage, deserve careful attention. The capitals of the inner portal shafts (E. side) display a king, queen, and bishop (Edward L., Eleanor, and Archbp. John Romanus?); and over the portal is a niche for a figure.

In the ch.-yd. is an obelisk raised over a single grave, in which the bodies of 43 sailors and 3 of their captains were interred after the great storm of Feb. 10, 1871. These bodies alone were recovered out of the crews of 23 vessels, which were the aisles). The architect of the

powerless spectators.

William Kent, the landscape gardener, was born at Bridlington in 1685: died 1748. His real name was Cant. "Mahomet," said Walpole, "imagined an Elysium, but Kent created many." - Richard Boyle, of Londesborough, son of Richard Earl of Cork, was in 1664 created Earl of Bridlington.

Excursions. — a. To Flamborough Head 6 m. Caves and Lighthouse. See Marton Stat. ante. It is a walk of 6 or 7 m. to F. Head along the top of the cliffs from B. Quay.

At Sewerby, 2 m. N. of Bridlington Quay (the walk along the cliff is pleasant), is a modern (Norm.) ch., built, at a cost of 4000L, by Yarburgh Greeme, Esq.

An interesting Excursion is to be made inland from Bridlington to Rudstone-on-the-Wolds, about 5 m. distant, worth visiting for the sake of its ch. and a rude stone monument adjoining. The road from Bridlington lies by Boynton Hall, a large brick mansion (Sir C. Strickland), in which Queen Henrietta Maria found refuge when bombarded in Bridlington by the Roundhead Adm. Batten. A portrait of her by Jansens, still in the Hall, was a gift from her to its owner. The Church of Rudstone, restored in 1861, has a Norm. tower (the upper windows are restorations) with a good Norm. arch opening into the nave, and a small shuttered window above it; an early Dec. (circ. 1280) chancel, and a later (circ. 1330) nave. aisle windows (Dec.) are facsimiles of The font, curiously the originals. dispered, is Norm. The modern stained glass is by Capronnier (in the chancel), and by Hodgson of York (in

restoration was Fowler Jones, under whose direction the chancel was (in 1869) elaborately decorated with flowing patterns, inscriptions, the emblems of our Lord's passion, and those of the 4 Evangelists. The reredos is of Ancaster stone, having panels filled with Minton's tiles. The ch. was restored as a memorial to Matilda Bosvill.

The Stone, which no doubt gave name to the parish (Rodestan in Domesday), adjoins the N.E. end of the chancel. Its height is 24 ft.; breadth, 5 ft. 10 in.; thickness, 2 ft. 3 in.; weight, 46 tons. Its depth underground, as tested by Sir W. Strickland, is equal to the height above. "The stone is a fine-grained grit, such as might easily be obtained on the northerly moorlands, about Cloughton beyond Scarborough, to which ancient British settlement a road led from Rudstone by Burton Fleming and Staxton."—Phillips. It is probably a Celtic menhir, and is at any rate one of the largest "standing stones" in Great Britain. (Little Rudstone is a village on the Wolds about 4 m. S.; and near Drewton (adjoining S. Cave, a little N. of the Humber) is the name of Rudstone Walk, apparently marking the line of an ancient road.) A Roman road, pointing in the direction of Filey, has been traced near Rudstone; and E. of the ch. are many pits, the supposed foundations of a British village. The dreary Wolds in this neighbourhood (for a general account see Rte. 11) are covered with entrenchments and "houes," of uncertain date and cha-One of the principal "Gypracter. seys" (the g is hard), as the variable and intermittent streams which appear on the surface of the chalk valleys are called, runs by Rudstone to the sea at Bridlington. resemble the Kentish "nailbournes" (also in the chalk), bursting forth with violence after wet seasons, and sometimes quite dry for months together.

Adjoining Rudstone is Thorpe Hall (Hon. Mrs. Bosvile). By making a round of a few miles, Burton Agnes (Rte. 9) may be visited in the drive back to Bridlington. Between the villages of Wold Newton and North Burton, and close to one of the "gypsey" streams, is a remarkable barrow called Willey-hous, which was partly excavated in 1857, but without result.

ROUTE 14.

YORK TO WHITBY, BY MALTON AND PICKERING.

RAIL.—The distance is 60½ m. The quickest trains perform the journey in 2½ hrs.

From York to Rallington Junct. (26 m.) the line is the same as that from York to Scarborough. (Rtc. 12.) At this point the Whitby line turns off N.; and crossing the Derwent (here a very small stream) not far from its junct. with the Rye, reaches

332 m. Marishes Road Stat. The country here is dreary and uninteresting.

[3 m. rt. is Thornton Church, in which is an effigy, said to be that of Sir Richard Cholmley, called "the Great Black Knight of the North," from his stature and complexion. He died in

1578, at Roxby Castle, not far from Caps, as are the transept arches (the Thornton, built by his father, Sir Roger, about 1520. Only foundations remain.]

caps, as are the transept arches (the caps of that N. have grotesque and hideous heads at the angles). In the S. aisle a large stoup remains; and in

3 m. farther we reach

37 m. Pickering Junct. Stat. (Pop. 5199), where the ch. and castle are worth a visit. The rly, passes between the castle and the Pickering Beck, which flows S. to join the Derwent. (Inn: the Black Swan, homely but clean—the keys of the castle are kept at the Bay Horse.) A railway connects Pickering with Helmsley (Duncombe Park and Rievaulx Abbey) by Kirkby Moorside and Sinnington, joining the line between Thirsk and Malton. (Rte. 18A.)

Railway from Pickering to Scarborough by Seamer Junct. (Route 12.)

The small town of Pickering, although no doubt a very ancient settlement (it was founded, says tradition, by a British king, Perdurus, who lost his ring in the river, and had it restored to him by a pike), has derived all its importance from its castle, which, situated at the entrance of the hill country, defended the approaches to that, and also commanded great part of the Vale of Pickering, a level district extending quite to the sex between the oolitic (northern) hills and the Wolds; and for some distance W. of the town. The district called the Lythe of Pickering is nearly conterminous with the vale. castle and town, with a great part of the Lythe, belong to the Duchy of Lancaster.

St. Peter's *Church, restored 1861 and 79, and partly rebuilt, is interesting, with a Trans.-Norm. tower, having a spire and additions of the Dec. period (14th cent.). The nave has (N. side) Norman pillars and arches with plain caps. On the S. side the piers are Trans., with leafed

caps of that N. have grotesque and hideous heads at the angles). In the S. aisle a large stoup remains; and in the W. end is a Norman font. The windows have flowing tracery; and the square-headed clerestory lights seem also Dec. The chancel is Dec. with modern glass, except some old in the E. window. Remark the sculpture (fighting dragons) on the capitals of the sedilla shafts. In the chancel are placed two fine effigies-a cross-legged knight, temp. Edward I. (removed from the N. aisle of the nave, where it was seen by Camden), in mail, with plates at the knees and elbows. The arms on the shield and surcoat are those of Bruce-which family had, says Leland, "a manorplace here called Bruce's Hall." Near this is a completely mutilated effigy, temp. Rich. II.; and opposite, those of a knight and lady, of the same reign. The knight has a chapel de fer with wreath, a collar of SS. lady wears the sleeveless "cote hardi." with rich mantle, and a narrower collar of SS. than her husband. Her hair is gathered under a jewelled caul. Probably these are effigies of some occupants of the castle under the Crown. In the church is buried William Marshall, born 1745, at Sinnington, W. of Pickering, died 1818. He was one of the most active agriculturists of his time, and published a 'Survey of the Rural Economy of England,' in 12 octavos.

Pickering *Castle, which stands on high ground N. of the town, was in the hands of the Crown temp. Henry III., when Lord Dacre was made Castellan. It was afterwards given to Edmund, son of Henry III., from whom it passed to his son, the great Earl of Lancaster, beheaded at Pontefract. (See Rte. 28.) The Earl's forfeited estates were restored to his heirs; and the castle and manor have since been attached to the Duchy of Lancaster. Henry of

Lancaster after landing (1399) at Ravenspurn (see Rte. 6) came at once to this castle, which the king had seized. It was immediately surrendered to him; and Richard II. was detained as a prisoner in this Lancastrian stronghold before his removal to Pontefract. The castle was besieged and ruined during the civil war, when a large breach was made in the W. side of it.

Pickering Castle "hath a pleasant seat," and commands a superb view over the richly-wooded country stretching away W. and S. There are fine sycamores and ash-trees about the castle itself, especially on the E. side. On the W. it overhangs the Pickering brook. A strong wall, with towers at intervals, went round the castle, adapting itself to the form of the hill. Cross walls divided the whole area into 3 courts; and where these walls met is the keep. Both the outer wall and the keep were surrounded by a deep fosse. Left of the main entrance is the Mill Tower. with a staircase rising to a small watch-turret. The view from this tower is very beantiful. The remains of a strong wall, of a fosse in front of it (carried to the outer wall from the fosse of the keep), and of a square tower commanding the inner portal, are crossed in passing to the inner court, where is a small E. E. chapel, now desecrated. Beyond it, in the outer wall, is a late Norman portal, blocked up. The tower next to this (on the outer wall) is the "Devil's Tower," well built, and showing, on the inner front, doorways opening to a passage on the top of the wall. Beyond again (but in the outer court) is Rosamund's Tower (the name is not of uncommon occurrence in earlier castles), the shell of which, 3 stories high, is nearly perfect. All these towers seem Edwardian (Edward I.), but there is little architectural detail, and the shoulder arch, which occurs in the portals, was in use for a very

were four towers in the outer court. and four (the keep being one) in the Many of these have been utterly ruined. The keep, on a lofty mound, has been multangular; but only a few arrow-slits remain its ruined walls. The most picturesque bits for the sketcher are on the E. side, where the keep fosse is filled with trees, and where the outer towers group not badly. Outside the castle there is a striking view of Rosamund's tower, with large ashtrees rising beside it. At the foot of the Devil's Tower is an arched sallyport, opening to the fosse.

Lastingham (Pop. 1478. It was 3748 in 1871), a place of great interest to the historical antiquary on account of its old Church (Rte. 18A.), is 7 m. from Pickering. The road runs along the slopes and under the "nabs" of the calcareous hills (see post). The pedestrian may arrange to walk from Lastingham up Rosedale, where (at the village) is a respectable Inn, and thence across the high moors to Egton and Grosmont, where he will join the Whitby rly.—See for this walk, Excursion from Whitby. The views are very fine.

[At Thornton-le-Dale, 2 m. S. E. from Pickering, is a grammar-school of some note, founded by Eliz. Viscountess Lumley, in 1657. Thornton Hall is the seat of the Rev. J. R. Hill, who holds Pickering Castle under the Crown.

The village of Middleton (1 m.) has a fine Church with Norm. tower and arcade; an old cross is walled into it. Within are old oak-stalls and an inlaid pulpit.

castles), the shell of which, 3 stories high, is nearly perfect. All these towers seem Edwardian (Edward I.), greater part of N.E. Yorkshire; but there is little architectural detail, and the shoulder arch, which occurs in the portals, was in use for a very long period. In Leland's time there and thus embracing Cleveland as

well as the district usually known as good view from the window of the the "Yorkshire Moors." N. of the Esk, the hills consist of lias, capped by sandstones. S. of the Esk, the land is formed on an axis that runs nearly E. and W. from the peak (S. Robin Hood's Bay), through Lilhoe Cross, Ralph Cross, and Burton Head, to Cold Moor (S. of The highest point is Stokesley). Burton Head, 1485 ft. From this high axis short glens pass N. and S., carrying streams which join the Esk N., and the Derwent S. "Thus the wide moorlands are split into many romantic dales, often edged with rocky borders, and somewhat enriched with wood along the course of the 'beck.'"- Phillips. These hills consist of lower colitic strata (arenaceous), based upon lias: and, based upon their slope, to the S., is a range upper oolitic (calcareous) hills, of less altitude, rising gradually from the sea at Scarborough Castle to Hambledon End (1300 ft.), and then diminishing southward. This terrace-like range is sharply escarped to the N., showing cliffs along every Its stream. hilf-ends are called "nabs," (Danish, næb, a rocky headland) and, as usual on the limestone, they are greener, more wooded, and less covered with heather than the arenaceous hills N. A remarkable dyke of dark-coloured basalt, about 60 ft. in horizontal thickness. penetrates the strata for a length of 60 miles from Cockfield Fell, in Durham, across the Tees to Eskdale, ending within 4 m. of the sea S.W. of Whithy. Through a succession of glens in these hills the rly. is carried to Whitby.

The rly. from Pickering to Whitby (at first a horse rly. constructed by the elder Stephenson) is one of the most picturesque lines in England. It runs through a series of narrow dales until it reaches the valley of the Esk, which it follows to Whitby. [Yorkshire.]

carriage for the whole distance.

(From any of the stations on this line very pleasant moorland walks may be taken rt. and l.)

Much of this country was within the liberties of the forest of Pickering. an ancient royal hunting-ground attached to the castle.

The Castle of Pickering is first passed rt. on its mound above the stream. The rly. then advances up the valley watered by the Pickering beck, the sides of which are richly clothed by wood and plantation. The meadows bordering the beck, and the side valleys which here and there open out, are pleasant; but the best bits of scenery are at the junct. of the Levisham beck with the larger stream, about 14 m. from the Levisham stat. Crossing a broad patch of rough ground, covered with patches of meadow-sweet and bog myrtle (Murica gale), we reach

43 m. from York, Levisham Stat. Rt. (but not seen) is the village of Levisham (church rebuilt 1804).

The Roman camps at Cawthorne are 2 m. from the Levisham Stat. These camps are on the ascertained line of a Roman road which ran from (or near) Malton to the sea at "Dunum-Sinus" (the bay N.E. of Whitby). They are 4 in number, and are placed (close together) on the very edge of the escarpment formed by the calcareous (upper colitic) hills (see ante). Their position is thus strongly defended N. The three most westerly of the camps have only a single agger; and (from their peculiar entrances—found also at Old Malton and at places more certainly known to have been held by the 9th legion) it has been conjectured that they were raised by this body of troops. The traveller should try to get a most eastern camp, which is perfectly

square, has a double ditch and vallum, ! and was a more permanent station. The Roman road runs through it from E. to W., and then turning N. descends the face of the hill. This camp too commands by far the widest view, looking N. up Rosedale and over the moors, and S. over a vast stretch of country in the direction of York. All the camps are overgrown with heath and furze, and the stag's horn moss is to be found in and about The wild surrounding country is covered with British intrenchments -howes-standing stones-and pits of ancient villages; indications of a numerous population of shepherds and hunters, whom the permanent camp would keep in some awe.

The remarkable manner in which these calcareous hills are scarped is well seen from this stat. E. and W. of the camps the headlands projects

like a long line of sea-cliffs.

Not quite 1 m. W. of the camps is the village of Cropton (where is a small Inn, at which the pedestrian may find rough, but clean, sleepingquarters). W. of the modern ch. is the remarkable mound of "Tallgarth hill" (the hall garth—a name often found applied to the sites of important Saxon houses. It is surrounded by a kind of fosse, and has some outworks about it -a double ditch of great strength sweeping round the base of the hill. This is a good specimen of the mounds called "raths" by Prof. Phillips. (There are others at Lofthouse, Kildale, Kippax, and elsewhere, the largest and most important being that of Barwick in Elmete; see Rte. 42.) Such mounds are generally found at the terminations of ancient villages. They have not been properly examined, and it is uncertain whether they are sepulchral, for defence, "most-hills" for the administration of justice, or, as is perhaps most likely, the raised foundation for a house protected by fosse and pali-

this mound, with Lastingham nestling under the hills l., and the country toward Helmsley beyond it. In front extends Rosedale (Rhos. Celtic, a moor (?) but the etymology is doubtful: see Roseberry Topping, Rte. 15), wide, tree-dotted, and stretching its sweeps of heather towards the upper moors.

[Under Saltergate brow, about 3 m. rt. of the Levisham Stat., is a narrow glen in the calcareous hills, called the Hole of Horcum. Here the mountain-plant " Cornus suecica " is found—its only known habitat S. of the Scottish Highlands and the Cheviots. Blakey-topping, a singular tumulus - shaped hill, is con-There are some picspicuous N. turesque scenes on the moors in this direction, over which the tourist may walk and find his way back to Pickering. Fringing the glen of the Dalby Beck (the upper valley is called Doedale-grif) are the Bridestones, natural rocks, but so curiously-shaped as to have received the name constantly given in this district to primeval stone monuments.

l. is Newton, from which the dale we are now entering is named. (A small Church, in a beautiful position on the edge of the moors, was consecrated here in 1870.) part of the line, between Levisham and Goathland, is the most picturesque. The valley widens and contracts in a remarkable manner, and the rly., as it follows its windings, opens scene after scene of great interest. The hill-sides, rising on either side to a height of about 500 ft., are generally rough, with copse and heath, and with broken scars, some of which are fine. striking of these rock ranges is on the and will be recognised by its semicircular form. This is Killingnoble Scar, long celebrated for its breed of hawks, which (according to evidence sades. There is a superb view from given in 1612, on a commission for ascertaining the privileges of Goath-|small waterfall on the Ellerbeck. land) the inhabitants of the dale worth notice. "were charged to watch for the king's use." A small pool at the foot of the scar is called "Newton Dale Well." and a fair was long held here on Midsummer Sunday, to which all the people of the district resorted. in order to perform certain ceremonies which ensured them the "blessing of the well."

Passing out of Newton Dale, the view becomes wide and open. the forms of the distant hills, as seen from this more open valley and from parts of Newton Dale, are low. heavy, and unpicturesque, and the interest is confined to the actual sides of the dale. On the moors l. is July Park, a village marking the site of a castle (St. Julian's-there was perhaps a hospice attached to it-St. Julian was the patron of travellers) of the Mauleys. 40 yds. W. of the villages, the Roman road to Dunsley (the same that passes through the Cawthorne Camps) may be traced among the heather. It is here about 12 ft. broad.

The rly. turns N.E. through the Vale of Goathland, in the farther part of which the scenery becomes again beautiful. Before reaching Goathland Stat. the rly. turns again rt. to avoid a most formidable incline (up and down which the carriages were dragged by ropes) on the line first constructed. This passage, which occupied from 5 to 10 min., and was accompanied by doleful noises from the tightening of the ropes, tried the nerves of most passengers: and a frightful accident that occurred in 1863 from the breaking of one of these ropes, led to its being abandoned. The rly. now descends the Ellerbeck glen at Beck Holes. Abbots House, a farm l., was a hunting-seat (?) of the Abbots of Whithy. Beyond it, we reach

On the moor, 11 m. l., is a place called Killing Pits, which is no doubt the site of a British village. The hut foundations resemble those at Egton (see post, Exc. from Whitby) and at Danby (Rte. 15).

The highest point (850 ft.) on the hills adjoining the rly, is marked by Simon Howe, a large tumulus, near which are 3 upright stones. name (commemorative in all probability of Sigmund, one of the earliest Teutonic heroes, who is recorded at Simonsbury on the Blackdown hills between Devon and Somerset, at Simon's Bath on Exmoor, at Simon's Seat on the ridge between the valleys of Wharfe and Nidd, and in many other places) indicates perhaps the line of an ancient division or "march" between distinct tribes. It is on the axis of the solitic hills. (See ante.)

The hamlet of Beck Holes (to be reached from Goathland Mill Stat.) is picturesquely placed at the junction of the Wheeldale and Ellerbeck streams; which descend rt. and l. through narrow glens, containing some very pleasing scenery. (There are smelting furnaces at Beck Hole ; and ironstone is quarried here.) The Ellerbeck glen (rt.) is at first bare of wood, and the rocks rise steeply from the edge of the beck. There is more wood higher up; and at about 14 m. from the main valley. Thomason Fors, a small but picturesque waterfall, is reached, worth the sketcher's attention. Osmunda regalis grows here in profusion. There is a second waterfall farther up the stream, which may be reached by winding round the rocks on the l.

The Wheeldale glen (l.) is wider and more wooded, but its sides are Goathland Mill Stat., where is a broken by large masses of rock, and

on the stream which runs down it | produce is estimated at the rate of are many waterfalls. The most important in the glen are Nelly Aure Foss (about 1 m. from the opening), where the beck falls over an edge of sandstone about 36 ft.; and (1 m. farther) Mallyan's Spout, formed by the descent of a tributary stream into the Wheeldale beck, and about 76 ft. high.]

Crossing and recrossing the stream formed by the junction of the two becks, the rly, passes through some very pretty scenery to Grosmont. About 1 m. from Beck Hole it is carried through the basaltic dyke which (see ante) ranges from Darkfield Fell in Durham to Whitby. At

543 m. Grosmont Junct. Stat. the valley of the Esk is entered. Here is the junction (l.) with the N. Yorkshire and Cleveland Rly., running from Whitby through Castleton to Stockton-upon-Tees (Rte. 15).

The Ch. at Grosmont was rebuilt in 1875. (For the beautiful scenery at Egton Bridge, 11 m. l. of Grosmont Station, see post. The visitor to Whitby should not miss it.) are iron-blast furnaces (belonging to Messrs. Bagnall of Whitby), the smoke from which is visible from all the heights round about, and is a good landmark. Each furnace is capable of producing 250 tons of pig-iron a week. The sandstone and ironstone in the neighbourhood are largely quarried; and are carried to Whitby for exportation. At a stone-quarry, about 1 m. down the line, a section of the great basaltic dyke is exposed. "Here it has the form of a great wedge, the apex uppermost; and the sandstone, which it so rudely shouldered aside, is scorched and partially vitrified along the line of The labourers, who break up the hard black basalt for macadamising purposes, call it 'chaney metal.'"—White. Where the ironstone beds are fully developed, their

22,000 tons to the acre.

From Leasering, the wood-crowned hill I. of the station (on the rt. bank of the Esk), there is a good view up and down the valley, toward Egton and Whitby, and back over the vale of Goathland, through which the rly. has passed. The roughness of the ground marks the site of an ancient alum-work, which, as Young ('Hist. of Whitby') contends, was the earliest in the kingdom. (For the alumworks of this district see Guisborough. Rte. 15A.) About 1 m. up the hill, on the ridge, are the remains of a Roman camp through which the road from Malton to Dunum-Sinus passed. There is a wide view from it.

There was a small Priory at Grosmont, founded about 1200 by Johanna de Turnham, and further endowed by the Fossards and Mauleys. It was attached to the Abbey of Grosmont. or Grandimont, in Normandy. Hence the name. The order of Grandimont was a branch of the Benedictine, but far more austere. It had only 3 houses in England-Adderbury in Shropshire, Cresswell in Herefordshire, and this. The site is marked by a farmhouse l. after leaving the station; but there are no remains of importance.

The Tunnel Inn at Grosmont is convenient for visitors from Whitby; but no conveyance is to be hired

About 11 m. before reaching Sleights Stat. is Sleights Chapel. built on the foundations of an ancient chapel in which tradition placed the scene of the story referred to by Sir W. Scott in 'Marmion:'-

[&]quot;Then Whitby's nuns exulting told How to their house three barons bold Must menial service do;

While borns blow out a note of shame, And monks cry, ' Fye upon your name!' In wrath, for loss of sylvan game, Saint Hilda's priest ye slew.'

Ralph de Percy, and two other barons, are said to have killed the hermit who lived here, and who had given refuge in his chapel to a wild boar, followed by their hounds. As a penance, they were enjoined to repair to the Eskdale woods on the morning of the Vigil of the Ascension, to collect certain stakes there. and to carry them on their backs to Whithy harbour, where they were to fix them in the sea, while an officer blew "Out on you," for their crime. The story seems to have arisen from some kind of harbour service due from the Percy and others at Whitby.

The main valley of the Esk, through which the rly runs, is pretty, and wooded. Sleights Moor is seen rt. From

574 m. Sleights Stat. the pedestrian may make his way to Falling Force (between 3 and 4 m. S.E.), a waterfall in one of the wooded glens that descend from the moor. grounds attached to Newton House, and the gate which leads to the valley is only open for visitors on certain days, which should be ascertained at There are pleasant walks Whitby. cut through the woods. The waterfalls throughout this district, it must be remembered, depend for much of their beauty on the season. In very dry weather they are mere threads.

The moors W. of the dales through which the rly. passes are somewhat dreary, although they are interesting to the antiquary from the number of howes and tumuli with which they are dotted. Urns and flint implements have been found in numbers. The highest point (on the main axis) is Lalla Cross (978 ft.), one of the boundary-marks of the Whitby monks.

There are fine sea-views from all this high ground. 1

Through scenery of the same character we reach

59 m. Ruswarp Stat. (l. is Rivet Hall, a Charles II. mansion, now a farmhouse), whence the line proceeds by the side of the river, which broadens as we advance to

601 m. Whitby.

Hotels: Royal, on the W. Cliff (board and in the w. Chin (board and lodging in public rooms 10z. 6d. a day), in the best situation; Crown, also on the W. Cliff; the Augel, in Baxtergate Road; county, Fishburne Park (commercial). Lodgings are plentiful and tolerably good. The best are on the W. Cliff. The best jet shops are—at the end of John Street; St. Illida's Hall in Buxterrate; and a very good marked. Hall in Buxtergate; and a very good one at the end of Bridge Street.

The rly. from Whitby by Egton and Castleton to Stokesley and Guisborough renders the country in that direction easily accessible (see the next route). Frequent communication between Whitby and Saltburn by Sea during season. Omnibus at times, but not reliable. (See post, Excursions from Whitby.) Excursions by steamer to Scarborough and

Hartlepool.

RAIL. Whitby to Scarborough, by Seamer Junct. The shortest route.

The old town of Whitby lies on either side of the river Esk (one of the many forms—Exe, Devonshire; Axe, Somersetshire, &c.—of the Celtic wysg, water), which here rushes to the sea between tall cliffs. The name is Danish or Anglian, the white dwelling — an epithet frequently given, as at Withern in Galloway, to houses of "stane and lime" (or to houses whitewashed on the exterior. as York Minster was by Wilfrid, see Rte. 1)—thus distinguished from the ordinary timber or wattle; its older name was Streoneshalch, see post) On the l. bank the town climbs upwards in a succession of steep and narrow streets; on the rt. it clusters under the cliff crowned by the famous Abbey of St. Hilda. The two parts of the town are connected by a bridge, of which the central portion is lifted for the passage of vessels. The mouth

of the harbour is protected by two stone jetties; but in spite of these, colliers and other vessels taking refuge here in stormy weather are obliged to moor above the bridge, where the river widens out into a basin large enough to contain a fleet, though nearly dry at low water. the modern houses are on the W. The town is curious and oldfashioned; and its fishing population (Leland calls it "a great fischar towne"), with its many vessels and foreign trade, give it distinctive character. Whitby (Pop. 16,744) has between 800 and 900 ships belonging to the port. These ships are engaged largely in the Baltic and American trade, but are chiefly employed as home coasters. Coals are shipped from here, and considerable quantities of ironstone; and the jetworkers of Whitby are famous.

Some vessels are still built here: but this part of the business of the place has decreased largely since the ships with which Capt. Cook made his first voyage round the world were built on the riverside, near the house (in the first turning rt. from Church St., with the date 1688 over the door) in which he served as apprentice. The whale-fishery has also deserted Whitby. Dr. Wm. Scoresby (died at Torquay 1857) was born here in 1789: the son of a captain in the Greenland service. He was his father's apprentice, and as such made many North Sea voyages. Chambers, the marine artist, was also a native of this place, and long an apprentice on board a Whitby trader.

Cobles, the fishing-boats used on all this coast, are nearly flat-bottomed, very sharp in the bows, and carry three men. They are taken to the water on wheels; and do not go so far to sea as the "Five-men boats," which generally take two cobles on board, and use them on arriving at the fishing-ground.

As a watering-place Whitby is one of the pleasantest on the Yorkshire coast. It is much quieter than Scarborough,—a great recommendation to The sea-views are superb. many. Many places of interest are within easy access; and the inland country is varied and very picturesque-especially that over the moors toward Cleveland. The chief promenades are on the West Cliff, and on the W. pier, nearly 🕯 m. long, with a lighthouse at its farther end, which the visitor should ascend for the sea-view, and for that of the town below him. with its background of steep, wild hills. (It should here be noticed that Whitby is the "Monkshaven" of Mrs. Gaskell's powerful but painful story, 'Sylvia's Lovers.' town and its immediate neighbourhood are well and most faithfully described.)

In Whitby itself the great point of interest is the ruined *Abbey, on the hill opposite the W. Cliff. A flight of 189 steps leads up from Church St., which runs parallel with the river, to the Abbey ruins and Parish Church.

The site consecrated for so many ages cannot be visited without extreme interest, although no fragment remains earlier than the 12th cent. A small charge of 3d. is made for admission to the ruins, which are enclosed by a fence. They are those of the Abbey Church, of which the choir, N. transept, and part of the nave The W. side of the alone remain. nave fell during a great storm of wind in 1763; and the central tower in 1830. The choir (E. Eng., but retaining a Trans. character) is the earliest portion. The N. transept is also E. Eng., but of later date, and the nave is rich Dec. All is much weatherworn; but well deserves attention. The triforium of the choir (a circ. arch, enclosing 2 pointed, each of which is again subdivided) should be compared with those of E. Eng. date at York and in the choir of

Rievaulx. It extended over the aisles. The E. end, square, with 3 tiers of 3 lancets, the uppermost rising into the gable, is fine; and the foiled openings (not quite piercing the wall) between the lancets of the lowest tier are worth notice. All the choir-work is much enriched with dogtooth. There is some trace of a screen between the 2 first piers from the E.; and perhaps the shrine of St. Hilda stood here, if her relics were ever brought back from Glastonbury. In the N. transept the window-mouldings show large open flowers (lilies) differing E. and W. One pier alone of the S. transept is standing. In the nave, the 3 easternmost windows are E. Eng., the others Dec., of a somewhat peculiar design. In the W. gable of the N. aisle is a small and curious lozenge-shaped window, of the same date. Outside the ruins, remark, in the choir, the clerestory windows, with heads at their corbel stones; the pinnacle-capped buttresses of the N. transept, much enriched with canopied niches; and the whole N. front. It is from this side that the sketcher will get his best points.

On the S. side of the ruins are the foundations of cloisters and domestic buildings, and of the Chapter-house next the S. transept. The ground slopes inland from this side, and afforded some shelter. After the Dissolution the Abbey became the property of the Cholmley family, who still retain it, and who built, about 1580, the House called Whitby Hall, on the site of the Abbot's dwelling. This house has been restored since 1867. In it is some tapestry which is said (no doubt since 'Marmion' appeared) to have been "worked by the nuns," a good old Venetian chest, and some antiquities of little interest. From the garden there is a fine view over Whitby, up the Esk.

The parish Church of St. Mary, on the cliff a little below the Abbey, con-

tains some Norm. portions; but has been so changed and filled with pews and galleries, that its interior is strongly suggestive of a ship's cabin. In it is a monument for Gen. Lascelles, of Whitby, who served in Spain during the reign of Queen Anne, and in Scotland in both the 15 and the The view from the ch.-vd., commanding the port of Whithy and the W. Cliff, is very striking. In unusually clear weather the coast of Durham is visible from this point. In Dec. 1870, a very considerable landslip occurred here, and great part of the E. Cliff slipped into the harbour. St. John's Church (completed 1850) is an indifferent building of E. Eng. character. St. Ninian's (also modern) is on the site of an ancient chapel attached to the abbey.

The *Museum, above the Public Baths, on the W. pier (established 1823), contains a very interesting series of fossils from the lias of the neighbourhood—ichthyosauri, plesiosauri, and a very fine crocodile. The ammonites are well represented; and there is a complete series of bones from the Kirkdale Cavern. Some antiquities from the howes and tumuli of the moors should also be noticed.

There is a tolerable Library, under the same roof as the Museum, to which strangers may subscribe by the week or month.

The Cliffs between Whitby and the Peak (the S. end of Robin Hood's Bay) "exhibit almost universally, in their lower part, a mass of laminated lias shale, and, very generally on the top, a crown of gritstone. The shale wasted by the rough sea perishes, though not very rapidly, and the crown of sandstone falls, though not often. The permanent effect of these circumstances is a formidable steepness in the whole range of these dark cliffs, which even at low water are margined by only a narrow belt of sands, or a scar of rugged rock, safe

only to those who take heedful note of the tide."—Phillips. It is from Leeds, in November 655, with the fierce heathen Penda of Mercia, vowed bands containing jet run through it. No. of Whitby, the low cliffs as far as Sandsend, are of sandstone, covered to a conventual life. Penda was by glacial drift. At Sandsend the colitic cliffs rise again.

Jet (the word is from the Greek Gagates, named from the river Gages in Lycia, where jet was first discovered) is a kind of cannel coal, sometimes found with fossils imbedded in it, and is dug not only in the cliffs, but in some places inland. electricity procured for it in the middle ages the title of 'black amber;' in fact, it often occurs in the same beds of lignite as the real amber, and is probably the fossilized branches of the same tree that produced the resin, the origin of the latter."—C. W. King. The best is found, as in Drayton's days, on the Mulgrave estate

"The rocks by Moulgrave too, my glorie forth to set,

Out of their crannied cleves can give you perfect jet."

Workers take a right of the bands of jet for a certain term. The value varies from 10 to 18 shillings a pound. It is worked into the desired patterns, at first with knives, then with grindstones, and last by wheels covered with list, to give a high polish. Ornaments of very good design will be found in the Whitby shops, and the process of working may be seen on proper application. How ancient was the working of jet in this neighbourhood is shown by the necklaces of jet beads found in British tumuli on the moors—examples of which may be seen in the museums at Scarborough and Whitby.

History of Whitby Abbey.

It was about the abbey that the town itself arose. Oswi, King of

Leeds, in November 655, with the fierce heathen Penda of Mercia, vowed that if he were victorious he would dedicate his infant daughter. Elfleds. to a conventual life. Penda was killed in the battle : and Oswi placed his daughter with large gifts of land at "Heruteu" (Hartlepool in Durham). where Hilda, the daughter of Hereric, nephew of King Edwin, was then abbess. Two years afterwards, Hilda. having acquired certain land "Streoneshalch" (now Whitby), established a monastery there, over which she presided until her death in 680.

"High Whitby's cloistered pile" thus stood out as the first point seen by the seaman in returning to his native shores, and the last he would miss in leaving them; and the lights streaming from its ch. windows must often have served him as a "pharos." accordance with the usage of that age, Hilda's foundation was for both monks and nuns; but the "Domina Hilda "-the " Lady Hilda," as she is still called at Whitby-remained the Superior. Whithy became at once the most important school of learning in the North; and five inmates, who afterwards became bishops, Bosa (York), Ætta (Dorchester), Oftfor (Mercia), John (York—this is St. John of Beverley-see Rte. 8), and Wilfrid (York-not the famous Wilfrid, but a successor of the same name), were brethren of the house under Hilda. In the year 664 Whitby (perhaps on account of its easy access by sea) was chosen as the place of the synod which was to determine the wellknown Easter controversy. King Oswi and his son Alfred were present at it. Wilfrid, then Abbot of Ripon, was the greatest supporter of the Roman party; and Colman, Bp. of Lindisfarne, on whose side were Hilda and Bp. Chad, represented the Scots. After a long discussion the controversy was summed up by Wilfrid. who asserted that St Columba could

Peter, to whom the Lord had given the keys of heaven; and King Oswi declared that he would not venture to oppose such an "ostiarius." "lest perchance he should turn from me when I reach the doors of the heavenly kingdom." Colman retired from his see; and both Hilda and St. Chad adopted the Roman computation. was whilst Hilda was abbess here that Cædmon composed his remarkable paraphrase of the Scriptures in Saxon verse. He had been a Ceorl (?) on or near the lands of the monastery; and was unable to sing or to compose until, as he once lay asleep in a cattlestall, a certain personage seemed to stand by him, and order him to sing. At his request Caedmon, then no longer a young man, composed in his sleep some verses on the creation; remembered them when awake; and after telling his story to St. Hilda, was, on due probation, received as a brother of the monastery, where he composed his long poem; which Milton may perhaps have seen, since some curious points of resemblance have been traced between it and the 'Paradise Lost.' Hilds herself died here in 680. Her successor was the Princess Elfleda (see ants), who had been brought up under her; and who, as abbess, used to sail from Whitby for interviews with St. Cuthbert on Ccquet Island off the Northumbrian coast. Elfleda, her father King Oswi, her mother, and many noble Northumbrians, were buried in the monastery here. The house continued to flourish until about 867, when it was destroyed by the Northmen under Inguar and Hubba, Titus, the abbot of the monks, taking flight to Glastonbury with the relics of St. Hilda. After the Conquest a new foundation (Benedictine, entirely for monks) was established here by Wm. de Percy (with the moustache—the founder of his family in England), to whom Whithy had been granted by Hugh Lupus, Earl of Chester, who first

on no account be preferred to St. | received it from the Conqueror. The actual restorer, however, was Regenfrith, one of the company of monks who set out from Evesham to "visit the holy places" in the North. The town of Whitby, its harbour, and a large tract of land along the coast (henceforth known as Whitby Strand), were included in the Percvs' grant. It was at first a Priory, but was raised to the dignity of Abbey temp. Hen. I. Toward the middle of the 12th cent. (the year is uncertain) the abbev. "intus et foris," was plundered by the "King of Norse," who landed here with many ships. But the Percys remained its patrons till the Dissolution, when its gross annual rental was 5057.

Whitby Abbey contained no nuns after the Conquest; and the "Abbess of St. Hilda's," with her nuns, who graced the galley of the famous voyage from Whitby to Landisfarne, in 'Marmion,' is entirely a lady of the imagination. The evening talk of the nuns, however, commemorates the true legends of the place—

"— how of thousand snakes each one
Was changed into a coil of stone
When holy Hilds prayed;
Themselves within their holy bound
Their stony folds had often found.
They told how seafowls' pinions fail
As over Whitby's towers they sail,
And sinking down with flutterings faint,
They do their homage to the saint."

(The ammonites of the lias are the snakes which St. Hilda petrified and beheaded; although the shield of the abbey — 3 ammonites — retains the heads. So St. Keyne, in Somersetshire, is said to have petrified the snakes which infested her district—also ammonites.) At one of the windows of the Abbey Ch. was seen, on certain occasions.

"The very form of Hilda fair Hovering upon the sunny air."

—an effect of light and mist which is still sometimes visible.

Walks and Excursions.

On the S., passing through St. Mary's churchyard, you can walk along the cliffs, here grand and lofty, in the direction of Robin Hood's Bay. At High Whitby, marked by a coast station and lighthouses, the cliff is 285 ft. high; and here fossil Equiseta may be seen erect in the gritstone rocks. (The double lighthouses distinguish them from others along the coast. The lights are "dioptric," the lens being a dome built up in horizontal rings or layers of thick glass). Nearer Whitby a promontory of broken rock stretches into the sea; and in the "wyke" or little bay N. of it the best specimens of saurians have been found. There was a complete nest of them imbedded here. The sea-views from these cliffs are fine: and inland, the ruins of the Abbev Ch. rise strikingly, suggesting what an excellent guide the buildings must have been to the Northmen who so often devastated them.

On the N. there is a walk along the low cliffs nearly as far as Sandsend (3 m.); and the sands below are firm and pleasant. Lythe Ch. is conspicuous on the hill, W. The bay here is probably the Roman " Dunum-Sinus;" but the name can hardly, as has been suggested, be retained in that of Dunsley, a small neighbouring village, towards which the Roman road, from near Malton, points. Sandsend (in Cleveland—the "beck" marks the division) were some extensive alum-works, abandoned since 1867. They were established here about 1620, when the old name of the village-"Thordisa"-no doubt "Thordis & "—the "beck" or stream of Thordis, a Scandinavian woman's name-was changed for the present East Row. (For the history of alum in Yorkshire see Guisborough, Rte. 15.) The quarry from which the alum shale was dug is about 1 m. W. of the works, and is a vast semicir-

a volcano, a resemblance which, when the works were active, was increased by the slowly smouldering heaps of shale crackling and smoking within it. Where freshly exposed, "the shale may be likened to slate soaked in grease: it has a greasy or soapy feel between the fingers. . . . Embedded in it, most abundant in the upper 25 ft., the workmen find nodules of limestone about the size of a cricket-ball: and of these the well-known Mulgrave cement is made."— White Fossils—saurians, amnionites (150 distinct species are found on the Yorkshire coast), fish, and plants, occur also abundantly in this lias A small modern ch. (St. Mary's) has been built at the upper end of the village of Sandsend.

Inland from Whitby there is a pleasant walk from the rly. stat. along the l. side of the Esk across the meadows to Ruswarn: and at Cockshot Mill (2 m.), on the opposite side, there is a small waterfall in a picturesque wooded glen. You should walk to it through Church-street, to the cemetery (whence a fine view is commanded), and 2 m. beyond it a white gate l. leads into the mill vallev. You may cross the rlv. bridge (over the Esk) to Ruswarp, and return to Whitby on that side of the river.

Longer Excursions may be made from any of the stations between Whitby and Pickering (see ants); and by rail from Pickering. Lastingham is also within a day's work from Whitby. Very picturesque country lies also within reach of the stations on the Egton and Castleton Rly. (Rte. 15.).

name—was changed for the present East Row. (For the history of alum in Yorkshire see Guisborough, Rte. 15.) The quarry from which the alum shale was dug is about \(\frac{1}{2} \) m. W. of the works, and is a vast semicircular hollow, not unlike the crater of woods, or (a much longer, but most

beautiful walk) along Glaisdale Ridge and scars of the bay are of this lowest to Whitecross, and thence to Castleton: across the moors to Rosedale; shale, covered with glacial drift. The form of the bay is striking; and the form of t

(a) Robin Hood's Bay (6 m.) may be reached by a walk along the cliffs, or (there is no public conveyance) by a carriage road that is marked by flagstone footpath all the way.

About 1 m. from Whitby, on rt., in a field, is an arch formed by a whalejaw, and others in the fields beyond. Up the lane nearly opposite are some gates made of whale-ribs, and in some of the fields such ribs are used as rubbing-posts for cattle. These are relics of the old and departed trade of Whitby. At the village of Hawsker were two upright stones [not now to be discovered], which, says tradition, marked the spots reached by the arrows of Robin Hood and Little John, when, to please the monks of Whitby, they shot from their church tower. The pedestrian will find fingerposts with R.H.B. to He should take the l. guide him. road thus indicated where these roads meet after leaving Hawsker. Steep descent to the bay through the curious old quaint village of Thorpe, perched on hill above a rivulet, some of the houses walled up perpendicularly Note the Coracles over the stream. of the fishermen here. There is no part of the Yorkshire coast more attractive to the naturalist or the artist than Robin Hood's Bay. the Peak, its southern termination, a fault throws up the strata to the N.; and nearly the whole series of lias is here visible, under its usual capping of gritstone. The order is-upper lias (alum) shale; ironstone, and maristone (laminated sandstone) series: and lower lias series (shale with nodules of ironstone). The low cliffs

shale, covered with glacial drift. The form of the bay is striking; and the ravine, with a beck running through it, passes up into Fylingdales Moor. At the N. end of the bay is Bay Town (at the New Inn a stranger may find rough but clean accommodation), picturesquely placed; and owning a small fleet of coal brigs and schooners. The beautiful Church was built through present vicar by Street. From Stoupe Brow (800 ft.), towards the S. end of the bay, is a far more extensive view over land and sea. On the moors beyond are Robin Hood's Butts, tumuli, which are said to have served as marks for the outlaw and his men. Robin, says local tradition (no ballad records it), fled to this remote coast on occasions of special danger, and had his boats ready to put to sea if necessary. The name occurs in other parts of the district, as on Danby N. Moors, where 3 houses are also called Robin Hood's Butts. (For the Peak, see Rte. 12, Excursion from Scarborough.)

(b) Egton Bridge. The very pleasant scenery here is reached either by a walk of 11 m. from the Grosmont stat., along the l. bank of the Esk; or you may proceed at once to the Egton Bridge stat. of the Castleton rly. Not far from the bridge is an old-fashioned country Inn, the Horseshoe, convenient as head-quarters for the day. The most picturesque scenes are in Arncliffe (Erne—eagle cliffe) wood, beyond the inn; but the seclusion has been destroyed by the passage of the rly. through the Esk valley, here lined with lofty scars of rock. You should walk through the wood to Beggar's Bridge, said to have been built by a lover who had found it difficult to get to his mistress across the swollen river (it is called Firris Bridge in a document 2 centuries old; its age is uncertain); and (1), passing under the rly. bridge, climb the hill beyond, up which a steep road winds.

A very beautiful view opens from the the granite blocks used in them.) top of the hill over West Arncliffe wood, lying in the hollow of Glaisdale (possibly "Glai" is a personal name), the steep sides of which rise above it Pass through this wood. which is unrailroaded and lovely, and beyond it turn l. over the moor into the Rosedale road, which will bring you back to Egton Bridge. On the highest part of the moor a superb view opens towards Whitby, with a long breadth of sea beyond it. This scene, over Goathland Dale on one side, and into the moors on the other. is alone worth the climb. Glaisdale (through which a stream descends to join the Esk) is a wide valley dotted with farms; the divisions of the crofts marked by fine trees, which cluster more thickly about the homestead. Here, and in all the Yorkshire dales, these farms are singularly suggestive of that old home life which has been so beautifully painted by Southey in 'The Doctor.' The rich, quiet valley opens very pleasantly as you descend toward Egton. On the moor, between the woods of E. and W. Arncliffe, a little N. of the Rosedale road (and fenced off from the surrounding land), is a collection of hut foundations, indicating the site of a primitive village. They are hollows, disposed quite irregularly round the sides of a piece of ground about 41 acres in extent, which is surrounded by a sort of fosse and a bank of earth and stones, having an opening on one They vary in diameter from 8 to 20 ft., and in depth from 3 to 6 ft. Traces of fire have been found in the centre, and in some are indications of rough walling. Similar foundations exist in many parts of the moors, the most important being at Killing Pits, near Goathland chapel (see ante), in Westerdale (Rte. 15), and near Danby Beacon (Rte. 15). They resemble in general character the British villages on the Cheviots and on Dartmoor. (These last, however,

(You may drive from Whitby to Egton Bridge, or a good pedestrian may return across Egton Low Moor. and through the village of Egton. From Swarthous Cross, on Egton Moor, the view is magnificent, with a vast extent of sea, and Whithy Abbey, on its cliff, far below the spectator; S. the Grosmont valley is well seen. The foreground of purple heather is here finely contrasted with the grey of the sea, and the rich verdure of the vallevs. Egton (Oak-town) church contains Norm. and E. E. portions, but is of little interest. (2) For the longer walk, proceed from Egton Bridge to the Beggar's Bridge, and thence (instead of taking the road over the hill followed in the former walk) continue about 1 m. to the little ch. at Glaisdale End. From this ch. the road is plain S.W. for about 14 m. Just before a Weslevan chapel is reached, a branch road turns up the hill rt. to the high ground of Glaisdale Ridge, from which very picturesque views (among the finest on these moors) are obtained into Fryup Dale, which here sends its "beck" towards the Esk. (A long isolated ridge divides Great from Little Fryup.) Pass round the head of Fryup Dale-there is a wellmarked track all the wav-and then make due W. for Whitecross — a mark easily seen from a distance. and well known to the natives, so that it will be easy to get directed to it. From Whitecross turn due N. down Castleton Ridge to the rly. (See Rte. 15.) stat. at Castleton. The whole distance, from Glaisdale End to Castleton, is about 16 m. The ground is elevated moorland throughout, and the views magnificent.

At Glaisdale End. where is a station, 3 large ironstone furnaces mark the works of Messrs. Wilson. are more distinctly marked, owing to They are very far from conferring an additional grace on the neighbour-

(c) Rosedale (the etymology is uncertain, but see Roseberry Topping, Rte. 15), 12 m. from Egton Bridge, is reached by a wild and lonely heath road, passing over Egton High Moor. (Driving to Rosedale, you must hire your vehicle at Whitby.) About 4 m. rt. a picturesque broken " gill " There is descends into Glaisdale. The effects no gorse on these moors. of colour are produced by heather (ranging from deep purple to white), fern, and much whortleberry. The short thick heather makes the ground difficult for walking. After passing Shunnor Howe (1085 ft.), we descend towards Rosedale, which soon opens below us, green with trees and fields. The charm of these dales is only half discovered by those who pass merely up or down them. should be come upon suddenly, from the dreary heathland that protects and isolates them, with which they are in admirable contrast. smaller dales, Northdale and Thorgill, open, above the village, into Rosedale, the head of which, under Glaisdale Moor, is not far to the N. The Crown, the village Inn, will probably be found full during the early shooting season, but it is a good centre from which to explore the adjoining moors and dales; and the accommodation is tolerable. village has been filled with life since the iron-works were opened on the hill above; but the site must have been intensely solitary when Robert de Stuteville founded here a Priory for Cistercian nuns, temp. Rich. I., and attached the whole of the dale to the Priory, worth (gross) annually, at the Dissolution, 41L 13s. A doorway (arch into cloister) and part of a turret staircase are the only remains, and are of the 13th cent. The modern ch., small and ugly (rebuilt in 1839). occupies one side of the cloister; the inscription, "Omnia vanitas," on a

stone inserted over the door, preaching such a lesson as the good Cistercians hardly contemplated when they carved the letters. In the ch.-yd. is a large and beautiful sycamore.

Iron-works existed in this part of Rosedale at an early period. Eustace de Stuteville, before 1209, gave to the Priory his lands called Baggthwaite, with the exception of his forges, which no doubt proved a great source of annoyance to the nuns, for he subsequently conceded his interest in them, adding in his charter, "Ita quod eadem forgia penitus amoveatur, et a nullo hominum unquam resedificetur."

Ironstone is now raised here largely. and is of unusual richness; and extensive works have been constructed on the hill by the "Rosedale and Ferryhill Iron Company." More than 600 men are employed, for whose use sundry Dissenting chapels have risen in the village, and a hospital has been founded by the Company. The works are readily shown. (See Middlesbrough, Rte. 17, for a notice of the Cleveland ironstone and its working.) The ore is conveyed by a rly., along the ridge of the moors, to Ingleby Greenhow (above which is a steep and dangerous incline), where it joins the N. Yorkshire and Cleveland line (see Rte. 17). By permission, which must be obtained from the proprietors, at the Rosedale mine. or at Ingleby, passengers are occasionally conveyed on this private line, the views from which, especially at the head of Farndale, are magnificent.

You may descend Rosedale to Lastingham (see Rte. 18A.). For the dales and moors accessible from Rosedale, see ante and Rte. 15, Castleton. Rievaulx Abbey may be reached by rail from Pickering to Helmsley, Rte. 18A.

(d) Mulgrave Castle (Marquis of Normanby), 4 m. W. of Whitby, is a handsome modern edifice, built by the Duchess of Buckingham, natural Earl of Mulgrave, Marquis of Normanby and Duke of Buckingham. The property came to the Phippses by the marriage of the duchess's daughter in 1718 to the father of the first Lord Mulgrave of the Phipps family. The Castle is not shown. It contains some interesting Pictures. among them the Ruspigliosi Claude, a landscape with banditti: P. Veronese, the Family of Darius; Cuyp, a landscape; Vandyck, Queen Henrietta Maria: Kneller, James II. and the Duchess of Buckingham; Jervais, Lord Hervey, and Molly Lepel; Gainsborough, Constantine Phipps, the Arctic explorer; Reynolds, Lord Mulgrave and boy (a Phipps) with a dog: Hoppner, Wm. Pitt: Wilkie. the Blind Fiddler and Queen Victoria in her youth. The woods and drives, however (a great attraction at Mulgrave), are open on certain days with an order, obtainable at Whitby. They cover the sides of 2 deep ravines, such as frequently open to the sea on this part of the coast, and extensive walks and drives have been cut through them.

On a high ridge between the ravines are the ruins of the Old Castle, traditionally said to have been founded by a certain Wade (no doubt the Wada or Vada famous in both Scandinavian and Teutonic folklore), a giant, who had a cow, which his wife was compelled to go to milk on the moors a long way off. For her convenience Wade constructed the road called "Wade's Causeway" (part of the Roman road between Malton and Dunsley). While she was assisting, by conveying stones in her apron, the string broke with the weight, and the burden still remains on the moor in a heap of not less than 20 cartloads. The cow's rib (a whalebone) was formerly shown at Mulgrave Castle. Wade's grave is pointed out at Goldsborough, and elsewhere. The castle was long the stronghold

daughter of James II., wife of John | of the Mauleys (de malo lacu). The situation must have been one of great strength, and the remains are interesting to the student of military antiquities. The Castle occupied the entire width of the ridge. On the E., approach to the walls was cut off by a most, from the brink of which still rise walls and towers of much strength. The main approach was on the W. where the entrance was between 2 massive circular towers. The ground lines within and without the containing walls are at very different levels, the inner being much the higher. The wall has consequently has bulged outward, and strengthened by massive buttresses. The oldest part of this enclosing wall is on the S. side of the S. entrance tower, and is marked by 5 shallow buttresses, which are clearly Norm. In a tower at the N.E. angle of the castle is a circular-headed doorway, built up with herringbone masonry, for which bricks are used which may be Roman. It would seem that a Norm. structure occupied the site of the present remains, and must have been the work of the Fossards, to whom the manor passed after the Conquest. A large window on the E. may have lighted the Great Hall of the castle in its later condition. This room was 25 ft. wide by 36 long. The ruins are picturesque, and worth a visit. Mulgrave Castle was "dismantled" by order of Parliament in 1647, and the blocks of masonry lying at some distance from the foot of the walls perhaps indicate the use of gunpowder for the "dismantling." It passed from Mauleys, temp. Hen. V., to the Bigods; then by marriage, temp. Ed. VI., to the Radcliffes; and about 1625 it came into the hands of Lord Sheffield of Butterwick, Lord President of the North, created Earl of Mulgrave by Charles I. Queen Anne created his descendant Duke of Buckingham and Normanby in 1703. The title became extinct in 1733.

and in 1767 Constantine Phipps, a 2 years. Kettleness was a favourite descendant of the Anglesey family, haunt of the Yorkshire bogles (fairies), was made Lord Mulgrave. His "who used to wash their linen in Claymore Well—and the noise of Normanby.

The view of Whitby, with the Abbey ruins, from the open park near the lodge, and from the ch.-yd. of Lythe above, is very striking. Lythe Church contains some E. E. portions, but is uninteresting. On the shore below are Roman cement works, for which the limestone nodules, found in the lias shale, are need.

(e) A coack or omnibus runs in summer from Whitby to Saltburn in 5 hours, Also an occasional steamer makes the trip. Passengers are landed at Staithes Bay in small boats. As the boatmen are addicted to extortion, arrangements for landing charges should be made with the master of the steamer. The distance is between 15 and 20 m. passing Lythe the places of interest along the coast are-Goldsborough, where the grave of giant Wade is pointed out (see ante, Mulgrave—the stones, about 100 ft. asunder, are 5 ft. and 4 ft. high)-Kettleness, a fine headland, 375 ft. high, with ironstone bands at its base (the name Kettle, famous in Iceland, is, perhaps, due to one of the Northern rovers, by whom this coast was haunted and partly settled), where are alum-works, rebuilt 1831. small ch. was consecrated here in 1871. On the night of December 17, 1829, a large mass of cliff, which had been perforated by excavations, gave way, and the hamlet glided down towards the sea. The inhabitants, having good cause for alarm, which was not a little increased by the darkness, took refuge on board a small sloop lying off for alum; and their houses and the works were overwhelmed. The cliff called the 2 years. Kettleness was a favourite haunt of the Yorkshire bogles (fairies), "who used to wash their linen in Claymore Well—and the noise of their 'bittle' was heard more than 2 m. off."—Runswick Bay, very picturesque, with jet-diggers busy in its cliffs, to the nearly complete destruction of Hob Hole, a cavern excavated by the sea in the lias shale, once the abode of Hob Thrush, a spirit, who used to be invoked for the cure of the hooping-cough. Standing at the entrance of the cave, with the sick child in her arms, the mother thus addressed him:—

"Hob-hole Hob! My bairn's gotten t' kin cough: Tak't off—tak't off!"

(Grimm suggests that "thrush" may be cognate with the O. N. thurs, a giant. Hob seems to be alb = elf. There are many Hobs in Cleveland, and at Mulgrave is a "Hob's Cave," see Atkinson's 'Cleveland Glossary.') The houses of Runswick village, at the W. end of the bay, "hang on the abrupt hill-side as martens' nests on a wall, among patches of ragwort, brambles, gorse, elders, and bits of brown rock, overtopped by the summit of the cliff." - White. The views from the cliffs here, with Kettleness rising E., are very fine. Hinderwell (inland) was anciently "Hilderwell," St. Hilda's Well, from a spring in the ch.-yd. so named.

haunted and partly settled), where are alum-works, rebuilt 1831. A Staithes are marked by tumuli. Staithes itself (Stxith, A.-S., a land-1871. On the night of December 17, 1829, a large mass of cliff, which had been perforated by excavations, gave way, and the hamlet glided down towards the sea. The inhabitants, having good cause for alarm, which was not a little increased by the darkness, took refuge on board a small sloop lying off for alum; and their houses and the works were overwhelmed. The cliff called the steel once took fire, and burned for

was apprenticed before he went to Whitby: and here, says tradition, he stole a shilling from his master's till, and ran off to sea, the real foundation of his fortunes. "No better station than this can be selected for exploring the sections or gathering the fossils of the lies. On the E. the upper lias and ironstone series: on the W. the upthrown marlstone and lower lias are easily examined; and by proceeding only a mile to the W. the great cliff of Boulby is reached, the loftiest of all the precipices which guard the English coast (660 ft.): and in this formidable cliff the whole series of strata, from the sandstone which caps the upper lias, to a certain depth in the lower lias, may be recognised. The alum-works, at either end of the highest part of the cliff, now abandoned for the most part, once afforded great facilities for this examination."—Phillips.

The wooded glens, which descend from the moors inland, are sometimes very picturesque. Near Lofthouse (ch. modern, 1811; on the W. side of the village is an ancient circ. mound and intrenchment), which stands on the edge of them, an upright stone is shown. said to mark the haunt of the "grisly worm," or dragon, killed, says tradition, by a certain "Scaw," whose story resembles that of Sir John Convers, the slaver of the famous dragon of Sockburne in Durham. (The stories of the Lambton worm, and of "the laidly worm of Spindleston heugh," are of the same character.) A coffinlid, carved with a sword, dug up on the site of Handale Priory (for Benedictine nuns, founded by Wm. de Perci 1133-no relics remain), at the head of the Lofthouse glen, was supposed to have belonged to the "dragon-killer," but it really differed not at all from hundred of similar coffin-lids found in the N. of England.

as busy as sand-martins." Here Cook tham coast (Hartlebool, and farther N.) is plainly visible. Skinningrove, a village at the mouth of a narrow valley, into which, somewhat higher up, many wooded glens open, is famous for the capture of a "sea-man" about the year 1535, who was kept many weeks in an old house "with raw fish to eat, for all other fare he refused." He escaped at last to the sea, and returned no more. Much ironstone is dug here. On the side of one of the upper glens, overhanging the stream, are the scanty ruins of Kilton Castle, long a stronghold of the Thwengs. Passing beyond Skinningrove, the tumulus-like Freebrouak Hill (see Rte. 15) is seen inland, and Roseberry Topping (Rte. 15) beyond it. Hunteliff Nab then rears its long dark precipice, 360 ft. above the sea; and beyond it is Saltburn (Rte. 17), with its excellent hotels, the Zetland and the Alexandra.

ROUTE 15.

WHITBY TO STOCKTON-UPON-TEES. STOKESLEY. (GUISBOROUGH. ROSEBERRY TOPPING.)

(North Yorkshire and Cleveland Branch of N.E. Railway.)

4 Trains daily, in 2 hours. This line joins the rly. from Whitby to Pickering at

Grosmont Junct. Stat., see Rte. 14. From the cliffs at Boulby the Dur- whence it runs through the upper

valley of the Esk to Castleton, and | Danby station, a walk of between then, skirting the Cleveland hills, to Stokesley to the Picton Junction stat., on the line between Northallerton and Stockton. Its course, as far as Stokesley, is through wild and very picturesque scenery. From Grosmont this line runs entirely through the district of Cleveland (see Introd.), which here justifies its name (as on the coast, Kliffond, O. Norse - the Cliff land). It is to the country between the hills and the sea that the old rhyme applies—

"Cleveland in the clay: Bring in two soles, carry one away."

For Egton Bridge, stat. beyond Grosmont, see Rte. 14 (Exc. b, from Whitby). At

Glaisdale Stat. (Rte. 14, id).

The next stat. is Lealholm Bridge; above which the river makes its way through Crunkley Gill, a narrow pass between precipitous scars of rock. The rly, is carried by a deep cutting through the hill to avoid this pass, which remains solitary and very beau-Beyond it, Great Fryupdale sends its beck to the Esk; a moorland ridge, with Danby Crag jutting from its northern face, separates Great from Little Fryup. Danby Beacon (988 ft.) rises rt. of the rly., and Danby Castle is seen on the high ground, l. Danby Lodge, belonging to Lord Downe.

Danly Stat.

good pedestrian may walk from Lealholm Bridge, across Danby Beacon, to the British settlement on Danby Moor, and thence to the stat. at Danby. The entire distance (over rough ground) will be between 8 and 10 m. Or he may proceed along the S. bank of the river, passing the "end" of the Fryup dales, to Danby Castle—well worth the antiquary's attention — and thence to Yorkshire estates [Yorkshire.]

4 and 5 m.

(a) From Danby Beacon the view is very extensive in the direction of Whitby, and over the moors westward. The hill itself (like Roseberry Topping, and most of the Cleveland hills) is of the lower sandstone, which belongs to the lower colitic series. About 11 m. due N. of it (between the Beacon and Wapely New Inn) is perhaps the most remarkable of the many British "settlements" on the Yorkshire moors. The pits, or hut foundations, "are in two parallel lines, bounded externally by banks, and divided internally by an open space like a street. A stream divides the settlement into two parts. In the most westerly part is a circ. walled space, 35 ft. in diameter."—Phillips. (This, however, is only a larger hutpit, and the vallum or bank which runs outside the row of pits is made to encompass this larger one entirely. It has been observed that in most of the Dartmoor hut-villages there is one circle of greater size and importance than the others—the hut of the chief.) To the N. is one tall stone, called Danby Long Stone; and 100 paces to the S. are 3 large tumuli, that in the centre about 70 ft. in diam. and girt round the bottom with fair-sized stones. are 100 ft. apart. The central tumulus has been opened by ancient treasure-seekers (who smashed the urn or urns of the chief interment), and by modern antiquaries early in the present century.

(b) Danby Castle, now belonging to Lord Down, was founded by the Latimers in the 14th cent. The lordship, with others in N. Yorkshire, was given by the Conqueror to Robert de Baus (see Castleton. post, and Skelton, Rte. 17). The Bruces held it until 1271, when their great fell to

heiresses, one of whom married Mar- in which the court leets are still held. maduke de Thweng. His granddaughter conveyed Danby to Wm. Latimer, and a branch of the Nevilles (also by marriage) became Lords Latimer and owners of Danby: until. temp. Eliz., their line also ended in females, the eldest of whom (retaining Danby) was wife of Sir John Danvers. Their son was Charles I.'s Earl of Danby-a title which died with him. but was revived in 1674 for Thomas Osborne, afterwards (for his share in bringing in William III.) created Duke of Leeds. Sir John Danvers (father of the Earl) sold the greater part of the estate to 5 Danby freeholders; and the residue, about 2500 acres, with the manor and its rights, was sold to Mr., afterwards Sir John, Dawnay, whose descendant, Lord Dawne, retains it.

The castle-which is surrounded by wild and free hunting-groundstands finely, with a wide view over the valley of the Esk. Its plan seems to have been a long parallelogram, with a central ourt, and square blocks projecting at the angles. From some shields of arms inserted in the N. front (including Bruce, Latimer, and Thweng, but without that of Neville), it is probable that the castle was built 1320-1370perhaps by William Latimer, 4th Baron Latimer, who died in 1380, leaving an only daughter and heiress, Elizabeth, afterwards married to John de Neville, of Raby. The angular projections, S.W. and S.E., were considerably extended, apparently early in the 17th cent. One of these additions is occupied as a farmhouse; the other has been destroyed, but foundations may still be traced. window openings in the N. front are few and narrow. The kitchens seem to have been here, and the principal chambers (perhaps) in the N.E. angle. In the inner court is a very picturesque chimney on corbels, and a flight of

The whole building is strong and massive—as was necessary so near the Scottish border-and there are few architectural details; but it is worth examination by the antiquary. and the artist may find subjects for his pencil among the broken walls, with ash-trees and rowans springing from them, and harebells fluttering from the ledges. There is a good view of the N. front from the river below; which is crossed by a bridge having the arms of Neville Lord Latimer on its keystone. A tradition in the district asserts that a queen of England once lived in the castle; no doubt Catherine Parr. who married John Lord Latimer.

Castleton Stat., is a good point from which to explore the wild country on either side. A pedestrian who is not very exacting may get bacon and eggand a clean bed at the "Railway Hotel." Castleton itself is a long village, with a mound, called " Castle Hill " (now occupied by a farmhouse), towards its centre. There is no stonework on the surface; but distinct foundations of a Norman castle have been traced here. A Norm. mullion and red-deer horns have been found, and there were 3 mosts or water-defences at different levels. This castle was, no doubt, the work of the Bruces, lords of the whole district after the Conquest; and it probably remained the stronghold of the country until Danby Castle was built, after the Bruces had passed away.

A long, but most delightful walk. may be taken southward from Castleton, proceeding along the crest of Castleton Ridge (the views from which, into Westerdale on one side. and Danbydale on the other, are fine. especially when the evening sun is lighting the valleys with their many tree-circled homesteads), by Ralph steps leading to a room on the wall | Cross to Blakev House. (The distance from Castleton Stat. to Blakev | heather is in flower. House is about 7 m.) Ralph Cross (1409 ft.) is on the high watershed, running E. and W., from which the dales descend N. to the Esk, and S. toward the Derwent. From Blakev House (1325 ft.) there is a magnificent view into Rosedale on one side and Farndale on the other, the two valleys being divided by Blakey (Blakey preserves the old name. "Black-a-moor." by which all this part of Cleveland was formerly Farndale, through which the river Dove runs S., is narrower and more picturesque than Rosedale; but all these dales have the same character. general Each has its "gills" running up into the high moor at the dalehead, wooded here and there, with their birch-trees and hollies dying away into the moorland; and each has its scars of grev rock projecting from the steep sides of heather, that seem to protect the homesteads nestling below. (From Blakey House you may cross to the village of Rosedale, about 4 m.—see Exc. c, from Whitby,—or you may descend Farndale to Kirkby Moor-This will be a long, though most picturesque route, and you will perhaps be inclined to find rough shelter at Gillamoor (at least 8 m. from Blakey House) for the night; but it must be remembered that these remote dales are not to be seen at all without some sacrifice of comfort.) —Returning to Castleton, you may branch off near Ralph Cross, and take a road across Westerdale Moor, which will bring you to the village of Westerdale, marked by the lofty prospect-tower of the Lodge (Colonel the Hon. O. Duncombe). Shortly before reaching the village you pass the "Ref holes" (Roof holes), a number of circ. pits of the same description as those on Danby Moor. The ch. of Westerdale is modernrebuilt 1835. The walk hence to

The runs through Westerdale: and before reaching Castleton is joined by the Basedale beck, descending from a valley, in the higher part of which was a small Cistercian Priory (for nuns), removed here from Nunthorpe by Guido de Bovingcourt, temp. II. There are no remains Hen. whatever, but the situation deserves notice from its extreme solitude.

The scenery N. of Castleton is still wild, but is scarcely so interesting as that S. It will be well seen in a walk across the moors to Freebrough Hill (5 m.), a remarkable circular elevation, like a gigantic An almost extinct piece tumulus. of folk-lore asserts that Arthur and his knights lie within the hill, like the great Emperor Frederick Barbarossa in the vaults of Kifhäuser. ready to start forth in their appointed season. It is natural, since a sandstone quarry has been opened in its side; but the name indicates that the court of the Anglian "Freeburgh " or Tything (above which was the Hundred court) used to assemble here. (There is another such conical hill at Fryup, and Whorlton Hill is of the same character, though less pointed.)

Danby Church, ded. to St. Hilda, in the midst of its vale, is modern and uninteresting, but has replaced a chapel of considerable antiquity. as the dedication indicates. At the parsonage is a collection of flint weapons, urns, &c., gathered from the howes and tumuli with which all these moors are dotted. vicar is the Rev. J. C Atkinson, who during a long residence here has given close attention to the history, antiquities, and dialect of To him we are inthe district. debted for a 'Glossary of the Cleveland Dialect,' and 'Cleveland, An-Castleton commands some striking cient and Modern, -books of very points, most picturesque when the great value, in which the existing

traces of an extensive Dutch colonization of Cleveland are pointed out by a thoroughly competent scholar (see Introd., *Cleveland*).

Leaving Castleton, the rlv. proceeds through Commondale,-more properly, says Graves ('Hist. Cleveland'), Colmandale, but hardly from a cell or resting-place established here by Colman, 3rd Bp. of Lindisfarne, for which there is no shadow of evidence. The name belongs to the general group of the district, and is probably Danish—a wide and pleasant valley, shut in, like the rest, by high moors. (Mountain-ashes, bright in autumn with their scarlet berries, are here marked portions of the colouring.) Sleddale, a valley descending from the Guisborough moors, here sends its beck towards the Esk, which it joins near Castleton. At

Kildale Stat., is a ch. dedicated to St. Cuthbert, and rebuilt 1868. Kildale is the abbreviated form of Ketildale—"Ketil" being a Northern personal name. The Percys (lords of the manor) had a manorial residence here,—now gone. Their name is retained in that of "Percy Cross," on the moorsabove.

(From this stat. an adventurous pedestrian may find his way over the moors to Guisborough—see post

-about 8 m.)

Beyond Kildale, Easby Moor is seen rt., with Cook's monument on its top. This is a tall plain column, seen far and wide over the native district of the great navigator (born at Marton, between Guisborough and Middlesbrough—see Rte. 17), and erected in 1827, at the cost of Mr. Campion of Whitby. N. of Easby is the conical hill of Roseberry Topping. The country soon becomes open on the rt., and the line of the Cleveland Hills, broken, varied, and picturesque, sweeps round to the l.

Battereby Junct. Stat. (Rtc. 15a.) A branch rly. for conveyance of ironstone and minerals passes off rt. (to join the line near Guisborough).

Ingleby Stat., another good point from which to explore the moors and dales S., has a fair Inn. The private rly. of the Rosedale Iron Company here descends the hills by a very steep incline. Permission is sometimes given to strangers to avail themselves of it. The Church, though modernized by ch.wardens 1741, has a N. arcade Norm. (or even Saxon), and in chancel two effigies of priests. Ingleby Manor was a residence of the Lords Eures, and later of the Foulis family.

Burton Head (1419 ft.), l. of the Ingleby Rly., is the highest point of the watershed, which rises gradually from the W. Besides a verv extensive prospect N., across the Tees, and along the far-winding coast of Durham, the moorland views here are magnificent, looking over the dales that pass S. between these heathery ridges. Burton Head is so called in the Ordnance maps; but the true name is Botton (O. Norse botn = a deep hollow), and is in connection with Greenhow botton, a narrow vale below. Danby "botton," is, in a similar way, often refined into "burton," which here is meaningless. Bransdale, dividing Farndale, W., is the narrowest of all these dales; and Biledale, up which runs a tolerably good road, is deep and fine, with high peaks between the glens that branch from it toward the N. end. Edges of freestone rise here and there from its sides, and at the pass out of it N. (the hollow immediately W. of Burton Head) there is a wide view over the low country of Cleveland, with Roseberry Topping conspicuous. The Wainstones, Cranimoor, and Carlton Bankbare peaks W. of Burton Head, and separated from one another by the

glens that unite to form Bilsdale, are all on the line of watershed, which gradually decreases in height from Burton Head. There is an Inn at *Chop Gate*, toward the upper end of Bilsdale, which a pedestrian may find convenient.

Stokesley Stat. is \(\frac{1}{2} \) m. from the town (Inn, Black Swan—comfortable and reasonable), itself without interest, but a centre for some pleasant excursions. Stokesley Church was rebuilt in 1771. In the Town Hall, built 1853, at the sole expense of the late Robert Hildyard, Esq., is a full-length portrait of the founder, by Sir John Watson Gordon.

You may drive from Stokesley to Newton for the ascent of Roseberry Topping, 1 m.,—or the walk, through fields and woods, is very pleasant. On the way you will pass the village of Ayton, where is a large agricultural college. In the village school here Capt. Cook was taught to read. N. of Ayton is Langbargh Ridge (bargh, or "barf," as the word is sounded, is the O. N. biarg, Danish bjærg, and signifies a long, not very elevated, hill) running E. and W. in the line of the basaltic dyke. It gives name to the wapentake, which is co-extensive with the district of Cleveland; and on this ridge the Wapentake The ba-Courts were formerly held. saltic dyke is marked generally by its thicker growth of trees. Roseberry Topping, 1067 ft. above the sea, is a conical peak of lias capped by sandstone, slightly bent toward the N. Its base is clothed with woods and larch plantations; but the summit is a fine mass of broken crag, commanding a wonderful view, singular from the many different heights and ridges which intersect the vast landscape. Easby Moor, with Cook's Monument, is conspicuous S., with the Cleveland range beyond: Guisborough with its red roofs and ruined abbey lies in the valley N., Newton.

with the heights of Kirk- and Upleatham between it and the sea-Rather more W. the smoke of Middlesbrough forges stains the sky,more perpetual "Devil's Kettles" than curling mists on the Cleveland hills, to which, as seen from Roseberry, that unsavoury title was formerly given. Much of the "bishoprick (Durham) lies spread out beyond, and N.W. a vast level stretches away N. of Richmond into Westmoreland. -a rich superb scene, especially with the glow of ripe cornfields on one side, and heather purpling the hills on the other.

Roseberry Topping has undergone a remarkable change of name. From the beginning of the 12th to the end of the 16th cent. the hill in all written documents is called "Othenesbergh" (with many variations of form) and "Ounesberry." "Roseberry" does not appear until after 1600. "Topping" signifies a "crest," or marked eminence, and is found elsewhere on these moors. "Othenesbergh" is, no doubt, the "hill of Odin," and must have been the name imposed by the Danish settlers. The etymology of "Roseberry" is not so clear; but Mr. Atkinson suggests, with great probability, that it is the olden Anglian name, displaced or translated by the Danish, and reappearing in the 17th cent. "Hreosesbeorh" = Roseberry, would be the hill of the "rusher," or "raging one," and thus equivalent to the name of Odin, "the lord of the air, who chases through the sky in the roaring storm."

Roseberry is a sea-mark, and a weather-sign; the old rhyme running—

"When Roseberry Topping wears a cap, Cleveland may beware a clap."

A footpath, seen from the hill, leads into the high road about 2 m. from Guisborough. The summit of Roseberry is 1 m. from the village of Newton.

S. of Stokeslev an expedition may l be made to Whorlton Church and Castle, skirting the hill-country. It may be continued to Mount Grace (Carthusian Priory), and to Osmotherley. There is a good and comfortable country Inn (the Black Horse) at Whorlton, 7 m. from Stokesley. Osmotherley is 12 m. Thence you may cross the country to Northallerton (8 m.), or reach the Welbury Stat., on the N.E. Rly. (4 m.).

In the ch.-vd. of Kirkbu, a short distance off the Whorlton road, are the much mutilated effigies of a knight and lady, of whom local tradition asserts that they killed themselves by (the man) cutting and (the woman) raking a field of corn in one day.

The great number of terminations in by throughout the district again indicates the extent of the Danish settlement in this part of Yorkshire. Busby Hall (George Marwood, Esq.), commanding a very wide view, contains a good St. Cecilia, perhaps by Vandyck; a pair of Dutch town pieces, by J. Mans; and many copies of good pictures and statues.

Faceby Hill, rising over Whorlton, is an excellent landmark. Many bars of silver were found on its side some years since by a man in ploughing, and were thought to have been plunder from Whorlton Castle.

Whorlton Church (dedicated to the Holy Cross) was given by Robert de Meynill (died 1206) to Guisborough Priory. It is Norm. and Dec., with a Perp. (?) tower over the S. porch. The aisles have disappeared; and the Norm. arches are built up on either side. aisle, and the adjoining piers, fell some 50 years since; the piers were rebuilt, hence the difference in height between the 2 sides.) The font is rude Norm. on a circ. pillar. The Meynill (rt.), and Gray (1.).

chancel arch is rude Norm., with roundheaded recesses (perhaps hagioscopes) built up on either side. The chancel, early Dec., with heads at the base of the window mullions, and other corbel-heads for brackets. all covered with whitewash. the N. side is an E. E. chantry. between which and the chancel is a fine Dec. altar-tomb with canopy. This is probably the tomb of Sir Nicholas de Mevnill, who died in 1343, having married a daughter of William Lord Roos. The arms of Meynill are in the canopy, and the water bougets of Roos on the central shield of the altar-tomb. (It is, however, uncertain to whom this tomb should be assigned. On the tomb is placed the oaken effigy of (no doubt) an earlier Sir Nicholas de Meynill (died circ. 1300). He is cross-legged, and wears the hawberk and close hood of mail, with long surcoat, open in front. The effigy is loose on the tomb, and is hollow. It is one of the earliest oaken effigies (rare at any time) in England, and, although of rude execution, it deserves careful attention.

In the walls of the tower many tomb-slabs with crosses are built up.

Henry VIII. gave Whorlton to Stewart, Earl of Lennox, who, by his wife Margaret (niece of Henry VIII.), was father of the Earl of Darnley. husband of Queen Mary of Scotland: and it was during the residence of Margaret Lennox at Whorlton Castle that the intrigues were carried on which ended in that luckless marriage. Whorlton was afterwards granted to Bruce of Kinloss, whose son was created Lord Bruce of Whorlton by Charles I. His representatives, the Earlsof Aylesbury, still possess it.

The gatehouse of the castle remains nearly perfect, and is a very fine example, probably temp. Richard II., as the arms in front indicate. They are Darcy (in the centre), Darcy married Elizabeth Gray of Heton, temp. Richard II.) Above is a shield impaling Darcy and Meynill. There is an outer and inner portal, with an open (once vaulted?) passage between them. and many rooms on either side. Remark the arrangement in the wall for fastening the great outer gates. A staircase (from the rt. near the inner portal), rises to the top. The whole has been protected by a most, which surrounded the castle, and drawbridge. Some vaults, covered with mason's marks, are the only remains of the castle itself, and may be of the 12th cent. There is a wide view from the castle hill. stretching towards Richmond on one side, and to Roseberry Topping on the other.

Scugdale, running up into the high moors, opens beyond Whorlton. From Scarth Nick there is a very fine view, and from the hill above it a still finer, stretching to the mouth of the Tees, and from the great central vale of Yorkshire, beyond Richmond, to the moors over Appleby in Westmoreland. Farther S. the flat summit of Pen Hill in Wensleydale may be distinguished.

The range of hills (still distinguished as the "Cleveland Hills") is here broken at intervals, and is fine in outline, with scars of rock, and much wood clustering below; all are of lias, capped by sandstone. Arnolific (erne = eagle) is a picturesque range of wooded hill, with projecting crags. Close to Arncliffe Hall (Douglas Brown, Esq.) is the modern Church, containing a mutilated effigy (temp. Edward II.) of (probably) Sir Robert de Colville, who was concerned in the death of Gaveston. The arms of Colville are on the stone. He married the daughter of Robert Ingelram, whose family had long been lords here. At Mount Grace we reach the limits of Cleveland. For it and for Osmotherley, see Rtc. 16.

Between Stokesley and Picton Junct. there are stats. at Sexhow, Potto, and Trenholme Bar. The Ch. of Rudby (1½ m. N. of Sexhow Stat.) contains E. E. portions, and is of some interest. It stands on the river Leven (Ueven, Celt.—smooth), which, descending from the hills, winds through this low country, and joins the Tees at Yarm.

Trenholme Stat., 2 m. N. of Crathorne, is said, but most questionably, to have been the residence of the Crathornes from the period of the Conquest. In the ch. is the crosslegged effigy of Sir Wm. Crathorne, circ. 1322. There is a Norm. chancel arch in the ch. of Kirklevington higher up the river; and Castle Levington, in this parish, is a good circular earthwork.

Picton Junct. Stat. The Cleveland line here meets the rly. from Northallerton to Stockton. The border of Yorkshire is soon reached at

Yarm Stat., a small town of no interest. (The name is Danish—Jarum in its old form; there is a Jarum (Hjardum) in S. Jutland.) The ch., rebuilt in 1730, contains an E. window, filled with stained glass by Pecket of York. A 14th cent. bridge, built by Bp. Skirlaw, here spans the Tees, which the rly. crosses by a long viaduct, and proceeds along its Durham bank by

Kaglescliffe Junct. to

Stockton Junct. Stat. (See Handbook for Durham.)

ROUTE 15A.

WHITBY TO QUISBOROUGH AND MIDDLESBROUGH.

As far as

Battersby Junct. Stat. This Route is described in Rte. 15.

Ayton Stat. In this village Capt. Cook went to school.

Nunthorpe Junct. Stat.

Here a branch rly. diverges by

Pinchingthorpe Stat., to

Guisborough Stat.

Guisborough (Inns: Cock, best; Buck.—Pop., in 1881, 6616) is surrounded by some pretty scenery, though few will be inclined to compare it, as Camden has done, with Puteoli in Italy, for "grateful variety and other advantages of nature." Guisborough has become the "capital" of the irondiggers in this neighbourhood, and entire new streets have arisen for their accommodation. The only points of interest here are the priory ruins and the church.

An Augustinian *Priory was

founded here either in 1119 or in 1129 (the date is uncertain), by Robert de Brus (whose brother was the first prior), lord of Skelton (see Rte. 17), and of great part of North Cleveland. It was richly endowed with, among others, the whole manor of Guisborough; and at the Dissolution, when its annual (gross) value was 712L, it was the wealthiest religious house in Yorkshire, except St. Mary's at York, Fountains, and Selby. In 1375 the prior had a licence to fortify his convent, which was too near the border to be quite safe. Hemingford, the Chronicler (Edw. I., II., III.), was a canon of Guisborough; and Robert Pursglove, suffragan Bp. of Hull, was the last prior. "The ch. was burnt down (May 16, 1289) through the carelessness of a plumber at work on the roof, and the canons seem to have set to work at once on its rebuilding. The E. end, very lofty, and conspicuous in all distant views, is the principal relic of this later ch. part of the lateral walls remains except the responds of the arcade, and some fragments which formed the angle with the eastern wall. church was 367 ft. long and 68 ft. wide. The window above the high altar, 60×28 ft., filled nearly the whole of the end of the choir, and must have been one of the largest of its date and style (early Dec.) in England; but the panelled wall below the base has been torn down. and the tracery destroyed. It has been enclosed in a highly enriched moulding of vine-leaves and grapes. and had 2 great sub-arches, surmounted, like the E. window at Ripon, by a wheel enclosing 6 trefoils. On the jambs are the armorial shields of Bruce, Bulmer of Wilton, and Thwenge of Kilton. There are many fragments of Norm. capitals and mouldings in the shattered wall below.

*Priory was has beautifully composed moulding

They are of 3 lights, the tracery formed by 2 quatrefoils surmounted by a trefoil. The lateral windows of the aisles have been similar to them, except that the vineleaf moulding across has not been introduced.

Excavations made by Admiral Chaloner in 1867 laid bare the ground plan of the ch., and brought to light many stone coffins, one of them being that of the founder, or of a later Robert Bruce, the competitor for the Scottish crown.

The Tower of the Gatehouse, with circular arch of Trans.-Norm. date, still remains, opening from the town.

Many of the Bruces, and other great lords of this part of Yorkshire, were interred here. "A passage," says a piece of local "folklore," "leads from the priory to a cave under the hills, in which is a chest of gold, guarded by a raven." The prior is said to have kept "a most pompous house," but there are few remains of the domestic buildings, except the cellar of the refectory.

The Parish Church was given to the priory by the founder. now Perp., and much barbarized. In the porch, under the W. tower, is an altar-tomb, which has been divided so as to allow of one side being fixed to either wall. Dugdale, who gives a plate of it when perfect ('Mon. Ang., ii. 148), says it was "lately in the Priory church." It is of the time of Henry VII., and probably a cenotaph either of Robert Bruce. King of Scotland, or of his grandfather, Robert de Bruce, the competitor for that crown, who was buried in Guisborough Priory in 1294. At the W. end, now in the possession of Admiral Chaloner of Longhull, was the full-length effigy of a king, crowned, holding a sceptre in his | the beck, about 2 m. from the town,

with capitals enriched with oak-I right hand, and the arms of Scotland before him with the other; a smaller figure, crowned and holding a sceptre, standing on each side of him. These, perhaps, represented David Bruce, King of Scotland, and Edward Bruce, King of Ireland. In the spandrels of the arch or niche under which they are placed are shields bearing a lion rampant for Bruce of Skelton. and a saltire and chief for Bruce of Annandale. Five armed figures on the N. side of the tomb bear the former arms on their shields.—three on the S. side the latter. The whole has been smeared with paint.

> Longhull (built 1857) has been the property of the Chaloner family since the reign of Philip and Mary, when the manor, which on the Dissolution fell to the Crown, was granted to Sir Thomas Chaloner. It was this Sir Thomas who began the working of alum in England. Whilst travelling in Italy he is said to have been struck with the resemblance of the soil about the Papal alum-works near Rome to that of Guisborough; and with the fact that in both places the leaves of the trees were of a paler green than usual. On his return he began works here, but found it necessary to smuggle workmen from Rome; the result being that Sir Thomas was excommunicated by the Pope. (The form of this papal excommunication, a copy of which was served on Sir Thomas, is said, with whatever truth. to have served as the original of that in Sterne's 'Tristram Shandy.' Sterne was frequently at Skelton in this neighbourhood, see Rte. 17.) Alum is now little worked here; but ironstone quarries have been opened in many places, - by no means to the improvement of the scenery.

> There is a Spa (chalybeate, now unused), and a very pleasant walk to it through the wood, with waterfalls on

You may continue the walk to Skelton, and if you please, to Saltburn. (For all this country see Saltburn, Rte. 17.)

Returning from Guisborough to

Nunthorpe Junct. Stat., the rly. proceeds by

Ormesley Stat.. 1 m. rt. is Marton, birthplace of Capt. Cook (see Middlesbrough).

Middlesbrough Junct. Stat. in Rte. 17.

ROUTE 16.

YORK TO DARLINGTON, BY THIRSK AND NORTH ALLERTON.

(North-Eastern Railway.)

This line of rly. which passes through the great central vale of York, keeping somewhat W. of the old North road, is at first uninteresting. E. of Poppleton Ch. it crosses the Ouse by a bridge of 3 arches cased with stone, 300 ft. long. Rt. of the line, for at least 15 m., the forest of Galtres (see Rte. 1, Excursion from York) anciently extended.

5½ m. Shipton Stat., the churches of Skelton, Overton, and Nun Monkton, may be visited (see Rte. 1, Excursion from York). The forces under Archbp. Scrope and the Northern lords encamped (1405) at Shipton, whilst Henry IV. was at Pontefract Passing

91 m. Tollerton Stat., we reach

111 m. Alne, where the ch. has some interesting Norm. portions. The portal, with inscriptions among the medallions, deserves special notice. [Easingwold, 2 m. N.E. from Alne, at the foot of the so-called "Howardian" hills, may be visited from this station.

An omnibus meets some of the trains. Easingwold (Pop. 2153) is a pleasant town in a well-wooded country — the northern termination of the ancient forest. The ch. is ancient (Dec., restored 1858; there are some memorial windows of stained glass), but of little interest. On an isolated hill, 3 m. E., are the remains of Crayke Castle; worth a visit. The parish of Crayke is one of those portions of Yorkshire which belong to Durham, and which are said to have been attached to the great monastery there after the shrine of St. Cuthbert had rested on them during its wanderings. They were freed from all burdens by Thomas of Bayeux, the first Norman Archbp. of York, who was ordered to grant such an immunity by St. Cuthbert himself. The saint appeared to the archbp, in sleep, as he rested before his shrine at Durham, cured him of fever, and exacted this reward. The archbp. himself tells the story in an encyclical. Bps. of Durham had a Castle here from a very early period, but the existing (which erarps building should be compared with Sheriff Hutton and Bolton) was built entirely by Bp. Robert Neville (1438-1457). It was one of the Yorkshire

the Parliament of 1646; and it re- (Rte. 18A). At mained in a ruined condition until Wm. Waite, Esq., restored a portion of it and made it his residence. There is a very fine view from the Castle hill, commanding the great plain, with its boundary of hills, and the towers of York, over the old forest ground, southward. Crayke Ch. is late Perp. 1

Between Alne and the next stat. the Howardian hills are seen rt. Crayke Castle is also visible. At

131 m. Raskelf Stat. there is (1 m. E. of the stat.) a Church of some interest, with Trans.-Norm. portions, and a wooden tower, dating perhaps from the 17th cent. (There are oaken towers at Itchinfield, Warnham, and Slinfold in Sussex—all, like Raskelf, in a great forest district. Sussex towers are very late Dec.) The piers in the chancel at Raskelf are also of wood, but earlier. There are some fragments of stained glass.

At this station, and beyond it to Thirsk, the figure of a White Horse is visible on the brow of the Hambleton hills (see post) rt. It was cut in 1857 under the direction of a Mr. Taylor, born at Kilburn (a village under the hill), who, living in London, wished to render his native district conspicuous by this rival of the famous Berkshire steed. white effect is produced by lime laid on the earth from which the turf has been removed. It covers nearly 2 acres.

161 m. Pilmoor Junct. Stat. Here branch lines pass to Boroughbridge (Rie. 19)—and to Knaresborough, by Brafferton.

A Rly. runs E. through Ryedale (between the Hambleton and Howardian hills), by Coxwold and Gilling, to Malton, with a branch from Gilling

castles ordered to be "slighted" by to Helmsley, Rievaulx and Pickering

181 m. Sessay Stat. there is a ch. rebuilt in 1848 by Viscount Downe (Butterfield, archit.). In it is the brass of Thos. Magnus, Archdeacon of the East Riding and "Parson" of Sessay, d. 1550, wearing a cope. was also the last master of St. Leonard's Hospital, York. There is a legend that he was found in the porch of Sessay ch. by some Yorkshire clothiers, who agreed to bring him up among them, calling him "Thomas amang us," afterwards corrupted to "Magnus." Leaving 1. Topcliffe and Baldersby (see Rte. 22), we reach

221 m. Thirsk Junct. Stat. whence a line runs l. to Ripon. An omnibus to the town (1 m.).

Thirsk (Inns: Golden Fleece, best; Three Tuns. Pop. of borough in 1881, 5750) a rather picturesque town with a large agricultural market, is the best station from which to visit the Hambleton hills, and the pleasant scenery of their western slopes Thirsk, from the time of the Conquest, was the "Caput baronise" of the great house of Mowbray, --- whose castle here was pulled down temp. Hen. II. No traces remain; and the sole point of interest in the town is

The *Church (said-but most improbably, judging from its masonryto have been built with the stone of the Mowbray's castle), which will strike and interest the ordinary tourist no less than the professed archseologist. It is throughout Perp., and underwent sparing but judicious restoration at the hands of Ed. Street, at a cost of 7000l., 1874. It was given by Roger de Mowbray, temp. Rich. L, to the Priory of Newburgh; and since the Dissolution has been in the patronage of the Archbp. On the exterior remark the lofty tower with

of the Virgin and Child in a niche over the W. window; the open parapets above the windows of the aisles and clerestory; the staged buttresses which rise between these windows; and the singular gurgoyles projecting from them at the basis of their pin-Within, the main arcade is of unusual beauty and purity; above it are lofty clerestory windows, of the same design as those in the aisles; and the superb original roof (said to be of Irish oak) remains untouched in both nave and aislesmuch enriched with carved bosses. and with figures of angels bearing shields. The font also retains its original Perp. canopy. There are some good old bench-ends in the S. aisle; and the eastern bays of both aisles are separated by screens of carved oak, of the usual Yorkshire type. The arch between the nave and chancel is modern. The chancel itself was restored in 1844, when an entirely new roof was placed on it of the same general character as that in the nave, but not so good. There are three sedilia; and a trefoiled niche on either side of the altar. The glass in the E. window was painted by Lady Frankland Russell of Thirkleby Park, and her daughters. The altar is a table of carved oak, said (without much reason, since it is apparently of later date) to have belonged to Byland Abbey; curious and worth preservation. In the E. window of the S. aisle is some good old Perp. glass, in which, besides a head of Our Lord, the figures of St. Margaret, St. Catherine, St. Giles, St. Leonard, Anna, and Cleophas are conspicuous. There are besides many coats-of-arms, including France and England quarterly, and the lion of Mowbray. On the N. side of the chancel a panelled door opens to a staircase leading to what is called a crypt, but which is in effect a room aboveground (the ch. stands on a bank, overlooking the Caldbeck, a

its massive buttresses, and a figure tributary of the Swale), now used as of the Virgin and Child in a niche over the W. window; the open parapets above the windows of the aisles square padlock, should be noticed.

Thirkleby, 4 m. S.E. of Thirsk, was the seat of the late Sir R. Frankland Russell, Bart., and now of Sir Wm. Payne Gallwey, Bart. It is approached by a long and remarkable avenue of Scots fir. The ch. was rebuilt (1850) as a memorial of Sir R. F. Russell, by his widow. Roger de Thirkleby, Chief Justice of the Court of Common Pleas, 1242, was a native of this place.

[Kilvingtun Church, on the road to Stockton, 1½ m. N. of Thirsk, is chiefly early Dec., but has some more ancient portions. The chancel arch is unusual. The stunted piers on either side rest on a solid wall, to which a chancel screen, or pierced gates, may have been fastened. The font bears the name of Thos. Lord Scrope (d. 1494) and Elizabeth his wife. (See Archæologia, vol. xvi.) At the vicarage are some drawings by Turner.

Leaks Church, 5 m. farther on the same road, suffered greatly during the Scottish foray of 1319, when the town of Northallerton was burnt. contains some early portions, and fragments of 14th cent. screenwork. One of the bells is said to have been brought from Rievaulx. There are indications that a large village once existed near the ch., but it seems to have been entirely destroyed by the Scots, and was never rebuilt. benefice is included in Archbp. Melton's return of churches, of which the valuation guiding the payment of tithes was to be reduced on account of this foray. In 1852 a mass of human bones was found buried without arrangement near the ch.-yard, and with them a quantity of silver coins, chiefly temp. Edw. J.

3 m. to the N.E. of Leake is the ateresting little ch. of All Saints, ber Silton. In the chancel are the emains of an elaborately carved creen. The arms of Neville and scrope, Archbps. of York in the 14th ent., are yet to be seen on the nave oof. The ch. is in a disgraceful state of disrepair.

The Hambleton Hills, which here bound on the E. the great central plain (generally known as the "plain of York" farther S.; but here, from its ancient lords, as the "plain of Mowbray"), rise about 5 m. W. of Thirsk. They consist of the unner colitic (calcareous) strata, which range S. of the lower colite forming the northern moorlands and the Cleveland hills. These calcareous hills range W. from Scarborough Castle to Black Hambleton (1289 ft.), which is their highest point. Here they turn S.; and at Kilburn Common trend away sharply toward the S.E. The vale of the Rye divides these calcareous hills from the range of lower colite forming the so-called Howardian hills.

The Hambleton hills are steeply escarped toward the N. and W. On the W. side three great precipices occur, one above Boltby, another opposite Thirsk, and a third at Rolston, where the hills turn S.E. These "great inland cliffs, which are among the most striking phenomena of Yorkshire, only differ from seacliffs because the water no longer beats against them. The Hambleton hills, the wolds . . . were cliffs against a wide sea."—Phillips.

Whitestone Cliff (that opposite Thirsk) is especially worthy of a visit; and the country all along the foot of the hills is very pleasant and picturesque—well-wooded, and affording striking views S. and W. You may proceed from Thirsk to Feliskirk, where is a ch. worth notice—themes to Gormire—and then climb

Whitestone Cliff,—returning to Thirsk by the village of Sutton. This round will be about 15 m. (You may drive, or a good pedestrian may walk across the hills by Rievaulx to Helmsley.) From Whitestone Cliff to Helmsley is about 10 m., but of very rough walking and still rougher driving. The scenery is very beautiful.

Feliskirk, 21 m. from Thirsk (the ch. is dedicated to St. Felix, the "Apostle" and first bishop (630-647) of the East Anglians-there was a close connection between the royal house of E. Anglia and that of Northumbria), nestles in a hollow between wooded hills. which has been almost rebuilt (Dykes, architect), is nevertheless interesting. It is Norm., with early Dec. S. aisle (piers and arches), and an entirely new N. aisle and chancel apse. The latter follows the plan of the old apse, which had been cut off with a flat eastern end in the Perp. period. It is Norm., with a wall arcade, and 3 windows with stepped sills above. Here are two very good effigies perfect to the minutest details, a knight and a lady, circ. 1310; which have been assigned to the De Ros family. Remark the strings for tying the chain mail at the wrists; and the graceful manner in which the lady's robe is folded round her feet, which are visible. The stained glass has been collected from different parts of the ch., and placed in the window above the knight's effigy. A shield with the three water bougets of De Ros occurs among the fragments. Byland Abbey possessed some property in this parish; but the ch. at the Dissolution belonged to the Preceptory of Mount St. John.

Affording striking views S. and W. | Close above Feliskirk is **Mount St.**You may proceed from Thirsk to Feliskirk, where is a ch. worth notice thence to Gormire—and then climb | J and E. Walker), where was a Pre-

ceptory of Knights Hospitallers. There | occurred as far back as the glacial are no remains worth notice.

(1 m. N.W. of Feliskirk is Nevison House, said to have been the occasional residence of Nevison, one of the most famous freebooters of the 17th cent. He was called by Chas. II. "Swift Nick," and is said to have been the true hero of the ride to York, generally assigned to Turpin. New Building, at Kirkby Knowle (2) m. N.) was bought by James Danby, Esq., from the Constables, in 1653. He enlarged the mansion. It is a curious house (now a farm), with a secret chamber or hiding-place. There is a very fine view from it. 1 m. S. of New Building is Upsall Castle, once a seat of a family of the same name, of whom Sir Geoffry de Upsale, probably the last of the race, d. in 1349; and afterwards the chief residence of the Lords Scrope, of Masham and Upsal, one of whom built the house, which has been quadrangular; with towers corners. It is now a farm. There is a very extensive prospect from this beautiful site.)

A pleasant, wooded road, with fine views S., and the heathy moors and cliffs rising in front, leads from Feliskirk to Gormire (3 m.). This, the only considerable "tarn" of the E. Yorkshire hills, is about 2 m. in circumference. On the E. rises for about 500 ft. the steep slope of the embankment, thickly strewn with fragments from Whitestone Cliff. which forms 100 ft. of sheer precipice at the back. On the other sides of the lake is a high ridge of arenaceous hill. "There are no streams except the mere runnels of the hill-bank which flow into it, and none flow from it: so that its waters are mainly supplied by rain, and diminished by evaporation."—J. G. B. The hollow of the lake was probably formed by a great landslip, which may have Whitestone Cliff is sometimes called

period. The road winds round the lake. and then climbs the hill (which is one of the worst in Yorkshire for horses to get up, if the carriage be at at all heavy), amid scenes of great beauty. "From the summit of Whitestone Cliff the view on a clear day is very fine and extensive. Immediately beneath are the precipice and the lake, and the steep embankment. covered with thickets of brake and blackthorn, and thickly strewn with fallen piles, confusedly upheaped, of massive and angular rocks. From Boltby Moor, southward to Hook Hill. a pleasant, undulated, wooded tract extends; and beyond, the broad central valley is spread out like a map from the Tees southward as far as York, with Thirsk and Ripon marked conspicuously, and the lines of railway easily traceable by the smoke of passing and repassing trains. beyond stretch the western moors. the huge bulk of Penhill looming in front to shut in Wensleydale like a barrier; and the higher great Whernside Peak, on the S. of it, for a focus from which the undulated lines of hill stretch N. and S. till they are lost to view in misty distance."-J. G. Baker. This is the scene of Wordsworth's well-known sonnet :-

"Dark and more dark the shades of evening

The wished-for point was reached, but late the hour.

And little could be gained from all that dower

Of prospect, whereof many thousands tell; Yet did the glowing West in all its power Salute us:-there stood Indian citadel Temple of Greece, and Minster with its

tower

Substantially expressed,—a place for bell Or clock to toll from.—Many a tempting

With groves that never were imagined, lay 'Midst seas how steadfast ! object for the eye Of silent rapture; but we felt the while We should forget them; they are of the

And from our earthly memory fade away."

Crag," and there is a legend that "once on a time" a white mare. carrying a young lady, took fright, and bounded over it. The body of the young lady, it is added, was never found. The name "White Mear" is probably a corruption of white "mire," or "mere," referring to the lake now known as Gormire.

The Hambleton hills, from Black Hambleton to Whitestone Cliff, have long been used as a race-course and a training-ground; and it is possible that a restive horse may at some time carried its rider over the cliff. (On the moor above Gormire is the Hambleton Hotel, with indifferent accommodation, but with stables for race-There were annual races horses.) at Black Hambleton from 1715 to 1770. This "mear" must not be confounded with the white mare on the hill-side above Rolstone (see ante). A local rhyme runs :---

" When Gormire riggs shall be covered with hay. The white mare of Whitestone Cliff will bear it away.'

(2 m. S. of Gormire is Hood Grange, near which the Mowbrays had a castle. At the Grange are the walls of an ancient chapel, which, perhaps, marks the site of the hermitage where the monks were received who afterwards settled at Byland. (See Rte. 18.) On the top of Hood Hill is a large stone, said to have been dropped there by the devil in his flight.)

Ancient dykes and tumuli occur frequently on the Hambleton hills, which are covered with short bent grass, mixed with heather and bilberries; and such names as "Scotch Corner" and "Douglas Ridge" (the latter on the Clevelands, opposite Black Hambleton) may perhaps be traced to the great forays of 1319 and 1322, when the Scots, under the

"the White Mear," or "White Mare | part of Yorkshire, and (in the latter year), after surprising and taking prisoner the Earl of Richmond. in the hills between Byland and Rievaulx, nearly made a captive of Edward II. himself, who was obliged to fly in all haste from Rievaulx.]

Thirsk to N. Allerton.

Proceeding N. from Thirsk, the rly. passes rt. the seat of Earl Cathcart, a little to the E. of Thornton-le-Street (on the line of a Roman road from Catterick—Cataractonium —to York. At Thornton-le-Street Hall (Earl Cathcart), formerly called "Wood End," there is a good collection of pictures,-four deserving particular notice:-(1.) A portrait of Mary Queen of Scots, crowned, supposed to have been painted by Richard Stephens, a Flemish artist; and said to have been brought by Charles, 8th Lord Cathcart, who was educated at Leyden, from the ch. of St. Andrew at Antwerp. A portrait of the Queen. engraved on copper, still exists in that ch. on the upper part of a mural monument to the memory of Barbara Mowbray and Elizabeth Curle, women of her bedchamber, who, after her execution, "fled from their country to the protection of the Catholic King. on account of the true religion." (2.) A Claude, verified by the Liber Veritatis. (3.) A painting on panel, probably by Broughel, which has the brand of Charles I., and the inscription "Given to the King by my Lord Newcastle, 1634." (4.) An original likeness of Napoleon I., purchased at St. Petersburg by the 1st Earl, when ambassador at that court. Behind the picture is the certificate, "Le portrait a été fait moi d'après nature, pendant le déjeuner de Napoléon après la paix de Tilsit.-Riesener." The Church of Thornton contains monuments of the Cromptons, Talbots, and Pudseys. Black Douglas, devastated all this Nearly opposite, I of the rly., is

Kirkby Wiske (on the river Wiske | only a fragment of the intrenchments (wisge. Celt. = water, the most sluggish of Yorkshire streams, which ioins the Swale a short distance S.). remarkable as the birthplace (1515) of Roger Ascham, the friend of Lady Jane Grev and the tutor of Queen Elizabeth. His father was steward to the Scropes. Dr. George Hickes, and Dr. Palliser, Archbp. of Tuam, were also born here. The ch. (restored 1872, G. E. Street, archit.) has a richly ornamented Norm. doorway on the S. side of the nave, and a fine Dec. chancel, with some fragments of stained glass in the E. window. Passing

261 m. Otterington Stat., we reach

30 m. North Allerton Junct. Stat.

(l. Railways run to Bedale and Leyburn, Rte. 23; to Hawes rt. by Picton Junction to Stockton, and S. to Ripon and Harrogatesee post).

Pop. of borough in 1881, 3692. Inn: the Golden Lion, representing the Black Swan of Sydney Smith, which never existed. " I shall he glad to hear," he writes to Lady Grey, "that you are safely landed in Portman Square with all your young ones: but do not set off too soon, or you will be laid up at the Black Swan, Northallerton, or the Elephant and Castle, Boroughbridge; and your bill will come to a thousand pounds, besides the waiter, who will most probably apply for a place under Government."

The visitor may try whether the "humming northern ale" of this place is as admirable as in the days of one George Meryton, sometime an attorney here, who (16s5), in verses praising "Yorkshire ale," asserts that

" Northallerton, in Yorkshire, does excell All England, nay, all Europe, for strong ale.

North Allerton (the many Allertons in Yorkshire are probably named from the alder-tree—ælr, A.-S.; Lower Sax. eller, still used in Yorkshire) consists mainly of one long and broad street, with the ch. (the sole point of interest in the town) at its There was a Roman encampment (possibly a station) here, the site of which, known as the

remains. Roman coins, urns, and (it is said) a portion of a votive altar. have been found within the area. The Domesday Survey records the manor of North Allerton as having "soke" (power to administer justice) over certain of the neighbouring manors, which have ever since formed the district known as "Northallertonshire." The manor was given by Rufus to William de Carileph, Bp. of Durham; and (except during the Commonwealth) it remained part of the "land of St. Cuthbert" until 1836, when it passed into the hands of the ecclesiastical commissioners. The bishops built a castle here, which was razed by Hen. II. in 1177, after the defeat and capture of William of Scotland, whom Bp. Hugh Pudsey had been supporting. A palace or manor-house was built on the site (now the cemetery, about 200 yards W. of the ch.). It was occupied, at different times, by Edward I., II., and III.; and in 1502 Margaret, eldest daughter of Henry VII., rested here on her way to her bridegroom, King James of Scotland. This palace was ruined during the civil wars, and no fragment remains.

From its position on the great North road, North Allerton was the usual gathering-place of the Yorkshire men-at-arms, when an expedition against Scotland was on foot. The same cause led to the fighting of the famous battle of the Standard (see post) in its neighbourhood, in 1138; and to the burning of the town by the Scots in 1319 and 1322. "northern earls" were here during the "Rising of the North" in 1569; and many executions took place in North Allerton afterwards. In 1640 the king's forces under Strafford were here; and in 1647 King Charles himself rested here as a prisoner in the hands of the Scots. (He was lodged in the "Porch House" near "Castle Hills," adjoins the rly., but the ch., now much modernised.) The Duke of Cumberland's army, on its way to Scotland in 1745, was encamped for some time on the Castle Hills; the intrenchments were then perfect.

The Church of North Allerton was given with the other "churches of St. Cuthbert" in Yorkshire, by Bp. Hugh Pudsey, to the Prior and Convent of Durham. It is said to have been burnt by the Scots in 1318; but this can only mean that the woodwork (and probably the central tower) was destroyed. It is cruciform, with a central tower and transepts. N. side of the nave has massive Norm. piers. The S. side is E. Eng., as (but of somewhat later character) are the transepts. The central tower, with its piers, is Perp.; and was the work of Bp. Hatfield (1345-1381) and of Edward III. The chancel was entirely rebuilt in 1779. There is a large Perp. window in the S. transept, and an E. Eng. portal within the S. porch. The font dates from 1662. There are no monuments of interest. Fisher, Bp. of Rochester (beheaded 1535), and Dr. Townsend, author of a 'Chronological Arrangement of the Bible,' were vicars of North Allerton.

The Grammar School (a modern building) was apparently founded at a very early period by the Prior and Convent of Durham. It is remarkable for a company of scholars educated here in the 17th cent., by Thomas Smelt, an "excellent grammarian," of whom some notices are preserved in Hickes's 'Life of Kettlewell.' These were Thomas Burnet (born at Croft in 1635), author of the 'Telluris Theora Sacra,' and one of the best Latinists of his age; Thomas Rymer (born at Appleton Wiske in 1638), William III.'s historiographer, and editor of the 'Fœdera'; George Hickes (born at Newsham in Kirkby Wiske, 1642), the northern antiquary, author of the 'Linguarum Vet. Septent. Thesaurus,' and consecrated [Yorkshire.]

nonjuring Bp. of Thetford in 1693; his brother, John Hickes, who joined the Duke of Monmouth, and was one of the persons for giving shelter to whom Alice Lisle was beheaded—Hickes himself was afterwards taken and hanged at Glastonbury; William Palliser (born at Kirkby Wiske, 1644), Archbp. of Cashel; John Radcliffe (born at Wakefield, 1650), founder of the Radcliffe Library, and of the Observatory at Oxford; and John Kettlewell (born at Low Fields, in the parish of Northallerton, 1653), one of the most learned and excellent of the nonjurors.

Edmund Gheast, Jewell's successor in the see of Salisbury, died 1576,

was born at North Allerton.

Races are held here in October, and continue two days. The course is immediately S. of the rly. station. The House of Correction for the North Riding was removed here from Thirsk about 1783. Here also is the register office for the public registration of all deeds, wills, &c., relating to lands within the North Riding.

More interesting than anything at North Allerton (although there is little to be seen) is the field of the Battle of the Standard, 3 m. N. of the town, a short distance rt. of the great North road. The rly. traverses some earthworks, which formed a strong position. A farm called "Standard Hill," is said, and probably with truth, to mark the position of the famous "Standard." It is generally said that the battle was fought on Cowton Moor, and, although the country is now entirely enclosed, there can be no doubt that it was then an open heath. The Cleveland hills and the high points of Hambleton are seen rt. The Scots were encountered here, on the first open fighting-ground S. of the Tees.

The story of the battle is briefly as follows:—On the accession of Stephen, David of Scotland took

Q

up the cause of his niece the Empress Matilda, and (1136) reached Newcastle with his army at the same time as Stephen, on his way to meet him, had advanced to Durham. A treaty was then signed between the kings: but David also claimed for his son the earldom of Northumberland, in right of his wife Maud, eldest daughter of the great Earl Waltheof. It was in support of this claim, which Stephen did not fully acknowledge, that David again stirred in 1137, and in the following year advanced through Northumberland and Durham, both of which counties were savagely plundered, into Yorkshire. The northern barons, incited greatly by Thurstan, Archbp. of York, who, very aged and feeble, was unable himself to advance beyond Thirsk, assembled in haste, and encamped near North Allerton, having in the midst of their host the "Standard "-a tall mast raised on a fourwheeled platform like the Italian "Carrocio," and bearing, beneath a silver crucifix, and a silver pyx containing the consecrated host, the holy banners of St. Peter of York, St. John of Beverley, and St. Wilfrid of Ripon -the three great protecting saints of Yorkshire. Among the English barons occur the names of Bruce. Baliol, Ferrars, Lacy, Mowbray, Peverell, Percy, L'Espec, and Albemarle. Robert de Brus, according to Aelred, having been from his youth "a friend and familiar to the King of Scots," sought him before the battle, and would have persuaded him to a " peaceable accord " but for the ferocity of the king's nephew, William MacDuncan, who insisted that the battle should go forward. English host was addressed from the platform about the Standard by Walter l'Espec, and by Ralph Bishop of Orkney, commissioned by Archbp. The Bishop concluded with an absolution of all who should fall in the battle; to which there was that the hills re-echoed," and at the on bases halfway up the wall.

same moment the Scots rushed forward with cries of "Albanigh! Albanigh!" The wild men of Galloway, who began the charge, were broken and fled after the death of their leaders; but meanwhile, Prince Henry of Scotland had forced his way beyond the Standard; and the English would have fled on their side, had not an old knight cut off the head of a slain man, and held it up on his lance. crying that it was the head of the king of Scotland. This decided the The Scots, already disbattle. couraged by the flight of the Galloway men, fled in haste; and King David himself was forced to retreat. retired to Carlisle, his host rallying again in such numbers as to make pursuit dangerous. Prince Henry escaped, but with difficulty. Only one English knight, Gilbert de Lacv. was killed; and the total English loss was very small. The Scots did not suffer much on the field; but some thousands were killed in the northern counties after the flight and dispersion. Besides Standard Hill itself, there is a farm about 1 m. S. of it called Scot Pits—from the holes into which the dead bodies of the Scots are said to have been thrown, The field, says John of Hexham, was known as "Baggamoor;" so many sacks and wallets had been left on it by the enemy.

[An excursion of great interest to the archæologist may be made from North Allerton to the remains of Mount Grace Priory, about 7 m. distant. The road passes by Osmotherley, a long village near the mouth of the hollow between the Hambleton and the Cleveland hills. the legendary derivation of motherley" see Rte. 15, Roseberry Topping.) The ch., much barbarised. is long, narrow, and aisleless, with some Norm. portions, and a remarkable early Dec. chancel arch, the a shout of "Amen! Amen!" "so triple shafts supporting which rest

James Strangeways, of Harlsey | the persons in whom Richard II. Castle, directed by his will, dated 1540, that a S. aisle should be added after the deposition of that king, he to the choir as a burial-place for himself and wife, and that 40l. should be expended on it. The tithes of this important parish are in the hands of four laymen, one of whom is resident and a large landowner in the place. The church demands, if not complete restoration, considerable repair, which the vicar, the Rev. H. Jones, M.A., is desirous to see effected. Near the ch. is a commodious school built by the present The Queen Catherine, the best inn in the village, will afford tolerable accommodation to the pedestrian who wishes to explore this neighbourhood. The moors are covered with heather: and Black Hambleton, the highest (1289 ft.) of that range, is conspicuous S.E. The springs of the Rye rise N. of Douglas ridge (the southern point of the Clevelands). You may follow the river S. to Rievaulx (Rte. 18A), a rough but very picturesque pilgrimage of between 12 and 15 m. from Osmotherley, to be attempted by none but thorough lovers of heather and wild scenery.

Mount Grace Priory lies rt. of the Stockton road, about 1 m. N. of Osmotherley. (Either going or returning you should walk across the hill by the Lady-chapel—see post.)

The Priory was founded Carthusians, - whose "observantias sanctas et singulares-valde miramur," says the charter of foundation, -in the year 1397, by Thomas Holland, Earl of Kent, and nephew of Richard II., who had just created him Duke of Surrey. It was established under the name of the "House of Mount Grace of Ingleby," in honour of St. Mary and St Nicholas, and for the "good estates" of Richard II., his queen, the founder and

placed most confidence; and in 1400, was deprived of his title of Duke of Surrey. He then joined his uncle. the Earl of Huntingdon, and other nobles in a plot to kill the new king. Henry IV., during a tournament at Oxford: but their intention was discovered, and the Duke of Surrey was seized at Circncester, and beheaded there, January, 1400-1. A great part of the work of the new priory was still unfinished, and the brethren were in much trouble and perplexity until Henry VI., circ. 1440, confirmed the original grant of the manor (Bordelby) in which the priory stands, and of the lands of Hinckley, Wharram, and Carisbrooke, 3 alien priories, which had been obtained from Rich. II. by the founder. The buildings were then completed, and the gross annual value of Mount Grace, at the Dissolution, was 382l. In 1412, Johanna, widow of the founder, obtained the king's licence to remove her husband's remains from the Abbey of Circucester, where they were buried, and to re-inter them at Mount Grace: but his tomb remains to be discovered.

Mount Grace was one of 9 Carthusian houses in England, the earliest of which was Witham in Somersetshire, founded in 1181 by Henry II., who brought the famous St. Hugh of Lincoln from the Grande Chartreuse to become its first prior. The remains of no English Chartreuse are so perfect or so interesting as these of Mount Grace; and the remarkable difference between the arrangements here, and those of a Cistercian or Benedictine monastery. calls for special attention.

The site of the priory, in meadow ground close under a wooded hill, is very sunny and pleasant. One of the Lascelles family (who became prohis wife. The duke was one of prietors here soon after the Dissolution) converted part of the buildings (into a dwelling-house (now a farm); and his initials, with the date 1654, remain over the door. Here the keys must be obtained. Within the enclosing wall are 2 courts -- the smaller of which, S., contained the guest-hall, and other apartments allotted to strangers; the larger, N., was surrounded by the houses of the In the smaller court, but monks. with access from the inner, was the priory ch. The farmhouse, with its outbuildings, may have been the In kitchens (?) and other offices. the outer court the remains are scanty. although the long narrow guest-hall may be traced on the W. side. houses (14 in number), ranged round the larger court, were of two stories; and each has, by the side of the doorway, a square "hatch" or opening for the reception of food. (This was the arrangement in all Carthusian houses: it may be seen in perfection in that of Miraflores near Burgos, which remains nearly as it was completed about 1480. -See Street's 'Gothic Architecture in Spain.') This inner court seems to have been surrounded by a cloister, and on the S. side is a lavatory. The Church (between which and the wall of the inner court are remains of apartments—the prior's house?) is (This long, narrow, and aisleless. also was a Carthusian rule. No pro-. cessions were ever made in their churches. The chancel has disappeared, except a portion of the N. wall. The central tower rests on 4 high, narrow arches, with a very narrow passage (making a kind of transept) N. and S. Larger transepts or chapels open immediately W. of the tower, lighted N. and S. On the N. side of the very short nave is an opening, by which the monks may have entered the ch. The tower, which has had good windows with foliated headings, is now a mere shell. All the buildings seem to have been plain and massive. The sketcher will find many excellent points, particularly in

the outer court where a large ashtree on the chancel wall adds very picturesquely to the effect. It is much to be desired that these most interesting (and in England unique) remains should be thoroughly examined and planned. They have not as yet received the attention they merit and will reward.

Many fine trees, elms, oaks, and ashes—encircle the priory walls and the ancient fishponds below them. At the back, near St. John's wella copious spring, protected by the monks by a picturesque arch,nath through the wood leads to the top of the hill, where is a ruined "Lady Chapel," built in 1515. was built strongly of squared stone, and had a priest's cell on the N. side. There is little architectural detail: and indeed the plainness of the work here and at the priory deserves notice as in accordance with Carthusian severity. The chapel, on its prominent hill, must have proved a "Dame de bon Secours" to many a wayfarer whom it guided through the woods. So late as 1614 there was such a public resort of "divers and sundrie superstitious and papistlie affected persons" to this "chapel or hermitage," especially on "the Lady's and other saints' eves," as to call for legal interference (see the "writ" against such persons, who "came secretly and closely and for the most part in the night-time," printed in 'Notes and Queries,' Dec. 1861. It is signed by Tobias Matthew, Abp. of York, and by John Thornborough, Bp. of Bristol and Dean of York).

From this point the view over the great plain, with the hills of West Yorkshire in the distance, is wonderful in clear weather. (In most of its features it resembles that from Whitestone Cliff—see ante.) A path leads down the hill to Osmotherley.]

[(On the Stockton rly., between

line beyond Picton, see Rte. 15).]

Leaving North Allerton, and keeping the river Wiske I. (but not seen), the rly. passes l. Hutton Bonville Hall (J. R. W. Hildyard, Esq.), and crossing the Wiske at Birkby (the modern ch. is seen rt.), reaches

371 m. Courton Stat. Much of the ground here passed must have been within the field of the Battle of the Standard (see ante); l. is Pepper Hall The "Vale of (H. Wood, Esq.). Mowbray " is here comparatively level, rich, and wooded; and from Great Smeaton, 2 m. E. of Cowton Stat., fine prospects are commanded. At

39 m. Dalton Junct. Stat., a branch line passes S.W. to Richmond (see Rte. 25), the hills above which are seen l., while the Cleveland hills rise in the distance rt. [Halnaby Hall, 3 m. N. of the Dalton Stat., on the road to Richmond, was the seat of Sir John Milbanke, but was sold by that family some years since, and is now the property of W. H. Wilson-Todd, Esq. Here Byron spent his honeymoon, having been married at Seaham, another seat of his fatherin-law. Sir Ralph Milbanke, in the county of Durham.]

The Tees is crossed at

411 m. Croft Stat., by a viaduct of 4 large arches, commanding fine views up and down the river. Croft (Inn: Croft Spa Hotel) lies on both sides of the Tees, and is resorted to for the sake of its sulphuretted waters, resembling those of Harrogate. building containing the pump-room and baths is faced with a verandah, making a pleasant promenade. The ch., chiefly Dec., with some good principal sight here.

North Allerton and Picton Junction, sculpture in the chancel, contains there are stations at Brompton (where Norm, portions, and the altar-tomb is a large linen (drill) factory) and (without effigy) of Richard Clervaux Welbury. There is nothing, however, — cousin. in the third degree, to the to call for special notice. For the kings of the house of York — died 1490.

> On Croft Bridge each new Bp. of Durham was formerly presented with a falchion, said to be that with which the Worm of Sockburn was slain (see Handbook of Durham), but the custom ceased on the abolition of the Palatinate.

> From Croft excursions may be made by rail to Barnard Castle and Rokeby (see Rte. 26), and to Richmond (Rite. 25); 1 m. to the W. is Clavereux Custle (the Misses Chaytor).

> The county of Durham is entered beyond the Tees, between which and Darlington (at Oxenhall—see Handbook of Durham for a longer notice) are the Hell Kettles—cavities in the rock, probably formed by running water, and now filled with standing water strongly sulphuretted. The 3 largest are about 120 ft. in diam., and from 19 to 14 ft. deep. Skerne runs near, toward the Tees, who speaks thus in Drayton's verse :-

"The Skern, a dainty nymph, saluting Darlington, Comes in to give me ayd, and being proud

and ranke, She chanc'd to looke aside, and spieth near her banke

(That from their loathsome brimms do breathe a sulphurous sweat) Hell-kettles rightly cald, that with the very

sight, This water-nymph, my Skerne, is put in

such affright, That with unusual speed she on her course doth haste,

And rasbly runnes herselfe into my widened waste.—Polvolbion."

441 m. Darlington, see Handbook of Durham. The very fine ch. of St. Cuthbert, Norm. and E. Eng., is the

ROUTE 17.

STOCKTON TO SALTBURN, BY MID-DLESBROUGH AND REDCAR.

(Branch of Stockton and Darlington (N.E.) Rly.)

(For the line from Northallerton to Picton Junct. see Rte. 16; from Picton to Stockton, Rte. 15. For Stockton see Handbook of Durham.) The distance between Stockton and Saltburn takes from \(\frac{1}{2} \) to \(\frac{3}{4} \) hr. Ten trains daily.

Stockton Race-course (where the races, in August, are of some importance) is passed rt. on the Yorkshire side of the Tees—which accompanies the train I. as far as Middlesbrough, whilst the Cleveland hills and Roseberry Topping are seen rt.

Middlesbrough Station was built at a cost of 100,000l.

Inns: Royal H.; Talbot.

While other towns and cities boast of their great age, Middlesbrough is proud of its youth, and still preserves the first house which stood on the spot—the only one in 1820. This "youngest child of England's enterprise," as Mr. Gladstone termed it,

came into existence about 1820; now it contains within the limits of the Municipal Borough 55,288. Its streets measure in the aggregate 50 miles. The Tees, on whose rt. bank it stands, lately a shallow tidal stream, has been dredged into a haven accessible for deep-sea ships, and Docks have been opened from it of 12 acres The first great impulse was given in 1829, when six very clever Quakers, Mr. Pease of Darlington at their head, known as "the Owners." bought 500 acres of land on the rt. bank of the Tees for 20s. an acre! On this ground the town now stands. In 1830 they lengthened the Darlington Railway from Stockton across the Tees to certain Staiths, erected by them for the shipping of their coal, and thus Middlesbrough became a flourishing Coal port, exporting to the extent of a million tons a Owing to the competition of rival ports, this trade began to fall off. and forthwith the founders substituted for it the manufacture of Iron. to this that Middlesbrough owes its renown and prosperity. Making slow progress at first, it assumed gigantic proportions after 1831, when iron ore, previously imported in great part from a distance, was found or discovered by John Vaughan, a practical iron-worker, close at hand, in the very Cleveland hills rising at the back The existence of coal of the town. and iron in abundance, close together and close at hand, gave the greatest impetus to the Works established here by Vaughan in conjunction with H. W. Bolckow, a German of great practical knowledge. Furnaces rose up like mushrooms-10, 20, 50-increasing down to the present time, when Middlesbrough possesses no fewer than 100 Blast Furnaces, some of them the largest in the world, 80 to 90 ft. high, of the most scientific construction, worked with hot air, and capable of "putting out" 500 tons a week; the production of Pig-iron in 1880 was estimated at 1,500,000 tons.

been destined to a career of unvarying prosperity. A serious objection was made to the iron produced here, owing to the Cleveland ore being infested with phosphorus, so as to prevent its conversion into steel; hence a falling off in the demand and another period of depression. Once more the town was rescued from this by the enterprise of its citizens. Messrs. Bolckow and Vaughan, who, by adopting the Gilchrist process, have removed the phosphorus, and in the vast works which they have erected at Eston the iron is now converted into steel of the best quality, and on a scale of unequalled magnitude. No fewer than 6000 men are employed in the furnaces and Middlesbrough, besides forges at many thousands in quarrying iron and limestone.

The works of Messrs. Bolckow and Vaughan, said to be the largest steel works in the world, are a wonderful sight, but are to be seen only by special permission. The "Bessemer Converters," huge iron cylinders from which the red-hot steel is poured out, with coruscations more brilliant than fireworks; the huge shears for cutting iron, the rolling-mills and steamhammers, are all causes of wonder and admiration. The labour is ceaseless day and night, being lighted at night Messrs. Hopkins, by electric light. Gelkes, and Wilson, have also very extensive iron-works.

Subject as this colossal industry has been to frequent fluctuations, one cannot but fear some future interruption to such an unequalled rise and prosperity. Still no one can refuse admiration at such undaunted struggles with difficulties.

Among the great works executed here must be numbered the attempt to convert the mouth of the Tees into a Harbour of Refuge, by throwing out two Breakwaters, the S. Gare, 12,800 ft. long, the N. Gare, 7000 ft. long. They are constructed chiefly wide, main streets, at 6s. per week,

With all this, Middlesbrough has not | of slag from the iron furnaces, which the ironmasters are only too glad to be rid of by payment. These deposits contribute to fix the shifting sands and to deepen the scour at the river mouth.

> At the various works are produced -plates for boilers and shipbuilding, wrought nails, rails, tires, railway fastenings, and machinery. At the Newport wire-mills, telegraph, fencing, and other kinds of wire are made. There are also ship-yards, where iron vessels up to 3000 tons are built. Brick-vards and chemical works contribute their odours: and Messrs. Bolckow and Vaughan have sunk salt-pits here, since a deposit of salt, 100 ft. thick, underlies the town.

Besides the parish Ch. (St. Hilda's), built in 1839, there are 3 or 4 others, and there are various chapels. the rly. stat. is the Ironmasters' and General Exchange, built 1868, at a cost of 35,000l. A Theatre, Free Library, Concert Halls, and other buildings have also arisen, and the number of public edifices increases yearly. The Cleveland Literary and Philosophical Society, with its Library, Museum, Reading-room, and classes, in Corporation Street, afford interesting evidence of educational progress. The Cometery, well laid out, is on the Linthorpe Road; and the Albert Park, an enclosure of 72 acres, was given to the town in 1866 by H. W. F. Bolckow, Esq. about 1 m. from Middlesbrough, on the same road, and has been picturesquely laid out and planted.

Considering the small size of the houses, the rentals varying from 3s. to 6s. per week, the streets are remarkably broad and well paved. editor of this edition visited several of the workmen's houses in 1880, and found them usually clean inside and comfortably furnished. Those in the than superficial observers of their smoke-grimed faces and rough exterior imagine.

Railways. Middlesbrough to Guisborough (Rte. 15A), with stations at Ormsby, Nunthorpe, and Pinchingthorpe. This rly brings much ironstone from the quarries near Guisborough.

To Whitby by Ingleby Junct. To Darlington by Preston Junct.

About 1 m. rt. of Ormsby Stat. is Marton, the birthplace of Captain Cook-born here October 27, 1728. The field in which his father's cottage stood is called "Cook's Garth." the church (which was restored 1846) a tablet to the memory of Cook has been placed by the parishioners; and a school, as an additional memorial, was founded in 1848. The ch. is Norm. (nave) and E. Eng. (chancel). The modern stained glass is by Wailes. The ch.-vd. contains the tombstone of Mary Walker, who taught young Cook to read. His father was a daylabourer in her service. (See Hartley Coleridge's 'Northern Worthies' for an excellent Life of Cook.)

Marton Hall, a large mansion of red brick, with a lofty cupola, was completed in 1869, as a residence for the late H. W. F. Bolckow, Esq. It commands very fine views.

Gunnergate Mansion was built by another ironmaster, Mr. Vaughan. The fitting and painting of the billiard-room alone cost 50,000l.

Opposite Middlesbrough, on the Durham side of the Tees, is Port Clarence—equally a place of smoke and iron. Ferry Steamer across Tees.

have 4 rooms and a back yard, with I that, bustling with the iron trade of washhouse to each. The men are the district-Messrs. Bolckow and more intelligent and better conducted Vaughan have 9 blast furnaces here), we reach

> Eston Stat.: where a branch line conveys ironstone rt. from the Eston quarries at the foot of Eston Nab. Here are Messrs. Bolckow and Vaughan's great Iron Furnaces and Steel Works, see above. It had long been known that the hills of Cleveland contained thick beds of ironstone. which had not been neglected during the Roman period, and which had certainly been worked by the monks of Rievaulx and of Whitby. although many attempts at bringing Cleveland iron into notice had been made during the present century, they were unsuccessful until 1850, when Mr. Vaughan made the discovery himself of the vast seam of ironstone lying in the N.W. side of Eston Moor. He convinced himself of its excellence; made arrangements for working it; and the quarry has since supplied the greater part of the iron manufactured at the Middlesbrough works of Messrs. Bolckow and Vaughan. (For Eston Nab itself. which is best visited from Redcar, see post.)

The ironstone district in this part of Yorkshire extends from Eston and Normanby, past Upleatham, to Guisborough, Skelton, Brotton, and Skinningrove. The principal mining-field occupies a tract of about 30 square miles in extent.

Cargo Fleet Stat.

Southbank Stat.

Redcar Stat. (Inns: Red Lion; Royal, facing the sea; Coatham; Clarendon; Swan: lodgings are numerous and reasonable.) Since 1842 Passing Cleveland Port (an older Redcar has become a watering-place "port" than Middlesbrough, and like of some importance. The village con-

sists of one long street; and has but | reconstituted in 1855, and removed stretch of firm and beautiful sands from Huntcliff Rocks to the Tees level) to mouth, and 1 m. broad at low water. along which you may gallop for 10 m. without drawing bridle. The Durham coast extends opposite; and the mouth of the Tees on one side, and the hills toward Saltburn on the other, form the boundaries. The low cliffs at the foot of which the sands spread themselves are of drifted clay or pebbles, resting on lias.

The whole of this coast is dangerous, and is ill provided with accessible havens. It was long since proposed (but it still remains a proposal) that a harbour of refuge should be formed at Redcar by constructing piers of masonry upon two reefs of rock called the Scars, which admit of passage between them at all times of tide.

Redcar has 2 Piers and an Esplanade formed. There are 2 lifeboats at Redcar.

At East Coatham (1 m. E. of Redcar) is a modern Gothic ch. (built 1854) of which the exterior is far better than the interior. The pulpit, font, and reredos, of Caen stone, were designed by Scott, and have been elaborately decorated in gold and colour.

The Convalescent Home was founded in 1860, enlarged 1869, and the chapel added in 1871. This is very good, of E. Eng. character, with an apsidal chancel and many stainedclass windows by Wailes. The Home accommodates 100 patients, who are received from all parts of England on a subscriber's order. Each convalescent may remain a month, or longer, if desirable. The Grammar School, a Gothic building, was opened in 1869. The school itself was founded at Kirkleatham

recommendation, — the long to Coatham. The church at Coatham is passed in the walk (across the

Kirkleatham (3 m. from Redcar), where the Hospital is one of the lions of the Redcar neighbourhood. This was founded in 1676 by "Sir William Turner, Kt., Lord Mayor of London." long a woollen-draper in St. Paul's Churchvard. He lent Charles II. 3200l. at several times, but was repaid only 1000l. One of his last transactions was a loan of 5001. to "King William upon a tally." Sir William's ancestors had possessed Kirkleatham Hall since 1623. His hospital was founded for 10 old men, 10 old women, 10 boys, and 10 girls. revenue exceeds 1500l. yearly. building (of brick, without architectural character) forms 3 sides of a square, the fourth being closed by an iron grille. In the centre is a figure of Justice. The Chapel, added in 1742, contains a very fine window of stained glass, with figures of Sir William Turner and his brother John, "Sergeant-at-law," with the "Adoration of the Magi" in front. The glass is superb in colour; but nothing is known of its history beyond a tradition that it was the work of "two Italians;" and that Chomley Turner was so gratified with their performance that he gave them 1001. in addition to the 500l. for which it was purchased. Two gilt chairs in the chapel were presents to the hospital from Charles II. There is a Museum. the most remarkable object in which is a carving of St. George and the Dragon cut from a piece of Turkish boxwood—date, later end of 15th cent.; size, 13 in. by 7. In former days of betting it is said that Sir H. V. Tempest wagered 1000 guineas that this carving was not from a single piece of wood. His bet was taken by Sir Chas. Turner, and "St. by Sir Wm. Turner in 1700, was George" was tested with boiling

water and vinegar, but came out | who suffered at Tyburn for his share in scathless. In the Library (consisting of about 2300 vols.) are some good books-mainly divinity and history of the end of the 17th and beginning of the 18th cents. There is a copy of Walton's 'Polyglot' which belonged to Cromwell, and near it one of Castell's Lexicon with the autograph of "Ri. Bentley." The merchant's books of Sir W. Turner are also preserved here.

Kirkleatham Church (built about 1763 by one Robert Corney, a native of Kirkleatham, in much better style and with far greater honesty of construction than was exhibited at that day by men of greater professional eminence) contains a statue of Sergt. John Turner, by Scheemaker, and a full-length brass of Rob. Coulthurst. d. 1631-a very fine example of Towards the E. end that date. is a circular mausoleum, erected in 1740 "to the memory of M. W. Turner, Esq., the best of sons," as an inscription round it testifies. very beautiful silver dish of the 17th cent., richly decorated - now used as the paten-was thrown up by the sea about 100 years since, within the privilege of the lord of the manor. Kirkleatham Hall, refronted and enlarged by Carr of York, who died in 1807, with well-wooded grounds, and commanding good views, has passed from the Turners, and is now the property of A. H. Turner-Newcomen, Esq.

The walk or drive may be continued to Eston Nab (about 3 m. farther), the view from which is superb. In front, as the hill is approached, are the woods of Wilton Castle (Sir Chas. Hugh Lowther, Bart.), a modern house, built from designs of Sir Robert Smirke on the ruins of a castle which belonged to the Bulmers. The village has been entirely rebuilt of late years. The last of the Bulmers of Wilton was Sir John, is a reading-room, and a table-d'hôte

the Pilgrimage of Grace; and whose second wife was the "Lady Bulmer" who was burnt at Smithfield on the same occasion, and whose fate has been specially dwelt on by Froude (H. E., vol. iii.). Wilton Chanel retains some Norm. features, and the effigies of a Bulmer and his wife. temp. Edward I. Eston Nab ("nab' is the name given throughout N.E. Yorkshire to the scarped termination of a hill), 800 ft. high, commands a very fine view W. and N. mouth and estuary of the Tees, and the rich country toward the hills of Richmond, lie mapped out below the spectator. There are many tumuli on the hill, and on Barnaby Moor (its southern end) is a semicircular Roman encampment. A Roman road is said to have passed in this direction from York across the Hambleton

The ironstone quarries, already noticed, are on the N.W. face of the

Leaving Redcar, the rly. skirts the estuary, passing l.

Marske Stat. The Hall, built by Sir William Pennyman, temp. Charles I., is now the property of the Earl of Zetland. The old church, useful as a landmark, is dedicated to St. Germain. The ch. stands on the cliff, and is now used only for burials. Mark's Church was built in 1867, chiefly at the cost of Lord Zetland. The architecture is not English, and the ch. might have been imported from Normandy. The E. window was given by the tenantry of Lord Zetland, as a memorial of the Countess. There are ironstone quarries in the face of the hill rt. We soon reach

Saltburn-by-the-Sea Stat. (Hotels: the Zetland, large and possessing every modern accommodation. There

besides attendance 1s. 6d. Arrangements made for families. To secure rooms it is desirable to write some days beforehand. The Alexandra Hotel, on the cliff, is also very good. The Queen's, near stat.) Saltburn stands at the mouth of 2 wooded glens, each of which sends its streamlet to the sea. The inland scenery is pleasant and picturesque; the coast between Saltburn and Whitby is accessible, and is very fine (See Rte. 14); and the quiet and excellent hotel accommodation render Saltburn by no means the least pleasant of Yorkshire watering-places. There is a firm sandy beach, with good bathing; and a Pier. built in 1867, extends about 500 yards into the sea, and is a pleasant promenade. Steamers touch here almost daily from Scarborough, Whitby, Hartlepool, and Middlesbrough, and afford the means of easy water excursions. A hoist, worked by hydraulic power, and nearly 120 ft. high, may be used for ascending or descending to the sands, and is a great boon to invalids. It leads on to the pier. The cliffs here are fine. Hutcliffe (about 350 ft.) is reached by a footpath passing the coastonard houses; and Rockliffe (550 ft.), on the rt., should also be

Advantage has been taken of the steep sides of the glen, which opens close under the terrace of the Zetland Hotel, to form very picturesque walks, laid out with shrubs and flowers, and with seats at the best points. On the opposite bank of the stream is a newly-built "château" (Rushwood Hall), with peaked roofs and tourelles, belonging to Mr. Bell of Newcastle, one of the great ironmasters of the district. The glen itself is well wooded, and is crossed near the sea by a light iron-girder bridge, 140 ft. high and about 800

during the season. Board and resi- up, a lofty viaduct, raised by the dence in public rooms 10s. 6d. a day, N.E. Rly. Company (Saltburn to Whitby line), which spans the glen, and is 790 ft. long, with a height of 150. You may pass up the glen (beyond the trimly-kept walks) as

Skelton Castle (John Thomas Wharton, Esq.), 2 m. from Saltburn. Skelton is now a very indifferent modern house, but includes a portion of the ancient castle, the "caput baronise"—the head of the great barony of Bruce. It was granted, soon after the Conquest, with 43 lordships in the E. and W. Ridings, and 51 in the N., to Robert de Brus (who was probably one of the Conqueror's followers actively concerned in the reduction of Yorkshire), and the Bruces continued lords of Skelton for many generations. Peter de Brus, one of the confederate barons at Runnymead, granted certain lands at Leconfield to Henry Percy, who married his sister, "on condition that every Christmas-day he and his heirs should come to Skelton Castle, and lead the lady by the arm from her chamber to the chapel,"-a curious and perhaps unique tenure. From the Bruces, Skelton passed (55th Hen. III.) to the Fauconbergs, one of whom married the Bruce heiress. It subsequently became the lordship of Nevilles and Convers, but after the death of the last Lord Conyers, temp. Eliz., the husbands of his 3 daughters and coheiresses quarrelled, and "every one, for despite, ruined that part of the castle whereof he was in possession." In the last cent. it was the property of John Hall Stevenson, author of 'Crazy Tales,' and more noteworthy as the "Eugenius" of Sterne, who often visited him here. "Here it was that Sterne bribed a boy to tie the weathercock with its point to the W., hoping thereby to lure the host from his chamber; for Eugenius would never ft. long, connecting Saltburn with leave his bed while the wind blew Brotton. There is also, much higher from the E., even though good company longed for his presence." Hall | (Rte. 26), may be visited by rly. was the chief member of a not very edifying society, called the "Demoniacs." The ch. of Skelton is modern and uninteresting (rebuilt 1785).

On the hill behind Skelton are very large ironstone quarries. Nearly opposite, and on the road between Guisborough and Saltburn, is U_{p} leatham Hall (Earl of Zetland), with good gardens, laid out in Italian fashion, and fine trees in the park. There is a modern ch. of Norm. The tower, and some character part of the old church, with the font and some curious monumental relics. still remain between the village and the Holebeck. The country between Upleatham and Guisborough is richly wooded and pleasant.

The second glen (that farthest from Saltburn) has no walk through it, but its picturesque scenery will repay a scramble, and the sketcher will find no lack of subjects. It is a peculiarity of these wooded valleys that they are scarcely seen until you are standing on the very edge of the descent, and that you can form no idea of their beauty until you are actually in them.

At Brotton, 21 m. S.E. of the Saltburn Stat., are many ironstone There is a very wide and quarries. beautiful view from the ch.-yd. The ch. itself dates from 1778, and has a good modern stained E. window by Powell and Co.

(For the coast between Saltburn and Whitby, see Rte. 14). Guisborough (6 m.), and Roseberry Topping (3 m. farther), are within a day's excursion. (For both see Rte. 15). A pedestrian may walk from Guisborough across the hills to Kildale (Rtes. 15 and 15A), and thus find himself within reach of the grand mountain and moorland scenery of Cleveland. Richmond (Rte. 25), and the latter part of 'Tristram Shandy.

during the long summer days. (For Whitby, see Rte. 14.)

ROUTE 18.

THIRSK TO MALTON BY COXWOLD BYLAND ABBEY, AND GILLING

N.E. Rly. 8 trains daily in 11 hr.

From Thirsk to Pilmoor Junction the main line is followed (see Rte. 16).

At Pilmoor this branch rly, turns skirting the Hambleton hills, and following the long valley (the lower part of Ryedale), which opens between them and the Howardian hills. scenery is fine, and the line throughout interesting.

Passing rt. (beyond Pilmoor) Husthwaite, where is a small station at which trains stop when required, and where the ch. has Norm, portal and chancel arch, we reach

12 m. Coxwold Stat. Of this very pretty village Lawrence Sterne was the vicar (holding it with that of Sutton-on-the-Forest, which Blackburne gave him in 1738) from 1760 till his death. Here he wrote even Barnard Castle and Rokeby and 'The Sentimental Journey.' "I

am," he says, writing toward the end | part of Yorkshire, is said to mean of his life, when, after foreign wanderings and London gaieties, he retired quietly to Coxwold, and found (or tried to find) some rest and pleasure there-"as happy as a prince at Coxwold, and I wish you could see in how princely a manner I live -tis a land of plenty. I sit down alone to venison, fish, and wild fowl, or a couple of fowls or ducks; with curds, strawberries and cream, and all the simple plenty which a rich valley (under Hambleton hills) can produce. . . . I have a hundred hens and chickens about my yard, and not a parishioner catches a hare or a rabbit, or a trout, but he brings it as an offering to me."

Coxwold Church has a fine Perp. W. tower (octagonal) with an open parapet and gurgoyles resembling (The Priory and those of Thirsk. Convent of Newburgh held the rectorial tithes of both parishes—hence the similarity in the architecture of the churches.) The chancel was rebuilt in 1777; but some fine monuments of the Belasyse family (Earls of Fauconberg) were replaced in it. The earliest (1603) is an altar-tomb with effigies of Sir William Belasyse and his wife; on the base is the inscription-

"Thomas Browne did carve this tome Himself alone, of Hesselwood stone."

There are others for Thos. Earl Fauconberg (the son-in-law of Cromwell) and his son, and for Thos. Beyond the Viscount Fauconberg. ch. rt. is Shandy Hall, the residence of Sterne, now occupied as 3 cottages. It had become dilapidated, and was put into its present state of repair by Sir G. Wombwell. The tenant who succeeded Sterne is said to have found a bundle of his MSS. in a lining for the paper of a room.

" crackbrained "-" crazv.")

John Webster, author of the 'Discovery of supposed Witchcraft,' was born in 1610 at Thornton on the Hill, in Coxwold. He tells a story of an apparition which discovered a murder at Raskelfe, a neighbouring parish.

Close to Coxwold Stat., rt., is Newburgh Park (Sir G. O. Wombwell. Bart., who inherited it from his grandmother, 2nd daughter of the last Lord Fauconberg). The house, which was long the residence of the Lords Fauconberg, occupies the site of an Augustinian Priory, founded by Roger de Mowbray in 1145. (Wm. of Newburg—whose history ends in 1197—was a canon here. The site was given by Henry VIII. to Ant. Belasyse, Ardn. of Colchester, and one of the Commissioners for inquiry into the state of monastic houses, whose descendant was created Lord Fauconberg by Chas. I. His descendant, the 7th and last Baron Fauconberg, died a priest of the R. C. Church at the beginning of this cent. Some portions of the Priory are incorporated in the present house. Many Cromwellian relics, including his sword, watch, and saddle, are preserved here; and there is a tradition that the remains of Cromwell himself, after their disgraceful exhibition at Tyburn, were brought here secretly, and walled up in solid masonry. His daughter Mary was the 2nd wife of the 2nd Lord Fauconberg. Their portraits are preserved here with others of the Fauconbergs; among them one by Vandyck, and another by Gains-borough. In the park are some fine oaks.

[Not quite 2 m. N.E. of Coxwold closet, and to have used them as are the ruins of Byland Abbey, only less interesting than those of Foun-("Shandy," in the dialect of this tains or of Rievaulx. About the

vear 1137, the Abbot of Calder and his brethren, who had left Furness, on the Lancashire coast, to establish a new monastery, were disturbed during an invasion of the country by David King of Scotland. They returned to Furness: but were repulsed by the abbot, and then, bearing with them their little property in a waggon drawn by eight oxen, they set out to seek counsel of Abp. Thurstan at York. As they passed through Thirsk, they were seen by the steward of the Lady Gundreda. widow of Nigel de Albini, and mother of Roger de Mowbray, then a youth in ward to King Stephen. He brought them to his lady's castle; and she, struck with their conversation and bearing, kept them with her for some time, and then placed them at. Hode (near Gormire, under the Hambleton Hills --- see Rte. 16), where her uncle was leading the life of a hermit. The monks remained at Hode till they were removed to Old Byland in 1143, by her son Roger, who was also the founder of the house of Newburgh, and, it is said, of 33 other religious houses. But at Old Byland (on the moor, above the l. bank of the Rye, opposite Rievaulx) they were disturbed by the bells of their brethren of Rievaulx; and they first removed to Stocking, and finally (1177) to the side of the existing ruins.

Amongst the benefactors of Byland figures Sir John Colvile of the Dale—a narrow valley and hamlet among the moors, about 2 m. N. of Old Byland. Many of the Colviles were buried in the ch. of the monastery. They always retained their distinctive title; and that "most furious knight and valorous enemy, Sir John Colevile of the Dale," who was concerned in the rising of the Percys and Abp. Scrope, and who, according to Shakspeare, "yielded himself" to Sir John Falstaff, was of this race.—"Colevile is

your name; a knight is your degree; and your place, the Dale: Colevile shall still be your name; a traitor your degree; and the dungeon your place,—a place deep enough; so shall you still be Coleville of the Dale." 'Henry IV., Pt. II.,' act iv. sc. 3.

In 1322 the Scots made a foray into Yorkshire, and (Oct. 14) took Alan Earl of Richmond prisoner among the hills N. of Byland. Edw. II., who was either here or at Rievaulx, escaped in all haste to York. (See Rte. 18a, Rievaulx.)

The situation of Byland, on open ground under a spur of the Hambletons, is by no means so picturesque as that of Rievaulx, or of Fountains, although there is much wild and pleasant country close at hand. chief mass of ruin is that of the Church, which is Trans.-Norm. and E.E. The composition of the west front is fine. Above a trefoiled portal arch are 3 pointed windows, with a blank arcade between. Over them is a portion of an enormous circular This is E.E. The east window. front has 3 circ.-headed windows. with clustered shafts between, and is more of transitional character; as is a lofty fragment of the N. transept. There was also a circ.-headed window at the end of each aisle. The ch. is of great length, 328 ft. 6 in., and its general effect (owing to this extent, and to the breadth of the square-ended chancel-a Yorkshire characteristic) must have been very fine and unusual. As in Abp. Roger's ch. at Ripon (see Rte. 22). there was a triforium throughout nave, transept, and choir. There is none at Fountains or Kirkstall; and it is not usually found in Cistercian churches. The abbot's house was inhabited within memory, but is now represented by a heap of rubbish at the S.E. angle of the general ruin.

The monastic buildings show little

more than foundations. The ruins | Ring, is about 1 m. N., within a are protected from injury, but have never yet received the thorough examination which has been bestowed on Fountains or on Jervaulx. the Dissolution the site was granted to the Pickerings, and passed from them to the Stapyltons, who still possess it.

At Scawton, 3 m. N. of Byland, is a small Norm. ch., with hagioscopes on each side of the chancel arch. the bellcot is a bell with a founder's shield, and inscription not easily decipherable. It is of the 14th cent.

(From Byland you may walk through pleasant lanes to the stat. or village of Ampleforth, about 4 m. On this road there is a striking view of the abbey ruins at the end of the vale. Or you may walk across the moors (about 7 m.) to Rievaulx, and thence (3 m.) to Helmsley. The road winds up to the moor through wooded hollows. There is a fine view across the great central plain, S.W., and a very beautiful one of Rievaulx as you approach it. The moorland walk is long, but pleasant when the heather is in flower.)]

The next station is

14 m. Ampleforth, about 1 m. from the long, straggling village, which is seen l. The Church has Norm. portions, but was almost entirely rebuilt in 1868. Built into the wall of the tower is the remarkable monument of an unknown knight (temp. Edw. II.), whose head rests on the bosom of his wife. The position is probably unique, and the effigy well deserves notice. It is possibly that of a knight who fell in the battle with the Scots near Byland, in On Ampleforth moors (the last and lowest spur of the Hambletons), at the back of the village, are many tumuli and earthworks—the largest, called Studfold | head and hands appear through the

wide outer embankment, enclosing a pentagonal (?) camp, with a steep agger. W. of the camp a deep ditch, called the Double Dukes. extends for some distance.

l. of the rly., between Ampleforth and the next stat., is a large Roman Catholic College, founded in 1802, by members of the society of Dieu Louard, near Pont-à-Mousson, in Lorraine, who, at the Revolution, were driven from their old home. The situation is very agreeable; and the existing buildings (the ch. built 1857, the wing called the "New College" in 1861) are rather picturesque. The college is a favourite place of education with the Romanist families of the north. It contains a small museum, in which are preserved some relics from the tumuli of the adjoining moors. A great landslip occurred (Nov. 1872) near this place, when some acres of clay glided off the face of the colite beds on which they rested, destroying the road between Ampleforth and Oswald Kirk. At

17 m. Gilling Junct. Stat., a Railway branches l. to Helmsley (see Rte. 18A), whence Rievaulx Abbey may be visited. Kirkby Moorside and Pickering (Rte. 18A). 5 m. rt. is the village of Gilling, and Gilling Castle (Mrs. Barnes). Here the scenery is very pleasing. The tourist should, if possible, arrange to see Gilling church and castle, and then to proceed by train to Helmslev.

Gilling was perhaps the "mark," or original settlement, of the Gillingas, whose name is also recorded in the Kentish and Dorsetshire Gillinghams. The Church, which has been restored, is E. E. (nave) and late In the chancel, Dec. (chancel). under the low arch, is the monument of a knight (temp. Edw. I.), whose

quatrefoil of a cross, the rest of the | took the Royalist side on the breakbody, except the feet, being hid. In the S. aisle of the nave is the monument, with efficies, of Sir Nicholas Fairfax, 3 times High Sheriff of Yorkshire (temp. Hen. VIII. and Eliz.), and two wives, who repose on projecting tablets beneath him.

Through woods and long avenues runs the approach to Gilling Castle, the seat of the Fairfaxes since the reign of Hen. VIII. until the death of the late C. J. Fairfax, Esq. It is now the property of Mrs. Barnes. At the time of the Domesday Survey it was held by "Hugh son of Baldrii:" and it afterwards formed part of the Mowbray fee. The existing castle is a Tudor building, attached on one side to an Edwardian keeptower, and on the other to a wing modernized by Sir John Vanbrugh (or more probably by his assistant, Wakefield, who was employed at Duncombe and Newburgh). work of the Dec. period remains in the lower apartments of the castle, now used as cellars and offices. The dining-room, a very noble apartment of the age of Elizabeth, has a frieze of forest work, decorated with the arms of the gentry of the different Wapentakes of Yorkshire in the year 1585, blazoned in their proper colours. In this room also are 3 windows filled with shields of the Fairfaxes, Stapvltons, and Constables, the work of one Bernard Dininckhoff, 1585; excellent specimens of the painted glass of that period. The gallery, in which are some beautiful carvings, is Vanbrugh's work. In one of the apartments are portraits (on one canvas) by Dobson of Sir Thomas Fairfax, the Parliamentary general, whose "firm unshaken virtue" is celebrated by Milton, and his wife-daughter of Horatio Lord Vere—whose voice was heard during the trial of Charles I. The picture must have been painted

ing out of the war, and died in 1646.

The castle stands on high ground, well surrounded with wood S. Eastward the valley opens, and a very beautiful view toward Stonegrave and Hovingham is obtained. On the S. the ground slopes into a narrow valley, the side of which nearest the house is formed into a succession of terraced gardens, very bright and well kept. The ch. tower rises picturesquely in the middle distance. Altogether, Gilling castle well deserves a visit. Its ivy-clad walls, its gardens glowing with colour, its many peacocks sunning themselves along the walks and terraces, the distant views, and the masses of deep wood crowning the nearer heights. make a series of pictures that will not soon be forgotten.

The village of Nunnington, about 1 m. from the station, stands on high ground above the Rye, but contains nothing to detain the tourist.

Leaving Gilling, and shortly before reaching

Stonegrave Stat., the Church is passed l., which has Norm. piers and arches; it was entirely rebuilt (1863), with the exception of these piers and of the tower. The canopied chancel screen, with the date 1637, has been retained. The tower, in all probability, dates from before the Conquest, and deserves careful attention. Stonegrave was the rectory of Thomas Comber (died 1699), Dean of Durham, and author of more than one valuable work on the 'Book of Common Prayer.' He is buried in the ch., and his descendants, who are still resident in the parish, assisted largely in the rebuilding. In the ch. are 3 efficies one of a cross-legged knight, temp Hen. III. They are for members of soon after their marriage, as Dobson the Thornton family. Some stones, with Runic inscriptions were found in 1745; and at Eastness on the during the recent work, and a cross marked with runes, which has been re-erected in the ch.-vd. At

201 m. Hovingham Stat. (Inn: The Worsley Arms) there is a Spawhich of late years has attracted some notice. The country is pleasant and wooded. The Spa is more than a mile from the village, and the road to it is scarcely passable in wet The Spa-house has a weather. garden, in which 3 springs-sulphursodiac, chalybeate, and pure rock water, are seen bursting forth, and diffusing an odour of rotten eggs. The waters, which are said to be useful in cases of debility, are here the chief attraction. In other respects Hovingham is but a sorry St. Ronan's; and the gaunt scantily furnished hotel ill represents the hostelry of Meg Dods. Many places of interest (all that are included in the present Route) are, however, readily accessible by rail. Hovingham Church was rebuilt in 1860, with the exception of the tower, which is Norm., and has on its S. side a curious piece of sculpture (the base of an Easter sepulchre?) inserted in the wall. The sculpture. perhaps of the 12th cent., represents, besides saints and angels under circ. canopies, the Annunciation. In one compartment is the angel Gabriel; in another, the Virgin seated, with a vase of lilies before her.

Close to the village is the entrance to Hovingham Park (Sir W. Worslev, Bart.), a modern Italian mansion, containing some good pictures, drawings by old masters, and other interesting objects of art,—among them a bust of Cromwell, from whom Sir W. Worsley is descended, through the Franklands of Thirkleby. Hovingham is on the line of a Roman vicinal way, which ran from [Yorkshire.]

same line of road, a sarcophagus was dug up in 1616, bearing an inscription by Val. Vindicianus to his wife and two sons.

You may walk (2 m.) from Hovingham, or proceed by rail to

221 m. Slingsby Stat., where the Castle and Church are worth notice. Mowbray and Hastings (the latter, Earls of Huntingdon) had successively a castle here; and Sir C. Cavendish. who afterwards acquired the manor. is said to have begun the present building about 1603. The moat is no doubt that of the earlier castle, which contained within its precincts a ch. nearly as large as the present parish ch. As the castle now stands, however, it is mainly a Charles I. house, on vaults of The plan seems to earlier date. have been a square, with a square tower containing cameræ privatæ (?) at each angle. There is much enrichment about the frames and pediments of the windows. Ivy covers part of the walls; and the fine trees about the castle group happily for the sketcher. A stone on one of the outer walls (which was taken down to be used as a hearthstone. and is now lost) bore the following inscription: "This house was built by Sir Charles Cavendish, son of Sir Charles Cavendish, and brother to William Duke of Newcastle. was a man of great virtue and learning; died in February 1653; and this is placed here by order of his nephew, Henry Duke of Newcastle in the year 1690."

Slingsby Church (which was mainly E. Eng.) has been pulled down, and another one built from designs by Messrs. Austin and Johnson, the base of the old tower alone being Malton to Aldborough (Isurium). A preserved. The features of the old bath and tesselated pavement (mark-|one are repeated; it was erected at ing the site of a villa) were found here the sole cost of the Hon Admiral

Howard (afterwards Lord Lamerton) Three stained windows (memorial) are by Clayton and Bell. Here is preserved the shattered effigy of a cross-legged knight, temp. Henry III., holding a heart in his clasped hands. He was probably a member of the Wyvill family, resident for many generations at Wyvill Hall in this parish. No traces of their old house remain.

[(From Slingsby, Castle Howard is distant 3 m. (Rtc. 12). The crest of the Howardian hills, over which the road passes, shows a long line of ancient entrenchment. Many tumuli here have been opened, disclosing urns of baked clay.)]

24 m. Barton-le-Street Stat. (gaining its distinctive name from the old Roman road) has a ch. rebuilt at the cost of the late H. F. Meynell Ingram, Esq. (archit., Perkins of Leeds). The style is Norm., and the N. porch retains some rich Norm. sculpture from the former building. At

252 m. Amotherby Stat., the Church has also been restored and the chancel rebuilt, the principal contributor being the vicar, the Rev. C. P. Peach, who himself carved the bench ends and desk in oak, and the pulpit in Caen stone, besides painting 3 lights of the E. window. The character of the restoration is Norm. (Fowler Jones, archit.). Some early crosses, and the effigy of a knight, temp. Ed. II., were found in pulling down the old chancel, and are preserved in the new. The knight was probably one of the Bordesden family, who had lands in this district. The ch. of Appleton-le-Street, 1 m. W., has a Norm. (or perhaps earlier) tower. The line now sweeps round to

30 m. Malton Junct. Stat. (See Rte. 12.)

ROUTE 18A.

GILLING TO PICKERING, BY HELMSLEY
[RIEVAULX ABBEY], KIRKBY MOORSIDE AND LASTINGHAM.—RATI.

For Rail, York or Thirsk to Gilling, see Rte. 18.

This line passes up the pleasant valley of the Rye. Newton Grange was the birthplace of the laborious Yorkshire antiquary, Roger Dodsworth, born 1585. The rly. winds round to

Nunnington Stat.

In Oswaldkirk Church (partly Norm.) Bp. Tillotson preached his first sermon.

Helmsley Stat

Helmsley (Inns: Black Swan, best, and comfortable; Crown; Royal Oak) is an excellent centre from which to visit some of the most interesting places in this part of Yorkshire. Helmsley (Elmeslae in 'Domesday,' from its elm-trees; afterwards known as Hamelac; the whole district, a parish 12 m. from N. to S., probably gives name to the village) stands on the N. bank of the river Rye, and on a line of Roman road which ran from

Bilsdale to Tees Mouth. have been this ancient road by which the Conqueror, after marching (Jan. 1070) from York to the Tees' mouth. descended upon "Hamelac," undergoing infinite difficulties from snow and rough weather on his way. From Hamelac he returned to York.

Helmsley was given by the Conqueror to the Earl of Moreton : passed to the Especs temp. Hen. I.; and to the great house of Ros or Roos by the marriage of Adelina, sister of Walter Espec (the founder of Rievaulx, and one of the leaders in the Battle of the Standard), to Peter de Ros, whose great-grandson Robert, called "Fursan," one of the 25 barons appointed to carry out the provisions of Magna Charta, built a castle here about 1200, which he called "Castle Fursan." His grandson married the heiress of Wm. de Albini, lord of Belvoir, which castle thus became the property of the Ros The direct line of De Ros ended in 1508; but the estates had been confiscated by Edw. IV. (the house of Ros was Lancastrian), and granted to Rich. Duke of Gloucester. They were afterwards restored to Edmund, the last De Ros; whose twin sisters became co-heiresses. Eleanor married Sir Robt. Manners, of Etall in Northumberland, and brought to him Belvoir and Helmsley. A descendant was created Earl of Rutland by Hen. VIII. in 1525. Francis, the 6th earl, had an only daughter, who married George Villiers, 1st Duke of Buckingham. His son was 16 months old when he succeeded to Helmsley; and escaped abroad during the civil wars. Helmsley was granted by the parliament to Fairfax; but in 1644 the castle was still held for the king, and, after Marston Moor and the surrender of York, Fairfax besieged it, and was shot through the shoulder by a musket-ball during the siege. Helmsley Castle surrendered (Nov. 22, 1644) on honourable con-

York through Crayke and Gilling, up | parliament, dismantled, and rendered It must untenable as a fortress.

> The Duke of Buckingham, the famous Zimri of Dryden-

> " Everything by starts, and nothing long "recovered Helmslev on the Restoration, and after the death of Chas. II. it became his favourite residence. He died at Kirkby Moorside in 1687 (see post), and in 1695 his trustees sold Helmsley for 90,000l. to Sir Chas. Duncombe, secretary to the Treasury temp. Jas. II. Thus

" Helmsley, once proud Buckingham's Slid to a scrivener, and a City knight." Pope's Imit. of Horace.

He left it to his nephew, Thos. Brown, who took his name, and built the present house, Duncombe Park, in 1718. His great-grandson was created Baron Feversham in 1826, and in 1868 his descendant was raised to an earldom.

The points of interest in Helmsley are the castle and the church. Castle ruins are on the rt., just within the lodge gates of Duncombe Park, on a natural isolated mound, close to the river. They are surrounded by a double most, and cover altogether about 10 acres. The earthworks that enclose these ditches are interrupted at intervals, and expand in places (the outer line) into broad barriers, and (the inner) into platforms, on which barbicans were erected. plan is rectangular; and "the earthworks are upon a scale not usual with castles of pure Norm. origin, and which, notwithstanding their form, raises a surmise that they may be of much earlier date."—G. T. C. A lofty fragment of the square keep, 96 ft. high, with 3 stories above the dungeon, rises on the E. side of the inner court, but is rent from top to bottom by the force of the explosion which demolished the rest, after the siege in 1644. ditions, and was then, by order of basement and lower story are Trans,-

Norm., but this lower story has been | some Norm. portions of the older ch. altered (the window recesses) in E. Eng. times. It is probably part of the original "Castle Fursan;" but the alterations may have been made by Robert de Ros., who married the heiress of Belvoir. The upper part of the keep, with its battlements and lofty turrets, is temp. Edw. II. tween the outer and inner moats S., is a barbican 233 ft. long, with round towers at each end, and returning angles. The main entrance is in its centre, through a gateway flanked by circ. projecting towers. "This gatehouse is late Norm, or E. Eng. behind the portcullis groove. The groove itself, with all before it, is late Dec., probably of the age of the upper story of the keep."-G. T. C. The whole work, with the barbican on which it stands, is remarkable. S. and N. of the inner ward in which is the keep, the ditches were crossed by drawbridges, of which the piers, counterpiers, and bridge-pits remain quite perfect. The causeway was but 12 ft. broad, so that any body of enemies approaching by it would be placed at a great disadvantage. On the W. side of the inner court is a range of buildings forming the later mansionhouse, partly retaining their roofs. There are traces of Trans.-Norm. and Dec. work, but much of this is Elizabethan, and was probably the work of Edward, 3rd Earl of Rutland and Baron de Ros, died 1587, whose shield remains on the cornice of one of the rooms. But the Villiers arms also occur here. There are foundations of a building (perhaps a chapel) near the keep; and of round towers at each angle of the castle platform. which is mainly of rock. The ditches could be filled from the Elton Beck, which here descends to join the Rye.

Helmsley Church was almost entirely rebuilt in 1869 (C. Barry. archit.), at a cost of 15,000l., the whole contributed by the Earl of

(the chancel arch and S. doorway) were retained. There is much stained glass. In the S. transept is a brass (early part of 16th cent.) probably for Sir Robt. Manners and his wife Eleanor, who (see ante) brought Helmsley to the Rutland family.

Behind the inn, and close to the ch. is the Canon Garth, once the residence of the parish priest, now a poor cottage, with an arched doorway and some other antique portions.

In the market-place is a memorial to the late Lord Feversham, erected by his son. It consists of a Gothic cross, by Sir G. G. Scott, and a statue by Noble (foundation-stone laid May, 1869).

In the neighbourhood of Helmsley are Duncombe Park, Rievaulx (4 m.), Kirkdale (4 m.), and Kirkby Moorside (3 m.). Lastingham (54 m.) may also be reached from here; and an excursion may be made up Bilsdale. (All these are described in the present Route, post).

(a) Duncombe Park (Earl of Feversham) who, with great liberality. allows the grounds to be seen at all times. The house (about 1 m. from Helmsley) was built from a design by Vanbrugh, but not under his personal direction. It is vast and stately, with much of Vanbrugh's "gloomy grandeur;" but is far from being so successful as the greater works-Castle Howard or Blenheim-of the same architect. Wings and a conservatory were added 1845 by Sir Chas. Barry. The house was destroyed by fire 1879, which consumed also part of a very important collection of works of art. Among the antiques which were preserved is a dog of Parian marble, bought in Rome by Henry Constantine Jennings for 801., which sum included its transmission to England. Feversham. The style is Norm., and He refused 1000l. for it; but it was afterwards bought at his sale for a l thousand guineas by Mr. Duncombe, ancestor of the present Lord Feversham. "It bears much resemblance to that in the Uffizi at Florence, called the Dog of Alcibiades, but is more animated and of more careful The left fore-foot workmanship. alone is new."-Waagen. It is said to be the work of the famous Greek sculptor Myron. However this may be, there can be no doubt as to the wonderful life and expression of the marble. Boswell reports some remarks of Dr. Johnson's relating to this dog :-

" F. 'I have been looking at this famous antique marble dog of Mr. Jennings', valued st a thousand guineas, said to be Alcibiades' dog.

"Johnson. 'His tail must be docked. That

was the mark of Alcibiades' dog.'
"E. 'A thousand guineas! The representation of no animal whatever is worth so much. At this rate a dead dog would indeed be better

than a living lion. "Johnson. Sir, it is not the worth of the thing, but of the skill in forming it, which is so highly estimated. Everything that en-larges the sphere of human powers, that shows man can do what he thought he could

not do, is valuable." -Life, vol. vii. p. 60. Here is also a Discobolus or quoitthrower-"a good Roman work of Parian marble."—W.

Among the best pictures, are: -Hogarth-Garrick as Rich. III., the original picture for which Mr. Duncombe, who gave Hogarth the commission, paid him 2001. Guido-David and Abigail (from the Orleans Gallery, engraved by Strange). Jan Both-a fine landscape, with a water-Hobbema-a large, but rather dark landscape. Claude-Two landscapes, good, but not of his best character. Carlo Dolce-Martyrdom of St. Andrew; "a very excellent picture of the master."—Waagen. Bassano-Annunciation to the Shep-Guido-Charity (engraved, very striking); St. Catherine; The Daughter of Herodias. Titian-The

landscape. N. Poussin-A Storm. Leonardo da Vinci-Head of St. State Bedroom :-Baroccio-The Nativity; "Pleasing, careful, and of very transparent colouring."-Wouvermans - Hawking Waagen. Party, very good. Rubens-An old woman and a boy, with a candle; cost 1500l. N. Hilliard-Q. Elizabeth. Small Dining Room:—Guido -Adoration of the Shepherds. the Guidos deserve special notice, as excellent examples of the master

The vast semicircle of park in front of the house, bounded by woods, and unbroken by a single tree, is fine, but somewhat dreary. On the garden side extends the *Great Terrace. commanding one of the most charming views, or rather series of views, in Yorkshire:—over Helmslev, its venerable castle and ch., the richly cultivated expanse of Helmslev Dale, the winding course of the Rye, which here forms a small cascade, the hanging woods which rise on its opposite bank, and the rich stretch of country beyond, in one part backed by the Eastern Wolds. At either end of the terrace is a Grecian temple; one of which, planted on high ground projecting into the valley, is an admirable point of view. No one should leave Duncombe without visiting this terrace.

(b) Rievaulx Abbey (the name, generally vulgarised into "Rivers," is Norm. Fr.="Rye vales" as Jorvaulx is "Yore vales") is 3 m. from Helmslev by the high road, and somewhat farther if the visitor takes the more picturesque path across Duncombe Park, and along the l. bank of the river. But in any case he should make it a point to obtain his first sight of the ruins from the terrace above the valley, to which a gate opens rt. of the high road. This terrace, which Burton justly calls "one of the finest in England," was formed Holy Family, in a very beautiful by Mr. Duncombe about 1754. The

visitor passes through a screen of l evergreens, and suddenly finds himself on a broad level of greensward, with a temple at either end. (One of these temples has an elaborately painted ceiling by an Italian artist; the other is floored with a tesselated pavement from the abbey.) Below winds the stream of the Rve, through its own vale, into which four lesser valleys open; all with narrow threads of greensward lying between their steep. wooded sides. Corn and pasture fields crown the nearer hills, the highest of which, in front, is nearly covered with wood. Bolder and more rugged hill-crests look over from the top of Ryedale (the most conspicuous being Easterside Moor, above the junction of the Rye with the Seph coming down Bilsdale); and all round, in the distance, sweeps the purple heather. The great roofless ch. rises on the l. bank of the river-its walls crested with ferns and grasses and half clothed with ivy. It may safely be said that the scene, from its own beauty and its impressive associations. can scarcely be equalled in England. (N.B.-No Inn at Rievaulx.)

Rievaulx, the first Cistercian house in Yorkshire, was founded in 1131, by Walter Espec-the great baron of Helmsley and of the Battle of the Standard (see Northallerton, Rtc. 16), whose picture has been painted by Ailred, Abbot of Rievaulx—"tall and large, with black hair, a great beard, and a voice like a trumpet" (de Bello Standardi). In 1122 Espec lost his only son by a fall from his horse. He then vowed "to make Christ the heir of a portion of his lands," and founded Kirkham for Augustinians (see Rte. 12). Meanwhile Waverley in Surrey, the first English monastery of Cistercians, was established; and St. Bernard seems to have sent a body of monks from Clairvaux into Yorkshire, recommending them to the care of his friend Abp. Thurstan. By Walter Espec Thurstan's advice,

"vastæ solitudinis et horroris" (W. of Newburgh, i. 14), and precisely such a situation as the austere Cistercians most affected, with the grant of a thousand acres (including Bilsdale and part of Helmsley), most of which were moorland and uncleared wood. After founding Wardon in Bedfordshire, Espec became himself a monk at Rievaulx, died, and was buried here. The piety and humanity of the colony from Clairvaux soon made them known in all directions, and they rapidly became "a great people" (gentem magnam). Much wealth flowed into their house, which occupied a dignified position until the Dissolution. Its first two abbots, William and Waltheof, were personal The third, friends of St. Bernard. Ailred, sent from Rievaulx the colony which founded Melrose, the first house of Cistercians in Scotland. At the Dissolution the gross annual value was 351l. 14s. 6d.

A winding path through the wood leads to the ruins. "Rievaux,"wrote Dorothy Wordsworth, July 9, 1802.—" I went down to look at the ruins: thrushes singing, cattle feeding among the ruins of the abbev; green hillocks about the ruins; these hillocks scattered over with arovelets of wild roses, and covered with wild flowers. I could have stayed in this solemn quiet spot till evening without a thought of moving, but W. was waiting for me."-Life of Wordsworth, i. 186. The ruins consist mainly of the choir and transepts of the Church, and of the refectory. The hospitium, at which travellers were entertained, was on the rt. of the lane leading to Helmsley. gatehouse is first passed; and beyond lies the ch., which stood (most unusually for England, although the position from E. to W. is by no means insisted on elsewhere) nearly from N. to S.—a position rendered necessary by the nature of the ground, hemmed settled them at Rievaulx, then a place in by a steep bank on one side, and

by the Rye on the other. The nave i in 1819, the site of the high altar and is reduced to shapeless mounds of ruin. It was, however, in all probability Norm., and the work of Espec. The lower part of the transcots is Norm., and probably, like the nave, belonged to the first ch. The rest of the transents and the choir are E. E. The choir (of 7 bays, and 144 ft. long, including presbytery and retrochoir) has most graceful clustered piers, with (like the arches) plain mouldings. The triforium (the beauty of which is beyond praise) has in the easternmost bay two circ. arches, each enclosing two subordinate pointed The main arches in the other bays are pointed. Above is a lofty clerestory with wall passage. grace and sharpness of the leafage in the brackets of the vaulting shafts and in the upper quatrefoils deserve special notice. There is more ornament throughout the ch. than was usual in Cistercian houses-far more than occurs in any of the work at The southern (for the Fountains. eastern) end of the choir has two tiers of triplets, much enriched with the tooth ornament, the central light being the loftiest. In the spaces between the lights of the upper tier are small, half-sunk trefoils. A buttress turret, carrying a staircase, remains at the N.E. angle. The sharpness of the stone-capping, and of the stone throughout (which is the calcareous limestone of the district), is remark-The tower arch opening to the choir (75 ft. high) remains, and makes a grand frame to the picture on either The most striking point of view is perhaps about halfway down what was the nave, looking up the choir, with thick masses of ivv clustering over its walls, and a wooded bank seen through the window openings. The grey stone, the floor of greensward, and the mounds of ruin covered with ferns and brushwood. contribute the most exquisite colouring to the picture. The entire ch. was 343 ft. in length. In clearing, described (Rte. 15). There is an Inn

the bases of the columns, a stone coffin was found which, it has been suggested, may have been that of the founder. (It was more probably that of Sir John de Ros, who was buried near the altar. The founder, Espec, is said to have been buried in the Chapter-house.)

W. of the nave (it must be remembered that the W. side here represents what would have been the N.) was the cloister, of which a few arches remain. Opening from their W. wall is the Refectory, with a remarkable trefoil-headed portal (from which there is a fine view of the exterior of the transept) and lancet windows. The recess for the reader's pulpit remains. Below it was a crypt. The refectory is E. E., of the same date as the choir. Some remains of the dormitory (below it N.) are Norm. There are considerable fragments of other buildings, but none calling for special notice; and the general arrangement of a Cistercian monastery will best be understood by a reference to the plan of Fountains, where the remains are more perfect, and have been more thoroughly examined.

Near the bridge at the lower end of the village is a place still called the "Forge;" and judging from the large heaps of slag mixed with charcoal that are still visible in the neighbourhood of the Abbev, there must have been extensive iron-works here, no doubt carried on under the superintendence of the monks.

From Rievaulx you may walk across the moors to Byland. Rte. 18.)

(c) Bilsdale may be visited from Helmsley. A tolerable road runs up the dale, which is wooded, picturesque, and even grand in some parts, with scenery of the character already dern), toward the upper end of the dale, which the pedestrian will find sufficiently comfortable. From this part of Bilsdale you may cross the hill either to Stokesley or to Ingleby The entire distance will Greenhow. be between 23 and 24 m.

On the hill rt., opposite Orterley, is a circle called the Bride Stones. The stream which descends Bilsdale is known as the "Bilsdale Beck" and the "Seph" until near Shaken Bridge it meets the Rve, coming from the N.W. above Black Hambleton. The united streams are known as the Rye (Rhe, Brit. swift? The etymo--logy of Bilsdale is not clear). The scenery on the Rye above Shaken Bridge is picturesque.

(d) Kirkdale and Kirkby Moorside

deserve a visit.

Rail to Pickering.

Newton Stat.

About 11 m. from this is Kirkdale and its Cave, interesting to geologists, but scarcely deserving a visit from others.

The road to Kirkdale, 4 m, from Helmsley, runs at the foot of the calcareous hills, which every here and there send down streamlets through wooded glens to join the Rye. Kirkdale itself is one of these glens; and the Church stands quite alone on the bank of the rocky Hodgebeck (the key is kept at Welburn, nearly 1 m. S.). It is for the most part E. E.; but was restored and the chancel rebuilt 1880. The S. door has been retained from an earlier building: and on a long slab of stone above it is an inscribed Sun-Dial, constructed about the year 1060; and one of the most ancient vernacular inscriptions (of this class) in Europe. The dial is in the centre, semicircular, divided into 8 hour-spaces. Above it are the words-"This is dæges sol merca"

at Chop Gate, near Bilsdale ch. (mo-! " et ilcum tide " (at every time), and "And Haward me wrohte and Brand Prs." (and Haward me wrought and Brand priest). On either side is an inscription, which runs-" Orm Gamal suna bohte scs Gregorius minster thonne hit wes sel to brocan and to falan and he hit let macan nowan from grunde, Chre and Scs Gregorius. in Eadward dagum cag, in Tosti dagum eorl,"-i.e. "Orm, Gamal's son, bought S. Gregorius Minster. when it was all-to broken and to fallen. He caused it to be made new from the ground, to Christ and to S. Gregorius, in Edward's days the king, in Tosti's days the earl." Tosti was the great Earl of Northumbria brother of Harold—who fell, fighting on the side of the Northmen, at Stamford Bridge (see Rte. 8). There is a sun-dial, with an inscription of the same date in the ch. of Aldborough on the E. coast (see Rte. 6); and at Edstone, about 2 m. S.E. of Kirkdale is another, with imperfect inscriptions, "Lothan me wrohte" and "Orlogiratory"-" hour circle." The plain, round-headed doorway below may be part of Orm's work (there are some curious crosses and other marks on the E. side); and within the tower (only accessible from inside the ch.), another and more . remarkable early portal remains. Some early tomb-slabs are built into the N. and S. walls of the tower. The stream (or rather its bed, for the water "sinks" about 1 m. higher up) here is overhung by fine ash-trees; and the quiet and solitude of the little ch.-yd. assist in taking us back to the days of Edward and Earl Tosti.

The famous Kirkdale Capera. which takes us back to far more ancient days—is in a quarry beyond the stream, on the E. side of the dale. Its entrance is now about 30 ft. above the Hodgebeck; but Professor Phillips has suggested that before a channel (this is day's sun mark); and below, was opened in the lime rock at Malton. the Vale of Pickering must have been a great lake, on the edge of which the Kirkdale cave may have opened. It was first explored in 1821, and described by Dr. Buckland in his 'Reliquiæ Diluvianæ'—but with a theory which both himself and other geologists have seen cause to abandon. Great part of Dr. B.'s cavern has long since been quarried away. Like so many other ossiferous caverns, this is in the calcareous limestone which skirts and overlaps the more ancient colites of the northern moors. (See Rte. 14.) It was, during the preglacial period, a den, occupied by successive generations of tigers, bears, wolves, and especially by hyænas, of which alone teeth were found sufficient to furnish 75 individuals. They dragged into it their prey, which sometimes consisted of remains of the elephant and rhinoceros; and when nothing better offered, had no scruple in eating one another. The bones found were almost all cracked and The cavern itself is about 250 ft. long, and from 2 ft. to 14 ft. high; but the entrance is difficult, and as all the bones have been removed, there is little inducement for the ordinary tourist to penetrate it. It was, however, one of the first ossiferous caverns discovered; and as such has its own interest. Excellent and complete examples of the bones found in it may be seen in the museum of the Philosophical Society in York; at Whitby, and at Scarborough.

The banks of the Hodgebeck, above Kirkdale, are very pleasant. The upper part of Kirkdale is known as Sleightholmedale, "And nowhere in the district have we a finer sweep of aboriginal wood than extends along the slopes of this stream; whilst from Sleightholmedale round the escarpment" (of the calcareous hills—which are sharply scarped, like sea-cliffs, toward the N.), "as far westward as Bilsdale, stretches a continuous belt

of larch plantations."—J. G. Baker Kirkdale and Sleightholmedale are, in fact, continuations of Bransdale (locally "Brancedil"), down which the Hodgebeck flows. There is no regular road up Bransdale, which is picturesque, narrow, and wooded in parts.

 m. Kirkby Mooreide Stat. (Inns: The White Horse; King's Head; both good.) This is a small market-town (Pop. in 1871, 1788) of little interest, except as the scene of the Duke of Buckingham's death, which took place, not "in the worst inn's worst room," but in the house of one of the Duke's tenants (it stands in the market-place, next door to the . King's Head Inn), which was then probably the best in the town. A sudden illness, while hunting, obliged the Duke to take shelter here. It is generally said that he was buried in the ch.; but Lord Arran (who was with him at his death) says in a letter to Bp. Sprat, "I have ordered the corpse to be embalmed and carried to Helmsley Castle, and there to remain till my Lady Duchess her pleasure shall be known but I have ordered his intestines to be buried at Helmsley, where his body is to remain till further orders." This letter is dated April 17, 1687; and on the same day his death (or the interment of his bowels) is thus recorded in the register: "1687 April 17th Gorges Vilaus Lord Dooke of Bookingham." The body was afterwards buried by the side of his father in Henry VII.'s Chapel in Westminster Abbey.

Pope's well-known lines, inconsistent as they are with fact, should be read at Kirkby Moorside:—

[&]quot; In the worst inn's worst room, with mat half hung,

The floors of plaster and the walls of dung, On once a flock bed, but repaired with straw, With tape-tied curtains, never meant to draw.

The George and Garter dangling from that bed Where tawdry yellow strove with dirty red,

Great Villiers lies-alas! how changed from him,

That life of pleasure and that soul of whim! Gallant and gay in Cliveden's proud alcove, The bower of wanton Shrewsbury and love;

Or just as gay at council, in a ring
Of mimic statesmen and their merry king.
No wit to flatter left of all his store;
No fool to laugh at—which he valued more.
There, victor of his health, his fortune,
friends

And fame, this lord of useless thousands ends."—Moral Essays.

Dryden's wonderful picture of this "Zimri," in the 'Hind and Panther,' and Sir Walter Scott's in 'Peveril of the Peak,' will also be remembered.

The Church of Kirkby, chiefly Dec., is of little interest. It contains a brass for Lady Brooke, 1600, with 6 sons and 5 daughters. E. of the town is the site (and nothing more) of the castle of the De Stutevilles, commanding a noble view over the Vale of Pickering. The Neviles also had a "hall" here, on the site of the present Tolbooth.

(On Rudland Moor, 6 m. N. of Kirkby Moorside, was a high tumulus called "Obtrush Roque" or Hobthrush's Ruck (heap). Hob Thrush, or "Hob o' th' Hurst," was a woodland and mountain spirit, of whom a story is told, found in various shapes and in the folklore of various nations. A Farndale farmer was so much troubled with Hob that he resolved to "flit;" and as he was journeying with his goods towards his new home, he met a neighbour, who said, "I see you're flitting." The reply came from Hob out of the churn, "Ay, we're flutting"—and the farmer, thinking it was as well to be vexed with Hob in one place as in another, turned back again. The mound was examined in 1836—(see Phillips)—when a stone kist, within a double ring of stones, was found in it. These still remain. "Hob Hurst's House" is the name of a sepulchral mound near Hartington in Derbyshire.)

From Kirkby Moorside you may proceed to Lastingham Ch., 5 m., by a rough, hilly road, through very picturesque scenery. The views up the valley of the Dove, which descends from Farndale, are especially striking.

Lastingham. The old Church is conspicuous on its high bank, as the village is entered. (There is a small Inn near the ch. which may do as a

resting-place.)

In the year 648 (22 years after Edwin had been baptized at York by Paulinus), a monastery was founded at Lastingham by Cedd, then Bishop of the East Angle, "among steep and solitary hills, where you would rather look for the hiding-places of robbers, or the lairs of wild animals, than the abodes of men; so that, according to the words of Isaiah, 'In the habitation of dragons might be grass with reeds and rushes'-that is, the fruit of good works." (Beda, H. E., iii. 23.) In 664 Cedd revisited his foundation during a pestilence which was ravaging Northumbria, and died here. Thirty brethren of a monastery which he had founded among the East Angles, hearing of his death, came to Lastingham, intending to remain where his body had been interred. They were well received by the brothers of Lastingham; but all, except one youth, died of the pestilence. Ceadda (St. Chad) became head of this house after his brother's death. He retired to Lastingham after his consecration to the see of York had been pronounced informal by Archbp. Theodore; and it was from this place that he removed to Lichfield on his appointment to the Mercian bishopric. It is probable that the house, like that at Whitby and others, was destroyed during the Danish ravages.

Cedd, we are told by Bede, was buried at first in the open ground, but afterwards, when a "stone church in honour of the Virgin" had been built, his body was removed to it, and

There can be little doubt that the present ch. (dedicated to St. Mary) occupies the site of this "stone building, if it does not preserve some portions of its ancient walls. The church was well restored in 1879, some of the objectionable alterations, or rather introductions, of 1835 being removed. The nave, with a narrow N. and broader S. aisle, is E. Eng. (circ. 1190). The piers should be noticed. The E. end of the N. aisle now forms the vestry, but the wall arrangements here are not very intelligible. Norm, chancel apse has had 3 roundheaded windows, one of which is quite closed, and the others filled with vile glass The S. porch was also "restored" from a design by John Jackson, R.A. (born here in 1778, died 1830).

A flight of steps descends from the nave into the Crupt, untouched and un-"restored," the massive and solemn character of which readily suggests the day of St. Cedd, although it is no doubt Norman. It is in effect a lower ch. (extending quite under the upper with the exception of the western bay), with a nave and aisle of 3 havs, and an apsidal chancel of 2. There are small circ.-headed windows, with deep internal splays at the E. ends of the aisles; and one narrow window-slit at the E. end of 2 of the 4 piers are the apse. very massive, with capitals of interlacing arches and rude volutes. The vaulting is quadripartite. The date of the work seems circ. 1090; and it is probable that the church here was rebuilt as soon as possible after the troubles of the Conquest. Two small stone crosses, with interlaced carving, probably for use within a church, and a portion of one which has been of unusually large dimensions—all apparently Saxon—with a portable altar 17 in. high and 14 in. wide, and some other fragments of early stonework, are preserved here.

placed on the right side of the altar. There is also some early carved wood-There can be little doubt that the work.

The present tower is Perp., but the E. Eng. ch. seems to have been longer than at present, and piers and arches of at least one additional bay are retained in the tower walls. Considerable foundations also, extending westward, have been disclosed in digging in the churchyard. On the N. side of the crypt is a passage which, within the recollection of old people still living in the viilage, was open for 40 yards and more, and was traditionally said to lead to Rosedale A few feet only are open Priorv. now. The ground on which the ch. is built slopes rapidly to the E., so as to admit of the scanty light there admitted to the crypt. The narrow buttresses and stringcourse should be noticed.

In the village is Cedds Well, with a plain and good design above it, and a modern inscription. The village itself lies in a hollow, among low hills; and on a rising ground above it is a plain cross, placed there on the day of the Queen's coronation. Round the trees and cultivated fields of the village the heather sweeps in great purple folds, so little is the scene changed since those early days when Bede visited the monastery to gather materials for his History. He must have approached it by the Roman road that leads S. through the Cawthorne camps; and the line of this road may have influenced Cedd in his first choice of the site.

(The pedestrian may walk across the moor to the village of Rosedale (about 4 m.—the position is marked by the tall chimney of the iron-mine), or he may take the r...d which passes up the dale itself. This will be a longer distance. From the moor the views are fine. The dale is pleasant, but not specially picturesque in this lower part. — For Rosedale village, and for the walk between it

and Whitby, see—Excursion from Whitby.)

(For the walk or drive between Lastingham and Kirkby Moorside, see Rte. 18a.)

At Appleton-le-Moors, about 2 m. S. of Lastingham, a ch. has been erected under very interesting circumstances. A poor boy went to sea from this his native village,realised a fortune,-returned to settle here, and determined to provide full means of instruction for all natives of Appleton who should have, like himself, to struggle with the world. intended to build ch. and schools. but he died before this could be done, and his widow has carried out his purpose. The ch., E. Eng. in character, with a spire 50 ft. high, is thus in effect a memorial of Joseph Shepherd, who was buried at Lastingham; but there is a monumental chapel here, the stained glass and other decorations of which illustrate his life and character. The glass is by Clayton and Bell, as is the incised work of pulpit and reredos. A parsonage and schools have also been built: the cost of the whole, with endowments, being more than 10,000l. (Archit., J. L. Pearson.) The ch. was consecrated in 1866.

Sinnington Stat.

Pickering Junct. Stat. (Rte. 14.)

ROUTE 19.

YORK TO BOROUGHBRIDGE AND ALDBOROUGH.

(North-Eastern Rly. 3 trains each way daily. Time of transit, 1 hr. 10 m.)

From York to (16½ m.) Pilmoor Junction, this route is the same as Rte. 16. From Pilmoor Junct. a branch line passes l. to Borough-bridge.

Brafferton Stat. about halfway between Pilmoor and bridge. Brafferton Church is seen 1... on a high bank above the river Swale, which here flows S. to join the Ouse near Aldborough. The ch. (Perp.) was rebuilt in 1832, with the exception of the tower. Local tradition asserts that St. Paulinus baptized his converts here in the Swale; and the position of the ch., on the brink of the river, may have been intended to commemorate some such event. That Paulinus visited this neighbourhood is suggested by the fact that in the time of Edw. I. "Paulin's Carr" and the "Cross of Paulinus" were referred to in an Inquisition as familiar objects in the adjoining parish of Easingwold. (Bede mentions his baptizing in the Swale, but with an especial reference to Catterick. See Rte. 25.)

Boroughbridge (Inn: the Crown. old-fashioned—it is the ancient man-

sion of the Tancreds-and mode- | I render myself to Thee, and put rately comfortable), on the Ure, the bridge across which gave name to the town, was at a very early period a place of importance, although it is now utterly dull and uninteresting but for its historical associations, and the ancient relics in its neighbour-The visitor should walk to the bridge and the "Devil's Arrows," and then proceed to Aldborough.

In an open space is a Memorial Well-in honour of A. Sherlock Lawson, J.P.

A Roman road from Malton (?), following (from Pilmoor) nearly the line of the rly., crossed the river at Boroughbridge on its way to Aldborough, 1 m. S.—the ancient Isurium. By this road (or by one following its general course) the Earls of Lancaster and Hereford, who had risen against Edw. II., and who had probably advanced to Boroughbridge along the line of another Roman road, leading from Castleford through Wetherby (March, 1322), purposed retreating before the royal army, when their progress was arrested by Sir Simon Ward and Sir Andrew Harclay, the governors of York and Carlisle, whose forces were drawn up in strength on the N. bank of the river. In the fight (March 16) which followed, De Bohun, Earl of Hereford, was killed on the bridge by a Welshman, with a spear thrust from below through a crevice of the planking—a repetition of the Northman's death at Stamford Bridge (Rte. 8). Lancaster attempted to cross by a ford, but was repulsed by Harclay's archers: he then begged and obtained a truce till the following morning, when he hoped that the Scots (with whom he was said to be in league) might appear; and at daybreak, when summoned to yield, he entered a chapel, flung himself on his knees before the crucifix, and exclaimed, "Good Lord,

me into Thy mercy." taken to his own castle of Pontefract, and there beheaded. Pontefract, Rte. 28, for a further notice of this famous earl.) bridge on which the Earl of Hereford was killed was of timber. which now exists is ancient, and no doubt occupies the same site. The chapel in which Thomas of Lancaster took refuge was probably that which stood in the centre of the market-place, and was destroyed in 1851. A new ch. has been built at a little distance.

About 1 m. from the town (take the turning opposite the Crown Hotel) are the so-called Devil's Arrows, 3 rude masses of gritstone. which have long puzzled the brains of antiquaries. They stand N. and S., the northern stone about 200 ft. from that in the middle, which is 300 ft. from the southern. In Leland's time there were four, the 4th being very near what is now the central stone. This 4th stone was lying on the ground when Camden saw it, and was, not long since, used as the foundation of a new bridge over the rivulet Test, which joins the Ure at Boroughbridge. This stone was 21 ft. high.) Whether these relics are Roman, as Leland thought, "trophæa a Romanis posita, in the side of Watheling Streat,"-rude British, like many single pillars on the Yorkshire moors, and like the "Rudstone" on the Wolds (see Rte. 13),or even of the Saxon period, is a question which is still in dispute. They are (northern) 161 ft., (central) 211 ft., and (southern) 221 ft. above the ground; and as has been proved by excavation, are imbedded about 4 ft. in the soil. They are marked at the top with long deep scorings, which are no doubt the effects of weather (similar marks are seen on the Rudstone), and not, as Leland thought, the traces of "certen rude

東京市は 日本日本日本の一、日日本日本

boltells" used for working the stones into the form of an obelisk. It has been suggested that they mark the limits of a Roman stadium, or race-course; but this, like everything else about them, is quite uncertain. The beds from which the stones were taken may perhaps be seen on the bank of the Nid, near Plumpton. They should be compared with the Rudstone, which they greatly resemble.

It has been suggested that these stones might have been connected with a British town occupying the site of Boroughbridge, but there is no reason for believing that that place was of any importance before the Conquest. It is not mentioned in Domesday.

Boroughbridge was first represented in Parliament in 1300 (Palgrave's 'Parl. Writs'), but did not again send members until 1553. Sir Richard Steele represented it for many years. Lord Eldon was its member at the time he was made a peer.

2½ m. from Boroughbridge is the Church of Skelton (dedicated to Christ the Consoler), built by Lady Mary Vyner in memory of her son. (Rte. 22.) It is a Gothic building, designed by Burgess, and enriched within with marble sculptures, &c.

Aldborough (Inn: Aldborough Arms), about 1 m. S. of Borough-bridge, beyond a doubt the Roman station, is not only the most interesting Roman station in Yorkshire, but one of the most important and instructive in the kingdom. It was not only a walled camp, but a city rivalling York itself in size and (as is proved by the remains found here) in wealth. The plan was an oblong parallelogram, the circuit of the walls being about 11 m., and including an area of nearly 60 acres. Two Roman roads

from York and Tadcaster (Calcaria) met here—that from Tadcaster proceeded N. to Cataractonium (Catterick); and the so-called Watling Ilkley Street running N. from (Olicana) here crossed the The position was thus one of great "Isurium," says Mr. importance. Wright, "seems to have held wards Eburacum somewhat the relation of Verulamium to Londinium." The place is mentioned (and only mentioned) by Ptolemy, and (twice) in the 'Antonine Itinerary,' where it is in one place called "Isubrigantum;" a contraction most probably of "Isurium Brigantum." The etvmology is quite uncertain, and the guesses which make Isurium the capital of Cartismandua, are entirely without authority. At what period it was occupied by Teutonic settlers is unknown, but they of course gave it its present name "Aldborough"the "old borough." (In Domesday, and in charters of the next century. it is only called Bure or Burg.) Higden (Polychronicon) asserts that the town was burnt by the Danes in 766.

The manor of Aldborough, and the greater portion of the town, are the property of Andrew Lawson, Esq., whose house (the first rt. on entering from Boroughbridge) marks the site of the ancient W. gate. The ch. stands exactly in the centre of the Roman city. Boards with inscriptions placed on the fronts of many cottages indicate the spots at which the most important discoveries have been made from time to time; and nearly at the head of the village is Mr. Lawson's Museum—the Museum Isurianum. 6d. is charged for admission to each cottage; and an examination of all the relics will cost about 4s., which the antiquary at all events will consider well spent.

The principal remains in the cottages are tesselated and mosaic pavements, indicating the size and beauty of the ancient houses. Of these the most important are in the gardens of the Aldborough Arms, and in a house (higher up the hill) outside which is the notice, "Basilica with Greek inscription." This building seems to have consisted of a rectangular ante-room, of a large rectangular central apartment, and of a semicircular apse beyond the central room. In this apse are the fragments of a Greek inscription (only a few letters in tesserae of blue glass remain-the red glass was so beautiful as to resemble artificial rubies, and was quite equal to anything produced in later ages) which may "perhaps be taken as evidence of the refinement of the inhabitants of Roman Isurium."-Wright. apse, it has been conjectured, may indicate that the building was a temple or basilica; but it is frequently found in Roman villas, and was possibly a sort of sanctuary, containing a statue of the deity whom the owner of the house had chosen for his protector.

The "Museum Isurianum" in the gardens of the Manor House is open to visitors. It is filled with relics of the greatest interest, collected chiefly from Mr. Lawson's own grounds; and seen as it is in immediate connection with the site and foundations of the ancient city, assists materially in carrying us back over the wide chasm of 1500 years. Here are numerous coins, ranging from Nero to Maximus (proclaimed Emperor by the legions in Britain, circ. 388): much Samian ware, one case full of pieces bearing potter's marks; mortaria; iron knives; deer horns and bones from the forest which closed up round the city, and pins made from the bone - (the pinmaker's house has been discovered); circular tickets of admission to places of amusement; dice; spoons; and knives found with oyster-shells, and probably used for opening them.

The course of the City Wall may be traced in Mr. Lawson's grounds, and near the Museum is one fragment still retaining marks of the mason's trowels. (Traces of fire are said to be visible on parts of the walls, and are assigned either to the destruction by the Danes, or to that after the Norman Conquest.) The foundations in this part of the city show how closely it must have been packed, and by what narrow streets and lanes it was intersected. Sepulchral remains of various kinds have been found at different spots outside the walls, including urns, and a remarkable coffin formed of red clay. like Samian ware, but unbaked, in form like the sole of a shoe, 7 ft. 2 in. long, and filled with ashes of oak wood and a few human bones-the remains possibly of a funeral pile. Outside the city, on the S.W. side, are the traces of an ancient stadium; and near them a large artificial mound, circular in form, and known as Studforth Hill. Near the ch. (within the city) was another mound called Borough Hill, removed many years since. On it the members for Aldborough (first returned in 1557) were elected. The Parliamentary General Lambert represented the place, as did the elder Pitt, 1st Lord Chatham.

Aldborough Church (restored, 1865, in memory of a former vicar, the Rev. G. K. Holdsworth), chiefly of the 14th cent., is of no great interest. Its walls are partly built of materials from the Roman town, and a figure of Mercury is conspicuous on the exterior of the vestry. Inside remark the peculiar set-off of the arch ribs. and the frightful masks (with hollow eyes) at the intersections. Against the wall of the N. aisle is a brass. temp. Edw. III. (circ. 1360) with the name "Wills de Aldburgh." Sir William de Aldburgh who was summoned to Parliament as a baron in 1377 was not of this family, but

of Aldburgh in Richmondshire.) The rowgate by Knaresborough. 4 trains knight's arms are on his shield and daily (see Rte. 20). jupon, and he bears a heart between his hands.

The Market Cross of handed shafts with capitals is of unknown origin.

Aldborough Hall is the residence of A. H. Croft, Esq.

3 m. E. from Aldborough, on the L bank of the Swale, is the village of Myton, close to which the "White Battle," or the "Chapter of Myton," was fought in 1319. In that year, whilst Edw. II. was at Berwick, endeavouring to recover the town, which had been surrendered to the Scots, Randolph and Douglas broke into Yorkshire, and the Archbp. (Melton) and John Hotham, Bp. of Elv. were ordered to raise the posse comitatus. The real strength of the county was with the king, and accordingly a motley crew of 10,000 men was collected, many of them The Scots had clergy and friars. destroyed the suburbs of York, and were lying near Myton when the disorderly English army came up. It was routed effectually; many were drowned in the Swale (a bridge over the river here had been destroyed by the great crusader Roger de Mowbray, and was never restored), many killed (among whom was Nicholas Fleming, mayor of York), many taken prisoners. The marauders made their way homeward with great booty, and called the battle "the Chapter of Myton," from the number of clerks present. (Archbp. Zouche in 1345 redeemed the clerical honour at the battle of Nevill's Cross,when he led a division of the English army.)

There is some old stained glass in the ch. of Myton, which, like that of Aldborough, is partly built of Roman tile.

ROUTE 20.

YORK TO KNARESBOROUGH AND HARROGATE.

North-Eastern Rly. 5 trains daily in 1 hr.

The rlv. runs through a flat, wooded country, of no great interest until the neighbourhood of Knaresborough is reached.

Passing the stats. at Poppleton and Hessay, we reach

Marston Stat. This is the best point from which to visit the battle-field of Marston Moor. By far the most complete accounts of the battle are contained in Mr. Merivale's 'Historical Studies,' in Mr. Sanford's 'Studies and Illustrations of the Great Rebellion,' and (latest and best) in Mr. C. Markham's 'Life of Fairfax,' where the very complete and careful narrative is assisted by an excellent plan of the battle.

In walking from the stat. to the village of Long Marston (2 m. l.) you will pass over Marston Moor (the Railway-Boroughbridge to Har- main portion stretched away to the

W.), now enclosed, but all open | ground at the date of the battle (July 2, 1644), "one of the two bloodiest ever fought on English ground and between Englishmen." (The other was Towton.) The name "appeals perhaps more to the imagination than that of any other field of our great civil war: partly from a certain amount of poetry and romance which has been expended on it, partly because it was (though indirectly rather than directly) the most important action and turning point of the contest."—Merivale. Between Marston and Tockwith runs a road (crossing, at Long Marston village, the high road from York to Wetherby) for about 11 m. S. of this road is a rising ground (now enclosed, then "open arable" and covered with rye), with a field on its higher part called "Clump Hill." and marked at present by a small clump of young fir-trees, carefully fenced. Along this rising ground, and not much behind a ditch running from Long Marston village to the Syke beck at Tockwith-a short distance N. of the road—the Parliament's army was drawn up, and "Clump Hill" is said to have been its head-quarters. N. of the ditch and of the Tockworth road the land was unenclosed (except about the villages of Marston and Tockwith), and here was the station of the Royalist troops. At their back (about 1 m. N. of the Tockwith road) was Wilstrop Wood, part of which still exists.

The Fairfaxes, Leven, and the Earl of Manchester (under the last of whom Cromwell was serving) were besieging York, then defended by the Marquis of Newcastle, the King's chief adherent in the north, when Prince Rupert was sent from Lancashire for the relief of the city. The Parliamentarians moved from their leaguer to intercept him, and took post on Marston Moor, commanding the western roads. But [Yorkshire.]

Rupert turned them by a flank movement, and entered York. He had passed a day there when the troops at Marston, who after some discussion had determined to leave Rupert in possession and to march south—Leven's Scots had already reached Tadcaster—heard that he was in full pursuit of them, and that he had drawn up his battalion on the ground they had abandoned on Marston Moor. The leaders at once halted their troops, faced about, and soon occupied the slopes of the hill already mentioned.

The battle did not begin until about seven in the evening, when the Marquis of Newcastle arrived on the moor in his coach and six. The Royalists were strongly defended in front by the deep and wide ditch already mentioned (so wide that it was partly filled with musqueteers), serving as a natural trench: and the enclosures at the villages also assisted them. (This ditch, containing at present but little water. may still be traced from Long Marston to Tockwith. It occupies a natural hollow or dip in the ground, which rises on either side immediately from it.) Their force was about 16,000 foot and 7000 horse; that of the Roundheads about 20,000 foot and 7000 horse. The Puritans wore white ribands or bits of paper in their hats. The Royalists fought without band or scarf. The Roundheads, about seven o'clock, descended from their vantage ground, and charged the Royalists' whole line along the ditch at once-" the most enormous hurly-burly, of fire and smoke, and steel flashings, and death tumult," says Carlyle, "ever seen in those regions." "We just get a glimpse of them joining battle in complete array, and the next shows them scattered, broken, straggling across moor and field on both sides, in utter bewilderment." David Leslie and Cromwell fell on the But Newark horse, under Lord Byron.

at the W. end of the ditch, close to i Tockwith: but Cromwell and his men paused at a critical moment, after dispersing Byron's horse (see Markham, p. 167. There is reason to believe that Cromwell at this time retired from the battle). Leslie advanced, met Rupert's horse in full career, and completely routed them, so that they fled at once "along Wilstrop Wood side." The Parliamentarians chased them along the York road for 3 m., committing fearful slaughter. "to which bullets found long afterwards in the heart-wood of Wilstrop trees bore silent testimony." Rupert himself would have been taken prisoner, if he had not hid himself in some "beanlands." At the same time, on the extreme E., the Cavaliers (Goring and Urry's horse) had received the shock of the Puritan's horse (Fairfax's and Leven's), had utterly beaten them, and chased them up the hill, whence they fled southward. (It was at this time that Sir Thomas Fairfax received the deep sabre-cut across the cheek, of which the scar is shown in the portrait by Walker at Newton Kyme, Rte. 43.) Fairfax's foot, who were ranged next to these Puritan horse, had to pass on to the moor through a lane (probably the "Moor Lane" near Long Marston, which still exists); were picked off by the Royalist musqueteers on each side of the way, and met Newcastle's foot regiment of "white coats" at the end of it, who beat them back in utter confusion. The battle was so far in favour of the Cavaliers. But 4 regiments of Scots foot, under General Baillie, remained unbroken in the Puritan centre, and held themselves against the Royalists until David Leslie's and Manchester's foot reappeared on the scene and gave the final victory to the Parliamentarians. Newcastle's regiment of "white coats" resolved to die rather than to submit. They retreated into "a small parcel of ground ditched in," called

White Syke Close (still traceable a short distance W. of Moor Lane). and "were killed as they stood, in rank and file," so that after an hour's close fighting not 30 white coats remained alive when the Puritans entered the close. The Roundheads remained masters of the field. 9 o'clock the field was cleared of all but prisoners and dead, and the next day the Puritans led their prisoner, Sir Charles Lucas, over it, in order that he might identify the bodies of the dead Cavaliers. But he could. or would not, say that he knew any one, except one gentleman "with a bracelet of hair about his wrist." which Sir Charles desired might be taken off, saying that "an honourable lady would give thanks for it." The dead were buried in trenches on the field, in White Syke Close, and along Wilstrop Wood; the country people asserting that they had thus disposed of 4150 bodies, no doubt an extreme exaggeration. Bullets and other slight relics are still picked up; and a gap in a hedge through which Cromwell is said to have ridden is still shown, and according to local tradition can never be filled up.

Sir Thomas Fairfax, after the defeat of his troops on the rt. wing. broke through the enemy, and joined Manchester's horse in the other wing. Lord Leven and Lord Fairfax fledthe former to Leeds, the latter (it is said) to Cawood—where "he went to bed, there being no fire or candle in the house." Rupert's share in the fight is not clear: but he was present, since his dog "Boy" was found among the killed. Before the great charge, some shots were exchanged between the armies, one of which killed young Walton, Cromwell's nephew-" a gallant young man, exceedingly gracious" - wrote Cromwell to his brother-in-law, Colonel Valentine Walton. (See this remarkable letter in Carlyle, i. p. 151.) The Parliamentarians took 25 pieces of ordnance, 130 barrels of powder, many thousand stand of arms, and about of the Tancreds of Boroughbridge 100 colours.

of the Church, with the S. side and E. the use of 12 decayed gentlemen, to end of the fabric, are either of Saxon be resident here, together with an date or of the first years after the estate for their maintenance, and Conquest. The N. aisle was added other beneficial purposes. "He was in the beginning of the 13th cent. buried, upright, within the wall of The original detail may be observed the cellar, under the chapel, in the in the windows and W. door of the house a circumstance which gave tower, part of the entrance to the rise to a popular fallacy most granave, and a narrow window with a phically illustrated in 'Chambers's triangular head on the side of the Edinburgh Journal' for June 20, choir (walled up).

(The very interesting E. E. ch. of Nun Monkton (see Rte. 1, Exc.) is 3 m. from Kirk Hamerton).

(The pleasant village of Green Hamerton, much noted in former days as a posting station, is 1 m. N. of Kirk Hamerton. It is said in a mediseval chronicle (Anglia Sacra, ii. 371) that after Henry IV. had caused Abp. Scrope to be beheaded, he was struck with leprosy on his way to Ripon, and spent the night at Hamerton. After he had retired to rest he was grievously tormented, and called loudly to his chamberlains, who found him in darkness, the fire and the lamps in the hall and his chamber being extinguished. The indescribable compound called Theriaca Andromachi—used alike in cases of leprosy and of poison-was administered to him in wine called vernage; and he so far recovered as to be able to reach Ripon the next day.)

A mile rt. from the next stat...

Cattal, is Whizley. The tower and nave of the Church are early The choir Dec. of good character. in the same style, was added by Sir G. G. Scott, under whose care the whole fabric was repaired. The Hall, on the W. side of the ch.-yd.,

from the time of Chas. L to 1754. when it was bequeathed by Chris-Kirk Hamerton Stat. The tower topher Tancred, Esq., to trustees for 1857."-J. R. W. The arrangements under Mr. Tancred's will have been set aside. It was found that the residence of "12 decayed gentlemen" under one roof was not conducive to tranquillity or general comfort, and they are now provided for separately,

> Allerton Stat. adjoins the village of Allerton Mauleverer. Rt. 3 m. is Stourton Castle, the seat of Lord Stourton. The house, which dates from 1850, stands on the site of one built by the late Duke of York, who was occasionally visited here by his brother the Prince of Wales. place was then known as Allerton Park. The park, of about 400 acres, is picturesque. There was a Benedictine priory here, founded in or before the reign of Hen. II., but no remains are visible. The Church was rebuilt in the last cent.; but it contains 2 cross-legged effigies, most likely of the Mauleverers, carved in wood, and a brass with the efficies of Sir John Mauleverer (1400) and wife, that are worth inspection.

Goldsborough Stat., the ch. of Goldsborough is seen l. It is mainly E. Eng., and was restored by Sir G. G. Scott. Two cross-legged effigies, of the 13th cent., deserve attention. (In 1858, in digging a drain near the ch., many Saxon and Cufic coins of the 9th and 10th cents. were discovered. A great quantity of was the residence of a junior branch oriental coins have been found on

with courtyard and gateway. God-frey Goldsborough, Bp. of Gloucester Railscays—to York; temp. Eliz., was of this family.

[2 m. S. of Goldsborough, very picturesquely placed on the bank of the Nidd, is Ribston Hall (J. D. Dent, Esq.; the gardens and chapel are open on Tuesdays), famous as the place where the "Ribston pippin" was first grown. The original tree, raised from the pips of an apple brought from Normandy (?) was still alive in 1874, bearing well. The collection of pines and firs in the grounds is one of the finest in the North of England. The Knights Templars had a preceptory here, founded by Robert de Ros, temp. The foundation of much Hen. III. of it might be traced. The effigy of a Ros (Robert, the builder of Helmslev Castle, see Rte. 18A), now in the Temple Ch., London, and said to have been brought out of Yorkshire, may perhaps have come from this place. In the chapel, the age of which is uncertain, are two large slabs, from which brasses have been removed. These are said (but very improbably) to mark the graves of Templars. 21 m. S.E. of Ribston Park, on the l. bank of the Nidd, and rt. of the Wetherby road, is Couthorpe, where the largest oak in England still exists in venerable majesty. (Cowthorpe is best reached from Wetherby, whence it is 3 m. distant. Wetherby, Rte. 43, for a full notice of this famous tree, and for the new church at Hunsingore, on the opposite side of the Nidd.)]

A tunnel leads into

Church, which the tourist should cavalier families of Yorkshire.

a line extending from the Baltic to first see. Other places of interest at England, and probably came from Knaresborough are the Castle, the Samarcand in the course of com- Dropping Well, St. Robert's Chapel, merce.) Goldsborough Hall is a good and St. Robert's Cave. Each of these example of an Elizabethan mansion, has its proper guardian, who expects

> Railsoays-to York; to Ripon and N. Allerton — to Leeds and

Boroughbridge.

Knaresborough (the town on the rock-knar, A.-S.; Pop. in 1881, 5000) is very picturesquely situated on the L bank of the Nidd (the Scottish Nith, and the Norwegian Nid, are perhaps the same), here a broad, full river flowing between high cliffs of magnesian limestone with wooded bases. In beauty of situation no inland town of Yorkshire, except Richmond, can compete with Knaresborough, which grew up under the shade of the great castle founded most probably by Henry I. There some Linen factories here, are but the prosperity of the place depends at present on its cornmarket, which is one of the largest The castle has in the county. some historical associations, and the connection of Eugene Aram with the town has, mainly since the publication of Lord Lytton's romance, given a sentimental interest of another sort to Knaresborough.

The Church, ded. to St. John the Baptist, and restored (Christian, archit.) 1872, is of various dates, from E. Eng. to Perp., and of considerable interest. The nave, of 4 bays, is Perp.,; but the piers of the central tower are earlier, and the chancel is apparently E. Eng.; the windows Perp., and Dec. insertions. These have been filled with stained glass by various artists. On either side of the chancel is a Knaresborough Stat. (Inn: the the N. side contains the monu-Crown, good and reasonable), lying ments of the Slingsbys of Scriven below the town, but not far from the and the Red House, one of the great

the floor, in the centre, is the fine most important fragment remaining. altar-tomb, with efficies, of Sir Henry (A small charge is made for showing Slingsby, d. 1602, and wife. On it.) It rose to a height of 3 stories the S. side is a standing figure of above the vault or "dungeon," the Sir Wm. Slingsby, the "discoverer" of Harrogate (circ. 1596, see post); between the windows, opposite, Sir Henry Slingsby (1634) in a "Roman habit:" and on a flat stone is an inscription recording that beneath it (which formerly covered the remains of St. Robert) now rest those of Sir Henry Slingsby, the famous Royalist, beheaded in 1658. It is certain. however (see post, St. Robert's Cave), that this stone never covered the true grave of St. Robert.

There is also a marble effigy of Sir Chas. Slingsby, d. 1869. The other Chapel belongs to the Roundell

family.

The font is Perp., with a rich Jacobæan cover. During the foray of the Scots into Yorkshire in May, 1318, after destroying Northallerton and Boroughbridge, they plundered Knaresborough. Many fugitives took refuge in the ch. tower; and the invaders piled up timber round it, and lighted an enormous fire in the hope of bringing it to the ground. They were unsuccessful, but the marks of their attempt, which reddened and calcined the stone outside the tower, are still visible.

The Castle occupies a commanding position on the cliff above the The Norman fortress of Hen. river. I., of Eustace St. John, and of the Stutevilles, who were successively lords of the manor of Knaresborough, and the most powerful barons of the district, has entirely disappeared. The existing remains are not earlier than the reign of Ed. III., who gave Knaresborough to his son John of Gaunt. When Leland saw the castle there were "11 or 12 towers in the walles, and one very fayre beside in the second area." This "fayre" tower was the keep, now little more than a ruin, but the under the ground, that goeth into

groined roof of which is supported by a circular central pillar, from which 12 ribs radiate. This apartment is lighted by a single loophole, and it is here that, according to the local belief, the murderers of Becket "dreed their weird" for twelve months after the commission of their crime. (They did in fact retire to this castle, then held by Hugh de Morville, and remained here for a Above this dungeon another vaulted chamber, with two pillars, in which are preserved some rusty cannon-balls dug up within the castle precincts, a suit of armour said to have been worn at Marston Moor by Sir Henry Slingsby, the staff of "Blind Jack" (see post), and some other relics. The story above, called the King's Chamber, is said to have served for a short time as the prison of Richard II., before his removal to Pontefract. This contained two apartments; the approach to which, carefully defended by a portcullis, was from the outer court. One of these rooms was lighted by an unusually large window, 15 ft. by 10, opposite which was the chimney. within an arch which also contains a long narrow lavatory, an unusual arrangement, which deserves notice. (In 1224 covering the "camera regis" here with shingle cost 7s. 2d. baldrics for the balistas for casting stones were made at the same time. Several of these round stone shot have been found about the castle. and are shown among the relics noticed above.) The story above the King's Chamber is entirely ruined.

Nearly 21 acres are contained within the area of the castle, which was of 3 wards. In a MS. account of it, written in the time of Hen. VIII., it is said, " In the castle are certeyn privey stayres vawted, descending

the bottom of the dytches for making privy issues and excursies. In the inner court a deep draw-well, with a myghty gret wheel, a hows above it." A portion of one of these sally-ports can still be traced. Some masses of the outer towers remain: and there is a fragment with pointed arches, which was probably the chapel. On the land side the castle was defended by a moat; the precipice was a sufficient protection towards the Nidd; and from the brow of it the eye looks down with pleasure upon the deeply sunken, winding river, with great ash-trees and a strip of green haugh stretching

along beside it.

The ruined condition of the castle is mainly owing to the bombardment it underwent from the forces of the Parliament, under Lilburne, who besieged it in 1644 for nearly weeks, until it surrendered; in 1648 he dismantled it. (It was then pulled down by one Richard Rhodes of Knaresborough.) The garrison during the siege was greatly straitened for want of provisions. youth, whose father was in the garrison, was accustomed nightly to get into the deep, dry most, climb up the glacis, and put provisions through a hole, where the father stood ready to receive them. was perceived at length; the soldiers fired on him. He was taken prisoner, and sentenced to be hanged in sight of the besieged . . . Fortunately, however, this disgrace was spared the memory of Lilburne and the Republican arms. With great difficulty a certain lady obtained his respite, and after the conquest of the place and the departure of the troops the adventurous son was released."-Lord Lytton.

The Nidd is here crossed by two bridges. The tourist should take that highest up the river (nearest the stat.); and after crossing it, a gate, l., will lead him into the long walk,

winding by the river side under a pleasant hanging wood. In this walk is the famous Dropping Well, which is nothing more than a source springing out at the bottom of the limestone cliff, and passing over the top of a projecting mass of rock about 25 ft. high, so as to fall in cord-like streamlets from its brow, into a semi-The rock circular channel cut below. itself, richly draperied with mosses, ferns, and grasses, is very picturesque; but, unhappily, the water is strongly impregnated with lime; and of this advantage has been taken to vulgarise the scene most effectually. The top of the cliff, with all its vegetation, has been naturally encrusted with carbonate of lime, which drops over in a continuous stony mantle. Beneath this the guardians of the spring have suspended dead birds and animals, branches of trees, old hats, stockings and shoes, and various matters equally absurd, which become "petrified" under the dropping, and are carried off as "objets de vertu" by the curious, chiefly visitors from Harrogate. Either at the well itself, or at the public-house (Mother Shipton Inn) through which he must pass to emerge at the further end of the long walk, the visitor will be called on to pay 6d, for his inspection.

Mother Shipton, the prophetess, is said to have been born near the Dropping Well at the end of the 15th cent. The cliff on the opposite side of the river, under the castle, exhibits a good section of the magnesian limestone, superimposed on red sandstone. Lower down the limestone alone is seen.

Recrossing the Nidd by the Lover bridge (near the public-house), we reach (on the l. bank) a very large quarry excavated in the limestone rock (magnesian), which is burnt in the adjoining kilns. Owing to the ease with which this rock is excavated, the cliffs below this have been hol-

lowed out into numerous cavities, had been twice mayor of York in the some of which serve as dwellings, sometimes walled in front, and having chimneys carried out at the top: sometimes with windows and doors let into the rock itself. The most remarkable of these is St. Robert's Chapel, scooped out and inhabited, it is said (but?), by the same St. Robert whose cave or hermitage we are about to visit further down the river. An altar has been cut out of the rock, and one or two rude figures carved within this so-called chapel. The figure of an armed man with a sword in his hand is sculptured outside as if guarding the entrance. The tracery of the window is Perp. Fort Montague was hewn out of the rock by a weaver and his son in the course of 16 years' labour, and was named in honour of the Duchess of Buccleugh, their benefactress.

Passing these Troglodytic dwellings, which need not take up much time, and are little better than traps for travellers' spare coin, and continuing along the l. bank, under rocks grown over with trees and ivv, the favourite Sunday walk of Eugene Aram, you come to the Priory (its site is now occupied by a modern house called the " Abbey "), founded in 1257 by Richard of Cornwall, brother of Henry III., for "brethren of the Holv Trinity and of captives." Some foundations have been laid open near the house, but there are no remains of architectural interest. A little more than a mile below Knaresborough is the cell hollowed in the rock called St. Robert's, or more generally, at present. Eugene Aram's Cave. path and some rude steps lead down to it from the road, and the keys are kept at a neighbouring cottage.

St. Robert (of whom there exist three distinct Lives, written probably by the Prior of the neighbouring convent early in the 15th cent., was

latter part of the 12th cent. In very early life, leaving, according to Leland, the lands and goods to which he was heir, he retired to the banks of the Nidd at Knaresborough, to a cave called St. Giles's Chapel. chapel ded. to St. Hilda, with as much land as he could dig. was afterwards given him in another part of the forest; but William de Stuttville, Lord of Knaresborough, one day passed by, and, declaring that Robert was an "abettor and receiver of thieves," ordered the building to be pulled down. The hermit then returned to the Cave of St. Giles, but William, once more passing by "with hound and hawk," declared that he should be again ejected, and was only restrained by a fearful vision, which compelled him to seek the hermit in his cave, to entreat his pardon, and to bestow on him land and alms for the needy. Walter, mayor of York, and brother of St. Robert, afterwards visited him, and caused a small chapel, ded. to the Holy Cross, to be built adjoining the cell: and the hermit's fame became so great, that King John, little given as he was to reverence saints or hermits, once visited him, and gave him as much of the neighbouring wood as he could till with one plough. St. Robert died about 1218, and the monks of Fountains sought to carry his body to their new choir, but were prevented. He was buried before the altar of the Chapel of the Holy Cross: and many miracles are said to have been performed at his tomb. In his lifetime, among sundry other marvels, he shut up in his barn all the stags of the forest which injured his corn, compelling them to walk in like lambs.

The Cave of St. Giles, with the chapel of the hermit, which had long been pointed out by tradition, became specially attractive after the publicathe son of a certain Tok Fluore, who tion of 'Eugene Aram,' since it was here that Daniel Clark was murdered on the night of Feb. 7, 1744-5, either with the hand or by the privity of Eugene Aram, and where the body lay concealed 14 years. The cave (which up to that time had been half filled with earth and rubbish) was cleared after the appearance of the novel, and the foundations of the chapel in front were discovered. This measures 16 ft. 8 in. long, by 9 ft. 3 in. wide: the eastern end being raised for the altar platform, of which a portion remains. In the western half is a coffin hewn in the rock, no doubt that of St. Robert (although no remains were found in it). Had Eugene Aram known of the existence of this coffin, he might have used it for the effectual concealment of his (The inscribed stone which now protects the grave of Sir H. Slingsby in Knaresborough Ch. cannot have covered this coffin. It may have been brought from the Priory.) cave itself, rudely cut out in the cliff, was the dwelling-place of the hermit, whose bed was a recess formed in the rocky wall.

The story of Eugene Aram is too familiar to need repetition here at any length. He was born 1704 at Ramsgill, in Nidderdale, and was an usher in a school at Knaresborough at the time of the murder. soon afterwards he went to Lynn, in Norfolk, and had remained there more than 13 years when the crime was discovered by the confession of Houseman, who was present at the discovery of some human remains in a quarry, and drew suspicion on himself by taking one of the bones in his hand, with the words, "This is no more Daniel Clark's bone than it is mine." Aram was apprehended, convicted, and executed at York in 1759. That he was of remarkable attainments for his position and opportunities is certain; but the glory reflected on him in Lord Lytton's romance is probably quite unmerited. He seems to have fully deserved his

fate; unless the remorse so powerfully depicted in Hood's 'Dream of Eugene Aram' should be held to have been sufficient punishment.

A far worthier "celebrity" of Knaresborough is John Metcalf, usually known as "Blind Jack," who was born here in 1717. When six vears old, his sight was destroyed by small-pox; yet, in spite of this, he made himself perfectly acquainted with the country for miles round his birthplace, and became noted as a man of strong natural ability and resources. After many adventures, he undertook, about the year 1765, the construction of a portion of a new turnpike-road between Harrogate and Boroughbridge; and from this time his life was spent in roadmaking and bridge-building. main roads of the N. were then in Blind Jack wretched condition. proved himself singularly skilful in the work of making new ones; and some most important lines of road in both Yorkshire and Lancashire were constructed by him. In conducting roads over boggy ground he anticipated a plan afterwards adopted by George Stephenson. He died in 1810, aged 93, at Spofforth, near Wetherby. The life of Blind Jack is a favourite Yorkshire chap-book. The best account of him will be found in Smiles's 'Lives of the Engineers,' vol. i.

In the neighbourhood of Knaresborough is Scriven Hall, the old seat of the Slingsbys; and (2 m. S.) Plumpton Park, for nearly 600 years in the possession of the Plumptons. but now belonging to the Earl of Harewood. Sir William Plumpton was beheaded with Archbp. Scrope (his uncle) in 1405. (The 'Plumpton Correspondence,' printed by the Camden Society, contains much curious information about this family. The pleasure-grounds here, formed out of an abandoned stone-quarry,

are extensive and beautiful. They are open to visitors.

On quitting Knaresborough Stat., there is a pleasing view of the town and castle from the lofty Viaduct. Between Knaresborough and Harrogate is Starbeck Stat, where is a spa with baths, and all the appliances for their convenient use. The springs here are sulphureous and chalybeate; both weaker than those of Harrogate; and invalids are recommended to begin with them before they proceed to the stronger spa.

1½ m. from Starbeck we reach
Harrogate Junct. Stat., midway
between High and Low Harrogate;
the former rt. on entering, the latter l.

Comnibuses meet every train, and cabs are in waiting. Hotels of the first-class, are (in High Harrogate) the first-class, are (in Low Harrogate) the Grauby, the Prince of Wales, the Queen, the Prospect; (in Low Harrogate) the Crown. Others, somewhat inferior, but still good, are (High Harrogate) the Royal, Clarendon, and ciscoigne's: (Low Harrogate) the White Hart, the Wellington, Binns's, the Adelphi, the George, N. Eastern Station. At the iranby and at the Crown, the weekly cost of ledging and board at the public table is about 3t, 4s. 6d., besides servants' fees. The cost at hotels of the second class is less, but is generally about 6s. a day. All the hotels have suites of public rooms. Lodgings are to be had in all directions. High Harrogate is the more aristocratic side, and the Granby Hotel commands the best view. The Harrogate season continues from the middle of summer to the end of autumn.

Railways to York; to Leeds; by Tadcaster, to the Great Northern Stat. at Church Fenton; to Pately Bridge; to Ben Rhydding and ilkley; and by Ripon or Boroughbridge to

Northallerton.]

Harrogate, the most important inland watering-place in the north of

England, has 9482 Inhab.

The name Harrogate no doubt indicates its position on a very ancient line of road—here gat (A.-S.) "the military way"—the way of the "host"—which ran northward through the forest of Knaresborough. The town is spread over the head of a ridge of millstone grit, which here breaks through the limestone, and along the

They sides of a valley opening W. from it. The land declines E., W., and N. from its highest point (near the rly. stat.). The general elevation is about 300 ft., the greatest 600 ft. above the sea-level. The climate is dry and bracing, owing partly to this elevation, and partly to the open character of the ground, which, when Smollett wrote 'Humphrey Clinker' (circ. 1767), was "a wild common, bare and bleak, without tree or shrub, or the least signs of cultivation." Plantations have since been made in various directions, but the greater part of High Harrogate still remains open; and when an Act of Parliament for dividing and enclosing the waste was obtained in 1770, 200 acres were reserved "to be for ever open and unenclosed." They form what is now the "Stray," S. of the rly. stat. From some of this ground, and from the hills beyond it, wide, but not very fine prospects are com-The scenery in the immanded. mediate neighbourhood is pleasant, though not very picturesque; and in Harrogate itself the chief resources are the promenades, the pump-rooms, and the balls given occasionally at the different hotels. All classes meet at Harrogate, and, making due allowance for the difference of modern manners, the way of life seems very much the same here at present as it was in the days of Matthew Bramble. "Most of the company," he writes, "lodge at some distance, in five separate inns, situated in different parts of the common, from whence they go every morning to the well in their own carriages. The lodgers of each inn form a distinct society, that eat together; and there is a commodious public room, where they breakfast in dishabille, at separate tables, from eight o'clock till cleven as they chance or choose to come in. Here also they drink tea in the afternoon, and play at cards or dance in the evening. One custom, however. prevails which I look upon as a

solecism in politeness. The ladies | treat with tea in their turns, and even girls of sixteen are not exempted from this shameful imposition. There is a public ball by subscription every night at one of the houses, to which all the company from the others are admitted by tickets; and indeed Harrogate treads upon the heels of Bath in the articles of gaiety and dissipation."—Humphrey Clinker. (See also Amory's 'Life of John Buncle' for some curious particulars of old

Harrogate life.) Harrogate lies in the parish of Bilton, and was included in the great forest attached to the Honour of Knaresborough, a portion of which (embracing Harrogate) was granted in 1200 by William de Stuteville to the Plumptons, who long held it. The forest was stripped of much of its timber in the reign of Elizabeth, when the smelting of iron ore was largely carried on in this district: but it was still wild huntingground when Sir William Slingsby, about the year 1596, accidentally discovered the first Spa. He had travelled much in Germany, "seen and been acquainted with their Spa," and found this of Harrogate "exactly like it." (The "German" spring was at Spa near Liège, whence all the others were named. This of Harrogate was the first discovered in England. Those at Tunbridge Wells date from 1606: and that of Scarborough from about 1620.) Sir William caused the spring to be protected; its fame increased; and many remarkable cures are recorded as effected by it before 1632. It was then called the "Knaresborough Spa," for, although the name of Harrogate had always been give to this part of the forest, it was too little known to be used. "Much company," wrote Stockdale of Knaresborough to Lord Fairfax (1641), "are now at the Spas; both of the gentry of the county and of for this water and the springs both

first "public-house," on the site of the present "Queen," was built in 1687; others were soon added. but Harrogate was still small and illprovided with accommodation until the present century. It has rapidly increased since 1840, and the railways have now rendered it easy of access from all quarters.

The "Spa" first discovered by Sir W. Slingsby was that called the "Tewit" Well, in the Stray, nearly opposite the Royal Hotel. ("Tewit" is the local name of the lapwing or "pewit," which frequented this open About 25 springs are common.) now known, and are available by the public. All are sulphureous and chalybeate, and nearly all are in Low Harrogate. They have been thus arranged :—

- 1. Strong sulphur waters.—The Old Well, the Montpellier strong sulphur Well.
- 2. Mild sulphur waters.—Of these there are 17 springs: 13 in Lower Harrogate, 1 at Starbeck, 3 at Harlow Car.
- 3. Saline chalubeates.—In the Montpellier and the Royal Cheltenham pump-rooms.
- 4. Pure chalybeates. 2 on the Common, High Harrogate; 1 at Starbeck; 1 at Harlow Car.

The sulphureous waters are most useful in cases of indigestion, and in all nervous disorders. The chalvbeates are alterative and bracing. None of course should be taken without medical advice. "The sulphuretted water of Harrogate, loaded with common salt, is an indication of a deep-seated spring, rising under peculiar circumstances. The 'Old Well' is in fact a salt spring with traces of iodine and bromine as in modern sea-water; and possibly there may be only one deep source the commanders reformadoes." The E. and W. of it, as far as Harley

hill. Starbeck, and Bilton. The differences between these springs—in proportion of sulphates particularly—seem to be explicable as effects due to the different channels through which they reach the surface."—Phillips.

To the ordinary tourist the most curious of these springs are the so-called "bog-springs," which rise in a triangular piece of ground in Low Harrogate. They are 17 in number, and all varying in the proportions of their constituent parts, though they rise within 3 or 4 yards of one another. The Harlow Car springs, about 1 m. W. of Harrogate, amid pleasant woodland scenery, were discovered in 1840.

The waters are used for baths as well as for drinking. Until 1832 the custom of bathing in tubs, immortalised by Matthew Bramble (see 'H. Clinker'), was retained. In 1871 the Victoria Baths, near the Town Hall, were built. There are others in the Montpellier Gardens, at Starbeck, and at Harlow Car. A "Bath Hospital," for the relief of poor patients, was founded in 1834, and is mainly supported by voluntary contributions.

Harrogate contains, of course, no ancient buildings. The most important promenade and pump-room is the Royal Cheltenham (Low Harrogate) opened in 1835. Pleasant gardens are attached to it. In the Montpellier Gardens is a venerable thorn, which is no doubt a relic of the forest, and has witnessed all the changes which the course of two centuries has brought to Harrogate. The only ch. which deserves notice is St. John's Bilton, built 1856 from the designs of Sir G. G. Scott.

Walks from Harrogate may be—to Birk Crag, about 1 m. S., a narrow the ch., are here to wood is 4 m. l. of and picturesque, with rocky sides; Stat. on the Leeds to Harlow Car, somewhat S. of Birk Harewood, Rte. 29.)

Crag, on the road to Otley, a quiet and pleasant spot, surrounded by wood. The Spa here has been noticed above. There is an hotel with agreeable grounds. Harlow Tower. 1 m. W., was built on Harlow Hill in 1829. Its height is 100 ft., and from its summit a magnificent view is obtained over the vale of York and the comparatively level country To the west the hills southward. of Nidderdale and Wensleydale close in the landscape. Lincoln Cathedral and the Peak of Derbyshire are said to be visible from this tower on a clear day. Longer walks may be to Great Almes Cliff, 5 m. S.W., a gritstone crag crowning a hill 716 ft. high. On its summit are numerous rock basins, no doubt the effect of weather, and not artificial; and on its W. side a fissure called "Fairy Parlour." A wide view is obtained from it. (Little Almes Cliff, 121 ft. higher, is 3 m. distant N.W.) The grounds of Plumpton, 4 m. S.E., are open daily, 6d. each charged for admittance (see ante - Exc. from Knaresborough); and Knaresborough (3 m.) is also within walking distance.

The many interesting places which are within long day's Excursions from Harrogate form one of its chief attractions. The most important are—

- (a) Knaresborough—see above.
- (b) Ribston (5 m., open on Tuesdays) and Cowthorpe (6 m.). Ribston is noticed in the present Rte. ante; Cowthorpe, Rte. 43. Plumpton (open daily) may be taken on the road to Ribston.
- (c) Harewood (8 m. by road). The house and grounds (open on Thursdays), the remains of the castle and the ch., are here to be seen. Harewood is 4 m. l. of the Arthington Stat. on the Leeds Rly. (See for Harewood, Rte. 29.)

- (d) Ripon (Cathedral), 11 m., and Fountains Abbey, 3 m. further, are easily reached by rly. (see Rte. 22).
- (e) Otley and Otley Chevin, whence is a magnificent view, lie 4 m. rt. of the Arthington Stat., whence a branch rly. runs through Otley to likley. There are 5 trains daily from Arthington to Ilkley and back. The transit is made in half an hour. Near Otley is Farnley Hall, with its fine collection of Turner drawings. (See Rte. 30.) Otley and Ilkley churches are worth notice, and there is much very picturesque scenery in the immediate neighbourhood of both places. (See Rte. 30.)
- (f) Bolton Priory and the Wharfe are sometimes visited from Harrogate. The drive (16 m.) across what is called the "Forest Moor" is a somewhat dreary one, but commands some fine views. The tourist, however, will thus get but a short day at Bolton, which is more easily reached from Ilkley or Skipton. (See Rte. 30.)
- (g) For Ripley (4 m., open on Friday) and Brimham Crags (11 m.) see Rte. 21.
- (h) Hackfall, 7 m. from Ripon, is well worth a day's excursion (Rte. 22). For this a carriage may be hired at Ripon.
- (i) York Minster and St. Mary's Abbey, 22 m. rail.
- (j) Aldborough and Boroughbridge Roman remains, 10 m. (Rte. 19). By railway.

Leeds (Rtc. 28) and Kirkstall Abbey (Rtc. 29) are accessible by rly. in less than 1 hour.

The Rly. from Harrogate to LEEDS JUNCT. STAT. is described in Rte. 29.

ROUTE 21.

HARROGATE TO PATELEY BRIDGE[BRIMHAM CRAGS] NIDDERDALE.

(Nidd Valley (N.E.) Rly., Pateley Branch; 14 m. 40 minutes' transit: 4 trains daily each way.)

The rly. follows the main line to Ripon for 2 m., until after crossing the Nidd by a viaduct it turns W., and reaches

33 m. Ripley Stat. The village lies about 1 m. rt. The Churck and the Gardens of Ripley Castle are here the points of interest. In the village is a Perp. Gothic Town-hall, with the inscription "Hotel de Ville, 1854." It was built as a memorial of Sir W. Amcotts Ingilby by his widow.

Ripley Church is Dec. with some later additions. It was restored in 1862, and the general effect is fine and solemn. At the E. end of the nave are the good effigies of Sir Thomas Ingilby (one of the Justices of the Court of Common Pleas temp. Edw. III.) and his wife Catherine. In niches round the altar-tomb are small figures of their children, whose costumes deserve notice. A chantry, with 17th and 18th cent. monuments

of Ingilbys, is on the N. side of the The tower bears the date chancel. 1567 on the exterior of its staircase turret, but the main tower may be earlier than the rest of the ch. the churchyard are some remarkable tomb-slabs, one of which bears what looks like a Roman sacrificial vessel. There is also (what is very unusual) the stump of a cross, with 8 hollows for kneeling round the base. Before the year 1300 the parish ch. of Ripley is said to have stood at a place called Kirk Sink, near the stat. ground was undermined by the river. and the ch. was destroyed. No monumental stones have been found at Kirk Sink later than that period.

Ripley Castle (Sir Wm. Ingilby) has been the seat of the Ingilbys for at least 500 years: and their star of five rays" is conspicuous here and in the ch. The castle was built by Sir Wm. Ingilby in the reign of Philip and Mary, and contains some valuable family records and MSS., several of which were brought from Fountains Abbey. It is not shown. The gardens alone are open on Fridays, and are worth a visit.

Cronwell passed the night before Marston Moor at Ripley Castle. Sir William Ingilby was absent, and his wife received the great Puritan with a pair of pistols stuck in her belt, and watched him carefully through the night, which both spent in the great hall. When he left on the following morning, she told him that he would have paid for any ill-conduct with his life.

From Ripley the line ascends the valley of the Nidd. Passing

61 m. Birstwith Stat. (1. is seen the modern ch. of Wreaks: and on the crest of the hill Swarcliffe Hall — John Greenwood, Esq.), and

9 m. Darley Stat., we reach

101 m. Dacre Banks Stat. Dacre Banks is a small manufacturing village, chiefly noticeable for the fact that tow was first in England spun here by machinery, about 1795. The machine for spinning it, the "Tow Card," was invented by Charles Gill, a self-taught mechanic, born in the village.

This is the most convenient point from which to visit Brimham Crags. As there is but one carriage at the Royal Oak, it should be ordered the day before by those who require it for visiting the rocks (Brimham is the "high dwelling." Brim is still a local term for a high place exposed to weather.— W. Grainge. It is used in other, but cognate senses: thus in the ballad of the 'Felon Sowe,' "She was brim as any boare"-meaning fierce, set on edge, and so the "brim of a vessel or cup), which are situated about 2 m. N. The road gradually ascends till it reaches the high ground (990 ft. above the sea), over which the rocks are scattered. This is open common, about 60 acres in extent. Over it, forming a labyrinth threaded by winding paths, are groups of shattered rocks, assuming the most fantastic forms that can be imagined, rising not merely in walls, pillars, and obelisks, but in shapes which more or less resemble the most varied objects, animate and inanimate. Upon the strength of these fancied likenesses, names not inappropriate have been given to different masses, such as the Oyster, the Baboon's Head, the Pulpit, the Frog, the Yoke of Oxen, and so on. Not far from the public-house are 4 rocking-stones, placed close together, Each of these huge masses, many tons in weight, is so nicely poised as to be movable by the application of the shoulder, or by standing upon it and oscillating the body. One of the rocks is supported on a stone table by a small foot or pedestal like a toadstool. Many of the forms remind one of

gigantic chess-men, and appear as though turned in a lathe. Of this class the most stupendous is the Idol. whose vast swelling bulk rests upon a basis not more than 2 feet diameter. Near it is one called the Lamb, from its resemblance to an animal reclining. Where the rock remains in beds or strata it is fissured and cleft down from top to bottom, with narrow cracks and passages. Sometimes a pinnacle of rock has fallen from the top and been caught in the fissure, where it remains suspended. of the most curious spots is the Druid's Cave, where there is barely space to pass through a crevice in the rock, which is perforated with openings like windows, admitting views of the surrounding country. Around the brow of the hill rise abrupt precipices overhanging the valley and commanding views of Fellbeckdale (recently reclaimed), and Nidderdale—a fine perspective. Another huge mass, called Cannon Rock, is perforated with holes, one of which is 30 ft. long, and not a foot in diameter. Perhaps the best general view of the whole scene is to be obtained from the platform adjoining the Great Rocking Stone. Much speculation has been thrown away on the Brimham Crags, and, as in many similar scenes, the Druids have been called in to account for the rocking-stones and the mysterious perforations. But all here is the handiwork of nature; and there is no reason for supposing that any human skill has been employed. The rocks are in fact only the remains of a vast continuous bed of the millstone grit, which covered the moor, and was broken up at some unknown period, and worn away by ice and currents of water, but which has subsequently been consumed and corroded in the course of ages, by the more gradual effects of the atmosphere; the rain and frost acting on the softer parts of the stone and wearing it away. In proof of this, it is only necessary to

take up a handful of the soil of the moor, which will be found to be merely sand, the disintegrated materials of the rocks. Professor Phillips. in his 'Geology of Yorkshire,' observes, "The wasting power of the atmosphere is very conspicuous in these rocks; searching out their secret lamination; working perpendicular furrows and horizontal cavities; wearing away the bases, and thus bringing slow but sure destruction on the whole of the exposed masses. Those that remain of the rocks of Brimham are but perishing memorials of what have been destroyed."

A small public-house has been built here for the convenience (or annoyance) of tourists, who are charged 1s. each by its keeper "for seeing the rocks," and for the inflic-tion of a guide. The views from this remarkable spot, over the plain of York, and toward the wild country E. and S.E., will alone repay a visit. the whole scene is strangely fantastic (and it becomes especially striking if visited at dusk, or under a gloomy sky) than any that can be found on this side the Saxon Switzerland, "It is difficult to conceive circumstances of inanimate nature more affecting to the contemplative mind than the strange forms and unaccountable combinations of these gigantic masses."-Phillips. There are masses of gritstone in a similar state of disintegration at Plumpton, at Great Almes Cliff, and elsewhere; but none so important as these.

Brimham was given by Roger de Mowbray (temp. Hen. II.) to Fountains Abbey. Brimham Hall, 1 m. S. of the rocks, occupies the site of the monastic grange. It is now a farm-house. Fragments of inscriptions have been built up in the walls.

Beyond the Dacre Banks Stat. the

scenery becomes more picturesque. Wooded slopes rise rt. toward Brim-The line crosses the river, passes Glasshouse Mill (flaxspinning), belonging to Messrs. Metcalfe. l. are the wood and rocks of Guy's Cliffe. Castlestead (G. Metcalfe, Esq.), and Bewerley Hall (J. Yorke, Esq.), are seen on the same side; and the rly reaches

14 m. Pateley Bridge Stat. (Inns: the King's Arms; the Crown. Conveyances may be had at either, but the tourist should be on his guard against a disposition to bring the carriages home too late for the last train. thus obliging visitors from Harrogate and elsewhere to remain all night at Pateley Bridge. Pateley is perhaps "the badger's field." Pale is This is still local for a badger). a long street of neat houses, itself without interest. But Pateley Bridge is an excellent centre from which to explore Nidderdale and the wild country towards the Wharfe. Brimham Crags are easily accessible, and close to the town is Bewerley, with Ravensgill and Guy's Cliffe-well worth a visit. Nidderdale (there is no occasion for going to the Teutonic "nieder thal" for its etymology, it is simply "the dale of the Nidd") stretches upwards for 12 or 14 m. from Pateley. It contains some picturesque scenery, which becomes grand and impressive in its upper part, where the "fingers" of the dale spread out on the slopes of the Whernside. A day may well be given to its exploration. In an opposite direction (on the road to Skipton), the lead-mines of Greenhow, and the Stamp Cross Caverus, deserve a visit. (The adventurous pedestrian may cross Whernside from Pateley Bridge, or descend upon Nidderdale, in Skipton: see post). the portion we have already traversed, from Dacre Banks, and above Pateley, is rich in building-stone

contains inexhaustible beds of mountain limestone—an excellent grey Lead and ironstone have marble. been worked here from time immemorial; and there is coal in some parts. In the lower part of the dale are some linen factories.

The view from the ch.-yard of the Old Church, now a ruin, 11 m. E. of the town, is worth notice. The ch. was late E. Eng., and was built by either the Abp. of York, lord of the manor in which it is situated, or by the Chapter of Ripon, in which parish Pateley is included.

The grounds of Bewerley (John Yorke, Esq., whose family has possessed lands in Nidderdale since the middle of the 16th cent.), which include Ravensgill and part of Guy's Cliffe, are open on Tuesdays and Thursdays (6d. for each person is charged; inquiry should be made at Pateley Bridge for the person who has the sale of the tickets). Bewerley occupies the site of a grange built by the Cistercians of Fountains: and behind the house the small monastic chapel remains perfect (but used as a tool-house). The motto ("Soli Deo honor et gloria") and initials of Marmaduke Huby, Abbot of Fountains (1494-1526), are to be seen on the walls. The gardener's house, S.E. of the mansion, is said to have been (but?) the priest's house. one of the upper rooms is a richly The walks to ornamented ceiling. which visitors are admitted wind up the Fishpond wood, and Ravensgill, a narrow and very picturesque glen, through which the Raven's Beck foams and tumbles, until at the top of the gill the brook is crossed, and less trimly-kept paths lead out upon Guy's Cliffe. From the heath above, called Naught Moor (marked by a rock called the Crocodile), there is a very fine view of Nidderdale, from the hills at the source of the Nidd to Brimham (grit, slate, and flags) and, high up, Crags. Immediately below (S.) is a

hollow called the Trough, through which the road to Otley passes. Opposite, a mock ruin marks the top of Guy's Cliffe. All along the edge of the cliff (1000 ft. above the sea) a prospect is obtained extending to York Minster (E.), and to Eston Nab at the mouth of the Tees (N.). The cliff itself is broken about midway by an opening called the "Three Gaps." The scene here is wild and striking. Enormous masses of gritstone, covered with moss and lichen, lie scattered in all directions; and trees spring from every fissure of the rocks. At the foot of the cliff is a small piece of water called Guy's Cliffe Tarn.

The house of Castlestead, seen below, stands in the midst of a Roman (?) camp (it was rectangular), which here guarded the entrance of the valley.

A good road, following the course of the river, winds up Nidderdale

from Pateley Bridge to

7 m. Lofthouse. As high as this the scenery is wild and picturesque Narrow wooded "gills," each with its own streamlet, open on either side into the main valley; and the dwellings throughout Nidderdale are almost always placed at the junction of one of these "becks" with the Nidd. Riddingsgill, about 1 m. from Gowthwaite Hall, is perhaps the most beautiful, but the artist may find work for his pencil in all. The chief place to be noted in this part of the dale is Gowthwaite Hall, at the opening of Burngill (31 m. from Pateley), an old seat of the Yorkes, dating from the 17th cent. (It is now occupied by three farmers, but is untouched outside.) In it is a large upper hall in which, says tradition, a masque was acted by the Yorkes and their servants, who personated Catholics and Protestants—the former driving off the others into the "great parlour "adjoining. The Star Cham-

as an insult on the established religion, and Yorke of Gowthwaite was so severely fined, that he was obliged to sell much of his property. Eugene Aram kept a school for a short time in one of the rooms in this house. His birthplace, Ramegill, higher up the valley, is another point of interest. although the cottage in which Aram (the son of a labourer) was born, in 1704, has been pulled down. From this place he went with his father to Skelton, near Boroughbridge, and thence, when about 16, to London, as bookkeeper to a merchant. turned to Nidderdale, married there in 1731, and in 1734 removed to Knaresborough, where the murder was committed. Lofthouse was given by Roger de Mowbray to the monks of Byland, the ruins of whose E. Eng. chapel remain here.

In the lower part of Blayshaw Gill. opening at Lofthouse into the Nidd valley, is a rocky and wooded glen. with a lead-mine and marble quarries near the opening.

Beyond Lofthouse the road continues to Middlesmoor (where is a small but comfortable Inn, the last place where refreshment can be procured before crossing Whernside), and thence proceeds (but henceforth it is indifferent enough) over the hills. At Lofthouse, however, the hills. At Lofthouse, however, the hilds bends N.E., and an equally important stream (the Stean Beck) joins it from the S.W. Both deserve exploration, though few besides hardy pedestrians will be able to accomplish the work satisfactorily.

pied by three farmers, but is a untouched outside.) In it is a large upper hall in which, says tradition, a masque was acted by the Yorkes and their servants, who personated Catholics and Protestants—the former driving off the others into the "great parlour" adjoining. The Star Chamber is said to have regarded this "flexuous, and narrow, and is in place"

filled by the river. parts of the cave the sound of its waters may be heard as they rush along the secret channels of the limestone."-Phillips. There is another swallow called Manchester Hole, somewhat higher up the river than Goydon Pot. The nearly dry channel between it and Lofthouse is enclosed in rocks of limestone, and woods overhung by lofty gritstone hills. Trees become scarcer, and the scenery more and more savage, as the upper part of the valley is reached. Angram, the last farmstead in the dale, is "fenced in by bleak heathy mountains; on the W. Great Whernside; N. Little Whernside; S. Argyll Pike; and hills ranging from 1600 to 1700 ft. in altitude."—Grainge. Beyond Angram cultivation does not extend. Nidd rises on the E. side of Great Whernside, 2000 ft. above the sea.

The scenery where the river rises at the head of the dale is grand and wild, but it lies out of the beat and reach of ordinary tourists. Angram, however, it is possible to cross between Great Whernside (2310 ft.: see Rte. 31) and Buckden Pikes (2302 ft.) by a pass called the "Limestone pass," and thence to descend upon Kettlewell in Wharfedale. "The views from this pass, and from the sides of Buckden Pike down the rocky length of Wharfedale, are superb."-Phillips. But this will be found a long and laborious pilgrimage, and should not be undertaken without careful inquiry at Angram as to the direction of the "no road." (Instead of following the course of the Nidd, the pedestrian who designs to undertake this adventure should take the road from Lofthouse to Middlesmoor, and thence to Angram. Middlesmoor (where is an Inn-ante) is a small village, with a chapel, erected in 1865 (on the site of one dating from 1484), the view from which down the dale is fine. A very rough road [Yorkshire.]

"In almost all sound of its waters by rush along the limestone."— another swallow Hole, somewhat "Goverdale, or rt., descending Coverdale into Wensleydale (see Rte. 24); but this is not the pedestrian's route noticed above.)

The scenery on the How Stean Beck. which joins the Nidd a little below Lofthouse, is finer than that on the main stream. For about 1 m. of its lower course (the road from Lofthouse to Stean leads to this part) it passes through a narrow cleft in the mountain limestone, 70 ft. deep, the sides of which are hung with mosses, ferns, and lichens, and near the top overshadowed by hanging wood. Streams fall into it from either side. The chasm is not seen until you are close to the edge of it. On the S. side, in a meadow about 200 yards from the chasm, is the mouth of Eglin's Hole, a stalactite cavern of unknown length. On the upper part of the Stean Beck are one or two small waterfalls, the most picturesque of which is Park Foss. close to the open moor.

On Blayshaw Bents, below Stean, and near the junction of the Stean Beck with the Nidd, is a line of pits nearly 1 m. long, which has been thought to mark the site of a British village. (Compare those on the Cleveland Moors, Rtes. 14 and 15.) There is a square enclosure at one end, and large heaps of iron refuse adjoining (ironstone is abundant here). Blayshaw Crags, above the pits, are 1100 ft. above the sea.

take this adventure should take the road from Lofthouse to Middlesmoor, and the Stalactile Caverns at Stump Cross, may also be visited from Patevillage, with a chapel, erected in 1865 (on the site of one dating from 1484), the view from which down the dale is fine. A very rough road leads from Middlesmoor, passing into hood of the mines. Miners' houses

and villages are scattered about: on the side of the Foster Beck are the leadsmelting works of John Yorke, Esq., of Bewerley; and "Baal hills," mounds of refuse left from early lead-smeltings, are frequent. (The word has been absurdly connected with the god Baal. It is simply the A.-S. "ball," a projecting mound or rock, still used in Devonshire, and with congeners in all the Teutonic and Scandinavian languages. "Men or animals poisoned by the fumes of lead are said to be Baaloned."-Grainge. The rough surface of a Cornish mine is called the "bal.") The mines themselves, worked by different companies, are in the Greenhow Hill range (1400 ft.), where metalliferous veins cross the limestone. Those at Cockhill (1 m. N. of Greenhow village) are easiest of access. 8 or 9 miles of "horse level." or underground tramways travelled by horses, here pierce the rock, and the smelting houses are close at hand. The mines of Greenhow have been worked from time immemorial. pigs of lead, bearing Roman inscriptions (Imp. Cas. Domitiano. Aug. Cos. VII. Brig.—one is now in Ripley Castle, the other in the Brit. Mus.), were found at Hayshaw Bank, on the Nidd, in 1735; and the monks of Fountains were not less active here. A small ch. was built at Greenhow Hill in 1858.

1 m. beyond Greenhow Hill are the Stump Cross Caverns, discovered in 1860 by miners searching for lead. They are rich in stalactites, with a floor of stalagmite, and have been explored for about 1100 yards. The "Stump Cross" marked the ancient limit of Knaresborough forest.

(From Greenhow the pedestrian may pass down the "Trowler's Gill"—very picturesque and romantic, with steep rocky sides—into Wharfedale. The "Gill" joins the Wharfe near Barden Tower.)

ROUTE 22.

HARROGATE TO NORTHALLERTON, BY RIPON, FOUNTAINS ABBEY, HACKFALL AND TANFIELD.

(North-Eastern Railway; 8 trains daily in 1 hr. 30 min.)

Between Harrogate and Ripon there are stations at *Starbeck* (Re-20),

Nidd Bridge Stat. Here the line to Pateley Bridge turns off L (Rte. 21).

Wormald Green Stat. There is nothing which calls for special notice until

(11½ m.) Ripon Stat. is reached. The distance is travelled by some of the trains in 20 minutes.

(Inns: 2nd class; the Crown, in the Market Place; the Black Bull: Pop. in 1881, 7390). The Cathedral towers are seen dominating the lower buildings l. as the train reaches the stat., which is \(\frac{1}{2} \) m. from the city. (Omnibuses at each train.)

As one of the three ancient religious centres of Yorkshire (the two others were York and Beverley), Ripon has special attraction for the historical antiquary; and the existing cathedral though comparatively small, is full of interest and architectural beauty. The cathedral is the one object of interest in Ripon; but some pleasant excursions may be made from hence, besides that to Fountains Abbey.


Ripon (the "Inhrypum" of Bede) occupies a point of land between the junction of the Ure with the Laver and the Skell. It first becomes distinctly mentioned after the establishment here in 660 of a monastic house dependent on that of Melrose. Scottish monks, however, did not remain here more than 2 or 3 years: and on their departure King Alchfrid of Northumbria gave the monastery and the surrounding lands to the famous Wilfrid, who had been his instructor. As Abbot of Ripon, Wilfrid on his elevation to the see of Northumbria (York) erected a new monastery here (not on the site of the present cathedral), which was built by workmen from Italy "after the Roman manner." When Wilfrid was deprived of the Northumbrian see by Abp. Theodore of Canterbury in 678, the diocese was subdivided, and sees were established at York. Hexham, and Ripon; of which place Eadhead was appointed the first and only bishop, the see being afterwards merged in that of York. Wilfrid, after his many struggles and wanderings, retired to the monastery he had founded at Ripon. He died in 711. at the Abbey of Oundle in Northamptonshire, when on a journey; but his body was brought back to Ripon, and interred in his own church. Athelstane is said to have bestowed the "manor" of Ripon on the Abps. of York. The manor belonged to the Abos. of York from a period long before the Conquest until it passed into the hands of the Ecclesiastical Commissioners; in accordance with whose report Ripon was re-erected (1836) into an Episcopal see, and the greater part of the West Riding was placed under its jurisdiction.

Wilfrid's monastery was in ruins at the period of the Conquest; and before that time, Odo, Abp. of Canterbury, is said to have commenced a new church on the site of the present Cathedral. This church was served by a body of Augustinian canons, who remained in possession until the Dissolution of collegiate churches, 1st Edw. VI.

Ripon was a favourite residence of the Abps. of York until Abp. Walter Gray, 1215-1255, built Bishopthorpe. The town was much injured by the Scots in 1319, when they remained here 3 days, and made the inhabitants pay a tax of 1000 marks. ing the "Rising of the North" 1569, the Earls of Northumberland and Westmoreland mustered here, and made their proclamation. ton displayed his famous banner here, and mass was sung in the great church. This was in November. the following January the rebel constables and serving-men of the West Riding, and the townsmen of Ripon who had favoured the Earls, were executed here. In 1640 a conference was held at Ripon between the Scottish Lords and the English Commission-Parliamentary troops, under Sir Thomas Mauleverer, were at Ripon in 1643, when they sacked the Minster; and in 1646 King Charles, then a prisoner, passed two nights here on his way to Holmby.

There is now little or no manufacture in Ripon; but the town was famous for its woollen cloth from a very early period, and only ceased to be so during the Wars of the Roses. (It is not true, however, as is sometimes asserted, that the trade was removed to Halifax in the 15th cent., since it can be proved that clothmaking existed there long before.) Leland when at Ripon, temp. Hen. VIII., observed that "idelness was sore encressed in the town, and clothe makyng almost decayed." It was

- A. Nava.
- B. West Entrance.
- C.C. Western Towers.
- D D. Transcot.
 - E. Central Tower.
 - F. Aisle of Morth Transcot.
 - G. Aisle of South Transept.
 - H. Steps to Lady Loft.
 - I. Choir.
 - K. Altar.
 - L. Chapter House,
 - M. Vestry.
 - . Entrance to Crypt, called St. Wilfrid's Needle.



SCALE-100 feet to 1 inch.

GROUND PLAN OF RIPON CATHEDRAL.

previously "much celebrated for byenge of horses," and a street is still called the "Horse Fair." At a later period Ripon was famous for its spurs. "'As true steel as Ripon rowels', is said," says Fuller, "of men of metal, trusty persons, faithful in their employment." "A gilte bowle and a pair of Rippon spurres" were presented to King James I. on his visit in 1617; "which spurres cost Vli., and were such a contentment to his Matte, as his Highness did wear the same the day followyng at his departure."

then, and had been for centuries sounding of the Mayor's horn-once announcing the setting of the watch, but now a mere formality. Three blasts are sounded nightly before the Mayor's door at 9 o'clock, and one afterwards at the Market Cross. The horn itself is decorated with silver badges, and with insignia of trading companies belonging to the town.

The visitor will at once find his way from the Market-Place to the Cathedral, the beautiful west front of which opens before him as he descends Kirkgate. Mr. Walbran has proved that the existing building was commenced by Abp. Roger A custom worth notice here is the (1154-1181), who rebuilt the choir of York (see Rte. 1) and the Abp.'s palace there, of which some portions remain. Abp. Walter Grav (1215-1255) probably added the west front. Toward the end of the 13th cent. (1288-1300) the eastern portion of the choir was rebuilt, the work of Abp. Roger being replaced by two Dec. bays. The Scots set fire to the ch. in 1319; and some restoration (for the most part, probably, of woodwork) was required after their foray. About the year 1454 the central tower had become greatly ruined, and part of it had fallen. It was then rebuilt; and during the first vears of the 16th cent. Abp. Roger's nave was removed, and Perp. work substituted for it. In 1604 King James I. erected Ripon into a collegiate church, with a dean and 6 prebendaries. The wooden spire above the central tower had been struck by lighting in 1593; and in 1660 it was blown down, demolishing in its fall the roof of the choir. This was restored; and the spires of the western towers were then removed in fear of a similar calamity. In 1862 the building was placed in the hands of Sir G. G. Scott for a complete restoration, which has been effected with the utmost skill, and with the strictest preservation of every antique fragment, and the cathedral was formally The cost of reopened in Oct., 1872. the restoration was about 40,000L. of which the Eccles. Commissioners contributed 15,000% The rest was principally raised in the diocese.

In accordance with these dates, the

Minster exhibits—

Trans. Work (Abp. Roger's)—1154-1181.

—Transepts; 3 bays, N. side of choir; N. wall of choir; portions of nave piers adjoining the W. and central towers.

Bariy English.—1215-1255.—W. front and W. towers; vaulting and circ. windows of chapter-house.

Decorated — 1288-1390. — 2 easternmost bays of choir.

Perpendicular — 1460-1520.—S. and E. sides of central tower; E. side of main wall of S. transept; choir screen; 2 bays, 8, side of choir; nave,

Abp. Roger's church was, however, constructed on the site of one far more ancient, founded in all probability (besides that of the monastery, which was on another site) by St. Of this church a most Wilfrid. remarkable relic exists in the crypt called "St. Wilfrid's Needle," entered from the nave. This is probably of St. Wilfrid's time (664-709). Another portion of the earlier ch. is the Norman S. wall and E. apse of the Chapter-house—possibly due to Thomas of Bayeux, the first Abp. of York after the Conquest

The West Front, Abp. Gray's addition to Abp. Roger's church, is a singularly pure and beautiful example of E. Eng. It consists of a central gable, 103 ft. high, between flanking towers of somewhat greater elevation. The towers are divided from the central compartment by flat unstaged buttresses, rising quite to the top. Although they project but slightly, these buttresses give considerable relief to the front, the whole of which is on the same plane. In the central compartment are 3 portals, receding in 5 orders, with double shafts (one behind the other-an arrangement occurring at Lincoln, and in the Galilee porch at Ely), much dogtooth ornament and gabled pediments. Above are 5 pointed windows, Above, again, are of equal height. 5 lancets; that in the centre, from which the others decline, being the highest; and in the gable are 3 narrow lights. Much dog-tooth ornament occurs in the mouldings of all these windows; but the caps of the lower tier are foliated, those of the upper plain; and generally it should be remarked that the ornamentation becomes less from the portals up-The towers have buttresses at each angle. Each tower is divided by string-courses into four equal stages, the lowest of which has a blind arcade, while the 3 others have each 3 lancets, the central

arch alone in each being pierced for light. All have much dog-tooth. These towers were originally capped by lofty octagonal spires.

Leaving the rest of the exterior for the present, we enter the Minster by the western door. Although the view here must not be compared with that afforded by the space and dignity of larger churches, it is nevertheless one of great interest, owing mainly to the unusual width (87 ft.) of the nave; for, eastward, the tall and massive organ-screen shuts out the choir, the E. window of which is seen above it.

The bays opening into the towers are E. Eng., of the same date as the whole W. front; but it is evident that Abp. Roger's work (seen in the first bay of the nave beyond them, and in the transepts) materially influenced their composition.

The double tier of lights in the W. front is set off by clustered shafts, with much dog-tooth in the hollows. Seen from within, this front has a simple dignity effective in the highest

degree.

The Nave of Abp. Roger's ch. had no aisles; and the piers of the existing nave rest on its foundations. The E. E. western towers (Roger's nave seems to have had none) projected beyond it, and the present nave-aisles have been obtained by a line drawn from the outer angle of the towers to the central wall-pier of the transepts. The first bay beyond the towers preserves for us the character of Abp. Roger's nave.

The present nave of 5 bays was begun about 1502, and is unusually light and wide; with a character which gives the whole an appearance of much earlier date than is really the case. The width of the central passage was determined by the width of Abp. Roger's entire nave. The width of the nave and aisles (87 ft.) is greater than that of any other Engrater than that of any other English nave, York, Chichester (which

has 5 aisles), Winchester, and St. Paul's excepted. Very graceful piers support a lofty clerestory. brackets of the vaulting shafts are carried by angels bearing shields. An interior oak roof has, under Sir G. G. Scott's anspices, taken the place of a flat ceiling, and has been constructed without disturbing the exterior roof, although there are not 6 inches of space between the two. and their beams in some places touch The bosses of the new one another. roof are richly carved, and display the emblems of the Evangelists, and others referring to the Holy Sacraments.

The windows of the S. aisle differ slightly from those of the N. The aisles were intended to be groined, and the springers remain. The towers, which now form their W. ends, projected, it must be remembered, beyond the earlier nave This accounts for the windows on this side, and the various mouldings. At the E. end of the nave are some remains of Abp. Roger's nave, which will best be explained in connection with the

central tower.

There are few Monuments of interest in the nave (or, indeed, in the cathedral). In the S. aisle is a remarkable altar-tomb, covered with a slab of grey marble, on which, in low relief, is the figure of a man in prayer, and, near him, that of a lion. among trees. There is a defaced inscription below; but nothing is known of the history of the monument. beyond a tradition that it is that of an Irish prince who died at Ripon on his return from Palestine, bringing with him a lion which had followed him like a dog. In the westernmost bay of the same aisle is the Perp. Font; and by its side that which was provided when Abp. Roger It is circ. and erected the nave. massive, without stem or base, and is ornamented by an arcade with round

Some 14th cent. stained glass, of great excellence, remains in the westernmost window of the S. aisle, removed from the E. window of the choir in 1854. These are roundels, representing St. Peter, St. Paul, and St. Andrew, and some other saints not easily distinguished. Other glass has been worked up with them, but the roundels alone deserve notice. There is some modern glass (of various quality) in other windows of the aisles.

The crypt is entered from the S.E. bay of the nave; but the whole of the upper church may first be examined. The central tower (part of Abp. Roger's work) had become ruinous in 1459; when the S. and E. sides were rebuilt as we now see The original arrangement remains N. and W.; but these arches, if the chapter funds had permitted, would probably have been altered like the others. At present the great mass of Perp. masonry at the S.W. angle projects awkwardly enough. It will be seen that the original arches were higher N. and S. than E. and W. The arrangement above the circ, arches should be noticed (the small openings in the wall between the pointed lights of the clerestory are no part of the original design, but were produced by walling up spaces probably in the 17th cent., with an idea of strengthening the tower, which was severely rent on the N. side). The tower has been thoroughly repaired, and has been enriched by a painted ceiling. On both sides of the nave, adjoining the W. arch, portions of Abp. Roger's nave remain; on the N. side part of the vaulting shaft, and one bay of the triforium; on the S., the tri-forium remains, but closed up. These portions resemble the more complete bay at the W. end. Against the wall (N.) is the monument, with bust, of Hugh Ripley, last "Wakeman" (as the chief officer of the town was thereon in a Ramillies wig and laced

anciently called, from his rule of the "wake" or watch) and first "Mayor" of Ripon, died 1637. The verses should be read. On the inner side of the N.W. tower arch a figure of James I. (in whose time Ripon was incorporated, and the Wakeman became a Mayor) is placed on a semidetached shaft.

The Transepts retain Abp. Roger's work more entirely than any other portion of the ch. The north transept especially is almost unchanged. Each transept has an eastern aisle of two bavs.

The N. transept had originally on its W. side 2 round-headed windows in its lower story, one of which remains. The other was cut through when the Perp. arch was formed, opening from the nave aisle. triforium has 2 broad arches in each bay, with a central detached shaft. The clerestory above has 3 arches in each bay; that in the centre round, the other pointed. Triple vaulting shafts, with cushioned caps (modern, and grafted on the old shafts), divide the bays. The arrangement of the N. end of the transept is the same, except that the bays are more compressed.

The transept ceilings are of carved oak. Outside the aisle is the muchshattered monument, with efficies, of Sir Thomas Markenfield and wife (died 1497). The chantry of St. Andrew, within the aisle, was the burial-place of the Markenfields (see post, "Exc. from Ripon," for Markenfield). In it is the alter-tomb of Sir Thos. Markenfield (living temp. Rich. II., and aged 39 when he was a witness in the Scrope and Grosvenor case), whose armour deserves notice. The sword-sheath is richly decorated. His livery collar represents the pales of a park, and the badge suspended from it is a couchant stag, surrounded by similar pales. Close by is the monument of Sir Edward Blackett of Newby (died 1718), who reposes

waistcoat, attended by two wives | eastern bays, or presbytery, are Dec. The helmets, gloves, and achievements here were used at his funeral.

The south transept has precisely resembled the north; but the eastern aisle was altered at the same time (probably) as the central tower. Abp. Roger's shafts remain against the E. wall; but the entire front of the aisle (including triforium and clerestory) is Perp.: although the original vaulting-shafts remain between the bays, and the Perp. work is grouped with them.

Against the S. wall of the transept is a copy of the Choragic Monument of Lysicrates at Athens, a memorial of William Weddell, of Newby. The

bust is by Nollekens.

In the aisle is a tablet for Sir John Mallorie, of Studley, who defended Skipton Castle for Charles I., and another for the Aislabies, also lords of Studley. At the N.E. corner of the aisle, steps lead upward to the library (see post).

The Choir Screen, Perp., like the piers between which it rises, was, like them, completed soon after 1459. is a mass of rich tabernacle work. 19 ft. high, with 4 niches on either side of the door, and a range of smaller ones above. Over the door is a small figure of the Saviour in glory, with censing angels. The organ, by Booth, of Leeds (but retaining the choir organ of Father Schmidt, built on the spot in 1695), was erected in 1833.

Through the screen we enter the Choir, which, including (as it now does) the Presbytery, contains work | of 3 distinct periods, Trans.-Norm., Dec., and Perp. The 3 westernmost bays on the N. side, and on the S. the second pier from the E., are Abp. Roger's work; and the existing choir with its aisles is built (probably) on the foundations of his choir. The 3 bays opposite (S. side) side of the choir are Perp.; but the are Perp., built after the ruin of the triforium still retains the circ, arch, central tower in 1459; and the 2 The wall space below is panelled.

(1288-1300). Abp. Roger's work resembles that in the transepts; but the fine vaulting-should be especially noticed. The triforium is glazed like the clerestory; but this change took place in the Perp. period. The arches of the triforium opened originally into the roof space above the vaulting This roof was lowered of the aisles. after 1459, and the triforium opening filled with glass. "Uninformed of this fact, the student has often gazed in astonishment on the 2 pointed lights of the round-headed arch. divided by a slender column, and ornamented with those sharp cusps, which are, in reality, shown from the more modern mullion behind."-J. R. Walbran.

The decorated work of the 2 eastern bays has a certain retrospective character, designed to assimilate it in some degree with the Trans. Norm. W. of it. The triforium openings (now lights) are enclosed. like Abp. Roger's, in a circ. arch. The clerestory passage has a double plane of tracery. On the S. side, the junction of the Dec. and Perp. is marked by 2 monastic heads at the spring of the main arch. Opposite. N., are two smaller heads. leafage of the Dec. portion (executed at the time when natural foliage was copied with the utmost care and accuracy) is very beautiful, and deserves special notice. The great E. window, of 7 lights, is unusually fine. At the angles are shafts with capitals of leafage; brackets support an inner rib, running round the soffete. The glass, which now fills the window, is by Wailes of Newcastle, and was placed there in commemoration of the erection of the see of Ripon in 1836. It cost 1000l., but is not good.

The 3 westernmost bays on the S.

The roof of the choir is modern; it is a wooden vaulting of the same pitch, plan, and section of ribs as the Dec. vault, which had been of wood. Some of the wooden bosses or centre knobs which had been preserved after the fall of the spire in 1660, when the original Dec. vault was broken through, were replaced in the groining of 1829, and, after proper cleaning, are fixed in the present vault. The oak vaulting is relieved with patterns in colour, and on the ribs are fillets of gilding. On the S. side of the altar are 3 sedilia, late Perp. in character, but showing small heads and details worth attention.

The choir retains much of its ancient wood-work. That at the W. end shows a good mass of tabernaclework, with angels bearing shields at the terminations of the lower cano-This is of the 15th cent., as are the carved subsellia (for the most part showing animals and leafage, with some grotesques) throughout the stalls, one of which bears the date 1489. All this wood-work was carefully restored, under the direction of Sir G. G. Scott. An Episcopal throne, erected in 1812, has been taken down; and the Bishop now occupies the easternmost stall on the S. side, which appears (from the sculpture of a mitre on the back) to have been that originally assigned to the Abp. of York.

The screen-work which encloses the choir is of the 15th cent., and of the usual Yorkshire type, in accordance with which the upper part of the heading alone is filled with tracery.

The north choir aisle follows the architecture of the choir, having its 3 westernmost bays Trans. (Abp. Roger's), and the 2 eastern Dec. The western bays have broad lancet windows (more resembling E. French than E. Eng.), with Perp. tracery inserted. (The windows are perhaps altogether insertions of the Dec. period.) The vaulting is quadripar-

The roof of the choir is modern; it | tite. A Dec. window, with an arcade a wooden vaulting of the same | below it, terminates the aisle.

The Shrine of St. Wilfrid rested, it is supposed, in this easternmost bay of the N. aisle. Leland, in his Itinerary, asserts that the saint's "reliquiæ" were buried "on the north side of the Quiere," "sub arcu prope mag altare." On the other hand, Odo Abp. of Canterbury, in his preface to Frithgode's Metrical Life of Wilfrid, asserts that on visiting the old monastery here he found the grave of Wilfrid in a state of utter neglect, and removed his bones to Canterbury. It is certain. on the one hand, that the canons of Ripon asserted that they had possession of St. Wilfrid's relics, and that pilgrimages were made to his shrine here from an early period. The banner of St. Wilfrid, which stood over his tomb, was, it will be remembered, one of the three displayed at the battle of the Standard, see Rte. 16. On the other hand, Gervase of Canterbury, writing after the rebuilding of the cathedral there by William of Sens at the end of the 12th cent., asserts that the body of St. Wilfrid of York reposed in the eastern chapel of the cathedral, which was burnt in 1174, and that it was removed, with the relics of other saints, into the new church. It would seem most probable that the Canterbury story (supported by Abp. Odo's positive assertion) is the true one; although the canons of Ripon may have honestly believed that they possessed their patron's body. The discordant assertions may be reconciled in a certain degree by a statewent of Eadmer, who, in his Life of Wilfrid, written in the 12th cent., after informing us that Wilfrid's body was removed to Canterbury by Abp. Odo, says that, from respect to the place which Wilfrid had loved beyond all others in his lifetime, a small portion of his remains was left at Ripon, and deposited in a suitable

The windows of Abp. Roger's portion are placed high in the wall, on account of the Norm. chapter-house and vestry, which abut the aisle. They now look into the Lady Loft (see post). Vaultingshafts with plain brackets, rise between the windows. In the bay adjoining the vestry-door is a long. square lavatory; and the piscina of the chapel in the eastern bay re-Staircases ascend into the buttress turrets at the exterior angle of both aisles (see post—Exterior).

The Chapter-house is entered from the second bay of the S. aisle (counting from the W.). This, with the vestry eastward of it, was either, as Mr. Walbran has suggested, the aisle, or, as other archeologists suppose, the choir of a Norm. ch., built by Abp. Thomas of Bayeux (1070-1100), after the devastation of Yorkshire by the Conqueror in 1069. There is no reason whatever for assigning an earlier date to the The rest of the ch. was most likely destroyed by Abp. Roger, who converted this remaining portion into a chapter-house and sacristy for his The vaulting and new minster. 2 central piers of the chapter-house are E. Eng., of later date than Abp. Roger's work. At the N.W. angle a doorway opens to a flight of steps leading to the crypt.

The Vestry, or sacristy, E. of the chapter-house, is of the same cha-Foundations of the choir buttresses (circ. 1288) project into it on the N. side: but the Norm. arcade is more evident here than in the chapter-house. The E. end is apsidal, with the base of the altar remaining. On the S. side is a small lateral apse, forming a room for storing treasures of the church. In it is a piscina or lavatory.

The south aisle resembles that | from the S. transept, is the Lady Loft, a chapel of Dec. date (circ. 1330), which formed the ancient Lady-chapel of the Minster, and now serves as the chapter library. There are no books here calling for special attention.

Returning to the nave, we enter, by stairs at its N.E. angle, the crupt, called * "St. Wilfrid's Needle," many respects the most interesting portion of the whole church. A long and narrow passage leads to a cell, cylindrically vaulted, 7 ft. 9 in. wide, 11 ft. 3 in. long, and 9 ft. 4 in. high; in each wall are plain niches, with semicirc. heads. One of these (W.) has a deep basin in the base; and others, apertures at the back, as if for the smoke of a lamp. At the N.E. angle is the passage called St. Wilfrid's Needle, which is said by Camden to have been used as an ordeal for women accused of unchastity. If they could not pass through it they were considered guilty. At the W. end a doorway opens into another passage; and other cells may perhaps exist, although they have yet to be discovered. (The crypt itself is untouched; but whether the passages were to any extent altered on the construction of Abp. Roger's ch., or at a later period, is not altogether certain. The western portion of the passage leading from the nave has an early sepulchral stone in the roof, proving that some change has taken place there at any rate.) The strongly marked Roman character of this crypt will at once strike the visitor. It has, indeed, been regarded by some antiquaries as a Roman sepulchre; but a crypt of very similar character exists at Hexham in Northumberland, benesth the conventual ch., which Wilfrid founded there; and it is therefore reasonable to conclude that this is Above both chapter-house and of the same date, and that it marks vestry, and approached by steps the site, not of Wilfrid's monastic

ch. here, which, as it is known, | lights the space between the choirstood elsewhere, but of a second ch.. either founded by him, or constructed by the same "Roman" workmen. It is therefore the most perfect existing relic of the first age of Christianity in Yorkshire, and as such cannot but be regarded with the utmost interest and veneration. The crypts, both here and at Hexham, are popularly known as "confessionals;" but it is more probable that they were used for the exhibition of relics at certain periods, "according to an ancient custom still in use on the Continent; the faithful descend by one staircase, pass along the narrow passage, look through the opening in the wall at the relics, and then pass on, ascending by the other staircase."—J. H. Parker. They belong, however, to a period so remote, and are connected with local rituals and observances so little known to us, that it is impossible to ascertain their original purpose with certainty. (An excellent notice of the Ripon crypt by Mr. Walbran will be found in the York vol. of the Archaeol. Institute, by the same writer; and another, on the crypt of Hexham, in his account of the fabric of that ch. embodied in Raine's 'Priory of Hexham,' vol. ii.) It is an important fact, which has not been previously noticed in describing or speculating on the original purposes of these crypts, that there is a "needle" or voided niche at Hexham, as well as at Ripon, and in the same position in the N. wall; but in the former instance it has not been enlarged on the side toward the passage, as in the latter case.

At the E. end of the ch. the massive Dec. buttresses between the choir and aisles form the most strik-The windows, with ing feature. their rich foliations, are very fine in the gable (above the E. window) | VIII.) at the E. end of the choir.

vaulting and the roof. In the pinnacle of the S.E. buttress is a remarkable place of concealment, or perhaps of imprisonment. (Every religious house had its "laterna, or prison for refractory members. Sometimes, as at Fountains (see post), there were several of different degrees of severity.) On getting to the head of the stairs, which wind up the buttress, no opening is seen; but when what appears to be the roof is pushed against, a trap-door opens, through which the prisoner might be thrust into his narrow quarters.

In the vestry and chapter-house. remark the Norm. string-course which runs round between the Norm. work and the Lady Loft. This latter is distinguished by its square-headed windows, the tracery of which is formed by intersecting arches. Under both the vestry and chapter-house is a Crupt like them of Norm. date. Owing to the fall of the ground, a range of round-headed windows has been obtained for the crypt, giving, by the double tier of Norm. lights, a peculiar character to the whole elevation. The western portion of the crypt is walled off, and used for inter-The eastern, until 1866, ment. formed what was known as the bonehouse, and was filled with an array of human relics resembling the ossuaries attached to most village churches in Brittany. Bones and skulls were piled up in vast numbers on its N. side; and for 3 feet beneath the surface of the ground the crumbling dust was that of the ancient inhabitants of Ripon. All these remains have been removed and buried. The vault of the crypt is supported by square pillars, with plain caps. These have been strengthened in the E.E. period. Over the door of the bone-house is the head of a cross which may very well be Saxon. It was found in 1832, in examples of early Dec. The window | taking down a wall (temp. Henry

are collected under the E. window. Near the S. transept is a tombstone with a curious epitaph for 6 infants.

The Cathedral is so closely surrounded with buildings that no good near view is to be obtained. Ăt a distance, and from the low hills about Ripon, it rises finely above the city, and is a conspicuous mark from the hills which border the great plain of York.

Except the Cathedral, there is little to be seen in Ripon.

The Hospital of St. Mary Magdalene, in Stammergate, not far from the Ure, was founded for lepers by Abp. Thurstan (died 1140). The houses attached to it were rebuilt in 1674; the little chapel on the opposite side of the way remains as it was left at the Reformation. The S. doorway (Norm.) has been altered in the Perp. period, when some windows were inserted, together with screen-work of the interior. are also some E. Eng. lancets. most striking relics here, however, are the stone altar, with the pavement before it. It is tesselated in coloured marble, stone, and brick, with a circular ornament in the centre. An iron-bound chest in this chapel deserves notice.

The Hospital of St. Anne, or Maison Dieu, in High-st., Agnes Gate, a retreat for 8 poor women, is thought to have been founded by one of the Nevilles (temp. Edward IV.). The little Perp. chapel is in ruins, but retains its piscina and altar-stone, on which tradition asserts that the ransom of a Scottish king was paid.

A good R. C. ch., with a lofty choir, deserves notice.

In the garden of the canon's residence is a remarkable tumulus called " Ailcy Hill," the evidence, no doubt,

Some 13th cent. sepulchral slabs since human bones are mixed in quantities with the gravel of the mound, and the teeth and bones of horses are found in quantities about its base. "Stycas" of Northumbrian kings of the latter half of the 9th cent. have been found in the mound, proving its date with tolerable certainty. It was called "Ilshow" in Leland's time; and its name has been connected with that of Ælla King of Northumbria, who, however (Sax. Chron.), fell at York in battle with the Northmen (A.D. 867).

> In the neighbourhood of Ripon (on the high land near "Blois Hall") are two curious circular earthworks. with a diameter of 680 ft. have been enclosed by a mound and trench; and it has been suggested that they were sites of temples or moot hills, rather than places of defence. (They must be compared with similar earthworks near Tanfield, see post.) There is nothing, however, to indicate their date, since, although there are many Celtic barrows in the neighbourhood, the earthworks may be much later. They are unusual, at any rate, in form and arrangement, and deserve careful examination.

> The Episcopal Palace, a Tudor building, designed by Railton, and completed in 1841, stands about 1 m. N.W. of Ripon. Attached to it is a chapel, of Perp. character, also designed by Railton.

Excursions from Ripon are (\ a) to Studley Royal and Fountains Abbey, 4 m.; b to Markenfield Hall, 31 m.; and to Hackfall. Studley, Fountains, and Markenfield may be visited on the same day; and the tourist may extend his excursion beyond Hackfall to Tanfield and Snape. This last will be a long day's work, but the antiquary should not miss Tanfield at any rate. Newby Hall, on the Ure. of a great battle fought on the spot, 4 m. from Ripon, contains a good collection of statuary, and is occasionally shown to small parties.

(a) The grounds of Studley Royal (Marquis of Ripon), in which lie the ruins of Fountains Abbeu, have long been ranked with the most famous "sights" in Yorkshire. Those who desire to visit both the grounds and the ruins of the Abbey may take the following route-beginning with the grounds. If it is only desired to see the Abbey, carriages may drive to the W. gate, by Fountains Hall, and close to the ruins, see post. A long summer's day can hardly be spent more delightfully than among the woods of Studley, and the ruins of Fountains. The arrangement and distribution of a great Cistercian house is nowhere in England seen so completely as at Fountains.

The entrance to the park of Studley Royal is about 2 m. from Ripon on the road to Pateley Bridge. (The grounds are open daily from 7 to 5; the house is never shown.) A long and most picturesque avenue of limes leads to an elegant Gothic Church, surmounted by a spire erected by Lady Ripon as a memorial to her brother, murdered by Greek brigands. Burgess was the architect. It stands on high ground, commanding views of both Ripon and Fountains.

Before reaching the church, the road to Fountains turns down a grand old beechen avenue to the margin of the little river Skell, which, winding onward to join the Ure below Ripon, is here dammed up into a lake of 12 acres; close to the Lodge and entrance Gates of the ornamental grounds; Is. admittance is paid here. (No guides are needed. The road through the grounds is marked by black hands painted on boards, and the visitor finds his way readily to the Abbey ruins for himself.)

At the beginning of the last cent. are among the best examples of their Studley Royal was the property of class,—perhaps indeed the very best;

John Aislabie, who had married the heiress of Mallory. The families of Aleman, Le Gras, Tempest, and Mallory had successively held Studley for five centuries. Mr. Aislabie, after having been for many years in public life (he had become Chancellor of the Exchequer), retired to Studley, and set himself to lay out and plant the park round the manor-house. which he partly rebuilt. Besides the park, he laid out a part of the valley of the Skell as a pleasure-ground; and his works here acquired so great a reputation, that Studley became known as the "most embellished spot in the north of England." From the Chancellor's son, William Aislabie, Studley passed to two heiresses in succession, Mrs. Allanson, and Mrs. Lawrence. On the death of the latter in 1845, it passed by will to Earl de Grey, whose nephew succeeded in 1859, and was raised to the Marquisate in 1871.

The pleasure grounds of Studley Royal, which we now enter, were begun about 1720. Mr. Aislabie was assisted only by his gardener, William Fisher; and the original design was formed on that Dutch taste which King William had introduced, and which Sir William Temple had made fashionable by his gardens at Moor Park in Surrey. The stream, canalized, and opening at intervals into wide ponds, was led between terraced banks adorned with statues, and bounded by tall ever-green hedges. Enough of this old arrangement has been retained to give a special character to the place; whilst walks have been cut through the woods behind the hedges, commanding wider prospects, well contrasted with the formal "pleasaunce" below. Those who can only admire the "natural" style of gardening will scarcely approve of the ponds, temples, and statues of Studley; but these grounds are among the best examples of their

occasionally afforded by the broad still water and dark wood-covered banks.

The valley is here much contracted. Its widest part is seen, shortly after entering the grounds, through an opening in a close vew hedge; the "Moon" and "Crescent" Ponds reflecting statues of Neptune, Bacchus, and Galen, spread out below; and on the opposite side, under the wood, is the "Temple of Piety." In this part of the grounds are some very fine Norway firs (black spruce), one of which, near the walk, is 132 ft. high and 121 ft. in circumference above its roots. A hemlock spruce, more than 60 ft. high, should also be (Like other trees in the noticed. park and grounds of Studley, these have been figured by Loudon in his 'Arboretum,' and are referred to by him as affording excellent standards by which to estimate the growth of their respective species under favourable circumstances.) The walks. sometimes passing by the side of the canal, and sometimes through the woods, afford many beautiful prospects, until the stream is crossed by a rustic bridge, and in the midst of natural wood a small irregular "pool" appears, with an island bearing a pillar to the memory of General Wolfe. The view from the Temple of Piety should be noticed. Beyond it, a path, cut through the wood, climbs the hill, and, passing through a tunnel in the rock, the Octagon Tower is reached, which, from the opposite side of the valley, has frequently been seen, crowning the hill. Here the visitor may rest, and enjoy the views towards Studley Hall on one side, and to How Hill (see post) on the other; before, passing through high woods of beach and oak, he reaches Anne Boleyn's Seat. This is a small arbour, from which is obtained a view of "Fountain Dale" with the ruins of its famous abbey rising on a strip of green meadow-ground, and tercians), applied to Thurstan, Abp.

and exquisite bits of landscape are | shut in by the wooded sides of the vallev.

> On the side of the stream is " Robin Hood's Well," a memorial, it may be, of the famous encounter between that "good man" and the "curtail friar of Fountains," whose fame was so widely spread that

" Robin he took a solemn oath, It was by Mary free, That he would neither eat nor drink Till that friar he did see."


After a fierce struggle, the friar threw Robin into the Skell, and obliged him to sound the "mot" for his 50 yeomen. The friar summoned as many bandogs, but Little John let fly his arrows among them, till the friar.

"who had kept Fountain Dale " Seven long years and more,"

called for a truce. According to Ritson, Robin Hood's bow and arrows were preserved at Fountains.

Passing beyond the well, with the ruins full in view rt., the visitor will reach a point at which the great ch. tower, rising above lower buildings and ruined walls in front, combines. with trees, undergrowth, and ivy. to form a picture which, for beauty of colour and outline, can hardly be surpassed.

In the year 1132 (the year after Rievaulx, the first Cistercian house in Yorkshire, had been founded by Walter Espec, who placed in it a colony of monks sent from Clairvaux by St. Bernard) certain Benedictines of St. Mary's at York, who had become greatly dissatisfied with the lax discipline of their own monastery, and were much influenced by the fame of St. Bernard (reformer of the Benedictine order, himself Abbot of Clairvaux, and founder of Citeaux, whence the reformed Benedictines took the name of Cis-



GROUND PLAN OF FOUNTAINS ABBEY.

of York, to procure for them the restoration of proper rule in the house of St. Mary's. Thurstan attempted it in vain; the discontented monks, after a scene of great violence, took refuge in the Abp.'s palace in York, and afterwards accompanied him to Ripon, where, about Christmas in the same year, he assigned them a place of retreat in the valley of the They sheltered themselves at first under the rocks which bordered the valley, and beneath some spreading yew-trees which still remain; and afterwards built wooden cells and a chapel under an enormous elm. which survived until the Dissolution. Here they underwent great hardship and privation for two years; and had obtained St. Bernard's leave to remove to one of the granges of Clairvaux, when Hugh, Dean of York, during his last illness, caused himself to be conveyed to Fountains. assumed the habit of the monks, and died, leaving them considerable property. From this time wealth poured in on the fortunate Cistercians. They began to build in more substantial fashion, and under the direction of monks (one especially, Henry Murdac, the 3rd abbot), who were personal friends of St. Bernard, and who no doubt brought the plan of their new house from Clairvaux. "Fontes" -- "Fountains" -- was the name given to the monastery, no doubt, as Matt. Paris asserts, from the springs which burst forth in this part of the valley. Six still rise within the site alone. The abbot, Henry Murdac, was raised in 1147 to the see of York, after the deposition of St. William (see York Minster. Rte. 1); and certain partisans of the latter attacked and set fire to the Abbey of Fountains. How much of the work was then destroyed we cannot tell; but the building continued throughout the 12th century. The choir of the church was commenced by Abbot John in 1203. This

between that year and 1247 the house was ruled by John of Kent, who added the transeptal aisle at the east end of the church, called the "Nine Altars"; built the southern part of the great cloister, the infirmary, and the hospitium. From this time there was little building, and little need of any, at Fountains, until Abbot Huby (1494-1526) raised the great tower which still dominates over the vallev. Fountains had long before become one of the wealthiest religious houses in Yorkshire. Its annual value at the Dissolution was 9981.—the Benedictine Abbey of St. Mary's at York alone exceeded it in yearly income: and if its monks had exchanged the ascetic rule of St. Bernard and Abbot Murdac for the life of comfortable country gentlemen. the house does not seem to have been in a bad state when the last abbot. Marmaduke Bradley, "the wisest monk within England of that cote, as Layton called him-" well learned, and a wealthie fellow "-resigned his monastery into the hands of the royal commissioners. At this time the lands of Fountains extended "from the foot of Pennygent to the boundaries of St. Wilfrid of Ripon, an uninterrupted space of more than 30 miles. Besides many other wide domains, the lands in Craven contained, in a ring fence, a hundred square miles, or 60,000 acres on a moderate computation."-Whitaker.

part of the valley. Six still rise within the site alone. The abbot, Henry Murdac, was raised in 1147 to the see of York, after the deposition of St. William (see York Minster, Rte. 1); and certain partisans of the latter attacked and set fire to the Abbey of Fountains. How much of the work was then destroyed we cannot tell; but the building continued throughout the 12th century. In front is the great Church, with its cannot tell; but the building continued throughout the 12th century. Close to the abbey mill, we enter the immediate precinct. (The walled Close, a parish of itself, of course, far beyond the precinct.) In front is the great Church, with its lofty tower, and the long range of from its S. side to the Skell. I. the steep side of the valley rises above was nearly completed in 1220; and

sheltered the first colonists of Foun- outer court, when the abbey was tains; and on a knoll, between the bridge and the mill, are the venerable which, beyond doubt, vew-trees. have witnessed all the changes of Fountain Dale from a period long before the Conquest. They are still known as the "Seven Sisters," although but 2 now remain. These are of great size, with twisted, fastdecaying trunks, one of which is 25 ft. in circumference. De Candolle supposed these trees to be more than 12 centuries old; but they may very well be far more ancient, since it is impossible to ascertain at what time their growth ceased. They are at any rate the most certain relics which the valley now contains, of the first two years during which the fugitives from St. Mary's led their struggling life here.

The abbey ruins have been carefully protected since they came (in 1768) into the possession of Mr. Aislabie, and are kept with the utmost order and propriety by their present owner. Since 1848 a series of excavations, under Mr. Walbran's direction, have been made at the S.E. angle of the buildings. In this manner the foundations (marked by a lighter shade in the plan) of the abbot's house and of adjoining offices have been uncovered; and the arrangements of a great monastery may now be studied more perfectly here than on any other site in England. general plan of Fountains resembled that of Clairvaux or of Citeaux, and was probably supplied from one of those great houses, under the supervision of St. Bernard himself.

Crossing the Mill Bridge, the main gate-house (O) is immediately in front. This is now a fragment, but must have been of considerable size. Standing in front of it, the visitor may restore, in imagination, the scene that would have presented Yorkshire.

the great "hospitium" of all this country. He should pass at once to the Conventual Church, on the extreme left, most of which is so perfect, that at first sight it seems as if little more than a roof were wanted to restore it. It consists of nave, transept, choir, and eastern transept, or "Chapel of the Nine Altars." The tower is at the end of the N. transept. The floor was entirely cleared in 1854; and it was then found that, after the Dissolution, the woodwork of the choir had been used for melting the lead of the roof. Part of the furnace was discovered in the nave, and even the tomb-slabs had been removed in search of treasure.

The nave and transept (see the plan) are Trans.-Norm., and were raised between the abbacy of Henry Murdac and that of Ralph Haget 1143-1190). Excavations since 1854, however, have proved that a most remarkable and picturesque Galilee Porch was added beyond the W. front of the nave toward the end of same century. It had in front a double open arcade (part of which has been replaced in its original position, and is so unlike anything of the same period in England as to suggest a foreign designer). porch, 15 ft. wide, has been used for burial; and at the N. end is a tombslab with cross of the 12th cent.

The W. window of the nave was inserted by Abbot Darnton (1479-1494), whose rebus (an eagle holding a crosier, and perched on a tun, from which issues a label inscribed "dern. 1494," - the eagle, emblem of St. John, gives the abbot's Christian name) appears on a bracket, below the niche which contains a headless figure of the Virgin, the great patroness of the Cistercians. The view up the long and narrow nave of 11 bays is solemn and impressive. There is no triforium. The main itself to a stranger, on entering this arches (pointed) rest on massive circ.

piers (the bases of which are remarkable, forming seats); and above are round-headed clerestory lights. aisles have pointed vaulting, divided by semicirc. arches, the imposts of which are lower than those of the The whole design is main piers. singularly plain and unadorned; in perfect accordance with the austerity of Cistercian rule, and with the dislike expressed by St. Bernard for the sculpture and decoration with which "they of Cluny" filled their churches. There were chapels divided by screenwork in the 5 or 6 eastern bays of both aisles. During the clearing of the nave, two walled spaces were found below the level of the floor, on either side of the last bay adjoining the transept, one of which contained 9 large vases of rude earthenware, imbedded in its sides. These, it is probable, were placed there for acoustic purposes. The choir of the monks probably extended beyond the transept (as was the case in nearly all Norman churches); and the vases may have been intended to increase the sound either of voices, or of an organ placed over or near them. Similar vessels have been beneath the stalls of churches in England and elsewhere, and have usually been looked upon as acoustic devices, though it is difficult to say in what manner they would act. dots in the plan mark the processional stones which were found in the nave. but so worn and crumbling, that the turf was allowed to recover them.

The transept, like the nave, is Trans. - Norm. The dark, closed chapels of its eastern aisles should be noticed. Abbot Huby (1494–1526) constructed the fine Perp. tower which rises at the N. end of the transept. Its height is 168 ft. 6 in. Above and below the belfry-windows are inscriptions. Shields of the abbey and of the Nortons of Norton Conyers, who no doubt assisted in building the tower, are mingled with these inscriptions. Above the lowest window an derdale.

angel holds a shield with the initials of Marmaduke Huby. The mitred figure on the N. side is probably Abp. Savage; and the effigy above the ridge of the transept roof is no doubt that of Abbot Huby himself.

The first, or Trans. Norm. choir, was aisleless, short, and narrow. Its foundations are traced by lines of flagstones within the present choir (A in the plan), which was begun by Abbot John of York (de Ebor -1203-1211), continued by Abbot Pherd (1211-1219), and completed by Abbot John of Kent (1220-1247). The design is simple, yet very graceful, E. Eng. Some tesselated pavement remains before the site of the high altar. But the choir. however graceful, must have yielded in beauty to the Chapel of the Nine Altars (B), an eastern transept, which was also the work of Abbot John of A similar eastern transept. bearing the same name, was added to Durham Cathedral nearly at the same time, and Peterborough Cathedral has a transept of Perp. date, in the same position. The want of space for shrines and altars compelled these Fountains indeed was additions. never fortunate enough to procure the relics of any distinguished saint, although great efforts were made to obtain those of St. Robert of Knaresborough (see Rte. 20), who died whilst this transept was building; but the abbey possessed lesser relics, and altar-room was much required. E. Eng. work here is plain and massive, but the general design is of great beauty; the lofty arches, in line with the choir-arcade, giving much peculiar character; and the view. looking across the transept, from S. to N., is especially to be noticed. The great E. window was a Perp. insertion. The grey marble, which was used plentifully here and in the choir (although the greater part has disappeared), was procured by the monks from their own lands in Nid-

A door at the S.E. angle of the date. nave aisle leads into the Cloister Court: round which were ranged, as usual, the chief conventual buildings. On the E. was the Chapter-house, with passages beyond it leading to the abbot's house. S. were the fraterhouse, the kitchens, refectory, and buttery. W. stretched along the great cloister, with the dormitory above it. The court was originally surrounded by a cloister, with round-headed arcades, of which a portion remained in the last cent.

The Chapter-house (C in the plan) is E.Eng., but of an earlier character than the choir, and was possibly, as Mr. Walbran suggests, the work of Abbot Richard Fastolph (1153-1170), who had been prior of Clairvaux, and may have brought the design from that great abbey. It is rectangular, and was divided into 3 aisles by a double row of 5 columns, the bases of which alone remain. aisled Chapter-house is peculiar. It occurs at Jervaulx and at Beaulieu in Hampshire (both Cistercian), and at Netley (Benedictine) and Tintern (Cistercian). It is found only in monastic churches.

The brackets here are noticeable. The simple long leaf, ribbed in the middle, like the leaf of a hart'stongue fern, runs through the ornamentation of the abbey. Here two leaves are sometimes laid one on The abbots of Fountains, from 1170 to 1345, were (with two exceptions) buried here, and the coffins and tomb-slabs of 10 abbots (including the most northerly in the 2nd row from the east, that of John of Kent, the builder of the 9 altars) remain on the floor. The library and scriptorium were above the Chapterhouse, and were approached from the S. transept of the church. Beyond the groined passage leading to the base court and the abbot's house, is the Frater-house or general refectory

From its upper end was a communication with the cellar (N) and brewhouse.

A staircase (which has been repaired) leads from the S.E. angle of the cloister to the Hall of Pleas, or the court-house of the abbey; in which the seneschal and his officers held the courts of the Liberty of Fountains. Here are deposited some interesting relics found during the excavations. The most remarkable is the effigy of Roger de Mowbray, who died at Ghent in 1298, and was brought here for interment. It was removed here from one of the chapels in the N. transept. Some capitals and bands of shafts, worked in Nidderdale marble, should also be no-

Beyond the staircase on the S. side of the cloister is the kitchen (L), vaulted, with a single central pillar. The heads of the two fireplaces, "straight, and formed of huge stones, dovetailed together on the principle of an arch," are remarkable. two openings in the W. wall were hatches into the refectory. Like the court-house, this building is of the 12th cent.

The great Refectory (F), which adjoins, is E. Engl., 109 ft. by 464. A row of marble columns ran down the centre, but only the foundations of one remain. On the W. side is a recess from which one of the brethren read during meals. Adjoining is the Buttery.

Leaving the great cloister for the present, we proceed through the passage into the base court (D). this part of the abbey, as well as the foundations of the Abbot's House beyond it, has been discovered since 1848. The most remarkable feature here is the group of 3 prisons (M) on the E. side of the base court. were used for refractory monks, as well perhaps as for other offenders (E.). 104 ft. by 29, of Trans.-Norm. within the abbey liberty, and seem to have afforded different degrees of dis- | part (as far as the porter's lodge) is comfort, the innermost being the smallest and strongest.

The Abbot's House, approached by a long passage, extended beyond, and was built partly over the Skell. was designed, probably, by Abbot John of Kent, the builder of the 9 alters, and seems to have remained unaltered (after the E. Eng. period) until one of the later abbots built a separate refectory, and divided the great hall into several apartments. It was pulled down by Sir Stephen Proctor (temp. Jas. I.), who built Fountains Hall with the materials. The discovery of its true site is entirely due to J. R. Walbran, Esq., who directed the removal of the rubbish with which it was covered, being convinced that the Abbot's House was really placed here, and not in the great court W. of the church, as had usually been conjectured. arrangement of the house will be best understood from the plan. The hall (171 ft. by 70) must have been one of the noblest in the kingdom, and its central space was divided from the aisle which surrounded it by 18 marble columns. The Abbot's Chapel, with the altar mound (the slab has disappeared), was E. of the hall; and N. of it is a crypt (cellar and storehouse) in which, says tradition, the abbot's "6 white horses" were kept. This tradition is so far accurate, that the abbot, at the time of the Dissolution, really possessed "sex equi ad bigam." His garden and orchard extended E. of the church.

The visitor may walk from this point round the N. side of the ch., and, returning into the main court, enter the so-called *Great Cloister (G), the long vaulted range of which is so striking and impressive that the late M. de Montalembert is said, on entering it, to have flung himself on his knees in an ecstasy of admiration.

Trans-Norm.; the rest, which is E. Eng., was built by Abbot John of Kent. The part adjoining the church seems to have been divided into storehouses. Above, and extending the whole length, was the Dormitory, containing 40 cells, divided by wooden partitions. Stairs of approach wind over the porter's lodge, and there is another staircase N., by which the monks descended into the church.

In the great court, and on the river bank, are the Hospitium, or guest-house (I), and the Infirmary (H)—both of the first, or Trans-Norm. period. In the Hospitium is a boss bearing a Templar's cross. The order was closely connected with the Cistercians, and St. Bernard drew up their rules.

The last abbot but one, William Thirsk (1526-1536), whom Layton describes as "a varra fole and a misereble ideote," resigned his office privately into the hands of the royal commissioners, by whose advice it was bestowed (not without payment of a "consideration") on Abbot Bradlev. He of course knew that the house was doomed, and three years later resigned it to the king, receiving a pension of 100l. a year. The ex-Abbot Thirsk was concerned, or was said to be concerned, in the Pilgrimage of Grace (1537); and, with the Abbot of Jorvaulx, the Prior of Bridlington, and others, was hanged at Tyburn in that It was at first proposed to apply the revenues of Fountains towards the endowment of a bishopric of Lancaster; but this was set aside with other propositions of the sort, and the abbey, with the greater part of its estates, was sold in 1540 to Sir Richard Gresham. In 1597 Gresham's representatives sold the site to Sir Stephen Proctor, who pulled down the abbot's house, and built the house It is 300 ft. long. The most northern | called Fountains Hall with the materials. It was again sold in 1623, of considerable importance. and passed through three different hands until it reached those of the Messenger family, by whom the abbey, its franchises, and a small estate, were sold in 1768 to Mr. Aislabie for 18,000l.

Fountains Hall, built by Sir Stephen Proctor, stands a little beyond the West Gate; and as the guides do not aways point it out, the visitor should make a point of asking for it. It is a most picturesque James I. mansion, unaltered since its completion; and with its bay windows, terraces, and gables, forms an admirable subject for the artist. is nothing which calls for notice within the house, except some tapestry in the dining-room.

(A magnificent view over the plain of York is obtained from How Hill, about 4 m. S.W. of Fountains Abbey. There was a chapel of St. Michael on its summit, but the tower now seen there was built by Mr. Aislabie in 1778. A stone built into the wall bears the initials of Abbot Huby, with his motto. The hill was anciently called "Herleshow," either, suggests Mr. Walbran, as the place where the Saxon Earl of the county held his court, or from some early proprietor named "Herled.")

3 m. N.W. of Fountains is Grantley Hall (Lord Grantley, who is the representative of the Nortons). Here are some good pictures, including a portrait of Richard Norton, the patriarch of the "Rising in the North"-(see post, Norton Convers); " Charles I. and Henrietta Maria" (Vandyck); and "The Good Samaritan" (Annibale Carracci).

(b) Markenfield Hall, 2 m. W. of Ripon, well deserves a visit from the antiquary. It was for many centuries the seat of a family who took their name from this place, and were dows of the Dec. part are (except

nian, according to the old poem, was a leader at Flodden :-

"Next went Sir Ninian Markenfield, In armour coat of cunning worke."

One of their descendants was still living here in the time of Leland; but in 1569 Thomas Markenfield took an active part in the "Rising of the North," and on his attainder his estates were forfeited to the Crown. The licence to crenellate Markenfield was obtained by "John de Merkingfield" (who had been Chan, of the Exch. under Edw. II.) in 1310; and the house was probably commenced about that time. The plan (as the house now stands) is a large irregular court, formed partly by the house and partly by stables and other outbuildings, surrounded by a moat. The Dec. house was added to and altered in the 15th and 16th centuries.

The original portion is in the form of the letter L, with the hall in one part and the chapel in the other, both on the first floor, with other rooms under them, one of which, under the chapel, appears to have been the kitchen. The entrance to the hall was by a doorway in one corner, from an external stone staircase, of which the foundations remain, and the weather moulding of the roof over it. . . . One window in the gable is at a higher level than the rest, having been over the music gallery. The corbels of the original open roof remain. The present roof is modern. A doorway leads from the dais of the hall to the chapel, and on the S. side of the chapel is a doorway opening to what was apparently the priest's chamber, with a At the E. end of room above it. the hall is the solar, and a large garderobe opening from it. All these rooms (hall, chapel, &c.) are on the first story, upstairs. The rest of the house is Perp., and later. The winsembles that of Aydon Castle, Northumberland (of somewhat earlier date, 1280-1300), but, on the whole, Markenfield Hall bears a greater resemblance to the generality of south country than northern manor-houses. The large Dec. windows are not characteristic of a house built with a studious view to defence.—(J. H. Parker, Domestic Architecture).

The house now belongs to Lord Grantley and is occupied as a farm.

(c) A very pleasant day's excursion from Ripon may be made to Hackfall, proceeding thence to Well and Snape, and returning to Tanfield. This will be a round of about 20 m. The three last-named places will interest the antiquary. A long day may be spent very delightfully at Tanfield Stat., on Hackfall alone. the rly. to Masham is about 3 m. from Hackfall.

Hackfall is about 7 m. from Ripon. Taking the Tanfield road, turn off at Sleningford, and, passing the little village of Mickley, we reach that of Grewelthorpe, famous for its cream [Off the road, l., is seen the church of Kirby Malzeard, where the Mowbrays had a castle (no frag-The ch., which ments remain). stands beautifully in the valley, has some Norm. portions, and a Perp. tower, into which some curious early sculpture has been worked.] At Grewelthorpe the carriages must be left, and through a wicket at the entrance of the village, the woods of Hackfall are entered. (Each visitor must pay 1s. for his ticket, which is to be had at a cottage opposite the entrance.)

"Hackfall" (the oak fall or stream?) is apparently so named from a stream which here descends through a steep narrow glen entirely filled with trees and dense foliage to join the

those of the hall and chapel) square- the woods, and the stream was The Dec. plan closely re- here and there artificially "guided" under the direction of Mr. Aislabie. in whose time the place was pronounced by Pennant "one of the most picturesque scenes in the north of England." The path winds downwards to the river, crosses the "Hack" burn, and then re-ascends steeply toward Mowbray Castle-an artificial ruin which might be removed with advantage, and to Mowbrau Point, whence a wonderful view bursts on the eye, extending over the wide "vale of Mowbray" (as the northern portion of the great Yorkshire plain has been called, from the great lords who were once its chief barons) as far as the Tees and the sea. In front is a magnificent foreground of wood, rock, and partial flashes of water—the Ure winding on toward Tanfield and Ripon. combination of this near view with the great plain beyond, full as that is of historical recollections, is one of the great features of the Hackfall woods.

(A gate on the opposite side of the road, after leaving the Hackfall woods, will lead the tourist to Nutwith Camp—a square intrenchment. with a single foss, and a mound at the N.W. angle. It is no doubt Roman, and was on the line of a road proceeding to Catterick (Cataractonium), and crossing another Roman road through Wenslevdale. view from this camp is more extensive than that from Mowbray Point. but has not the same foreground. The plain of York extends E.; and N., looking beyond Wensleydale, a clump of trees on Richmond racecourse is visible. The view will amply repay a visit. Beacons on the hills in sight communicated with this camp from a vast distance on all sides.)

Newby Hall (Lady Mary Vyner). on the Ure, about 4 m. from Ripon, was built in 1705, from (it is river Ure. Paths were cut through said) a design by Sir Christopher Wren, but has since been much The house contains an important collection of sculpture, made on the Continent by the late Wm. Weddell, Esq., of whom there is a portrait by Battoni, and a bust by Nollekens. The most remarkable pieces are—the so-called Barberini Venus, a statue 5 ft. 11 in. high, in the attitude of the Medicean. arms, the right leg from the knee, and the head are modern: the rest is of fine Greek workmanship. fragment long remained in the vaults of the Barberini Palace. The restorations are by the sculptor Pacili. Muse, seated (the head is not original). A colossal head of Hercules. with a tripod of Bacchanals. A head of Minerva, in Parian marble, the casque and back part of the head Besides many other restorations. statues and busts, there is an antique sarcophagus of Pavonazzo marble, and a smaller one sculptured with There are some boys and fruit. paintings, chiefly family portraits, in the house, and the drawing-room is hung with fine Gobelins tapestry.

Skelton Ch., an elegant Gothic building, with spire (Burgess, archt., stained glass by Saunders), was erected by Lady Mary Vyner, in memory of her son so cruelly murdered by Greek brigands, May, 1870.

Ripon to N. Allerton.—Rail.

Leaving Ripon, the rly. proceeds for a short distance along the l. bank of the Ure, and then turns away.

The woods of Norton Conyers are seen l. before reaching Melmerby. Strike (now the property of Lord Downe) is the ancient home of the Nortons, famous for their share in the "Rising of the North" in 1569. They were ardent in the cause of the "old religion," and of the Queen of Scots. Old Norton had no doubt fine.

been out in the Pilgrimage of Grace, the banner of which was the same he displayed in the rising; and the Nortons had undertaken to kill the Regent Murray, as he passed Northallerton on his return to Scotland after the Commission at Westminster in January, 1569; but this intention was countermanded. Wordsworth, in his 'White Doe of Rylstone,' has accepted the popular tradition, which follows the old ballad:—

"Thee, Norton, with thine eight good sons, They doom'd to die, alse, for ruth!"

But the facts are, that, although the family were ruined after the Rising of the North, and their estates confiscated, only one of the sons was executed. Richard Norton. the father (whose offence was increased by his having been the Queen's sheriff for Yorkshire in the preceding year), escaped with his sons Francis and Sampson to the Low Countries, but when or where they died is unknown. the third son, was the ancestor of the Lords Grantley. Norton subsequently became the property of the Grahams; one of whom, Sir Richard Graham, according to the popular fled, popular story, fled, desperately wounded, from Marston Moor. He was followed to Norton by Cromwell, who galloped into the hall and up the staircase, arriving just in time to shake Sir Richard in his bed until he died. As the horse turned to descend the broad staircase, the print of his hoof, with the shoe, was stamped on the topmost stair, where it still remains to confound the incredulous. (It appears to be the impression of a horseshoe heated.) It is true that Sir Richard Graham was severely wounded at Marston, but his death did not occur until 1655. 10 years after the battle. The house of Norton is for the most part Elizabethan, and seems to have been built by the last Norton. The woods are

3 m. Melmerby Junct. Stat.

Railway lines branch from this W. to Tanfield and Masham. N.E. to Thirsk by Baldersby and Topcliffe.

m. from Melmerby, l., is the ch. of Wath (Celt., a ford; it is the same as the Gaelic Ath, as the Athlone. "Nadum" and the Fr. "Gué." are cognate) - worth a visit. Wath Church is E.Eng., with Perp. insertions and alterations. The chancel is unusually long (remark the manner in which the door and window above it on the S. side are arranged), and has adjoining it, N., a vestry with priest's room above it, like that at Well, except that this was accessible from within, by a staircase in the S.W. angle. A narrow hagioscope opened from the upper room toward the altar. In the chancel is a double piscina with shafts, and 3 sedilia (all E. Eng.). Remark also an indifferent tablet by Flazman, to the Rev. Thos. Brand, 15 years rector (d. 1814), and a brass against the E. wall commemorating Stephen Penton, also rector, d. 1706, with a long string of advice to his parishioners. In the S. transept is the much-worn brass of Rich. Norton (that of his wife is lost), who, with his wife, died of the plague in 1433; and under the flooring of the pew belonging to Norton Conyers are brasses of Rich. Norton, Chief Justice of the King's Bench, 1420, and of his wife. The boards are so fixed, however, that the slab can be exposed when necessary. The arms of Norton have been defaced on the later brass: and an "address to the rebels" of 1569, written by Lord Burghley, refers to the defacing of "former ensigns of nobility" as a "due prejudice to disloyal and untrue subjects," whence it has been thought probable that the Norton shields in this ch. were erased after the rebellion. The Norton arms, however, remained in their chapel, a niche or recess provided with a

together with several brasses of the family, now lost, about 1660, as appears by a survey of that time. In the transent are monuments to Sir Richd. Graham (Cromwell's traditional victim) and others of that family. Against the S. wall is a Dec. tomb with gabled canopy, probably belonging to the Nortons.

The base of a stone pulpit remains attached to the S. angle of the chancel arch. The pulpit itself is of wood. The font (E. Eng. base with later bowl) should be noticed. In the chancel are some fragments of Dec. stained glass, and one fine shield, with the eagle of Monthermer. There is a fine Flemish chest in the vestry.

The Masham branch Railway ascends the valley of the Ure at Wath, and touches the l. bank of that river near

Tanfield Stat.

Tanfield was the ancient lordship of the Marmions; and the Church, very interesting in spite of restoration, is rich in their monuments. "townlet," as Leland calls it, stands on the l. bank of the Ure, which he "crossed by ferry for lack of bridge." The Marmions' Castle, or "Manor Place," was on the S. side of the ch., adjoining the river; and its "fair towered Gatehouse," which Leland mentions, is still in existence, though the rest has perished. It is Perp., and a striking ivy-covered oriel fronts the visitor as he passes toward the Church. This was originally Norm., with Dec. and Perp. additions. has been "restored" at much cost. but with little judgment. The Norm, chancel arch has been replaced by one of Perp. character. and the new roof is far too pretentious for a simple village church. The so-called confessional (?) at the N.E. side of the chancel arch is

small trefoil-headed opening on the line before 1340, when the widow of E., and two a little higher, S. These Robert, the last of the line, was reapparently are merely Squinches, openings pierced in a pier to command a view of the high and side alters at the raising of the Host. The N. aisle of the nave contains seven Marmion tombs, and is singularly picturesque, with its mouldering effigies and mysterious lights. It was always the burial-place of the Marmions, but was rebuilt by Maude de Marmion in 1343, when the earlier monuments were replaced in it. The chief high tomb is that either of Sir Robert Marmion (temp. Edw. III.), or of his brother Sir John, who married sisters, daughters of Herbert de St. Quintin. The effigy affords a good study of armour. The knight wears a collar of SS. His wife has on her robe the arms of Marmion impaling those of St. Quintin. Over the effigies remains the iron "herse," one of the best examples in England. (There is a brass "herse" over the effigy of an Earl of Warwick in the Beauchamp chapel at Warwick.) This is an open frame of iron-work, with prickets for lights rising from it. It was usually covered with rich tapestry. effigies in this aisle are a knight (cross-legged), temp. Hen. III.; a lady in a long mantle, temp. Rich. II. (Maude de Marmion?); a lady "with the apparail of a vowes" (vowess), as Leland describes her, in a mantle, with an inner swathed dress, which may represent that of some religious order; and a knight and lady, temp. Hen. III. The greater part of these monuments are much worn and disfigured, but all are of interest. Some ancient stained glass, with shields of Marmion and St. Quintin, and borders of bees or butterflies, has been collected in the last N. window of the aisle toward the east.

In the nave is a plain coffin-lid of mountain limestone, of early character.

married. Sir John Grev of Rotherfield married the sister of the last Marmion, and received the lordship on condition of his assuming the name. His son Sir Robert left an heiress, who carried Tanfield to the Fitzhughs.

(Three very remarkable earthworks remain at Thornborough, 11 m. N.E. of Tanfield. They are of the same character as those at Blois Hall, near Ripon (see ante), and are circular, enclosing, with a lofty mound and trench, an open central platform. They are in a line, of about 1 m. long, with an earthwork at the centre, and one at each Nothing has been found to end. indicate their date or purpose, although it has been conjectured that they are temples of the British period. Four of the many adjacent tumuli have been opened, and disclosed rude pottery, chipped flints, many of which had been exposed to great heat, and other indications of præ-Roman interments.)

Tanfield is about 3 m. distant from Hackfall, see p. 294.

Masham Terminus. This commonplace market town on rt. bank of Ure, has large sheep fairs: poor Inn, King's Arms.

The Church of Masham, not very interesting, but having a tower, the lower part of which is late Norman. The upper part is octagonal, and from it rises a Dec. spire. There is a good late Norm. W. portal. At the E. end of the N. aisle is the elaborate monument (temp. Jas. I.) of Sir Marmaduke Wyvill and his wife; he in armour on the upper shelf, she in hood on a lower one—both of marble. The churchyard contains the shaft of a cross of the Norm. period: circ., with figures of the Saviour and his Apostles The Marmions expired in the male round the top, and other sculptures

below. In the ch.-vd. are the grave-! stones of Julius Casar Ibbetson, d. 1817, a landscape artist of some reputation (many of his works are preserved at Swinton Park, see post); and of George Cuitt, d. 1854, whose etchings, especially those of the 'Abbeys of Yorkshire,' are of high excellence.

Masham was the lordship, first of the Mowbrays, and afterwards of the Scropes, but no memorials of either house remain in the church. It was Lord Scrope of Masham-

-cruel. Ingrateful, savage, and inhuman creature"-

who conspired with other lords against Henry V. when about to sail from Southampton for the campaign of Agincourt. — (See Shakspeare's 'Henry V.')

Swinton Park, S. of Masham. The house, a castellated mansion, erected in the present cent. by one of the old Yorkshire family of the Danbys, to whom it passed by marriage from the Scropes, was sold 1881. The estate, whose rental exceeds 12,000L per ann., extends over a wild and picturesque grazing district, with much moorland. The house contains a habitable suite of state rooms commanding fine views, and the pleasure grounds, with abundant clumps of rhododendrons, come close up to it. A small brook, descending from the more distant deer park, is dammed up to form a charming small lake, the resort of wildfowl in winter. By inquiry at the lodge the tourist may find his way to a remarkable stone monument (possibly Druidical). There are three stone circles: the smallest one is roofed over and has in the centre a large block or slab that may have been an altar. Little or nothing is known of their origin, and they are well worthy investigation by competent archæolo-

wall as far as a bridge, then to rt. down hill and along a stream. The stones stand in a wood 3 m. E. of Masham.

Within the park is a ravine, called Quarry Gill, through which the Eller beck rushes, and is crossed by a lofty bridge of 3 pointed arches, constructed by Mr. Danby at great cost. A very wide and fine view is commanded from a seat on one side of the ravine.

The Church of Well is for the most part early Dec., with a S. door remaining from a Trans.-Norm. building. It was restored (1854), and without any great destruction, al-though the arrangement of Lord Latimer's monument was then altered. and the fragments of stained glass collected into one window. peculiar flat-headed windows of the nave are characteristic of churches within the rule of the Nevilles (who were lords of Snape Castle-see post), and are most conspicuous at Staindrop, near Raby Castle, where most of the Neville Earls are buried. On the N. side of the chancel is a chantry (now used as the vestry). which has a priest's room over it. accessible from without, and with a window opening to the chancel. The altar of the chantry remains. At the E. end of the S. sisle is the monument, with effigy, of John Neville. the last Lord Latimer (1596), son of the Lord Latimer who married (for his 2nd wife) Queen Catherine Parr. The monument is covered with the names of certain Yorkshire gentry, who seem to have paid a visit of honour (?) to the tomb, July 9, 1618. The window above contains some fine shields of arms of the Dec. period (Neville, Percy, Ross, &c.), so finely dispered and designed as to deserve engraving. On the floor adjoining is laid a square (with border) of tesselated pavement from a Roman villa gists. To reach them, skirt the park discovered here in 1859 (the rest of the villa remains under the sward, untouched). Here is also a tomb-slab, with a sword on one side of a cross, on the other a hammer and horseshoe; perhaps commemorating an armourer (?).

The village, named from a holy well, dedicated to S. Michael, still to be seen near the entrance, contains a hospital founded and supported by the Nevilles, and their successors the Cecils, Earls of Exeter—(there are no remains of importance) and a little beyond it, W., the lower story of an E. Eng. house worth examination. A vaulted apartment, with 2 central piers and carved wall-brackets (all 12th cent.), now serves as the farmhouse kitchen. Nothing is known of its history.

1 m. from Well is Snape Castle, now a farm-house, but long a stronghold of the Nevilles, and afterwards of the Cecils, Earls of Exeter. It is approached by a picturesque avenue of lime-trees; and the house, with its ivy-covered tower, and long curtain of grey wall, is worth the sketcher's attention. It is late Perp., with large Elizabethan additions, and in plan was a quadrangle with towers at the corners. On the hall-ceiling are the arms of Cecil impaling those of Neville. The interior has been much changed; but a chapel (late Perp.) remains unaltered. great hall of Snape, says a local tradition, stood a long oaken table, with hollows sunk in it all round, serving for plates. A knife and fork were chained beside each, and the whole was "washed down" at once after dinner.

Adjoining is Thorpe Perrow (— Milbank, Esq.), in a park of about 200 acres. The gardens are large and fine.

From Melmerby to N. Allerton, 21 m. Sinderby Stat.

(L. 11 m. is Kirklington, where is a good Church (Dec. with fine Perp. tower), containing the effigies of a knight and lady (14th cent.) belonging to the house of Mowbray, and the tomb (with effigy on a high slab, ugly and cumbersome) of Sir Christopher Wandesford, temp. Chas. I. He accompanied Strafford to Ireland, and was himself made Deputy on Strafford's leaving. Chas. I. created him Baron Mowbray and Musters, and Viscount Castlecomer. but he would not assume these honours whilst the king's fortunes were so depressed, and his grandson was the first to do so. There are also a Wandesford brass (1463), and some fragments of stained glass, among which is a singular representation of the Holy Trinity, with 3 heads and one crown, and in the rt. hand what seems to be a loaf (the bread of life?).

The old hall of Wandesford, with the exception of one wing, was pulled down by a steward without the owner's knowledge about 50 years since. The remaining wing, now a farm-house, contains one room with carved panels and an enriched ceiling, temp. Eliz.

Between Sinderby and the river Swale, the line passes the ch. of Pickhill, rt. It is partly Trans.-Norm., and contains a late parclose screen with inscription.

The rly. crosses the river Swale, and has a station at

5 m. Newby Wisks. 4 m. beyond Newby it reaches

Northallerton Junct. Stat. (see Rte. 16).

Rail from Melmerby Junct. to Thirsk.

1½ m. Baldersby Stat. Nearly 1 m. rt. the tall spire of Baldersby Church is conspicuous, and will be a good

a point of seeing one of the best modern churches in Yorkshire. was commenced (Butterfield, archit.) by the late Lord Downe, who had shortly before purchased Baldersby Park from Mr. Hudson of railway celebrity. Lord Downe died in 1856 and the ch. was completed in 1858. It is early Dec. in general character, with a campanile and lofty spire (165 ft. high). The internal walls are of red brick, with bands of white stone inlaid with grey quatrefoils. eastern bay of the chancel is divided from the rest by a shaft, carrying a peculiar foliated roof rib. All the windows have stained glass --- by O'Connor (E.), Preedy (aisles and clerestory), and Wailes (W.). Chairs are used instead of long seats. The services are choral, and the doors of the ch. are always open. In the ch.-yard is a cross on steps. A vicarage, school-house, and cottages surround the ch.-yard, and group pleasantly with the ch. itself.

Baldereby Park (Lord Downe) contains some fine caks, but the country here is scarcely picturesque. The Swale bounds it on the N. It was known as "Newby Park" when in Mr. Hudson's possession.

After crossing the Swale we reach

2 m. Topcliffe Stat. The village is distant 2 m. S. The Church (the dedication of which to St. Columba indicates its very early foundation, probably dating from the 6th or 7th century) has been entirely rebuilt. and its interest for the antiquary nearly destroyed. It still contains however, some Trans.-Norm. portions, and the fine brass of Thomas de Topcliffe (1362), with his wife (d. 1391) It is no doubt of Flemish workman-Both figures wear mantles, and the lady has the gorget. The canopy displays souls, angels, &c., as is usual with Flemish work of

guide to the visitor, who should make a point of seeing one of the best modern churches in Yorkshire. It was commenced (Butterfield, archit.) by the late Lord Downe, who had shortly before purchased Baldersby Park from Mr. Hudson of railway celebrity. Lord Downe died in 1856 and the ch. was completed in 1858. It is early Dec. in general character, with a campanile and lofty spire (165 ft. high). The internal walls are of in England.

This period. On either side is a shield, displaying what has been described as a "chevron between the service with the heraldic fancies of the time. It has, however, been suggested that these "pegtops" are in reality "otelles," an ame given to rate, has been found nowhere else in England.

Topcliffe was one of the great lordships of the Percys, Wm. de Perci having received it from the Conqueror, with \$5 other "manors" in Yorkshire. Their principal Yorkshire castles were here—at Spofforth—at Wressel—and at Leconfield, near Beverley. A fir-crowned mound alone marks the site of their house here, which was situated at "Maiden Bower," 1 m. from the village.

Between Topcliffe and Thirsk (2½ m.) there is nothing which demands notice. For

Thirsk Junct. Stat., see Rte. 16.

Bedale (Stat.). Inn: The George. (The name is possibly from honey-bee; there is a Beedale among

Isurium (Boroughbridge) to Cataractonium (Catterick), we reach (30

min. from Northallerton)

the wooded glens near Hackness.) The town (Pop. 1145) consists of

ROUTE 23.

NORTHALLERTON TO LEYBURN. BY (MIDDLEHAM, BOLTON, BEDALE JERVAULX).

A branch of the N.E. Rly.

4 trains daily in 1 hr. 5 min. The country through which it passes is interesting, and Leyburn (easily accessible by this line) is the best point from which to explore all the lower part of Wensleydale. A branch line (Rte. 24) unites Leyburn with Hawes in Wensleydale, and there meets the line of Midland Rly., which connects Settle with Carlisle.

At Ainderby Steeple (Stat.) the ch., Dec. with additions, is seen l. (Steeple is here used, as it is frequently in Yorkshire, to signify the tower, and not the spire, as in the S. and W. of England.) The Church (restd., 1870) contains some stainedglass windows by Clayton and Bell. Within the altar-rails is the brass William Caleys, rector, and "confessor to Lord le Scrop." The Swale, here flowing between flat banks, is then crossed; and passing i stations at Scruton and at Leoming

one long wide street, with a market cross remaining in it, and the Church This (although at its upper end. it has been restored) is of great interest, and well deserves a visit from the ecclesiologist. It is early Dec. with some Perp. additions, and others which seem to have been made in 1556 (temp. Mary). The S. side of the nave was entirely rebuilt (after the old design, which is a somewhat unusual one) in 1855; the plainer arcade N. was only "tooled over." Adjoining the chancel arch, at the end of each arcade, is a small arch, which can hardly be a hagioscope, and is difficult of explanation. The nave clerestory is Perp., as is the roof, which has not been tampered with. The chancel roof is also Perp., but it has been raised. In the S. aisle the east window remains untouched. and is an excellent specimen of early (geometrical) Dec. The east window of the chancel (filled with stained glass by Wailes) has been rebuilt, it is said, precisely on the original design, which shows a later Dec. than the aisle window. Holes for supporting the rood beam remain on each side of the chancel arch. the wall of the N. aisle is the effigy of a priest (early Dec.) of the Fitzalan family—no doubt, Thos., son of Brian Fitzalan, who was rector of Bedale, and living in 1254. In this aisle also is a remarkable incised slab, with the rude figure of Thomas Jackson of Bedale, merchant, who died July 1st, 1529, and 2 daughters. the S. aisle is an indifferent mont., by Lane, where the rly, crosses the line | Westmacott, to Lady Beresford and of the Roman road which ran from her father, H. Pierse, Esq., of Bedale

The most interesting monuments in the ch., however, are placed on either side the tower arch. On the N. side are those of Sir Brian Fitzalan. the viceroy of Edward I. for Scotland, and his wife. The effigy of Sir Brian is one of the finest sepulchral memorials in England, and deserves the most careful attention. The sculptor, whoever he may have been, ranks with the unknown artist who designed the noble Alard efficies at Winchelsea, nearly of the same date. The lady at his side is not so good. Her attitude is strained, with the knees slightly bent towards Her long mantle was husband. coloured pale pink, of which some trace remains, and from her hand falls a long scroll. These effigies were originally in the S. aisle, at the end of which was probably the Fitzalan chantry. On the S. side of the tower are two unknown effigies. temp. Edw. III., the design of which may serve to show the great superiority of the earlier artist. In the ch. are many modern memorial windows of stained glass.

The tower arch, Dec. and fine, was opened during the restoration. The font (modern) is placed within it. The tower itself is Dec. in the 3 lower stages, Perp. in the upper-It was probably the work of the Fitzalans at a time when Scottish forays rendered protection necessary. and was accordingly built for defence, with a portcullis at the foot of the "The existence of the staircase. portcullis itself was unknown till it fell, from the effects of a stroke of lightning. All communication with the clock and bells was stopped till it was hacked away."-W. H. L. The lower story of the tower contains a chamber with fireplace and garderobe seat.

Below the chancel is a crypt (the entrance is from without, on the S. side), of early Dec. character, retaming its original vaulting, and its stone altar with the 5 cresses. Here are

preserved some curious fragments of crosses and of tomb-slabs, found at different times in the ch. and ch.-yard. which are probably of Saxon workmanship, and, at any rate, indicate the existence of a ch. on this site long before the erection of the present building. The antiquary will deeply regret the "restoration," and almost rebuilding, of this very fine ch., especially as the greater part of the work is said to have been wholly uncalled for.

The Fitzalans were lords of Bedale Castle, all traces of which have disappeared. The manor afterwards became the property of the Digbys, whose representative was attainted in 1569.

Bedale Hall (H. M. Pierse, Esq.) contains a fine drawing-room, added in the reign of George II., 60 ft. long by 30 wide. The ceiling is much enriched.

Bedale is the best place from which to visit Hornby Castle 5 m. N., or Jervaulx Abbey, 5 m. S., since it can furnish means of conveyance, which are not to be relied upon at the nearer Stat. of Jervaulx, 3 m. (Newton-le-Willows).

Hornby Castle (Duke of Leeds) is 5 m. from Bedale, the nearest place at which any carriage can be obtained. The walk is pleasant, with fine views. and the pictures at Hornby well deserve a visit. The castle is generally to be seen at all times.

The ch. of Patrick Brompton (restored, 1864) should be seen on the way to Hornby. It contains Trans.-Norm. work, and the early Dec. work of the choir is of especial value and interest. Some stained glass remains. The ch., ded. to St. Patrick. belonged to St. Mary's Abbey. York.

ing its original vaulting, and its stone [Hornby Castle, which belonged altar with the 5 crosses. Here are from an early period to the St.

Quintins, passed from them by mar- 1 riage to the Convers, thence to the Darcys, and from them to the (Thomas Osborne was Osbornes. created Duke of Leeds by Wm. III. He was chairman of that "Committee of the whole House" which resolved, on the flight of Jas. II., to place William on the throne) The castle, which, according to Leland, was before but "a mean thing," was rebuilt by William Lord Convers, in the early part of the 16th cent. One ivy-covered tower, called "St. Quintin's Tower," is earlier than this: but the greater part of the castle, although it retains the general plan of Lord Conyers' building, has been modernized. It is rarely inhabited, and has an air of neglect The park is extenand discomfort. sive and well wooded. The views from it are fine, especially that from below St. Quintin's Tower, ranging over the vale of Mowbray to York, with the Cleveland and Hambledon hills in the distance. Under certain effects of light, especially when light spring showers are fleeting across it, this scene will recall some vast landscape by Rubens or by Turner.

Besides numerous portraits of Conyers, of Darcys, and of Osbornes, the chief pictures to be noted here are

Great Hall.—Vandyck: Lord Newburgh, full length, in black, with mastiff, very fine; Earl of Stafford. Lord Burghersh, Holbein: length, with white staff of office; Earl of Worcester; Earl of Pembroke. Sir G. Kneller: Duke of Schomberg. Velasquez: Marquis of Montrose (?) on a piebald horse. He is richly dressed, with a ruff and damasked armour. In the ears are carrings. It seems very doubtful whether this can possibly be a portrait of Montrose.

billiard-Boom.—Vandyck: Family tude when the ex-king of Chas. I. Canaletti: 4 very fine again on the Continent.

Venetian scenes, 2 of them festivals, with the Bucentaur conspicuous. The 2 others are views from the head of St. Mark's Place. These are among the best Canalettis in England. The skies are especially clear and beautiful.

First Drawing-Room.—Vandyok: Earl of Derby (head) fine. Rubens: The 4 quarters of the globe, with tiger, crocodile, &c. The family of Rubens. Paul Veronese: A music party, fine. Hogarth: Scene from the Beggar's Opera.'

Second Drawing-Room.-4 Canalettis, scarcely equal to those in the billiard-room. Gaspar Poussin: Adoration of the Shepherds, curious. Sir J. Reynolds: portrait of a boy. Here also is one of many repetitions of the remarkable picture at Hampton Court, usually called the 'Family of Henry VII., and exhibited at S. Kensington in 1866. Mr. Scharf has however proved (from an entry in the catalogue of the pictures of Chas. I., to whom the Hampton Court original belonged) that the children represented are really those of Christian II., King of Denmark — the youngest being Christina, afterwards Duchess of Milan, whom Henry VIII. wanted to marry. The picture at Hampton Court is most probably by Mabuse; and it seems likely that this repetition is also from his hand. There are others (of more or less value) at Wilton House, at Sudeley Castle, at Corsham, and at Longford Castle. As these children were nearly related to Charles V. (whose sister Isabella married Christian II.), and as their parents (after the expulsion of Christian from Denmark in 1523) took refuge and sojourned for some time in England, it is quite probable that these repetitions may have been sent over as memorials of gratitude when the ex-king had settled

Lady Elizabeth Harley. Titian: The 4 Evangelists.

Adioining the park is Hornby Church, chiefly Norm., with a late parclose screen that retains its painting of flowers, fruit, and parrots. the ch. are 2 early efficies of unknown knights, and 2 of a knight and lady, circ. 1400. On the bascinet of the knight are the words "Johan Mare" (not "Jhesu Maria"); but in spite of this he has not been identified. (One "John Mare" held one quarter of a knight's fee of the honour of Richmond in 1218.) There is also a brass for Thomas Mountfort and family, 1489. Ralph Neville, 3rd Earl of Westmoreland, is buried in this ch. Wm. Lord Convers had married his daughter; his only son died young, "whereupon," says Leland, "the Earl took much thought, and died at Hornby Castle," 1523.

Tunstall. Bishop Cuthbert Durham (1530, died 1559), the friend Erasmus, "who only burned books," and died at Lambeth, in the nominal custody of Archbp. Parker, was born at Hackforth, close without the park of Hornby Castle. His brother, Sir Brian Tunstall. killed at Flodden. The family (which took its name from the neighbouring village of Tunstall) was one of great antiquity here.

(You may walk from Hornby by Brough Hall and Catterick to the Catterick Bridge Stat. on the Richmond Rly. The distance is about Rte. 25). 4 m. (see Catterick Bridge is the first stat. beyond Richmond.

Crakehall Stat., 3 m. from Hornby.

Jervaulz Stat. (near Newton-le-Willows) is about 3 m. from Jervaulx Abbey. Pop. 306.

State Bedroom.—Sir G. Kneller: | usually pronounced "Jarvis." is the Norm.-Fr. form of Yore, or Uredale) has suffered more complete demolition than any other of the greater Yorkshire abbeys. But scanty fragments remain in the Marquis of Ailesbury's grounds. The church has been levelled with the earth, and only its ground-plan is discernible from its foundations. One doorway leading into the nave of the ch. at one end retains its arch mouldings. The ruins, which closely adjoin the Ure, are picturesque with ivy and are well kept.

Akar Fitz-Bardolph, a follower of the great Earl of Richmond, gave, in the reign of Stephen, land for building a religious house at Fors in Wenslevdale to Peter de Quincev and certain other monks from Savigny, who were then at the Earl's court. some difficulty Peter procured leave to remain at Fors, where a colony from Byland was to be sent, and the new house was to be subject to that abbey. In 1150 monks from Byland arrived at Fors; but the site was barren and solitary; and in 1156 Conan of Brittany, Earl of Richmond, gave them the meadows by the Ure. to which they at once removed, and on which they built the abbey of

Jervaulx.

The monks began to build at once. and they seem to have continued until at least the end of the century. since the existing remains range from Trans.-Norm. to E. Eng. Little or nothing was known of the groundplan until 1805, when a complete and most careful examination was made by direction of Lord Ailesbury. to whom the ruins belong. had previously been used as a quarry by the farmers for some miles round. and for the repair of the high road. The plan is nearly the same as at Fountains and other Cistercian houses —the cloister court on the S. side of the nave, the chapter-house on the E. side of the cloister, the dormitory Jer- or Jor-vaulx (the name, W., and the refectory and kitchen S.

The Abbot's house was beyond the force itself on his speculative eye kitchen S.E. must surely have been extreme.)

The church was of large size, and contained many altars. That in the N. transept remains perfect, with its 5 crosses, and a recess in front, probably for relics. Before the site of the high altar is the mutilated effigy of Lord Fitzhugh (died 1424), a descendant of Akar, the founder of the first monastery at Fors. The Chapterhouse (48 ft. by 35 ft.), erected most probably before the close of the 12th cent., but of strong E. Eng. character, was divided into three aisles, as was usual in Cistercian houses. is so at Fountains, and many others.) The pillars of grey Nidderdale marble, 3 on each side, remain (their capitals are worth attention), and the springers of the roof still retain traces of vermilion colouring. The chapterhouse was lighted by 3 windows at its eastern end, and by another at the E. end of each aisle. Here many of the abbots were buried; and their tomb-slabs remain in due order.

The great kitchen contained 3 huge fireplaces. The refectory is noticeable for its mixture of Norm. and E. Eng. work. The dormitory (like that at Fountains), extended above a long cloister, the low circ. arches of which remain in part.

The monks of Jervaulx were famous for their cheese, the prototype, no doubt, of the sort now popularly known as "Wensleydale." They were no less famous than those of Coverham for breeding horses; and the commissioners of 1537 recommended the place to the king on this account. "Surely the breed of Gervaix," writes Arthur Darcy, "for horse was the tried breed in the North. I think in no realm should be found the like to them; for there is hardy and high grounds for the summer, and in winter woods and low grounds to fire them." (In the same letter he says, "Here is one of the fairest churches that I have seen "-and the beauty which could [Yorkshire.]

must surely have been extreme.) The house was thoroughly ruined in the following year. All the lead was removed from the roof; and the site, with much of the land, granted by Henry VIII. to the Earl of Lenox and the "Lady Margaret his wife." The last abbot, Adam Sedburgh, was hanged in 1537 for his share in the Pilgrimage of Grace. He attempted, as he declared, but in vain, to escape the importunities of the rebels: and to avoid them, remained for three days "in a great crag on Witton Fell," above the abbey. He was brought back, however, and compelled to join them. His sculptured signature remains in the Tower of London, where he was confined before his execution at Tyburn.

The gross rental of Jervaulx at the Dissolution was 455L, but this was reduced by out-payments to 220L. Its scanty remains are in sad contrast with the splendours of the Abbey in the days of Prior Aylmer, who figures so amusingly (though without much propriety, for the Cistercian houses were then at the height of their austerity) in 'Ivanhoe.'

John Brompton the chronicler (his Annals are printed in Twysden's 'Decem Scriptores') was Abbot of Jervaulx in 1436. (See Brompton.)

The Marquis of Ailesbury has a small shooting-lodge near the ruins, surrounded by pretty gardens.

The tourist may proceed to Leyburn, 6 m., by Coverbridge (over the Cover), and, close to it, Ulshawbridge, over the Ure, where are the Soke Mills, to which the inhabitants of Middleham are obliged to bring their corn to be ground. Thence the road runs by Spennithorne and Harmby to Leyburn.

Passing the Finghall Lane Stat., the next.

Constable Burton Stat., will be the most convenient for the antiquary who desires to visit the ch. of Hauxwell (2½ m. N.). The road skirts Burton Park (M. Wyvill, Esq.), and [then proceeds through a pleasant country to Hauxwell, where the Church. situated at some distance from the village, has E. Eng. portions. The S. door of the nave is Trans.-Norm., with ornamented arch mouldings and tympanum. A chapel on the N. side contains a flagstone marked R. B., said to mark the grave of Roger de Brough, who, being excommunicated, founded this chapel, which has an aperture commanding the altar. (It need hardly be said that the story is most improbable.) In the ch. is some ancient wood-work, and one or two fragments of early (Saxon) sculpture. The ch.-yard has some stone coffins; the effigies of an unknown knight and his wife, temp. Edw. I.; and a remarkable Cross 5 ft. 3 in. high, covered with the interlaced ornament which indicates Saxon work of early character. ch. is ded. to St. Oswald.

Adjoining the ch. is Hauxwell

Hall (Miss Gale).

There is little to delay the tourist The church at Spennithorne Stat. has Norm. piers on the S. side of nave, but is for the most part Dec. The tower has figures on the battlements S. looking towards Middleham -perhaps a stratagem of defence, to appear as if the tower were guarded. The sedile—one long stone seat with ends—is unusual. John Hutchinson, the author of 'Moses's Principia,' was born here in 1674 (died 1737). He was the propounder of a special set of doctrines called "Hutchinsonian," the leading feature of which was, that all knowledge, natural as well as theological, is contained in Hebrew Scriptures,-although mysteriously involved in roots and etymologies. His book was intended to "explode" the theory of gravitation established in Newton's 'Principia.

A few minutes after leaving Spennithorne the train reaches

Leyburn Stat. (Inn: *Bolton Arms—the best in the district, well kept. clean, moderate, but small. Post-horses and carriages.

Levburn is a small town (Pop. in 1871, 888), on the N. bank of the Ure. in the Dale and parish of Wensley, with a small ch., built by subscription in 1868, and a town-hall, built in The North Eastern Co. rlv.. from Levburn to Hawes, in Upper Wensleydale, joins the Midland from London to Carlisle 7 m. beyond Hawes. Here the tourist finds himself on the edge of the great mountain district which stretches N. toward Richmond and Barnard Castle, and S., skirting Coverdale and Nidderdale, to Wharf-(This district may be said broadly to extend hence to the sea. ranging through the counties of Westmoreland and Cumberland, and northward through Durham .into Northumberland. Southward it extends through Lancashire into Derbyshire, and forms what is known as the "Pennine range"—the "backbone of England."—See Introd.)

Leyburn will be found an excellent centre for exploring the lower part of Wensleydale (Rte. 24). The chief places to be visited from here are—Wensleydale, upwards, Bolton Castle. and as far as Aysgarth, Askrigg, and Hawes; down the Vale to Middleham, Coverdale and Jervaulz Abbeys, and a portion of Swaledale between

Leyburn and Richmond.

First, however, the tourist must find his way to the Shaud—a green terrace about a mile long, running along the N. side of the valley above the Bolton Woods. It is entered by a gate ½ m. from Leyburn, ascending the road to Reeth—a walk along the foot of a steep "scar" of rock, overlooking the entrance of Wensleydale. The view here—one of the finest in the N. of England—will give him an excellent general idea of the country he is about to explore. The Shawl itself (the lower banks, and

the clefts of the scar, are clothed i with coppice, and the name may be connected with shaw=wood) forms the N. side of the valley, through which the stream of the Ure winds towards the S.E. In this direction a wide extent of rich country opens towards Masham, with Middleham Castle (see post) rising above the Immediately below are the ch. and village of Wensley, and the woods and plantations of Bolton Hall: and across the cultivated valley S., the flat top of Pen Hill (see Rte. 24) is conspicuous; with the hollow of Bishopdale winding up behind it. A little to the N.W. rise the crumbling towers of Bolton Castle, backed with dark moors. The contrast of this wild country with the rich valley below renders the whole scene unusually striking. At the E. end of the Shawl there is a fine immediate foreground of rock and wood, and the short turf is covered in autumn with the flowers of a small yellow cistus. About halfway along the walk is the Queen's Gap, where the terrace narrows between At this spot, says tradition, Queen Mary of Scotland was stopped. when attempting to escape during her detention at Bolton Castle (see post). Such an attempt was in all probability never made, although the Shawl may have been visited by the queen, who, whilst at Bolton, was allowed to ride forth "hunting and hawking" under due supervision. Searth Neck, a much higher point, where the road from Askrigg to Richmond passes, and the view is still more extensive, may be reached from the Shawl.

(a) Middleham (Castle and Church) Coverham Abbey and Jervaulx Abbey, may be visited in one excursion.

Middleham (21 m. from Leyburn) stands on the rt. bank of the Ure, which is here crossed by an iron (Inn: Swan; there are

and is well known as the headquarters of many race-horse trainers, whose horses are exercised on the moor above, between 6 and 7 A.M.,a performance which many visitors may like to see.

On the top of the hill are the ruins of Middleham Castle-famous as the stronghold of Warwick the king - maker - the " last of the Barons,"-and as the favourite residence of his son-in-law, Richard III. It was founded by Robert Fitz-Ranulph, grandson of Ribald, who was brother of Alan of Brittany, the first Earl of Richmond after the Conquest, and passed in the 18th cent. by marriage to the family of Except Raby, Middleham Neville. was the most important of the many great castles held by the Nevilles in the N. The ruins now consist of a great Norm. keep (the work of the Fitz-Ranulphs) within outer works of the Dec. period; all of which have evidently been destroyed or much damaged by gunpowder. (The committee at York, during the civil war, ordered the castle to be made untenantable.) The keep, of the 12th cent., has square corner turrets with very little projection; and others, of bolder character, in the centre of two of its sides. A wall of division, as usual in Norm. keeps, runs across its interior. The great hall was on the E. side of the 1st floor; with an entrance from the barbican tower. This tower, as at Rochester, Scarborough, and elsewhere, is rectangular, and built against the keep, about 12 ft. from the S. end of the E. face. On the 2nd floor of the barbican was the chapel and the vestibule at the top of the stairs leading to the keep. Halfway up staircase is a large cavity, capable of holding 20 men, evidently as a guard in case the entrance should be forced. The keep has a basement floor at the groundothers.) The town is clean and open, level; a first or state floor, with the

Burton Park (M. Wyvill, Esq.), and | then proceeds through a pleasant country to Hauxwell, where the Church, situated at some distance from the village, has E. Eng. portions. The S. door of the nave is Trans.-Norm.. with ornamented arch mouldings and tympanum. A chapel on the N. side contains a flagstone marked R. B., said to mark the grave of Roger de Brough, who, being excommunicated, founded this chapel, which has an aperture commanding the altar. (It need hardly be said that the story is most improbable.) In the ch. is some ancient wood-work, and one or two fragments of early (Saxon) sculpture. The ch.-vard has some stone coffins; the effigies of an unknown knight and his wife, temp, Edw. I.; and a remarkable Cross 5 ft. 3 in. high, covered with the interlaced ornament which indicates Saxon work of early character. ch. is ded. to St. Oswald.

Adjoining the ch. is Hauxwell

Hall (Miss Gale).

There is little to delay the tourist at Spennithorne Stat. The church has Norm. piers on the S. side of nave, but is for the most part Dec. The tower has figures on the battlements S. looking towards Middleham -perhaps a stratagem of defence, to appear as if the tower were guarded. The sedile—one long stone seat with ends—is unusual. John Hutchinson. the author of 'Moses's Principia,' was born here in 1674 (died 1737). He was the propounder of a special set of doctrines called "Hutchinsonian," the leading feature of which was, that all knowledge, natural as well as theological, is contained in the Hebrew Scriptures,—although mysteriously involved in roots and etymologies. His book was intended to "explode" the theory of gravitation established in Newton's 'Principia.

A few minutes after leaving Spennithorne the train reaches Leyburn Stat. (Inn: *Bolton Arms—the best in the district, well kept. clean, moderate, but small. Posthorses and carriages.

Leyburn is a small town (Pop. in 1871, 888), on the N. bank of the Ure, in the Dale and parish of Wensley. with a small ch., built by subscription in 1868, and a town-hall, built in 1857. The North Eastern Co. rlv.. from Leyburn to Hawes, in Upper Wensleydale, joins the Midland from London to Carlisle 7 m. beyond Hawes. Here the tourist finds himself on the edge of the great mountain district which stretches N. toward Richmond and Barnard Castle, and S., skirting Coverdale and Nidderdale, to Wharf-(This district may be said broadly to extend hence to the sea. ranging through the counties of Westmoreland and Cumberland, and northward through Durham .into Northumberland. Southward it extends through Lancashire into Derbyshire, and forms what is known as the "Pennine range"—the "backbone of England."—See Introd.)

Leyburn will be found an excellent centre for exploring the lower part of Wensleydale (Rte. 24). The chief places to be visited from here are—Wensleydale, upwards, Bolton Castle, and as far as Aysgarth, Askrigg, and Hawes; down the Vale to Middleham, Coverdale and Jervaulx Abbeys, and a portion of Swaledale between

Leyburn and Richmond.

First, however, the tourist must find his way to the Shaud—a green terrace about a mile long, running along the N. side of the valley above the Bolton Woods. It is entered by a gate \(\frac{1}{2} \) m. from Leyburn, ascending the road to Reeth—a walk along the foot of a steep "scar" of rock, overlooking the entrance of Wensleydale. The view here—one of the finest in the N. of England—will give him an excellent general idea of the country he is about to explore. The Shawl itself (the lower banks, and

the clefts of the scar, are clothed! with coppice, and the name may be connected with shaw=wood) forms the N. side of the valley, through which the stream of the Ure winds towards the S.E. In this direction a wide extent of rich country opens towards Masham, with Middleham Castle (see post) rising above the river. Immediately below are the ch. and village of Wensley, and the woods and plantations of Bolton Hall; and across the cultivated valley S., the flat top of Pen Hill (see Rte. 24) is conspicuous; with the hollow of Bishopdale winding up behind it. A little to the N.W. rise crumbling towers of Bolton Castle, backed with dark moors. The contrast of this wild country with the rich valley below renders the whole scene unusually striking. At the E. end of the Shawl there is a fine immediate foreground of rock and wood, and the short turf is covered in autumn with the flowers of a small vellow cistus. About halfway along the walk is the Queen's Gap, where the terrace narrows between At this spot, says tradition, Queen Mary of Scotland was stopped, when attempting to escape during her detention at Bolton Castle (see post). Such an attempt was in all probability never made, although the Shawl may have been visited by the queen, who, whilst at Bolton, was allowed to ride forth "hunting and hawking" under due supervision. Scarth Neck, a much higher point, where the road from Askrigg to Richmond passes, and the view is still more extensive, may be reached from the Shawl.

(a) Middleham (Castle and Church) Coverham Abbey and Jervaulx Abbey, may be visited in one excursion.

Middleham (2½ m. from Leyburn) stands on the rt. bank of the Ure, which is here crossed by an iron bridge. (Inn: Swan; there are others.) The town is clean and open,

and is well known as the headquarters of many race-horse trainers, whose horses are exercised on the moor above, between 6 and 7 A.M., a performance which many visitors may like to see.

On the top of the hill are the ruins of Middleham Castle-famous as the stronghold of Warwick the king - maker - the "last of the Barons,"-and as the favourite residence of his son-in-law. Richard III. It was founded by Robert Fitz-Ranulph, grandson of Ribald, who was brother of Alan of Brittany, the first Earl of Richmond after the Conquest, and passed in the 13th cent. by marriage to the family of Neville. Except Raby, Middleham was the most important of the many great castles held by the Nevilles in the N. The ruins now consist of a great Norm. keep (the work of the Fitz-Ranulphs) within outer works of the Dec. period; all of which have evidently been destroyed or much damaged by gunpowder. (The committee at York, during the civil war, ordered the castle to be made untenantable.) The keep, of the 12th cent., has square corner turrets with very little projection; and others, of bolder character, in the centre of two of its sides. A wall of division, as usual in Norm. keeps, runs across its interior. The great hall was on the E. side of the 1st floor; with an entrance from the barbican tower. This tower, as at Rochester, Scarborough, and elsewhere, is rectangular, and built against the keep, about 12 ft. from the S. end of the E. face. On the 2nd floor of the barbican was the chapel and the vestibule at the top of the stairs leading to the keep. Halfway up staircase is a large cavity, capable of holding 20 men, evidently as a guard in case the entrance should be forced. The keep has a basement floor at the groundlevel; a first or state floor, with the

Burton Park (M. Wyvill, Esq.), and | then proceeds through a pleasant country to Hauxwell, where the Church, situated at some distance from the village, has E. Eng. portions. The S. door of the nave is Trans.-Norm.. with ornamented arch mouldings and tympanum. A chapel on the N. side contains a flagstone marked R. B., said to mark the grave of Roger de Brough, who, being excommunicated, founded this chapel, which has an aperture commanding the altar. (It need hardly be said that the story is most improbable.) In the ch. is some ancient wood-work, and one or two fragments of early (Saxon) sculpture. The ch.-vard has some stone coffins; the effigies of an unknown knight and his wife, temp. Edw. I.; and a remarkable Cross 5 ft. 3 in. high, covered with the interlaced ornament which indicates Saxon work of early character. ch, is ded, to St. Oswald.

Adjoining the ch. is Hauxwell

Hall (Miss Gale).

There is little to delay the tourist The church at Spennithorne Stat. has Norm. piers on the S. side of nave, but is for the most part Dec. The tower has figures on the battlements S. looking towards Middleham -perhaps a stratagem of defence, to appear as if the tower were guarded. The sedile—one long stone seat with ends-is unusual. John Hutchinson. the author of 'Moses's Principia,' was born here in 1674 (died 1737). He was the propounder of a special set of doctrines called "Hutchinsonian," the leading feature of which was, that all knowledge, natural as well as theological, is contained in the Hebrew Scriptures,-although mysteriously involved in roots and etymologies. His book was intended to "explode" the theory of gravitation established in Newton's 'Principia.

A few minutes after leaving Spennithorne the train reaches Leyburn Stat. (Inn: *Bolton Arms—the best in the district, well kept. clean, moderate, but small. Posthorses and carriages.

Leyburn is a small town (Pop. in 1871, 888), on the N. bank of the Ure, in the Dale and parish of Wensley, with a small ch., built by subscription in 1868, and a town-hall, built in 1857. The North Eastern Co. rlv.. from Leyburn to Hawes, in Upper Wensleydale, joins the Midland from London to Carlisle 7 m. beyond Hawes. Here the tourist finds himself on the edge of the great mountain district which stretches N. toward Richmond and Barnard Castle, and S., skirting Coverdale and Nidderdale, to Wharf-(This district may be said broadly to extend hence to the sea. ranging through the counties of Westmoreland and Cumberland, and northward through Durham .into Northumberland. Southward it extends through Lancashire into Derbyshire, and forms what is known as the "Pennine range"—the "backbone of England."—See Introd.)

Leyburn will be found an excellent centre for exploring the lower part of Wensleydale (Rte. 24). The chief places to be visited from here are—Wensleydale, upwards, Bolton Castle, and as far as Ayegarth, Askrigg, and Hawes; down the Vale to Middleham, Coverdale and Jervaulz Abbeys, and a portion of Swaledale between

Leyburn and Richmond.

First, however, the tourist must find his way to the Shawl—a green terrace about a mile long, running along the N. side of the valley above the Bolton Woods. It is entered by a gate ½ m. from Leyburn, ascending the road to Reeth—a walk along the foot of a steep "scar" of rock, overlooking the entrance of Wensleydale. The view here—one of the finest in the N. of England—will give him an excellent general idea of the country he is about to explore. The Shawl itself (the lower banks, and

the clefts of the scar, are clothed! with coppice, and the name may be connected with shaw = wood) forms the N. side of the valley, through which the stream of the Ure winds towards the S.E. In this direction a wide extent of rich country opens towards Masham, with Middleham Castle (see post) rising above the Immediately below are the river. ch. and village of Wensley, and the woods and plantations of Bolton Hall; and across the cultivated valley S., the flat top of Pen Hill (see Rte. 24) is conspicuous; with the hollow of Bishopdale winding up behind it. A little to the N.W. rise the crumbling towers of Bolton Castle, backed with dark moors. The contrast of this wild country with the rich valley below renders the whole scene unusually striking. At the E. end of the Shawl there is a fine immediate foreground of rock and wood, and the short turf is covered in autumn with the flowers of a small yellow cistus. About halfway along the walk is the Queen's Gap, where the terrace narrows between At this spot, says tradition, Queen Mary of Scotland was stopped. when attempting to escape during her detention at Bolton Castle (see post). Such an attempt was in all probability never made, although the Shawl may have been visited by the queen, who, whilst at Bolton, was allowed to ride forth "hunting and hawking" under due supervision. Sourth Neck, a much higher point, where the road from Askrigg to Richmond passes, and the view is still more extensive, may be reached from the Shawl.

(a) Middleham (Castle and Church) Coverham Abbey and Jervaulz Abbey, may be visited in one excursion.

Middleham (21 m. from Leyburn) stands on the rt. bank of the Ure, which is here crossed by an iron (Inn: Swan; there are

and is well known as the headquarters of many race-horse trainers, whose horses are exercised on the moor above, between 6 and 7 A.M.,a performance which many visitors may like to see.

On the top of the hill are the ruins of Middleham Castle-famous as the stronghold of Warwick the king - maker - the " last of the Barons,"—and as the favourite residence of his son-in-law, Richard III. It was founded by Robert Fitz-Ranulph, grandson of Ribald, who was brother of Alan of Brittany, the first Earl of Richmond after the Conquest, and passed in the 13th cent. by marriage to the family of Neville. Except Raby, Middleham was the most important of the many great castles held by the Nevilles in the N. The ruins now consist of a great Norm. keep (the work of the Fitz-Ranulphs) within outer works of the Dec. period; all of which have evidently been destroyed or much damaged by gunpowder. (The committee at York, during the civil war, ordered the castle to be made untenantable.) The keep, of the 12th cent., has square corner turrets with very little projection; and others, of bolder character, in the centre of two of its sides. A wall of division, as usual in Norm. keeps, runs across its interior. The great hall was on the E. side of the 1st floor; with an entrance from the barbican tower. This tower, as at Rochester, Scarborough, and elsewhere, is rectangular, and built against the keep, about 12 ft. from the S. end of the E. face. On the 2nd floor of the barbican was the chapel and the vestibule at the top of the stairs Halfway up leading to the keep. the staircase is a large cavity, capable of holding 20 men, evidently as a guard in case the entrance should be forced. The keep has a basement floor at the groundothers.) The town is clean and open, level; a first or state floor, with the

Burton Park (M. Wyvill, Esq.), and then proceeds through a pleasant country to Hauxwell, where the Church, situated at some distance from the village, has E. Eng. portions. The S. door of the nave is Trans.-Norm., with ornamented arch mouldings and tympanum. A chapel on the N. side contains a flagstone marked R. B., said to mark the grave of Roger de who, being excommuni-Brough, cated, founded this chapel, which has an aperture commanding the altar. (It need hardly be said that the story is most improbable.) In the ch. is some ancient wood-work, and one or two fragments of early (Saxon) sculpture. The ch.-vard has some stone coffins; the effigies of an unknown knight and his wife, temp. Edw. I.; and a remarkable Cross 5 ft. 3 in. high, covered with the interlaced ornament which indicates Saxon work of early character. ch. is ded. to St. Oswald.

Adjoining the ch. is Hauxwell

Hall (Miss Gale).

There is little to delay the tourist The church at Spennithorne Stat. has Norm. piers on the S. side of nave, but is for the most part Dec. The tower has figures on the battlements S. looking towards Middleham -perhaps a stratagem of defence, to appear as if the tower were guarded. The sedile—one long stone seat with ends—is unusual. John Hutchinson, the author of 'Moses's Principia,' was born here in 1674 (died 1737). He was the propounder of a special set of doctrines called "Hutchinsonian," the leading feature of which was, that all knowledge, natural as well as theological, is contained in the Hebrew Scriptures,-although mysteriously involved in roots and etymologies. His book was intended to "explode" the theory of gravitation established in Newton's 'Principia.

A few minutes after leaving Spennithorne the train reaches Leyburn Stat. (Inn: *Bolton Arms—the best in the district, well kept. clean, moderate, but small. Post-horses and carriages.

Leyburn is a small town (Pop. in 1871, 888), on the N. bank of the Ure. in the Dale and parish of Wensley. with a small ch., built by subscription in 1868, and a town-hall, built in The North Eastern Co. rlv.. from Leyburn to Hawes, in Upper Wensleydale, joins the Midland from London to Carlisle 7 m. beyond Hawes. Here the tourist finds himself on the edge of the great mountain district which stretches N. toward Richmond and Barnard Castle, and S., skirting Coverdale and Nidderdale, to Wharf-(This district may be said broadly to extend hence to the sea. ranging through the counties of Westmoreland and Cumberland, and Durham .into northward through Northumberland. Southward it extends through Lancashire into Derbyshire, and forms what is known as the " Pennine range "-the " backbone of England."—See Introd.)

Leyburn will be found an excellent centre for exploring the lower part of Wensleydale (Rte. 24). The chief places to be visited from here are—Wensleydale, upwards, Bolton Caetle, and as far as Aysgarth, Askring, and Hawes; down the Vale to Middleham, Coverdale and Jervaulz Abbeys, and a portion of Swaledale between

Leyburn and Richmond.

First, however, the tourist must find his way to the Shawl—a green terrace about a mile long, running along the N. side of the valley above the Bolton Woods. It is entered by a gate ½ m. from Leyburn, ascending the road to Reeth—a walk along the foot of a steep "scar" of rock, overlooking the entrance of Wensleydale. The view here—one of the finest in the N. of England—will give him an excellent general idea of the country he is about to explore. The Shawl itself (the lower banks, and

the clefts of the scar, are clothed and is well known as the headwith coppice, and the name may be connected with shaw=wood) forms the N. side of the valley, through which the stream of the Ure winds towards the S.E. In this direction a wide extent of rich country opens towards Masham, with Middleham Castle (see post) rising above the Immediately below are the river. ch. and village of Wensley, and the woods and plantations of Bolton Hall; and across the cultivated valley S., the flat top of Pen Hill (see Rte. 24) is conspicuous; with the hollow of Bishopdale winding up behind it. A little to the N.W. rise crumbling towers of Bolton Castle, backed with dark moors. The contrast of this wild country with the rich valley below renders the whole scene unusually striking. At the E. end of the Shawl there is a fine immediate foreground of rock and wood, and the short turf is covered in autumn with the flowers of a small vellow cistus. About halfway along the walk is the Queen's Gap, where the terrace narrows between At this spot, says tradition, Queen Mary of Scotland was stopped, when attempting to escape during her detention at Bolton Castle (see post). Such an attempt was in all probability never made, although the Shawl may have been visited by the queen, who, whilst at Bolton, was allowed to ride forth "hunting and hawking" under due supervision. Scarth Neck, a much higher point, where the road from Askrigg to Richmond passes, and the view is still more extensive, may be reached from the Shawl.

(a) Middleham (Castle and Church) Coverham Abbey and Jervaulz Abbey, may be visited in one excursion.

Middleham (2½ m. from Leyburn) stands on the rt. bank of the Ure,

quarters of many race-horse trainers. whose horses are exercised on the moor above, between 6 and 7 A.M.,a performance which many visitors may like to see.

On the top of the hill are the ruins of Middleham Castle-famous as the stronghold of Warwick the king - maker - the "last of the Barons,"-and as the favourite residence of his son-in-law, Richard III. It was founded by Robert Fitz-Ranulph, grandson of Ribald, who was brother of Alan of Brittany, the first Earl of Richmond after the Conquest, and passed in the 13th cent. by marriage to the family of Neville. Except Raby, Middleham was the most important of the many great castles held by the Nevilles in the N. The ruins now consist of a great Norm, keep (the work of the Fitz-Ranulphs) within outer works of the Dec. period; all of which have evidently been destroyed or much damaged by gunpowder. (The committee at York, during the civil war, ordered the castle to be made untenantable.) The keep, of the 12th cent., has square corner turrets with very little projection; and others, of bolder character, in the centre of two of its sides. A wall of division, as usual in Norm. keeps, runs across its interior. The great hall was on the E. side of the 1st floor; with an entrance from the barbican tower. This tower, as at Rochester. Scarborough, and elsewhere, is rectangular, and built against the keep, about 12 ft. from the S. end of the E. face. On the 2nd floor of the barbican was the chapel and the vestibule at the top of the stairs leading to the keep. Halfway up staircase is a large cavity, capable of holding 20 men, evidently as a guard in case the enwhich is here crossed by an iron trance should be forced. The keep (Inn: Swan; there are has a basement floor at the ground-The town is clean and open, level; a first or state floor, with the hall; and on the E. side an upper | floor. A well-stair ascended in the S.E. angle from the basement to The buttresses at the battlements. the angles no doubt rose above the battlements into rectangular turrets. This Norman keep (about 55 ft. high to the base of the parapet) stands in the centre of an enceinte. or curtain-wall, about 30 ft. high. the area between which and the keep must always have been limited. but which was further narrowed by domestic buildings of the Dec. period placed against the curtains on the N.W. and S. sides, and which reduced the ward to a mere passage. The Norm, enceinte wall was greatly altered, if not rebuilt, at this time: and the gatehouse, at the N.E. angle. is Dec. The builder of this Dec. castle was either Robert Nevile. called the "Peacock of the North." who died before 1331, or Ralph, Lord Nevile of Raby, his brother and successor, who died 1367. Some alterations were made in the castle by Richard Duke of York (Rich. III.), who obtained Middleham after the battle of Barnet, and was much The large window opening on the W. face of the keep, and perhaps the upper story on the E. side of the keep are of his time. (See G. T. C., in the 'Builder,' April 13, 1872, for a full notice of this castle.) The buildings in the ward of the Dec. period have been so completely ruined that their arrangements can no longer be traced; but from a survey of the castle taken upwards of 800 years since, it appeared that there was a tower above the gate, and a mantel wall from it to the first tower. Near this were the chapel and brewhouse.

Middleham Castle is hardly picturesque, but it stands grandly on the height, and is imposing from its massive masonry, and walls 10-12 ft. thick. It is more interesting from its history and associations than from its

actual remains. The only son of Richard III., by the Lady Anne. daughter of the Earl of Warwick. was born here in 1473, and died here "morte infansta" as Rous says, April 9th, 1484. However Richard may have been regarded elsewhere, he was always popular in Yorkshire, and Middleham was often visited by him. ("The memory of King Richard was so strong in the north," wrote Bacon. "that it lay, like lees, in the bottom of men's hearts, and if the vessel was but stirred it would come up." -Life of Henry VII.) Whether. as has been asserted, Edward IV. was detained here as a prisoner by Warwick in 1469, is not certain. Holinshed asserts that the Earl "caused King Edward to be conveyed by secret journeys in the night from Warwick to Middleham. where he was detained in the custody of the Archbp. of York (Warwick's brother). He escaped—according to the same chronicler-by the stratagem of the Stanleys and other friends, who, one day, as he was hunting with the Archbp., " met him on a plain with such a great band of men, that his keepers durst not move him to return into prison again." On the other hand, it has been proved that many acts of kingly authority were performed as usual by Edward at the very time when he is represented as having been a prisoner. Sir E. B. Lytton has taken a different view of the matter in his 'Last of the Barons,' many scenes in which are laid at Middleham: but this most confused portion of English history has yet to be satisfactorily unravelled.

The Church (restored) dating for the most part early in the 13th cent. with additions of late Dec. character, is of no very great interest. There are some fragments of ancient glass, commemorating St. Alkelda (of whom nothing is known—the ch. is dedicated to her and to St. Mary. Gigglesworth ch. (Rte. 32) is also daughter of Ranulph de Glanville. dedicated to St. Alkelda). Against the W. wall of the S. aisle is the tomb-slab of Robert Thornton, last but one of the Abbots of Jervaulx. bears the mitre, staff, and rebusthorn and tun-the dispering of the centre is formed of thorn-leaves) of the abbot. The view from the roof or tower is the finest in the district. Richard III., when Duke of Gloucester, wished to make the ch. collegiate, and intended to have endowed it accordingly. His design, however, was frustrated by his death at Bosworth; although the incumbent was styled "Dean of Middleham" as head of the college, until the death of the late Dr. Wood in 1856. Charles Kingsley was a canon of the once collegiate ch. of Middleham.

Many fragments from Jervaulx are scattered about the town. A stone sculptured with the Crucifixion remains over the inner door of the S.

porch of the ch.

Middleham Moor, at the back of the castle, has long been a famous training ground for racers. A great cattle fair is held on it in November, and is attended by traders from both sides of the border. On the moor, about 1 m. from the castle, are the mounds and trenches of a large camp (?) called "William's Hill "-which has been considered Danish, but may be of a much earlier period.

A cross road will lead the tourist from Middleham to Coverham (2 m.), where the scanty remains of the priory are worth a visit. Coverham is the chief village of Coverdale. a long narrow dale through which the stream of the Cover descends from the ridge of watershed between Wharfedale and the lower part of Wensleydale. (The Cover joins the Ure about 1 m. W. of Middleham.) Coverham Abbey, on the border of stratensian Canons, by Helewyse, little interest.

the great justiciary of Henry II., and then the widow of Robert Fitz-Ranulph, who built the Norm. portion of Middleham Castle. Her foundation was made in 1190 at Swainby. near Pickhall: but her son, Ranulph Fitz-Robert: removed the canons to Coverham about the year 1212, together with the remains of Helewyse, who had been buried at Swainby. He conveyed to them the ch. of Coverham with much land: and was It is stated in buried in the abbev. a charter of Edw. II. (dated March 1. 1321) that the monastery had been destroyed by the Scots; and in 1330 the poverty of the house was so great that the canons feared a dispersion. The Gatehouse, and three bays of the nave, are the chief relics at Coverham, and are of Dec. character. The foundations of the entire ch., of the cloister and adjoining buildings, are traceable; and two crosslegged effigies among the ruins (removed from their original positions in the chapter-house) possibly represent Ranulph Fitz-Robert - died 1251-who removed the abbey, and his son Ralph - died 1270. latter effigy (figured by Gough, i. 18) is "considerably inclined to the left, on which side are three dogs, one playfully biting the scabbard of his master's sword, while the two others are keenly pursuing a stag into the recesses of a deep wood." domestic buildings of the abbey seem to have been rebuilt early in the 16th cent.; and from a sculptured stone inserted in the adjacent house it appears that Abbot John Askew finished much of this work. It bears the figure of an eagle (John) and the capital letter A, and the crowned monogram I.H.S. between. Many fragments of Abbot John's buildings remain. The ruins are badly kept, and farm-buildings occupy the main The parish ch. of site of the abbey. the stream, was founded for Premon- | Coverham, partly rebuilt, 1854, is of

Leland says, "there was good syngynge in Coverham." The canons are said to have been famous for a particular breed of white horses; and in this and the neighbouring dales such horses are still of frequent oc-CUTTANCA.

Ranulph de Glanville, the justiciary of Henry II., who was the first to make a "digest" of the laws and customs of England, was born at Coverham. His lands here passed to his daughter Helewyse, and from her son to the Premonstratensians. Here also (or at least in the dale, from which he took his name) was born, toward the end of the 15th cent., Miles Coverdale, who assisted Tindal in his English version of the Bible, published in 1537, and afterwards revised and corrected it in a new edition (1540). Coverdale was the first Bishop of Exeter (consec. 1551) " of the reformed religion."

(A road, passing Coverham, ascends Coverdale, and, crossing the ridge, passes down to Kettlewell in Wharfedale, whence the tourist may reach Skipton or Settle. But Coverdale itself is not very picturesque or Where the road gains interesting. the summit of the ridge, between Little Whernside and Pikes, there is a magnificent view down Wharfedale. (For Wharfedale see Rte. 30.)

From Coverham you may walk to East Witton (21 m.), where the ch. was built, in 1809, by the (then) Earl of Ailesbury, as a memorial of George III.'s having entered the 50th year of his reign. It was much altered in 1871. 12 m. beyond East Witton are the ruins of Jervaulx Abbey (see p. 304).

(b) The historical antiquary must on no account omit visiting Bolton From Castle, distant about 5 m.

(2 m.), and across the Ure at Aysgarth (where the waterfalls and the ch. are to be seen), and return to Leyburn on the S. side of Wensleydale. This will be a delightful day's excursion.

From Leyburn to Bolton take the road to Reeth, which runs above the Shawl, and at about 2 m. from the town turns l. into the main road from Richmond to Askrigg. After proceeding a little more than 1 m. on this, it reaches an eminence called Scarth Nick (the name means a "nick" or cleft in the scar of rock), whence a magnificent view is obtained over Wensleydale. It is of the same general character with that from Leyburn Shawl, and presents the same contrast of mountain and richly-cultivated land; but the foreground is different. A glimpse of the Ayegarth Falls is obtained rt., with Bolton Castle 1 m. distant. village of Preston under Scar lies close below. From this point the road descends the Scar to Redmire, where is a small Norm. and E. Eng. ch., worth notice, and a maypole on the green. There are some falls here on the Ure. Thence a rough road, crossing the Avedale Beck, will bring the tourist under the walls of Bolton Castle, about 1 m. from Scarth Nick.

The distance from Leyburn to Richmond, taking the direct road over Hipswell Moor, is 10 m. views are commanded from this high ground; but a far more striking and picturesque road runs through the valley of the Swale, and may be reached by turning off the former road at a wayside inn called Halfpenny House, and proceeding thence by Walburn Hall. The distance to Richmond by this road is at least 12 m.

[Close to the left-hand side of the direct road from Leyburn to Richmond, which crosses Hauxwell Moor. and about a mile beyond Halfpenny Bolton he may proceed to Carperby | House, is Hartleap Well, the scene of

Wordsworth's poem. A hunted hart is said to have made three "cruel leaps" from the top of the hill to the spring in the hollow. The leaps were marked by upright stones; and a "bower" was built near the well.

the red and gold of its sycamores is contrasted with the dark green of numberless yew-trees scattered over the face of the scar behind, this wood to possible top of the scar two upright stones well.

Wellance's Leaps" so called

"I look'd upon the hill both far and near, More doleful place did never eye survey; It seem'd as if the springtime came not here, And Nature here were willing to decay."

The stones have disappeared, and close to the well, which is scarcely larger than a bucket, hangs but one of the trees mentioned by the poet, who draws his beautiful moral from the story—

"Never to blend our pleasure or our pride With sorrow of the meanest thing that feels."]

Taking the lower road, Walburn Hall, now a farm (but carefully restored by T. Hutton, Egg., of Marske), is worth notice as a characteristic example of a smaller Yorkshire "hall house." It is built round an inner court, and is almost entirely Elizabethan, having been probably renewed by Francis Lascelles of Brekonbergh. During the civil war it was garrisoned for Chas. I. by some companies of the Richmondshire train-Beyond it the road crosses bands. the ridge dividing Uredale and Swaledale. and descends to the river-side. The bits of pastoral scenery, with heath beyond, are pleasant; and just below the summit of the ridge a very beautiful view opens up part of Swaledale into Arkengarth dale; mountains close in the distance with fine out-This is a point for the Thick woods of ash and artist. sycamore extend along the river; l. are seen the parks and plantations of Marske (J. Darcy Hutton, Esq., see Rte. 25), and close to the road is the small village chapel (Dec.), which has been restored. Whiteliffe Wood, beyond Marske, is within a walk from Richmond. In autumn, when

contrasted with the dark green of numberless yew-trees scattered over the face of the scar behind, this wood is magnificent in colour. On the top of the scar two upright stones mark "Willance's Leap," so called from a man on horseback having been carried over the precipice at this spot. The accident happened in 1606. The man broke his leg, but was saved; the horse rolled to the bottom and was killed. A silver cup. still in the possession of the Corporation of Richmond, was given to them by Willance as a memorial of his Hence the Swale rolls quietly onward to wash the foot of the Castle Hill at

Richmond (see Rte. 25).

(The upper part of Swaledale and Arkengarthdale are of course accessible from Leyburn as easily as from Richmond. Reeth is the best point for exploring them. See Rtc. 25.)

(c) For Wensley and Wensley-dale, see Rte. 24.

ROUTE 24.

WENSLEYDALE-LEYBURN TO HAWES JUNCTION AND SEDBERGH. BOLTON CASTLE, AYSGARTH, ASK-RIGG, HAWES [HARDRAW FORCE].

35 m. Rail: 5 trains daily in 14 hrs. (For Leyburn, see Rte. 23.)

The scenery throughout Wensleydale is fine; and the upper part of the dale especially has a pastoral character that will recall Wordsworth at every step. Bolton Castle, the waterfalls at Aysgarth, at Askrigg, and at Hardraw near Hawes, are well worth visiting. The Passes out of the dale northward afford some of the finest mountain scenery in Yorkshire; and the lateral dales S. will repay exploration. A good road runs all the way to Sedbergh, and the Railway extends to Hawes Junction. (There are comfortable Inns at Levburn, Aysgarth, and Askrigg.)

Wensleydale (named from the village of Wensley—it is, in fact, the valley of the Ure) is supposed to begin at Kilgram Bridge, below Jervaulx Abbey, and to extend to the Westmoreland border. Wensleydale of ancient days ended. westward, at the junction of the

a wild forest. But this part of the dale must always have been of a different character to the "heads" of Teesdale or of Swaledale: both of which narrow, and are hemmed in by mountains. Wensleydale runs broad and open to its extremity where the road crosses the ridge. and, descending into Garsdale. proceeds to Sedbergh. The hills which close in the dale are throughout of mountain limestone, capped in places with millstone grit. They rise gradually on either side of the dale to a watershed ridge which separates Wensleydale S. from Wharfedale and N. from Swaledale. A third ridge crosses the dale W.; and bevond it the streams flow W. into the valley of the Lune. The scars or precipices of broken rock which. crowning the slopes on either side. form a main feature of the dale, are characteristic of the limestone.

The lower part of Wenslevdale is famous for its dairies. Wenslevdale cheese (and especially its excellent cream cheese) should not be neglected by the traveller. Baron Parke took his title (1856) from this Yorkshire

dale, in which he was born.

14 m. Wensley Stat.

The pretty village of Weneley (it is called Wendreslaga and Wenderslaga in Domesday) lies on the Ure, above Levburn. Close to this stat. is a Lead Mine, whose chimney is carried up the hill behind. The Church, made collegiate by letters patent of Rich. II., 1399, is well worth a visit, nave is late Perp.; the long choir fine E. Eng. Under the nave battlements are many shields of Scropes and their alliances, and below the E. window are (very unusually) stone seats of the same date as the chancel itself. At the end of the N. aisle portions of a richly-carved parclose brought from the Scrope chantry at Easby Abbey, near Richmond (the Bain with the Ure. All beyond was | ancient burying-place of the Scropes

-see Rte. 25), now enclose the pew of the lords of Bolton. Inscriptions run along the top of the screen. which has besides "a sort of Scrope pedigree in wood-work." The original oak seating remains in the nave. The chancel has very fine stalls, covered with heraldry, and bearing date 1527, when they were erected Ъv "Henry Richardson, rector." Before the poppy-heads, and looking toward the ch., are figures of animals, thoroughly good, spirited, and life-like. Here also is the fine (Flemish) brass of Sir Simon de Wenslagh, rector (circ. 1390), with the veiled chalice on his breast above his crossed hands. (It has been engraved by both Waller and Boutell.) In the N. aisle is a monument for two children of Lord Henry Scrope, who died in 1525. The vestry contains some early Saxon fragments dug up in the ch.-yd.; among them a stone marked with a cross and the name Donfrid. In the ch. is buried the father of Mason the poet, rector of Wensley (1673-1683); and in the ch.-yard, Thomas Maude, the "poet" of Wensleydale, who died in 1798. His 'Wensleydale, a Poem,' was published at York in 1771. He also wrote 'Verbeia, or Wharfdale, a Poem,' and other works.

Bolton Hall (Lord Bolton), adjoining the village W., was finished in 1678, after Bolton Castle had become untenantable, by the 1st Duke of Bolton, son of the Marquis of Winchester, so famous for his defence of Basing House during the civil war. It contains some interesting portraits of the Scropes, among them one of the 9th Lord, who gathered his Wensleydale followers for Flodden (see Rte. 23); of the 11th Lord, who had the custody of Queen Mary; of his wife, sister of the Duke of Norfolk; and of the 13th Lord Scope. the last of his line, created Earl of Sunderland by Chas. I.—by Vandyck. The park is well wooded.

(From Wensley you may take the N. side of the dale, see Bolton Castle, and cross at Caperby to Aysgarth.)

Wensley bridge was made, says Leland, "by one called Alwine, parson of Wencelaw," who died in 1430. Crossing it, the road on the rt. bank of the Ure passes through West Witton, where the ch. is E. Eng. (some portions perhaps earlier) there is a fine view from the ch.yard. It then proceeds under Penhill (1817 ft.) (Pen, Cymric, a hill-crest), a broad, flat-topped mountain, conspicuous throughout the dale, and, from its peculiar outline, a landmark even from the Cleveland Hills. The summit, although flat, is bold and craggy (it is of millstone grit, the mass of the hill mountain limestone), and in Leland's time had on it a "castelet" or watch-tower. view from this hill, almost isolated as it is by the narrow glens, Bishopdale, Waldendale, and Coverdale, which wind round and behind it, is magnificent, and will amply repay the climb. It may best be mounted from the village of West Burton, in Waldendale.

[The becks which descend Bishopdale and Waldendale join a little above the road through Wensleydale. Both these dales are picturesque, with fine sycamores and ash-trees clustering about the farms, and with grand hill scenery at their higher ends, where the watershed ridge separates them from Wharfedale. (A rough road passes up each dale, and joins that which runs up Wharfedale, by Kettlewell, to Askrigg and Hawes—see post, Hawes.) They are much narrower than the main valley of the Ure, and are worth the artist's attention. In Foss Gill, a narrow glen opening into Bishopdale on the W. side, about 3 m. above Thorelby, is a long series of falls or "fosses," descending from the fell, ledge after ledge, for more than 1 m. In Waldendale, close to West Burton, is a water-fall, still very wild and striking, although a lead-mine is working in the rock immediately in front of it. The houses of West Burton are built round a green, with a cross on steps in the middle. Many of the houses have a flight of steps to an upper door, that below opening into a stable for cattle. This arrangement is common throughout the northern dales. The tourist who desires to explore this neighbourhood will find a good Inn at Aysgarth (see post.)

Near the opening of Bishopdale are some scanty remains of a preceptory of Knights Templars, established before the year 1185, the history of which seems little known. (The remains, little more than foundations, are those of the chapel attached to the preceptory.) By the roadside, and commanding a view of Aysgarth Force, is a building called the "Temple" (with reference to this foundation), in the grounds of Swinithwaite Hall (J. Pilkington, Esq.).

Redmire Stat. The village on the Ure has a small Trans. Norm. Church, and a Maypole on the green. A rough road leads up the hill about a mile to

Bolton Castle.

This great castle of the Scropes will have been for some time visible, with its four towers rising grey against the russet moors that stretch away from it N. and W. N.W. broken crags and steeper hills extend towards Askrigg. On the E. side along the course of the Apedale Beck. The castle stands on the N. side of Wensleydale; and the ground rises gradually behind it to the crest of the ridge dividing Wensleydale from Swaledale.

Here the Scropes lived in the midst of their own followers, and in the greatest feudal state. from the reign of Richard II. to the days of the Long Parliament. Here the Lord Scrope marshalled his men before joining the host which fought at Floiden:—

"Lord Scrope of Bolton, stern and stout, On horseback who had not his peer; No Englishman Scots more did doubt— With him did wend all Wensadale From Morton unto Molsdale Moor; All they that dwelt by the banks of Swale With him were bent in harness stour.

With lusty lads and large of length Which dwelt at Seimer-water side, All Richmondshire its total strength The lusty Scrope did lead and guide."

The Scropes of Bolton were frequently wardens of the west marches. and it is the "Keen Lord Scrope" who thus figures in the ballad of Kinmont Willie. As march-warden. Lord Scrope attended Queen Mary of Scotland at Carlisle, whither she was first conducted on her flight to England. Lady Scrope was sent to wait on her; and on the 13th of July. 1568, she was conveyed from Carlisle to Bolton Castle, where she remained until January 26, 1568-9. During her stay at Bolton the famous Commission sat at York, and afterwards at Westminster, which professed to examine the charges brought against her; and while the Commission was sitting at York the intrigue was commenced between Mary and the Duke of Norfolk, who was the chief of Elizabeth's commissioners, which afterwards cost the Duke his head. Lady Scrope was his sister, and by her means letters and love-tokens passed from the Duke to Mary at Bolton. Here the Queen was watched by the vice-chamberlain, Sir Francis Knollys, on Elizabeth's part, and was visited by her own friends, Lesley Bishop of Ross, and Sir Robert Melville; and here, while the result of the Commission was still doubtful, she professed to listen with interest

" hearing," wrote Sir Francis Knollys to Cecil, August 8, 1568, "the faults of papestry revealed by preaching or otherwise with contented ears, and with gentle and weak replys." Queen was permitted her usual exercise at Bolton, and rode, with due attendance, over all the surrounding country-riding always so fast as to outstrip all who accompanied her. "Bolton," wrote Knollys, was the " highest walled house he had seen." " It hath but one entrance, and half the number of soldiers may better watch and ward the same than the whole number thereof could do Carlisle Castle."

During the civil war Bolton Castle was held for the King by Colonel Scrope and Colonel Chaytor, the latter of whom, after being reduced to eat his horses, capitulated (Nov. 1645) and marched to Pontefract. The committee at York ordered it to be "made untenable" in 1647, and from that date it has been falling more and more into decay.

The castle, with which these associations are connected, was built by Richard Lord Scrope, Chancellor of England under Richard II., and father of the Abp. of York, beheaded in 1405. He made it "out of the ground," says Leland, "of four great strong towris, and of good lodgings. It was a making 18 years, and the charges of the buildyng came by yere to 1000 marks. . . . Most part of the timber that was occupied in buylding of this castle was fett owt of the forest of Engleby, in Cumberland; and Richard Lord Scrope for conveyance of it had layd by the way dyvers draughts of oxen to carry it from place to place till it came to Bolton."

The licence to crenellate was granted in 1879: a date which it will be useful to remember in ex-

to the claims of the reformed faith, licence to fortify which was granted by Bishop Hatfield in the same year. Of the 4 large square towers at the corners, 3 remain entire; the 4th has fallen down from neglect: the rest of the walls are nearly perfect. The outer openings up to 2nd floor are slits. The buildings enclose a courtyard, on one side of which is the great hall, on the other a chapel. There is a dungeon and well, and some rooms are inhabited by cottagers, who have been allowed to take out part of the old mullioned windows, and put modern cottage casements in their places. It is one of the most perfect houses of its period remaining in England. Besides the great hall in the north part, there is a smaller hall or banqueting-room in the S. front, the kitchen and offices of which remain almost perfect. Near the fireplace is a sink or water-drain, of plain character, but original. The only entrance to the castle is at the E. end, through a well-protected gateway; and it is said that each of the small doors leading from the court-yard into the building was protected by a portcullis, so that if an enemy did force an entrance into the court-yard he would be exposed to a murderous cross-fire from all 4 sides. This unusual precaution may have been considered necessary from the circumstance of there being no most, which probably the steepness of the hill rendered impracticable.

Close to the N. side of the castle is a chapel, now the parish ch., outside the walls. It is dedicated to S. Oswald, and has been "restored" and fitted with new seats. (In this chapel Richard Lord Scrope, the founder, richly endowed a chantry, for the health of the soul of King Richard II.).

The ground-rooms throughout the amining the detail and distribution castle were vaulted with plain barrel of the several parts, as well as for vaults . . . the upper rooms comparison with Raby Castle, the had wooded floors, and the roofs were nearly flat. square towers, there is a small square tower or turret in the centre of the N. front, and another in the centre of the S. front: the latter is filled entirely with garderobes, one on each floor, which have passages leading to them from each of the rooms. The ground-room of the N. tower is the dungeon, with a barrel vault, the only entrance being by a trap-door from a similar room over it, which has loopholes only; above this is a guard-room, with a fireplace and windows. The eastern half of the upper stories in both (N. and S.) fronts is divided into small chambers . . the western half is a hall, the larger and more important in This hall occupies the N. front. the same height as the two upper stories in the eastern part, and was open to the roof, which was nearly flat. It has on each side three tall windows of a single light, divided by a transom, with foliated heads and hood molds, of late Dec. character. The entrance is by a newel staircase at the inner angle of the tower, and the staircase also led to the offices, which were partly in the tower and partly in the W. front, where (from a large chimney remaining) was probably the kitchen. Bolton was clearly a baronial residence - not merely a military fortress; and although Raby Castle (still inhabited) is nearly of the same period, it has been so much altered as to make the original arrangement scarcely intelligible.

The wall of the two halls are perfect, but roof and floors are now wanting. "Two halls were usual in all great residences both in the 13th and 14th cents." - J. H. Parker, ' Domestic Architecture.'

In the hall of Bolton, Leland " much noted " how the smoke of the hearth was "wonder strangely conveyed by tunnels made on the syds

Besides the 4 large [passage which has sometimes been supposed to prove that chimnevs were not in use before this time. This, however, we know to be an error. (Chimneys were in common use from the 12th cent. downwards.)

A room adjoining the S.W. tower is called "Queen Mary's," and no doubt was that occupied by her. (A local tradition asserts that she escaped through one of the windows in this part of the castle, and had reached the "Queen's Gap" on Levburn Shawl when she was retaken. Her signature, "Marie R.," remained for some time on a pane of glass in one of the windows of this room. but this has been removed to Bolton Hall.

A pleasant walk may be found across fields from Bolton Castle to

Ausgarth Stat. on the height, which is about 2 m. from the Force; it is approached by path down l. bank, a little way below the bridge and Church.

Inn: Miner's Arms, at Palmer's Flatt.

The view from Aysgarth Bridge, a fine arch of 70 ft. span, is singularly picturesque. The Ure is here much broken with waterfalls, more varied (though not so grand) than those of the more famous Force below. "The gloom of the pendent trees," says Pennant, "the towering steeple of the ch. above, and the rage of the waters beneath the ivy-bound arch. form together a romantic view. Aysgarth Force is about 1 m. below. The river here descends a series of flat limestone ledges (none of great height) which stretch across its bed. The banks are fringed with natural coppice. When in flood, the river falls over these ledges (then completely hidden) with tremendous force. At other times the margin of the stream, worn and fretted into potof the walls betwixt the lights"—a holes, forms a singular frame to the dashing water. The "force" (very | much Turnerised) forms one of the series in that great artist's "Richmondshire."

The Church (dedicated to St. Andrew) stands on the hill above the bridge. In 1866 it was entirely rebuilt, with the exception of the lower part of the tower (perhaps E. E., and evidently meant for defence, like many other church-towers in this dis-The present church trict). throughout Perp. in character, and has a distinct chancel. some modern stained glass, an enriched reredos, and a mural decoration representing the Call of St. Andrew. A painted window commemorates the escape of Rev. J. Winn from burglars! But far more interesting than any portion of the modern church is the magnificent Roodscreen (late Dec.), said to have been brought from Jervaulx, and which was the most conspicuous feature in the old church of Aysgarth, as it is in the present. On it may be seen the letters A. S., the initials of the last Abbot, Adam of Sedbergh. It has been re-painted and re-gilt. The woodwork in the chancel is modern, with the exception of two enriched stall - ends. with initials and devices of abbots of Jervaulx, to which house the ch. belonged. There is a fine view " Aykesgarth," from the ch.-yard. the ancient form of the name, seems to mean "oak enclosure."

You can either cross the river here. and proceed along the N. bank to Askrigg, or follow the road to Bainbridge through Thornton Rust. The latter road affords perhaps the finer views.

On quitting Aysgarth the railway passes near Nappa Hall, the ancient house, well worthy of a visit, of the Metcalfes (called locally "Mecca"), heads of a great "clan" which formerly extended throughout the dale.

would have been easy "to make a 300 men in very known consanguinity of the Metcalfes;" and in 1556 Sir Christopher Metcalfe, as sheriff, met the Judges at York with 300 "of his own name and kindred," all on white horses. Camden says (Britannia) the family of Metcalfe was then (1607) counted the most numerous in England. The last of these Nappa Met-The family, howcalfes died 1756. ever, is by no means extinct; and in our own day Lord Metcalfe was governor successively of the three greatest dependencies of the British Crown,—Jamaica, Canada, and India The house of Nappa, which was built by Thomas Metcalfe. Chancellor of the Duchy of Lancaster in the reign of Rich. III., contains a bedstead in which Queen Mary is said to have slept, a pair of her gloves, and an autograph letter from her to a Metcalfe. Jas. I. was entertained here, and, says tradition, crossed the Ure on the back of Metcalfe's huntsman (Metcalfe of Nappa was Master Forester of Wensleydale).

11 m. from the Hall, and skirted by the railway, is a warren of silvergrey rabbits. It is said that only 2 or 3 warrens of this species exist in England.

From Thornton Rust (said to be a corruption of St. Restitutus) the views over the dale, into which the mountains send out great projecting buttresses, are very fine. At Bainbridge (where the homely Inn, Rose and Crown, is one of the best for pedestrians in Yorkshire) the little River Bain is crossed, close to its junction with the Ure. Here the "forest of Wensleydale" commenced, and horn is still sounded at 10 at night "from Holyrood to Shrovetide" as a guide to travellers. Bainbridge is the conjectured site of the Roman Bracchium: and a Roman road, running through Wensleydale from Mid-Leland says that about Nappa it deham, is thought to have turned wild country toward Bowes (Lavatræ). Over the door of the grammarschool at Bainbridge is a mermaid. said to have been found in a camp on the top of Addleborough, or in one below, nearer the town. These camps are sometimes called "High Bruff " and " Low Bruff." One was perhaps a summer camp, while the other represents the Roman station.

In this neighbourhood the family of Parke held land from an early date. In 1856 one of the family distinguished in the law, attained the title of Lord Wensleydale, which was first granted as a life peerage, but after a notable contest in the House of Lords, was made hereditary.

Askrigg Stat., about 1 mile from the dull little town of grey houses, which has an Inn: King's Arms, clean and homely, but small; P. H. and traps. There is an uninteresting ch., and a picturesque stone-house, with date 1675, in the main street.

Behind the town, approached by paths across the fields, are two small waterfalls, picturesque, but of no great size or height; not holding the first rank among Yorkshire cascades, but still worthy to be the objects of a morning's walk.

Millgill Force. Like all the "forces" in this district, the water descends (69 ft.) over a scar at the end of a long hollow. Here the sides of the glen are narrow and broken. The water flings itself over a scar of black rock, the sides of which are clothed with trees, ferns, and grasses. In front, the basin of the fall is hidden by a great "platform" of rock, with other masses piled irregularly round it. "On a nearer approach," writes Wordsworth, "the waters seemed to fall down a tall arch or niche that had shaped itself by insensible moulderings in the wall of an old castle. We left this spot with reluctance, but highly exhibarated."

from this point northward over the Above it (on the same beck) is Whitfell Force-more difficult of access, but repaying the severe climb up the hill. Here the glen is much narrower, between limestone rock, and the water falls (42 ft.) in broad sheets over gritstone rock.

> From Bainbridge, p. 317, you may climb Addleborough (1564 ft.), the remarkable limestone hill rising E., of the village. On its top is Stoneraise, a cairn 360 ft. in circumference, piled above 3 stone cists, one of which retains its shape. A square Roman camp, now almost obliterated, once existed here. The view from the summit of Addleborough is vast, but perhaps less so than that from Penhill. It however commands Seamerdale, out of which the Bain flows, and which is "unique among Yorkshire dales in its shape and The lake is fed by character." streams descending from three dales -Bardale, Raydale, and Cragdale. The hills that on each side guard its entrance stand boldly out toward the Ure; and 2 m. up the dale is Seamer-water (locally called Semerwater; the etymology is not clear), a lake of 105 acres, with a sprinkling of wood round its shores. It cannot be compared with the least picturesque lake in the adjoining counties of Westmoreland and Cumberland; but the scene is quiet and pleasing. and under some effects of light even The lake contains some fish trout, bream, and grayling—the last introduced within memory: but the trout here are by no means so fine as those in the neighbouring streams. There is a tradition that a large town once stood on its site. and that an old man sought alms from house to house throughout it. receiving none till he came to a cottage on the outskirts. There he was fed and lodged, and on the following day departed. As he climbed the hill he turned, and, looking on the city, exclaimed

"Simmer water rise, Simmer water sink, And swallow all the town, Save you like house,

Where they gave me meat and drink."

The earth gaped, the lake rose, and all perished except the inhabitants of the "li'le house."

A large block of limestone called the "Carlow Stone" lies at the foot of the lake.

(A rough mountain road leads Bainbridge E. of Seamer Water, across the ridge to the road through Widdale, from Hawes to Ingleton. (See post.) A pedestrian may make his way by this road to the little Inn at Gearstones, near the source of the Ribble. This inn is about 10 m. from Bainbridge. on the Widdale road, and is 8 m. from Ingleton. Distances, however, in this mountain district are hardly to be reckoned by miles, and the walk from Bainbridge to Gearstones will prove a long (and somewhat dreary) one. (See for it and the country round, post, and Rte. 32).]

On quitting Askrigg, the railway crosses the Ure to its rt. bank, passing 1. Bainbridge (see above, p. 317).

Hawes Stat., 820 ft. above sea-level (from hals, Teuton, neck or col or pass: in Cumberland "hawse," leading across a watershed). Inn: The White Hart (2nd rate, commercial). dale here is broad and open, and not very picturesque. Hawes is a town of 1843 Inhab., just halfway between Leyburn and Sedbergh. Much knit worsted hosiery is made here sailors' jackets, shirts, stockings, &c.; and Hawes is the chief depôt for the butter produced in this and the neighbouring dales. As much as 700l. has been paid in one week for The town itself is unin-The ch., built in 1852, is teresting. tolerably good. It is a pity there is not a better and more commodious Inn here. Hawes is a centre from which several excursions may be made.

Hardraw Force, 1½ m. above Hawes, on the opposite N. side of the valley, must on no account be left unseen.

A road crossing the Ure by a bridge (there is a shorter footpath) leads to Hardraw, a hamlet, with a very neat Gothic Church, built 1880, by Lord Wharncliffe, and a small and clean public house-Green Dragon. Behind the church opens Fossdale, in the mouth of which is Hardraw Force, the most remarkable of the waterfalls in Wensleydale. The glen, running up into the flanks of Shunnor Fell, near its entrance, assumes the shape of a horseshoe. thickly wooded, in pleasant contrast with the surrounding moors. It is walled in by limestone cliffs, perhaps 200 ft. high, and the width of the glen is not much more. At the extremity of it, in the centre of the curve, the stream dashes down a depth of 96 ft. from the brink of the cliff, which, being composed of two beds of soft black shale, with one thin stratum of hard limestone interposed between. is cut away, down to this stratum, in a deep channel by the force of the water, and is washed out and disintegrated below the limestone by the dashing of the spray. The consequence is, that the limestone-bed. insensible to any erosive power in running water, projects 10 or 15 ft. from the face of the precipice, forming a ledge or cornice over which the water leaps at once in one great spout into the centre of the black circular pool below, leaving a vacant space of 30 or 40 ft. between it and the scooped-out rock. Along this hollow, and beneath the cornice of limestone, there is a ready passage quite behind the fall, which may be thus approached and examined from below with the greatest ease. It is very striking to watch the vast jet shoot off from the overhanging ledge above your head, and to gaze through the falling foam, as through a veil, upon the scene around. The

path is continued up the face of the rock by stone steps, laid in a gap or chasm, and then turns back by a wooden bridge over the top of the The view from the cliff, looking down on the fall, and over Wensleydale beyond, is very fine; the white column of water relieved against the inky rocks, and the impending character of the precipices around, form an imposing scene, which has been worthily portrayed by the pencil of Turner.

During very hard winters (e.g. 1880-81) this fall forms a huge stalagmite of ice, pyramidal in form, reaching up the face of the rock to a height of 80 or 90 ft., and nearly as broad at its base. In the centre of this icy pyramid the water may be seen flowing as through a glass tube.

The cranesbill geranium (Geranium sulvaticum) grows in such plenty over the fallen masses of limestone at the bottom of the glen as to give distinct colour to the foreground. Geranium pratense and lucidum are also found in the neighbourhood.

Among the trees above Hardraw is seen Simon's Hall, shooting-lodge of Earl Wharncliffe. whose grounds occupy part of Fossdale.

Seven dales-Mossdale. Yoredale proper, Cotterdale, and Fosedale (N.), and Widdale, Galedale, and Seamerdale (S.), open out within 3 m. of Hawes, radiating from it N., S., and W. All these dales contain scattered farms and cottages, generally nestling under three or four old ash-trees or sycamoresthe originals of Wordsworth's picture-

"And he had trudged through Yorkshire dales.

Among the rocks and winding scars, Where deep and low the hamlets lie, Beneath their little patch of sky,
And little lot of stars,"—Peter Bell, pt. 1.

All are pastoral; and the green meadows running up their hollows

rough mountains that guard them. Black-faced sheep are plenty, and in winter are smeared with tar and grease to protect the wool. animals are so much reduced during that season, that the wool would become diseased without some such help. Much wool is spun and knitted in the dales, and clogs (wooden shoes, generally of alder) are made in great plenty during the winter. Piles of them may be seen in front of many of the houses.

There are waterfalls on almost all the becks that descend through these dales. On the Cotter, not far from its junction with the Ure, there is one worth a visit. (For the upper

part of the Ure, see post.)

Hawes to Hawes Junct. Stat.

The rail, constantly ascending, soon turns l. out of the valley of the Ure, which is here nearly as broad and flat as at its mouth, and is wild moorland. not picturesque; rt. is seen the gap of Hardraw and Ld. Wharncliffe's lodge above it, and N, the Ure is visible sweeping down from the flanks of Wildboar Fell.

7 m. Hause Junct. Stat., where our line joins the Midland, near where it crosses the valley on a Viaduct of 12 arches. In front rises the mass of Bough- or Bowfell, an isolated mountain, 2216 ft. high.

A long mountain road (15 m.) runs from Hawes through Widdale to Ingleton. Widdale is, however, hardly worth exploration on its own account, and the Rly. by Hawes Junct. is much quicker.

The carriage-road crossing the ridge. 6 m. from Hawes (where is the boundary between the N. and W. Ridings), descends into Garadale, through which the streams run W. towards the Lune.

The scenery hence to Sedbergh is contrast very pleasantly with the pleasing, without being grand or especially striking. Rt. rises Baugh | is a mound of natural drift, which Fell. and l. the much less lofty hills of Rysell and Craggs. The road crosses and recrosses the Garadale beck, that gives life and animation to the valley, the sides of which are scarred with hollows, lined with wood in places, and gleaming with streamlets. There is little heather, and the hills are green to the summits. cottages and farms are whitewashed. so as to be seen at some distance. Halfway through the dale is a modern chapel, of E. Eng. character, pleasant to come upon. A very fine group of hills (one of which is the "Crook of Lune"), wild and marked with deep gills, rises in front shortly before the road crosses the stream of the Rothay, and enters

Sedbergh Stat. (Inn: Bull and Dog), a town on the extreme border of Yorkshire, in the valley of the Rothay, which here flows onward to join the Lune. The Church of St. Andrew, Norm., with Perp. additions, is worth a visit. The alter-steps and the font are of black Dentdale marble. The bust of a mathematician. John Dawson, a native of Sedbergh parish, who had 11 senior wranglers for pupils, is in the nave. In the ch.yard are two yews under which George Fox the Quaker preached, drawing all the people out of the church to hear him.

The neighbourhood of Sedbergh is wild and pleasant, the steep hills rising close round the town. The Grammar School, founded by Roger Lupton, Provost of Eton, temp. Ed. VI., is richly endowed, and has produced many scholars of distinction. Among them was the late Professor Sedgwick. Hartley Coleridge Was (1837-38) one of the tutors here, and was especially fond of the Sedbergh hills and rivers—the latter, he used to say, were precisely Homer's olvowes ποτάμοι - being, when flooded, the colour of old port. Above the town [Yorkshire.]

has been scarped, and may, perhaps, have been used as a Roman watchtower. Cautley Spout, a long, narrow waterfall on the side of Howgill Fells, is worth a visit when full of water. The mass of Hougill Fells (the highest point is the Calf. 2188 ft.) consists of the Silurian slatv rocks usual in Westmoreland (in which county it is for the most part): and the scenery differs greatly from that of the limestone. "Intersecting slopes in angular masses of grev rock, breaking through steep green surfaces, give to this district a very different aspect from the broad swells. rough craggy edges, and brown or purple heath, which mark the greater part of the Yorkshire fells." -Phillips. The mountain view from the Calf," extending far over the Westmoreland hills, is very fine.

(The Rly. from Leeds and Ingleton to Low Gill, Penrith, and Carlisle, has a stat, at Sedbergh, about 1 m. from the town. By it the tourist may proceed into Cumberland.)

(Dentdale (see Rte. 32), a long winding dale, famous for its beds of black marble, runs from Sedbergh nearly to Ingleton. (The name of the Dee, which flows down it. seems to be partly retained in that of the dale.) The upper part is wild and romantic, but it is not one of the most interesting dales. At Dent, a small town still famous for its knitters (witness the story of the "terrible knitters of Dent," told in Southey's 'Doctor'), was born Adam Sedgwick, the well-known geologist and Professor of Cambridge.

ROUTE 24A.

HAWES TO MUKER.

The "Buttertubs Pass," (1760 ft. above sea-level), as the road is called running over the ridge from Hawes to Muker in Swaledale, is singularly wild, and commands most extensive mountain views. distance is 6 m. from Hawes to Thwaite, and 1 m. thence to Muker.) The climb to the summit of the pass is rough, and calls for good sinews. The road passes between Great Shunnor Fell (2351 ft.) and Lovely Seat (2216 ft.)—the latter of which "is, perhaps, the most conveniently situated of all the hills of the district for giving a panoramic view of the upper part of the Swaledale and Yoredale hollows."-J. G. B. "The evening view toward the S., on gaining the summit of the pass, is of the utmost grandeur, Ingleborough, Whernside, and other fine outlines coming boldly out beyond the broad undulations about the head of Yoredale."-Phillips. The walk (for the sake of this view) should rather be taken from Muker to Hawes than in the contrary direction. The "Buttertubs," which give name to the pass, are six or seven deep holes in the limestone a little below the Swale- road, both crossing the Hell Gill dale side of the summit. "One or Beck.

two have pillars like basaltic columns: some are very deep; several have ferns growing down the sides, and juniper-bushes about the top; all are curious."-W. S. Banks. The hills on either side do not offer much interest, and the ascent of Lovely Seat will not give much more than is gained from the pass itself. There is a clean but rough Inn at Thwaites, and another, but indifferent, Muker. (See Rte. 25.)

The upper part of Swaledale, including the road from Reeth to

Muker, is described in Rte. 25.

ROUTE 24B.

HAWES TO KIRKBY STEPHEN. HELL GILL

Proceeding from Hawes to Sedbergh, the road is at first uninteresting. At 4 m. a road turns to N. to Kirkby Stephen.

This route, after quitting Hawes. passes r. the village of Thwaites, and leaving the railway on 1., adheres to the course of the Ure following it up nearly to its source on rt., I. rises the rough summit of Wildboar Fell. The Midland Railway going N. from Hawes Junct., runs parallel with our

The pedestrian will find no inconsiderable pleasure in exploring the almost savage solitudes about the sources of the Eden and the The hills here are dark and rugged, displaying, in Camden's words, "such a dreary waste and horrid silent wilderness, that certain little rivulets that creep here are called 'Hell-becks'-rivers of hell. In this part the goats, deer, and stags of extraordinary size, with branching horns, find a secure retreat." By the "Hell-becks" the stream of the Eden near its source is meant. (Al or Hel (Celtic) indicates high or prominent ground; but the "hel" here is probably the northern root, signifying something covered or closed in, as in "heling"= roofing.) This river plunges suddenly into what is called Hell Gill, 9 m. from Hawes. "From the very edge of the water on both sides limestone precipices to a height of 50 ft. rise so sheerly and abruptly, that in one place, with the maddened mountain torrent foaming and boiling below, it is easy to leap across from one crag to the other. The cliffs are ravine is under 1 m. overgrown by mosses and bushes, but the recesses of the glen it is almost impossible to explore without a rope, for its sides are much too steep to be climbed."—J. G. Baker.

Kirkby Stephen Junct. Stat., on the rly. from Barnard Castle to Appleby and to Tebay, see *Hndbk. for Durham*.

ROUTE 25.

YORK TO RICHMOND, SWALEDALE, REETH, MUKER, AND BARNARD CASTLE, BY DALTON JUNCTION AND CATTERICK BRIDGE.

(From York to *Dalton* Junction on the N. E. Railway, this route is the same as Rte. 16.

across from one crag
The length of the
1 m. The cliffs are osses and bushes, but the glen it is almost plore without a rope,
Darlington.)

From Dalton Junct. a branch line of 10 m. runs to Richmond. 5 trains daily: on Saturdays 2 additional trains run each way. This branch line is in direct communication with Darlington.)

Passing the stations at Moulton and Scorton, we reach

61 m. Catterick Bridge Stat.

The places of interest here are the site of the Roman Station, the Chapel of Brough Hall, and (only to be seen by special permission) the pictures at the Hall itself; and Catterick Church.

Cutterick Bridge crosses the Swale a short distance S. of the rly. stat.; it has been much altered and widened since it was completed in 1425. According to the contract for building it, still preserved at Brough Hall, "with the grace of God," was to be made "accord and in substance to Barnacastell-brigge." It crosses the Swale in the line of the Roman road (now called Leeming Lane), which ran from Isurium (Aldborough, Rte. 19) to this place: a little N. of which. at a place called Violet Grange, roads parted N. to Vinovia (Binchester), and N.W. to Lavatræ (Bowes).

Until 1840, this road was one of the chief lines of communication with the North: and the Inn at the bridge (still not uncomfortable) was famous in the days of posting. There was an Inn here in the time of Hen. VIII., and a chapel near it, ded. to St. Anne, of which some traces (Leland says, "Keterick remain. Bridge selfe hath but one house as an ign.")

Looking up the river from the bridge, a high bank on the S. side marks the site of the Roman Cataractonium (the name is retained in the modern Catterick, but its etvmology is quite uncertain; Caerdar-ich, "the camp on the water," has been suggested, but such a name would be just as applicable to hundreds of other camps. Ptolemy calls it Katapaktov). The position was of importance, and Cataractonium was a walled camp, with sides of 240 and 175 yards, enclosing about 9 acres. A portion of the wall has been cleared, and partly rebuilt (for the sake of preservation). A few inscriptions have been found hereone in 1620, recording the restoration of an altar to the deity of roads and paths, "Deo qui vias et semitas commentus est "—an important personage in this wild corner of the Brigantian territory. Other relics are preserved at Brough. The field, in which the camp now exists is known as "Thornborough," a name of frequent occurrence in connection with British and Roman relics. (It

the bridge cost 173l. 6s. 8d., and, | Thurn=tower.) According to Bede. Paulinus used to baptize in the Swale here. "In provincia Deirorum, ubi sæpius manere cum rege solebat. baptizabat in fluvio Suala, qui vicum Cataractum præterfluit."-H.E.. l. ii. c. 14. This passage probably gave rise to the story that Paulinus baptized 10,000 in one day in the Swale, a story which has been transferred to him from St. Augustine of Kent. But although Pope Gregory, writing to the Patriarch of Alexandria, says that Augustine baptized 10,000 Saxons on Christmas-day, he does not mention the scene of the baptism. Gocelin (Acta Sanct.) and Gervase (Act. Pontif.) place it at the Swale; meaning, certainly not the Yorkshire river. but the passage so called between the Isle of Sheppey and the mainland. The etymology is not clear.

> A gate, just beyond the bridge, leads to Brough Hall (Sir John Lawson, Bart.). The Roman Catholic Chapel is seen rt. of the entranceroad, and is shown to visitors. (Ask at the school below.) It was built by the late Sir William Lawson, and is a close and very successful copy of Abp. Roger's Chapel (now the Chapter Library) at York (see Rte. 1). An Ecce Homo, said to be by *Correggio*, deserves notice. The stained glass of the windows is by Willement and Wailes.

The House of Brough is partly Elizabethan, but has been modernized and added to. The ceiling of the entrance-hall is a very good example of Elizabethan work, having the beams decorated in arabesque, with shields. Here is a very beautiful Virgin and Child in marble (of small size), said to be by Rubens. who sometimes modelled. A portrait of Arabella Fermor, heroine of Pope's 'Rape of the Lock,' should also be remarked. Under the stairis perhaps in some shape the Teutonic case is a large cauldron of mixed metal, found at Cataractonium. It! holds 24 gallons, and was at one time "fixed in a furnace to brew in." When found, it was covered with flat stones and full of Roman coinsa true "crock of money." In the Drawing-room are three "Holy Families" by Garofalo, Ghirlandajo, and Perugino: a "Virgin and Child" by B. Van Orlay; and a small early triptych (panel) with figures of saints ---very good and noticeable. A small case in this room contains some interesting relics from Cataractonium. including a Saxon fibula; plaques of Limoges enamel; some miniatures; and a garter and glove worn by Charles Edward, the "Young Chevalier." The Dining-room contains two wonderfully fine portraits by Nicholas Maas, said to represent the Dutch poet Jacob Cats and his wife. The portrait of the wife is signed and dated 1669; Cats the poet died in 1660; so that, if they really represent him and his wife, they must have been painted by Maas after some earlier and perhaps inferior pictures. Here is also a fine copy of Raffaelle's Leo X. A small "Pietà" is called Vandyk. In the Breakfast-room is the portrait, by Lely, of Miss Lawson-" virtuous only found" among the beauties of Chas. II.'s Court.

Fragments of columns, and two small lions carved in stone, from Cataractonium, are preserved in the The lions (it has been garden. suggested) may have been connected with the Mithraic worship introduced in the north of Britain by Caracalla.

A road of a little more than I m. leads from Brough Hall to Catterick Church, of considerable interest to the ecclesiologist, since the contract for building it (in 1412), between "Richard of Cracall, mason, and Dame Catherine of Burgh," is still preserved, and was edited by the late Dr. Raine. The ch. has been "restored." · Catterick is an excellent | example of true "preservation." The man road from near Richmond to

ch., ded. to St. Anne, is of course Perp. - plain, and only of special interest from the fact of its date being so clearly ascertained. deep outer mouldings of the main arches are remarkable. Some screenwork, and the original flat wooden roof, remain. In the wall of the S. aisle, under a recessed canopy, is the effigy of Walter de Urswick, Constable of Richmond (still living in 1373), brought from the ch., which was pulled down when Master Cracall had completed his labours. The N. aisle is the burial-place of the Burghs, and contains some good brasses: John de Burgh (d. 1412) and his wife, Katherine, foundress of the ch. (inscription only); William Burgh, d. 1442; and Wm. his son, d 1465 (effigies); Wm. Burgh, "hujus cantar. fund." (founder of this chantry), d. 1492 (effigies of himself and wife). The font has some shields of arms, and an inscription not easily decipherable. Over the porch (called Our Lady's Porch) are the arms of Burgh (swans), Aske, and Lascelles. In the chancel is the monument of Richard Braithwaite. called "Dapper Dick" by his boon companions at Catterick, but better known as "Drunken Barnaby;" whose 'Itinerary' in Latin and English verse was first published in 1638.

The churchyard may possibly have been an ancient camp. Palet Hill, a large tumulus near it, was, perhaps, connected with this early for-This is little more than tification. conjecture; but the whole country between the Swale and the Tees abounds in camps, dykes, and entrenchments, all of which have been most carefully surveyed (at the cost of the 4th Duke of Northumberland) by Mr. Maclachlan. (Archæol. Journal, vol. vi.)

The most remarkable of these dvkes ran somewhat W. of the RoStanwick, where it was connected ! those of St. Martin's Priory l., as. with the singular earthworks in which the house of Stanwick Park is placed, and thence to the Tees. Diderston Hill (700 ft.; N. of the road to Bowes, which branches off at Violet Grange), and Caldwell Camp (450 ft.: N. of Stanwick), command the country through which this great dyke ran. The Stanwick earthworks have been looked upon as the site of British village; but this is quite uncertain, and the dyke may be of still Much has been more ancient date. destroyed; but portions (see the map in Maclachlan's survey) are still very strongly marked.

In the churchyard of Bolton-on-Swale, across the river, opposite Catterick, is buried the famous "Old Jenkins," whose life, if the accounts were accurate, would have been one of the longest on record. He died in 1670, aged, as it was said, 169. He declared that he could well remember the Dissolution of the monasteries, and the mustering of the English forces before the battle of Flodden, when, as a boy of 12, he was sent to Northallerton with a horse-load of arrows. ("Old Parr" died in 1635 at the reputed age of 152. These are the two longest lives which have been claimed as authentic: but it has always been doubted whether the age of Jenkins was really so great as he asserted, and Mr. Thoms (Longevity of Man') has disposed of the question. died at Ellerton; and the parish register of Bolton records, "1670, Decem. 9, Henry Jenkins, a very aged and poore man of Ellerton, buryed." His last wife had been buried there, Jan. 27, 1668. An obeliskal mont., stating his name and age, and that it was erected by contribution in 1743, is in the ch.-yd.

The rly. crosses the Swale about 1 m. below Richmond. The ruins of Easby Abbey are seen rt., and

below thick woods that overhang the rushing river, the train reaches

Richmond Stat. Richmond (Inn. the King's Head, good; Pop. of parish in 1881, 4502) is one of the most picturesquely placed towns in England. The Swale, in a rocky and broken bed, a true mountain stream. flows round the foot of the hill; and. cresting a precipice above the river. rises the great castle of the Breton earls, magnificent even in decay. The stat. is on the rt. bank of the Swale, and the town is approached by a modern bridge.

After the Conquest Richmond became the head of all this country, as Cataractonium had been during the Roman period. At Gilling, 3 m. N. (whence the Wapentake is named), was the chief stronghold of Earl Eadwin, brother of Morcar. Eadwin's last revolt, and his death in 1072, his lands, in this part of Yorkshire, were bestowed by the Conqueror on Alan the Red, one of the sons of Eudo Duke of Brittany, who had joined William's expedition. Alan received 164 manors in Yorkshire: and removing the chief place of his "honour" from Gilling, established it in a situation more proper for a Norman stronghold-

"Where the castle of Richmond stands high on the hill."

He founded the castle, gave the place its Norman name, and became the first Earl of Richmond. new "Honour" comprised altogether 440 manors (including those of "Richmondshire" itself). scattered throughout England. The town of Richmond, as usual, grew up under the shadow of the castle, and the borough became of sufficient importance to give its name to new civil and ecclesiastical divisions of the country-"Richmondshire" and the archdeaconry of Richmond.

The fourth Earl of Richmond

married the heiress of the Breton of course, the most prominent. This, His son, Conan, thus became both Duke and Earl; and it was he who built the massive keep of Richmond Castle, which still exists. His daughter was the Lady Constance of Shakspeare's 'King John:' the mother of Arthur, and of the still more unfortunate Eleanor "la Brette." Henceforth the Dukes of Brittany retained their English possessions on but an uncertain tenure: since whenever, in time of war, they attached themselves to the kings of France, their honour of Richmond was forfeited and passed into the hands of the English Crown. It was finally severed in the reign of Rich, II., and was afterward held, but without the earldom, by Ralph Neville, first Earl of Westmoreland. The earldom was granted (for life) to Edmund Tudor, and to George Duke of Henry VII., who claimed Clarence. of Earl of Richmond the title through his descent from John of Gaunt, to whom it had been given by Edw. III., transferred the name, after his accession, to the palace he rebuilt at Shene, on the banks of the Thames. The first Duke of Richmond was Henry Fitzroy, natural son of Hen. VIII. After his death the title was not revived until 1613, when Lodowic Stuart, Duke of Lennox, was created Earl, and, in 1623, Duke of Richmond. Finally, the dukedom, with the site of the castle-all the rest of the honour had been long alienatedwas bestowed on Charles Lennox, natural son of Chas. II., who is represented by the present duke.

The *Castle is, of course, the first point of interest in Richmond. approached by a lane opening from the market-place. A space of 5 acres, on the suminit of a rock, which projects over a bend of the river, is surrounded by walls and buildings, which should be examined in due order, the great keep-tower being,

stern and massive, and with scarcely a tuft of vegetation along its ledges, has not been "mouldered into beauty." but still "frowns with all its battlements," almost as when it passed from the hands of Duke Conan's masons. Some earlier remains, however, exist in the buildings of the enceinte.

which may first be visited.

L. of the entrance is Robin Hood's Tower (the name is probably modern). in the lower portion of which is the Chapel of St. Nicholas (18 ft. by 10 ft., 12 ft. high). The E. end is apsidal, with a long loophole light. the sill of which formed the altar. The walls are arcaded. It is of early Norm. character, and may have been part of the first Earl's building. An upper floor beyond this tower shows a second chapel of later date, with a trefoiled piscina remaining. The Golden Tower is so called from a tradition that a treasure was once found in it. The basement story, once completely dark, and sunk below the level of the castle-yard, has been used as a prison. A fracture in its western wall used to be considered as the mouth of a subterranean passage leading under the river to St. Martin's Priory; and it may be questioned whether Speed had better authority for inserting on his map of Richmond in 1610 the locality of a "vault that goeth under the river and ascendeth up into the castell " from the high ground opposite to the S. side of This hall, which Scolland's Hall. adjoins the Golden Tower, deserves careful examination. Unroofed as it is, it is one of the most perfect Norm. halls of its class remaining in England; since, although many halls with Norman keeps still exist. there are few which, like this, form a distinct building. It probably served as the great banqueting-room of the castle, and was an upper apartment, approached from the exterior by stairs at the S.W. angle. rooms adjoined it E., and there was

probably a separate access from | from the keep, "shows how completely. them.) On each side of the hall are 2-lighted windows, divided by a central shalf. The corbelling which supported the roof is perfect. has been asserted that this hall is of earlier date than the keep; but the details are so similar as to make it probable that it also was the work of Duke Conan. Scolland, who gave his name to the hall, was Lord of Bedale (Mon. Angl., i. 401) and "dapifer" of Earl Alan III., several of whose charters he witnessed, and was living in 1145. He was one of the great tenants of the Honour, who were bound to take their share in the "watch and ward" of the castle.

In the early part of the 16th cent. a large space adjacent to the S. wall of the enceinte was occupied by the pantry, buttery, kitchens, and other offices. The turret at the S.W. angle is now nearly filled up with rubbish: but it appears to have been constructed as a place of confinement, the entrance being at the top, and communicating with the path on the summit of the mantel wall.

In the W. wall of the castle-yard is a large window-like opening which never seems to have been filled with tracery; and there are no traces of walls on each side to show that there had been a contiguous structure. marks, however, the position of the principal chapel of the castle, which seems to have been founded in 1278 by John of Brittany, Earl of Richmond, son of the Duke of Brittany. There is in Gale's 'Register' a convention made in that year between him and the abbot and convent of Egliston, whereby the latter, in consideration of the endowment mentioned, agree to find six chaplains, canons of their church, "divina celebrantes in castro Richmundiæ in perpetuum." An enclosed space within the castle was provided for the residence of the chaplains. The manner

at all events in castles of this palatial kind, the keep was merely an occasional place of defence."-Freeman. iv. 296, note.

The great Keep, to which we turn last, is one of the finest and most perfect Norm. keep-towers in England. Those of Dover, of Newcastle, and of the Tower of London, can alone be fairly compared with it. Norwich has been entirely modernized: whilst Rochester. Canterbury. and other keeps of the same date, are in ruins. It was probably (although this is not so certain as to admit of no question) the work of Duke Conan (1146-1171); and we may fairly suppose that the fame of its newly finished strength had been spread abroad throughout the north in 1174, when, according to the rhyming chronicle of Jordan Fan-(edited for Surtees toeme the Society), the first question asked by Henry II., on the invasion of the Scottish king, William the Lion, was, "Is Ranulph de Glanville" (Henry's great Justiciary and most powerful baron) "in Richemunt?" The keep is 100 ft. high, and the exterior walls are 11 ft. thick. Whilst other portions of the castle had fallen into ruin so early as the reign of Edw. III. (owing probably to the indifference of its later Breton lords), this tower has suffered little or nothing from time; though its antique effect, as seen from within the court, is damaged by some modern "pointing" of the masonry, and by a modern portal.

The walls of the keep (built of Gatherley Moor sandstone) flanked by flat buttresses, which rise at the angles into solid turrets, overcapping the main tower. turrets, and the buttresses between them, are of later date than the rest of the work. The chief entrance is on the S. side, and on a level with in which hall and chapel stand apart | the first floor; but below this is

(very unusually) an enriched portal; opening to the vaults underneath. which are carried by a central octagonal pillar. The pillar and vaulting, however, are insertions, as is the circular staircase. Here is a well, sunk in the natural rock, forming the floor; and a circular staircase, in the left-hand corner, leads to The interior of the the floor above. keep has been "restored." Floors (which had disappeared) have been relaid for the several stories, and the building now serves as a store for the accourrements of the militia. Under these circumstances it is not easy to follow the ancient arrangement. (There are plans and descriptions of the keep in the 'Journal of the Archeeol. Inst.' vol. i.) The principal hall, however, was on the first floor (above the vaults), with three large windows looking N. over town: the staircase, on the S. side, overlooking the enceinte and the river. Above the hall are two other stories, through which you climb to reach the battlements. view from them is one of the very finest in England. On one side the eye ranges up the wild hollow of Swaledale, and on the other over the fertile plain of Mowbray, to the distant towers of York and to the estuary of the Tees. Far below, the river foams and dashes over its rocky bed, through a grand broken foreground, with trees and hanging banks. The "riche munt" here shows itself fully entitled to its name; and although the climb to the top of the tower is laborious, it should on no account be omitted.

In the Castle Court are some barracks, which, though not bad in style, do not assist us in recalling the days of Duke Conan and the ermine shield of Brittany. A piece of "folk lore" which has been localized in various places—among others, under the triple height of Eildon and at Freeburgh Hill in Cleveland, see

mond Castle. Arthur and his knights are said to lie under the "roots" of the great tower, spell-bound in mys-A certain Potter terious sleep. Thompson was once led into the vault, where he saw the king and his knights, and, on a great table, a horn and sword. He began to draw the sword; but as the sleepers stirred, he was frightened, and dropped it, when a voice exclaimed,-

" Potter, Potter Thompson, If thou hadst either drawn The sword, or blown the born, Thou'd been the luckiest man That ever yet was born.

The exterior of the castle is best seen from the opposite hill. There is a walk close under the walls, which the tourist should follow throughout. Here he will see the manner in which the foundations have been planted on the rock. He should cross the Swale by the bridge at the end of Bargate, and mount to the top of the From this point the extent hill. and general position of the castle will be readily understood. unusual height of the keep is here esspecially noticeable; and the shadows and varied lights, changing along its different sides, add to its picturesque effect. Above the bridge you should walk a short distance up the rt. bank of the river, as far as an old lime-This is a good point for the kiln. artist, with the great keep towering above a wooded foreground. Richmond Castle has long been a favourite subject for the pencil; Turner's magnificent drawing (first engraved for Whitaker's 'Richmondshire') bearing away the bell.

The parish Church of Richmond, which stands on the hillside near the stat., was restored and in effect rebuilt, under the care of Sir G. G. Scott. The greater part of the choir, the clerestory of the nave, and the tower are Perp., the rest Dec. The old work has been used wherever Rte. 15-has found a home at Rich- possible; the new is enriched with some good sculpture. Of the old, 2 Norm. piers remain at the W. end, The stained glass in the windows is modern, with the exception of some shields in the E. window. The screen and stall-work in the choir was brought from Easby Abbey (see post), and is of great beauty. It is of the usual Yorkshire type, the arches being left far more open than in the richer screens of Devonshire or Norfolk. The subsellia have some curious devices; among which is a sow playing on the bagpipes to her young ones, who dance around. stall of the abbot (marked by a shield with a tun, and the letters "ba" pierced by a pastoral staff, and surmounted by a scroll inscribed "Abbot," the device of whose election Bampton. to abbacy was confirmed in 1515) is occupied by the mayor, whose mace is proudly reared in front of it. the S. of the modern reredos is an inscription recording the rebuilding of the ch.

In the chancel has been replaced a heavy monument to Sir Timothy Hutton of Marske, who died "Anno ultimæ patientiæ sanctorum, 1629." The inscriptions, in which his own name and his wife's are played upon in various ways, should be read. The Perp. tower remains unaltered. It was possibly the work of Ralph Neville, 1st Earl of Westmoreland, to whom the Honour of Richmond was granted in 1399. The church of Richmond had been given to the Abbey of St. Mary at York at a very carly period.

The churchyard is remarkable as the scene of the well-known lines, written in it by Herbert Knowles, who died in 1817, aged 19:-

"Methinks it is good to be here,
If thou wilt let us build—but for whom? Nor Elias, nor Moses appear; But the shadows of eve that encompass the

gloom-The abode of the dead, and the place of the

At the corner of the churchyard is the Grammar School, generally known as the Tate Testimonial, it having been completed in 1850, as a memorial of the labours of the Rev. James Tate, who was master of the old Grammar School for 37 years. and sent forth among his scholars many who attained great eminence. Among them was Dr. Musgrave, the late Abp. of York (1847–1860). Mr. Tate became a Canon of St. Paul's in 1833, and then resigned his charge. The school is one of those founded by Queen Elizabeth.

Trinity Church, in the Marketplace, has been so desecrated as to call for little notice. The chancel has disappeared, and a dwelling-house intervenes between the nave (Dec.) and the tower (Perp.). It is, however, still used as a ch.

More interesting is the Tower of Grey Friars (Franciscans), in the garden of J. J. Robinson, Esq. was the central tower of their ch., and is the sole remaining fragment of a house of Franciscans, founded in 1258, by Ralph Fitz-Ranulph, the last lord of Middleham of that race (see Middleham, Rte. 23), in coniunction with the Scropes. tower, a very graceful composition. is Perp.; and, according to tradition. the ch. of which it formed a portion was never finished. It was to these "Freers of Richmonde" that Ralph of Rokeby gave the Felon sow "to mend their fare," which caused such infinite trouble in the bringing home, although "Freer Middleton conjured her on Greta Bridge with "cross and creed."-See Rokeby. Rtc. 26.

Rather more than 1 m. from Richmond, S.E., is the village of Hipscell. which there is every reason for regarding as the birthplace of Wickliffe the reformer. There is some confusion in the original printed versions of Leland's 'Itinerary' where the not easily intelligible. The cloister name appears, there being no such a place as Spreswell. But, very fortunately, in an account of places taken from Leland's 'Itinerary,' and digested in topographical order, about 100 years after he wrote (Harl. MS. 812), the passage is given at full length :- "They save that John Wiclif, hæreticus, was borne att Ipreswell, a poore village a good mile from Richmont." It is thus clear that in Leland's time there was a tradition that the reformer was born at Hipswell, the name of which was no doubt given to Leland in a broad Yorkshire tone-hence his spelling "Ipreswell."

The tourist should on no account leave Richmond without visiting Easby Abbey (1 m. E.) and the Racecourse (11 m. N.). From the latter a magnificent view is commanded.

(a) The walk from Richmond to Easby passes below the parish ch., and turns off l. before crossing the rly, bridge. Nothing can be more The river, broad, sparkling, and rocky, and overhung by great trees, accompanies the path rt.; l, the bank rises well wooded, but leaving a stretch of green meadow ground between it and the Swale. On this meadow stand the ruins, affording, in combination with the graceful lines of the hills and the masses of rich foliage, a series of pictures which can hardly be surpassed.

The abbey was founded in 1152, for Premonstratensian Canons, Roald, Constable of Richmond Castle, and was thus in building at the same time as the great keep of Richmond. It was dedicated, like the neighbouring ch. of Gilling, to St. Agatha. (The parish ch. of Easby is ded. to St. Agatha. Besides these, Brightwell, in Berkshire, is the only ch. in England so dedicated.)

Owing probably to its position on the bank of the river, the ground-

is duly placed on the S. side of the nave; but its western walk slants toward the S.E., and all the surrounding buildings are thus thrown out of rectangular order. W. of the cloister are the dormitory and a large common room (?). Dormitory and common room (?), where the canons were allowed the comfort of a fire (the fireplace remains), are marked by the foundation of a row of central All this part is Trans .columns. Norm. and E. E. of very plain character, except an enriched doorway, engraved in Whitaker's 'Richmondshire.' S. of the cloister is the long refectory (Dec., with a fine E. window —the reading-pulpit is evident in the 2nd side window from the E.), and below it, W., the kitchen. On the E. side is the chapter-house (E. E.), with the library above it and the sacristv. Between the chapter-house and the refectory is a small tower, which seems to have been the prison of the monastery. The church, most irregularly shaped, had a N. aisle, with the Scrope chantry projecting from it for about half its length. The cloister intruded on what would have been the S. aisle; but the Premonstratensians, whose order abjured processions, and was one of great severity, preferred long narrow naves (as at Bayham in Sussex). chancel is long, and aisleless. transept had eastern aisles, of which the columns remain. Adjoining the N. transept was the Abbot's house, with a small oratory, marked by a piscina. It was from the ch. of this monastery that the stalls in Richmond church, and the screen-work now in the church of Wensley (Rte. 24), were removed at the Dissolution.

Adjoining the mill-race, which still serves the mill of the abbev, is the ancient granary, perfect, and still in use. The great Gateway, beyond the parish ch., is a very fine example plan of Easby is very irregular, and of E. Dec. (temp. Edw. I.). The apartment above it, generally called the Record-room, was far more probably the guest-chamber of the monastery. The gateway itself has one great pointed arch of 2 orders, the third and inner order being semicircular. "Above this is a string, then a 2-light window with good early tracery, and above this, in the apex of a steep gable, another 2-light window, the whole very simple and beautiful, and early in the style."—

J. H. P.

The red-brick house on the hill above is the residence of R. M.

Jaques, Esq.

The little parish Church, which closely adjoined the abbey, was originally Trans. Norm., but was so greatly altered during the Perp. period, that a commission was issued, May 17, 1424, to the Bp. of Dromore, to "dedicate" (re-dedicate?) it and its Above the porch is a cemetery. priest's room, with fireplace. ch. was (1869) restored (Sir G. G. Scott, archit.), and some curious and early wall-paintings discovered in it have also been partly "restored," at the hands of Messrs. Burlison and Grulls. A shield of Scrope (there are others of Aske and Convers) on the porch is the sole memorial of that great house now remaining at Eashy. In the monastic ch., however, nearly all the Scropes of Bolton, including the builder of that castle (see Rte. 24), were interred: and on their visits to Easby they were received with solemn ceremony and procession, as patrons and part founders of the house. John, Abbot of Easby, was one of the witnesses produced by Richard le Scrope in the memorable Scrope and Grosvenor controversy in 1389. In his deposition he describes the tombs of the Scropes in the abbey ch.; and says that their arms were to be seen there "in windows, in tablets before altars, on vestments, in glass of the chambers and of the refectory, and also on a corporas case of silk.

On the green, S. of the ch., is a large tree, known as the Abbot's Elm, which probably witnessed the expulsion of the canons from their ancient home.

In returning to Richmond the visitor may look (about halfway between Easby and the town) for some traces of the great earthen dyke which ran from the Swale at this point to the Tees at Gainford. They are here, but faint. (See ante, Catterick.)

On the rt. bank of this river. a little beyond the station, is the ruin of St. Martin's Priory-a cell attached to the Abbey of St. Mary at York. The chapel was given to that monastery, probably about 1100-the charter is not dated-by Wyomer Lord of Aske, steward to the Earl of The house here con-Richmond. sisted of 9 or 10 Benedictines. and its annual value at the Dissolution was 47l. (gross). A Norman doorway in the little ruined chapel (now part of the surrounding farm-buildings) is the most interesting relic.

(b) The Racecourse is about 11 m. from Richmond, N. In climbing the hill toward it, remark the view of the town, with the castle dominating it in true mediæval fashion. higher, the river opens W., with its broad rocky bed, and the noble banks of trees which clothe it. From the grand stand on the course one of those vast prospects is obtained which perhaps in England only Yorkshire can show. The great central plain stretches below the spectator from York to the Tees, with rt. the hills enclosing Swaledale and Wensleydale (among which Pen Hill, with its flat top, is conspicuous), and l. the ranges of Hambledon and Cleveland. towers of York Minster and Darlington Church (more than 45 m. apart as the crow flies) are visible at once in clear weather; and it is

said that Durham Cathedral is also to interest, among them portraits of the be seen.

(c) The upper part of Swaledale may be visited from Richmond. The tourist may make a day's expedition to Reeth and back, and in so doing will become acquainted with some very pleasing scenery; but to explore the higher and wilder part of the dale, he should arrange to sleep at least one night at Reeth, where there is a tolerable Inn (the Buck). Swaledale is wild and picturesque, but certainly less so than Wensleydale or Teesdale. Its lead-mines are of great importance, and those who care for mining operations will find them worth a visit. Only a pedestrian, however, who is not too particular as to accommodation, will explore satisfactorily the "head" of the dale.

A good road passes up Swaledale as far as Reeth. It starts from Richmond, on the N. side of the stream. (Before crossing the river observe on the S. side a singular green hill, called the "Round Howe." Near it is a cavern named "Arthur's Oven"). It soon crosses the river, and proceeds through the beautiful scenery already noticed (Rte. 23, Excursion from Leyburn to Richmond) under 4 m. Marske (J. T. D'Arcy Hutton, Esq.). The Huttons have been settled at Marske since the beginning of the 17th cent., and removed then from Priest's Hutton, in Lancashire. house has produced two Abps .--Hutton, translated from Matthew Durham to York in 1595, died 1606 -"a learned prelate," says Fuller, "who lived a pious man, and left a pious memory:" and a second Matthew Hutton, translated from Bangor to York in 1747, and thence to Canterbury in 1757, died 1758. A gold cup, presented by Queen Elizabeth to the first Abp., remains among the treasures of Marske, which include some pictures and portraits of explore Arkengarth

two Abps.: the widow and son of Sir W. Raleigh; Sir Convers D'Arcy, the Royalist: and a beautiful picture of the unfortunate Duke of Monmouth. The views from various points in the park are of great beauty.

34 m. beyond Marske are the ruins of Ellerton Priory, a small house of Cistercian nuns, founded (temp. Hen. II.) by Warner, sewer (dapifer) of the Earl of Richmond. The shell of the little church (without aisles or transepts) remains, but is without interest. 1 m. further on, on the N. side of the Swale, stood Marrick Priory, founded early in the reign of Hen. II. by Roger de Aske for Benedictine nuns. The roofless chancel seems to have been their chapel, whilst the nave served as the parish There are a few ancient tombstones.

Near Grinton (11 m. from Marrick) where the river is again crossed, are some early intrenchments, tumuli, and camps (one 11 m. E. is known as " Maiden Castle"). Grinton (which has an ancient church of no great interest) is the mother-parish of Swaledale, all the upper part of which, up to the Westmoreland border, is included in it.

At Freemington, between Grinton and Reeth, horse-trappings (?) of brass, inlaid with silver, have been found, and deposited in the museum at York. They belong to the Roman period; and there can be little doubt that the lead-mines here were worked by that people.

Resth (Inn, the Buck), about ½ m. from Grinton and 10 m. from Richmond, is placed on the Arklebeck, which here descends through Arkengarthdale to join the Swale. This is now the mining capital of the dale, and is the best point from which to and Upper Swaledale. At this point the good | The scenery becomes road ceases. much wilder and sterner, and the tourist must be content with rough tracks, and (if he sleep at Muker or at Thwaite) very homely accommodation.

In the hills which border Arkengarthdale some of the most productive lead-mines in the district are worked. The best are those on the slope toward the Arkle, of Great Pin Seat (1914 ft.), on the W. side of the For the last 40 years the leadmmes of Swaledale have yielded an average annual produce of 1500 tons. They have been worked from a very early (perhaps from the British) period, and the hills throughout the district are covered with traces of worked-out and abandoned mines. The lower part of Arkengarthdale is bordered E. by a long range of limestone scars, which continue for some miles, and are striking as seen from Reeth. The dale is picturesque, but is hardly worth exploration for the sake of its scenery only. Towards its upper part a branch road crosses the Arkle, and proceeds over Barningham Moor to Barnard Castle. The distance from Reeth is about 12 m.

From Reeth to Muker (9 m.) there is a somewhat rough road along the N. bank of the Swale. The river, true mountain stream as it is, gives in the season when it is usually seen by tourists little notion of its destructive strength during the floods of winter and early spring. Then, in Mason's words.

"The savage spirit of old Swale is roused-He howls amid his foam."-English Garden.

Banks and buildings, especially in the lower part of the dale, are frequently swept away; and the floods on the tributary becks, especially on the Arkle, are scarcely less sudden and

narrows, and its steep sides are sometimes covered with wood. the N. there is a sweep of wild, broken moorland, rising to the watershed that divides Swaledale from the valley of the Tees. The highest summits are Pin Seat (1914 ft.). and, further W., Rogan's Seat (2204 ft.). Towering above the road, in the angle between the Swale and the Arkle, is Calvey (1599 ft.), All these hills are of mountain limestone, with occasional gritstone cappings. Limestone scars run along the edge of the dale in places between Reeth and On the Ivelet beck, which Muker. falls into the Swale (rt.) about 11 m. from Muker, are 2 good fosses, each descending between 40 and 50 ft.

Muker (Inn, the White Hart, very poor and rough) is without interest in itself; but the Old Gang leadmines, perhaps the most ancient in the district, lie nearly opposite, N. (There is a poor but very clean public-house, which the pedestrian may find useful, at Thwaite, 11 m. beyond Muker. Either from Thwaite or from Muker you may cross the Buttertube Pass into Wensleydale. and descend upon Hawes. (See Rte. 24A.) This is the proper direction in which to take this walk-it is possible to drive across, but the road is tremendously steep and rocky--since the great views from the summit of the pass lie southward. In clear weather there is a grand prospect of mountain peaks.)

From Muker the road turns northward, following the stream to Keld, a small mining village under Keasdon (1636 ft.), a very picturesque mass of limestone, girdled with broken scars, and dividing the dale, which branches round it in two narrow glens. river runs through the eastern valley. Below Keld is a waterfall (30 ft.), called Keasdon Force. which is worth a visit. dangerous. The dale beyond Reeth | flinging itself over the force, the

from which two glens branch out W.; | panion.) E. rises Rogan's Seat. "This steep craggy sylvan glen, shut in upon three sides by high mountain walls, showing through its opening upon the W. the brown moors and the wavy line of the ridge of the crescent peaks" (at the head of Swaledale), is one of the finest and most interesting portions of the river."-J. G. Baker. A mile above Keasdon is Catrigg Force—fine and picturesque in wet seasons.

Above Keld the upper part of the dale stretches toward the sources of the Swale, in the great crescent of hills sweeping round from Water Crag, on the Westmoreland border, by Nine Standards (2153 ft.), over Kirkby-Stephen, to Great Shunnor Fell (2346 ft.). All these are "cragless, treeless, undulated sweeps, with little to attract botanists or geologists." This portion of Swaledale, grand and severe as it is, is far less picturesque than the "heads of Teesdale or Wensleydale; yet for those who care to explore solitary and little-known tracks of moorland, the region is not without charm. " Everything indicates an unfrequented district—the natural ruggedness of the face of the land, the great flocks of grouse, the seeming scarcity of habitations, and the speech and personal appearance of the very few farmers and shepherds we meet."—W. S. The road from Keld to Kirkby-Stephen crosses the ridge, from which the Swale and Ure descend on one side, and the Lune and Eden on the other. The views from the summit are wide and interesting. From Keld to Kirkby-Stephen the distance is 10 m.

(The many branch glens which open into Swaledale, as well as the main dale, are carefully noticed and characterised in Mr. J. G. Baker's 'North Yorkshire' which the botanist

river passes through a narrow ravine, | should by all means make his com-

(d) There is a good road from Richmond to Barnard Castle (17 m.). which passes one or two places of interest, and crosses the Greta at Rokeby. On this road, 2 m., is Aske Hall (Earl of Zetland), on high ground, in a well-wooded park, and commanding very wide views. Roseberry Topping is visible from the front of the house. Aske was one of the manors of the family which took their name from it, one of whom, Robert Aske, was the great leader of the Pilgrimage of Grace. (The family descended from Wyomer, the founder of St. Martin's Priory, Richmond; and Roger de Aske assumed that name when he settled at Aske in the 12th cent.) 1 m. further is Gilling, the head of the Wapentake before the Conquest. Castle Hill, near the farmhouse of Low Scales, 11 m. S.W. of the village, marks the site (there are no remains) of Earl Eadwin's This, too, was probably the castle. "Ingetlingum" of Bede (H.E., iii. c. 14), where, in 651, Oswin King of Deira was killed by the "præfect" of Oswi of Bernicia. Oswin had disbanded his "host," and, with a single follower, had taken refuge at "Ingetlingum," in the house of Earl Hunvald, who betrayed him.

The ch. of Gilling has been nearly rebuilt, chiefly at the expense of the Wharton family, formerly of Aske Hall. In it is a black marble tombslab, with figures, in low relief, of Sir Henry Boynton, and his wife, d. 1531, the last of the Boyntons of Sedbury.

From Gilling the road turns N.W. into the line of the so-called Watling Street, a branch of the Roman road that ran direct from Catterick Bridge to the Tees. This branch turned off to Bowes (Lavatræ). Neither the ch. nor the ruined castle of Kirkby Ravensworth (passed 1.) is of much interest. The latter was the castle of the Fitzhughs (descendants of Akar, the founder of Jervaulx Abbey, Rte. 23), and after them of the Parrs. The ruins are late Perp. Round a small room, in a turret between the courts, runs the inscription—"xp'c d'n's ih'c via fons & origo alpha et oo." The ch. dates from the end of the 14th cent.

(2 m. rt. of the road is Stanwick Park (Duke of Northumberland), surrounded by very remarkable earthworks. These are on the line of the great dyke (see ante) running from Richmond on the Swale to Barford, opposite Gainford, on the Tees. That this deserted village was really that of Barford (although it is generally, but without apparent authority, called Old Richmond) is evident from the fact that the mediæval manor-house there still retains its ancient and proper name, as it did when Leland wrote. There is a very pleasing view from the hill S. of the house; and on the summit of that opposite are the foundations of the village, which was not altogether deserted in Elizabeth's time, since coins of her reign have been found there. The outline of the main street, stretching N. and S., is discernible, together with the ruin of an E. E. chapel.

Beyond Ravensworth there is little to notice until the road reaches Greta Bridge, where we are in the midst of the Rokeby scenery. Greta Bridge is 3½ m. from Barnard Castle, and will best be visited thence at leisure. For it Rokeby and the surrounding country, see the following Route 26.

ROUTE 26.

DARLINGTON TO BARNARD CASTLE, (ROKEBY), BOWES CASTLE, AND EGGLESTON ABBEY.

15 m. Rail.: 6 trains daily in 11 hr.

This line of rly., which runs throughout on the Durham side of the Tees, is described at length in the Handbook for Durham. The principal stations are

Piercebridge Stat. on the site of the Roman station of Magis, where the road from Catterick (Cataractonium) to Vinovia (Binchester) crossed the Tees;

Gainford Stat. (the ch. has an altar and other Roman remains, probably from Magis, built into its walls). opposite which, on the Yorkshire side of the river, is Barford, commonly called Old Richmond (see Rte. 25), at which place the Great Dyke, running across the country from Richmond on the Swale, terminated.

Winston Stat., where an omnibus for Staindrop (3 m. rt.) meets the trains. (For Staindrop Church and Raby Castle, which is close by, see the Handbook for Durham.) After passing Winston we reach

from the town; an omnibus meets

the trains).

Barnard Castle (Inn. The King's Head - old-fashioned and comfortable; -- good lodgings are to be had out of the town, near the stat., and the artist will find this place excellent head-quarters - Pop., 4514) lies entirely on the Durham side of the Tees, and is described at length in the Handbook for Durham. short notice of the town is inserted here, since it is the centre from which some most interesting excursions may be made on the Yorkshire side of the river—to be fully described.

(Opposite the King's Head is a clockmaker's shop, with a large clockface, on which the name "Humformally W88 inscribed. Dickens was staying at the King's Head for some weeks when collecting materials for 'Nicholas Nickleby. and took the name of his next book from this clockmaker and his clock.)

Barnard Castle is most picturesquely situated on the high rocky bank of the Tees, though nothing is seen of the true position of the town in approaching it from the rly. Church of St. Mary is of no great interest, but contains portions ranging from Norm, to Perp. The Perp. font deserves notice; also an inscribed monumental effigy of stone, of Robert de Mortimer, vicar of Gainford, who founded a chantry in this ch. about the year 1339. The remains of the

Castle, close behind the King's Head Inn, should be visited; not only on account of their own importance, but for the sake of 'Rokeby,' the first scenes of which are laid here. It was founded (1112-32) by Bernard Baliol; and, like some other Norman strongholds, received it founder's name, which it transmitted to the town that sprang up around, and had survived it. The Castle remained in the hands of the Baliols until 1293, in which year John Baliol (who in 1292 had been raised to the Scottish throne in prefer- no very great strength. [Yorkshire.]

Barnard Castle Stat. (1 m. distant | ence to his rival, Bruce) renounced his fealty to Edw. I. Barnard Castle and all his English estates were then confiscated, and in 1307 it was made over by Edw. I., with other estates of the Baliols, to Guy Beauchamp, Earl of Warwick. From the Beauchamps the Castle passed to the Nevilles, on the marriage of Anne of Warwick to Richard Neville the Kingmaker, whose daughter Anne brought it again to the Crown on her marriage to the Duke of Gloucester, afterwards Richard III. It was still in the hands of the Crown when in 1569 it was held for 11 days by Sir George Bowes against the Earls of Northumberland and Westmoreland, the leaders in the "Rising of the North."

> "Sir George Bowes to his castle fled, To Barnard Castle then fled hee ;-The uttermost walls were eathe [easy] to win, The Erles have won them presentlie.

The uttermost walls were lime and bricke: But though they won them soon anone, Long ere they wan the innermost walles, For they were cut in rock of stone."

In the civil wars the Castle was held by Sir H. Vane, from whom it has descended to the Duke of Cleveland.

The Castle crowns the summit of a precipitous rock, rising about 100 ft. above the river, and with "a projecting shoulder, by means of which the N.W. quarter is protected naturally by a cliff. The remainder of the area was covered by a deep and broad artificial ditch, now mostly filled up, which intervened between the N. and E. sides of the castle and the town. . . . The N. front of both town and castle received a further defence from the Percy beck. a stream which flows into the Tees about 450 yards higher up."—G. T. C. The plan of the castle is oblong, with an area divided into 4 wards. whole area and the several wards were protected, where necessary, by walls and ditches. The outer ward. on the S., was surrounded only by a buttressed and embattled wall, of This ward

could only have been held by a very strong garrison. It represents the "uttermost walls" of the ballad, "easy to win," and "was probably designed, like the Scottish barmkin, to afford a refuge for the townsfolk and their cattle, supposing the town to be taken by an enemy."—G. T. C. A strong ditch, running E. and W., defended the other wards from this The town ward occupied the N.E. quarter of the area. E. curtain are the remains of a rectangular building, projecting inward, and called Brackenbury's Tower. There was a main entrance to the castle on the N. side.-a roundheaded doorway (late Norm.), flanked by a half-round tower. Beyond it (W.) is a square Norm. tower, and thence a curtain of great height and strength runs up to the keep. There was a drawbridge between this town ward and the middle ward, which contained stables and offices, now destroyed, and was also accessible from the first or outer ward. Beyond this middle ward is the inner ward. the most perfect and curious part of the castle, in level about 30 ft. above the rest, commanding the whole area, and rising grandly over the Tees. The keep is circular, about 40 ft. in diameter and 50 ft. high to base of parapet. It has a basement and 3 upper floors, the state-room being on the first floor. This is "one of the finest, though not largest. round towers in England. Its proportions are good, its materials of proper size and rich colour, and its very plainness is indicative of strength."—G. T. C., in the 'Builder' The stone vaultfor June 31, 1873. ing of its first floor, and the staircase winding round the walls to the top, should be noticed. (It is called the "round tower" in a MS. survey of the castle made in 1592, and the name by which it is sometimes known-"Baliol's Tower"—seems to be modern. It is not at all events so named

in 1794, and Hutchinson was a native of Barnard Castle.) The great tower is occupied by a guide who will show the chief points of interest. It should be ascended for the sake of the view, which is magnificent, though scarcely so far extending as Sir Walter has described it in the opening to the 2nd canto of 'Rokeby:—

"What prospects, from his watch-tower high, Gleam gradual on the warder's eye! Far sweeping to the cast, he sees Down his deep woods the course of Tees, And tracks his wanderings by the steam Of summer vapours from the stream. . . .

Nor Tees alone, in dawning bright, Shall rush upon the ravish'd sight; But many a tributary stream, Each from its own dark dell shall gleam: Staindrop, who from her sylvan bowers Salutes proud Raby's battled towers; The rural brook of Egliston; And Balder, named from Odin's son; And Greta, to whose banks ere long We lead the lovers of the song; And silver Lune, from Stanmore wild, And fairy Thorsgill's murmuring child; And last and least, but lovellest still, Romantic Deepdale's slender rill."

At the N.W. angle of this ward was Mortham Tower, now a mere fragment. Between it and the keep were the hall and other apartments, on the first floor, as shown by the two windows of the hall in the curtain, Dec., but insertions in an older wall. Between the hall and the state floor of the keep, above a passage, was an apartment, of which the bay-window, in the curtain, displays in its soffit the "bristly boar" of Rich. III. This is mainly Perp., but some Tudor work has been added.

The area of the castle, although it may have been a fortress in the 10th cent., was inclosed by the Normans; and the remaining walls and wall-towers are their work. The keep and much of the other fragments are Dec.

by which it is sometimes known—
"Baliol's Tower"—seems to be modern. It is not at all events so named
in Hutchinson's 'Durham,' published

The Castle should be seen from the
river, and from the walk close under
its walls, which winds upward from
the bridge. There are some very

beautiful walks through the Flatt | Here the river flows over broad beds Wood, covering the sides of a narrow valley which the Harmire beck de-The Flatt scends to join the Tees. Wood lies between the Castle and the rly. stat., and the walk is continued for some distance up the l. bank of the Seats are placed at intervals. From many points here most striking views are obtained of the Castle, with the river, and the long and picturesque bridge: the whole walk is rich in combinations of river-bank and wood scenery. It should not be neglected by the artist.

Excursions from Barnard Castle may be made to, (1) Streatlam Castle. 4 m., the ancient home of the Bowes family—there are some pictures of interest; and Staindrop and Raby, 7 m. These places are in Durham, and are fully described in the Handbook for that county. (2) Eggleston Abbey and Rokeby, 4 m., returning by Wycliffe and Whorleton Bridge, 7 m. (3) Middleton in Teesdale, 10 m.; and beyond, the High Force and Caldron Snout. (See the next route for this excursion.)

Deepdale, Eggleston Abbey, and Thorsgill are within easy walks of Barnard Castle; but Scott has made all this country as completely his own as that which lies under the "triple height" of Eildon; and the tourist should first make his pilgrimage to Rokeby, as the centre from which the charm has been spread.

(a) Rokeby (Col. Morritt) lies about 4 m. S.E. of Barnard Castle. house is only shown in the absence of the family; but the grounds are always open. Guides are in attendance at the Inn at Greta Bridge (the " Morritt's Arms"),—fair Inn, good rooms.

The road from Barnard Castle to Rokeby crosses the Tees by the "right fair bridge" below Eggleston Abbey, which had 3 arches in Leland's time, but has now only 2. | influx of cockney romancers, artists,

of marble, the "mighty trench of living stone"-

"Where Tees, full many a fathom low, Wears with his rage no common foe; For pebbly bank, nor sand-bed here, Nor clay-mound, checks his fierce career, Condemned to mine a channelled way O'er solid sheets of marble grey." Rokeby, canto il.

The house of Rokeby itself is seen among the trees on the rt, bank of the river, below the bridge. The ruins of Eggleston Abbey stand very picturesquely above the bridge, rt. (For them see post.) You can descend to the bed of the river, where the scene

is striking.

The road skirts Rokeby Park for some distance before reaching Greta Bridge. Here it joins the line of Roman road which ran from Catterick (Cataractonium) to Bowes (Lavatræ, Itin. Anton., It. ii. and v.). Close behind the "Morritt's Arms" is a small Roman camp (not mentioned in the Itinerary), tolerably perfect in spite of the plough.

" the mound Raised by that Legion long renown'd-

'Stern sons of war!' sad Wilfrid sigh'd, Behold the boast of Roman pride! What now of all your toils are known? A grassy trench—a broken stone!" Canto il.

Sir Walter visited Rokeby for the first time in June, 1809, and was then greatly impressed by its scenery. "It is," he writes to George Ellis, "one of the most enviable places I have ever seen, as it unites the richness and luxuriance of English vegetation with the romantic variety of glen, torrent, and copse, which dignifies our northern scenery." December, 1811, he communicated the design of his new romance to his friend Mr. Morritt, who replies, at the end of a long letter full of details, "Should I, in consequence of your celebrity. be obliged to leave Rokeby from the

I shall retreat to Ashestiel or to your new cottage, and thus visit on you the sins of your writings." In the autumn of 1812 Scott revisited Rokeby, and under Mr. Morritt's guidance minutely examined the scenery of the poem. The result was that "admirable, perhaps unique, fidelity of the local descriptions," which gives its greatest "Ť to 'Rokeby.' interest admit." writes Lockhart, "that I never understood or appreciated half the charm of the poem until I had become familiar with its scenery."

After passing through a more open part of the park-

" Where, up the sunny banks, The trees retire in scatter'd ranks. . Save where, advanced before the rest, On knoll or hillock rears his crest, Lonely and huge, the giant oak "-

the visitor is led to a walk on the left bank of the Greta, winding onwards through woods and between steep rocks, to its junction with the Tees. The river is crossed at the "dairy bridge," below Mortham Tower, and the path returns on the rt. bank.

"Rokeby, though nigh, is seen no more-sinking 'mid Greta's thickets deep, A wild and darker course they keep: A stern and lone, yet lovely road, As e'er the foot of minstrel trode!

It seem'd some mountain, rent and riven. A channel for the stream had given, ' So high the cliffs of limestone grey Hung beetling o'er the torrent's way, Yielding along their rugged base . A flinty footpath's niggard space."

" The cliff's Were now all naked, wild, and grey, Now waving all with greenwood spray; Here trees to every crevice clung, And o'er the dell their branches hung; And there, all splinter'd and uneven, The shiver'd rocks ascend to heaven."

" Now from the stream the rocks recede. But leave between no sunny mead.

But here, 'twixt rock and river, grew A dismal grove of sable yew, With whose sad tints were mingled seen The blighted firs sepulchral green."

illustrators, and sentimental tourists, I should be in the visitor's hands (or memory) during his walk, "endlang Greta side." Crossing the dairy bridge (underneath which the "Mortham dobby," a headless lady, "with a piece of white silk trailing behind her." was confined by the parson's Latin, until the arch was injured by floods and the ghost released)-Mortham Tower is reached, on the high rt, bank of the river.

> "Twas a fair scene! The sunbeam lay On battled tower and portal grey: And from the glassy slope he sees The Greta flow to meet the Tees: Where, issuing from her darksome bed, She caught the morning's eastern red, And through the softening vale below Roll'd her bright waves in rosy glow."

Mortham Tower is a square peel or border fortress (perhaps the most southerly of this peculiar type) of the 15th cent., with some outbuildings and additions of Elizabeth's time. The whole has been carefully restored, and is now occupied as a farm-house. The tower should be ascended, although no view of importance is commanded from its summit. On the stairs certain bloodstains are pointed out, said to be those of a lady who was killed in the glen below, and who was afterwards known as the "Mortham dobby." The three rooks of Rokeby appear on an outer wall, and again within. That family had a house on the site of the existing mansion of Rokeby, which was burnt down by the Scots in one of their forays after Bannockburn. The Rokeby of that time had just acquired Mortham by marriage with the heiress of Mansfield; and instead of rebuilding his ancestral manor-house, he built one at Mortham. which was replaced at a later period by that now remaining. "Colonel Rokeby, the last possessor of the old blood, was ruined in the civil wars by his loyalty and unthriftiness, and the estates were bought by the Robinsons, one of whom, the long Sir Thomas The second canto of 'Rokeby' Robinson, so well known and well

quizzed in the time of our graudfathers, after laying out most of the estate on this place, sold the place and the estate together to my father in 1769."—Morritt to Scott. The "Philip of Mortham" of Sir Walter is therefore entirely the poet's creation.

The "junction of the Grets and the Tees" has been drawn by Turner (Richmondshire), as well as described Scott-an honour which the scene well deserves, although, notwithstanding Sir Walter's extreme truthfulness, it will perhaps be felt that both poet and painter have somewhat "exalted" their subject. Yorkshire herself on the Wharfe, or Devonshire on her Dartmoor rivers, can show much and far grander scenery of the same character as that on the Greta. But "carent vate sacro." Even Wordsworth has been unable to fling over the Wharfe the wonderful charm that Scott has added to the natural beauty of Rokeby.

In an open part of the upper walk by which we return to Greta Bridge, on the rt. bank of the river, is a tomb, brought from Eggleston Abbey to its present resting-place, with the bad taste of sixty years ago. It is late Dec., but whose remains it once covered is unknown—possibly those of a Rokeby or a Bowes. It is made to play a part in the poem:—

"South of the gate an arrow flight, Two mighty elms their limbs unite, As if a canopy to spread O'er the lone dwelling of the dead; For their huge boughs in arches bent Above a massive monument, Carved o'er in ancient 6 othic wise With many a scutcheon and device,"

Here is also the effigy of a priest (late E. E.). Some fine points of view are obtained in this walk—the best perhaps at a summer-house which Mason the poet, who greatly delighted in all this scenery, is said to have assisted in arranging.

The house of Rokeby is only

shown in the absence of the family. It contains some good tapestry, one or two pictures of interest (among them a Venus with the Mirror, by Velasquez), and (in the entrance hall) some fragments and inscriptions from the Roman camp at Greta Bridge. Some Roman remains from Burd-Oswald in Cumberland. given by Lord Carlisle to Sir Thomas Robinson, are also preserved here. The old church of Rokeby stood near the back of the house. It was pulled down by Sir Thos. Robinson, who built a new one outside the park.

From Greta Bridge the tourist may drive to Wycliffe (on the Tees), and, crossing Whorlton Bridge, return to Barnard Castle by a road on the l. bank of the river (this will be a round, including the drive to Rokeby, of 11 m.); or he may drive from Wycliffe to Winston, and return by the Darlington road (a round of 16 m.); or he may drive by Brignall to Bowes, and return thence to Barnard Castle (a round of about 18 m.).

(1) Taking this last round, you should drive to Brignall Ch., whence a footpath leads along the bank of the Greta, emerging again at Moorhouses, higher up the stream, where the carriage may be in waiting. The river here runs between steep wooded banks, with quarries of flagstone which have been worked from an ancient period.

"Brignall banks are fresh and fair, And Greta woods are green."

The glen usually known as "Brignall Banks" lies below Scargill, and is the scene of Bertram's interview with Guy Denzil.

"He stands in Scargill wood alone; Nor hears he now a harsher tone Than the hoarse cushat's plaintive cry, Or Greta's sound that murmurs by.

Twas silence all. He laid him down Where purple heath profusely strown, And throatwort with its asure bell, And moss and thyme his cushion swell,

There, spent with toil, he listless eyed The course of Greta's playful tide Beneath her banks, now eddying dun, Now brightly gleaming to the sun.

Then, tired to watch the current's play. He turn'd his weary eyes away To where the bank opposing show'd Its huge square cliffs through shaggy wood. One, prominent above the rest, Rear'd to the sun its pale grey breast; Around its broken summit grew The hazel rude and sable yew A thousand varied lichens dyed Its waste and weather-beaten side: And round its rugged basis lay, By time or thunder rent away Fragments that, from its frontlet torn, Were mantled now by verdant thorn."

The robbers' cave of the poem. quarried in the flagstone, is close to this spot; and it was here that Mr. Morritt observed Scott noting "even the peculiar little wild flowers and herbs" that grew round the spot, in order to give the utmost local truth to his description.

These woods, and the banks of Greta, are the scene of the grotesque poem of the 'Felon Sowe of Rokeby,' first printed by Whitaker in his 'Hist. of Craven.' It dates from the end of the 15th cent. The sow, "the grizeliest beast that ever mote

be." was

- " bred in Rokeby wood: Ther were few that thither yoode [went] That came on lyve away."

"Her walk was endlang Greta side."

Ralph of Rokeby gave her to the friars of Richmond, "full well to gar them fare:" and the poem describes the misadventures of the friars, who in spite of conjurations, for "the sow she wolde no Latin hear," were unable to bring home "the beest of pryce" until two stout champions set forth and killed her.

> "Whan they saw the Felon come, They sang merrilye Te Deum, The Freers everych one."

About the year 1789 two leaden tablets, marked with figures and talismanic signs, were found in a heap of |

nall. An inscription ran partly, " I do make this that . . . all kin of Phillip shall fle Richmondshire and nothing prosper with any of them in Richemondshire." In the other tablet were the names of James Phillip (the father), "Jhon Phillip" and "Arthure Phillip" (sons), all of whom the spell was to bring to "outter beggary." James Phillip of Brignall. who died about 1582, and is known to have had children bearing these Christian names, was an unjust steward of the Lord Scrope of Bolton; and as a contemporary complained, "soo vexithe many poore menne with proces and suits in the lawe that there be utterly undoone, and almost readye to goo about in the cuntrye, or begging, with staff and pouke." It is a singular coincidence that, from the close of the 16th cent., no branch of the family flourished in Richmondshire; and the name, from being once common, is now extinct there.

The drive from "Brignall Banks" to Bowes passes over wild moor, and is somewhat dreary. Bowes itself (see post, Exc. b) is easily reached by rail from Barnard Castle.

(2) A drive of about 3 m. across a comparatively level country brings us from Greta Bridge to Wycliffe on the Tees. The place is of considerable interest, as having possibly given name to the family from which John Wicliffe, the herald of the Reformation, sprang in the 14th cent. (The name is here pronounced Wycliffe; but in the reformer's case the long vowel may have become shortened in the S. of England. Walter makes the first syllable long in 'Rokeby,' where "Oswald Wycliffe" holds Barnard Castle for the Parliament.) Wycliffe was the chief residence of the family; but there is every reason to believe that the reformer was born at Hipswell, near Richmond (see Rte. 25). stones on Gatherley moor above Brig- | the name of the village, a connection

with the great enemy of the "freers" is suggested by the common speech of the district, changed as that has been since 1820. "My father," writes Mr. Raine ('Lives of the Abps. of York,' i. 463), "was born within a mile of the village of Wycliffe, and I have often heard him say that at the beginning of the present century the dialect of the neighbourhood was so identical with the language of the reformer's version of the New Testament, that he would undertake to read any chapter of it to an old person, and it would be understood thoroughly, with the exception perhaps of a word or two.

Wycliffe Church, shrouded in ivy, stands pleasantly on a green hillock above the river. There is some wood about it; and the whole scene, quiet and tranquil, is little in keeping with the stormy times to which it sends The ch., late back the memory Dec., has been partly restored, and at present there are no windows on the N. side, except one in the nave. W. window seems plain E.E. Above it is a bell-turret of later date. Some old stained glass remains in the choir windows. In the chancel, besides some tomb-slabs, with brasses bearing inscriptions for members of the Wycliffe family, is an incised slab with the rude figure of a priest, for "John Forster, Vicar" (instituted to the rectory in 1435). Outside the ch., under the N. wall of the nave, are some carved fragments, one of which, with an interlaced pattern, is of early date; and some tombstones of the northern type, bearing floriated crosses with swords. An older church seems to have been worked up in the walls of that which now exists. In the Parsonage close by is a head of Wycliffe, copied by Sir Antonio More from an earlier portrait. In the rt.hand corner is the inscription "John Wicliffe, died ano 1384." This picture was presented as an "heirloom" to the parsonage by Dr. Zouch, a former vicar. Wycliffe Hall (J. J. H | be especially noticed.

Taplin, Esq.), on the site of the old house of the Wycliffes, is not far from the ch., down the river.

From Wycliffe you may take the shorter route back to Barnard Castle, by crossing Whorlton Bridge, a little distance up the river. By the longer route (by Winston) there are some pleasant views of the valley of the Tees-an undulating, wooded country, but not so picturesque as at and There is a good about Rokeby. view from Winston Bridge. Darlington road, by which we return to Barnard Castle, Raby Castle and woods are seen rt.

(b) Bowes Stat. may be reached by rly. in 1 hr. from the Barnard Castle Stat. The Tees is crossed by a viaduct 732 ft. long, and 142 ft. high in the centre (cost of erection 25,1191.). There is an intermediate station at Lartington, above Lartington Hall (Rev. Thos. Witham), a house for the most part modern, but containing some portions temp. Charles I. There is a large museum, chiefly of minerals and geological specimens. collected by the father of the present proprietor; and some pictures, chiefly good copies. (A 'Holy Family and a small portrait of the rebel Lord Lovat deserve notice.) The house contains a R. C. chapel. Fine views are commanded from Lartington; and very picturesque walks are formed through the long wooded "gills" (Pecknell and Raygill—the latter a name found elsewhere, and perhaps indicating the ancient presence of the roe (raa) in this part of Yorkshire) that here descend to the Tees. Beyond Lartington, Deepdale (see post) crossed by a viaduct - (an ironcolumned bridge, with lattice girders upon a stone foundation; 740 ft. long, 161 ft. high in the centre; cost 20,6871.)—the view from which, down the wooded ravine, should

then passes over high ground to purely through love. March Bowes, the "Lavatree" of the Romans, but far more famous as representing "the delightful village of Dotheboys, near Greta Bridge, in Yorkshire." Bowes, before the publication of 'Nicholas Nickleby,' was the head-quarters of the Yorkshire "cheap school" system. every other house was an "Academy" presided over by some Whackford Squeers, after the fashion which Mr. Dickens did such excellent service by exposing. Such was the effect of the story, that school after school was closed, until Bowes entirely lost its "bad pre-eminence"and not one now remains. than one house here is pointed out as the original Dothebovs Hall: but Mr. Squeers, says the novelist, was "the representative of a class, and not of an individual."

Bowes consists of one gaunt, dreary street of grey stone houses. The ch., mainly early Dec., with transepts, but without aisles, was restored (almost rebuilt) in 1864. The font is Norm., and above the Perp. S. porch is a rude sculpture of the Crucifixion, with St. Mary and St. John. ch. was situated within the ruined walls of the castle in 1325, and then declared to be a "free chapel of the king."

In the churchyard is the grave of the lovers who are commemorated in Mallet's well-known ballad 'Edwin and Emma.' Dr. Dinsdale, author of the 'Teesdale Glossary,' has inserted in his edition of Mallet's 'Ballads and Songs' (1857) all the information he could collect relating to the subject of the poem; and has erected a monument to the memory of the lovers, on which is an extract from the register: "Rodger Wrightson, junr., and Martha Railton, both of Bowes, buried in one grave. He died in a fever, and, upon tolling his passing bell, she cry'd out, 'My heart is broke,' and in a few hours expired.

1714-15."

Bowes Castle (a little S. of the ch.) was built by the Earls of Richmond as a defence (according to a tradition in the family of Bowes) against the men of Westmoreland and Cumberland, who during the Norman period sometimes sided with the Scots. The date of its erection. however, is uncertain. The "Tower of Bowes" (Turris de Arcubus) may perhaps have given name to the family of the great lawyer Adam de Bowes), who married the heiress of Streatlam, although the shield said to have been assigned by Alan the Black, Earl of Richmond, to the founder of the house at Bowes, as castellan here, must certainly be apocryphal. The castle was built within the Roman station-(hence perhaps the saving-

"When Julius Casar was a king. Bowes Castle was a famous thing ")-

but early became ruinous, and was pronounced untenable in the 15th year of Edw. III. The great square tower of the keep alone remains. This is of uncertain date, but may. perhaps, be late Norman. A strong and thick cross wall divides the space within; and the large, roundheaded windows in the second story mark the principal apartments. Without and within the walls are faced with ashlared stone. The entrance seems to have been at the S.W. angle. where the ruin has laid open two passages and a hollow running down from the battlements, perhaps for defence. (Compare a similar squared In both hollow at Scarborough. cases the position (and termination) of this hollow close to the entrance seems to render it probable that it was intended for pouring hot water and lead on besiegers, rather than for the drain of a garderobe.) The mass of ruin is hardly picturesque: some ivy has gathered round it, and grass and harebells flutter from the ledges within. The whole is too shattered to be of great archæ-

ological interest.

The dry most of the castle seems to have been that of the Roman station, which extended S. toward the Greta. Lavatræ—the name of which is preserved in that of the Laver, a stream which here falls into the Greta, if indeed the stream did not give its name to the station-lay on the line of road which ran from Cataractonium (Catterick) by Greta Bridge and Brough (Verterse) to Lugubalia (Carlisle). It was rectangular, measuring about 500 ft. by 400. At the S.E. corner (without the vallum) are some remains of baths; and portions of an aqueduct have been discovered, which brought water to them from Laver pool, 2 m. distant. Many inscriptions have been found here-among them one, mentioned by Camden, in honour of the Emperor Hadrian; and another, recording the repair of a bath for the first Thracian Cohort (perhaps that of which the remains still exist) by Virius Lupus, Legate and Proprætor of Britain in the time of Severus. The bath had been destroyed by fire (" balineum vi ignis exustum"). Camden's time the Hadrian stone formed part of the altar in Bowes Church, and so continued until about the year 1700. Six massive gold rings (with disunited ends) were found at Bowes in 1850. They were probably British.

The Greta flows over a rocky bed below the Roman station; and opposite is Gilmanscar ("rock-begirdled Gilmanscar," Rokeby, cant. ii.)—a fine piece of limestone cliff. Two miles above Bowes is God's-bridge-a natural bridge of limestone, arching the river, and used as the ordinary carriage-road. Below it, for some distance, the stream is usually swallowed up by the hollows so frequent in mountain limestone.

From Bowes a good pedestrian

may follow the course of the river, descending through the picturesque scenery of Brignall and Scargill to Greta Bridge. This will be a walk of between 9 and 10 m.

The Railway runs from Bowes over the wild hills of Stainmore to Tebay Junct. Stat., where it joins the Lancashire and Carlisle line. It leaves Yorkshire at the head of Greta dale. about 6 m. beyond Bowers. Here are two "spitals"-" green oases in a desert of brown moor"-now farms. but serving in old days as restingplaces for travellers over these desolate wilds. The Roman road (the line is marked by one or two square camps) ran somewhat N. of the rly. A little beyond the Yorkshire border, in Westmoreland, is the camp of Rev or Rere Cross - so named from a rough square pillar—the shaft of an ancient cross, still standing within the intrenchment. A weather-worn slab, with traces of a human figure, once inlaid with metal (?), lies near The cross is said (but it is Geoffry of Monmouth who first tells the story) to have served as the memorial of a battle between one Marius and Rodric King of the Picts, A.D. 73, in which Marius was victorious, and gave his name to West-Mare-land, on the borders of which the monument stands. Another tradition, of perhaps equal authority, says that it was chosen as the boundary of England and Scotland in the days of the Conqueror and King Malcolm - hence its name "Rev Cross," the "Cross of the Kings," Its wild, solitary position gives it a certain interest; and it may well have served as a look-out post for such "broken men" as Sir Walter's Allan-a-Dale :-

"And the best of our nobles his bonnet must vail Who at Rerecross on Stainmore meets

Allan-a-Dale."

(c) Walks or shorter excursions

may be made from Barnard Castle to | tion.) Catcastle is a massive edge Deepdale and Eggleston Abbey:— of gritstone rising on the l. bank of

(1) Crossing the bridge below Barnard Castle, and proceeding a short distance up the rt. bank of the Tees, Deepdale is entered near the mouth of its "beck."

— "Last and least, but loveliest still, Romantic Deepdale's slender rill. Who in that dim-wood glen hath stray'd, Yet long'd for Roelin's magic glade? Who, wandering there, hath sought to change Even for that vale so stern and strange,

Even for that vale so stern and strange, Where Cartland's Crags, fantastic rent, Through the green copse like spires are sent?"

The dale is deep and narrow, "with waterfalls over gritstone edges in the upper part of it, and thick woods and abundance of the beautiful silver fir planted among them, and a profusion of wild strawberries and brambles." The most striking part of the "beck" is close above the viaduct, where the stream is contracted between steep cliffs on the W. side, and banks covered with coppice on the other. The cliffs are of millstone grit, and their ledges are hung with tufts of grass, heath, and harebells. Enormous gritstone boulders, among which ash saplings and ferns have rooted themselves. lie in the bed of the stream : and the scene is altogether well worth seeking by the artist. The rush of the trains across the viaduct somewhat breaks the solitude in which Sir Walter's Wilfrid delighted-

"In Deepdale's solitude to lie, Where all is cliff and copse and sky; To climb Catcastle's dizzy peak, Or lone Pendragon's mound to seek."

("Pendragon's mound" is not in Deepdale; it lies near the opening of Baldersgill beyond Cotherstone (see the following route); but it is mentioned in Morritt's long descriptive letter to Sir Walter ('Life of Scott,' vol. iii.), and the name no doubt thus caught the poet's atten-

tion.) Catcastle is a massive edge of gritstone rising on the l. bank of the stream. (It is on the rt. in ascending the dale.) A path turns off toward it a little beyond the viaduct, the stone for which was brought from it. On the summit is a rocky seat overhung by birch and mountain-ash, commanding a fine view of the viaduct, of the dale below, and of the distant country, backed by the Durham hills. The path beyond leads to the open moors above Lartington, but the views from them are

not very picturesque.

In ascending the dale you should search (about halfway between the mouth of Deepdale and the viaduct) for a huge boulder of Shap granite, lying in the bed of the stream. It is marked by a white board, on which are inscribed some doggrel lines. The boulder is one of many "erratic blocks" conveyed by ice during the glacial period—from the Cumberland mountains toward the eastern shores of the island. "Some of these blocks may be traced from their parent mountains of Shap and Carrock across Edendale to Brough, and up the slope towards the summit of Stanmore. On the eastern side of the slope they follow radiating lines toward Romaldkirk, Cotherstone, Barnard Castle, and Brignall, and are scattered over many parts of the vales of Cleveland and York. the sides of Eskdale, the cliffs of Scarborough, Flamborough, Holderness."-Prof. Phillips. Barnard Castle there is another granite boulder in the Harmire beck, not far from a white farm-house, between the stat. and the town.

(2) Eggleston Abbey is 1½ m. from Barnard Castle, on the rt. bank of the Tees. A pleasant field-path leads to the Abbev bridge (crossed on the way to Rokeby. Exc. a). All that is known with certainty of the early history of the house (which was for Premonstratensian canons)

is that, between the years 1195 and 1208, Philip of Poicton, Bp. of Durham, granted "to St. Mary and St. John Baptist, and the canons of Eggleston," with the consent of Matilda, widow of Gilbert de la Leya, the manors of Egleston (in the county of Durham) and Kilvington near Thirsk, which the said Gilbert had held of the Bishop.

The ruins stand very picturesquely on a rising ground above the junction of the Thorsgill beck with the Tees. The domestic buildings have been converted into a mill and farmhouse; but the ch. has been allowed to fall into ruin undisturbed. has consisted of a nave, -aisleless, as usual in Premonstratensian churches -broad transepts with eastern aisles. and chancel. The greater part is E. E. (circ. 1230). In the nave, the triple lancets (each group enclosed by an outer arch) are raised high in the wall on account of the cloister which ran without. At the W. end is a Dec. window, and there are traces of alteration here which are not easily intelligible. The lancet lights of the chancel are richer, with shafts at the angles. In the E. wall is a broad piscina with shelf. and another on the S. wall with a good trefoiled heading. The E. window, with its 5 bare mullions, is a Perp. insertion. The chancel windows have the dog-tooth ornament on the exterior. At the S.E. angle of the nave is a staircase There are tower, of later erection. tomb-slabs with crosses in the nave, and one inscribed for a "Rokeby Bastarde;" but the principal monuments have been removed (some to Rokeby, see Exc. a)

The last scene of Rokeby—in which the execution of the Knight of Rokeby is prevented, Wilfrid dies, and his father is shot by Bernard,—is laid in this ch., of which Sir Walter's description is still accurate:—

"The reverend pile lay wild and waste, Profaned, dishonour'd, and defaced. Through storied lattices no more In soften'd light the sunbsams pour, Gilding the Gothic sculpture rich Of shrine and monument and niche. The civil fury of the time Made sport of sacrilegious crime; For dark Fanaticism rent Altar and screen and ornament; And peasant hands the tombs o'erthrew Of Bowes, of Rokeby, and Fitz-Hugh."

—Canto vi

The glen of Thorsgill, where it widens toward the Tees, below the abbey, is very beautiful. Fine old trees, mostly elms and ashes, are scattered irregularly over the steep broken sides of the glen, up which the artist will find it well worth his while to proceed—at least so far as it retains this character. scenery will recall many a picture of Crewick's, who for some years made the neighbourhood of Barnard Castle his sketching-ground.) In its upper part the glen narrows, and there is a close wood walk through it. soft character of the valley, with its rounded sandy slopes, is in sharp contrast with the limestone cliffs and scars of the lower Greta. name "Thorsgill" is perhaps, like others in this district (see the following route), a trace of Danish or Norwegian colonists, whose settlements extended into this part of Yorkshire, probably from Westmoreland.

"Yet better were its banks assign'd
To spirits of a gentier kind:
For where the thicket groups recede,
And the rathe primrose decks the mead,
The velvet grass seems carpet meet
For the light fairies' lively feet."
Roleby, canto iv.

(A rough road, called the "Stang," climbs the high moors behind Barnard Castle, and descends upon

Muker, in Swaledale (Rte. 25). It commands some wide views, but offers no special attraction to the pedestrian.)

ROUTE 27.

BARNARD CASTLE TO MIDDLETON-IN-TEESDALE, HIGH FORCE.-**MICKLEFELL**

Railway (the Tees Valley branch of the North-Eastern), 5 trains daily in a hour. The tourist should on no account leave the "High Force" unvisited. It is easily reached from Middleton, where there is a tolerable country Inn. Close to the High Force itself there is a better Inn. which is sometimes closed to the public during the shooting season. Inquiries should be made about it at Barnard Castle. High Force Inn is 5 m. from Middleton, beyond which there is no public convey-

The Rly, and high road from Barnard Castle passes Lartington (Rte. 26, Exc. b), and then turns toward the Tees through the village.

Cotherstone Stat. (said to be Cuthbert's town; and to have been one of the places at which the body of the saint rested in its many wanderings), famous for its cheese and Quakers. Cotherstone is colonised almost entirely by the Society of Friends; and

made on all the surrounding farms. S. of Cotherstone, the broad-topped peak of Goldeborough, with its gritstone edges, is conspicuous. Balder here joins the Tees; and on a mound above the junction are some fragments of Cotherstone Castle -- a keep-tower of the Fitz-Hughswhich seems to be the "Pendragon's lonely mound " of Rokeby. " We rode next, if you remember, to Cotherstone, an ancient village of the Fitz-Hughs on the Tees, whence I showed you a rock rising over the crown of the wood, still called Pendragon Castle."—Morritt to Scott. Ralderdale somewhat resembles Deepdale, but is scarcely so picturesque. is thickly wooded. "Balder Grange" stands on its rt. bank; and a little beyond, nearer the Tees, is Woden Croft, now a farm-house, but long a school of some reputation, at which Richard Cobden received part of his education. These names, like Thorsgill, are relics of the Northmen, who

"Gave their gods the land they won. Then, Balder! one bleak garth was thine, And one sweet brooklet's silver line; And Woden's croft did title gain From the stern Father of the Slain." —*Rokeby*, canto iv.

Nearly opposite Woden's Croft is the base of the "plague Cross," at which, during the infection, a market was held for Barnard Castle.

Romaldkirk Station (Inn. Crown, where a pedestrian may sleep), the ancient centre of population for all the upper part of Teesdale. The parish extends over all the wild moorland that forms the N.W. of Yorkshire and down the Tees to Startforth near Barnard Castle. The Church is apparently the only one in England dedicated to St. Romald the hermit, of whom little is known. It is large and fine. E. E. and late Dec.; and contains. the "Cotherstone cheese," some of in the N. transept, the effigy of Sir which is hardly inferior to Stilton, is | Hugh Fitz-Henry (father of the first Lord Fitz-Hugh), who died at Berwick-on-Tees, 12th March, and was buried at Romaldkirk 22nd of the same month, 1304, by John prior of Guisborough.

Beyond Romaldkirk the dale widens, and fells rise on either side. On the Durham side of the Tees is Ediston Hall (- Hutchison, Esq.). After passing the village of

Mickleton Stat. the Lune is crossed a little above its junction with the (Lunedale, through which the stream descends from the slopes of Micklefell, is not very picturesque: broad and undulated in its upper part, and with no wood but some fir plantations at Wemmergill. A good road runs up it, and crosses the hill to Brough. Then, crossing the Tees, we enter

Middleton-in-Teesdale (Stat., and the terminus of the rly.), standing almost entirely in the county of Durham. (Inns: Cross Keys, best; Rose and Crown; King's Head.) Middleton is the capital of the mining district, which extends up the dale on either side of the river. The ch. contains late Norm., E. E., and early Dec. portions, but is of no great interest. The principal mining company has built large and picturesque schools here for the use of the children of their miners. The most important lead-mines in this neighbourhood are on the Durham side. are said to be more extensive than those in Swaledale or near Pateley Bridge. Strings of "jagger" ponies, as they are called, convey the lead from the mines to Middleton and the rlys. Each pony carries a weight of 200 lbs., strung on a kind of pack-There is a large ironstone bed in Upper Teesdale, the working of which is in progress, and will not improve the picturesque character of the district.

open, the tourist will do well to proceed thither. He will find it the most convenient station not only for the High Force itself but for Caldron Snout, and for the ascent of Micklefell. A conveyance may, however, be hired at Middleton; and by starting early, the whole of this expedition may be accomplished from that place in a long summer's day. If ponies are desired for the ascent of Micklefell, the landlord at High Force or at Landon Inn (see post) should be written to beforehand.)

The drive from Middleton to High Force (on the Durham side) is plea-This upper part of the dale is pastoral, with much wood near Middleton, which becomes rarer as we ascend: the steep sides of Harter Fell and Holwick Fell rise beyond the meadows, l. of the road. The Tees. in this part of its course, eats away the low banks, and has worn more than one new channel for itself. One or two flat holms now on the Yorkshire side are in the county of Durham, marking the changes of the river. Near the hamlet of Newbiggin a road descends to Winch Bridge, over the Tees, a small suspension-bridge, built originally for the use of miners, and said to be one of the earliest of its sort in England. It is thrown across a narrow chasm about 60 ft. deep, above which the river descends in small waterfalls, making a picturesque scene. Primula farinosa is to be found here in its season. (Holwick Scars may be visited from herea range of "smoke-grev basaltic crags," crowned by the wide grassy plateau of the fell. The parsley fern grows in great luxuriance among them; and the adjoining hill-sides are covered with juniper.)

The High Force Inn stands by the roadside immediately opposite the waterfall, seen in the distance finely backed by steep fells, and at the (If the Inn at the High Force be end of a long rocky ravine, which has been planted with spruce and civilisation in the solitude) stands at silver firs. Walks have been cut through the wood, rendering the approach to the fall easy, and so well managed, that after the first distant view up the ravine the "force" is hardly seen until you are close to it. The scene is wonderfully grand. The Tees descends 69 ft. "over greenstone resting on shale and limestone, the shale prismatized by the heat of the trap, but the limestone not bleached as that above the trap is." A single spire of rock rises in the midst of the precipice over which the force flings itself, dividing the great mass of water when the river is at all swollen. The lower layers of the rock are perfectly blackened, and miniature caverns are worn in the base of the cliff, rt. The water falls into a deep black pool, whitened with foam; and the l. bank of the river, strewed for some way with broken rock, opens into a folding of the hill, down which a ruin of stony fragments has fallen. Green tufts of fern, grasses, and heath wave from the ledges; and on the rt. side of the cliff, immediately above the fall, is a cluster of yew-trees. The water, stained with moss, descends in dark brown masses between the foam. The colouring of the whole scene is exquisite; and it may safely be said that no waterfall in the north of England (and few even in Scotland) is grander or more impressive than the High Force. Many hours may well be spent in and about the ravine.

Ponies may be hired at the High Force Inn for proceeding to Caldron Snout and ascending Micklefell. About 3 m. farther on the road is Landon Inn, a small wayside house, the landlord of which will procure ponies if written to beforehand. (The ascent is nearer from Landon Inn. to which you can drive from High Force.) This little Inn (before reaching which a small modern E. E. ch. is

the junction of Yorkshire, Westmoreland and Durham. A good pedestrian may walk from it to the waterfall of Caldron Snout, thence ascend Micklefell, and return to the inn in 6 or 7 hrs., but the time will be shortened by hiring a pony. reach the Caldron Snout from Landon Inn you should make for the farmhouse of Widdyfell, just at the point where the Tees turns sharply round Cronkley Scars, a very fine mass of rock from 100 to 200 ft. high, forming the "N.E. corner of Yorkshire. About 2 m. of very rough no-road will then bring you to Caldron Snout. The walk, whether over the hill or following the river, is difficult, since there is much mossy ground, and on the hill deep heather, with peat haggs. "It is a dreigh (lonely) road over the fells," say the natives; but the lover of wild scenery, almost Norwegian in its savage loneliness, will not regret his scramble.

On Cronkley Fell, above Cronkley Scars, "the curious sugar limestone occurs. There are several sorts. from the large, crystal-like barleysugar to the finest brown and white. It appears a stone, cropping out of the short, dry grass, but crumbles away to fine crystalline particles on pressure. Geologists explain that this condition has been caused by the pushing upward heated whinstone into close contact with the lime-stone."—W. S. Banks.

Cronkley Scars exhibit the greatest development of a mass of basaltic rock, known locally as "whin-sill," which extends from near Brough in Westmoreland into the upper parts of Teesdale, Weardale, and Tynedale, and is continued thence with some interruptions as far as the Northumbrian coast near Alnwick. At Cronkley Scars it is from 200 to 300 ft. thick. This neighbourhood is famous for its passed at Forest Kirk, marking a botanical rarities, since, in common

several montane plants, "which, as growing there, are separated more or less conspicuously from the other localities in which they occur. Polygala austriaca, a species diffused upon the Continent from Scandinavia southward to Italy and Transylvania, is not known elsewhere in Britain. (It is found near the White Force, a waterfall on the Merrigall beck. falling into the Tees a little above Cronkley Scars.) "Potentilla fruticosa and Gentiana verna, both of which are abundant in Teesdale, and both widely diffused upon the Continent, grow in the W. of Ireland, and sparingly in the Lake district, but are not known elsewhere in Britain. Bartsia Alpina 16 (found at Cronkley Scars, and near the High Force) "grows in Craven and the Lake districts and from thence leaps to the East Highlands. Elura caricina" (found at Cronkley Scars) " is like the Bartsia, except that it is not known in Craven. Myosotis alpestris," (found at the eastern extremity of the Micklefell ridge) "and Tofieldia palustris" (on the fell between the White Force and Caldron Snout) "from Teesdale leap to Perthshire; and Hieracium iricum" (Cronkley Scars and neighbourhood) "and Carex capillaris" (Cronkley Scars and neighbourhood) "are also not known elsewhere in England, and leap from Teesdale to the hills of Dumfriesshire."-J. G. Baker: All these plants appear to be part of a Scandinavian flora, "communicated to Britain before the glacial period, and now preserved on certain elevated tracts, which, during that period, stood above the water."-Phillips.

A range of high basaltic scars called Fulcon Clints borders the Tees for some distance on its 1, bank, between Cronkley and Caldron Snout.

Here the river—

with all Upper Teesdale, it furnishes | descends in broken rapids through a chaos of black basaltic rocks, which jut out in patches between the heather above the fall. A golden lichen colours them finely; and the whole scene, totally different in its features from the High Force, is wild and savage. The fall (or long rapid) is 200 ft. high; and "nowhere else in England have we so deep a fall upon so large a stream."—J. G. B.The name "snout" probably refers to the long narrow channel through which the stream here suddenly pours, after sleeping, as it does, for a considerable distance above it in a long lake-like expansion called the "Weil" (well-so the "wells" often mentioned in old ballads — deep. smooth eddies, the favourite haunts of mermaids :-

> "O promise me now, Clerk Colvill, Or it will cost ye muckle strife, Ride never by the wells of Slane, If ye wad live and brook your life." Clerk Colvill.

A narrow plank bridge (1489 ft. above the sea) crosses the river over the waterfall. A little below Caldron Snout the *Maze beck* joins the Tees The Tees itself rises on the slope of Crossfell in Cumberland, and for 5 m. forms the boundary between Westmoreland and Durham. From Caldron Snout it divides Yorkshire and Durham. The Maze beck descends from Dufton Fell in Westmoreland, and divides, in the lower part of its course, Westmoreland and Yorkshire.

There is a small sheep farm at Birkdals (on the Westmoreland side), where a guide may perhaps be procured either to High Cup Nick (a curious boat-shaped chasm in the hills about 3 m. distant in Westmoreland; the view is superb; see the Handbook of Westmoreland) or to the top of Micklefell. This is the great mass of moorland between the Tees and the Lune, having at its summit a long ridge of limestone, with patches of millstone grit. The western end

[&]quot;Where Tees in tumult leaves his source, Thundering o'er Caldron and High Force" Rokeby—

of the ridge is 2580 ft. above the sea, and is the highest ground in Yorkshire. It was one of the points for the Ordnance Survey, and the sappers have left their pile of stones on the summit. The form of the hill-steep toward the S.E., and gradually rising from the N.W.—renders it easily climbed from Caldron Snout, and a pony can well get to the top. view on a clear day will amply repay the labour of ascent. "On the N.W. there is a sudden fall in the direction of Maze Beck, and across a broad hollow may be seen a mass of hills in which the three peaks of Crossfell, Dunfell, and Scoredale Head, are conspicuous, and the head of High Cup Nick and the far-off peaks of the Lake country looming dimly on the edge of the horizon." Toward the Toward the N. you look down on Teesdale. Eastward, far over Barnard Castle and Richmond to the distant Hambleton hills. " And on the S. over Lunedale and Balderdale, and the Stainmore depression, are the innumerable undulated peaks which cluster round the upper part of Swaledale and Yoredale, and beyond them the more abrupt outlines of Whernside and Ingleborough, and Pennyghent."-J. G. Baker.

(An adventurous pedestrian may follow Mr. White's ('A Month in Yorkshire,' ch. xviii.) example, and descend from Micklefell upon the road leading across from Mickleton to Brough. The walk will be a long one, however, and should on no account be attempted unless the weather is entirely favourable. A mist among these trackless hills may bring unpleasant consequences, to say the least.)

ROUTE 28.

LONDON TO LEEDS: (1) BY DON-CASTER AND WAKEFIELD; (2) IN PONTEFRACT AND WAKEFIELD; (8) BY PONTEFRACT AND CASTLEFORD.

1. By Doncaster and Wakefield.—
This is the main line of the Great
Northern Rly. By it 6 through
trains run daily from London (King's
Cross Stat.) to Leeds. Ordinary
trains perform the distance in about
5 hrs. 20 min.; the Express in about
4 hrs. This (or the N. Midland line
—see Rtes. 1 A and 41) is the best
route for those who wish to reach
Leeds with as little delay as possible.
For the line from London to

Doncaster Junct. Stat., see Rte. 1. From Doncaster the rly. crosses a pleasant, rather picturesque and wooded country, by Adwick S. Emsall, Hemsworth, and Nostell Stats.. to Wakefield. For Adwick-le-Street (where is a rather interesting ch.) see Rte. 1, as well as for Hampole, which the rly. skirts, beyond it. At South Emsall there is nothing.

Hemsworth Stat. Here the ch. was rebuilt. 1867. Robert Holgate, Abp. of York (1544—deprived on the accession of Mary), founded here a

grammar-school and a hospital, both of which have been rebuilt—the grammar-school (near the ch.) about 1865, the new hospital, 1 m. S.W., in 1860. The latter is Elizabethan, with a chapel in the centre, 12 houses on one side and 10 on the other. The 20 immates receive each 40l. a year, besides a house. The master (with a separate house) has 600l. The old hospital buildings, erected in 1770, remain near the church.

Nostell Stat. The Priory (Ch. Winn, Esq.) contains a fine collection of pictures, and the ch. is interesting, see Rte. 38.

Sandal Stat. (Rtc. 38). The train then speedily reaches Watefield Junct. Stat., see Rtc. 38; as well as for the line thence to Leeds.

2. By Pontefract and Wakefield.—This and the following line, from Pontefract by Castleford, are by no means the most direct route from London to Leeds. They pass, however, places of great interest; and the tourist who is not pressed for time may very well take either of them, stopping if he chooses at Pontefract, where there is good hotel accommodation. For the line from London to Knottingley Junction, where the main line is left, see Rtes. 1 and 2.

At Knottingley the branch rly. turns W. Just before reaching the Pontefract Stat. it passes, rt., the unpicturesque ruins of "New Hall," an Elizabethan house, once the residence of Talbots and Pierrepoints. The Talbot supporters, 2 "talbots," may be seen over an arch.

Pontefract, 10 min. walk from stat., often, but not on the spot, called Ponfret—(Inns: Green Dragon; Elephant; Red Lion: Pop. of the town in 1881, 8798. Rly. Stations: 1. at the English lord, Ailric.

[Yorkshire.]

Pontefract (Monkhill); 2. at Tanshelf, for Lancashire and Yorkshire Rlv. from Wakefield to Goole; 3. at Baghill, on rly. from Swinton to Knottingley. The rocky height covered with trees. which rises I. near the stat., is the site of the Castle)—is a place of little importance at present, but one which is closely associated with some of the greatest events in English history. "I love Pomfret," wrote Swift; It is in all our histories." " why? The town lies a little to the rt. of the Great North Road, which follows the line of the Roman " Watling Street," and about 3 m. N.W. crosses the Aire at Castleford—the Legiolium of the 5th and 8th Antonine Itinera. From the 11th to the 17th Pontefract Castle was the cent. great stronghold of S. Yorkshire. commanding the passes of the Aire nearly as effectually as the Roman station had done, close on the river; whilst its position gave it infinitely greater strength as a mediæval fortress. It was partly owing to the importance of its site, and partly to the power of the great barons who at different times were lords of the Honour, that Pontefract Castle plays so conspicuous a part "in all our histories."

The remains of the Castle, and of All Saints Church below it, are the sole points of interest in Pontefract. and the history of the place gathers entirely about the Castle. The old name of the place, as appears from Norman charters, was Kirkby, and it was included in the manor of Tateshall or Tanshelf, which before the Conquest belonged to the King. and was, no doubt, the "Taddenes scylf," where, in 947, King Eadred received the fealty of Abp. Wulfstan and the Northumbrian "Witan." The Witan probably met on the site of the later castle, in part an artificial hill, on which, at the time of the Conquest, stood the house of In the

York for his final conquest of the North, and was delayed for 3 weeks at Castleford, on the Aire, the river being then impassable by boats or by fording (Freeman, iv. p. 285). At this time he probably "found the means of inspecting so strong a place as the English house at Kirkby. and when he granted the district to Ilbert de Lacy it may reasonably be supposed that he followed his usual practice of directing a castle to be built."—G. T. C. "Pontefract" then acquired its present namewhether from a broken bridge over the Aire at Castleford, as Mr. Freeman suggests, the bridge having been broken to prevent the Conqueror's passage - from a wooden bridge which is said to have given way as St. William of York passed over it. when the multitudes who thronged it were saved by his prayers (but this is only a repetition of the York story, see Rte. 1)—or from a "Poumfreite" in Normandy, is un-The castle at any rate was certain. founded by Ilbert de Lacy, to whom William I. had made large grants of land in this part of Yorkshire (about 150 manors, chiefly in the W. Riding -they fill 7 pages of Domesday book); and the son of Ilbert is called "Robert of Pontefract" by Ordericus Vitalis (l. xi. c. 1) circ. 1102—the first instance of the occurrence of the (It should be remarked that name. Ailric, the English lord, held his lands, but much reduced, under the new Norman possessor,—as did his son and grandson, Sweine and Adam, the former of whom gave a church to the monks of St. John's at Pontefract, and the latter founded Bretton Priory (Rte. 40). The Yorkshire lands were erected into an Honour. of which Pontefract became the chief seat.) With one or two intermissions, when the Laceys were tem-

winter of 1069. William advanced to line in 1310: and the castle and honour were then transferred to the nephew of Edw. I., Thomas Plantagenet, Earl of Lancaster, who had married Alicia, heiress of Henry de Lacy. On the death of this great earl, his estates were confiscated; but they were afterwards restored to his heirs by a special Act of Parliament, and passed to John of Gaunt. created Duke of Lancaster. On the duke's death, Pontefract would have descended to his son, Henry of Bolingbroke: but Richard II. seized the castle and estates, and Henry only regained them as Henry IV. England, when the deposed Richard was sent here as a prisoner. From that time the castle remained in the hands of the Crown, until, after undergoing three sieges during the Civil War, it was finally dismantled and "slighted" by order of the Parliament.

No important historical event occurred at Pontefract until the beheading of Thomas of Lancaster here in This "mighty lord," the 1322. grandson of Hen. III., and Earl at once of Lancaster, Lincoln, Leicester, Salisbury, and Derby, supported a magnificent household at Pontefract. As leader of the confederate barons against Edw. II. he commanded the forces which besieged Scarborough Castle, in which Gaveston had taken refuge; and on its surrender (May 17, 1312) conveyed him to Warwick. Gaveston was beheaded (June 19) on Blacklow Hill near Warwick, in the presence of Lancaster, and on ground within his jurisdiction. This was the offence which the king never But there was an apparent forgave. reconciliation before, in 1321, Lancaster joined the Earl of Hereford in that attack on the Spencers, the new favourites of the king, which led to the battle of Boroughbridge (March 16, 1322 : see Rte. 19). At Boroughporarily banished from the realm, bridge, Lancaster was taken, and that great family held Pontefract was carried down the Ouse to York, until it became extinct in the male and thence to his castle of PonteEdw. II. and the barons of the royal army, and was condemned to suffer as a traitor—the more barbarous portions of the sentence being remitted on account of his noble birth. He was led at once (June 19) to execution, on a grey pony without a bridle; and the crowd, as he passed along, flung mud at him, with cries of "King Arthur"—the name which he was said to have assumed in correspondence with the Scots. of heaven!" he exclaimed, "grant me mercy, for the king of earth hath forsaken me." When they stopped on a hill outside the town, the Earl knelt, facing the east; but he was ordered to turn northward, toward his friends the Scots, and in that position he was beheaded.

Lancaster, like Simon de Montfort, had been the great supporter of the popular cause against the exactions of the Crown and its officers; and, as in the case of Simon, the reverence for him did not cease with his life. He was buried in the Cluniac Priory at Pontefract, on the rt. of the high Miracles were wrought at his tomb: "and for resort of people to the Monte, where Thomas was behedded. Bauldok the Chauncelar caused xiiii Gascovnes, welle armid, to watche the hille a certen tyme."— (Leland, Collect. ii. 466.) The king, it is also said, "lete close the church dores of Pountfret of the Prioree, for no man shall come therein to the hody for to offeren." In spite of these precautions the miracles, it was averred, continued; and within 5 weeks after the accession of Edw. III., a mission was sent to the Pope imploring the usual investigation preparatory to canonization, and alms were collected throughout England for building a chapel on the hill of the beheading. Other embassies were sent to Rome at different times, and in 1390 (13th of Rich. II.) Walsingham records the actual canonization

of "Sanctus Thomas de Lancastria."

Here he was brought before Land the barons of the royal and was condemned to suffer the more barbarous porthe sentence being remitted punt of his noble birth. He canonization of this great earl calls for further examination.

The hill on which the Earl was beheaded is the high ground above the castle, and is still known as St. Thomas's Hill; no traces remain of a chapel there. The Cluniac Priory has also disappeared: but in 1828, in the "Priory Field," not far from St. Thomasis Hill, a stone coffin was found, and conveyed to the grounds of Frystone Hall, the residence of Lord Houghton. It has been suggested that the coffin may have been that of the Earl, removed from the priory at the Reformation. It was opened in 1863, and the bones which it contains were seen to be of unusually large proportions.

The death of Rich. II. is the next great event that occurred here. the Parliament of October, 1399, it was decreed that the deposed king should be perpetually imprisoned in a place "unfrequented by any concourse of people." He was first sent to Leeds, then to Pickering Castle (like Pontefract, one of the hereditary possessions of the Dukes of Lancaster), and then to Knaresborough; but was soon removed thence to Pontrefact. At the end of January, 1399-1400, his death was The famous scene in announced. Shakespeare ('Richard II.,' act v. sc. 5) has given such a reality to the assertion that the king was murdered by the hand of Sir Piers of Exton-

"That hand shall burn in never-quenching fire

That staggers thus my person. Exton, thy fleroe hand Hath with the king's blood stain'd the

king's own laud"-

that it is hard to disbelieve it; yet Abp. Scrope, who was near at hand, and had probably good means of ascertaining the truth, declared that, after lingering 15 days, Richard died of starvation—"the basest death any one in England had ever undergone." Strate is the version adopted by Grav—

"Close by the regal chair
Fell Thirst and Famine scowl
A baleful smile upon their baffled guest."

His body was brought to London and publicly exhibited. There can be little doubt that he really died at Pontefract, although the story of his escape into Scotland has found supporters (see Tytler, 'Hist. of Scotland,' vol. ii.). The Exton story first appears in the 'Chronicque de la Traison et Mort de Richart,' edited by Benj. Williams for the Eng. Hist. Soc. in 1846.

Henry IV. was often at Pontefract after Richard's death; and it was here that Abp. Scrope, having joined the insurrection of the Percys, was brought, after he had been induced by a stratagem to disband his forces. before Henry himself, who carried him in his train to his own palace at Bishopthorpe, where he was tried and beheaded. (See Rte. 1.) After the battle of Agincourt, the Dukes of Bourbon and of Orleans, who were there taken prisoners, were sent to Pontefract Castle, where they remained for many years. Here too the young King of Scotland, James I., who had been captured off Flamborough in 1405 (see Flam. Head, Rte. 13), was for some time their After the battle of companion. Wakefield, the Earl of Salisbury, Sir Ralph Stanley, and many other Yorkist prisoners were sent by Queen Margaret's orders to Pontefract, beheaded there, and their heads sent to be fixed on the "bars" of York. 1483, Earl Rivers, Sir Richard Gray, and Sir Thomas Vaughan "lay shorter by the head " at Pontefract, in order to clear the way for the accession of Richard III .-

" O Pomfret, Pomfret! O thou bloody prison, Fatal and ominous to noble peers! Within the guilty closure of thy walls Richard the Second here was back'd to death;

And for more slander to thy dismal seat
We give to thee our guiltless blood to
drink,"—Rich, III, act iii, sc. 3.

(Rivers, who was one of the most accomplished men of his age, and the first English patron of Caxton. composed, according to Rouse, "unum balet in Anglicis" during his con-

composed, according to Rouse, "unum balet in Anglicis" during his confinement here.)

During the Pilgrimage of Grace (1536), Pontefract was besieged by the insurgents under Aske, and the

(1536), Pontefract was besieged by the insurgents under Aske, and the castle was surrendered to them by Lord Darcy and the Abp. of York. It sustained 3 memorable sieges during the civil war. In the December following the battle of Marston Moor (1644), Sir Thomas Fairfax endeavoured to reduce it: and after an incessant cannonade for 3 days. one of its 7 towers was knocked down, Jan. 19th, 1645, and in its fall carried away part of the wall. The breach, however, was stoutly defended by Colonel Lowther, the governor, so that the enemy, despairing of being able to enter by it, had The besieged recourse to mines. countermined, sinking more 100 shafts within the walls. at last, the garrison had been extremely diminished by slaughter, and weakened by dearth of provisions, the place was relieved by Sir Marmaduke Langdale, assisted by a sortic of the garrison; and the Parliamentarians retired in disorder. stronghold was not long allowed to remain unmolested, for in March of the same year (1645) it was again beset by the republican army, and after a siege of 3 months was compelled to surrender, though upon honourable terms

Pomfret Castle was regained for King Charles by the stratagem of Colonel Morris, a man of doubtful principle, who had served both sides, but at the time pretending to be a Roundhead had gained the confidence of the governor. In June, 1648, I having heard that Colonel Cotterel expected a supply of bedding, furniture, and provisions, Morris loaded a number of waggons with these articles, and drove them into the castle, escorted by himself and nine other officers disguised as peasants, but having arms concealed beneath their clothes. The drawbridge was at once lowered to admit them and their cargo. A pretext was found to send some of the soldiers into the town with money to buy ale; the rest of the guard was then mastered, possession was obtained of the gate. and the main body of the confederates posted outside was admitted. governor was secured after a desperate resistance; the garrison, who did not exceed 100, were overpowered, and the capture of the fortress secured by the arrival of a reinforcement from the Royal army, swelling the garrison to 30 horse and 500 foot. Oct. 1648, they were again enclosed by a besieging army, which obtained little success until the arrival of Cromwell himself: but he. after a month, deputed the command to General Lambert, having first taken those energetic measures which led to its ultimate capture, and having addressed the following forcible letter to the Council in London:— " My Lords,-The castle hath been

victualled with 220 or 240 fat cattle within these three weeks; and they have also gotten in, as I am credibly informed, salt enough for them and more: so that I apprehend they are victualled for a twelvemonth. men within are resolved to endure to the utmost extremity, expecting no mercy, as indeed they deserve none. The place is very well known to be one of the strongest inland garrisons in the kingdom, well watered, situated upon a rock in every part of it, and therefore difficult to mine. The walls very thick and high, with strong towers, and, if battered, very difficult his son and successor, Charles II,

steepness of the graft. The county is exceedingly impoverished, not able to bear free-quarter, nor well able to furnish provisions, if we had moneys. The work is like to be long, if materials be not furnished answerable. therefore think it my duty to represent unto you as followeth, viz.;-That moneys be provided for 3 complete regiments of foot and 2 of horse; and, indeed, that money be provided for all contingencies which are in view, too many to enumerate. 500 barrels of powder and 6 good battering-guns, with 300 shot to each gun, be speedily sent down to Hull; we desire none may be sent less than demy-cannons. We desire also, some match and bullet; and, if it may be, we should be glad that 2 or 3 of the biggest mortar-pieces, with shells, may likewise be sent. And, altho the desires of such proportions may seem costly, yet I hope you will judge it good thrift; especially if you consider that this place hath cost the kingdom some hundred thousands of pounds already, and, for aught I know, it may cost you one more, if it be trifled withal; besides the dishonour of it, and what other danger may be emergent by its being in such hands."—Carlyle's 'Cromwell,' i. p. 330. "Had these 'propositions' been acted upon in full," says Carlyle, "that business might have ended sooner."

In the interval since its capture the Royal cause had grown desperate; no army remained to the king to reinforce the garrison, and, except Pontefract, the only strong place in England which held out was Scarborough. Notwithstanding all this, and the vigour and skill with which Lambert pressed the siege, the garrison resisted bravely all attacks. They even heard undismayed of the death of Charles on the scaffold; and while the rest of the country was mute, they were the first to proclaim of access, by reason of the depth and making at the same time a vigorous

sally. It was not until the end of six | months, when their numbers were reduced, by the losses they had suffered, from 500 to 100 men, that they capitulated. Six persons were excepted from mercy, including Morris and 4 of his confederates in the seizure of the castle. Of these, 2, Morris and Blackburn, cut their way through the enemy in a sortie. They were taken, however, a few days after, near the coast of Lancashire, while seeking for a vessel to escape beyond sea, and tried and exe-The remaining 4 cuted at York. concealed themselves, on the surrender of the castle, among its ruins, and two of them lived to see the Restoration.

The present dilapidated state of The Caelle was owing to the thorough demolition ordered by the Parliament immediately after its surrender: but the effects of the artillery on its walls during 3 destructive sieges, had prepared the way for this. Evelyn records in his journey through Pomfret, 1654, that "the castle was now demolishing by the rebels; it stands on a mount, and makes a goodly show at a distance." It can hardly be said to do so now, though the scene of so many important events cannot be visited without unusual interest.

Architecturally, the remains of Pontefract Castle are of little value, but for the military antiquary few places have more attraction. site, on an elevated rock, commanding all the country about it, is precisely such as best suited a great Norman stronghold, but, as a natural "strength," it was, as we have seen, appropriated by the Saxons. There, Ailric, or his ancestors, threw up a mound at the S.E. angle, commanding the natural entrance just E. of On this the Normans built a small shell keep; and the summit of the rock, about 7 acres, was enclosed by a curtain-wall, with towers at equal distances. A deep fosse en- a similar kind exist in Pontefract.

circled the whole rock. the original Norman arrangement; and the plan was retained in all the later constructions. There are three wards, N., S., and middle. is a curious rock staircase in the middle ward, in front of what is called the "King's seat." This is mainly Norman; but the present was not the original entrance—that was by a turnpike stair on the rt. The 2 great Round Towers at the base of the keep deserve special attention. The Normans first scarped the base, to the south, into the form of round towers, and faced them with masonry, since renewed; that, although they look like towers in their lower portion, they are really solid bastions. The keep is reached by a long flight of steps, and cells were cut in the rock, which have been altered, but still show traces of Norman work. The chapel at the N.E. angle retains (on the W. side, below the keep) some portions of Norman masonry. From the lesser tower of the keep a narrow staircase leads down to a sallyport; and about halfway down, other stairs branch off, leading on one side to (possibly) a well, and on the other to a dungeon barely 6 ft. square.

The most unusual construction here, however, is a long subterranean passage on the N. side of the castle, which "descends for several feet by steps in a direct line: at the bottom it terminates in three or four small chambers, hollowed out of the solid rock. Some portion of it is arched over with ashlars, and in one part the peculiar heading, which may be termed Edwardian shouldering, is observable. Looking at these and some minor features in connection with them, the whole work seems to have been done in the reign of Edward II., and most likely by Thomas Earl of Lancaster. subterranean passages are sufficiently curious in themselves; 2 others of Chapel were cleared out and 7 bodies found, probably of those who fell in

the siege.

Close to the new Dispensary in Southgate is a winding staircase, below the street, cut with great care; at the bottom of 90 steps it ends with a Close by is a subterranean chantry for a hermit priest; the altar still remains; it scarcely seems large enough for the anchorite to have made it his constant residence, and therefore he must have frequently descended into this crypt to perform his devotions.

A room in the Red Tower is pointed out as that in which Rich. II. was confined; and in the socalled Swillington Tower, Thomas of Lancaster is said to have been immured before his death.

The area of the castle, once planted with liquorice - literally fulfilling the old line—"Nunc glycerhiza crescit ubi castellum fuit," has been taken by the Corporation for public Pleasure Grounds.

Below the castle is All Saint's Church-the old church of Pontefract-which was ruined during the siege of the castle by Cromwell. (The S. transept alone was preserved as a burial-place.) There are scanty remains of nave, choir, and aisles; and in 1837 the central tower and transepts were repaired, and fitted for divine worship. A considerable sum was expended in 1866 in "restoring" this part of the ch., and in strengthening and supporting the ruins.) The ch. seems to have been Early Dec. with Perp. insertions; but the stone of the ruined portions has crumbled so far that they possess little interest. tower (Perp.) is square and lofty, with an octagonal turret rising from it. It contains a double geometrical staircase worth notice.

In 1882 the foundations of the with square tower, upper part octagonal and surmounted by a crown of flying buttresses bearing a vase, retains many mediæval features.

> The town of Pontefract is clean, with broad streets, and a very fine market, the front of which was begun in 1859. On it the bull's head, the device of the town, is conspicuous; and over the entrance is the ancient shield of the corporation, the castle gate, with the letters P.P.

> A large agricultural market, corn and cattle, is held on Saturday.

Pontefract is famous for its Liquorice, which is grown largely in the neighbourhood. Liquorice (the word is formed from the Greek "glycyrrhiza" = sweet root), a native of southern Europe and of the Levant, was first cultivated in England in the reign of Elizabeth (Stowe), Pontefract speedily became the headquarters of the manufacture. plant, very graceful, with feathery leaves, is planted in ridges, and does not come to perfection until the fourth year. The sandy soil suits it, and the fibrous roots are sometimes 10 or 12 ft. deep. These are dug in autumn, and pounded in the following winter. The juice thus extracted is boiled down and mixed with gumarabic and other ingredients, and formed into large cakes. Portions of these are rolled by hand till they take the form of lozenges, and then stamped one by one with the wellknown Pontefract Gate. The trade is slowly decaying, since Spanish liquorice is now imported free of duty.

Extensive Barracks, being the depôt of the 7th and 8th Brigades of the Northern District, were erected 1878.

Abp. Bramhall, Primate of Ireland, died 1663, was born at Pontefract.

Nostell Priory and Walton Hall (see Rte. 38) may be visited from The Ch. of St. Giles (in the town) | Pontefract. Both are within a short

distance of the Crofton Stat. on the (Rte. 38); and after crossing the line to Wakefield. (See post.)

At Ackworth, 2 m. S. of Pontefract, on high ground, commanding very wide views, is a large and celebrated school belonging to the Society of Friends. It was founded in 1778, by Dr. John Fothergill, an eminent physician, and himself a "Friend" (see his Life in Hartley Coleridge's 'Northern Worthies'). Among those educated here are Jeremiah Wiffin (the translator of Tasso and of Garcilasso de la Vega), Bernard Barton, and Wm. Howitt. The Flounders Institute here was established in 1848 by Benjamin Flounders, of Yarm, for training young men to be teachers in the Society of Friends. Ackworth Ch., Early Dec. throughout, has been completely "restored;" the windows contain much stained glass by Wailes. On the font is the inscription "Baptisterium bili phanaticorum dirutum denuo erectum 1663." Ackworth Park (William Peel, Esq.) was for some years the residence of Mr. Gully, the well-known ex-prize-fighter, who long represented Pontefract in Parliament. Mr. Gully, who died in March, 1863, was greatly liked and respected both on the turf and as a country gentleman.]

From Pontefract the rlv. to Wakefield proceeds through some cuttings in the coal formation (which joins the magnesian limestone at Pontefract) to

Tanshelf Stat. and Featherstone Stat., near which are

coal-pits. Somewhat flat and uninteresting

country succeeds to

Crofton Stat. (Nostell and Walton are about 2 m. l.) Walton Hall is seen l.; and the scenery improves as Wakefield is approached. The line passes under the Midland Rly. (Rte. 41); a pretty view of Kirkthorpe village is gained rt. The Barnsley canal is crossed. 1 m. rt. are seen the scanty remains of Sandal Castle

river Calder, we reach

Wakefield Stat. (For Wakefield. and for the rest of the line to Leeds. see Rte. 38.)

3. By Pontefract and Castleford. The Lancashire and Yorkshire Rlv. -the direct line from Knottingley to Leeds-runs from Pontefract to

Castleford (Stat.) on the Aire, the site of the Roman Legeolium, a very important station on the Roman road between Doncaster and Tadcaster at the Ford across the Aire. No remains of the castrum exist; but numerous relics have been discovered. Eastern, Midland, and Lancashire and York. Rlys. have Stats. here. The This district. ch. was built 1866. owing to the flourishing Glass-bottle works and the opening of collieries. has much increased in population (the township of Castleford, in 1861. contained 3876 persons; in 1871. 6268). A little above Castleford the Calder joins the Aire, and a local rhyme runs--

"Castleford women must needs be fair. Because they wash both in Calder and Aire."

The present inky condition of the Calder, due mainly to the dye extracted in shoddy washing, spoils the old rhyme, for "fair" should now read " black."

(The N. Eastern Rly., running from Normanton Junet. to Milford Junct. (on the Gt. Northern Rlv. Rte. 2) here crosses the Leeds and Knottingley line.) At

Methley Junct. the line falls into that of the Midland Rly. (Rtc. 41). A few minutes later it reaches

Methley Stat. 1. is Methley Park (Earl of Mexborough). The Saviles became owners of Methley about 1588, "and have the great distinction of being the living representatives of their remarkable family." The back of the hall was probably built by Sir

John Savile, whose initials, with the central niche, S., a representation of date 1593, occur on it. The front was built about the beginning of this century by the 2nd Earl. The house was famous for a vast gallery, in the windows of which the arms of the Yorkshire families were arranged in wapentakes (so at Gilling Castle, Rte. 18; it seems to have been a favourite decoration). Much of this glass remains in the possession of Mr. Holmes of Methley. In the park are some fine cedars. All this country, lying within the coal formation, is richly wooded; and the Aire flows through bright meadows, bordered by hills of no great height, but affording very pleasing views. On one of these the house of Methley is placed.

Methley Church, ded. to St. Oswald, closely adjoins the park; it has long been attached to the Duchy of Lancaster. The Methley estates passed from the Watertons, through the Dymokes, to the Saviles Earls of Mexborough, the present owners; and the most interesting portion of the ch. is the Waterton Chantry, in which the lords of Methley have long been interred. The rest of the ch. is Dec. (circ. 1320, much glass of this date remains in the E. window), but much altered and injured, with a later tower and octangular spire. The Waterton Chantry ranges with the chancel at the E. end of the S. aisle. It was founded by the will of Sir Robert Waterton, who died in 1424, and is divided from the aisle by a rich stone screen of Perp. character. It is lighted by 3 windows, one of which is partly blocked. Under an enriched canopy in the wall between the chancel and chantry is the tomb, with effigies, of the founder and his wife Both wear collars of SS; Cecily. and there are many rings on the fingers of both. On each side of the tomb are canopied niches, in which are angels with shields, charged with the arms of Waterton and of Water- by will 12,000% to erect the ch. and a ton impaling Fleming; and in the parsonage house, besides 4000l. for

the Holy Trinity. Opposite this tomb is the monument with efficies of Lionel Lord Welles, and Cecily his wife, daughter and sole heir of the Lord Welles fell at the founder. battle of Towton (1461). The effigies are of alabaster, and have been richly gilt and coloured. In the centre of the chantry is a tomb with 3 effigies— Sir John Savile, Baron of the Exchequer (died 1606); his wife; and in the centre their son. Sir Henry There are Savile, the 1st baronet. also monuments for Charles Savile, Esq. (died 1741), in a "Roman habit," with his widow leaning on a pillar; and John Savile, the first Earl of Mexborough (died 1778); a fine example of a bad time. The roof of the chapel is panelled and painted; and many remains of achievementshelmets, swords, and gauntlets (chiefly of the 17th cent.)-moulder on the walls. On the N. wall of the nave hangs a triangular board, recording the aspiration toward a seat in heaven of Roger Holling, churchwarden, who, . in 1624, "auctoritate archiepiscopi," placed seats in this ch.

In the belfry are 2 recumbent effigies of ecclesiastics (14th cent.) which deserve attention.

The rly. proceeds through the valley of the Aire, marked by its flat meadows, "formed by gradual deposits from fresh-water inundations and the tide, laid upon a more rugged and uneven basis, which was an old arm of the sea."—Phillips. Near the

Woodlesford Stat. is (l. of the rly.) the village of Oulton, with a modern Gothic ch., finished in 1830, and interesting as having been designed by the late Mr. Rickman, author of the well-known work on Gothic architecture. The ch. has an hexagonal chancel, and a spire at the W. end. It was built at the sole cost of the late John Blayds of Leeds, who left endowment. The son of the founder | trains on the Midland Riy, line new run beis owner of Oulton Hall. Oulton was the birthplace (1661) of the great scholar Richard Bentley.

The John of Gaunt Inn. in the parish of Rothwell, a little S. of Oulton, is said by tradition to mark the spot where the last wolf in Yorkshire was killed by John of Gaunt, Duke of Lancaster It has been said-Notes to Somerville's 'Chase, ed. Topham - that the corner of England in which a price was last set on a wolf's head was the Yorkshire Wolds; but no date is given, and the assertion must stand for what it is worth.]

Passing Woodlesford, the Aire and its canal continue rt., with fine wooded heights beyond. Large quantities of coal are dug on the estate of Sir John Lowther, owner of Swillington Hall (about 1 m. N.).

Hunslet Stat. is then passed, and amidst a labyrinth of crossing and recrossing rlys, we enter

LEEDS .- Wellington Stat.

There are three principal Stations in Leeds itself, all near together in Wellington Street. From the Central Stat. start the trains of the Great Northern, and Lancashire and Yorkshire Rlys. From the Wellington Stat. those of the Midland Rly.; and from the New Stat. those of the North-Eastern, and London and North-Western Rivs.

At Holbeck Junction, on the outskirts of the town, is another station, at which all the

trains which pass it stop.

The General Post Office is in Park Row, very near to the Wellington station.

Inns: The Queen's Hotel at the Wellington Stat. and the Great Northern Hotel at the Central Stat. These are equally good and reasonable. The Trevelyan Temperance

Hotel in Boar Lane is good.

Railroays. Leeds is connected by rly, with every part of England; and it is only necessary here to refer to the various routes described in this Handbook which start from, or end at, Leeds. The most direct commu-nication with London is by the Great North-ern Riy.; or by the Midland Riy. (Res. 1, and 41). On either rly, the express performs the distance in 4 hrs. 45 min. Pulman's car

tween London and Bradford by way of Leeds-Post Office and Telegraphs in Park Row. Pillar-boxes, general.

Leeds (Pop. in 1871, 253,212; in 1881, 309,126) is the great commercial capital of Yorkshire; the centre of the clothing trade (it is the great mart for broadcloths, as Bradford is for worsteds), and the fifth town in England in size and importance. is the assize town for the West

Riding of Yorkshire.

It is the greatest cloth market in the world. Every kind of woollen cloth is made here, and (besides some worsted mills which exist here. although Bradford is the true centre of that trade: see Rte. 35) there is hardly a branch of manufacture which is not represented in Leeds. mills; dye and bleaching works; felt factories: iron-works, and factories for the making of machines; brass foundries, glass-works, cap and shoe factories on a great scale, chemical works, and leather-works are among the most important of these.

mass of manufacture, with its enormous mills, its myriad chimneys, and their dense cloud of smoke. Leeds has become (with the exception of Sheffield) the blackest and most unsightly town in Yorkshire. of course an air of great wealth, and the stir and movement in the principal street (especially on market days-Tuesday and Saturday) considerable. The long rows of warehouses belonging to the principal firms give a special character to the more modern part of the town. These are chiefly in Wellington Street, and

As a necessary result of this vast

types. The principal sights in Leeds are the Churches, the Town Hall, the Philosophical Hall with its Museum. the Mechanics' Institution, and the Factories and machine "shops" of

it is perhaps to be regretted that so

many of them have been designed after Lombard and "Renaissance

some of the greater firms. These last | district, was consecrated in 1845, and form of course the great and peculiar features of the place, but they are not to be seen without a special introduction, and not always even with one.

St. Peter's Parish Ch., Kirkgate, is chiefly interesting in connection with the late excellent pastor and divine, Dr. Hook, "the Apostle of the West Riding," by whose influence it was entirely rebuilt, 1839-41, at a cost of 28,000, raised by subscrip-On the side of the altar is an altar-tomb and effigy of him, designed by G. G. Scott, raised to him by his former parishioners. The building, black outside and dark within, from much modern stained glass, holds a congregation of 3000, and the choral service is well performed. Here is an ancient carved Cross, also a modern Reredos elaborately sculptured, in ala-The glass in the E. window is ancient, and was brought from the Continent by Thomas Blayds, Esq., who presented it. At the end of the N. sisle, is a monument by Flaxman (not a very successful work), to Captains Walker and Beckett, natives of Leeds, who fell at Talavera; and under the N.E. window is an elaborate monument for the late Chris. Beckett, Esq. (designed by Dobson of Leeds). In the chancel is a memorial to Thoresby the antiquary, removed from the former ch.

The organ, a very fine one, consisting of 2070 pipes, was originally built by Price of Bristol, in 1714, but was reconstructed by the Messrs. Greenwood. The height of the tower is 139 ft. The length of the ch. is 180 ft., and the width 86 ft. Hook was appointed to the vicarage in 1837, then worth 1300l. a year. He afterwards resigned to Ecclesiastical Commissioners of this income for the endowment of 7 districts, to be taken out of the

St. Saviour's Ch., on Cavalier Hill,

is understood to have been built as a penitential offering; the funds (nearly 10,000l.) having been supplied through Dr. Pusev. Round the W. door (within) is the inscription. "Ye who enter this holy place, pray for the sinner who built it." This ch., built under Dr. Hook's own eyes, caused him great grief, owing to the number of perverts to Rome that issued from it. It stands well, is striking, although the details are not good.

An excellent example of modern Gothic is the Ch. of All Soul's, Blackman Street, raised also as a memorial to Dean Hook, at a cost of nearly 20,000l.—1876-80—and held by his son as vicar. It is one of the best designs of Sir G. G. Scott, and is in English Gothic of the 13th centv.

Since 1837, at least twenty new churches have been built in Leeds and its suburbs, but few call for special notice. The ch. of St. John. Little Holbeck, built in 1850 at the sole cost of the Messrs. Marshall, was designed by Sir G. G. Scott. It is E. Eng. in character.

*St. John's Ch., in St. John Street (leading out of the top of Briggate), consecrated by Abp. Neale, Sept. 21, 1604, is probably a unique example of a "Laudian" ch., completed just before the outbreak of the civil war. Until 1870 it retained its original fittings. It has now been "restored." but "every old feature" has, we are told, "been carefully preserved." But a new chancel window, with Dec. tracery, has been inserted, and above the altar a mosaic reredos has been placed. The canopy of the original pulpit has been removed from its place, and is now hung above the S. door of the ch. The organ-case, of carved oak, "in keeping with the ancient fittings around it," is also new. St. John's was built by John Harrison, a rich merchant of Leeds. "Methinks," says Fuller, "I hear that great town East Street, in the midst of a poor accosting him in the language of the children of the prophets to Elisha- | the rly. stat., is the *Town Hall. be-'Behold now, the place where we dwell with thee is too strait for us.' The ch. could scarce hold half the inhabitants, till this worthy gentleman provided them another. He accepted of no assistance in the building of that fair fabric but what he fully paid for, so that he may be owned the sole founder thereof."— Worthies of Yorkshire.

The ch. consists of a long nave and chancel, with S. aisle. The pillars dividing nave and aisle display a strong Gothic feeling, which appears also in the capitals, and in the curious corbels (cherubs with folded wings) at the intersecting of the arches. The ancient pews, all uniform, with carved tops, remain; as does the pulpit, at the side of the nave. (In this pulpit, on the day of consecration. Dr. Cosin, afterwards Bp. of Durham, preached, and in the afternoon the first incumbent, Robert Todd, who was suspended on the same day for some disparaging remarks on the morning's sermon.) The division of the chancel is marked by a screen of woodwork (passing across nave and S. aisle). The altar-table is carved. and round the chancel are ranged seats, with desks in front of themthe original arrangement for communicants. Within the altar-rails is the founder's monument, with inscription, which should be read. Harrison died in 1656. The arms of Chas. I. and the Prince of Wales are on the The windows in the chancel screen. aisle are flat-headed. In all, the tracery is Gothic. The tower was rebuilt during the present century.

Adjoining the ch. is Harrison's Hospital, founded by the builder of the ch. in 1653, as a dwelling-place for poor people. It was entirely rebuilt in 1850. In the school-room attached to the ch. and hospital is a full-length portrait of John Harrison, in his robes as alderman of Leeds. It formerly hung in the ch.

gun in 1853, and opened by Queen Victoria in 1858. The architect was Cuthbert Brodrick. The building is surrounded by an open portico with Corinthian columns. From the centre rises a peculiar tower, crowned by a dome. The great, or Victoria Hall. 162 ft. by 72 ft. and 75 ft. high, is capable of holding 8000 persons. It is perhaps too short for its great width, and its pillars, painted to imitate marble, are scarcely worthy of so imposing a structure. At the N. end of the hall is an enormous organ. built by Messrs. Gray and Davison. and one of the finest in England. Statues of the late Ed. Baines, Eeq., and of Robt. Hall, Esq., are placed in recesses on either side of the hall. and in the vestibule are fine statues of the Queen and *Prince Consort by Noble. The Mayor's Room contains a portrait of Sir P. Fairbairn in his robes as mayor, by Grant; and one of C. J. Fox by Raeburn. In the square in front is a bronze statue of the Duke of Wellington.

The cost of the Town Hall was about 120,000%. The Corporation Offices adjoining the Town Hall, is a

fine Italian building.

The Board School Offices by the side of these is a building of similar style of architecture, and corresponding with the Town Hall.

*The Philosophical Hall, in Park Row, corner of Bond Street, contains the library and Museum of the Leeds Philosophical and Literary Society: the building was commenced in 1819, but was greatly enlarged and reopened in 1862. Admission 1d. for each person. It will thoroughly repay a visit.

On the ground-floor are the lecture hall, council-room, and library. Busts of benefactors to the institution (including those of Benjamin Gott and John Marshall), are placed in the hall; and in the vestibule is a statue In Park Lane, not very far from of the late M. T. Sadler, M.P.

the inner hall are a few local antiquities in cases: a tesselated pavement from Aldborough (Rte. 19), with a rude representation of Romulus and Remus; some smaller British and Roman relics-flints, jet beads, &c.; urns of unusual pattern; celts, including a lead celt from Anwick, near New Sleaford, Lincolnshire: many antiquities (bone and flint ornaments, spear and adze heads, and a coin of Antoninus commemorating the conquest of Britain) from Dowkabottom Cave in Craven (see Rte. 31). Here is also a canoe of hollow oak found in draining the tarn near Giggleswick - perhaps British, but such rude vessels may have been used to a late period. In the Library, which is exclusively scientific, is preserved a most valuable collection of coins and medals, of all periods, bequeathed by the late George Baron, Esq., of Drewton.

On the upper floor are the Geological and Zoological Rooms. The first is rich in both geological and mineralogical collections admirably arranged. There is a fine plesio-sarus macrocephalus, and a great collection of hippopotamus' bones from Wortley near Leeds (found in brick earth). Altogether they are the remains of 4 animals, 1 very old, 1 young, and 2 middle-aged. The plants from the coal-measures are especially fine.

The Zoological Room contains an admirable series of mammalia, described by Professor Owen as the "most complete and unbroken serial exposition of the mammalian class" existing in England. Among the animals is a magnificent tiger, displayed in the Great Exhibition of 1851, and bought for this museum by William Gott, Esq., at a cost of 90l. Here also are the fine skeletons of the great extinct deer (Cervus megaceros) and of the extinct cave bear (Ursus spelseus), the latter unique. The collection of foreign birds is extensive, and the British

birds (in the gallery) well deserve

There is a small Industrial Museum, full of interest for visitors to Leeds. and which will, it is to be hoped, speedily increase. It is intended to contain specimens of the manufactures carried on here, and of the materials used in producing them. The various specimens of flax, and the different dyes, especially the tinctorial lichens, are worth notice: and there are some examples of a curious manufacture from the aloe (Agave Americana) carried on at The fibre, commercially Newlay. known as "Mexican fibre," is used for making brushes, stuffing chairs instead of hair, and for chair seats.

The Mechanics' Institution, a massive stone building of Italian character, is in Cookridge Street, near the Town Hall. The cost was about 22,000l. The advancement of technical education and instruction in the fine arts are well provided for here. The Library contains about 18,000 volumes.

The Leeds Library in Commercial Street, founded in the last cent.. and belonging to a proprietary of 500 shareholders, contains a good and extensive collection. Among the books are 20 vols, of Civil War tracts, including many of local interest; 11 vols. of German and Latin tracts, relating to the early Reformation in Germany; a large paper copy of Thoresby's 'Ducatus Leodensis,' with Wilson's MS. notes; and 4 MS. vols. of Yorkshire Pedigrees, besides one of Lancashire. These were first compiled by Hopkinson toward the end of the 17th cent., and received additions and notes by Thomas Wilson at the beginning of the 18th.

e great extinct deer (Cervus)

and of the extinct cave is in Infirmary Street. There are about 27,000 vols. Branch libraries

The collection of foreign exist at Hunslet and Holbeck.

The Mized Cloth Hall, a long

building without architectural character, stands nearly opposite the Wellington Rly. Stat. It is divided into 6 compartments or "streets," each of which contains 2 rows of stalls, with the name of the clothier to whom it belongs marked on each stall. On Tuesdays and Saturdays the hall is open for an hour and a half, and the business done in that short time is sometimes very extensive.

The White Cloth Hall, in Wellington Street, is on a scale of some magnificence. The cost was about

30,000l.

Near the Mixed Cloth Hall stands a bronze statue of Sir R. Peel, de-

signed by Behnes, costing 1500 guineas, raised by public subscription.

Opposite, at the corner of Boar Lane and Park Row, is the Royal Exchange, the foundation-stone of which was laid in 1872 by H. R. H. Prince Arthur. The design (by Messrs. Healey, of Bradford) is Perp. Gothic, of the latter part of the 15th centy., and merits more than a casual glance. Any one caring for architecture cannot do better, after leaving the Royal Exchange, than to take a walk up Park Row, and examine the principal buildings there. The Unitarian Chapel, the first building we come to, though erected in the early vears of the Gothic revival, is, from its excellent proportions, one of the best buildings in the town. A little higher up the street Sir Gilbert Scott is well represented in the Bank of Messrs. Beckett and Co., and Mr. Waterhouse and others have shown how well Gothic is adaptable to shop requirements.

Leeds is rich in charitable institutions, and contains of course Dissenting places of worship of every kind. But the town can show few relics of earlier days. The most interesting is perhaps the Red Hall, in Upperhead Row — the house in which Charles I. was confined for a day or two when passing southward in the custody of Cornet Jovce.

Wellington Street, in which are the principal warehouses, and Briggate, where are the best shops, are the most important streets in Leeds and a fine street has been made on the site of the ancient Boar Land. At the foot of Briggate is Leeds Bridge, over the Aire, on which, before 1684, the cloth market was held. The cloth was brought to the bridge on pack-horses, and hung over the battlements for exhibition. The old stone bridge, was entirely replaced in 1873 by a wide iron bridge.

On the skirt of Woodhouse Mox.

above the town, is the Grasser School, a Gothic building by Edecard Barry, from a design by his father Sir Charles Barry. The school was founded in 1552, by "Sir William Sheafield, priest," and has since been well endowed.

Woodhouse Moor itself is the "breathing-place" of Leeds; and happily, is safe from enclosure, since it has been bought by the corporation. From it there is a fine view up the

which, and round the moor, are the houses of the principal merchants.

The Hospital and Medical School near it, built from the designs of Sir G. G. Scott, are good, and well placed. The former is built on the principle of separate pavilions, so at to obtain as much quiet and free ar as possible. The design is a kind of Lombard Gothic, with an arcaded screen connecting the several portions.

valley of the Aire: on the side of

The great Manufactories of Leeds are the chief sights of the place, but those to which a stranger without introductions has the least chance of access. They are collected, for the most part, near the W. or Kirkstall road; and at night, when the light streams from innumerable windows rising tier above tier, all this quarter of Leeds is very striking and impressive. Of the Cloth mills one of the largest is that of Messrs. Gott, at Bean Ing, where the whole process of manufacture may be witnessed

from the very commencement. (See guise; but the "taskmasters" here Introd.) Their great establishment, have little cause to fear a comparison where the completed goods are sorted with those on the banks of the Nile. Besides building a church (St. John's,

In Leeds and its immediate neighbourhood there are between 800 and 900 manufacturers of woollen cloth. some of them representing firms of great wealth and importance. Cloth is still the staple produce of the district: but the flax trade is increasing here fast, and with the exception of Belfast, the mills are said to turn out more work than any other town in the United Kingdom. One of the largest flax-mills in Europe is that of the Mesers. Marshall, on the S. side of the Aire. (Turn down Neville Street, opening from Swinegate, near the Wellington Stat.; cross the Victoria Bridge, and take the first turning rt.) There are here two mills. the old, built after the usual style of factories; and the new, a very remarkable building, which, instead of being raised to a height of 5 or 6 stories, is spread over a space of about two acres, forming one enormous apartment 400 ft. long by 216 ft. broad, and 20 ft. high. The roof, of groined arches built of brick, rests upon 50 cast-iron pillars. There are 66 of these arches or domes, each of which is lighted by a circular lantern, 14 ft. in diameter, and rising about 9 ft. above the roof. This arrangement avoids the steam, which collects in the older factories, story over story; and provides a far better light. (It is said that the plan does not really involve a greater extent of ground: but this seems questionable.) Upon the roof itself (between the lanterns) is laid coal-tar mixed with lime, so as to be impermeable to moisture; and this is covered with eight inches of soil, sown with grass, -by which means an equable temperature is secured for the hall below. The entrance to the mill is designed after the propyleeon of an Egyptian temple; and the lofty obelisk which rises beside it is a chimney in dis- | Marshall's.

guise; but the "taskmasters" here have little cause to fear a comparison with those on the banks of the Nile. Besides building a church (St. John's, opposite the mill) for the "hands" which people the district, the Messrs. Marshall have established schools, and have provided an excellent library for their workmen.

All the operations connected with flax-spinning and weaving are carried on in this vast hall, where about 1000 hands are at work daily. spindles alone are valued at 100,0007. The view in every direction is of course wonderful; and the thorough ventilation, the order, cleanliness, and silence (broken only by the click of machinery) are most striking. The best flax is imported from the neighbourhood of Poictiers, where the water of the Liesse has some peculiar quality which greatly improves it. Flemish flax comes next, then Dutch, and last that imported from the Baltic.

Huckaback towels, coverings for mattresses, all kinds of linen fabrics, and an immense amount of sewing thread, are made here. The great engines, each of 100 horse-power, are worth special notice; the working machinery is carried underground from them, for the sake of safety.

Of the Iron Factories and Foundries the largest is perhaps the Airedale Foundry (Messrs. Kitson), where locomotives, stationary engines, and boilers, &c., are made; but one still more interesting is the Wellington Foundry, belonging to Messrs. Fair-This covers nearly 4 acres of ground; and all the delicate machinery used for spinning flax, tow, hemp, and silk, may here be seen in process of construction. The moulding of the various pieces of iron is very curious and interesting; and the visitor will have a good opportunity of studying here the construction of the machines which he may have seen at work at Messrs. Gott's or

Messrs. Fairbairn's is the machine " shop " of Mesers. Batley and Greenacood, at Armley, where is turned out an immense amount of machinery for the making of field-guns, rifles, and other implements of war, and for the more peaceful trade of silk dressing.—(It may here also be mentioned that Armley gaol, 11 m. from the Town Hall, is a model in its way.) Taylor, Wordsworth and Co.'s tool manufactory is an extensive establishment.

The Glass Works of Messrs. Bower Hunslet, and the Sheepscar Spanish Leather Works belonging to Messrs. Wilson, are also well deserving of a visit. Every kind of manufacture is indeed represented at Leeds. There are 9 tobacco factories; and more than 30 firms engaged in chemical preparations of

various sorts.

Among many men of note born in Leeds were-Ralph Thoresby, the antiquary; Dr. Milner, author of History, ' Church and brother the Dean of Carlisle; Benjamin Wilson, the landscape artist; and William Lodge, the engraver.

No one who can afford the time should leave Leeds without visiting Roundhay, the Public Park, about 3 m. from the top of Briggate, situated in the very centre of the handsome, homes and gardens of the wealthy citizens of Leeds. It was purchased in 1872 by the corporation on behalf of the public, at a cost of 140,000l. It is 773 acres in extent, situated on beautifully undulating ground, well-wooded, with several lakes and waterfalls, far away from the noise and turmoil of the town. It appears to exactly answer the purposes for which it was acquired. The mansion of Roundhay, a large house with a lofty colonnaded portico, is set apart as an Hotel of the first class. The gardens are generally open to all. It may safely be

To some even of more interest than | possesses such a "people's park" as Roundhay.

History of Leeds.

There was no Roman station at Leeds, which lay in the heart of the Brigantian territory; but Roman roads ran through or near the site of the existing town from Cambodunum (Slack) to Tadcaster, and from Castleford (Legiolium) to Ilkley (Olicana). At Adel, 5 m. N. of Leeds, on the latter of these roads, are traces of a considerable Roman town; and there is reason to believe that the iron with which this country abounds was worked and smelted by the Romans not only in the neighbourhood, but on the site of Leeds itself. (Heaps of scorise have been found here.) During the troubles which followed the departure of the Romans, the country of which Leeds was the centre seems to have become a small independent kingdom, which, about the year 616, was ruled by a certain Cerdic-whom Bede expressly calls " rex Britonum" (H. E. iv. 23)indicating that the district had not at that time been taken possession of by the Anglians. It was, about that year, conquered and incorporated by Edwin of Northumbria (Nennius H. Britonum), whose nephew, Hereric, exiled from the Northumbrian court, had taken refuge with Cerdic. who poisoned him. This kingdom of "Loidis," or Leeds (the name first occurs in Bede, l. ii. 14, and its etymology is altogether uncertain), included the greater part of the valleys of the Aire, the Calder, and the At or near Leeds (pro-Wharfe. bably at Osmundthorpe) the Northumbrian kings possessed a villa; and the western portion of Loidis was known as Elmete-" the wood of Elmete"—(so named, it has been conjectured, from the "elm" trees which then, as now, may have thickly covered it: but this derivation is not said that no other town in England quite satisfactory). In this wood,

and probably on the site of the exist-lover from Hamburgh, nay, even from ing parish ch. of Leeds, stood the monastery " of the most reverend abbot and priest Thrydwulf," in which was preserved the altar which escaped the fire when Penda burnt Cambodunum (see Rtc. 37).

After the Conquest, Leeds suffered like the rest of Yorkshire, and the whole neighbourhood is described in · Domesday ' as " wasta." It then passed to the great baron Ilbert de Laci, who built a castle here, which was besieged and taken by Stephen in 1139, and in which Richard II. was confined for a short time before he was taken to Pickering (see ante, Pontefract). No trace of this castle seems to have existed when Leland visited Leeds, which he describes as "a praty market towne as large as Bradford, but not so quick as it." The town was first incorporated in the 2nd year of Charles I. In 1642 it was taken by the Royalists, under the Marquis of Newcastle: and in the following year was retaken for the Parliament by Sir Thomas Fairfax, after a severe skirmish. 500 prisoners fell at this time into the hands of Fairfax. Cloth-making had been established in this district from a much earlier period, probably from the reign of Edward III., when Flemish workmen were brought into Yorkshire; and at the beginning of the last. cent. Leeds had become the great centre of the northern cloth trade—the cloths made here being called "narrow," says De Foe, "when they are spoken of in London, and compared with the broad cloths made in Wilts, Gloucester, Somerset, and Devon." Writing about 1714, he describes the neighbourhood as "a noble scene of industry and application, which, joined to the market at Leeds, where it chiefly centres, is such a surprising thing, that they who have pretended to give an account of Yorkshire, and have left this out, are inexcusable-many travellers and gentlemen having come much broken into hill and valley, [Yorkshire.]

Leipsick in Saxony, on purpose to see it."-Tour in Great Britain, 111. The cloth market was at first held on the large and wide bridge which crossed the Aire; "and therefore the refreshment given the clothiers by the inn-keepers, being a pot of ale, a noggin of porrage, and a trencher of broiled or roast beef, for twopence, is called the brigg-shot to this day."-De Foe. Afterwards the market was held in the street now called Briggate, until in 1758 the Mixed Cloth Hall was built, and is still in use. In 1775, the White Cloth Hall was erected, and was used until 1866. when it gave place to the New Hall in Wellington-street and King-street. The prosperity of Leeds increased gradually and steadily until the beginning of the present century, when, like other manufacturing towns in the north, it made sudden and rapid progress; and the population, which in 1801 was 55,162, had become 172,270 in 1851, in 1861 was upwards of 200,000, and is now (see ante) more than 300,000.

Unless the tourist's object be to study the mills and manufactures of Leeds (for which he must have special advantages and introductions), he will hardly care to remain here for more than a day or two. Most of the places, however, mentioned in the preceding and following routes may be made the objects of a day's excursion from Leeds; and the great manufacturing towns (Bradford, Halifax, Huddersfield, Barnsley) are reached in so short a time by rly, that a long day may be spent in each without difficulty. Kirkstall Abbey (see Route 29) is within a few minutes' distance by rly., and trains are constantly running. Longer excursions may be made to (a) Adel (5 m.) and to (b) Temple Newsam (4 m.).

(a.) The country round Leeds is

and is still much wooded, though table below the roof should be espethere are few relics of the ancient "forest of Elmete." The road to The road to Adel passes across Woodhouse Moor, having below it, rt., the pretty Meanwood valley, through which a stream descends to join the Aire. At Headingley (21 m.) is the skeleton of a most venerable oak known for ages as the Skyrack, or Shire-oak, and giving its name to the Wapentake. It is quite dead, but the trunk is still supported by ivy. Near it are two Inns—the 'Oak Tree' and the 'Sky-rack.' Like other famous oaks, this tree probably served as a boundarymark, and may have been the place of assembly for the Wapentake. The ch. of East Headingley, St. Chad's, was built, 1863, from designs of Sir Edmund Beckett, Bart., at the expense of his father.

21 m. beyond, on high ground, in an open country with little wood, is the Norm. ch. of Adel, well-known to archæologists. Adel is on the line of a Roman cross-road which ran from Castleford to Ribchester. There was a station on the hill-slope N. of the village, where many Roman remains (among them an altar inscribed to the goddess Brigantia) have been discovered; and it has been suggested that the existing church may have been built on the foundations of a

Roman building.

The Church of St. John the Baptist was given by Ralph Paganel to the Benedictine Priory of Holy Trinity at York; and remained in the possession of that house until the Dissolution. It was judiciously restored 1878. It is a small Norm. building, consisting only of nave and The windows on the N. chancel. side are all (except one) roundheaded, of one light; only one original window remains on the S. At the W. end are three Norm. windows. (The belfry above is modern.)
The E. window is Perp. All the windows are above a stringcourse, high in the wall; and the corbel- is about 5 m.).

The most striking cially noticed. features of the ch., however, are the S. porch and the chancel arch—both enriched with very elaborate Norm. sculpture. Over the porch is a gabled pediment, in which appear Saviour, with the emblems of the four Evangelists, and the Lamb with a cross. The chancel arch recedes in three orders, the outermost of which has the bird's-head moulding. the capitals of the shafts are—the Baptism of our Lord—(an angel, as in the earliest Byzantine representations, holds his robe)—the Crucifixka -a knight with spear and shieldand a sagittary. This last emblem (the device of King Stephen) probably marks the date of the ch., which may be compared with that of Iffley near Oxford, nearly of the same time and character. The glass in the E. window dates from 1601. three bad pictures in the chancel, representing the Agony of our Lord. His Crucifixion, and Ascension, are by Vanderbank, and were given to the ch. by Wm. Jackson, rector, who died in 1766.

In a hollow near the ch. is a mill, -a modern building on a mill site of extreme antiquity; and close above it is the site of the Roman station, marked by one line of the original vallum. On the S. it was defended by a stream and a deep bog. The Roman road ran above it. Sepulchral remains, alters, &c., have been found at and near this station -the name of which has not been preserved, although in the Domesday Survey a place in the parish of Adel receives the name of Burhedurum possibly representing that of the Roman town. Of the altars, some are to be seen in the Leeds Museum.

In the valley above the mill is a Reformatory School, estab. 1857.

(The pedestrian may walk across the country from Adel to Harewood. (See the following Rte.) The distance

(b.) 5 m. S.E. of Leeds, on high ground, in a country which must have been very pleasant before the days of smoke and tall chimneys, is Temple Newsam (Mrs. Meynell Ingram). The house is famous for its collection of pictures, which are shown on Thursdays in the absence of the family.

At Newsam (Newhusam in Domesday) a preceptory of Knights Templars was founded in 1181; which on the suppression of the order passed to the Hospitallers, who ceded the manor to Edward II. in 1324. It was afterwards granted to Sir John D'Arcy. After the death of Thomas Lord D'Arcy, who was beheaded for his share in the Pilgrimage of Grace (1569), Temple Newsam passed to the Earl of Lennox and his wife Margaret, grand daughter of Henry VII.; and it was here that their son, the unlucky Darnley, husband of Mary of Scotland, was born. James I. gave the estate to his kinsman the Duke of Lennox, who sold it to Sir Arthur Ingram. From Lord Irvine. who represented the Ingram family, it came in 1807 to the Marquis of Hertford, who took the surnaine of Ingram before that of Seymour; and from him to the late proprietor, H. C. Mevnell Ingram, Esq.

The existing house was built temp. Charles I., by Sir Arthur Ingram, who pulled down the older mansion. retaining, however, a portion of the building which contained what, according to Thoresby, was called the - Royal Chamber," in which Darnley This room, however, can was born. no longer be identified. The new house was injured by fire in 1635; but seems to have been at once re-It is of brick, with stone stored. coigns, very picturesque, in plan resembling a half H; and in compliance with a quaint fashion of the time, the open battlement running round the roof is composed of capital letters, cut in stone, forming the words, "All Glory and Praise be

given to God, the Father, the Son, and Holy Ghost, on High; Peace upon Earth, Good Will toward Men; Honour and true Allegiance to our Gracious King, Loving Affections among his subjects, Health and Plenty within this house." The interior is fine, and contains two very striking apartments: the Library, 24 ft. square: and the Picture Gallery 108 ft. by 28 ft. Unfortunately this room is badly lighted, and it is impossible to get a good view of the pictures it contains. The most important are—

Guido.—John the Baptist; St. Margaret. Rubens .- The Virgin and Child, the Baptist, and Joseph, in a landscape. Nicholas Poussin.—The Virgin, with the Baptist and St. Elizabeth. Annibale Carracci.—The Dead Christ with Disciples. William Vandevelde.—Two sea-pieces; one of Van Tromp's naval victories. Poelemburg .- A Charity, with children and angels; "belongs in every respect to his finest works."— Waagen. Miere-veldt,—Maurice, Prince of Orange. Sir J. Reynolds. - Marchioness of Hertford; full-length, with landscape background; Lord and Lady Irwine; and a Shepherd Boy. W. Jan Asselyn .-- "A large and very beautiful picture, inscribed and dated 1646." Rembrandt. — Portrait of himself. Albert Dürer. — A Crucifixion; Dr. Waagen assigns this picture to a "good master of the Dutch school of the latter half of the 15th cent." Jan Fyt,-A Wild-Boar Gaspar Poussin.—A land-Hunt. *Titian.-Portrait of Martin scape. Bucer, the reformer; "unquestionably the finest picture in the collection."-Waagen. Claude.—Landscape with ruins; fine. Le Bourguinon,-Landscape and sea-piece.

The park of Temple Newsam is large, well-wooded, and full of deer; but the smoke of Leeds extends even here, and the trees are much blackened on the side towards the town. One avenue is very picturesque.

(The ruins of Thorpe Hall, 2 m. S.

2 B 2

of Temple Newsam, the mediseval residence of the Skargills, will repay the visit of an architectural antiquary. It was partly demolished by Sir Arthur Ingram in the time of Chas. I. after he purchased it from Major Clough.)

A drive of not quite a mile will bring the visitor from Temple Newsam to the village of Whitkirk; very near which is Austhorpe Lodge, the birthplace of John Smeaton the engineer, and the constructor of the Eddystone lighthouse. He was born here June 8, 1724; his father was an attorney. Austhorpe remained his home during the whole of his active life; and the square tower which he built for his study still exists. died here, October 28, 1792, and was buried in Whitkirk church. (For an sketch of his life, see Smiles's 'Lives of the Engineers, vol. ii.) He is said to have designed iron gates for the park of Temple Newsam; and water is still raised in the grounds there by an ingenious hydraulic ram which he constructed.

Whitlirk Church deserves a visit. It is Perp., with a tower, of which the parapet overhangs, as if machicolated. In it is an altar-tomb, with effigies, temp. Henry VII., for Robert Scargill and his wife, founders of a chantry here; a monument, with effigies, for Ed. Viscount Irwine; and another (by Nollekens) for the last Lord and Lady Irwine. On the wall of the chancel is a tablet for John Smeaton and his wife. It is surmounted by a model of the Eddystone.

ROUTE 29.

LEEDS TO HARROGATE (KIRKSTALL,

(N. Eastern Rly., 10 trains daily, in 40 to 50 min.)

Leaving Leeds from the New Stat., and stopping at the Holleck Junct., the line curves northward. crossing the Wharfe by a viaduct. In the valley l. is the village of Burley, with a good modern Church (St. Matthias). At the end of the S. transept is a tower and spire 166 ft. high.

10 min. after leaving Leeds the train reaches

3 m. Headingley Stat. (For the village and its ancient oak-tree, see Rte. 28, p. 370.) Below the stat., l., is the manufacturing village of Kirketall. and in the valley close above it the ruins of Kirkstall Abbey.

The remains of Kirkstall are more perfect than those of any other Yorkshire abbey, with the exception of Fountains. They have consequently a very high interest for the archeologist. But, although the situation is still beautiful, the smoke of Leeds has so blackened the ruins and the trees which surround them; the Aire, which flows by, is so completely discoloured; and the valley above and below is so full of busy life and tall chinneys, that Kirkstall has far less charm than many a ruin of less importance. There is of course something very striking in the contrast between these relics of a former age. and the factories and railroads that encircle them.

In the first half of the 12th cent. Henry de Lacy, "vir magnaram rerum, et inter proceres regni notissimus," made a vow, during a dangerous illness, that, should he recover, he would found a house of Cistercian of money and departed elsewhere. monks-the order which had just (see Rievaulx, Rtc. 18A; and Fountains, Rte. 22) been introduced in Yorkshire. His abbey was first established at Barnoldswick in Craven (see Rte. 30), where, in 1147, a colony of monks was translated from Fountains. At Barnoldswick, however, the Cistercians encountered many troubles and difficulties, some of their own seeking (Rte. 30); and the abbot was anxious to remove his convent to a better situation, when, journeying on the business of the house, he chanced to pass through the then lonely and wooded valley of the Aire. Near the place where Kirkstall now stands, he found a small body of hermits; and, savs the chronicle of Kirkstall (preserved in the Bodleian-a part has been printed in the Monasticon), "delighted with the amenity of the place," he turned aside to ask of the hermits whence they came and what was their mode of life. A certain "Seleth," whom they recognised as their head, told him that he came from the southern part of England, in obedience to a voice which called him in a dream.

The abbot, who had been struck with the capabilities of the site, " began at once," says the chronicler, to point out to Seleth and his brethren the superior advantages of a true monastic life to that which they had adopted; and leaving them to ponder his words, went straightway to Henry de Lacy (probably to Pontefract). He told De Lacy of the Barnoldswick troubles, and added that he had found a site in every way preferable, to which the convent might be removed. Kirkstall, however, belonged to William of Poictou, and not to De Lacy: but by the latter's influence the site was gained. (The arms of the abbey, 3 swords palewise, points downwards, were adopted from those of William of Poictou.) Some of the hermits joined themselves to the Cis-

(The names of Nostell-North-stall. Kirkstall, indicate foresters' and "stalls" or lodges in the midst of the wood: and it would seem that a small ch. had once existed at Kirkstall before the arrival of the hermits.)

Henry de Lacy laid the foundation of the monastic ch. at Kirkstall with his own hands, and the whole fabric of the monastery was completed at The brethren entered their his cost. new house May 19, 1152. Across the river there was a tract of rich land. William de Rainville, its lord, gave it to the monastery, which henceforth had its cornfields and granges close at hand; and other benefactors speedily increased its possessions.

Of the later history of the house there is little to record. The gross annual value at the Dissolution was 512l. 13s. 4d. The site was then granted, in exchange for other lands, to Abp. Cranmer, and after many changes it came, with adjoining estates, into the hands of the Earls of Cardigan, who still possess it.

A small sum is paid for admission to the ruins, which the visitor is then left to examine at his leisure. greater part of the remains is Trans.-Norm.; no doubt belonging to the original building erected by Henry de Lacy. The first abbot—Alexander, who had been prior of Fountains when he removed to Barnoldswick. and who had procured the site of Kirkstall -- ruled the house for 35 The general plan of the remains resembles that of Fountains (Rte. 22), except that the hospitium (perhaps owing to the nature of the ground) seems to have been here placed E. of the abbot's house, instead of in the court W. of the ch., as was most usual.

The Church, which consists of a long nave, with transepts, and a very short choir, is throughout Trans.-Norm, with the exception of the upper part of the tower (at the intertercian house, Others received a sum section of the transept) and of the

E. end of the choir. These are Perp. [of late character. The original tower, in accordance with Cistercian precepts (see Fountains), rose but little above the roof; but, as at Fountains. a later age grew impatient of this simplicity, and a lofty Perp. tower was raised on the older structure. This seems to have been incapable of supporting the additional weight. At all events 2 sides, and a part of a third, fell in 1779, leaving the remaining portion in somewhat insecure condition. From the occurrence of the letters W. M. on the buttresses, it appears that this superstructure was added by William Marshall, abbot from 1509 to 1528.

The design of the W. front is unusual, very picturesque, and should be especially noticed. The pointed pediment of the portal rises to the sill of the window above it, which has 2 rounded arches within a wider circ. arch, the tympanum of which is (at present) quite plain. (The gable and side pinnacles are of later (Perp.) date.) The long nave and transepts are of nearly the same date as those of Fountains, and, like that, are plain and massive, though there is perhaps a greater tendency to enrichment at Kirkstall. The arches of the main arcades are pointed. The windows of aisles and clerestory are round-headed. The transepts were without western aisles, and each eastern aisle was divided into 3 chapels, separated,, as at Fountains, by solid walls. The choir or chancel was unusually short, projecting only 1 bay beyond the E. wall of the transept. Neither monuments nor tomb-slabs exist in the ch., the entire length of which is 224 ft. 6 in. It does not stand due E. and W., but the Cistercians seem to have paid no great attention to the observance of this rule, which is English rather than universal.

The Cloister, as usual, is on the S. side of the nave, and forms a quadrangle of 143 ft. by 115. The whole

is Trans.-Norm. with round-headed windows and doors. On the E. side. adjoining the S. transept of the ch. is the Chapter-house, a long parallelogram (as was usual with the Cistercians), with 2 massive piers rising in the centre, and dividing the apartment into 3 bays, the 2 westernmost of which are Trans.-Norm.; eastern (with the eastern pier) Dec. The Chapter-house is 64 ft. 9 in. long and 30 ft. 6 in. wide. stone coffins with their covering slabs were inserted in the walls when the apartment was extended, and bones that have been fractured have been found in some of them. they were those of members of the Lacy family, or of the earlier abbots Some stone coffins, which have not been appropriated, remain on the floor. Beyond the Chapter-house are two small apartments of uncertain use, and on the S. side of the court is the Refectory, the 4 doorways opening to which are now walled up. The Kitchen opened from the S.E. corner of the refectory; and W. of it was what seems to have been the Fraterhouse, or "common room" of the monks. Eastward of the refectory. but now indicated by little more than foundations, was the abbot's house. with hall and chapel as at Fountains. though on a less magnificent scale: and beyond again are the foundations

of the Hospitium. A wide passage W. of the Fraterhouse formed the main entrance to the cloister court; and stretching along and beyond the W. side of the court was the Great Covered Cloister. 172 ft. 6 in. long by 29 wide. Extending W. of this cloister, at its southern angle, is a building, the appropriation of which it is difficult to determine. Above the cloister was the Dormitory. All these buildings are Trans.-Norm. The Gatchous. N.W. of the abbey, is now attached

rangle of 143 ft. by 115. The whole lease by a committee formed in Leeds.

to a private residence.

and some excavations have been made I under their direction. Some very interesting objects have been discovered. among them a chess-piece of the 12th cent., carved from the tusk of a walrus (see description and figure in the Archaeol. Journal, vol. vi.); a mould of Caen stone for casting metal escallop-shells: several ornamented keys: fragments of glass and pottery; and a large number of encaustic pavingtiles, portions of patterns of elaborate design. The ruins are tolerably kept. but it is to be regretted that noisy fetes and large picnics are sometimes permitted among them. The gatherers on such occasions are hardly so reverential as Dr. Johnson, who persisted in remaining uncovered within the roofless walls of St. Andrew's Cathedral.

The large iron-works at Kirkstall Forge, about a mile from the abbey, probably mark the site of a very ancient foundry established by the monks, who, here as elsewhere in Yorkshire, did not neglect the ironstone which they found on their lands.

Kirkstall Church is modern, and dates from 1829.

Leaving Kirkstall, the next stat. on the rly. is at

5½ m. Horsforth. The large village (Pop. 5465) with its cloth-mills lies 1. of the line. Rt., soon after leaving the stat. is Moseley Wood, through which ornamental walks have been cut; and behind it Cookridge Hall, once a seat of John Sheffield, Duke of Buckinghamshire (born 1650, d. 1720), court favourite throughout the reigns of Chas. II., Jas. II., and Anne; a poet whose verses are now forgotten, and a critic whose merit was recognised by Dryden, by Prior—

"—Happy the poet, blest the lays, Which Buckingham has deigned to praise"— Alma. and by Pope" Such was the muse, whose rules and practice tell

'Nature's chief master-piece is writing well.'"—Kssay on Criticism.

The last line is from the Duke's 'Essay on Poetry.' Cookridge Hall has been partly rebuilt.

A very handsome Convolescent Home for the town of Leeds has been erected here at the cost of J. Metcalfe-Smith, Esq. (archit. Norman Shaw). It is supported by voluntary contributions.

Soon after passing Moseley Wood the rly. plunges into Bramhope Tunnel, cut through the high ground of which Otley Chevin is the cresting ridge. This tunnel is more than 2 in long, and during its construction some of the workmen were killed by a fall of rock, an accident commemorated by a tablet in Otley Ch. (Rte. 30). A short distance beyond the tunnel the line reaches

9½ m. Arthington Junct. Stat. The view on either side is of great beauty, with the Wharfe, here a wide and full river, flowing between green banks and backed by steep wooded hills. 1. branches off the Railway to Otley and Ilkley (Rts. 30).

Rt. Harewood, castle, ch., house, and park, is distant about 4 m.

No conveyance is to be had at Arthington Stat. Harenood House (see post) is open on Thursdays between 11 and 4.

The walk from Arthington to Harewood is pleasant; turning l. from the high road about 24 m. from the Stat. and crossing Harewood Park to the village. Arthinaton Hall Thomas Sheepshanks) and Park are passed l.; and opposite, rt., is a striking modern Church, built and endowed by the late Mr. Sheepshanks (archit., - Healey of Bradford). The style is early Geom., of rather French than English character, and with a tower and spire decidedly French. The stained glass is by Clayton and Bell. There are some good Schools

on the l. of the road. Arthington Hall (in which is a fine picture by Constable) stands near the site of a house for Cluniac nuns, founded, in the middle of the 12th. cent., by Peter of Arthington. There are no remains. The hall was built in the reign of Charles I. by Cyril Arthington, "an ingenious gentleman, well seen in hydrostatics," says Thoresby, "for he conveyed water from the Wharfe to his house. Nearer Harewood (across the river) is the site of a mosted house called Rougemont, once a manor-house of the Lisles, lords of Harewood in the 13th cent. The main road winds round the wooded hill on which Harewood Castle stands, and then enters the village-pleasant, neat, well kept. The pedestrian should turn off by the first road rt., after passing Arthington Ch., ascend Rawdon Hill, and then take the first fork l., which will bring him to the village of Low Weardley (birthplace of John Nicholson, the so-called "Airedale poet," in 1790), and thence to an entrance of Harewood Park, through which he may walk to the village (where the keys of the ch. are kept,-on Thurs-This will be a days it is open). shorter and pleasanter walk than that by the high road.

The manor of Harewood was granted after the Conquest to the Romellis, who no doubt erected the first castle here. It passed from them through Fitzgeralds and Lisles to Sir William de Aldburgh, who became lord of the castle and manor in 1365, by feofiment of Robert Lord de Lisle of Rougemont (on the opposite side of the Wharfe). Harewood afterwards passed to the Gascoignes; and the family of Lascelles, who now possess the estate, obtained it by purchase about the year 1740.

The ruined Castle of Harewood stands on high ground, but on the slope of a mound falling towards the river. This mound is probably pre-Norman, and there are traces of large earthworks E. At the back extends

a flat open space. The plan was a quadrangle, with towers at the angles. and with the main entrance through a projecting tower on the N. side. This entrance admitted at once to the great hall, near the partition wall. which, on the W. side, separated the hall from the kitchens, over which were the solar chamber and other There are square towers S.E. and N.E., in which were 4 stories of rooms. The hall is 54 ft. 9 in. by 29 ft. 3 in.; and on the S. side near the dais is a remarkable recess in the wall, of some depth, with a projecting shelf, under which runs a grace-The ful leaf-moulding. foliated canopy of the recess rests on sideshafts, and at the back is a slit-opening in the wall. It was no doubt intended to serve as a permanent sideboard or beauffet; and it is curious to find a design which might have served for that of a tomb recess so appropriated. The whole is rich Dec. work. The entrance-tower has the portcullis grove remaining, and the portcullis-chamber above. There was an oratory or chapel above again; and outside this tower is seen the motto of Sir William de Aldburgh, "Vat sal be sal." his shield of arms, and that of Baliol, King of Scotland. Wm. de Aldburgh was " messenger" of Edward Baliol, 27 Ed. III., and it was, perhaps, owing to this connection that the church and village escaped pillage during the Scottish forays of that time. The whole of the castle seems to be the work of this Sir Wm. de Aldburgh, who, in 1367, obtained licence to crenellate the "mansum manerii" of Harewood.

The castle was probably dismantled during the civil war, since it was habitable in 1630, but uninhabitable in 1657, when Sir John Cutler bought it. Its towers are covered with iv. and the sketcher may find work for his pencil among the picturesque ruins.

Norman, and there are traces of large Harewood Church (ded. to All earthworks E. At the back extends Saints) stands in the park about

I m. E. of the village. It is Pero... and was possibly built by the prior of Bolton, to whom it was appropriated by Lord Lisle in 1353. In 1793 much of the ancient glass and oak fittings was removed, and the ch. was " beautified" in the fashion of that In 1865 it was "restored." and the interior is now in very perfect order. (The pulpit and font were given by Mr. Edwin Lascelles.) The Perp. work of the ch. is fine. with a lofty arcade (no clerestory), and piers without imposts or caps, but having a small bracket at the intersections of the outer mouldings. The N. and S. aisles have chapels at the E. ends, opening to the chancel, with lofty arches. The chancel is the same width as the nave, and the proportion throughout is excellent.

The Monuments, however, are far more interesting than the building itself. In the E. chapel of the S. aisle are (1) Sir Richard Redmayn and wife; daughter of Sir William Gascoigne, d. 1540; collars of SS under the sole of one foot, a hermit with rosary. (2) Sir William Gascoigne and wife; he in coif and robes. she with plaited head-dress and coronal. This is the famous Chief Justice of the King's Bench who, in the reign of Henry IV., is said to have the heir-apparent to committed prison for an insult to himself, who had just sentenced one of the prince's servants. The striking scene in Shakespeare's 'Hen. IV.' (Pt. II. act v. sc. 2) in which Hen. V., after his accession, reappoints Sir William as chief justice will occur to every

one-

" You did commit me; For which, I do commit into your hand The unstain'd sword that you have used to

With this remembrance,—that you use the With the like bold, just, and impartial spirit As you have done 'gainst me."

The truth is, that the young king did not reappoint Gascoigne-a suffi-

Foss ('Judges of England') has proved that, instead of Gascoigne, Sir William Hankford was appointed chief justice March 29, 1413, eight days after Henry V.'s accession. an inscription, moreover, which formerly surrounded this altar-tomb (but which has disappeared). Sir William was recorded as "nuper Capit. Justic. de banco, Hen nuper regis Anglise quarti"-without reference to Hen. V., which of course would not have been the case had he been also that king's chief justice. (3) Sir John Nevile, d. 1482, and wife. His daughter married Sir John Gas-Collar of SS., bareheaded. coigne. Wife in wimple covering the chin, showing that she survived him. Sir Richard Franks and wife, of Al woodley, bare-headed; good example of armour. (5) Under arch into chancel, Sir William Ryther and wife Sibyl, daughter and co-heiress of Sir William Aldburgh, d. 1440; helmet, collar of SS., gloves noticeable. Under an arch on the N. side of the chancel is (6) Sir Richard Redmayn and wife Eliz., daughter and co-heiress of Sir W. Aldburgh, d. 1442. All these monuments are in English alabaster, and are good examples, but without special character or beauty. are somewhat conventional, and may be the work of one hand. effect is solemn and striking. The small figures or "weepers" at the sides of the altar-tombs deserve notice.

From the W. door of the ch. (which is private), there is a pretty view of Harewood House (Earl of Harewood; open on Thursdays). It was built by Henry Lascelles, 1st Baron Harewood, in 1760, from designs by Adam and Carr of York. This house replaced a mansion known as Gawthorpe Hall, which stood by the side of the lake, about 200 yards S. of the present house. In Gawthorpe Hall the Gascoignes lived for a considerable time, and the chief cient mark of his resentment. Mr. justice was born there. It afterwards

passed to the Wentworths, and the great Lord Strafford occasionally made it his home in early life, delighting much (as his letters prove) in the heauty and retirement of the place. "Lord!" he writes to Abp. Laud. Aug. 17, 1636, "with what quietness in invself could I live here, in comparison of that noise and labour I meet with elsewhere; and I protest put up more crowns in my purse at the year's end too!" Afterwards the notorious Sir John Cutler bought itthe Cutler of Pope ('Moral Essays,' ep. iii.):--

"Cutler saw tenants break and houses fall; For very want he could not build a wall. His only daughter in a stranger's power; For very want he could not pay a dower. A few grey hairs his reverend temples crown'd.

'Twas very want that sold them for two pound.

What e'en denied a cordial at his end, Banish'd the doctor, and expell'd the friend? What but a want, which you perhaps think

Yet numbers feel—the want of what he had!

Cutler and Brutus, dying, both exclaim,
'Virtue and wealth! what are ye but a
name?"

The present Harewood House is one of those porticoed houses of the last cent. which are "so thoroughly English and aristocratic that one is inclined to overlook their defects of style in consequence of their respectability and the associations they call up."—Fergusson. Some alterations were made in the house by the late Sir Charles Barry. The interior is fine and stately, with ceilings painted by Zucchi, Rose, and Rebecci; and besides, a few good pictures by Revnolds, Lawrence, Hoppner, and Jackson. The Gallery, a noble apartment 77 ft. by 24, contains a collection of china, valued at 100,000k. It is for the most part Sèvres, old Dresden, and Celadon. Finer than anything in the house, however, is the view from the terrace. The gardens and pleasure-grounds are extensive and very beautiful, and the park, of about

2000 acres, is well wooded and picturesque. Both grounds and gardens were originally laid out by "Capability" Brown, but have since been much altered and enlarged. principal garden, on the S. side of the house, was designed by Nesfield. and is wonderfully striking when in full blaze of colour, with enclosing "walls" of shrubbery and wood. One of the vineries, 70 ft. by 26 ft.. is entirely filled by a vine of the "Tokay" species, planted in 1783. and still a vigorous bearer. A summer's day may be spent very agreeably at Harewood.

Returning to Arthington, the next

11½ m. Weston. A little beyond it Great Almes Cliff is seen 1. (see Rte. 20). Passing

15 m. Pannal Stat., the train soon reaches

18 m. from Leeds, Harrogate (see Rte. 20).

ROUTE 30.

LEEDS TO SKIPTON: A. BY OTLEY
AND ILKLEY (BOLTON PRIORY,
WHARFEDALE).

RAIL (Midland) as far as Ilkley. from Wellington Stat. 10 trains daily to Ilkley: time, 35 min. to 1 hr. To Otley, 6 trains.

From Ilkley to Skipton coach road.

Rte. 34, as far as

Calverley Stat.

Guiseley Junct. Stat.

Guiseley, a large village with some worsted-mills, has a ch. with Norm., Trans. - Norm., and E. E. portions, There is also a deserving notice. pretentious modern town hall. Hence a line diverges rt. to Otley.

Otley Stat. (see below).

FOtley may also be reached from Leeds by N. E. Rly., by Horsforth,

Arthington Junct. Stat. (see Rte. 29).

The view from the Arthington station up Wharfedale is fine, and the walk to Otlev (4 m.), following the broad stream of the Wharfe, fringed with fine trees, very pleasant.]

Otley (Inn: White Horse, indifferent) is still, as in the days of the poet Gray, "a large, airy town, with clean, but low, rustic buildings." It has several woollen factories and paper-mills; but the Church (restd.) alone need detain the tourist. During the restoration, fragments of a pre-Norman ch. were found in the Norman walls of the chancel; and it was discovered that a foundationwall ran directly across the ch. in a line with the W. walls of the transepts. This may have been the W. wall of the first ch. Then came a Norm, building, of which portions In the Perp. period the nave was built, and the nave-aisles were added about 1505. In 1851 the walls of the nave were raised and a clerestory added, thus making the chancel-arch seem low. The chancel-walls are Norm., and one Norm. window remains. The others are Perp. The S. door of nave has Trans.-Norm. shafts and caps. There are some modern stained-glass windows. At the end of the nave some fragments of stone carving, &c., are placed, the church, and built his own at found in the walls during the restora- | Bramham, which, it is said, is still

The present Route is the same as | tion of 1867. Others of the stones have interlaced knot-work. is a bird, holding a flower in the beak, and with a tail ending in a dart; under the bird is a nimbused head (St. John, with the eagle?). Another stone has 3 busts, each with a book, and each under a circ. arch. There are also some fragments of window balusters, resembling those found at Jarsow. All these fragments, from their early character, are of great interest.

> In the S. transept are some Fairfax monuments which should be noticed. The principal is that of Thomas, the first Lord Fairfax of Denton. stud there was one of the best in England. He was the father of Ferdinando Lord Fairfax, and grandfather of the great Lord, better known as Sir Thomas" (see Nun Appleton, Rte. 2). He died in 1640. His wife, Helen Aske, had died in 1620, and the inscription on the tomb may have been supplied by her husband. Under her figure are the lines-

'Here Lea's frytfylnes, here Rachel's beyty Here lyeth Rebecca's fath, here Sarah's duty."

"The figures," wrote Gray, "are not ill-cut, particularly his, in armour. but bare-headed."

There is another Fairfax monument (but not certainly appropriated) on the wall; and the tomb-slab of another has been brought here from the nave.

In the chancel is an elaborate modern monument for Walter Fawkes of Farnley, d. 1825, the friend and patron of Turner: and below it a curious shrouded figure for William Vavasour of Stead, near Ben Rhyd-There is also a tomb, said to be that of a Dinely, whose family held lands here and at Bramham; but one of them coming to Otley church on Easter Day, would not kneel to receive the Sacrament, left during the excavation of the Bramhope tunnel.

The Manor House, a modern building, occupies the site of a palace of the Archbishops of York, who were

lords of Otley.

Overhanging the town, S., is the long hill of Otley Chevin (pron. "Shevin," or "Shiven." It is perhaps the Brit. Cefn, a back or ridge. The Cheviots, and Chevening in Kent, have been referred to as from the same word, though doubtfully). The highest point near the W. end is 925 ft. above the sea, and commands a magnificent view. York Minster 30 m. distant, is easily distinguished in clear weather. Southward the smoke of Leeds, and of all the manufacturing district towards Halifax. clouds the sky; but towards the N. and N.E. a vast extent of rich country lies mapped out below the spectator, with the Wharfe winding through its broad green vale. The view from Otley Chevin is an excellent introduction to the picturesque scenery of Upper Wharfedale.

[11 m. N. of Otley, is Farnley Hall, the seat of Ayscough Fawkes, Esq., who has here a very fine collection of pictures, including some of the most admirable works of J. M. W. The uncle of the present Turner. proprietor was one of Turner's earliest and best patrons: and the artist was for some time in the habit of working on water-colour drawings for Mr. Fawkes whenever he had spare time and opportunity. He was a constant visitor at Farnley, and to this connection we are indebted for most of the wonderful drawings by which the great artist has illustrated Wharfedale and the N.W. of Yorkshire. "The scenery," writes Mr. Ruskin, "whose influence I can trace most definitely throughout his works, varied as they are, is that of Yorkshire. . . . His first conceptions of mountain very grand; the Devil's Bridge, Mt.

unconsecrated. In the ch. is a me-1 scenery seem to have been taken from morial of 54 labourers who perished Yorkshire, and its rounded hills, far-winding rivers, and broken limestone scars to have formed a type in his mind to which he sought, so far as might be obtained, some corresponding imagery in other landscapes. Hence he almost always preferred to have a precipice low down upon the hill-side, rather than near the top: liked an extent of rounded slope above, and the vertical cliff to water and valley better than the slope at the bottom and the wall at the too: and had his attention early directed to those horizontal or comparatively horizontal beds of rock which usually form the face of the precipices in the Yorkshire dales, not, as in the Matterhorn, merely indicated by veined colouring on the surface of smooth cliff, but projecting or mouldering away in definite succession of ledges, cornices, and steps."---Modern Painters.

> Farnley Hall and its treasures can only be seen by special permission of the owner. After passing a bridge over the Wharfe, near which is a weir, the lodge is reached, and a drive of perhaps a mile through woods leads to the house. The woods are noticeable for many spruce firs of great size. The house is partly Elizabethan. but the older parts are concealed by a modern house built by Carr of York. It stands on high ground, and commands fine views of Wharfedale and the Chevin. The drawing-room was painted by Le Brun. In the salonn are arranged about 50 drawings by Turner, some of them of considerable size. Remark, especially, Scarborough; the Strid at Bolton, very fine, with a distance of extreme beauty, and a grand rush of water in the foreground; the Pass of Mt. Cenis, with a snow-storm.—Turner was himself present at the accident represented, when the horses of the diligence turned round, close to the precipice; at Putney Bridge, figures,

a grand Swiss waterfall: Lancaster Sands, very fine; a remarkable sketch of a man-of-war, drawn, between breakfast and luneheon, at Farnley, at the request of Mr. Fawkes: View of Wharfedale, from Otley Chevin; some Views of Farnley; the High Force; Fountains; besides many early pictures, one marked 1804. But every one of these drawings will repay the most careful attention, and it is difficult, when all are so fine, to make any selections. In the Library is a very grand picture, attributed to Velasquez, and representing the Magdalenc at the foot of the Cross a picture alone worth a long pilgrimage to see. Here also are—the Grecian daughter, Rubens (on panel); a Holy Family, by Sir Joshua Reynolds (painted in Italy); and a portrait of Lord Cottington, by Janssens. The Drawing - room, among other good pictures, contains the following oil pictures by Turner:—the Pilot-boat; a Calm; a Fresh Gale; the Lake of Geneva; the 'Victory,' with the body of Nelson on board; and, grandest of all, the Haven of Dort. This last is a large picture; a ship in foreground, with boats approaching and departing. The light, the air, the movement, in this picture are marvellous. It is Turner at his very best. Pilot-boat is hardly less striking. The pilot, standing up in his boat, is waving a farewell to the ship he has left, in which sailors are busy. A burst of light from a fine, broken sky falls on the sails of the vessel. The Victory is grand, with an inky sea reflecting the black clouds only half-seen above. In this room are also a full-length of the Duchess of Aremberg by Vandyck, very fine (the companion portrait of the Duke is at Holkham); a Mignard portrait of a young lady; a good Greuze; and an unfinished portrait by Sir Joshua. A curious picture by Turner, full of fine colour - Rembrandt's have been formed for the water-sup-Daughter reading a Letter-should ply of Leeds. The little ch. of Stain-

St. Gothard; and a finer companion, I be noticed as an example of his wonderful versatility.

In a portfolio are preserved some very interesting drawings of birds, made by Turner during his visits to Farnley. An owl and a turkey arc especially excellent, and in all, the wild expression is admirably caught without any "semi-human" addition. In small cases are some drawings by Turner for illustrating a set of poets —those for Sir Walter Scott the best. The extreme power and versatility of the artist, and his sharp insight into the character of a scene (remark the waterworn rocks, the hollows and linings, of the Strid drawing), are nowhere more strongly shown than at Farnley. The Turner drawings have been excellently photographed by the Messrs. Caldesi.

In the hall, with a good old chimney-piece of carved oak, are one or two pictures by Snyders, set in the panel. Here too are arranged Oliver Cromwell's hat, worn at Marston Moor, with his watch and sword: the swords of Ireton and Fairfax (the latter straight, with a basket-hilt inlaid with silver); a chair which belonged to Fairfax: a drinking-horn manufactured from his shoe; and the matrix of a seal, cut by order of the Commonwealth "for the approval of ministers" (this seal was formerly preserved at Browseholm, in Ribblesdale, see Rte. 33). The curious gateway, leading to the garden, was brought from Menston, the seat of Col. Fairfax. Half a mile higher up is the Chapel, a fragment which retains only a chancel, dating from the 13th centy.

Leathley Church, close without Farnley Park, has a very early Norm. tower; massive and high in proportion to its area, built of rubble with wrought coigns. The rest of the ch. is late Perp. In the valley of the Washburn, which here descends to join the Wharfe, large reservoirs portions, and a picturesque bellgable.

The Midland Rly. proceeds from Otley to Ilkley, on the rt. bank " Whordals .- for," of the river. writes the poet Gray, "so they call the vale of Wharfe, and a beautiful vale it is, - is well-wooded, well-cultivated, and well-inhabited, but with high crags at distance, that border the green country on either hand: through the midst of it. deep. clear, full to the brink, and of no inconsiderable breadth, runs in long windings the river."

Burley Stat. A village with large worsted-mills, and an ugly modern ch. Nearly opposite, on the rt. bank of the Wharfe, is Weston Hall, long the seat of the Vavasours, and still possessed by their representative in the female line. It is a good example of a considerable Yorkshire proprietor's house, temp. Jas. I. Besides an original portrait of Cromwell, a great collection of Vavasour papers is preserved here, beginning with a grant of free-warren, temp. Hen. III. In the garden is an unusual relic-a "casino," or pleasure - house of 3 stages, with an upper turret. of the same date as the mansion.

11 m. beyond Burley, across the river, is seen Denton Park, a modern house by Carr of York, occupying the site of the ancient hall of the Fairfaxes, who became possessed of Denton about 1515, by the marriage of Sir William Fairfax to the heiress of John Thwaites. Thomas Lord Fairfax (created Baron of Cameron for his bravery before Rouen in 1605) lived and died here. His son, Ferdinando, and his grandson, the famous Sir Thomas of the Parliament, were both born at Denton, and Edward Fairfax, the earliest and best translator of Tasso, was born here about 1570—the natural son of an

burn, 2 m. N.E., has some Norm | earlier Sir Thomas Fairfax, who was present with the Constable Bourbon at the sacking of Rome in 1577 (Edward Fairfax lived afterwards at Fewston, in the valley of the Washburn, at the back of Denton). Prince Rupert, on his way to Marston Moor. lodged in the old house, and, finding in it a portrait of John Fairfax (younger brother of Lord Fairfax). who had fallen at the siege of Frankenthal in the Palatinate, spared, for his sake, the home of the great Puritan leaders. The estate of Denton was purchased from the Fairfaxes by the Ibbetson family, wealthy clothiers of Leeds; one of whom, in 1745, raised a troop in defence of the Crown, and was rewarded with a baronetcy.

> Ben Rhydding Stat. (see post). and the rly. soon reaches its terminus

Ilkley Stat. (terminus).

Hotel: the Crescent, best and reasonable; board and living in public rooms, 31.3s.a week; the Middleton H.; Royal H. Hydropathic Establishments—these are at some little dis-Establishments—these are at some interests that of the moor, see post — Ben Rhydding; likley Wells House (at these, board and lodging for each visitor, not a patient, is 31, a week). Craiglands and Troutbeck are cheaper. At all, visitors are received who are not patients. (A different charge is made for them.) All have a table-d'hôte and public rooms. All the "Establishments" stand pleasantly and command fine views; see further, post. There are many private lodgings in the village.

Carriages of all sorts may be hired at the rly. stat. or at the Hotels. Tickets for fishing in the Wharfe to be had at the Crescent, 2s., 6d. a day. Ilkley is much used as a place of winter resort by the inhabitants of Bradford and other large manufacturing towns.

Ilkley, the Malvern of the North, stands very pleasantly on the S. bank of the Wharfe, at the base of Rumbald's Moor. It derives its importance wholly from the water-cure establishments which have established in its immediate neighbourhood. These are large and wellconducted, and afford most pleasant

resting-places to all who desire to works) have existed near likley, but explore this portion of Wharfedale. The open moors at the back, with their broken rocks and low cliffs of millstone grit, are easily accessible and command fine views. Bolton Abbey, Skipton, Settle, Malham Cove, and Gordale can be visited from here, and altogether Ilkley will prove a very convenient centre for the tourist.

Ilkley is without doubt the "Olicana," ranked by Ptolemy among the "cities" of the Brigantes. It is not mentioned in the Antonine Itineraries or in the Notitia. On the site, or in the immediate neighbourhood of the British town, the Roman fortress was constructed, the foundations of which are still traceable, W. and N., between the Wharfe and a brook which falls into it. The enclosure, a steeply scarped plateau, commanding, and only just raised above, a long reach of the beautiful river, formed a square of about 160 by 100 vards. The existing parish ch. stands within it; and, in a field at the back, a fragment of the Roman wall is visible above the sward. Roman relics-brick, glass, pottery-are constantly found here, and Camden has preserved some inscriptions discovered at Ilkley, one of which records the rebuilding either of the town or of some important edifice in it, in the days of Severus and Antoninus (Caracalla); and another is the dedication of an alter to "Verbeia," the genius of the Wharfe-"Verbeise secrum Clodius Fronto Præf. Coh. II. Lingon." This altar is still preserved at Middleton Lodge (on the hill side above the river, opposite Ilkley), but the inscription has become illegible. "Verbeia" is no doubt the Latinized form of the British river name, which became "Guerf" or Wharfe under the Saxons. Roman roads have been partly traced, leading to Ilkley from Calcaria (Tadcaster), from Isurium (Aldborough), and (probably) from Cocceium (Ribchester in Lancashire). Heaps of

have been nearly all carted away to make roads. At Eldwick, on the S. side of Rumbald's Moor, toward Bingley, there are similar remains. Iron seems to have been the metal smelted here, as in other parts of the N. Riding.

Ilkley was long famous for its springs of clear cold water, and was frequented during the summer by many Yorkshire families, before 1843. in which year the land on which Ben Rhydding stands (the name is a corruption of Bean ridding, i.e. clearing, belonging to the field in which the house was built) was purchased by a Company with a view to the erection of a building in which the "watercure" system might be properly carried out. The house of Ben Rhydding was completed in 1844 (it has since been greatly enlarged), and at once proved a success. It stands about 11 m. E. of the village, on high ground, commanding very fine views, and is surrounded by extensive grounds, opening on the moor at the back, close under the "Cow and Calf rocks." Ilkley Wells House was built about 10 years afterwards (architect, Cuthbert Brodrick). Dr. G. Radford is the manager, and Dr. J. F. Little is the resident physician at Ben Rhydding; Dr. Leeson at Ilkley Wells. Ben Rhydding is a castellated building: Ilkley Wells is in the style of an Italian palace. Both are of imposing elevation. The arrangements are good and very comfortable; but visitors who are not patients must accept the simple but excellent table necessary in such an establishment. Each establishment contains Turkish baths, bowling-alleys, &c., and each has a regular tariff of charges for both patients and visitors.

There are other Hydropathic Establishments — Craiglands, Troutbeck, and Rockwood.

Ilkley Church, for the most part early Dec., has been restored, to the Roman scories (dross from smelting confusion of the antiquary, who has

no means of distinguishing old work from new. The chancel is entirely new, and contains a pictorial east window (the Crucifixion) by Warrington. At the W. end of the N. nave aisle is a curious new of carved oak (date 1633), with an open balustrade in front. In the S. aisle is the cross-legged effigy of Sir Adam de Midelton (temp. Edw. II.). He wears the long cyclas open in front, and projecting from his poleyns or kneeplates are small shields. (The effigy has always been assigned to Adam de Midelton, but the armour seems earlier than Edw. II .- perhaps circ. 1280.) The family of Midelton were settled at Middleton, a township with a few cottages opposite Ilkley, from a very early period, and are now the principal owners here. (Their residence is Middleton Lodge.) In the base of the Tower (N. side) is a fragment of Roman sculpture; and in the churchyard (fronting the road) are 3 remarkable Sculptured Crosses (the cross itself, perhaps of metal, may have been fixed on the top): "things antiquissimi operis," says Leland, "and monuments of some notable men buried there." These are upright pillars (the tallest 8 ft. high), rudely sculptured with scrolls, animals, birds, and the human figure. They no doubt date from a period before the Conquest, and deserve more careful preservation from the effects of time and weather than they have hitherto received. The sculpture resembles that in the fragments in Otley Ch. (see ante); and there are crosses of similar character in the ch.-vd. at Whallev on the Yorkshire border (Rte. 33).

The Convalescent Home, built by Mr. Simon, a Bradford merchant, for 65 patients, is managed by the Cor-

poration of Bradford.

Very pleasant walks may be taken in all directions from Ilkley. Overhanging Ben Rhydding are the "Cow and Calf Rocks," a fine and most

commanding a magnificent view of Wharfedale. (The rock is the same of which Brimham Crags and Great Almes Cliff are composed. See Rte 21.) On the face of the "Cow" is a mark called the "Foot of Giant Rumbald." who, in stepping across from Great Almes Cliff, missed his hold, and stamped the face of the rock instead of the summit. The rocks are covered on the top with names and inscriptions, which vulgarize but cannot The view from them is spoil them. fine, extending to Barden Moors and the hills near Settle. Near them are some quarries, which show the soft millstone grit as it is first raised. blackens with exposure, giving a peculiar darkness to the blocks scattered among the fern and heather of The so-called "Panothe moors. rama " Rock, some distance beyond Ilkley Wells house, commands a wide view of the hills N. of Bolton and Skipton. Above Panorama Rock, and a little W. of it, is a stone covered with the cup and ring marks which have been found in such numbers in Northumberland and in Scotland. Rumbald's Moor (the highest point 1323 ft.) is well worth climbing. Ingleborough and Whernside are seen from it; northward, Brimham Rocks and How Hill, over Fountains Abbey; the great plain of York, and York Minster itself, E., with the Wolds beyond; S.E., part of Leeds, and, more S., Bradford are visible. Rumbald's (generally called Romell's or Rumble's) Moor was so named, apparently, from William de Romillé, the first Norman lord of Skipton. It extends almost uninterruptedly to that place. There is a British intrenchment on the side of the moor, about 2 m. S.E. of Ilkley, and many barrows. The walk or drive from Ilkley to Keighley (Rte. 34), across Rumbald's Moor, is about 7 m., and is pleasant, with fine views.

Other walks may be, to Hollis Hall, on the Skipton Road (11 m.), picturesque "edge" of millstone grit, the old house of the Hebers; the Bp. of Calcutta belonged to a branch of | Hill-it is 4 m. from Ilkley)-a lofty this family. It is now a rather picturesque farmhouse, with gabled end and mullioned windows. A gate nearly opposite opens to a "gill, through which descends a "beck," which the pedestrian may follow to Rumbald's Moor. The scene throughout is pleasing, and on the moor the beck becomes wild and broken. scend on Ilkley by the Keighley road. The so-called Fairy Dell, 3 m. from Ilkley, above the hamlet of Middleton, is a narrow wooded glen, with a profusion of wild flowers, and is The Black Fors, a worth a visit. waterfall in Langber Gill (3 m.), is picturesque.

Ilkley to Skipton.

The rly. does not go beyond Ilk-The direct road to Skipton is 9 m.; but tourists who intend to visit Bolton Priory, and the beautiful scenery on the Wharfe between the Priory and Barden Tower, should proceed to Ilkley Bridge, where there are two roads, each leading to Bolton. The main road is on the same side of the river as the hotel, the other across the bridge. The latter keeps nearer to the river, and follows its windings, but is muddy in wet weather, and rather longer. It is well to go by one and return by the other, and this should be made a matter of bargain with the driver before starting. The distance to the Priory is 6 m. from Ilkley. Addingham Church, on the main road to Skipton, l. of road to Bolton Abbey, and 2 m. from Ilkley, is for the most part Perp., but has a Norm. chancel arch. The Perp., on a very small scale, resembles that of Harewood (Rte. 29), and, like that, was the work of the Bolton monks, to whom the ch. belonged. The road from Addingham follows the valley of the Wharfe, and the scenery soon becomes very striking. Left is Farfield Hall (J. C. Kay, Esq.). Beamsley Beacon (the old name is Howber [Yorkshire.]

hill (1314 ft.), the form of which will at once recall many of Turner's Wharfedale drawings—is conspicuous More distant, in front, is Simon Seat (1593 ft.) (see post), with the upper part of Bolton Park. From the top of Lobwith Hill a view is obtained of the Priory ruins by the river-side. (A road, rt., over Bolton Bridge, leads to Beamsley, where is an hospital for old women, founded, temp. Eliz., by Margaret Clifford, Countess of Cumberland. The old portion of the building was circular, and the rooms of the mother and sisters could only be approached through the chapel. Modern buildings have been added.)

The Devonshire Arms Hotel, rt., is a good Inn, usually charging hotel prices, and often full in season, but proprietor finds rooms in the neighbourhood when this is the case. may be used for a day or two as a resting-place by those who desire to explore the Bolton scenery at leisure. But the visitor who desires to make himself really acquainted with this country should establish himself in one of the farm-houses of the neighbourhood, many of which take lodgers. About & a mile beyond the Devonshire Arms are the houses of the guides to the Priory and to the woods.

The first view of Bolton Priory is scarcely less interesting or impressive than that first obtained of Rievaulx or of Fountains. Whitaker compares the situation, with some justice, to that of Tintern; but even Tintern has less of the delicious seclusion and repose which are the great characteristics of Bolton. ruins stand on a patch of open ground. round which the Wharfe curves after emerging from the narrow wooded glen between the Abbey and Barden Tower. Much wood—chiefly large oak and ash-trees—clusters about the ruins and the river bank; and across

the Wharfe, immediately opposite the ch., rises a steep rock, painted by Turner; in Whitaker's words, "of the richest purple." Downward, the stream is bordered by quiet green meadows. At the back the valley is grandly closed by the hills of Simon Seat and Barden Kell

Seat and Barden Fell. In 1120 (nine years before the first Cistercian house was established in Yorkshire) William de Meschines and his wife Cecilia de Romillé founded a priory for Augustinian Canons at Embsay, 2 m. N. of Skipton. 33 years afterwards the canons were removed to Bolton by William Fitz Duncan and his wife, another Cecilia de Romillé, the only child and heiress of the founders of the house at Emb-The only child and heir of William FitzDuncan and the second Cecilia was the "boy of Egremond" (so named, suggests Whitaker, from one of his grandfather's baronies. where he was probably born), whose unhappy fate, according to the local tradition recorded in Wordsworth's well-known poem, was the cause of the removal of the Priory to Bolton. Leading a hound in a leash, he attempted to spring across the "Strid," in Barden Woods (see post); but the dog hung back, and the boy was dragged into the stream and drowned :-

"Now there is stillness in the vale, And deep, unspeaking sorrow; Wharfe shall be to pitying hearts A name more sad than Yarrow."

The forester, who had witnessed the boy's fate, met his mistress with the words, "What is good for a bootless bene?" (i.e. a hopeless prayer)—

"And she made answer, 'Endless sorrow,'
For she knew that her son was dead.

Long, long in the darkness did she sit, And her first words—' Let there be In Bolton, on the field of Wharfe, A stately Priory.'

The stately Priory was reared; And Wharfe, as he moved along, To matins joined a mournful voice, Nor failed at even-song."

It is cruel to question a tradition round which such associations have gathered; but the fact is, that the "boy of Egremond" is himself a witness to the charter by which Cecilia de Romillé granted Bolton to the canons in exchange for their manors of Skibdun and Stretton; and we can only suppose either that the first house at Embsay may have been founded after the death, possibly by drowning in the Wharfe, of one of the sons of the first Cecilia de Romillé (she had two, both of whom certainly died young),-or that the "boy of Egremond" was drowned after the grant of Bolton, and that the canons made his death a pretext for changing the site of their house to their lately acquired possession. The establishment at Bolton consisted of a prior and about 15 canons; more than 200 persons altogether (servants, lay-brethren, &c.) being supported here. (Whitaker. Hist. of Craven.) The most important events in the history of the house were the frequent spoliations of "land and gear" by the Scots, between the years 1316 and 1321. In 1316 the Prior fled into Lancashire, and many of the canons took refuge in Skipton Castle, whither they drove some of their cattle. In 1320 they were again obliged to disperse, and the "moveables" from the Priory were conveyed to Skipton. Prior de Land (1275-1330), who witnessed all these calamities, had himself built the Prior's Lodgings and Chapel: and in the course of his long priorate entertained at Bolton two Abps., Greenfield and Melton. made two journeys to Rome, and attended 3 Parliaments. At the surrender of the house in 1539 its annual rental was 298l. 15s. 11ld. In 1542 the site and demesnes were sold to Henry Clifford, 1st Earl of Cumberland, for 2490L From the last Earl of Cumberland it passed, with his daughter and heiress, to the 2nd Earl of Cork, and thence by descent to William

Duke of Devonshire, whose representative still possesses it.

The chief relic of the Priory is the Church, the nave of which, after the Dissolution, was retained as the chapel of the so-called "Saxon Cure." (This Saxon Cure seems to represent a certain part of the ancient honour of Bolton or "Boltune" (A.S. botl, a hall,—the hall town), which had belonged to Earl Edwin before the

Conquest.

The nave is perfect, but the rest of the ch. is in complete ruin. The lower walls of the choir are Trans.-Norm. The upper walls and windows (the tracery of which is destroyed) are Dec. The nave is E. E. and Dec. The original west front remains within an elaborate Perp. front of excellent design, intended as the base of a western tower, which was never finished. was the work of the last Prior, Richard Moyne or Moon (Inst. 1513), whose inscription remains on the cornice of the tabernacle work below the window. "In the ver of our lord MVCXX. R. \equiv " (the half-moon is the Prior's rebus) " begaun thes fondacoon on qwho sowl God have marce, Amen." In the spandrils above the portal are the arms of Clifford and of the Priory (g. a cross patonée), and on the sett-off of the buttresses are, on the S. side, a figure which may possibly represent a pilgrim; on the others seated dogs. (Prior Moon was master forester to the Cliffords; and Whitaker suggests that the dogs may indicate this office.) It is said that long after the Dissolution the crane which had been used in building this tower remained fixed in its place, and that the people of the district could not be persuaded but that the canons would return to their ancient home to complete the work.

The nave (which has been restored by the Duke of Devonshire, under the direction of Crace)—the

> "One protected part In the shatter'd fabric's heart"—

is E. E. on the S. side and Dec. on The windows on the S. side, the N. with a wall passage along the base of the lights, deserve notice. (The glass in them is modern, by Crace.) The triforium, or wall-passage, communicated with the dormitory of the The windows on this side are high in the wall, in order to give room for the cloister which extended without. There is no S. aisle. N. aisle is divided from the nave by piers alternately cylindrical and octagonal. There is a clerestory of plain lancets, and the aisle windows, retaining some fragments of 13thcenty. glass, are Dec. The roof, of flat oak work, was probably the work of Prior Moon, and was "painted, like most of the roofs in Craven about that time, with broad lines of minium."—Whitaker. Unfortunately it has been renewed, and not according to the ancient design. The plain wall which closes the E. end has been replaced by a handsome reredos, the old Roodscreen repaired placed at the W. end, the area filled with open oak seats, all at the Duke's charge; and the stone pulpit, lectern and font, are his gifts.

At the end of the nave aisle, enclosed by a Perp. screen, is a chantry founded by the Mauleverers, and below it the vault in which, according to tradition, the Claphams of Beamsley, and their ancestors the Mauleverers, were interred upright:—

" Pass, pass who will you chantry door, And through the chink in the fractured floor Look down, and see a griesly sight; A vault where the budies are buried upright!

There face by face and hand by hand The Claphams and Mauleverers stand; And in his place among son and sire Is John de Clapham, that tierce Esquire, A vallant man and a name of dread In the ruthless wars of the White and Red; Who dragg'd Earl Pembroke from Banbury

church,
And smote off his head on the stones of the porch."—White Doe of Ryistone. I.

Whitaker, however, could never see this "griesly sight" through the

2 c 2

chink; and it is perhaps altogether traditional.

Leaving the nave, the ruined portion of the ch. is entirely Dec., with the exception of the lower walls of the choir. The transepts had eastern aisles. The N. transept is nearly perfect; the S. retains only its western wall, in which are 2 Dec. win-In this transept is the tombslab, with incised figure, of Christopher Wood, 18th prior, who resigned in The piers of a central tower 1488. remain: but at what period it was destroyed, or if it was ever completed, is uncertain, although Wordsworth has made

"From Bolton's old monastic tower
'The bells ring out with gladsome power."

The choir is long and aisleless, and is lighted on either side by 5 3-light windows, only one of which retains its Dec. tracery. Some fragments of tracery remain in the E. window, which was a very fine one. the windows runs a Trans.-Norm. arcade. In the N. wall is an arched recess, either for the Easter sepulchre, or an actual tomb. Some portions of tomb-slabs remain in the choir, one of which is thought to have commemorated John de Clifford, killed at Meaux in the 10th year of Henry V. A very beautiful view, looking across the choir, through its S. door, should be especially noticed. On the S. side of the choir were 2 chapels, extending to about half its length. One of these was beyond doubt the "resting-place" of the Lords of Skipton and patrons of Bolton.

Of the conventual buildings the remains are too scanty to be of much interest. As usual, the cloister court was on the S. side of the nave, and round it were ranged—W. the dormitory, S. the refectory, and E. the chapter-house and prior's lodgings. There was a second and larger court beyond this, in which were various offices. An arch remains, once opening to the vestibule of the chapter-

house—(it makes an admirable frame to the picture seen through it on either side)—and the parsonage occupies the site of the monastic kitchens.

The Churchyd. lies on the N. side of the ruins. This has been made classic ground by Wordsworth's poem. in which he has preserved a tradition that, not long after the Dissolution, a white doe "made a weekly pilgrimage from Rylstone over the fells of Bolton, and was constantly found in the churchyd during divine service, at the close of which she returned home as regularly as the rest of the congregation."-Whitaker. The connection of the doe with the Nortons of Rylstone is due entirely to the poet, whose verse has given a fresh interest to even Bolton.

The Priory Barn, with some curious timber work, is still used, and is

worth a visit.

Bolton Hall, the Duke of Devonshire's house, which stands a short distance W. of the ch., is entirely modern, with the exception of the central portion, which was the gatehouse of the priory. The hall, which has been formed out of the ancient archway, is represented in Landseer's well-known picture. The house is sometimes shown, and contains a few pictures and portraits of some interest, the principal being-the Cobham family, on canvas, a repetition of the panel picture at Longleat. is dated 1567, and represents Wm. Brooke, Lord Cobham, d. 1596, and his second wife Frances Newton, with Johanna her sister, standing behind a table, round which 6 children are The child numbered 6 is the seated. son who died so miserably in the reign of James I. This picture is attributed to Lucas de Heere: George Calvert, 1st Lord Baltimore, bust, in falling frill; Henry Clifford, 5th and last Earl of Cumberland, in armour; Anne Clifford, Countess of Dorset, Pembroke, and Montgomery, in advanced life, dated 1672,—a striking

F ...

picture; Richard Earl of Burlington (the architect), to the waist, hat under arm; Lord Charles Clifford, eldest brother of the 2nd Earl of Burlington, died young in 1675, full length, in richly jewelled dress, as a hunter with two dogs and a javelin.—Lely, who painted many of the youthful nobility with dogs, in this fanciful hunting costume. This is the portrait said to represent the "Boy of Egremont," a notion which has arisen from its accessories.

The woods and walks of Bolton are freely open, except on Sunday. scenery between the priory and Barden tower, where the Wharfe, for a distance of about 2 m., runs through a deep-wooded ravine, is of "finest and most rememberable" character. The walks and drives through the woods were for the most part arranged, early in the present century, by the Rev. William Carr. who, in Wordsworth's words, "has worked with an invisible hand of art in the very spirit of nature." These walks are indeed so numerous that (especially if the visitor's time be short) it will be better for him to be accompanied by a guide. A carriageroad ascends the rt. bank of the river as high as the "Strid" (the favourite spot for picnics, much thronged in the season, and therefore not that which the visitor should make his own resting-place); beyond, footpaths wind through the woods up to Barden Tower. (There is also a road on the l. bank of the Wharfe, which may be gained by steppingstones across the river near the E. end of the church. Carriages cross further down.)

[Across the river, and climbing the side of Simon Seat (1593 ft.), is Bolton Park, the ancient deer-park of the Cliffords, still marked by its venerable oaks, and still the home of numerous red-deer, descendants of the old stock. From Simon Seat, above it, there is a magnificent view

in clear weather, embracing, it is said, York and Ripon Minsters, and Roseberry Topping beyond the Cleveland Hills. There is a very fine foreground toward Appletrewick. Simon Seat (the name no doubt is that of the Northern hero, Sigmund, found elsewhere on boundary ridges-see Rte. 14) may be reached either through Bolton Park or from Barden. The latter is the easier route. summit is of millstone-grit. may reach Simon Seat from Park Gate Seat, in Bolton Woods, overhanging the river, as follows. down from Park Gate Seat to a stream and bridge; cross and proceed up the so-called " Valley of Desolation" (up the stream) to a waterfall about 50 ft. high; there is a second fall of 30 ft.; and this walk up the stream is worth taking. A little below the second fall, l., turn off and get over a fence, beyond which an old cart-track will be seen, and must be followed upwards for 1 m. to a gate opening on the moor. A rough track on the moor leads to a beck, which must be crossed, and then a well-defined footpath climbs to the top of Simon Seat.)]

The scene at the Strid (certainly not so named from its being possible to stride across it, but from the A.-S. stryth=turmoil, turnult) is exceedingly fine, especially after rain. The river is here hemmed in between ledges of rock, and roars below like an angry "Kuhleborn." The story of the boy of Egremont has already been questioned; but we may believe, if we choose, that some life dear to the founders of Embsay or of Bolton was lost at this place. The scene is in great favour with artists —who would find subjects far less well known, and of extreme beauty, in different parts of the woods, and in Upper Wharfedale—and a beautiful drawing of the Strid by Turner (see ante) is preserved among the treasures of Farnley Hall. The woods

here are for the most part of oak and I when nearly 60, and led the "flower ash. The absence of holly and birch is very marked, especially when the scene is compared with those afforded by deep-wooded valleys of a similar character in Scotland or on the borders of the Devonshire moors. Paths. all beautiful and all worth tracing, wind through the woods and along the hill-sides; and a little beyond the Strid, Barden Tower rises beyond the valley, backed by slopes of hea-"Grey tower-like projections of rock, stained with the various hues of lichens, and hung with loose and streaming canopies of ling, start out at intervals," as when Whitaker composed his word-pictures; and the Wharfe, rocky and whitened with foam, as it has been all the way from Bolton, is a good guide to the bridge below the old tower of the Cliffords.

Before the restoration to his estates of Henry Clifford the "Shepherd Lord," on the accession of Henry VII., there seems to have been a small lodge or tower at Barden for the protection of the keepers,—one of six which existed in different parts of Barden Forest. (This forest comprised the greater part of the township of Barden, and was attached to the Honour of Skipton.) The Shepherd Lord, whose early life among the Cumberland Fells led him to seek quiet and retirement after his restoration, preferred Barden to his greater castles, and enlarged (or rather rebuilt) it so as to provide accommodation for a moderate train of attendants. He spent the greater part of his life here, and the neighbouring canons of Bolton assisted him in his favourite studies—astronomy and alchemy. At Barden the old teachers of his youth, as Wordsworth has numbered them. were still close at hand :--

"Love had he seen in huts where poor men His daily teachers had been woods and rills, The silence that is in the starry sky-

The sleep that is among the lonely hills."

of Craven:

" From Penigent to Pendle Hill, From Linton to Long Addingham. And all that Craven coasts did till. They with the lusty Clifford came."

This "good Lord Clifford." as he was sometimes called, died in 1523. probably at Barden, and seems to have been buried in the choir of Bolton Priory. After his time Berden was still occasionally inhabited by the Clifford Earls of Cumberland. but it had fallen into decay when the famous Lady Anne Clifford, "Countess of Pembroke, Dorset, and Montgomery," restored it in 1657. inscription she placed over the gate (still remaining and perfect) records that the tower "had lavne ruinous ever since about 1589, when her mother then lay in itt, and was greate with child with her, till nowe that it was repayed by the said Lady. Is, chapt. 58, v. 12. God's Name be Praised! The verse to which reference is made was placed by the Countess on all the castles she repaired. "Thou shalt build up the foundations of many generations, and thou shalt be called the repairer of the breach, the restorer of paths to dwell in." She kept possession of Barden till her death in 1676; but in the division of the Clifford estates Barden had passed to Lord Cork, and is now the property of his descendant the Duke of Devonshire. The ruin (Whitaker saw the house entire in 1774) is that of a large square building, the greater part probably of Hen. VII.'s time, with a chapel attached. A part of the adjoining the chapel still tower serves as a farmhouse, and lodgings are sometimes to be had here in The chapel is now only sunmer. accessible from without. Until 1860 the "Lord's room" opened into it. and served as a sort of gallery for the chief persons of the household. was the arrangement "restored," if He was present at Flodden in 1513, not first made, by Lady Anne Clifford; and it is to be regretted that it no longer exists. The texts still remaining on the wall of the chapel, which is without an altar (the pulpit is at the E. end), were perhaps chosen by her. They are from Prov. chap. xi. and xxxi. The view from the front of the chapel is very fine, and the whole position of the tower, with Barden Fell rising behind it, is most picturesque.

There is a small picturesque fall on the Gill-beck, which descends to the Wharfe a little N. of the bridge below Barden Tower. It will be desirable to return to Bolton on the left bank of the river. The paths lead by the Laund House, Posforth Gill, and the so-called "Valley of Deso-

lation."

[The road from Skipton to Pateley Bridge crosses the Wharfe below Barden Tower. It winds round N. of Simon Seat, from which point the view is very striking; and l. of the road is the Trouler's Gill, a narrow rocky path, well worth exploration, through which a stream descends to join the Wharfe. Nearer Pateley Bridge the road passes the lead-mines of Greenhow Hill. (See Rte. 21.)]

[The Wharfe, above Barden, should not be neglected. The scenery as far as Burnsall is wild and pleasing. Burnsall Church (the parish, owing to a division of the manor, rejoices in 2 rectors, 2 parsonages, and 2 pulpits) is Perp., with a low tower and a rude Norm. font. The ch. was well restored in 1859; when an inscription, formerly over the porch, was removed inside the tower. This records that the ch. " was repaired and butified at the onlie coste and charges of Sir William Craven, Kt., and Alderman of the Citie of London, and late Lord Mayor of the same, A.D. 1612."-This Sir William was a native of Appletrewick (or Aptrick), in this parish, who, a second Whittington, went to London under the Dissolution,

care of a common carrier, and afterterwards became Lord Mayor. His son, trained in the armies of Gustavus Adolphus and the Prince of Orange, was one of the most distintinguished soldiers of his time: and after fighting for the unfortunate Queen of Bohemia, is supposed to have been privately married to her on her return to England as a widow. "Thus," comments Whitaker, "the son of a Wharfedale peasant matched with the sister of Charles the First." He was created Baron of Hamstead Marshall by Charles I., and Earl of Craven (the first of that title) by Chas. II. At Burnsall the gritstone ceases, and the thick lower limestone. extending as far upwards as Deepdale Moor, gives a totally different character to the river-bed, which is contracted and rocky. For the Wharfe above Thresfield and Grassington, see Rte. 31.]

Barden to Skipton.

The scenery on the road (7 m.) is fine, and will repay the drive. opens at once on the moor, with a fine wide view N. and N.E. Barden Moor (1 m. from Barden Tower) are the reservoirs which supply Bradford with water and a village of workmen connected with them on the top of the hill. reservoir cost 200,000l. It is considerably higher than the old one. From the summit of a steep ridge the Valley of the Aire is opened, with Skipton below and Ingleborough, a grand dark mass, towering in the distance. An interesting relic is visible from here. A little below the topmost knob of the moor the heather terminates abruptly in a straight line; this is the old Leeds coach-road, now completely superseded by the railway. Embeay, the original site of the priory, afterwards removed to Bolton, is passed 2 m. from Skipton. No remains exist at present, but the canons had a cell and ch. there until the

Skipton. Inns: the Midland Hotel, near Stat.; Devonshire Arms Inn and Black Horse, commercial, in town. Pop. in 1881, 9091. Skipton is a stat. on the Midland Railway from Leeds to Carlisle. The old rhyme hardly now applies :--

"O, in Skipton in Craven ls never a haven,

But many a day foul weather.")-

It consists principally of one long and not very picturesque street, at the head of which are the ch. and the The houses are built chiefly of the sandstone or millstone grit from Rumbald's Moor, which blackens with age, and gives a peculiarly sombre appearance to the town. Skipton is famous for its cattle-markets. held once a fortnight. It is the "capital" of Craven; and as this part of the Valley of the Aire has always been regarded as one of the richest tracts in Yorkshire, the town partakes of the prosperity of the district. (Its name, Scepetone in Domesday, from Scep, A.-S. a sheep, must, however, have been given to it from the great sheep-walks on the hill-sides which bound the valley.) Skipton is a good point from which to visit Wharfedale—both the Bolton and Barden scenery, and that higher up (see the next route)—and the grand scenes at Gordale and Malham between Skipton and Settle. Rte. 32.)

(A mail omnibus so-called, but which is really a jolting cart with very uncomfortable seat, runs daily from Skipton to Buckden, through Grassington and Kettlewell, returning in the afternoon. This may help the tourist in going or returning, but will not allow him time to enjoy the country.) The town itself, however. contains nothing to interest, except the castle and the church.

The Deanery of Craven (the etymology is no doubt that suggested by Whitaker—Craig Vaen (British)

Sax, name of the Waventake, Stais Cliffe) extends from the sources of the Wharfe and the Ribble to the borders of Lancashire, stretching also along the Aire as far as Binglev. This tract of country, which comprises 25 parishes, contains some of the wildest and most picturesque scenery in Yorkshire, and, from the peculiar character of the limestone which almost entirely covers the deanery, it has been compared to Greece. (See Gordale, Rte. 32.) From the 12th to the 15th cent. nearly the whole of Craven divided between the two great houses of Percy and Clifford, and four monasteries — Bolton, Fountains, Barnoldswick (or Kirkstall), and Sallay. The head of the Clifford barony was Skipton.]

The Castle, which the tourist should visit before the church, is entered beneath a square tower, bearing the Clifford motto, "Desormais," in open letters, as a battlement. It is of 2 periods,—the round towers, connected by a curtain, dating from the reign of Edw. II.; the inhabited portion, E., from that of Hen. VIII. Skipton Castle is perhaps of more interest from its associations with the Clifford family than from its architectural importance.

History of Skipton.

William de Romillé, who obtained a grant of Earl Edwin's lands after the Conquest, removed the chief place of his honour from Bolton to Skipton, where the steep rock on which the castle stands offered a position of great strength and secu-From the heiress of Romille Skipton passed by descent to the wife of William de Fortibus, the great Earl of Albemarle. It descended in that house until the death of Aveline de Fortibus, who had married Edmund Plantagenet (Crouchback), son of Hen. III., in 1269, when the barony of Skipton passed to the Crown, and the "stony rock,"—translated in the so continued until the 1st of Edw. II.

That king bestowed it on his favourite, Piers de Gaveston, who held it but for a short time, and afterwards, in 1310, on Robert de Clifford, who had signalized himself in the Scottish wars under Edward I., was Governor of Carlisle, and "Dominus" (hereditary sheriff) of Westmoreland. He fell at Bannockburn From this time until the 17th cent, the estates of the Cliffords extended, with only 10 m. interruption, from Skipton to Brougham Castle, a distance of 70 miles. most noticeable of the house have been-the 8th lord, who fell at the battle of St. Alban's (83rd Hen. VI.), the "old Lord Clifford" of Shakespeare, although he was but 40 when he fell, a mistake to which we are at any rate indebted for a beautiful passage :--

"Wast thou ordained, dear father, To lose thy youth in peace, and to achieve The silver livery of advised age; And in thy reverence and thy chair-days, thus

To die in ruffian battle?"—

K. Hen. VI., Pt. II. act v. sc. 2.

His son, who thus speaks, is the "black-faced Clifford" who killed the young Earl of Rutland at Wakefield (Rte. 38), and afterwards himself fell at Ferrybridge (Rte. 2). His son was the "Shepherd Lord, who, after his father's death, and when the Cliffords had been attainted by the triumphant house of York, lay hid, by his mother's care, among the shepherds of Cumberland, and of Londesborough, in Yorkshire (see Rte. 8) for nearly 24 years, when the accession of Hen. VII. restored him to all his dignities. (See ante, Barden.) The next Lord, whose "ungodly and ungudely disposicion" is much complained of by his father, was created Earl of Cumberland by Hen. VIII. It has been conjectured, with some probability, that, during his early irregular life, he was the here of the ballad of the 'Notbrowne Maid: '-

"Now understand; to Westmarlande, Which is mine herydage, I wyll you bringe, and with a rynge By way of maryage I wyll you take, and lady make As shortile as I can.
Thus have you won an erlys son, And not a banyabed man."

See a note in Whitaker's 'History of Craven,' p. 256.

It was this first Earl who built the more modern portion of Skipton Castle (in the short space of 5 months) for the reception of his daughter-in-law, the Lady Eleanor Brandon, daughter of Charles Brandon, Duke of Suffolk, by Mary, Queen Dowager of France, the sister of Hen. VIII.: and it was in his time that Skipton Castle was besieged during the "Pilgrimage of Grace." The narrow escape of the Lady Eleanor has been duly recorded by Froude (H. E., iii. p. 142). When the insurrection broke out she was at Bolton Priory, either on a visit, or in sanctuary there. insurgents threatened, if Skipton Castle were not given up to them, to seize and outrage Lady Eleanor, and to kill her infant son and daughter. Christofer Aske, brother of Robert Aske, who, unlike him, had taken the King's side, had crossed the country to Skipton (the Earl of Cumberland was his cousin), and was in the castle. In the dead of night, with the vicar of Skipton, a groom, and a boy, he stole through the beleaguering camp, crossed the moors with led horses, by unfrequented paths, and brought back Lady Eleanor with her ladies safe through the besiegers into the castle. The siege continued for some time, but the castle was not taken.

The 3rd Earl, who "performed 9 viages by sea in his own person, most of them to the West Indies," and at his own expense, set out with a larger estate than any of his ancestors, and rapidly made it less. His only daughter and heir was the Lady Anne Clifford, who became Countess of Dorset, Pembroke, and Montgo-

mery, and who, after 38 years of | family discord, attained undisputed possession of the barony of Skipton. On the death of the 3rd Earl without heirs male, the earldom passed to Francis, "heir male of the 1st Earl." His son Henry was the 5th and last Earl of Cumberland. Until his death there was a constant struggle with the Lady Anne, heiress of the 3rd Earl, for the lands of the barony of Skipton, which the earls however managed to retain. Skipton Castle was besieged by the Parliamentarian troops under Lambert, Poyntz, and Rossiter, from Dec. 1642 to Dec. 1645, when it was surrendered upon articles. It had been held for the King (under the Earl of Cumberland) by Sir John Mallory of Studley, and during the siege the last Earl died and was brought to the church here for interment.

Of the famous Lady Anne Clifford, daughter of the 3rd Earl, born in Skipton Castle, Jan. 1589-90—the first great lady, not of royal birth, who can be said to occupy a conspicuous place in the history of English life and manners—the best and pleasantest account will be found in Hartley Coleridge's 'Lives of Northern Worthies.' She died, aged 87, in 1675—having passed the whole of her life, after she recovered her great inheritance, in her northern castles, which she restored and rebuilt. Her house, says Whitaker, was "a school for the young, a retreat for the aged, an asylum for the persecuted, a college for the learned, and a pattern for all." The poet Daniel was her tutor in youth. She showed that she had profited by his teaching when she erected the monument to Edmund Spenser which still remains in Westminster Abbey; and that she "could talk well on all subjects, from predestination to slea-silk," was testified by Bishop Rainbow, when he preached her funeral sermon. She settled the castle and honour on her

Earls of Thanet: and Skipton is still the property of their descendant. Sir Henry James Tufton.

The Castle.

Lady Anne Clifford, on recovering Skipton, found the castle and church almost in ruins, from injuries during and after the siege. She placed them in complete repair-as an inscription records over the inner en-It is there said that the castle " was pulled down and demolished almost to the foundations, by order of the Parliament"-but this is certainly an exaggeration. battlements of the outer gateway were added by Lady Anne; as were the roofs of the main castle, and its principal entrance. This entrance hides a Norm. portal, which seems to be the only portion of the castle of older date than the grant to Robert de Clifford. He, or his immediate successors, built the existing western portion of the castle,-a square, with massive round towers at the angles and in the sides. These are not very striking without; and perhaps the most picturesque scene is obtained in the inner court, where a yew-tree. growing in the centre, brushes with its dark green boughs the walls of the little quadrangle, and contrasts well with the reddish stone. On one side steps ascend to the hall, which. with its kitchens and adjoining offices, is a good example. An apartment in one of the round towers is pointed out as having been a " prison " of Mary of Scotland-who was never This Edwardian castle at Skipton. is uninhabited; adjoining it E. is the range of building erected by the first Earl of Cumberland (temp. Hen. VIII.) for the reception of the Ladv Eleanor Brandon. It consisted mainly of a long gallery—the usual appendage to a great house of that period -which during the last cent. was divided into smaller rooms. Thi two grandsons, who were successively part of the castle is inhabited, but

is usually shown to visitors. Lady | Anne Clifford lived in it during her visits to Skipton, making the octagonal room at the top of the great tower her bedroom. In it is some tapestry (temp. Hen. IV.), worth notice for the excellent examples of costume it affords. It is apparently Flemish, and represents the Vices and Virtues, with their several attendants. There is a marriage ceremony, in which the coffers filled with This room also gifts are curious. contains two portraits of the famous Lady Anne-when young and in advanced life-very bad pictures, but otherwise of great interest and deserving more careful preservation. large family picture of the 3rd Earl of Cumberland, his Countess, and two sons, both of whom died young, was also to be seen here, but has been removed to Otford, in Kent. His daughter, Lady Anne Clifford, caused this picture to be made, after the original portraits of these "honourable personages "-and composed (it is said, with the assistance of Sir Matthew Hale) the long inscriptions with which it is covered. the precincts of the castle was the chapel of St. John-now desecrated, and used as a stable.

On the N. side the castle overhangs a narrow valley, from which the rock on which it stands rises to a considerable height. A branch of the Leeds and Liverpool canal is carried close under this rock. Much limestone is embarked here, by means of tramroads, from the neighbouring quarries of Hawbank, worked on the body of the hill called the Haw.

Skipton Church, which belonged to the priory and convent of Bolton from the first foundation of their house until the Dissolution, closely adjoins the castle. It is for the most part Perp. and late, and is of little interest. It was restored 1854 and a reredos, designed by G. Scott, erected.

siege and was repaired by Lady Anne. who has left her name (which she was by no means slow to immortalize) on one of the pinnacles. The flat wooden ceiling is of Henry VIII.'s time, and the chancel screen came from Bolton Abbey, 1533. (The ch. was partly restored in 1853, after having been struck by lightning. The E. window, and one in the N. aisle, are by Capronnier, of Brussels.) Until the Dissolution the Cliffords seem to have been buried at Bolton (although none of their remains have been found there). Afterwards they had a vault under the altar of Skipton church. the Earls of Cumberland and their countesses are interred; and the monument, above, of the 1st Earl. was restored, and that to her father. George, the 3rd Earl, and last male of the Cliffords, erected, by Lady Anne. These monuments have been carefully restored, and the brasses and inscriptions on them are modern. The shields of arms at the sides of the altar-tombs are enamelled Lady Anne Clifford was colours. herself buried at Appleby.

The Free Grammar School was founded temp. Edw. VI., and has a vearly revenue of 600l. On the E. side of the town there is a saline sulphuretted spring, over which a pumproom and baths have been erected.

1 m. out of Skipton, on the Bolton road, is a large limestone quarry.

Skipton was the birthplace of the antiquary Holmes; and boasts of a more distinguished son in Lord St. Leonards.

Railways to Settle and Ingleton. leading to the Cave district and the mountains of Craven (Rtes. 32 and 34).

Rail to Colne, Burnley, Blackburn and Liverpool.

There is little to attract the tourist on this line, which has stations at Elslack, Thornton, and Earby, before crossing the Yorkshire border. A short loop turns N.W. The tower was shattered during the | beyond Earby to Barnoldswick, now

a large village. Here was the first | cient in Craven. It was settled a: foundation of the Cistercian abbey Kirkstall near Leeds. Henry de Lacv. "vir inter proceses regni notissimus," having made a vow during a dangerous illness, established the house here in 1147, and colonised it from Fountains. The monks called their new home "Mont Ste. Marie." Six years after their first settlement they abandoned Barnoldswick for Kirkstall, where the site had greatly approved itself to the abbot (see Kirkstall, Rte. 29). The parish ch. of Barnoldswick was then rebuilt (on the edge of a deep glen,-hence its name Gill Church), but at some distance from the former site. Portions of it are E. Eng., the tower Perp.

2 m. N.W. of Barnoldswick is Bracewell, the most ancient home in Craven of the Tempests. Some ruins of their old manor-house (of brick, temp. Hen. VIII.-there is part of an earlier stone building adjoining, in which is a room called "King Henry's Parlour") remain near the ch. This has Norm. portions: and, in the windows, many shields of arms of the Tempests and their quarterings. The Tempest motto, "Loyouf (love - perhaps a very ancient form in the Craven dialect) as thou fynds," also occurs frequently. On Howber and Gildersber, 2 heights beyond the manorhouse, are small square encampments. said to have been thrown up by Prince Rupert in his march through

Craven.

The high road from Skipton to Clitheroe passes (4 m. from Skipton) Broughton Hall (Trustees of Sir Charles Tempest, but occupied by Mrs. Semon). The family of Tempest, resident at Broughton since the middle of the 15th cent., when Sir Roger Tempest married the heiress of the and passing the village of E. Marton Gilliotts, is probably the most an- (the ch. is without interest), we reach

Bracewell (see ante) soon after the which was afterwards removed to Conquest; but that (the eldest) branch lost its estates after the civil war, and the Broughton Tempests now represent the family. stately house, a Palladian building with a portico carried through two stories, was refaced, and wings were added, about 1835. On one side is an Italian garden. There are some fine trees in the park, and some picturesque old yews in the drive toward Skipton. The house contains some good pictures, probably collected by a Stephen Tempest at the beginning of the last century. Among them are - Daughter of Herodias with head of St. John Titian (?); St. Sebastian, A. del Sarto; a Virgin and Child, attributed to Raffaelle, and of great beauty; 2 river scenes, Breughel: St. Catherine, Carlo Dolce: pictures attributed to Fra Bartolomeo. and to Perugino (?); Landscape, Both; and, most important of all. a very fine Salvator Rosa; the subject a seaport, with rocky landscape. l.; and in front a "philosopher throwing his gold into the sea. The picture is full of silvery light, and is probably one of the finest Salvators in this country. In the dining-room are 2 more Salvators, one of them, a rocky scene with brigands, very fine. Here are also 2 Canalettis; a Rocky Coast, by Vernet; and an interior. Ostade. In other rooms are a halflength of Pope, with book in hand. and a portrait of Col. Thomas Tempest, temp. Chas. I.

The Church of Broughton (1 m. distant and off the road) has Norman portions, and a N. aisle (Perp.), with niches for figures in the faces of the piers. A chapel at the E. end contains mural monuments to the Tempests of the 18th cent., with their

pedigree.

Proceeding on the Clitheroe road.

W. Marton, the residence, for many | Kilnsey, or at Kettlewell, where there generations, of the Hebers (here called Haybers), from whom the Hebers of Hodnet (and the Bp. of Calcutta) are descended. (There was another branch near Ilkley, see ante). Gledstone House, a large house built toward the end of the last cent., standing high above the village, and commanding fine views, is the property of the Roundells, formerly of Scriven near Knaresborough. Ingthorpe Grange was a grange attached to Bolton Priory.

For Gisburne, through which the

road passes, see Rte. 33.

ROUTE 31.

SKIPTON TO KETTLEWELL. (UPPER WHARFEDALE.)

A very uncomfortable mail cart runs daily from Skipton to Buckden, through Grassington and Kettlewell, starting at 7 A.M., and returning to Skipton in the evening. The pedestrian may travel by it to Kettlewell or to Buckden, whence he may proceed by rough but most picturesque mountain roads, either down Coverdale to Middleham (Rte. 23, and the present route post), down Bishopdale toward Aysgarth (Rte. 24), or below Addleborough to Bainbridge and Askrigg (Rite. 24). Either of these routes, however, will be too long (starting from Skipton) for a single day's excursion; and it will be best to heriting through the attainder of the

is rough accommodation for pedestrians. But it must be remembered that these remoter mountain districts are not to be explored at all without some sacrifice of comfort. pleasant day's excursion may be made from Skipton to Rylstone, thence to Kilnsey and Kettlewell; there crossing the Wharfe, and returning by Grassington. (There are some small inns on these roads, as far as Kettlewell, passable for pedestrians; but the pleasantest and best are at Kilnsey, see post.)

Between Skipton and Threshfield the road winds up the great limestone ridge between Airedale and Wharfedale, passing under (l.) Flasby Fell (1151 ft.), and (rt.) Rylstone Fell. Rylstone (5 m.) brings us at once into the company of Wordsworth. Here was the "sequestered hall " of the Nortons, who lost the whole of their Yorkshire property for their share in the "Rising of the North"—the rebellion headed by the Earls of Northumberland and Westmoreland (Nov. 1569); with the view of restoring the "old religion," and of supporting Mary of Scotland, then imprisoned at Tutbury, but who was removed at once, for greater security, to Coventry. In his 'White Doe of Rylstone,' Wordsworth has connected the Nortons' share in the rising with a local story (see Bolton, Rtc. 30), and has made the "exalted Emily" the survivor of her father and brothers, "Norton and his eight bold sons," whom, following the old ballad, he condemns to death at York:

"Thee, Norton, wi' thine eight good sonnes,
They doom'd to dye, also for ruth! Thy reverend lockes thee could not save, Nor them their fair and blooming youthe "

In fact, however, all except two, Thomas and Christopher, seem to have escaped with life—though the family was rendered incapable of inremain a night either at the inn at father. Of "Rylstone's old sequestered hall" little remains but the site, marked by large remains of foundations in a field E. of the ch., looking over to the Fell. Some sycamore-trees are grouped about them, and they are probably the traces of a "Vivery," as Whitaker calls it, - a pleasure-ground, with topiary works, fish-ponds, and an island, attached to the hall. house fell into decay immediately after the attainder of the Nortons: and, with the estates here, remained in the hands of the Crown until the second year of James I., when they were granted to the Earl of Cumberland. Although Wordsworth makes the Nortons raise their famous banner here, they assembled their followers in fact at Ripon (Nov. 18, 1569), but their Rylstone tenants rose with them; and one at least, "Richard Kitchen, butler to Mr. Norton." was executed at Ripon. A small ch., of Dec. character, has replaced the little chapel adjoining the manorhouse; and in the chancel is a tablet for Richard Waddilove, Esq., of Rylstone, d. 1850, who left 1000l. towards rebuilding the ch. The old bells disappeared with the old tower. and Wordsworth's lines are no longer applicable:--

" When the bells of Rylstone played Their Sabbath music-' God us avde.' That was the sound they seem'd to speak."

A ring, bearing the same motto, was sold at a sale of antiquities from Bramhope Manor, Feb. 1865.

On the highest point of Rylstone Fell, opposite the ch., some pious hand has erected a cross; and on a much lower elevation towards the end of the ridge, are the remains of a square tower-built, it is said, by Richard Norton, probably as a hunting and watch tower:-

"High on a point of rugged ground Among the wastes of Rylstone Fell, Above the loftlest ridge or mound Where foresters or shepherds dwell. An edifice of warlike frame Stands single (Norton Tower its name): It fronts all quarters, and looks ront.:
O'er path and road, and plain and delt.,
Dark moor, and gleam of pool and streat.
Upon a prospect without bound." White Doe, cant

Some mounds near the tower ar thought to have been used as bur for archers: and there are trace a strong wall, running from the tower to the edge of a deep glen, whene a ditch runs to another ravine. was once a pound, used by the Nortons for detaining the red der within the township of Rylstone.

The scenery round the little vil lages of Cracoe, Threshfield. am Grassington (Inn: Devonshire Arms quite passable as a resting-place) wild without being fine or very in-Trees will not grow: teresting. and stone walls take the place of hedges. These villages are the "capitals" of the mining district. which extends upward, rt., over Grassington Moor. Lead has been worked here from a very early period: and Whitaker suggests that the lead coverings of the ancient Craven churches are in all probability of native metal. Arassington lead-mines belong to the Duke of Devonshire. The lead from some of them is melted on the sudthat from others is sent to Skipton The mines are drained by an open level, commenced in 1796, and completed in 1830, at a cost of 30,000l. From Threshfield a pedestrian may descend the Wharfe to Barden and Bolton. (See the former route.)

At Linton, 1 m. E. of Threshfield.

is a hospital for aged women. The Upper Wharfedale, The Upper above Threshfield, is a wild moorland valley The Wharle with wooded slopes. (here fully entitled to Spenser: epithet "swift Wherf," which he borrowed from Camden, who derive the name from the British guer= rapid) issues rapidly from amour these woods, and after expanding into a glassy pool struggles through a

narrow passage (about 2 ft. wide) the top, whence the view is striking. which is worth seeing) is called the Fastrills—a name of uncertain signification, but scarcely meaning the rills of the Ghost," as has been sugrested. The river is fine and rocky. Nearer Kilnsev is Chapel House (Rev. W. Bury), on the hill 1., from which he views are very fine; and nearer the river, Netherside (Colonel Nerille).

Kilnsey Craq is 4 m. from Threshfield, on the rt. bank of the Wharfe). Here are two wayside Inns. the Angler's Arms, and the Tennant's Arms, which offer good fishing quarters. (The Wharfe abounds in trout. 5s. a-day is charged for the privilege of fishing here.) Kilnsey ("Chilesie" in Domesday and still pronounced "Kilsey") Crag itself is a magnificent crag of overhanging limestone, -(" Cautes omnium," wrote Camden, " quas quidem ego vidi, editissima et præruptissima") — and one of the best examples in the county of those great inland cliffs "which are among the most striking phenomena of Yorkshire,-only differing from sea-cliffs because the water no clonger beats against them."-Phillips. This "was a promontory overhanging the primæval sea-loch, which is now the green valley of the Wharfe; and the mural precipices which gird the bases of Whernside. Ingleborough, and Penyghent, formed bold margins to similar branches of the sea, which extended up Chapeldale and Ribblesdale."—Ib. Saplings and ivy spring from the many fissures that cross and divide the face of the rock. Larger trees and brushwood, with a sedum (the lesser orpine), cluster along the ledges; and a colony of swallows keep the crest of the great cliff alive with their constant flitting. The limestone crag extends for nearly half a mile; but its highest part (165 ft.) is

early period to Fountains Abbey (the moors l. beyond Arncliffe are still called "Fountain Fell"); and the vast flocks which the monks fed on the adjoining moors were driven to Kilnsey for their annual shearing. The scene on such occasions must, as Whitaker remarks. have been one "to which nothing in modern appearances or living manners can be supposed to form any parallel."

Across the Wharfe, nearly opposite Kilnsey, is Coniston, where is a small chapel, most picturesquely situated, and probably, as Whitaker suggested, "the most ancient building in Craven." Two Norm. and two Perp. arches remain within; the font is rude, square Norm., and an early triangular-headed window deserves notice. The old chapel was added to in 1800; but the work then built has been removed, and a modern structure of good character erected-preserving all the ancient building. The opening of Coniston Gill Hole, E. of this chapel, is very picturesque (hole, used throughout this district for the narrowest. deepest part of a valley, is the A.-S. hol = hollow).

[Close beyond Kilnsey, the little river Skirfare, which descends by Arncliffe, through Littondale, joins the Wharfe. This lateral valley has scars of limestone, with green meadows below them, and "tofts" of trees overhanging occasional hamlets. Such tree "tofts" (tufts-it is the old French "touffe de bois"), sheltering insulated homesteads, each of which has its little garden plot, are characteristic of Craven villages. "These," says Whitaker, "are the genuine tofts and crofts of our ancestors, with the substitution only of stone walls and slate to the wooden crocks and thatched roofs of antinear the inn. You should climb to quity." Arncliffe Church has been

"restored." The tower is temp. Hen. VIII., and there is an early bell with the inscription: "Petre poli clavis fac ut intremus prece quavis."

Between Arncliffe and Kilnsey is the Dowkabottom Cave, -one of the numerous caverns in the limestone of this district, formed mainly by the solvent action of water charged with free carbonic acid. The entrance. which is merely a fall in the roof of the cave, is on a plateau of rock (1250 ft. above the sea, and difficult to find without a guide). The original mouth of the cave is not now visible. During most of its course the chambers and passages of the cave are not separated by any great thickness from the rock above, and thus other falls must be expected. The E. division of the cave is about 450 feet long, and has three fine chambers separated by two passages, the first very short, and the second very long. In the first and second are stalactites and stalagmite: the third is floored with mechanical deposits, blocks of limestone fallen from the roof and a stiff brown clay beneath. The W. division, about 250 feet long, also contains three chambers and two passages, with stalagmites and fallen blocks throughout. Since 1850 the cavern has been carefully explored by Mr. Jackson, of Settle, and by Mr. Denny (curator of the museum of the Leeds Philos. Soc.). They found, sometimes under the stalagmite, and sometimes among loose stones and charcoal ashes above it, bones of the wolf, wild dog, and fox, and of the ox, sheep, wild boar, horse, and red deer. In the first chamber, under a layer of charcoal ashes, 3 human skeletons were found, in a bed of clay, which rested on soft stalagmite; fragments of weapons and of perfibulse, rings, &c.—besides Roman covered in different parts of the relics - animal and human - have

cavern; and in one instance a human skull on the floor of the cave, below the stalagmite. When first examined. the surface of the cave was strewn with bones and skulls of animals The relics found seem to be of two periods-late Brito-Roman, and primæval,-the latter being bone pins and ornaments, pierced sea-shelk. and pierced teeth (of the wolf apparently), which seem to have formed a necklace. These results were obtained by exploration of only the surface layers, where it was not deeply buried by the fallen blocks.

During August, 1881, further explorations were made by Mr. E. B. Poulton, who presented a preliminary report to the British Association. which is printed in the Reports of the 1881 meeting. Sinking a shaft in chamber 3 of E. division, previously unexplored, he passed through the following layers of cave deposit: (1st) a Romano-British layer, one or two inches thick, of black earth. with pottery ornaments, &c., and numerous bones; (2nd) hardish stalagmite, about 6 inches thick, with bones of a dog or small wolf; (3rd) soft stalagmite, 4 inches thick: (4th) hardish stalagmite, 6 inches thick: (5th) soft stalagmite, 2 ft. 6 inches thick; (6th) stiff brown clay, with fragments of fallen roof imbedded in This was 8 feet thick. It has been suggested that the cave formed a retreat for certain inhabitants of the district during the disturbed times which followed the departure of the Romans. The bones of animals may either have been washed into the cave by a flood-or, more probably. the Dowkabottom cavern may have served for a long period as a wolfs den-an animal which had perhaps its latest home in England among sonal ornaments bronze armlets and | these Yorkshire hills. (The last wolf is traditionally said to have been killed coins, including a brass and a silver at Rothwell, near Leeds, by John of denarius of Trajan, were also dis- Gaunt in the 14th cent.) Similar

been found in the "Victoria" cave near Settle (Rte. 32.)

Crossing the Wharfe either at Coniston, or above Kilnsey, the road passes along the L bank of the river to Kettlewell (3 m. from Kilnsey). The views are pleasant, and the road bordered rt. by a low range of the limestone cliffs which so greatly characterise these dales. Kettlewell (" well ") here possibly represents the Teutonic weller, a dwelling = the house of Ketel) boasts of two little Inns. the Racehorse, and the Tennant's Arms. The village, simple and oldfashioned, is the best place for exploring the upper part of Wharfedale and the fine passes out of it. It was one of the most ancient settlements in the valley; and until 1800 there was a small Norm. ch. here (aisleless, with narrow round-headed windows). built probably by the Arches (de Arcubus), who were lords here soon after the Conquest. All distinctive features were destroyed in 1800; but the Norm. font, circ. on 4 rude pedestals, remains.

Immediately round Kettlewell the chief hills are Great Whernside (2310 ft.), dividing Wharfedale from Nidderdale, and Buckden Pike (2304 ft.). Between these hills a deeply sunk road winds upward, and then descends Coverdale to Middle-"The views from this pass. and from the sides of Buckden Pike down the rocky length of Wharfedale, are superb. The easy ascent from Kettlewell should on no account he omitted." -- Phillips. Buckden Birks (2001 ft.), and Raisegill Hag (1985 ft.), both on the N. side of Littondale, are also marked features : and far down the dale the fells of Rylstone and Simon Seat bound the horizon. All this is still the region of the lower limestone—green sheepwalks rising far up the hillsides, and broken by crags and " girdles " of rock.

[An adventurous pedestrian may make his way across Hard Flask (1746 ft.)—a broad hill, with great "floors" or terraces of limestone, very finely displayed—to Malham Tarn (where he is close to Gordale and Malham Cove), and thence to Kirkby Malham or to Settle (p. 407). The distance to Malham Tarn is about 7 m.—and thence to Kirkby 5 m. See the next route.]

Still passing up the Wharfe, 2 m from Kettlewell is Starbotton (whatever the "Star" may be, "botton" is the same word found in Cleveland. and representing the Norse botn = adepth), "a little place of rude stone houses, with porches that resemble an outer stair . . . trim flowergardens, and fruit-trees, and a fringe of sycamores." - White. Beyond Buckden, the next village (2 m .here is an Inn which may do for a pedestrian), the main road turns away rt. and climbs the pass separating Wharfedale from Bishopdalea long, beautiful valley that descends to Aysgarth (see for it Rte. 24). From Kettlewell to Aysgarth is about 15 m., but the distance over these rough roads and hills is hardly to be measured by miles. The walk is, however, to be recommended: and the views across toward Penyghent on one side, and down Bishopdale on the other, are fine. A branch l. from this road leads through Cragdale by Seamer-water to Bainbridge. (For this see Rte. 24.)

Following the Wharfe, however, the road ascends Langstrothdale (as the valley is called above Buckden), passing out of the limestone near Deepdale. From this point to the source of the river under the brow of Cam Fell. 1665 ft. above the sea, the course of the Wharfe is through gritstone; the scenery very wild described moorland, with Cam Fell, Ingleborough, Penyghent, and Whernside conspicuous.

At Hubberholme, on the rt. bank of i the river, a little beyond Buckden, is a small ancient chapel, some parts of which (the piers and arches on the S. side very rude and without ornament) may perhaps date from before the Conquest. The roodloft-painted with broad red lines-remains, with the date 1558, the year of Queen Mary's death. There is a tradition of a great flood here, which left many fish in this little ch.—where the foresters of Langstrothdale have been baptized and buried at least ever since the Conquest.

Langstrothdale, or Langstrother (the name seems originally Celtic—strath hir, the "long valley"—and, as in many similar cases, the Teutonic translation of part of the name was added to it—Langstrother and Cornstrother occur in the "Black Book of Hexham" among the boundaries of Carraw; and comp. Anstruther in Fife)—formed a chase (it is sometimes called a forest) in days when the valley was far more filled with wood than it is at present. Its

"Milk-fed fellows, fleshy bred,
Well browned, with sounding bows up-

followed, according to the old poem, the Shepherd Lord Clifford to the field of Flodden; and certain natives of this remote dale have been commemorated in other verse, of a somewhat different quality. In Chaucer's 'Reve's Tale,' "Johan and Alayn," scholars of Soleres Hall at Cambridge,—

"Of oo toun, were thei born that highte Strother Fier in the North I can not tellen where."

And Whitaker first suggested what Mr. Garnett has confirmed—that this "toun" was really Langstrother. The dialect which Chaucer employs in this story is still, to a great extent, that of this little-visited corner of Craven; and he copied, in all probability, the language he had himself heard spoken in "Solere Hall"

by some Langstrothdale student. It may be added that Mr. Garnett ('Philological Essays,' 1859) has printed a portion of the poem from a MS. which retains the peculiarities of dialect more exactly than any which has been collated by editors of Chancer.

On the hills about the source of the Wharfe the cloudberry (Rubes chamemorus) abounds to such an extent as, when ripe, to redden the surface of the ground.

ROUTE 32.

SKIPTON TO INGLETON, BY SETTLE. (MALHAM, GORDALE, VICTORIA CAVE.)

(Midland Railway.)

For a short distance this line follows the valley of the Aire (as it does throughout its course from Leeds to Skipton, Rtc. 34). The "Leeds and Liverpool Canal" also accompanies it as far as

4 m. Gargrave Stat., where it turns S. Gargrave Church has a low massive Perp. tower,—the rest of the building is modern and throughout of good Perp. character. Nearly all the windows have stained glass. much of which is by Capronnier of Brussels. The font, of alabaster, has panels, well carved, with emblems of

the Evangelists and good foliage. | Charles I., in armour, 1. hand on There is a lofty canopy of carved oak. Many of the windows are memorials of Currers and Wilsons of Eshton Hall (see post). Ch. and ch.-yd. are excellently kept. Tradition asserts that Gargrave had once 7 churches. all of which were destroyed by the Scots in a sudden foray—except that remaining-which they spared because it was dedicated to St. Andrew. About 1 m. below the town the site of a Roman villa was discovered toward the end of last cent. traces now remain. The nearest Roman road was that which ran from Ilkley to Ribchester.

The village of Gargrave (Pop. in There 1871, 1291) is uninteresting. is a large "spinning" mill. The Aire, here somewhat canalised, runs through the village, and the Leeds and Liverpool Canal a little N. of it. Gargrave House (W. Coulthurst, Esq.), lies among trees. W.

11 m. N. of Gargrave is Eshton Hall (Sir Matthew Wilson, Bart.), a large mansion, in a fine situation, built 1825-7 (Webster, of Kendal, archit.), in the style of Inigo Jones. There is a fine staircase and entrance hall; and the library and drawing-room, opening into each other, contain about 10,000 vols., chiefly of English history and topography-books in fine condition and well bound, a portion of the great collection of Miss Richardson Currer, whose library and whose praises have been sung by Dibden, and who was half sister of the present owner. (The house and estate were bought by Matthew Wilson, of London, in 1646.) There are some good pictures. In the Dining-room, Diana and Actson, in a very fine landscape, Rubens (on copper); Virgin and Child, with dance of angels, Vandyck; Virgin and Child, Luini; Drawing after Raffaelle, Heliodorus driven from the Temple,

glass globe, *Dobson?*—this picture came from Browseholm (Rte. 33); Cromwell, Fairfax, and Lambert, all three attributed to Walker. In the Billiard-room are some graceful Pompeian drawings, floating figures on a black foreground; and here also is a very fine Turner landscape, -Thurland, in the valley of the Lune; a clear evening sky, against which the old tower is projected. In the Hall, Centaurs and Lapithm, Luca Giordano; Cottage-door, Westall. In the Library hangs a portrait of Miss Currer, by Masquerier. There is a fine view from the terrace in front of the house, and a still finer from a path leading to the gardens, ranging over a richly-wooded foreground to Rylstone and Flasby Fells. Wood, N. of the house, contains some very ancient ash-trees (the place is named from the ash-"ash (esh) town"), and is mentioned in documents of the 12th cent.

Some of the rarer volumes of Miss Currer's library have been dispersed; but among the important MSS. still remaining here is the correspondence of Dr. Richardson, the naturalist, with all the men of science of his day, and some volumes of Dodsworth's 'Yorkshire Collections.' The park is traversed by a stream fed from a spring called St. Helen's Well. About 1 m. from Eshton is Friar's Wood, an old house to which the abbots of Furness used to come for hunting; and on a field near at hand, three long parallelograms of turf, called the "Giants' Graves." Two becks meet at Eshton Bridge; and above it, E., is Flasby Hall (Captain Preston). The next

23 m. Bell Busk Stat. is the nearest to Malham (5 m.)—close to which are Gordale and Malham Cove, two of the most remarkable scenes in Great Britain. (The best Inn at Vandyck; Dutch Lady, Rembrandt; Malham is the Buck; and the landlord, if written to in time, will send a | lost his 3 sons in his own lifetime trap to Bell Busk, where no conveyance is to be hired. This inn is at the village of Malham, a mile higher up the valley, and nearer Gordale than Kirkby Malham, where is the ch.)

Detour to Malham and Gordale.

The road from the station follows the upper valley of the Aire,-here but a slender stream. (The etvmology is very uncertain. Oarus Araxes. Arar, seem to contain the same root.) The village of Kirkbu Malham is deep-seated among the limestone hills, and is only interesting for its ch., and its connection with the Lambert family. The Church, which was given before the reign of John to the Augustinian canons of Dereham in Norfolk (who held it till the Dissolution), is Perp. The piers have niches on the W. sides, with rude canopies, and monograms. The font is Norm. At the end of the S. aisle is a mural monument for John Lambert-died 1701 -son of the Parliamentarian general, and the last male representative of his family. At Calton Hall (now a modern farmhouse) John Lambert, afterwards the famous Major-General of the Parliament's forces, was born in 1619. (The record of his baptism, on November 7 of that year, remains in the Kirkby Malham registerwhich also contains the signature of Oliver Cromwell (as witness to or registrar of a marriage), twice repeated.) Lambert died, not in Guernsey, as is generally asserted, but in the severe winter of 1682-3, on St. Nicholas Island in Plymouth Sound, where he had been brought from Guernsey, a prisoner, in 1667. See 'Choice Notes from Notes and Queries,— History, p. 155.) His estates, for-feited on the Restoration, were permitted the son of the majorgeneral to repurchase them. He The Craven limestone is not the

and died the last male of his family.

1 m. beyond Kirkby Malham is the village of Malham, where is the Buck Hence the visitor should walk to Gordale Scar and the "Cove," a round of between 2 and 3 m. Gordale should first be visited. (Gordale = the narrow valley? Gore = a slip.) The stream which descends through it. E. of the village, will be a sufficient guide. The approach is between two ranges of limestone cliffs; which offer nothing especially noticeable until, on turning a projecting corner of rock, you find yourself in front of the "chasm" as it is sometimes called. The impression is one of absolute awe, especially if the place is visited alone, and toward evening.

"Gordale chasm, terrific as the lair Where the young lions couch,"

writes Wordsworth; who was always "full of praises of the fine scenery of Yorkshire. Gordale Scar, near Malham, he declares to be one of the grandest objects in nature. though of no great size. never disappointed him."-H. Robinson's Diary, vol. ii. p. 365; and Pococke, according to Whitaker. "who had seen all that was great and striking in the rocks of Arabia and Judea, declared that he had never seen anything comparable to this place." "I stayed there," says Gray the poet, "not without shuddering, a quarter of an hour; and thought my trouble richly repaid, for the impression will last with life."

Gordale is first noticed, under the name of Gordale, or the Quern (?) by Dr. Lister, in his account of Yorkshire plants added to Gibson's edition of Camden, 1695. It has been compared to the ravine above Lebadea, in which is the sanctuary of Trophonius; and the semicircle of granted to Lord Fauconberg, who Malham is not unlike the cliff above the fountain of Castalia at Delphi. same as that of Greece; but the dry | tend for some distance, tufts of yew watercourses, the underground passages of the streams, the cavernous fissures and abrupt escarpments of the rock, produce a certain general resemblance which is worth noting. The narrow glen is walled in by limestone precipices (called Gordale Scar) more than 300 ft. high, in places overhanging their bases more than ten yards, and stratified in thick horizontal beds. At the end is the "chasm" in the rock, through which a stream (descending from High Mark, E. of Malham Water-the whole "dale" is about 1 m. long) dashes in a series of waterfalls, giving life to a scene which would otherwise be almost too oppressive. Above the first waterfall a limestone ridge unites the two sides of the scar; and a hole through it, 8 ft. high by 15 ft. long, gives a passage to the water, which, it is said, first burst through in 1730, after a violent thunderstorm; but it is probable that the whole fissure, however started, has been enlarged by the action of All limestone regions are more or less tunnelled and excavated by the solvent action of the free carbonic acid contained in the water that has flowed over grass, peat, or other vegetable matter. Gordale is said to be especially grand in winter, when the waterfall is frozen; and a most striking effect is sometimes produced when the full moon is above the chasm.

The stream may be crossed at the foot of the cascade, and it is possible to ascend the rock by natural steps in the fractured limestone. (The ascent is easy, and is continually made by An upper fall is then disladies.) closed, bursting through the solid limestone wall, which thus forms a natural bridge across the stream. (Both falls may be seen from below, by retiring under the projecting cliff rt.) Primula farinosa grows on the sides of the rock. Along the ledges of the scars, which above the fall ex- are comparable to shallow glacier

(possibly indigenous) grow in plenty; and in spring the rocks are bright with golden broom. There is a tradition, which any one may believe who chooses, that one of the Tempest family once leapt his horse across the chasm of Gordale. The base of the mountain limestone is exposed in the ravine, resting unconformably upon Upper Silurian slates. A kind of sandstone, containing Silurian pebbles, occasionally lies between the two formations, and is exposed in Fossil corals abound Gordale beck. in loose blocks of limestone near the entrance to the glen.

Among the rare plants which grow above and below the waterfall are Palemonium cæruleum (Greek Valerian—fl. in June); Gentiana amarella (fl. in Aug. and Sept.); G. campestris (fl. in Sept. and Oct.); and Parnassia palustris (Grass of Parnassus—fl. Sept. and Oct.). Primula farinosa (fl. June and July) is plentiful in the wet meadows below the chasm.

Having climbed to the top of the chasm, you should walk across the hills to Malham Cove—about 1 m. The hills are covered with the short. fresh greensward characteristic mountain limestone; and here and there patches of saxifrage enliven it pleasantly. (There is a wide view S., with Pendle Hill rising a great mass in front. Rt. are the serrated peaks of the limestone hills N. of Skipton; and below stretches away the wide wooded valley of the Aire, shut in at the sides by tumbled hills, broken with clefts and hollows.) Long ridges and Pots of limestone (called Malham Lings), lie along the surface nearer the Cove, to which you must descend by a path on the side farthest from Gordale. The limestone on these "lings" or upper flats is honeycombed in the most complex manner conceivable with convoluted furrows that

crevasses. luxuriant vegetation of ferns within them. They are evidently due to the solvent action of water charged with carbonic acid, and are well worthy of a special visit as illustrating the potency of this action. Malham Cove (the name "cove," frequently given to the deep limestone hollows and fissures of this district, is perhaps the Celtic "Ogof" = a cave)—is a magnificent amphitheatre of rock. 285 ft. high (the Lower Scar limestone is here about 800 ft. thick), seeming, as Wordsworth has described it-

" by giants scooped from out the rocky Tier under tier.

From the foot of the cliff the Aire springs to light at once,—a full stream. "The water is supplied by subterraneous channels in the limestone; some no doubt coming by this means from Malham Water." a " Looking lake nearly 2 m. distant. up at the front of the Cove, we perceive that, if the water came flowing in abundance over the top, it would make a cascade of almost unrivalled grandeur; and it is said that such an event has occurred, in consequence of some choking of the channels from Malham Water, in time of great floods."-Phillips.

The semicircle of the Cove is part of a long line of elevated limestone cliff, beginning near Kirkby Lonsdale, and extending as far as Threshfield in Wharfedale. This dislocation is known to geologists as the "Craven Fault," and is one of the grandest examples in England. Malham | Cove and Giggleswick Scar are the most important cliffs formed by it; but at many points it causes enormous vertical faces of limestone, opposed to quite different strata on the

The limestone, at some unknown period, dropped along the line of the fault, leaving the cliffs exposed.

Many of them bear a view from the summit; and (for those who have good heads) a path along the face of the rock, on the projection of one of the ledges. Small trees and bushes of yew cling to these, and root themselves in every crevice. Both E. and W. of Malham the difference in contour and vegetation between the limestone hills to the N. of the fault and the grit hills to the S. is very apparent. Trollius Europæus occurs at the Cove; and Limestone Polypody (Polyp. calcareum). There are some calamine pits on the bridleroad to Settle (near the Cove) which abound in fossils, including trilobites, usually rare in mountain limestone.

Malham Water, or " Malham Tarn," is a small lake about 3 m. in circumference, 2 m. above the Cove. and 570 ft. higher than the outlet of the Aire at its base. It is 1246 This is the ft. above the sea-level. most important "tarn" in Yorkshire. and its wild seclusion gives it an interest hardly due to picturesque beauty. A modern house (belonging to Walter Morrison, Esq.), has been built on the further side of the tarn, and is surrounded by flourishing plantations. The lake abounds with yellow and "silver" trout and perch; and was given to the monks of Fountains by William de Percy. temp. Stephen. A confirmation of this grant in 1175 mentions, besides this lake, all the "pastura" of Malham " deversus rupes"—the rocks, no doubt, of Gordale. Fountain Fell (1944 ft.) rises N.W. of Malham Tarn.

From Malham you may cross the high moors to Settle (7 m.). These moors form a joint of the Pennine chain-the great "backbone of England," extending S. into Derbyshire, and N. to the Scottish border. constitute the watershed between the streams flowing into the German The Cove should be seen both from Ocean by the Aire, and those running below and above. There is a fine into the Irish Sea by the Ribble; and

very fine views are obtained in cross- | and comfortable; Commercial, oppoing them. Settle may be reached either by Malham Tarn, descending by Langcliffe,-the longest road, but commanding magnificent views back over Malham and Airedale, and (near Settle) over part of Ribblesdale, with Ingleborough soaring grandly on one side, and Penyghent on the other: or through Malham village. over Highsides, by Attermyre Crags, (see post). These moors are for the most part great sheep pastures, with crags and ridges of limestone scattered over them. There is little heather. Saxifrages of different species abound; and the great flocks of peewits that breed here aid the effect of the solitude by their wild " eerie " cries. The few small farms on the slope of the hills are sheltered by sycamore and ash trees. highest ground of the ridge is about 1700 ft.7

Returning to the rly., the first

station beyond Bell Busk is

3 m. Hellifield Junct. Stat., where is remaining a square "castelet" or peel tower, built by Lawrence Hamerton in the 19th year of Hen. VI.rather as a place of protection in stormy times than as a dwellinghouse. It is now the residence of John Hamerton, Esq., whose family is of great antiquity on the borders of Lancashire and Yorkshire.

Rail to Clitheroe, Bolton, Liver-

pool, and Manchester.

[Malham is 72 m. from here and this is the best stat. for it when the trains do not stop at Bell Busk. Benson of the Beech Inn, Malham, will send conveyance to meet the train, if written to. Passing-

12 m. Long Preston Stat.—the ch. in the village has been restored, and has some stained-glass windows

by Capronnier-we reach

4 m. Settle Stat.

Inas: Lion; good, old-fashioned

site. Settle (A.-S. Setl = a seat) is a market-town of, in 1881, 5600 Inhab., and the tourist will find it an excellent centre from which to explore the wild but most interesting country which surrounds it. Cove and Gordale (see ante) may well be visited from Settle. Ribblesdale and Penyghent are near at hand; and Ingleborough and the Clapham Caves are within a day's excursion.

The town of Settle contains many 17th-cent. houses—showing its comparative wealth and importance at that time. One house especially, called "Folly Hall" (now a farmhouse), close under Castleberg, is a large and fine example of a Charles II. mansion in Craven. The Elizabethan town-hall and the ch. are modern. At the back of the town rises the Castleberg, a limestone precipice 300 ft. high, capped by a pinnacle of rock, and rendered accessible by zigzag walks, planted with trees. (It once served as a gigantic sundial, and the time was marked by its shadow thrown on rocks placed at regular intervals. These have long been removed.) There is a tolerable view from the top,-N. towards Penyghent, and S. along the valley of the Ribble; and the visitor who has not more time at his disposal should by all means climb the fell at the back of Castle-Thence he will get a fine view of Ingleborough and the district beyond-broken, rocky, with uplands and green hollows stretching away for a great distance. Between Burnmoor and Ingleborough the faint blue range of the Westmoreland mountains is seen in clear weather. The valley of the Ribble opens N. and S.

The view of the valley from the grounds of Anley (John Birkbeck, Esq.), between the station and the town, is also very fine.

(1) Giggleswick Stat. on the Ingle-

ton Railway and the Ebbing Well. The Ribble (the former part of the word seems connected with the Celtic rhe=swift; but the etymology is uncertain) descends from Cam Fell, at the head of Langstrothdale, and, passing Settle and Clitheroe, runs through Lancashire to the sea below Preston. The first cotton and thread mills appear on its banks at Settle. which is in the parish of Giggleswick, on the left bank of the river. From the bridge there is a picturesque view up the dale, with Penyghent conspicuous; resembling from this point a huge plum-cake,—as Paley is said to have remarked. The Church of Giggleswick (dedicated to St. Alkilda), picturesquely placed, is Perp. and of little interest, except for its readingdesk and pulpit-one placed above the other, and, to judge from the forms of the panels, of Elizabethan date. On the pulpit are the emblems of the 12 tribes, with their names; on the desk, in front, the inscription -- "Heare is the standardes of the Israelites when the to Canan cam agenes the Canaanites." This is a good example of the carving which was at one time the favourite winternight's work of the Yorkshire dalesmen; and the choice of subject curiously illustrates the Puritanism which made this corner of England one of its chief strongholds. A brass plate in the middle aisle commemorates the Rev. William Paley, master of the grammar-school here for 54 vears—died 1799.—and his wife. These are the parents of Archdeacon Paley of the 'Evidences' and 'Natural Theology'-who was born in July, 1743, at Peterborough, shortly before his father removed to Giggleswick. The Paleys had been settled at Langeliffe in this parish for some generations.

Adjoining the church is a Cross (14th cent.?), and at no great distance the Grammar School, a good modern building, with a master's house.

best endowed in the north of England. It was founded by Edw. VI. in 1553. shortly before his death, at the instance of John Nowel, the King's chaplain and vicar of Giggleswick. Some distinguished scholars have been sent into the world from Gigglesamong them Archdescon wick: Paley, who was educated here under his father.

In the Museum attached to the school is preserved a very large collection of bones and other relics found in the Victoria Cave (see post. Of the Roman-Celtic class, are -portions of bronze ornaments and of glass vessels, fibulæ, carrings. and brooches, of very graceful form. and some of them enamelled; coins of the period of the Thirty Tyrants: bone implements, curiously carved; iron fragments; much pottery, including portions of Samian. lithic, but of uncertain age, are-bone implements and ornaments; combs; a bone spoon carved with the head of a bird, and some curious stone weapons. Among the bones are rhinoceros, hyæna, bear, &c., and some human teeth. (This museum is to be seen on application.) Giggleswick Scar, a long and fine range of limestone cliffs, rises for some distance above the road to Clapham, and, like Malham Cove, marks the line of the great Craven "fault." (See ante.)

At the foot of the scar, close to the road and not far beyond the village, is an " Ebbing and Flowing well," a spring " of very irregular habits," savs Whitaker, which rises and flows at uncertain periods into a stone basin. "Variable pressure on the water. derived from a curved or siphonal passage underground, is the principle on which explanations have been offered for this and similar springs by Gough and other writers; and the effect may be copied by artificial experiments."—Phillips. spring sometimes ebbs and flows many times a day; but it is affected and a hostel. The school is one of the by the weather, and in dry seasons it is useless to wait for the exhibition, the principle of which is the
same as that of the Icelandic Geysers. The well has always been
famous, and Whitaker suggests that
it may have given name to the parish
(called Guglesvic in some ancient
charters, but Ghigeleswic in Domesday), from the A.-S. gugglian=to
bubble forth. Drayton (Polyolbion)
describes the fountain as "sometime"
a nymph:—

"——Among the mountains high Of Craven, whose blue heads for caps put on the sky."

Flying from a Satyr, the "topic gods" changed her to a spring; and

"Even as the fearful nymph then thick and short did blow.

Now made by them a spring, so doth she ebb and flow."

(2) Attermyre Clefs, 2 m. E. of Settle (above the road to Malham), well deserve a visit. The great castle-like walls of broken jointed limestone, with green ledges running across them, are here wonderfully fine, and the artist will find magnificent rock studies in all directions.

Under the cliff, rt. of the road to Kirkby Malham, is Scaleber Force, a small but picturesque waterfall

among larches.

After visiting Attermyre, the tourist will do well to proceed some 3 m. further, to the summit of Ryelosf, a round-topped mountain of millstone grit, 1794 ft. high. There is a very wide view from it S. toward Pendle Hill, and from its skirts, near the road to Kirkby Malham, a picturesque view of Settle.

Some ancient zinc-mines are still worked on the moor S. of Ryeloaf (and S. of the road to Kirkby).

(3) Victoria Cave.—To the geologist this is one of the most interesting places to be visited from Settle. It lies 1½ m. N.E. of the town, in the W. face of Langeliffe Scar (hanging over the village of that name), and is about 1450 ft.

above the sea. It is 11 of a mile from the nearest point on the river. and about 900 ft. above it. limestone in which it is excavated dips N.N.W., and the main direction of the cave is N.N.E. The cavern was discovered by Mr. Jackson, of Settle, on the Coronation-day of Q. Victoria. He explored the surface. and since 1870 the cavern has been examined under the direction of a committee. The result of the explorations has been that much of the original evidence has disappeared, and that we have to depend chiefly on the accounts of Mr. Boyd Dawkins (' Journ. Anthrop. Inst.,' I.) and Mr. Tiddeman ('Geol Mag.,' and 'Geol. Soc. Journ. Nov.). "The uppermost beds contain deposits ranging from Neolithic to modern times, but chiefly Romano-Celtic. In this layer have been found bronse and bone implements and ornaments, pottery, coins, and bones of the following animals: Bos longifrons, goat, roe-deer, stag, pig, horse, dog, badger, and other smaller carnivora and rodentia. Neolithic layer has yielded three rude flint flakes, a bone harpoon, a bone bead, and broken bones of the brown bear, red deer, horse and Bos longifrons; the bear possibly belongs also to the Romano-Celtic These lie on the surface of laver. Below this the upper cave-earth. last is a bed of laminated clay, in places 12 ft. thick, but variable, which dips from the central chamber to the lateral chambers on the rt. and l. At some distance below this. in the lower cave-earth, was a bonebed, containing remains of the following animals:—Elephas primigenius, Ursus spelseus, U. priscus, Hyæna spelæa, Rhinocerus tichorinus, Bison, Cervus elephas. great question has been whether the laminated clay is of glacial age; and this supposition has been strengthened by the discovery of a bed of drift containing scratched boulders

edges of the lower cave-earth and the bone-bed. If it be so, the age of the animals found in the bone-bed is, of course, thrown back to a far greater antiquity than has been hitherto assigned them; but discoveries in Kent's Cavern and elsewhere seem to confirm this view. The remains in the uppermost bed show that the cave had been used as a dwelling or place of refuge for a considerable period, during the disturbed times which followed the withdrawal of the legions from Britain. The relics show an advanced state of art, and nothing but the necessity of concealment could have induced any persons to take up their abode in a place so wild and so difficult of access. (For the relics found here, see Giggleswick School, ante.) Some of the ornament on the brooches is not Roman, and the Celtic character indicates that they were made in this country. débris fallen from the cliff, and forming the talus, 2 ft. thick, at the mouth of the cave, has accumulated, as is shown by remains found under the talus, since the middle of the 8th cent.-about 1200 years.

[The so-called "rocking stones." on the fells N. of Attermyre, are great blocks of Ribblesdale slate, drifted or ice-borne from their native beds, and deposited on the bare surface of the limestone. They are easily moved; but the Druids are probably guiltless of all part in the matter. This slaty rock is in situ about Horton in Ribblesdale, and its greatest elevation there is about 1160 ft. in Moughton Fell, the limestone rising over it to the height of 1404 Blocks of the slate have been drifted S.W., S., and S.E., as far as Austwick, near Ingleborough, Giggleswick Scar, the hills over Settle, and Malham. On the Settle hills the blocks have been carried to a height of 1350 ft., nearly 200 ft.

all the talus, but resting upon the labove the highest part of the native "The blocks are very often rock. perched; show no marks of abrasion: no other drift matter is with them; they are collected sometimes into small groups: and they may be regarded as having been uplifted and floated by ice, and dropped on surfaces which had been swept by currents clear of other loose matter. the lower ground the blocks have been carried farther, are mixed with other detritus, and sometimes show marks of attrition in water."-Phillips.

> (4) Walk by Little Stainforth.— There is a very picturesque fall-Stainforth Fose—on the Ribble here. The walk may be—on the rt. bank of the river, through the village of Langeliffe, to Great Stainforth. Here cross the Ribble, and a short distance below the bridge is the fall.—a fine scene, the river foaming down a succession of limestone steps, the bank overhung with trees above mossy rocks. A lane from the bridge leads to the road on the rt. bank, by which you may return to Settle. There are excellent views of the fine scaurs above the l. bank, especially over Langeliffe, in which is the Victoria Cave. The road will be about 5 m.

> Longer excursions from Settle may be made (a) to Malham Core and Gordale, going by Langeliffe and Malam Tarn, and returning by the lower road, under Attermyre. The round will be 14 m. (see p. 404; to Malham from Bell Busk Stat., see above): (b) up Ribblesdale to Horton and Penyghent; and (c) to Clapham and Ingleborough.

The Midland Railway runs up the valley of the Ribble as far as Horton Stat. The dale is pleasant and picturesque, with occasional woods skirting the sparkling Ribble; scars of limestone girdling the hills on either side, and beyond, the great mountain masses of Ingleborough and Penyghent confronting each

other across the intervening moorland. This part of Ribblesdale is an excellent specimen of a quiet Craven valley, and the stream, but for poachers, would be as "troutful" as the most eager fisherman could desire. (There are some picturesque falls on the Ribble below the village of Little Stainforth, called "Stainforth Foss," see ante (4); and others, called "Catrigg Foss," on the Cowside beck, which falls into the Ribble at Stainforth.)

ing, especially from the lower part of the valley, above Giggleswick. Penyghnet is of mountain limestone, capped with millstone-grit, which encircles the top with a coronal of crags. From its summit the view is saye Phillips, not so interesting as that from Ingleborough), extending N. to the mountains shutting in Ungleborough, E. to the high moors about Wharfedale, and S. to Pendle

The Rly. leads past quarries and limekilns in the Craven limestone.

6 m. Horton Stat. lies between 1. Ingleborough W., and Penyghent on The village of Horton (Inns: New Inn; Golden Lion, passable for pedestrians) has a Church of some interest. The arcade of main arches and the font are Trans.-Norm. tower is not ancient. In the E. window is a fragment of stained glass, with the head of Becket, mitred, with aureole, and the words, "Thomas sanctus." There is an ancient Grammar School, of which the buildings are modern.

Penyghent may be ascended from Horton; or the tourist may drive from Settle as far as Dale End (time 1 hr.), thence send round his trap to Horton, and climb the mountain from Dale End, descending on the village. From Dale End follow the line of a wall seen running up Penyghent. The climb is steep, but not at all difficult. Allowing time for rest, it takes 1 hr. to reach the top, which is marked by a stake in a stone "raise." Penyghent (2231 ft. — Pen-y-ghent (Celt.) = the head of the road or

ascent) figures in the old rhyme:—

"Ingleborough, Pendle-hill, and Penyghent,
Are the highest hills between Scotland and
Trent."

In the district, with equal accuracy, it was long thought to be the highest hill in England. (Micklefell, 2600 ft., Rte. 27, is the highest in Yorkshire.) The outline of the mountain is strik-

the valley, above Giggleswick. Penyghent is of mountain limestone, capped with millstone-grit, which encircles the top with a coronal of crags. From its summit the view is wide and very interesting (though, says Phillips, not so interesting as that from Ingleborough), extending N. to the mountains shutting in Wensleydale, W. to Whernside and Ingleborough, E. to the high moors about Wharfedale, and S. to Pendle Hill. Morecambe Bay and Furness are also visible. The long dividing line of Ribblesdale is here very The side of Penvehent marked. which descends toward Ribble has (low down) "several caves, picturesque glens, and hollows in the scar limestone."—P. The effect of this view, however, depends greatly on the lights and shadow which the sky may fling on it. It is wild and desolate, and the "pavement" of limestone toward Ingleborough is striking. The descent on Horton is steep, but not difficult. (The artist will remark that the "screes" of the millstone-grit capping the hill are red in colour, those of the limestone purple.)

A remarkable band of slaty Silurian rocks fills, in the neighbourhood of Horton, "what may be regarded as a hollow space between two elevated ranges of limestone," and extends round northward to Sedbergh and into Westmoreland. Under Moughton Scar (across the Ribble, opposite Horton), "an uncommon junction may be seen of the limestone and Silurians, with interposed beds not known elsewhere. The Silurian strata dip in various directions very steeply, but their top is nearly level, as if cut off or planed away by some great and widely acting force, and the limestone lies level above them." -Phillips. The limestone of all this district is pierced in every direction with caverns, long subterranean passages, "swallow-holes," and depths

locally called Pots, which are in fact | caves from which the roof has disappeared. Of these the most remarkable are-Alum or Hellen Pot, near Sèlside (see post), Hull Pot, and Hunt Pot, both on Horton Moor. Hull Pot is visible as a deep hole in the heath from the side of Penyghent, and the pedestrian may take It is a it in his way to Horton. hollow, with great walls of limestone, gloomy and mysterious. the far end are enormous blocks. fallen from the sides and roof, and covered with moss. Water rushes out from the side, and there is the sound of a great fall within the recesses of the rock. There is a "swallow-hole" a little above, in which a stream disappears, to emerge in the "pot," the bottom of which is not accessible. Hunt Pot, a little S.W., is very similar.

Nearer Horton is a very picturesque spot, called *Dowk* or *Dove Hole*. Under a semicircle of scaurs a stream falls among trees into a deep hole,

below.

Alum, Allen, or Hellen (Hele=to cover) Pot, at the foot of Simon Fell. 1 m. from Selside, is a long, deep, gloomy cavern, with others called Long Churn and Diccan Pot, in which, as in so many of these limestone caves, there are subterranean falls of water. "The Alum portion is an immense hole in the ground, perhaps 60 yards long by from 10 to 20 broad, and 300 deep, the lower parts of which very few have ever seen. The Long Churn and Diccan Pot opening lies 150 yards W. of Alum Pot.".... The lower portion leads into the great Alum Pot; and after passing through a very crooked cavern, with sharp turns and abrupt descents, "we come into a large and high chamber, rough with protruding rocks, and standing in the water-worn channel at the end, see a gloomy gulf below us, and right forward a glimpse of daylight

from Alum Pot."—(W. S. Bankt' Walks in Yorkshire.')

Many of these caverns are interesting and important to the geologist : but the ordinary tourist will find the Clapham Cave (see Rte. 32A) and the very striking Weathercote Cave, new Ingleton (Rte. 32A), far more easy of access than any of the others, besides being probably the finest and most pirturesque examples. It should here be said that it is unsafe to wander over the limestone hills after dark, on account of the many chasms which intersect the surface, some of which resemble deep funnels of greensward. at the bottom of which the sound of flowing water is heard. These natural traps have frequently proved fatal to animals, and even to men.

Ling Gill (2 m. N.W. of Selside). through which a stream descends to the Ribble, is wild and rough. In Brow Gill, \(\frac{1}{2}\) m. S., is a cave called "Cove Hole," which has not been

thoroughly explored.

The extension of the Midland Rly. from Settle to Carlisle passes through this the wildest corner of Yorkshire, and will be useful for tourists who desire to explore it. Even hurrying tourists will do well to take a return ticket to Kirkby Stephen, and return at once, merely for the sake of the scenery on this line. The average level of the line is 1200 ft. above the level of the sea.

The Rly., a little beyond Horton, leads by Selside, under the N.E. skirts of Ingleborough. Cam Fell (1926 ft.) stretches out S.W. of the Dod. (The view from the summit of Cam Fell is very fine, with Ingleborough, Whernside, and Penyghent conspicuous.) The Wharfe rises on the S. side of Cam, and on the W. some of the small head-springs of the Ribble. (The spring usually called Ribble Head is nearer Gearstones.) Just after leaving Horton Stat., the line cuts the glacial drift. and presents fine sections of this kind of moraine matter known as "boulder clay," which is so hard in this region, that the navvies were unable to cut through with their picks, and blasting was therefore necessary. (Selside, see ante, is passed 2 m. further on the line.) The valley now opens out with rolling mounds of drift apparently left by retreating glaciers, as they lie transverse to the general slope of the ground. One of these is cut through and well displays their structure, just before reaching

Ribblehead Stat. (1 m. rt. E. is Gearstones. Tolerable Inn at Chapelle-Dale), 14 m. W. of Ribblehead, and close to Weathercote Cave. This Stat. lies between l. Whernside, W., and Cam Fell, E. Here the scenery is remarkably fine as the train runs on towards the watershed of Blea Moor, passing over Batty Moss Viaduct, thence along a great embankment succeeding it towards Whernside (2500 ft.), which seems to bar the way. To partially avoid it, the line curves a little to the rt., and the train enters the cutting and short tunnel that precedes the great Blea Moor Tunnel. The short tunnel passes under Force Gill, which gave much trouble to the engineers in making the line. cutting is chiefly through millstonegrit and black marble. At 400 yards from the S. end of the tunnel the rails are 1500 ft. above the sea, with 500 ft. of mountain overhead. line now begins its descent towards Carlisle, the drainage being north-Presently the train emerges at the head of the Dent Valley, and passes over the Dent Head Viaduct, 200 yards long, with ten semicircular arches rising 100 ft. above the road below. The view, peering down into this valley on l., is magnificent. (See Rte. 24.)

Dent Stat., a village on the Dee, was the birthplace of Adam Sedgewick, geologist, who is commemorated by a huge block of granite bearing his name. Next the train branch from the Tebay Junct. (on

passes over wild moorland, with streams cutting through the boulder clay; Cow Gill is crossed by an embankment 80 ft. above the stream. and Black Moss or Rise Hill Tunnel is entered, and the train emerges in the valley of Garride, and runs on

Harces Junct Stat. The Wensleydale and Levburn Rlv. branches E. to

Hawes (Rte. 24).

From Hawes Junction, northwards. the line proceeds over rolling moorland, breaking across wild transverse valleys. Then plunging into a long noble valley with stream on rt., and fine range of hills beyond, it enters Westmoreland, in which county is the

Kirkby Stephen Stat., and to Appleby Stat.

CARLISLE STAT. See Hdbk, to the Lakes.

ROUTE 32A.

SKIPTON TO CLAPHAM. INGLETON KIRKBY LONSDALE-THE YORK-SHIRE CAVES.

[4 Trains daily, 55 min., to Ingleton.]

This line diverges from Rte. 32, beyond

Hellifeld Junct. Stat.) Rte. 32. Long Preston Stat. Giggleswick Stat. is close to Settle.

At Clapham Junct. Stat, the Midland Rly. from Skipton is met by a the Carlisle and Lancaster Rly.), | which proceeds to Clapham by Sed-

bergh and Ingleton).

This is the stat, from which to visit the Clapham or Ingleborough Care, and to make the ascent of the mountain (unless Ingleton is preferred for the latter). (See post.) Close to the stat. is the Flying Horseshoe, a comfortable Inn. but 1 m. from the At the village is the New Inn (comfortable and moderate in charges), where the guide to the Cavern may be heard of. To see it a single person is charged 2s. 6d., a party of 8 or 10, 1s. each. Leave must be asked at the steward's house in the village for walking to the cave (about 11 m.) through the beautiful grounds of Ingleborough Hall (J. W. Farrer, Esq.).

Clapham (the name is probably identical with the Surrey Clapham = Clapa's ham or home) is a pleasant, bright village, with a broad "beck" running through it, and Ingleborough rising above. A white gate at the head of the village opens to the grounds, and close within it the road The l. road leads to the cave; that rt. to a waterfall artificially formed on the Clapham beck -a picturesque scene. The l. road soon opens to a tarn, of which the banks are covered with larch and fir plantations, and at the back are Clapdale scaurs, sprinkled with Keeping still to the l., through the wooded glen of the beck (where Listera ovata and many other limestone plants grow abundantly), you come to a limestone scaur half-hidden by foliage. In this is the cave, with a low opening; and just beyond, the stream rushes out of the rock and is crossed by a The cavern-which is nebridge. cessarily kept locked, or the stalactites would soon disappear-so far as it is now known, extends 2106 ft., nearly half a mile from the entrance. There is little difficulty in passing

with a due consideration for their dress, may safely make the adventure.

The cavern is throughout in the limestone. The first 80 vards have always been known to exist: but it was not until about the year 1837 that the wall of stalagmite which seemed to close the cave was broken through, and the rest of the cavern gradually explored. At the extreme end a stream of water falls into a deep pool, which Mr. Farrar explored by swimming, and found all progress stopped by a wall of limestone,—the "Heart of Ingleborough." The "Old Cave" is lined "with a brown incrustation resembling gigantic clusters of petrified moss." This is stalactite over which water has ceased to run, and which then loses its snowy whiteness. The New Cave beyond this portion is very different, and of extreme beauty. A passage, lined with masses of white, glittering stalagmite, rising in various shapes to the roof, leads to the Pillar Hall, where the roof is studded with stalactites of all form and dimensions. some having united with the stalagmite rising from the floor so as to form transparent pillars. There are pools of water on the floor and at the sides, and at the end a deep hollow called the Abyss. The growth of one of the stalagmites here, called the Jockey's Cap, was carefully measured in 1851 (it is fed by a single line of drops), and it was then found that, at the rate of 100 pints of water a day, containing 100 grains of calcareous earth, the Jockey Cap had taken 259 years to attain its burly size.

Beyond the Pillar Hall the passage is very narrow, and you have to creep forward for a few yards into the Cellar Gallery-long, tunnel-like. and without stalactites. This leads into the Giant's Hall,—again a magnificent mass of stalactite and stalagmite, and containing in its side two small holes leading to a lower through any part of it, and ladies, level, from which issues the sound of

a torrent, falling in perpetual darkness. It must have required no small courage to venture on the exploration

of this gloomy hollow.

"The roof and sides of the cavern are everywhere intersected by fissures which were formed in the consolidation of the stone. To these fissures." adds Prof. Phillips, "and the water which has passed down them, we owe the formation of the cave and its rich furniture of stalactites. direction of the most marked fissures is almost invariably N.W. and S.E., and when certain 'master fissures occur, the roof of the cave is usually more elevated, the sides spread out rt. and l., and often ribs and pendants of brilliant stalactite, placed at regular distances, convert the rude fissure into a beautiful aisle of primeval architecture. Below most of the smaller fissures hang multitudes of delicate, translucent tubules, each giving passage to drops of water. Splitting the rock above, these fissures admit, or formerly admitted, dropping water: continued through the floor, the larger rifts permit, or formerly permitted, water to enter or flow out of the cave. By this passage of water, continued for ages on ages, the original fissure was in the first instance enlarged, through the corrosive action of streams of acidulate water; by the withdrawal of the streams to other fissures a different process was called into operation. The fissure was bathed by drops, instead of streams of water; and these drops, exposed to air currents and evaporation, yielded up the free carbonic acid to the air, and the salt of lime to the rock. Every line of drip became the axis of a stalactitical pipe from the roof; every surface bathed by thin films of liquid became a sheet of sparry deposit. The floor grew up under the droppings into fantastic heaps of stalagmite, which, sometimes reaching the pipes, united roof and floor by pillars of exquisite beauty."- Rivers and Mountains of Yorkshire, p. 31.

White rats inhabit the cave, and fresh - water crustacea (among the rest, Gammarus pulex) are found in the subterranean stream.

Sand and pebbles from the hills above lie plentifully in certain parts of the cavern. These have been conveyed into it by the water, which, in all probability, finds its main entrance by a deep cavity in the limestone on the hill-side above, called " Gaping Ghyll." This is on much higher ground than the cave, and is an enlargement of the natural fissures of the stone. It is about 340 ft. in depth (the first landing-place is 190 ft. deep; from it the bottom, about 60 ft. lower, may be seen),and a " beck" flings itself into it with a grand fall in rainy seasons. way down this great opening a "subterranean" stream enters it from the side: the water thus swallowed up percolates through the fissures and hollows of the limestone, and then reappears near the mouth of the cave at an opening called "Little Beck The sand and pebbles brought in by the water have assisted in excavating the cavern.

Gaping Ghill Hole should be visited; and above it is another deep "pot" (at least 360 ft.), discovered in 1872 by Professor Hughes.

Ingleborough may be ascended from Clapham with ponies, going round by Newby Cote. The pedestrian may walk through the grounds to the cave, and then proceed upward by Gaping Ghyll. The distance either way is about 4 m. The ascent of Ingleborough—that "huge creature of God," as the poet Gray calls it in one of his letters-is nowhere difficult. The hill (like many others) is popularly said to be a mile high. is really 2361 ft. above the sea; higher than Penyghent (2231 ft.), but not so high as Whernside (2414 ft.). But the mass and peculiar outline of Ingleborough render it a better landmark than either of its neigh-

bour hills, and it is perhaps, more than any other, the great " representative" of the Yorkshire mountains. (Micklefell, in the N.W. corner of the county, is the highest, 2600 ft.) The mass of Ingleborough consists of three very distinct portions,-Ingleborough itself on the S., and Simon Fell and Park Fell successively N. The whole mountain is composed of slaty shales and limestones, capped by thick beds of millstone-grit, the limestone forming vertical cliffs or bands, while the shale is worn to slopes. The summit of Ingleborough itself, rarely free from clouds, is a broad level. There is a small irregular camp (British?) on the S. side of the hill, and on the summit what has been regarded as a walled hillfort, resembling some of those in N. Wales and in Ireland, and containing the foundations of huts. The area enclosed is more than 15 acres, the figure is irregular, and the wall a little within the rocky crest of the mountain. There are 3 openings through the wall, which is of varying height. The hut-foundations, 19 in number, are horseshoe-shaped, and are scattered irregularly over the area. A grander watch-tower than this fort can hardly be imagined. The view is magnificent and most interesting, embracing all the neighbouring mountain groups, besides others in Westmoreland and Cumberland, and extending far S. beyond Pendle Hill, in Lancashire, to St. George's Channel, which is visible at Morecambe Bay; Ingleborough is a landmark for ships off the Lancashire coast. Among the ferns on the limestone sides of the mountain are Polypodium calcareum, Allosorus crispus, Polystichum Lonchitis, and Botry-The Cloudberry chium Lunaria. (Rubus chamemorus) is found on the highest summit; and on the mountain (high up) Salix herbacea—a Scandinavian plant, one of the lingering survivors of a "flora" imported to Britain before the glacial period,

when these mountains and valleys were wrapped in a thick robe of ice. as Greenland is at present. The rounded and striated hill-sides and summits, over which we gaze from the top of Ingleborough, still bear witness to the glaciers and ice-currents that once moved slowly along and over them to the low country beyond.

[A good pedestrian may cross Ingleborough from Clapham, and, descending to the Ingleton road. visit Weathercote Cove and Chapel-le-Dale, and thence proceed to Ingleton. The distance altogether will be about 12 m.]

From the Clapham Junct. we reach 4½ m. Ingleton Stat. (Iss: the Ingleborough Hotel; and an old-fashioned inn, the Wheatsheaf.) The village is very picturesquely placed above a rocky beck, and at the junction of two valleys, divided by the mountain of Whernside. (A trap may be hired here.)

The views from the station are fine, with the flat top of Ingleborough conspicuous above rocky scaurs; and at the top of the hill above the village, where the road opens to the "Dale," the view is especially noticeable, with the Westmoreland mountains, peaked and serrated (differing in their slate outlines from the limestone), in the far distance. Ingleton Church contains Norm. portions (piers and font, which is of the local marble. and curious), but was partly rebuilt The place is noticeable in 1743. from the use which Souther has made of it in his 'Doctor.' Daniel Dove was at school here, and here he saw Rowland Dixon's puppets. tourist should at all events find his way from Ingleton by the Hawes road to the "Doctor's" birthplace at Chapel-le-Dale, and to Weathercote Cave, beyond it.

(a) There is a good view on the stream (the Dale beck, which descends

Chapel-le-Dale, and, after its junc- | sown them. To the east and west tion with the Kingsdale beck below Ingleton, forms the Greta river, flowing into the Lune) above Ingleton, and the whole course of the beck as far as Beesley, 14 m. from Ingleton, is very picturesque; but the road which leads up the dale beyond, with Whernside on the l. and Ingleborough rt., offers no very remarkable scenery until Chapel-le-Dale (4 m.) is reached. (On the western slope of Ingleborough are some deep "Pots" or caverns-Meregill, Barefoot-wives, Hardrawkin, and Great and Little Dowkbut none having the beauty or importance of Weathercotes.)

At Chapel-le-Dale the mountains shutting in the quiet pastoral dale are well seen. The little chapel, with the "manse" adjoining, lies between the road and the stream. and a very short distance above it is the old farmhouse which Southey has pictured as the ancestral home of the Doves. Often as his perfect and most accurate (except that there is no porch) description of the chapel has been quoted, it must be read on

the spot :-

"The little ch. called Chapel-le-Dale stands about a bowshot from the family house. There they had all been carried to the font; there they had each led his bride to the altar; and thither they had, each in his turn, been borne upon the shoulders of their friends and neighbours. . . . A hermit who might wish his grave to be as quiet as his cell could imagine no fitter resting-place. On three sides there was an irregular low stone wall, rather to mark the limits of the sacred ground than to enclose it; on the fourth it was bounded by the brook, whose waters proceed by a subterranean channel from Weathercote Cave. Two or three alders and rowan-trees hung over the brook, and shed their leaves and seeds into the stream. Some bushy hazels grew at intervals along the lines of the wall; and a few ash-trees as the winds had a dim half-twilight. The trees and [Yorkshire.]

some fields adjoined it, in that state of half cultivation which gives a human character to solitude; to the south the common, with its limestone rocks peering everywhere above ground, extended to the foot of Ingleborough. A craggy hill, feathered with birch, sheltered it from the north.

"The turf was as soft and fine as that of the adjoining hills; it was seldom broken, so scanty was the population to which it was appropriated; scarcely a thistle or a nettle deformed it, and the few tombstones which had been placed there were now themselves half-buried. sheep came over the wall when they listed, and sometimes took shelter in the porch from the storm. voices, and the cry of the kite wheeling above, were the only sounds which were heard there, except when the single bell which hung in its niche over the entrance tinkled for service on the Sabbath day, or with a slower tongue gave notice that one of the children of the soil was returning to the earth from which he sprung.

After lingering in this quiet place, Weathercote Cave must be visited. The first gate 1. beyond the chapel leads to Mr. Metcalfe's house—the original of Daniel Dove's-where the key will be furnished. (1s. is charged for each visitor.) Weathercote is, without exception, the most picturesque of the many Yorkshire caves; and it would be difficult to find elsewhere as striking a scene of the same The "cave" is now a character. deep, rocky chasm, with a waterfall at the farther end. The cave is entered by a steep flight of steps, under overhanging blocks of stone, touched here and there with ferns and mosses. At the bottom you find yourself in front of the fall-80 ft. in heightdescending among huge blackened blocks with a deafening roar, and in

chasm. The stream leaps from a hollow at least 30 ft. below the surface; and immediately above it a huge mass of rock is suspended between the cliffs at the side. On sunny days, between 11 and 12, a rainbow . hangs over the spray of the fall, tingeing the mosses with its colours. This effect is well worth seeing; but the solemn grandeur of the scene is independent of weather. A recess at the side of the fall, which it is possible to gain, affords a good view of the manner in which the water is swallowed up among the pebbles, to reappear below. You may even get behind the fall and look through it, as at Hardraw; but at the risk of a good wetting. The stream which supplies the fall disappears underground on the moor about 1 m. higher up. In winter, or after much rain. the whole cave is full of water; and small fir-trees, brushwood, and rushes. which have been brought down by floods, are seen entangled among the bushes above the opening. Westall and Turner have illustrated Weathercote-which may well attract the artist, as it will certainly try his powers. A little above the entrance to the cave, rt. of the road, is a humble but comfortable Inn.

Between Weathercote and Chapelle-Dale are two great crevices or caves in the limestone, Gingle Pot and Hurtle Pot. The first is usually dry and about 80 ft. deep. The other contains a pool of unknown depth, in which are small trout. The water from Weathercote is perhaps connected with this pool. 1 m. above Weathercote is Gatekirk Cave. traversed by the stream that forms the Weathercote Fall. Gatekirk was once enriched with stalactites, but the greater part has been destroyed by visitors. It is about 80 yards long, and is perhaps worth seeing, though far less important than the Clapham

bushes meet above the line of the across the base of Whernside (about 3 m.) to Kingsdale. (See post.)

Ribblehead Stat. (Rte. 32) is 14 m. from Weathercote and Chapel-le-Dale.

The Inn at Gearstones (see Ric. 32) is 3 m. from Chapel-le-Dale. road hence to Hawes (9 m.) is somewhat desolate, with wide, far-stretching hill-slopes, and no special points of interest.

(b) Wherneide forms a long insulated mass, 2414 ft. high, and by no means so picturesque in its outlines as Ingleborough or Penyghent: like them, it is of limestone, capped with millstone-grit, and is easily ascended from the E. or S.E. It is steep and difficult on its western face over Dent Dale.

Whernside (or rather the long spur which it throws out S.) separates the two valleys which unite at Ingleton. The western valley, Kingsdale, contains some very interesting scenery. It is a long glen in the scar limestone, which, at Thornton Force, 1 m. from Ingleton, joins the slaty rock. much quarried in the neighbourhood. Thornton Force is a waterfall of 30 ft., poured " from a ledge of limestome over a breast of slate—the horizontal beds of the upper part contrasting curiously with the angularly meetingpoints below."—P. From Ingleton the walk to the Force along the ridge of the glen, on the rt. side of the stream, should be followed. whole wooded ravine is striking; and all the accompaniments of the falltrees, rocks, and background-will delight the artist. Behind Thornton Force stretches Raven Ray, a deep pass between high rocks; and beyond it. Kingsdale—a long, narrow glen, between Ingleton Fells (the lower spurs of Whernside) and a long ridge called Gragreth. Kingedale is well worth penetrating, at least as high as Yordas Cave, 41 m. from Ingleton. Cave. (See case.) You may walk Grand scars of rock tower upwards on

Yordas Cave (so called ! its W. side. from a traditional giant, whose chamber and oven are pointed out in the limestone) is at the foot of the upper slopes of Gragreth. It is a grand limestone cavern, rich in stalactites, with 2 chambers; the first, 60 yards long by more than 20 yards high; the second, circular, with pillars of stalactite, and (in wet seasons) a cascade, curiously enclosed within an inner hollow. (To see Yordas Cave it is necessary to write beforehand to Mr. Whittingdale, of Westhouse, Bentham, fixing the time for the visit.) Gingling Pot, and Routing Pot, are deep hollows in the limestone, im. S. of Yordas, and higher up the side of Gragreth.

TAcross the hill, west of Yordas Cave, and in Lancashire—(the Yorkshire border runs along the top of Gragreth,—Dent Crag, 2253 ft., a little farther N., marks the junction of Yorkshire, Lancashire, and Westmoreland)-is Easgill, a very remarkable valley on a stream which descends to the Lune. The upper part of Easgill is of limestone, wasted by water and storm into all manner of fantastic shapes, and full of small winding caverns, partly laid open by the falling of the limestone. This mass of open caverns, about which there is much wood, is known as Easgill Kirk, and is well worth a visit. Easyill itself, shut in by steep precipices, opens into a wider and very beautiful valley, to which the slate rock gives a totally distinct These very interesting character. scenes are best visited from Kirkby Lonsdale. (See Handbook for Westmoreland.) In walking to the village of Thornton in Lonsdale, 1 m. W. of Ingleton, you pass from the limestone to the slate - with a change of scenery, from wild moor to rich pasture, which is positively startling. Thornton Ch. (restored) is of some interest, since portions are early, and there is a range of Norm. arches he-

tween nave and N. aisle, besides a Norm tower-arch. Near it is a country Inn, with the date 1672 on its front, which might do for a tourist not too exacting.]

(From Ingleton you may proceed by rail to Kirkby Lonsdale and Sedbergh (Rte. 24); and thence up Garsdale and Wensleydale, by Hawes, to Leyburn. (Rte. 24.)

ROUTE 33.

SETTLE TO CHATBURN. (GISBURNE, SAWLEY ABBEY).

The railway from Settle to Chatburn, in Lancashire, joins the line running by Blackburn and Bolton to Manchester. It follows the valley of the Ribble; and near Hellifield, on the line between Settle and Skipton (Rte. 32), there is a junction with the Midland Rly., from Settle to Carlisle (Rte. 32).

The valley of the Ribble between Hellifield and Gisburne is in parts very pretty, green and pastoral. At Halton there is much wood, and Penyghent is conspicuous in the distant view, N.

Gisburne Stat. (Inn: Ribblesdale Arms, a comfortable old-fashioned house, characteristic of old Craven building, with the date 1635 over the porch). This is a quiet village, the character of which is likely to be much

2 m 2

changed by the railway. The Church, late E. E. and Dec., with Perp. tower, has been restored, and stands in a ch.-yd. surrounded by fine sycamores, in one of which the curfew-bell was

long hung.

Gisburne Park (Lord Ribblesdale) opens close from the village, and is very pleasantly placed at the confluence of the Ribble and Stockbeck. The park is varied, with much fine wood and broken ground, and there are some very striking views into and across the wooded glen through which the Ribble here passes. The house (which is modern, and of little architectural character) is shown in the absence of the family, and contains some interesting pictures. In the Library is a portrait of Major-Gen. Lambert (see Kirkby Malham, Rte. **32).** The Drawing-room, among other good pictures, contains-Thomas Lister, first Lord Ribblesdale—a boy of 13-a most graceful portrait, by Sir J. Reynolds: Beatrix Lister, his sister. Sir J. Rewnolds: Henrietta of Orleans, and an Infanta of Spain, both by Vandyck; and Martin Rycaut (a duplicate of the picture at Warwick), also Vandyck; Flowers and Fruit, Van Os: and Diana and Acteon, Filippi (?). In other rooms are-Tobit and the Angel, Gerard Dow; Chateau of Muyden, in Guildres, Cuyp; 1st Lord Ribblesdale. Sir Thos. Lawrence; William III.'s Yacht, Backhuysen; President Bradshaw, Walker; Cromwell, Sir P. Lely. (On the canvas is the word "Now." referring perhaps to the mandate signed by him for the immediate execution of the King. This picture was brought from Calton Hall, the old home of the Lamberts, and may have been Cromwell's own present to the General.) Attorney-General Lee, Sir J. Reynolds; Sir Martin Lister, Janssens; Miss Assheton, as a shepherdess, Dahl; Gisburne Park in 1730, with portraits of the Listers, and the white cattle in the background, Nollekens.

The last of the white cattle kept for many ages in Gisburne Park were killed off in 1859. Only two or three remained; and there was no prospect of perpetuating the race. They differed from the wild cattle of Chillingham in Northumberland, and of Cadawa near Hamilton, in being without horns, but were like them in all other respects—white, with hlack muzzles, feeding toward dusk, and showing a wild, half-savage nature.

A curious ancient drinking-horn is preserved at Gisburne Park. It is the horn of a buffalo, containing about 2 quarts and supported on 3 silver legs. Round it are silver filetings with inscriptions, one of which runs, "Qui pugnat contra tres perdet duos."

[On the rt. bank of the Ribble, 3 m. below Gisburne, and very picturesquely placed, is Bolton Hall (C. B. E. Wright, Esq.), (generally called "Bolton-by-Bolland"—it is in that forest—to distinguish it from the many other Yorkshire Boltons), the ancient house of the Pudsays, still interesting in spite of much alteration. Parts of it are perhaps as early as the reign of Edw. III., especially the hall, and the adjoining "King's Room" with a chamber called Paradise over it. Almost immediately after the battle of Hexham (May 15, 1464) Henry VI. reached Bolton as a fugitive, and was concealed here by Sir Ralph Pudsay, a zealous Lancastrian. A well adjoining the house is called "King Harry's," and is said to have been walled and protected as a bath for the unfortunate monarch. who found some months of repose among the quiet woods of Bolton :-

"Gives not the hawthorn bush a sweeter shade

To shepherds, looking on their silly sheep. Than doth a rich embroidered canopy To kings that fear their subjects' treachery?"

-K. Hen. VI., Pt. III., act fl. sc. 5.

From Bolton King Henry visited Pracewell, Whalley Abbey, and Wad-

dington Hall, at which last place (about 6 m. farther down the river. on the Yorkshire side) he was taken by Sir James Harrington, after more than a year of concealment. dington then belonged to the Tempests; and a monk of Whalley seems to have been the King's betrayer. Waddington Hall has lost all its ancient features. A pen-case, brought from there, which belonged to Henry VI., is now among the treasures of Parham in Sussex. The limestone about Bolton is cavernous, though not to the extent of that forming the North Craven hills.

The banks of the river here are very beautiful and finely wooded. Not far beyond the house is a scaur, called "Pudsay's Leap," from which one of the Pudsays is said to have leaped on horseback, when pursued by the queen's (Elizabeth's) officers. He had been "false coining" with lead found on his land; and after escaping he is said to have made his way at once to the queen, who promised him pardon for everything but murder. (Some of his false silver pennies still exist in Craven.) Farther down the river is a fine point, called Denholm Wheel, or Weil (well?). There is a sulphur spring near the scaur, and others in the neighbourhood.

Bolton Church, almost entirely Perp., is possibly the work of the same Sir Ralph Pudsay who sheltered Henry VI., and deserves a visit. The font, of grey marble, has on its 8 sides the shields of Pudsay and of connected families. On a brass let into the marble is the inscription :-- " Orate a'i'bu' D'ni Radulphi Pudsay, Milit. et D'ne Epw'ne uxor' ejus. ac D'ni Wil'i quondam filii eoru'd, rector' huj' eccl'ic." On the S. side of the choir is the Pudsay chapel, of later date than the rest of the ch., and against its N. wall are the brasses of Henry Pudsay, "Armiger, dominus de Bolton, qui construxerat hanc cantariam, et obiit MDIX." (he is in an heraldic dress), and his wife Margaret. Between this chapel and the chancel is a remarkable high tomb, covered with a slab of Craven marble, 10 ft. by 6 ft., having on it, in low relief -above, the figures of a Pudsay and 3 wives, with figures below each, 6, 2, 17, referring to the number of their children; and below, smaller figures of these 25 children. It is raised on a white altar-base, with shields. The Pudsay who rejoiced in these numerous olive-branches was Sir Ralph, the faithful Lancastrian, and the probable re-builder of the ch., and an inscription records the restoration of the tomb "by his descendant and heir Pudsay Dawson, of Hornby Castle, Esq.," in 1857. The Pudsay motto, "Penser peu de soy," appears on the tomb, and the arms, a chevron between 3 stars, are on the knight's breast, his folded hands being ingeniously arranged to form the chevron. In the chapel are modern monuments for H. A. Littledale, Esq., who represented the Pudsays through the Dawsons, and for others of his family.

(At Bolton the road from Skipton joins that from Settle to Burnley. The Settle road runs for much of its course through the valley of the Ribble, and is pleasant. There is a pleasanter road from Bolton to Settle. however, by Forest-Becks to Wigglesworth (where is a medicinal spring. In Tosside Chapel, 1 m. l., is a curious font of late date), and thence by The distance by either Rathmel.

road is nearly 12 m.)]

31 m. from Gisburne, in the vale of the Ribble, and just above the point where that river becomes the boundary between Yorkshire and Lancashire, are the ruins of Sawley Abbey (Cistercian). The actual remains are very slight, and of little architectural importance; but the ground-plan, by the direction of the Marq. of Ripon, the present owner of the abbey, has been

most carefully traced; and in this! respect Sawley is as intelligible as Fountains, St. Mary's at York, or Jervaulx-the only other monastic houses in Yorkshire which have been

properly excavated.

Sawley (no doubt, as Whitaker suggests, the "willow field," seal, A.S. = a willow) was founded in 1147 by William de Percy, Lord of Topcliffe and Spofforth, and of the whole of Ribblesdale within Craven. house (which was dedicated to St. Mary and St. Andrew, and known as " Mons Sti Andrese de Sallay") was colonised from Newminster in Northumberland—the first offshoot from Fountains: but about 40 years after its foundation, the poverty of Sawley was so great that it would have been suppressed, had not Maud Countess of Warwick, the daughter and heiress of the founder, granted to it the ch. of Tadcaster, and 100 acres of land in Calton. where she was born. last abbot, William Trafford, was concerned in the Pilgrimage of Grace, and was accordingly hanged at Lancaster (1537). The house, which was then dissolved, was granted to Sir Arthur Darcy, one of the Northern Commissioners for the suppression. From him it passed through many hands to its present owner.

The site of Sawley can never have been so secluded as those of other Cistercian houses in Yorkshire; but the highway, which now runs close to the ruin, was originally on the W. of the mill-stream; and the park or close, of about 50 acres, quite surrounded the abbey. This close, which was entered by two gates called N. and S. port, has been cleared of hovels and fences; and from the high ground above it there is a very fine view up and down Ribblesdale. old poverty of the house is shown by the rough material (black shale and boulder-stones) with which the buildings were constructed, until shortly before the Dissolution, when ashlar

progress of alteration when the house was suppressed; and the plan, owing to the condition in which the work was arrested, is at first perplexing. The first ch. was cruciform, but with the great peculiarity that the length of the transept exceeded that of the united nave and choir by 12 ft. Nave and choir were aisleless. The transept had 3 eastern chapels in each wing. The short nave, of which the walls remain to a height of 25 ft., seems to have had no side windows. and to have been lighted only from above the W. door. Outside its N. wall is a foundation ranging with the nave, but prolonged considerably beyond it. The walls of the transept remain about 12 ft. high, and the eastern chapels are worth attention. In the southernmost is a large tombslab, sculptured with 2 foliated crosses. and 2 skeletons were found in the grave below. S.W. of it, in the body of the transept, is the tomb-slab of William of Rimington, Prior of Sawley, and, in 1372, Chancellor of He was named, no doubt. Oxford. from the neighbouring village of Rimington, and was probably the "William of Rimington" who wrote sundry tracts against the Wickliffites remaining in MS. in the Bodleian The pavements in the Library. middle chapel of each transept wing are of the 13th cent.. excellent in design, and closely resembling one found in 1760 at Meaux Abbey (see Rte. 7), also Cistercian. In the northernmost chapel is a slab from which the brass has disappeared, but which covered the remains of "Sir Robert de Clyderhow," once "Parson" of Wigan, in Lancashire. Robert was a strong supporter of Thomas Earl of Lancaster, in his contention with Edw. II. in 1821. Outside this chapel, but in a sunk area of the transept floor, is a slab of the 14th cent., with cross and sword, and what seems to be a sling for casting stones. A slab forming a step of the doorway stone was used. The Church was in | in the S. wall of the transept also deserves attention; it bears a cross, the bar and stem of which are formed by an enormous sword. The choir seems to have been rebuilt in the Perp. period: although the walls of the original Norm, choir, about 9 ft. high, still remain, and were probably left until a central tower could be erected. The Perp. choir was much longer, and had aisles. That this choir was completed is to be inferred from the existence of part of the floor of the high altar, and from the discovery of much Perp. glass upon and around it.

At the S. end of the transept are the foundations of the chapter-house, and of 2 adjoining apartments not easily appropriated. The unusual shortness of the Norm. nave interfered altogether with the usual arrangement of the cloister court; and accordingly buildings were continued beyond it, in a line with its eastern side. These were probably the Fraterhouse (or common refectory), with buttery and other offices attached. The S. side of the cloister court has been demolished nearly to the foun-Here, however, were the great refectory (102 ft. by 28) and kitchen. On the W. side seems to have been the Abbot's house, enlarged apparently in the Perp. period. At the southern angle is a cottage (of Tudor works), which has been inhabited since the Dissolution, and was probably part of this house.

Of the farm-buildings of the abbey, a granary and corn-mill alone remain, at a short distance W. The northern gate-house-in which the Tudor arch of the outer and inner walls is alone ancient—stands about 270 ft. from the ruins. Much stained glass, many encaustic tiles, and other fragments, were found during the excavations, and carefully preserved. (Mr. J. R. Walbran's paper on the excavations here will be found in the Report of the United Archit. Soc. for 1852.)

boundary of Yorkshire is crossed. and we reach the rly. stat. at Chatburn. (See Handbook for Lancashire.)

From Chatburn, Pendle Hill may be ascended; and Clitheros Castle and Whalley Abbey, both very interesting, may be reached in a few At both places there are minutes. stations. Clitheroe was a castle of Whalley (on the Calder) the Lacys. was Cistercian, and there are many remains, including one of the finest monastic gatehouses in England.

The corner of Yorkshire of which the Ribble forms the boundary is interesting from the great mass of Pendle Hill (across the border), which so often forms the background of picturesque views. The old forest of Bolland or Bowland, which lifts its limestone summits toward the N.W., is a district which will hardly reward the patience of the explorer. It is the watershed of streams which run into the Lune on one side, and into the Ribble on the other; and the Yorkshire boundary passes along the crests of its highest ridges - Wolf Crag, Cross of Greet, Bolland Knots, and Burnmoor - names which are more picturesque than the country in which they are found. "On the northward slope of Bolland Knots, looking toward Ingleborough, many fragments of trees appear, rooted below or lying prostrate in the peat, especially in situations where water might stagnate, at elevations and in aspects where now the utmost art and care fail to raise oaks or pines, or indeed any tall trees. This is one of many examples spread over the British Isles and Northern Europe, for which no satisfactory explanation can be given by climatal variation of merely local character. Similar phenomena have been noticed on the E. side of Ingleborough at more than 1300 ft. above the sea."-Phillips.

A Roman road ran through this About 1 m. beyond Sawley the part of Craven from Ribchester (Coc-

ceium?) in Lancashire to Over-| kinds that rise along the valley; still borough (Bremetonacse?) in West-Great part of this road, moreland. which crossed the Hodder W. of Browsholme, has been traced. The Hodder, a picturesque tributary of the Ribble, descends from Longridge, a conspicuous fell W., and forms the boundary between Yorkshire and Lancashire from its junction with the Ribble as far as Whitewell. A little above the Junction, on the rt. bank of the Hodder, is Stoneyhurst College (Handbk, for Lancashire.) Bashall, an ancient house of the Talbots, and Browsholme (Thomas Goulbourn Parker, Esq.), a house dating from the reign of Hen. VII., are in the valley of the Hodder, and may easily be visited from Clitheroe.

ROUTE 34.

LEEDS TO SKIPTON, BY BINGLEY AND KEIGHLEY (SALTAIRE; HAWORTH).

(Midland Railway. 261 m. To Skipton, 11 trains daily; to Brad-

ford, 21.)

Leaving Leeds from Central?, the Wellington or the Holbeck Stat., the rly. throughout its course to Skipton runs through the valley of the Aire. The river is accompanied by the Leeds and Liverpool Canal; at first on its S. side, afterwards on the N. River and canal are alike black with streams that run into them from the many dyeworks and factories of all

pretty and wooded, in spite of the change which has filled it "with mills and looms, water-wheels and engine-chimneys." Airedale and Calderdale are the two great centres of Yorkshire enterprise and manufacture.

(The Leeds and Liverpool Canal was partly opened in 1774, but the works, which were commenced s: both ends, proved very difficult and expensive, and the canal was not finished until 1816. James Brindley, the famous engineer of the Bridgewater Canal, surveyed and laid out the whole line of this navigation, 130 miles in length. The advantages of the canal are still felt, not withstanding the railways which have since been constructed; and the rise of Leeds, Bradford, and other manufacturing towns on its course has no doubt been hastened by the facilities afforded by it. It was the first good "highway" for the conveyance of raw material and manufactured produce along the valley of the Aire to Liverpool.)

Hardly beyond the smoke and stir of Leeds is.

13 m. Armley Stat., a large village, chiefly inhabited by the "hands" who work in the neighbouring factories. On the hill above is Armley House (John Gott, Esq. -it is not generally shown), containing some good pictures, including some of the best portraits of Sir T. Lawrence. The house stands in a park, the trees in which would be fine but for the smoke, and commands good views over Kirkstall. In Armley Church, rebuilt 1835, is a monument, by Joseph Gott of Rome, for the late Benjamin Gott, the founder of Armley, and the proprietor of the largest cloth-works in Leeds. His figure is sculptured reclining on a mattress.

Passing 31 m. Kirkstall (see Rte. 29) Stat., where the Abbey rains are seen rt., and Kirkstall Forge, where | removed a few years ago from Little are the large ironworks of Messrs. | Horton (Bradford), where it was esta-Beecroft, we reach

42 m. Newlay, where the Airedale Dye-works send their black streams

to the river: and

52 m. Calverley Stat. l. at some little distance is seen Calverley Church: rt. is Horsforth Old Hall. now a farm; but a good example of the Jas. I. Yorkshire "hall-house" of a smaller proprietor. It is the mixture of these old houses, and of other more ancient remains, such as British camps and Roman roads, with the vast population, the chimneys and long window-ranges of modern factories, that gives such a peculiar character to much of this district.

In the village of Calverley is Calverley Hall, still nearly the same as when, in 1605, it was the scene of that succession of murders which were dramatised under the name of the 'Yorkshire Tragedy'-a play which has been assigned, and with less improbability than many others, to Shakspeare. A family of the same name had been settled at Calverley since the 12th cent. Their representative, Walter Calverley, a man of evil life, who had dissipated nearly the whole of his estate, in a fit of jealous frenzy and remorse killed his two sons and his wife (April 23, 1605), and then attempted to make his own escape. But his horse fell, and he was taken. After having been examined by Sir John Savile of Stowley, he was conveyed to York Castle. On his trial he refused to plead, and suffered accordingly the "peine forte et dure," being pressed to death. By this means he preserved the remnant of his estate to a third son, who was at nurse when the others were killed. and so escaped. The room in which the murders were committed is still pointed out.

On the brow of the hill, below Rawdon, near Apperley Bridge, is the Baptists' College, for educating young

blished in 1805. On the hill above, Billinge, a gold torque was found many years ago.

About 11 m. from Apperley Stat. is Esholt Hall (Col. W. H. Crompton Stansfield), approached by a fine avenue of elm-trees. It was built 1707 by Sir Walter Calverley (whose father, one of Chas. II.'s knights of the Royal Oak, had married the heiress of Thompson of Esholt), on the site of a nunnery for 6 Cistercian nuns, founded by Simon de Warde in the 12th cent. Some remains of the ancient priory exist in the present house. (Esholt=Ash-wood. An osierbed is here called an "osier-holt.")

73 m. Apperley Bridge Stat. After crossing successively the river and the canal, the rly. passes through a long tunnel in the projecting hill, which here occupies an angle of the river. At

11 m. Shipley Junct. Stat., a branch line turns S. up the course of the Bradford Beck to (132 m. from Leeds) Bradford. (See Rte. 35.) Here also is the junction of the Midland system. of rlys. with a line which, passing round the hills to Laister Dyke, on the Gt. Northern Rly., between Leeds and Bradford (Rte. 35); and here a short line of rly. branches off to Guiseley, materially shortening the distance between Bradford and Ilkley. (Rte. 30.) Shipley, full of mills and dye-works (Pop. of parish in 1881, 15,089), has a Perp. ch. of little interest; but in the parish is what every visitor to this neighbourhood who cares for factories and their most perfect arrangements should endeavour to see-the great establishment of Saltaire.

Saltaire Stat. 2 m. beyond Shipley. Most but not all the trains stop here. The manufactory is not shown withmen as Baptist ministers. It was out an especial introduction.

exterior, however, the church, and the from alpaca-wool consist of alpaca

village are well worth a visit.

Saltaire-manufactory, town, and ch.-has arisen entirely from the energy and resources of the late Sir Titus Salt. The factory was opened in 1858, when an entertainment was given in it to more than 4000 persons. The position of the great factory on the bank of the river is striking. the N. side the bank is high and well wooded: a dam across the Aire gives a dash of white foam as a foreground to the mass of plain but good Italian building, with the ch. opposite the main entrance. The Byzantine character of this ch., which has a gilt spike upon the cupola of its tower, assists the "Imperial" impression produced by the entire settlement. The whole is, in fact, very Russianthe work of one autocratic mind.

This is a worsted factory, like most of those in the neighbourhood of Bradford; but its great feature is the manufacture of alpaca fabrics. alpaca (the wool of which had been spun and woven into stuffs of great beauty by the ancient Peruvians, among whom Pizarro, in 1525, found the animal, called by them "Pacos." domesticated) was first brought to England in 1809. Some attempts, which proved unsuccessful, were made to acclimatize it; and some of the wool, imported from S. America, had been spun and woven in the neighbourhood of Bradford, with unsatisfactory result, until Mr. Salt finally overcame "the difficulties of preparing and spinning the alpacawool, so as to produce an even and true thread, and by combining it with cotton warps, which had then (1836) been imported into the trade of Bradford, improved the manufacture, so as to make it one of the staple industries of the kingdom."--(James, 'Hist. of Worsted.') An enormous quantity of alpaca-wool is now annually imported, nearly all of which is worked up in the Bradford district. The main articles now manufactured

histres (dyed) and alpaca mixtures (undyed), both made of cotton or silk warp. Great quantities of "fancy alpacas" are also made, varying with varying fashions, and distinguished by all sorts of fantastic names. Those who are fortunate enough to see the works here will find a stuffed alpaca and its young one at the end of the first office. The animal is about the size of a full-grown deer, with a fleece averaging from 5 to 8 in. long. Passing beyond this office, the whole process of preparing and spinning the wool, from its first arrival in great bales to the finished fabric of various descriptions, may be seen and wondered at.

Besides alpaca, Russian, "Botany" wool, mohair (or goat's hair), and silk are used here. The "Botany" wool (from Van Diemen's Land) is softer and finer than any other; alpacawool, in its natural state, is of three or four colours—grey, brown, and almost black. In the first rooms goes on the cleaning, combing, and washing of the wool, all by machines of great ingenuity and beauty. Then. ascending by the lift, we pass to the rooms where the spinning of the wool is in progress — the fibre passing gradually through different machines to its last and finest condition. other rooms the actual weaving may be seen, and the fabrication of almost every kind of material for which the various wools (sometimes mixed with silk) are used. The vast length of the rooms, where the eye loses itself in the perspective of machinery, and the ear is half deafened by its clang: the perfect order and cleanliness, and the multitude of well-dressed, healthylooking "hands," although they are characteristics of many a great Yorkshire factory, are especially striking The main shafting, moving the machinery, is placed under the floor of the weaving-room, which is thuentirely without the giddy whirl d the gearing, and is comparatively free from dust. (James), 'History of Worsted Manuf.' The warehouses, the rooms for mending the machinery, and the engine-rooms are not less

interesting.

The factory (which covers 12 acres. is 6 stories high, 550 ft. long, 50 wide, and 72 high) stands on the S. bank of the Leeds and Liverpool Canal, between that and the river. from which the water for the works is supplied. Its architects were Messrs. Lockwood and Mawson of Bradford. The walls, enormously thick, are supported by arches on iron pillars. The roof also is of cast iron, and the whole building is fire-proof. "Congregational" Church opposite (it cost 11,000L) is fine. Close to the stat, are schools for the express use of the workmen's children. In the town. which is built entirely of stone, streets of houses are arranged for the workmen, who pay a very mode-There is a working men's rate rent. club and Institute, which cost, it is said, 30,000%; a dining-hall; baths and washhouses; a square of almshouses; and a dispensary; the whole built at the cost of the late Sir Titus Salt, Bart.; and finally a Park of 14 acres, laid out in an ornamental manner, also given by him, was opened in July 1871, when he stated that Saltaire was at last completed. This park includes a cricket-ground of 5 acres, a bowling-green, and croquet-ground; and a noble terrace, reaching the full length of the park, is a striking feature.

You may walk from Saltaire, across Rumbald's Moor, to likley, 7 m.

(Rte. 30.)

Leaving Saltaire, the hills become steeper and more picturesque on the N. side of the valley; the "Loadpit Beck" descends through a wooded glen to join the Aire on the W. side of Baildon Common (927 ft.), a high ground marked by some cairns and barrows; and (entering the district of Craven a little before) we reach

141 m. Bingley Stat., close to a series of canal locks. An arched tunnel of masonry, 150 vds. long, conveys the rly, under part of the town. Bingley (Pop. in 1881, 9465; Imp. district, 8972) is, like all these towns, busily engaged in the woollen The first worsted factory was built here about 1806 (shalloons and calimancoes had been made here long before), and there are now more than 20 large worsted factories in the parish. The town consists for the most part of one long street, and is very picturesquely placed on high ground between the river and the canal. The Church is Perp., but has been modernised. A castle (it is said) once existed here, of which there are no traces; and there is now nothing to delay the tourist in Bingley. (The churchwardens' books contain some remarkable entries relating to the purchase of wine for the Communion in 1651: "20 quarts of wine for the Christmas Communion. 1li.; bread, 1s. 2d. 20 gallons of wine for Easter Comm., 4li.; bread, 3s. 1d." This extraordinary disproportion was perhaps a Puritan peculiarity)

Beyond Bingley the sides of Airedale are covered with fine natural wood; and although worsted and cotton mills are everywhere present, the valley is very beautiful. view of it is obtained from the "Druid's Altar," a projecting rock on the side of Harden Moor. (Harden Grange, on the S.E. side of the moor, is the residence of W. Ferrand, Esq.) The rock which forms the high ground on each side of the valley is millstone-grit, which has been quarried largely for building purposes through Airedale. At Morton, on the hillside, rt., a great quantity of Roman coins (no Roman road has been traced through the valley) were found toward the end of last cent. They were denarii of Sept. Severus, Caracalla, and Geta, and had been contained in a brass chest, perhaps the military chest of a

Legion.

A little before reaching Keighley, rt., is seen *Riddlesden Hall*, an excellent specimen of a good Yorkshire house of the 16th and 17th cents. It stands on a knoll overhanging the river, and belonged to the Paslews. The house has now fallen from its high estate, and is divided into tenements.

171 m. Keighley Stat. (pron. Keatley or Keathley), from which Haworth may be visited. The stat. is 1 m. from the town (Inn, Devonshire Arms). Keighley has been transformed from a populous oldfashioned village into a still more populous town. (Pop. in 1881. 25.245.) It stands very pleasantly at the entrance of a lateral valley, down which the small river Worth hastens to join the Aire. Woollen and worsted manufacture was early introduced here, the weaving of stuffs gradually absorbing the more ancient manufacture of woollen cloth. The first cottonmill was erected in 1780. The business of the place has largely increased since 1840; it is still rapidly extending. The largest mill is that of Messrs. Craven. Keighlev is the last manufacturing town of importance on this side of Yorkshire. Church, once E.E., was "modernised" in 1710, and almost rebuilt in 1847 and 1878. It contains nothing of interest, except two slabs with crosses and inscriptions for the "Kyghlay," or Keighley family, whose heiress transferred the manor and estate to the Cavendishes.

A very pleasant walk of between 7 and 8 miles, over Rumbald's Moor, will bring the tourist to Ilkley (Rte. 30.) Rail to Halifax, Great Northern.

The Branch rly. from Keighley to Haworth and Oxenhope, at the head of the Worth valley, has a station at Haworth. The distance is 4 m., but, as there are stoppages at four other stations, the time occupied is 15 m.

The stream of the Worth has been utilized for many mills throughout the valley, which is marked by factories and rows of workmen's houses, and "can hardly be called country any part of the way." There are stations at Ingrove, at Damens, and at Oakworth; and the train then reaches

Haworth Stat. The village (Inn: Black Bull) lies 1 m. rt. of the stat. and "is situated on the side of a pretty steep hill, with a background of dun and purple moors, rising and sweeping away yet higher than the ch.. which is built at the very summit of the long, narrow street. All round the horizon there is this same line of sinuous, wave-like hills, the scoops into which they fall only revealing other hills beyond of similar colour and shape, crowned with wild, bleak moors."-Life of C. Bronte. In the grey village itself, the places of pilgrimage are the parsonage-house and the ch. The former, which is the highest house in the place, overlooks the churchyard, and it was to it that Mr. Brontë brought his wife and children in Feb. 1820. Charlotte, the eldest, was born in 1816, at Thornton. about 4 m. W. of Bradford (see Rte. 35): she died May 31, 1855, in the parsonage of Haworth, having been married to the Rev. A. B. Nicholls on the 29th of June in the previous year. With the exception of a short residence in Brussels, her life was spent almost entirely at Haworth. novels were written here; and the wild, grim features of the surrounding moors, together with the scarcely less grim character of the population that nestles under and among them, are faithfully reflected in her writings. The tourist will hardly visit Haworth without Mrs. Gaskell's 'Life' in his hands or in his memory; and he must be referred to it for full particulars of the strange and solitary existence led here for so many years by the Brontes. Mr. Bronte, the father, died, aged 85.

in 1861, having survived all his children, and having been incumbent of Haworth for more than 41 years.

The vicarage and its garden remain as in the time of the Brontës, except that the windows of the old house have been filled with large glass panes, and that a new wing has been added (1871) on the N. side.

The Church, Perp., was pulled down, except the tower, in 1879, and a neat Gothic Church, by Healy of Bradford, supplies its place. A tablet on the chancel wall records the deaths and ages of the Brontë family, all of whom are buried here, except Anne (authoress of 'Agnes Grey,' and the Tenant of Wildfell Hall '), who died was buried at Scarborough. Emily, the authoress of 'Wuthering Heights,' -a story in which the gloomy, half-mysterious influence of this lonely country is strongly feltdied in 1848; and Charlotte Brontë (Currer Bell) died 1855. The register, with C. Brontë's autograph, is shown. The visitor will do well to climb the moors at the back of the parsonage, if he desires to make himself acquainted with scenery that had its full share in nurturing the genius of Charlotte Brontë.

A path by the side of the vicarage will lead straight to the moors, which are hardly picturesque—rather high, undulating ground, thinly covered with heather and bilberries. About 2 m. from the vicarage is a waterfall. often visited by C. Brontë.

Mrs, Gaskell has given some curious anecdotes illustrating the character of the people of this neighbourhood -- "self-sufficient" in the widest sense, relying on their own energy and power, "sleuth-hounds in pursuit of money," and as strong "There is little haters as lovers. display of any of the amenities of life among this wild, rough popula-Their accost is curt, their lation. accent and tone of speech blunt and harsh. Something of this may probably be attributed to the freedom | village of Crosshills; rt. the Aire is

of mountain air, and of isolated hill-side life; something be derived from their rough Norse ancestry. They have a quick perception of character, and a keen sense of humour; the dwellers among them must be prepared for certain uncomplimentary, though most likely true, observations, pithily expressed."-Life of C. Bronte. Many of their wilder customs, such as the " Arvills," or funeral feasts, generally succeeded by ferocious fighting—just as in Iceland in the days of the Nials and the Ketels-or the marriage "ridings" from Haworth to Bradford, have either disappeared altogether or have become greatly modified since the early part of the cent. The change in this district since the railways have penetrated it is necessarily enormous: and even the "loneliness of the grey ancestral houses to be seen here and there in the dense hollows of the moors" has not preserved them from its influence.

The railway from Keighley has, of course, much changed the valley of the Worth. Mills-cotton, or cotton and worsted mixed-have increased in numbers and in hands; and Haworth itself is a more bustling place (Pop. in 1871, 5966) than in the days of the Brontes.

The rlv. is continued to Oxenhope, at the extremity of Haworth parish.

Returning to Keighley, the next stat. toward Skipton is

201 m. Steeton. The village lies under the high ground l.; rt. the valley opens up broadly to Silsden. The Leeds and Liverpool Canal passes through the village of Silsden. which lies in a hollow of Rumbald's Moor, up which the road climbs twards Addingham.

The scenery increases in beauty as we approach.

21 m. Kildwick Stat. l. is the

crossed by a handsome stone bridge! (built temp. Edw. II. by the Canons) of Bolton) at the entrance of Kild-The Church, called from its unusual length the "Long Church of Craven," is good Perp. and contains a rood-screen and carved wood-work worth notice. There are some fragments of stained glass; and in the nave the effigy of Sir Robert de Stiverton or Steeton, died 1307. Until the Dissolution, Kildwick Ch. and manor belonged to the Canons of Bolton. Kildwick Grange was a residence of the Prior (the building now dates from the 17th cent., and is remarkable for a balconied portal). Kildwick Hall, on high ground above the ch., is also of the 17th cent., and a very good example of a Craven "hall" of that date. From the terrace there is a fine view over the valley.

In this district the hills are often dressed with lime to the summit, giving them the appearance of being white with snow. The limestone ridges above Skipton rises rt. as we

approach

23\frac{1}{25} m. Cononley Stat., from which the rly. soon sweeps up the valley to 26\frac{1}{25} m. Skipton (see Rte. 30).

ROUTE 35.

LEEDS TO BRADFORD.

(Great Northern Rly., Leeds, Bradford, and Halifax Junction. 15 trains daily, some of which are in connection with trains from Knottingley Junction by Wakefield to Leeds.

Time of transit, 30 min. All trains leave Leeds from the Central Stat., and stop at Holbeck.)

(For the Midland Rly. from Leeds

to Bradford see Rte. 34.)

The Great Northern Rly. passes through an industrial district, thickly packed with woulen factories, tall chimneys, and quarries from which the millstone is excavated for building. There is little to attract the tourist, or which calls for special notice.

Bramley Stat., Stanningley Stat.
Pudeey, a village passed L, gave
name to the knightly family which established itself at Bolton by Bolland,
and there sheltered Henry VI. (see
Rte. 33). At Fulneck, in this township, is a Moravian settlement, estab.
1748. The chief buildings (hall,
chapel, schools, and houses for single
men, single women, and widows)
stand on a terrace, from which there
is a wide view. James Montgomery
the poet, whose father was a Moravian

At Laister Dyke Junct. Stat., a branch direct to Bradford turns rt. out of that to Low Moor and Halifax. Here is a small Church, completed in 1861; adjoining, the Bowling Ironworks (see post.)

St. Dunstan's Stat.

minister, was educated here.

Bradford Junct. Stat. Isss: Victoria, close to the Great Northern Rly. Station, at which the traveller by this route will arrive. Talbot, in Kirkgate, rebuilt; good and reasonable: the Alexandra, Great Horton Road, nearly midway between the two stations.

The Midland Stat. (Rtc. 34) is at

the bottom of Kirkgate.

The Exchange Stat. (Lancashire and Yorkshire; Great Northern, Huldersfield, &c.) is near St. George's Hall.

Pop. of borough in 1881, 180,459; in 1861, 106,218; in 1801, 13,264. The population of no town in Yorkshire

(Middlesbrough, Rte. 17, has risen and throughout the district, has bemore suddenly) has increased more rapidly since the beginning of the There were only 8 factories here in 1800, there are between 160 and 170 at present. The rapid increase of wealth in Bradford is indicated by the fine buildings which are rising on all sides, as well as by its Bradford new streets and roads. stands at the head of a wide valley. down which the Bradford Beck flows to meet the Aire at Shipley. older part of the town lies completely in the valley; and the "Beck" and its tributaries used to stagnate in a broad, open space below, until the making of the Bradford Canal (completed before 1796, 4 m. long, with 12 locks, and a fall of 87 ft.), which joins the Leeds and Liverpool Canal near Shipley. From this marsh. which had to be forded, the town was named—Brad (broad) ford.

It has little ancient history. In the civil wars it was Parliamentarian. and, after twice repulsing troops sent from the Leeds garrison, was taken by the Earl of Newcastle. Fairfax, who had attempted to defend the place, finding it hopeless, made a bold sally and cut his way through to Leeds; but his lady, who had accompanied him on horseback on this and his other campaigns, was made prisoner before she could reach the brow of the hills. Newcastle, however, courteously sent her to her husband in his own carriage under an escort.

Bradford is now the great centre of the worsted trade (as Leeds is the chief mart for broadcloth); and the "raw material" is purchased here by manufacturers from the whole clothing district. Indeed, though foreign nations may rival us in weaving cloth, the stuffs (formed of long-stapled wool, in distinction to the short-stapled, of which cloth is made), for which Bradford is famous, maintain their superiority, and the spinning of worsted yarn, which is steadily increasing here Others soon followed, not without

come of great importance. Norwich. the cradle of the worsted trade, is now supplied from hence with finer yarn than she can herself make, and at a far lower price. Besides yarn, the mills of Bradford produce every kind of fabric, wrought from wool, worsted mohair, alpaca, or China grass. These are stored in the great warehouses which line the streets, towering story above story; and eventually find their way to almost every part of the world. The spinning of worsted yarn by machinery was first introduced here toward the end of the last cent., and the first steam-engine was erected in 1800; but the prosperity and the increase of Bradford have been most noticeable since 1830, and it is only of comparatively late years that the town and its neighbourhood have been overhung by the canopy of smoke which is now rarely lifted except on Sundays and Whitsuntide.

The earliest manufacture of Bradford, as of all this part of Yorkshire. was that of woollen cloths. Early in the last century the making of worsted stuffs encroached much on this; and at last grew to so great importance, that in 1773 the "Piece Hall" was built. At this time nearly all the population of Bradford was engaged in spinning and weaving stuffs fabricated altogether from wool; and much of the yarn used by them was spun in Craven and the northern dales of Yorkshire with the domestic spinning-wheel. The manufacturer had himself to set out from Bradford with work for the spinners, and to bring back yarn (having first, in the same way, brought home "long wool" from Lincolnshire); and many of them carried their stuffs, with droves of pack-horses, to fairs and markettowns all over the kingdom. About the year 1794, spinning-machines. were first set up here; and in 1800. the first factory, with a steam-engine of 15-horse power, was erected.

much opposition from the inhabitants: but from this time the prosperity of the place increased rapidly; and it is owing to the backwardness of Halifax and other towns to adopt the factory system and the use of machinery that Bradford has so far outstripped them, and has become the capital of the "worsted" trade. Bradford had little to do with the "Luddite" disturbances of 1812: but in 1826 a determined opposition rose against the weaving of stuffs by power-looms. Some mills were then attacked and damaged, without of course interfering with the advance of machinery. Few pieces are now woven by hand in the parish; and hand-combing, which used to be one of the great occupations here, has been almost entirely superseded by Lister's machine.

The old town of Bradford contained little that was characteristic. Church (ded. to St. Peter), on the hill-side, is Perp., and has been restored; but is of no great interest. The corbel table under the roof is unusual and very ugly. Within, the oaken roof is ancient. There is a good (late Perp.) canopy of tabernacle-work for the font, resembling that in the parish ch. of Halifax (Rte. 36); a monument, by Flaxman, for Abraham Balme, worth notice (it is a fine personification of old agean old man between his son and daughter); and one for Abraham Sharp, the mathematician (died 1742: see post, Horton Hall). Wool-packs were hung round the tower, during the attack on the town by the Earl of Newcastle, in order to protect it; in spite of which it was much shaken by the shot of the Royalist artillery. The Manor Court-house, a building of the 17th cent., remains in Westgate. John Sharpe, Abp. of York (1691-1714), was born at Bradford.

Modern Bradford has extended itself up the hills on either side of the old town, and farther down the valley.

buildings, and almost every year adds to their number. The lofty tower of the Town Hall groups well, from most points of view, with the surrounding buildings, and the musical carillon which sounds from it is pleasant and enlivening. The view from Peel Place, where stands the smoke-stained statue of Sir Robert Peel, by Behnes, is fine. Great warehouses stretch away on each side. many with good architectural elevations, very lofty, and giving an imposing idea of the wealth stored within. Neither the warehouses nor the factories are shown without a special introduction. Of the latter. by far the best example in the district is Saltaire (see Rte. 34), easily accessible from Bradford by rly. The scene in the streets of Bradford, when the "hands" turn out at mid-day for dinner, is remarkable, although the bonnet has now almost entirely replaced the coloured shawl, once worn over the head with a far more picturesque effect. Clogs are still generally worn, as the clatter along the pavement makes sufficiently evident. They are made (in all the towns) from alder-wood, cut down and piled for some time in conical heaps. It is then easily hollowed.

Of the public buildings in Bradford, the Town Hall, in New Market Street, is by far the most important. It was completed, in 1873, from the designs of Messrs. Lockwood and Mawson, at a cost of more than 100,000l., and is of so-called "mediæval " character, rather Italian than Flemish. The exterior niches contain statues of the kings and (reigning) queens of England, from the Conqueror to Queen Victoria—Oliver Cromwell appearing among them. From the centre rises a lofty campanile. The building, besides offices for the various members of the Corporation, contains a suite of apartments for the Mayor, Council Cham-The town has many fine ber, Borough Court, &c. None of the

rooms are very large. The interior of cemetery lies the town in its troughthe Town Hall, although not officially like valley, the mouth of which, at shown, can generally be seen by The application to the Hall-keeper. interior is better than the exterior. The staircase and passages, like cloisters with stained-glass windows and fine stained-glass skylight, should be seen especially from upper landing. This part stands open during the day; the wood-carving in the council-The stone used chamber very good. throughout is from Cliffe Wood Quarries, near the town. A memorial to Sir Titus Salt, Bart., has been erected in front of the building. The Town Hall is, as it should be, by far the most conspicuous building in Bradford. Opposite is the Mechanics' Institute (opened 1870), Italian in character, with lecturerooms and a library (cost 36,000l.).

St. George's Hall, on the other side of the Town Hall, was completed in 1858, and cost 13,000l. The style is classical: but the exterior is almost beaten by the range of warehouses which adjoins it. Within, the great hall—152 ft. by 76, 54 ft. high—is fine, and the effect is especially good at night, when it is lighted by a continuous row of gas-jets above the

cornice.

The foundation stone of the new Exchange (Market Street) was laid by Lord Palmerston in August 1864. The building itself (Lockwood and Mawson, archits.) is Venetian Gothic in character.

On the hill-top, N. of the town, is the Cometery, which should be visited for the sake of the view to be obtained from it—fine in itself, and giving an excellent notion of the position of Bradford. (The hill-sides round the town, and indeed throughout this part of Yorkshire, are covered with mills, and with cottages built for the workmen; and it should be said that this view is only to be well seen on Sundays, when the tall chimneys cease to pour forth their

Shipley, opens to the Aire. country must have been pleasant, with some wood in the hollows and open downs above, before its conversion into one vast manufactory. The hills rise to some height above the town, forming part of that mass of rolling, tumbled land that extends between the Aire and the Calder. Beyond Shipley is seen the valley of the Aire, with the heights above Bingley, and Rumbald's Moor op-

posite.

A short distance below the cemetery is Peel Park, a space of open ground well laid out, and commanding good views. It is open to the public. Two other parks have been purchased by the Corporation; Lister Park, containing about 53 acres, N.W. of the town, on high ground, and commanding wide views; and Horton Park, on the S. side of the town. The system of waterworks, and those for sewage defication, have been devised with equal zeal and forethought. There are three levels for the water From Heaton, near Lister supply. Park, a conduit extends to the storage reservoirs of Chelker and Barden (see Rte. 30), 20 m. distant. provide water for the low level. The medium level is supplied springs near Cullingworth, conducted to reservoirs at Chellow Dean and at Whetley. The high-level is from Thornton Moor, S. of the town, and a massive conduit, 4000 ft. in length. assists in conveying the water. expenditure on these waterworks has been considerably more than one million sterling.

A short distance S.W. of Lister Park, and adjoining Heaton Road, are the colossal buildings of Manningham Mills, erected by Messrs. S. C. Lister and Co. for silk and velvet. The structure, which cost about 500,0001. has received a considerable amount of ornamental chadense clouds of smoke.) Below the racter. Between the mill and the warehouse are a reservoir, the engine-house, and a lofty chimney, with panelled sides. The area covered is nearly 11 acres. Mill and warehouse are 6 stories in height, and are fire-proof.

Horton Hall, on the hill S. of Bradford, is, in its more ancient portions, an excellent example of the "hall-house," so many of which were built by the smaller Yorkshire proprietors between 1580 and 1680, all with a good-sized common hall, and a parlour in the gable-end adjoining. Horton Hall was rebuilt in 1676, on the site of the more ancient house, a portion of which remains, by Thomas Sharp, rector of Adel, near Leeds, who was ejected for nonconformity. He became a celebrated Presbyterian preacher, and was a friend of Thoresby, the Leeds antiquary. His younger brother, Abraham, resided here till his death. He was a mathematician and astronomer of much repute, and the friend and correspondent of Flamstead, for whom he made considerable calculations. room, with a long, low, lattised window, is pointed out as having been in all probability licensed as the first meeting-place for Presbyterians in Bradford.

Although the immediate neighbourhood of Bradford has little to attract the tourist. Saltairs and the Low Moor Ironworks will be visited with great interest by all who care for ingenious machinery and the processes of manufacture. Saltaire (Rte. 34) may be reached by rly. in 10 min. from Bradford. The Low Moor Stat., also reached in 10 min., is the 2nd stat. from Bradford on the Halifax Rlv. (4 trains stop at it). The works are freely shown to visitors who bring introductions. (In most cases, perhaps, the presentation of your card at the office will be sufficient.)

The Low Moor Ironworks were established in 1796, and present, therefore, a very different appear-

ance from those at Middlesbrough and elsewhere in the iron district of Cleveland (see Rte. 17). The accumulation of cinders and calcined shale actually overspreads the country, and exceeds in cubic bulk the mass of the Pyramids. In some cases the hillocks of rubbish have been levelled. and covered with soil brought from a distance. Through these "outworks" the visitor finds his way to the factory (about 1 m. distant from the stat.). Ironstone, it should be said, is found throughout this district, and coal (we are here near the N.W. corner of the coal formation) is raised by the company on their own estate. Limestone, used in part of the process, is brought from quarries above Skipton. Iron plates, bars, and railway tires, sent to Russia, America. India, and, in fact, all over the world. are the principal manufactures here; but guns are also made, and the processes of boring and rifling may be followed throughout. Every runlet of water for miles round is dammed up to supply the works, and every drop is carefully economized.

These works are justly celebrated for the high quality of wrought or malleable iron they produce. "Low Moor brand" is known whereever iron of great toughness and tenacity is required. The process of manufacture is as follows:-The tall blast-furnaces are charged from the top or "throat" with coal or coke, or mixture of these, with iron ore, and with lime, the coal and coke dcoxidize the ore, the lime combines with its siliceous impurities, forming a fusible glass or "cinder," commonly miscalled "slag," This cinder, together with the melted iron, accumulates at the bottom of the furnace. the iron in the "crucible," and the cinder which is lighter, floating as a liquid above it. There is a dam, over which the cinder, which is more abundant than the iron, flows off into iron pots mounted on wheels When filled, these are carried away,

and their contents form the heaps | streams of carbonic oxide gas, which above described. The flow of cinder is continuous, but not so the iron. This is allowed to accumulate until the crucible is filled. Then it is tapped by the removal of a clay plug that was driven into a hole communicating with the bottom of the crucible.

Before tapping, a large bed of sand is prepared, with a main channel communicating with outlet of the crucible, and small side channels branching from it. The molten iron flows down the main channel, thence into its many smaller side branches. The main channel is called the "sow." its side branches the "pigs," hence the term "pig-iron," which has the form of rough bars that have solidi-

fied in these channels.

Pig-iron is very impure and brittle. To convert it into malleable iron, these impurities are wrought out, hence the name "wrought-iron." To do this, the pig-iron is melted in a puddling-furnace, consisting of a fireplace, communicating with a sort of dish, roofed over with firebrick. The flame from the fireplace passes over "the bridge" to the dish chamber, and the heat of this flame is "reverberated" downwards to the dish or furnace-bed, on which a charge of 4 to 5 cwt. of pigs is laid. These are soon melted, and then the puddler commences the working with his "rabble," a long iron bar or poker, with which he stirs the liquid metal, bringing all its parts successively in contact with the "fettling" or lining of the furnace-bed. This lining, renewed at each "operation," consists mainly of oxide of iron, which gives up its oxygen when thus treated, and this oxygen, aided by the efforts of the puddler and the action of the fluid cinder separated from the pig, removes the impurities by combined chemical and mechanical action. The chemical action is strikingly displayed by the "boiling" of the fluid mass, that is, the uprising of bubbles and are full of interest; and in one of

burn on the surface as jets and spurts

of blue flame.

The mass now begins to granulate, and appears like a porridge, consisting of infusible grains of iron diffused through liquid cinder. The puddler now presses these granules together, to separate them from the fluid impurities. This is called "balling-up," and thus the true iron of the "heat" is made up into balls -usually three-which are carried off to the steam-hammers, and there "shingled," that is, squeezed and thumped, to press out the still adhering liquid impurities from the spongy mass. (This liquid, thus thumped out, is properly called "slag" by the workmen, from the old Scandinavian root signifying a blow, while that which flows from the furnace he calls "cinder," probably from the old Norsk root, signifying to trickle down. It is a curious fact, that the rude workmen have retained the old etymological distinction, while scholars—including technological writers - have confounded the two things under the one name of "slag.")

The balls thus squeezed and rudely shaped by the hammer, are reheated in the "mill-furnace," and then passed between rollers that squeeze out still more of the liquid impurity, and bring them to the shape of plates, sheets, bars, rails, &c., as re-

quired.

Formerly there was an intermediate process between that of the blast-furnace and the puddling-furnace, viz. the refinery, in a "fineryfurnace," where the pig was melted alone or with scrap-iron, and sub-This is jected to a strong blast. now but rarely used. (For steelmaking, see Sheffield, Rtc. 44.)

The pummel-shop, with machines by which iron and brass are cut as easily as wood, and the fitting-shop, with its steel bores and cylinders, the offices are specimens of railway tires, and of iron plates rolled into balls, tied in knots, made into tables, &c.—all testing the excellence of the work.

About 4000 men are employed here; and churches have been built at Buttershaw and at Wisbey, for their accommodation, by the proprietors.

[A Railway (8 m.) connects Low Moor with the Mirfield Stat. on the Lancashire and Yorkshire line. There are stations at

2 m. Cleckheaton, where machinery is made for carding and spinning. There are also some manufactories of worsted and coarse woollen fabrics. Roman remains have been found here; and in the chapel are interred many of the Richardsons of Bierley (see post); among them Dr. Richardson the naturalist, who died in 1741.

4 m. Liversedge. The church was built and endowed in 1816 by the Rev. Hammond Roberson, a somewhat remarkable character, and the original of Parson Yorke in Miss Brontë's 'Shirley.' Adjoining is Mill Bridge, a large village, which, with Liversedge and other villages thickly scattered over this district, is busily occupied in cloth, carpet, blanket, and card manufacture; and at

5 m. Heckmondwike, a populous town, and next to Dewsbury (Rte. 37), the chief seat of the blanket and carpet manufacture, for which a market is held every Monday and Thursday in the Blanket Hall. Here are also several cloth factories. The ch. was built in 1830.]

The Bowling Ironworks, adjoining Bradford, S.E. (and having a stat. on a loop of the Bradford and Halifax Junction Rly.), are of the same character as those at Low Moor, but are not so extensive. Between the works and Bowling Hall is the modern church of St. John, constructed en-

the offices are specimens of railway tirely of iron and stone, at a cost of tires, and of iron plates rolled into 4000L

Bowling Hall is an Elizabethan building flanked by two older towers. The once stately mansion is now stripped of its splendour, partly modernised and subdivided. rounded by coal-heaps and enveloped in smoke. It was anciently the seat of the Bollings and Tempests. but now belongs to J. M. Tankard. Esq. It was the headquarters of the Earl of Newcastle during the siege of Bradford, 1642. According to popular tale, he was deterred from sacking the town, which he had threatened in consequence of the coldblooded slaughter by the townspeople of a young cavalier, Sir John Harp. by the apparition of a female, who implored him to "pity poor Bradford."

Bierley Hall (dating from 1676. but altered), about 11 m. S. of Bowling, was long the residence of the Richardson family-one of whom was Dr. Richardson, the eminent botanist and friend of Sir Hans Sloane, who sent him a slip of the cedar of Lebanon, then a novelty in This was planted at this country. Bierley, and was the first cedar seen in the north of England. The tree, of moderate size, is still in existence. Bierley could also boast of the second hothouse built in the N. of England. The first was constructed for John Blackburn, Esq., of Orford, near Liverand the workmen having pool: finished that, proceeded to Bierley and built the second. "This in my memory was entire, and was principally remarkable for being glazed like the windows of a cottage, with leaded squares."—Whitaker's 'Loidis." Dr. Richardson's MSS. are preserved at Eshton Hall, near Gargrave (Rte. 32), his family having become, by marriage, representatives of Currers of that place.

Near Bierley Hall, remains proving that the Romans worked the coal

and ironstone of the district have at times been discovered.

At Undercliffe, N.E. of Bradford, is Airedale College, a large and handsome building belonging to the Independents, containing accommodation for 20 students. It enjoys a yearly revenue of more than 800L derived from endowments, bequests, and subscriptions. Bradford, like other great manufacturing towns, is rich in chapels and "colleges" belonging to the various religious bodies. The Weslevans have 5 chapels here, and a "Seminary" at Woodhouse Grove (founded 1812), for educating the sons of ministers. The first Temperance Society in England was established at Bradford, and its members have built for themselves a Temperance Hall in Chapel Street.

ROUTE 36.

LEEDS TO BRADFORD AND HALIFAX, BY LAISTER DYKE, QUEENSBURY, THORNTON.

18 Trains dally, # hr. to 1 hr.

LEEDS New Stat. in Rte. 29.
Holbeck Stat. Bramley Stat.
Stamingley Stat.
Laister Dyke Junct. Stat.
Here a line branches to
BRADFORD STATION in Rte. 35.
St. Dunstan's Stat.
Manchester Road Stat.
Great Horton Stat.
Clayton Stat.

Queensbury Junct. Stat.

Queensbury is a prosperous manufacturing village, with the large mills of Messrs. J. Foster and Son, for mohair and alpaca. On this high ground, 1000 ft. above the sea, the mill settlement has grown up within the last generation. Church and schools have been built (there is a very wide view from the church tower). The firm is said to be richest in the "worsted" district. There is neither railway nor canal, and everything used in the mills has to be carted up the hill, and the goods despatched in the same manner.

Here a rly. branches to

Thornton Stat., to be continued to
Keighley.

At Thornton, 31 m. W. of Bradford, Charlotte Bronte was born. April 21, 1816. "The neighbourhood is desolate and wild; tracts of bleak land, enclosed by stone dykes, sweeping up Clayton heights. The ch. itself looks ancient and solitary, and as if left behind by the great stone mills of a flourishing Independent firm, and the solid square chapel, built by the members of that denomination."-Mrs. Gaskell. 1820 Mr. Brontë removed to Haworth (see Rte. 34). On the road to Thornton is Leventhorpe Hall. A Leventhorpe of Leventhorpe was one of the executors of the will of Henry IV.

Holmfield Stat.

Halifax—N. Buildings Stat.
Mills, factories, and collieries abound.
The country (entirely within the coal
formation until close to Halifax) is
hilly but uninteresting; and the line
passes through 4 tunnels between
Bradford and Halifax, after emerging from the last of which the traveller finds himself in a deep valley,
with bare hills of millstone-grit
rising on either side, and (rt.) the
town of Halifax filling the hollow
of the valley, and extending up the
hill-side,

thern Company's Stat. on North of the place in both cloth and wer-Bridge. (Inns: White Swan, best; Railway Hotel: Pop. in 1881. 73.633.) Halifax ranks third in importance among the "clothing" towns of the West Riding, the two which take place before it being Leeds and Bradford. It stands on the Hebble. small stream flowing into the Calder, 2 m. lower down: in a region which De Foe (who lived some time at Halifax and describes it in his 'Tour') calls "frightful," from its rough treeless hills, but which, he adds, "seems to have been designed by Providence for the very purposes to which it is now allotted, for carrying on a manufacture which can nowhere be so easily supplied with the conveniences necessary for it"-coal and water. In the year 1443 there were, it is said, only 30 houses in the town of Halifax; but cloth-making, which had probably been introduced into this district by Flemish workmen in the reign of Henry VII., extended rapidly in the next cent. The town increased; and the "gibbet law," as Jus Furcæ " (see post for a longer notice), which had always belonged to the Lords of the Forest of Hardwick (extending beyond the present parish of Halifax), and of the manor of Halifax, was brought especially to bear upon such persons as stole the cloth hung to dry on "tenters," and often left unprotected by night as well as by day. (The feudal "jus furcæ" implied a right of hanging the offender on a gallows, but here criminals seem to have been always beheaded. This mode of execution was, however, known elsewhere in England: and Whitaker asserts that he has "traced it, as appurtenant to the rights of ingfangtheof and outfangtheof, in the domains of the Lacies, both in Lancashire and Cheshire.") The making of worsted stuffs was added to the cloth trade den. Pilgrims in numbers visited

Halifax Junct. Stat. Great Nor-1 last cent. Towards its end. the trade steds had so far extended that in 1779 its large Piece Hall (see post) was erected. After the rise of the factory system, however, and the introduction of machinery. Bradford. which adopted both freely (whilst Halifax was indifferent to them), began to rise rapidly, and soon exceeded in importance Halifax, which until then had stood at the head of the worsted manufacturing seats in the North of England. The town thus lost its vantage ground; but since 1820 it has rapidly risen, mainly through the efforts and influence of two or three great manufacturing firms. It is now, as a place of worsted manufacture, second only to Bradford. Many new articles have been produced here, and the eld greatly improved. Factories and tall chimneys rise in and about it in all directions; and the railways, which now connect Halifax with all parts of the kingdom, would not a little astonish the much-enduring De Foe. who journeyed hither with pain and danger, over the "frightful wilds" of Blackstone Edge. Besides worsted and woollen factories there are also some cotton-mills, and many factories in which machines are made. In addition to those in the town. large worsted and cotton-mills are scattered throughout the parish, which is one of the largest in England, begining at Brighonse, and extending all the way to Todmorden. nearly 20 m. Its average breadth is 12 m.

The name of Halifax has been variously explained. Camden gives us the local legend—that a certain evil clerk, having cut off the head of a saintly maiden, hung it on a yewtree; where it was found and greatly reverenced by the people. The fibres beneath the bark of the tree were held to be the long hair of the maiof Halifax in the beginning of the the place, which from the relics of

the vew-tree was called Halifax = | faces fluted. The chancel is raised holy hair. A relic called the "face" of St. John is said by others to have given name to the place. Other antiquaries explain it as "holy ways" (as Carfax in Oxford is quartre voies"), from the meeting of many roads at a spot where a hermit had built a cell and a chapel to which pilgrims resorted. None of these etymologies seem entirely satisfactory. The termination is apparently found elsewhere in Yorkshire, as at Kippax, near Leeds.

The chief points of interest in Halifax are the Parish Ch. of St. John Baptist, the Town Hall, the Church of All Souls, and the works of the great manufacturing firms (Crossleys and Akroyds are the two In entering the most important). town from the rly, stat., the stranger's attention will at once be caught by the tall spire (235 ft. high) of an Independent Chapel, completed in 1857 at a cost of 15,000l. (archit. J. James). The proportion and details of the tower and spire are very good. It is locally named "Square Chapel," probably from the old chapel, which it replaced, a square red-brick building still standing near to it. The old quadrangular market-place is near to

The existing Parish Church, well restored 1878, which is for the most part Perp., circ. 1447; but it retains portions of two earlier churches, one which has been claimed as Saxon (Halifax is however unmentioned in Domesday), and a second of the 18th cent. (circ. 1260), built in all probability by the Earl of Warrene and Surrey, the then lord of the manor. The ch. is divided by a central arch, which has 5 bays on either side of it. (Similar central arches exist at Elland and at Hepstonstall, both of the 15th cent.) The existing tower is western and Perp. (begun, according to an entry in the ch. books, in 1450, and 20 years in building). The piers of the nave, and two of those E. of the central arch, have their alternate | 105.

on a kind of crypt (also Perp.), which serves as vestry and library. (Among the books is a fine copy of de Lyra.) The original door into the rood-loft. of riven oak, with the chisel-marks on it, remains S. of the chancel screen. The flat wooden ceiling of the ch. was entirely renewed, no doubt after an older design, in 1605. In the panels are painted the arms of the vicars of Halifax from the year 1274. those of some ancient families connected with the town, and the emblems of the 12 tribes.

The organ is by Schnitzler, and Dr. Herschel was once organist here. Within the organ-screen the ch. is seated regularly with black oak, dating from 1621, as does the gallery above. The chancel screen retains part of its Perp. carving; and in the chancel itself the Perp. miserere seats remain. The pulpit, according to the ch. books, was made in 1595. gether, owing mainly to the great quantity of black oak, the effect of the ch. is grave and solemn. There are some modern stained-glass windows by Clayton and Bell, and Hardman. On either side of the chancel are Perp. chantry chapels, that S. having been founded circ. 1554 by one of the Houldsworth family, vicar here in the reign of Mary: that N. by Rokeby, Archbp. of Dublin, who died in 1521. The Font (Perp.) has a fine lofty cover of carved wood.

In the S. aisle is a mont, for Robert Ferrar, Bp. of St. David's (1548-1555), burned for his religion in the reign of Q. Mary at Caermarthen, a native of Halifax; and the register records the baptism here (Oct. 6, 1630) of John Tillotson, the future Abp. of Canterbury. Tillotson was born at Haughend, near Sowerby Bridge, in the parish of Halifax. Here also are monts to the Rokebys, Savilles, and Waterhouses. In the ch.-yard is the tomb of John Logan, died, 1686, aged

the Cloth or Piece Hall, built in 1780, a proof of the high prosperity of the cloth and worsted manufactures here at that time. It is a simple stone building, but imposing from its great size. Within, a quadrangle encloses a court of greensward lined by handsome colonnades, forming 2 tiers; and on one side are 3 tiers of stone galleries, divided into 315 shops for clothiers and merchants, who formerly met here every Saturday to dispose of their goods. A few "piece-makers" may still be seen here on Saturdays; but nearly all the Halifax manufacturers now carry their goods to the great mart of the district-Bradford

The Town-hall, which may be visited in passing through the town toward All Souls Ch., was completed in 1862, from the designs of Sir Chas. Barry, and his son F. M. Barry. It is a building of Palladian architecture, with pagoda-like tower; is picturesque, striking from the use of gilt and burnished metal on its exterior, and deserving a better situation than that in which it is placed, hemmed in by tall buildings. It cost about 25,000L, and contains rooms for all municipal purposes.

The Church of All Soul's, Haley Hill, one of the best and most elaborate of the churches of which Sir G. G. Scott is the architect, the munificent gift of Edw. Akroyd, Esq., who built and endowed it, 1858-9, at a cost of 70,000l., should be seen by every lover of Ecclesiology who visits Halifax. It well deserves its reputation, although it has been suggested-with some truth-that the main building has a somewhat stunted appearance in proportion to the height of the spire. (Haley Hill, on which it stands, is on the line of the old turnpike-road to Bradford; and a little above the ch. a branch of the Roman road from Manchester to Ilkley crosses

In the lower part of the town is the North Bridge, a lofty viaduet of e Cloth or Piece Hall, built in 6 arches, is crossed, by which an (80, a proof of the high prosperity awkward ascent and descent is the cloth and worsted manu-avoided.

The plan of the ch. comprises nave with aisles terminating eastward in transepts; chancel with N. and S. chapels; and tower and spire at the N.W. angle of the nave. The style is early Dec. (Geometrical). exterior stone is millstone-grit, from quarries near the town : with dressings and quoins of magnesian limestone, from Steetley, near Worksop (the limestone of which Doncaster Ch. is built). The nave is 87 ft. 6 in. long by 54 ft. broad. height of the tower and spire is 236 ft.

A clerestory of 15 lights, with a continuous internal arcade, carried on shafts of Derbyshire marble, runs Shafts of Aberdeen granite. carried on carved corbels, rise between each bay, and support the main roof trusses. In the spandrils of the principal arches are sculptured medallions, with (N.) SS. Gregory. Augustine, Ambrose, and Jerome: (S.) SS. Polycarp, Ignatius, Ambrose. A low wall of alaand Clement. baster, carrying a screen of hammered iron, divides the nave from the chancel, the sculpture in which de-The reredos is of serves attention. English alabaster. Over the arches into the N. and S. chapels are sculptured groups, representing angels singing and carrying instruments of music.

The pulpit is of Caen stone, supported on a shaft of Devonshire marble, and enriched with carved foliage and mosaics. The font is of Cornish serpentine, on a pedestal of polished red granite.

The stained glass throughout the

ch. is very good.

it stands, is on the line of the old turnpike-road to Bradford; and a little above the ch. a branch of the Roman road from Manchester to Ilkley crosses it. On the way to All Soul's Church, local gritstone is unaffected. A peal Messrs. Crossley's, at Dean Clough of 8 bells hangs in the tower.

Near, but not adjoining the ch., is the burial-ground of the parish, also provided by Mr. Akroyd. In it is a small but very good mortuary chapel. An arch opens from it into the monumental chapel of the Akrovds, in which is an altar-tomb with effigy of the late Jonathan Akroyd, Esq. (father of the founder), by Joseph Gott, of Rome. Good view from the top of the hill behind ch.

Near All Souls' Church is Bankfield, the residence of Edward Akroyd, Esq.; and nearly opposite is the recorsted manufactory of the same proprietor. This is not to be seen without a special order or introduction, but will amply repay a visit. Above 1000 hands are employed. In one room more than 800 looms may be seen in motion at once, a wonderful scene, the apparent confusion of which is in reality the most complete order. In the woollen-room the wool passes through various processes nntil it becomes windable.

At an early period Halifax established a trade with South America, and has ever since retained it. Rugs, &c., are made here for various South American markets at which Indian tribes supply themselves; and the patterns of these, as well as the colours and designs of other fabrics manufactured expressly for particular countries, are curious and noticeable. (Pennant, who passed through Halifax about 1770, says that "says of a blue colour were manufactured here expressly for Guinea. They were packed in pieces of 121 yds., and wrapped in an oilcloth painted with negroes and elephants "in order to captivate the natives.") Damasks (for curtains), tablecloths, and various fabrics for dresses are made here. (The work is of the same general character as that at Saltaire, Rte. 34.) Messrs. Houldsworth's mills at Halifax are also for woollens, and are on the same large (or even larger) scale. | liberty, examined the truth of the

(the largest mills in the place, employing more than 3000 hands), is a great carpet manufactory, in which Brussels, tapestry, velvet pile, and all descriptions of carpets are made. Carpets, however, are to be bought (ordinarily) in London cheaper than in Halifax.

The fine Church of St. Mary. built, at a cost of 80001., by Michael Stocks, Esq., was consecrated Aug. 4, 1870.

The Museum, in Harrison Road. contains a few local relics and antiquities of interest. Some large querns are arranged in the hall; and in the upper room are a number of bronze celts and copper spearheads, found in 1856 at Upper Westercroft quarry, near Shelf, in the parish of Halifax; a candlestick of the 14th cent. (a very good example), found among old metal; and the staple for supporting the axe of the Halifax gibbet. Here also is a tolerable collection of fossil plants, shells, &c., from the Halifax coal-measures.

In a court opening from Gibbet Lane, on the W. side of the town, the raised platform of stones about 8 ft. by 6 ft. (with steps leading up to it), on which the famous Halifax gibbet formerly stood, is still in existence in the enclosed garden of a house at the top of the lane. May be seen by application at the house. The whole is now grass-grown, and the walls of the court are covered with ivv. More than 50 persons were beheaded here between 1541, when the gibbet was first erected, and 1650, when the last execution took place. The criminal detected stealing cloth (or any commodity of the value of 131d.) within the liberty of the forest of Hardwick (hand-habend, back-berand, or confessand) was carried before the bailiff of the lord of the manor of Halifax, who, after summoning to his assistance 4 "frithburgers" from 4 townships within the precincts of the charge. (These jurors seem to have had no great reputation for integrity. Bp. Hall, in his 'Satires,' writes-

" Or some more strait-laced furor of the rest. '\ Impanelled on an Halifax inquest.")

If the offender was found guilty, and the trial had taken place on the principal market-day, he was beheaded at once. He could be executed only on such a day, and if the trial had taken place before it, he was exhibited, on the ordinary market-days, in the stocks, with the stolen goods on his back, or before him. The gibbet itself, a rude instrument, having an axe weighing about 8 lbs., fixed in a block of wood, and suspended within a framework 15 ft. high, grooved so that the axe might descend rapidly. may be regarded as the original of the French guillotine, since the Scottish "maiden," from which the guillotine was partly copied, was itself a copy of the Halifax engine. Regent Morton, who introduced the "Maiden" to Scotland, and was himself the first to suffer by it, is said to have witnessed an execution at Halifax, and, says De Foe, to have been much "pleased with the performance." The Maiden still remains in the Museum of the Society of Antiquaries at Edinburgh. The axe of the Halifax gibbet is preserved at Wakefield, in the house of Mr. Lomb. steward of the Duke of Leeds, lord of the manor of Halifax. Each person who suffered by it is entered in the town register as "decollatus." It was the severity and unusual character, of the punishment that caused the insertion of Halifax in the so-called "thieves' litany," " From Hell, Hull, and Halifax, good Lord deliver us!" gibbet was removed in 1620; and De Foe, writing early in the last century, remarks that, "though criminals have from that time been left to the ordinary course of justice, we do not find stealing cloth from the tenters so frequent now as it was in former times." -Tour through Great Britain, 111.

It is said, but without much authority, that, if the criminal was beheaded for stealing an animal, an arrangement was made by which the animal itself set free the rope supporting the axe, and thus took revenge

on its own account. The Manor Court-house, in which criminals were tried, still remains in Nelson Street, near the parish ch. contains a room once fitted with an inclined plane, so that all present could The rest of the floor was level. for bailiff, jurors, witnesses, and prisoner. (The sloping floor is now covered with an horizontal one.) each side are flat-headed windows,

divided by oaken munnions.

At the head of the town is a **People's** Park, laid out by Sir Joseph Paxton, and given to Halifax by the late Sir Francis Crossley, M.P. for the West Riding, of whom there is a statue, by J. Durham, in a pavilion at the end of the garden. The statue was erected in 1860 by the inhabitants of the town "as a tribute of gratitude and respect to one whose public benefactions and private virtues deserve to be remembered." From the terrace in front, a good view is obtained of the rocky valley in which Halifax stands, with Halifax Bank-"steep, rugged. and sometimes slippery," says De Foe -opposite.

The old quadrangular open Market Place, surrounded by a colonnade and galleries, has a curious Venetian piazzalike character. It is just behind the Independent Chapel (see ante).

The town is built chiefly of brown freestone from the quarties of N. and S. Owram, contrasting agreeably with the glaring red brick of Manchester and Leeds. There still remain a few picturesque timber-framed houses in the old market-place. Daniel de Forwhen forced to fly from London on account of his political writings, resided here under the name of Dr. Nettleton, in the Back Lane, at the sign of the Rose and Crown. He is said to have here written his treatise

De Jure Divino, and part of creative ground of about 60 acres has 'Robinson Crusoe.'—Other celebrities of Halifax and its wide parish are Henry Briggs, a very learned mathematician, and friend of Napier, the inventor of logarithms, born here in 1556, died Savilian Professor at Oxford in 1630; Archbp. Tillotson (see ante); and Sir Henry Savile, one of the most accomplished scholars of his day, and provost of Eton, where he published (1612) an edition of 'Chrysostom,' which "both in splendour of execution and in the erudition displayed in it leaves immeasurably behind it every earlier production of the English press."- Hal-The expense, said lam, Lit. Hist. to have been 8000l., was borne entirely by Savile, who was born at Bradley, in the parish of Halifax, in 1549, and died at Eton in 1622.

The 32nd regt., the men of which were formerly known as " haver-cake lads," used to be recruited almost entirely from Halifax and its neighbourhood. The sergeant, when recruiting here, carried a "haver-cake" (oat-cake—the common bread of the district) stuck on the point of his

sword.

A branch of the Calder Canal. carried up the vale of the Hebble to Halifax in 1828, gives the town a water-communication with Liverpool on one side, and with Hull on the Here are a canal basin with warehouses, and a supply of water is pumped up through a tunnel 12 m. long from a depth of 109 ft., out of the Rochdale Canal.

On Skircoat Moor (now Saville Park), W. of the town, a handsome Orphanage has been erected by the Crossley family, at a cost of 50,000L, and an endowment of 3000L per ann. It provides for the education of some

250 children.

The church of *Illingworth*, 3 m. N. of Halifax, has been restored: and another ch. has been built in a

been provided by Col. Akroyd, M.P.

A short branch line, passing down the valley of the Hebble, but turning off toward Copley, connects Halifax with the stat. of Sowerby Bridge on the Lancashire and Yorkshire Rly. The valley is not unpicturesque, although mills and tall chimneys rise in all directions.

Sowerby Bridge Stat. itself is one of those rapidly increasing, overgrown villages, merging into towns, which has burst into existence since 1825, as a seat of the cotton trade and woollen manufacture. It stands at the angle of the vale of Ripponden, down which the Rochdale Road descends from Blackstone Edge; and at the point where the Rochdale Canal joins the Calder Navigation. The railroad here crosses the valley on an elevated viaduct of 5 arches, looking down on the village, the new Townhall and the ch. of St. George, the river, and canals. In addition to the railroad stat., here are commodious wharfs, corn, worsted, and scribblingmills, chemical works, and iron foundries.

The village of Sowerby lies 1 m. S. of this, on a height above the valley. Its Church, rebuilt 1763, contains a statue of Archbp. Tillotson, erected in conformity with the will of his grandnieces. He was born (1630) at Haugh End in this parish—an old house, but in its present state later than the date of the archbp.'s birth. It may have been renewed by him. The parents of Tillotson were decided Puritans.

The high road from Sowerby Bridge to Rochdale in Lancashire crosses Blackstone Edge—a portion of the hill-chain running from Westmoreland into Derbyshire, and sometimes called the "backbone of Engremote and populous quarter of the land." Blackstone Edge is on the parish, near which a park and re- extreme border of Yorkshire; and

ascending it by a series of zigzags, winding along the edge of a ravine, and over the shoulders of the hills. Near the top are several great pools or reservoirs, which supply the Rochdale Canal. The summit is a dreary open moor of heath and black bog, which from its colour probably gave the hill its name. It is little altered since the days of Taylor the water-poet, who, writing in the reign of James I., says,-" I rode over such ways as were past comparison or amendment, for when I went over a lofty mountain called Blackstone Edge I thought myself in the land of break-necke, it was so very steep and tedious." It may now, however, be crossed without such traveller's dangers as De Foe describes in a most characteristic passage (Tour Through Great Britain, iii. 73), recording his journey from Rochdale to Halifax. It was in August, 1714 (?), but the "mountains were covered with snow;" and when the party got to the top of Blackstone Edge, "it was not easy to express the consternation we were in. The wind blew exceedingly hard. and drove the snow so directly in our faces, that we could not possibly keep our eyes open to see our way, nor, if we could, was there any to be discovered, except as we were showed it by a frightful precipice on one hand, and uneven ground on the other. Our very horses betrayed their uncasiness at it; and a poor spaniel dog that was our fellow-traveller, and usually diverted us with giving us a mark for our gun, turn'd tail and cry'd." After this came "a surprising clap of thunder, the first that ever I heard in a storm of snow, or, I hope, ever shall." But they overcame all difficulties at last, taking nearly the whole day to ride the 8 miles from Blackstone Edge to Halifax.

At Sowerby Bridge we enter the to save the exvale of the Calder, the main stream railway over it.

the road is carried directly over it, ascending it by a series of zigzags, winding along the edge of a ravine, and over the shoulders of the hills. Near the top are several great pools or reservoirs, which supply the Rochdale Canal. The summit is a dreary open moor of heath and black bog, which from its colour probably gave the hill its name. It is little altered since the days of Taylor the

[In this corner of Yorkshire, which is generally known as the "moor country," the word royd, either alone or as a suffix (Mytholmroyd, Holroyd, Ackroyd, &c.), is very common. It is apparently confined to this part of England; and almost certainly means essarted land-land cleared from wood and tree-roots. the meaning of the termination rode. so frequent in the Hartz country-Elbingerode, Gernrode, &c. It has also been regarded as the A.-S. rad. converted into "royd" by the peculiar pronunciation of the West Riding: and the prefix of local names of which it forms part may seem to support this notion—as stony-royd, "the stony road;" hod-royd, "the old road;" holroyd, "the hollow road;" how-royd, "the high or hill road," &c. (The word rad or rode is used with similar adjuncts in A.-S. charters.) Rood, a measure of land, has also been held to be the original of royd; but the cognate H. G. rode seems, on the whole, to suggest the most satisfactory explanation.]

The stat. beyond Sowerby Bridge is reached after passing a long tunnel. Luddenden Foot Stat.,

Mytholmroyd Stat. - the ch. of

Sowerby is seen on a hill, rt.,—and Hebden Bridge Stat. These villages are assemblages of mills, and cottages for their "hands," like all others in this district. Near Hebden Bridge the course of the Calder has been diverted, to save the expense of carrying the railway over it.

The upper part of the Vale of Calder lies in the parish of Halifax, and within its limits 9 tributary streams fall into the river from the moorlands on the right and left. In almost every instance a little town or colony of factories and dwelling-houses is built at the point of junction; and spreads thence up and down the main valley, with such rapid increase, that the village will soon become united. This is the country which De Foe describes in his • Tour,' when (about the year 1714) it must have been very populous, though the life here must have been somewhat different from what it is at "The nearer we came to present. Halifax," he says (Tour through Great Britain, vol. iii.), "we found the houses thicker, and the villages greater in every bottom, and not only so, but the sides of the hills, which were very steep every way, were spread with houses In short, after we had mounted the third hill. we found the country one continued village, though every way mountainous, hardly a house standing out of a speaking distance from another: and as the day cleared up we could see at every house a tenter, and on almost every tenter a piece of cloth, or kersie, or shalloon, which are the three articles of this country's labour. These by their whiteness reflecting the bright rays of the sun that played upon them, formed, I thought, the most agreeable sight I ever saw; the hills rising and falling so thick, and the valleys opening so differently, that sometimes we could see two or three miles this way, sometimes as far another . . . Tho' we met few people without doors, yet within we saw the houses full of lusty fellows, some at the dye-fat, some at the loom, others dressing the cloths; the women and children carding or spinning; all employed from the youngest to the oldest; scarce anything above 4 years old, but its hands were sufficient for its own support. Not a listic.

beggar to be seen, not an idle person, except here and there in an almshouse, built for these that are ancient and past working. The people in general live long: they enjoy a good air, and under such circumstances hard labour is naturally attended with the double blessing both of health and riches."

The mention of "shalloon" is a proof that the worsted manufacture (now the great staple of all this district) had been introduced before De Foe wrote. Woollen or cloth manufacture had been general here from a much earlier period. (See ante, Halifax.)

[1 m. rt. of Hebden Bridge is Heptonstall, on a bleak hill, where the old ch., now a ruin, dates from about 1180. The modern church, of Perp. character, was built near the old one, 1854. It is dedicated to St. Thomas, the old ch. to "St. Thomas Becket." The hills beyond Heptonstall, on the extreme border of Yorkshire, are wild and solitary. "I am at the highest point of the mountain road from Burnley to Heptonstall like the long lines of these hills with endless variety and sweet subtlety of curve. They are not mountains, nor have they any pretensions to the energetic character of the true mountain form: but they have a certain calm beauty and a sublime expression of gigantic power in repose, that we do not find in the loftier regions."—P. G. Hamerton, 'Painters' Camp.,' i. p. 10.]

From Hebden Bridge to Todmorden the valley of the Calder—here usually called "The Vale of Todmorden"—is very picturesque. Lofty hills of millstone-grit close close it in on either side; and the mixture of woollen and cotton mills with patches of ancient wood and old houses, teatifying to the former condition of the valley, is striking and characteristic.

Eastwood Stat. is passed, and then 3 tunnels—Horsfall, 424 yards long; Castle Hill, 192 yards; and Millwood, 225 yards—are traversed within a short distance of each other. Nearly above the first of these, Crosstone Chapel, perched on the summit of the hill, is a very conspicuous object; it was rebuilt in 1834, and its tower was struck by lightning, 1838, on the day of the Queen's coronation. In its lofty situation, it resembles one of those churches in Roman Catholic countries which are the resort of pilgrims.

Rt. a little beyond the Todmorden Viaduct the old mansion of Stansfield Hall looks down from the hill upon the railroad. It was probably built about the time of Henry VII., but is much altered and partly modernised.

Behind this viaduct, in the angle of the valley, is a ch., completed in 1832. (The old parish ch. of Todmorden, date 1770, remains in the middle of the town, and, after having fallen into the hands of Dissenters. was recovered for the Church, 1866.) Crossing the viaduct, the rly. enters

Todmorden Stat. Inns: Queen's; White Hart. This is a rustic town, flourishing in the manufacture of cottons, calicoes, fustians, dimities, and in the spinning of cotton yarn, situated on the Rochdale Canal, which hence accompanies the Calder river as far as Sowerby Bridge. The town stands partly in Yorkshire and partly in Lancashire, on the borders of the 2 counties, and near the junction of 4 townships, with a united population of 23,861 in 1881.

There are more than 40 cottonspinners and manufacturers here, at the head of whom was the late John Fielden, M.P., commonly called "King of Todmorden." His mammoth cotton-mill in the town is flanked on either side by a weavingshop—a room measuring 100 yds. by 60 yds. on the ground, lighted from above by skylights, filled with 900 or

1000 pair of looms, placed as close together as is possible to allow passage for the 400 or 500 men. women, and children who attend to them. It is scarcely possible to see to the other end through the interminable lines of shafts, straps, warps. and beams. A very handsome Tours Hall, of classic architecture, was erected here in 1875 at the expense of Messrs. Fielden (Gibson, archt.). In plan it is a rotunda, with a circular colonnade of Corinthian columns attached to a square. At one side is the statue in bronze of John Fielden. who obtained the Act for limiting the time of factory labour to 10 hours per The statue is by Foley, R.A.. and was erected by public subscription.

The Castle, Dobroyd, is the residence of J. Fielden, Esq.

ROUTE 37.

LEEDS TO MANCHESTER, BY DEWS-BURY AND HUDDERSFIELD.

(London and North-Western Rly. —10 trains daily.)

Leaving Leeds from the Wellington (Central) Stat., a viaduct of 44 lofty arches conducts this rly. through and over part of the town of Leeds, traversing the Leeds and Bradford line, the Leeds and Liverpool Canal by an arch of 70 ft. span, and the river Aire by one of 105 ft. span. Passing stations at Wortley and Churwell, we reach (in about 1 hr. from Leeds)

shop—a room measuring 100 yds. by 60 yds. on the ground, lighted from ship, in 1881. 15,016, is almost entirely above by skylights, filled with 900 or engaged in the woollen-cloth manufac-

ture. There is little to notice here be- | wainscotted rooms) marks the spot vond the fact that the ancient shapel of Morley was let by Saville, Earl of Sussex, in the reign of Charles I., on a lease of 500 years to the Presbyterians, from whose hands it has never been recovered. It remains a Calvinistic chapel, though still retaining in part the outward character of a ch. Unhappily it has been "restored," and many of its old features destroyed. The town (which gives its name to the Wapentake) was completely ruined by the Scots, who remained here for some time during one of their English forays in the reign of Edw. I. Immediately beyond the stat. the rly, enters a tunnel 2 m, in length. (The Bradford, Leeds, and Wakefield rly. is carried over this tunnel.) After emerging from it, the ruins of Howley Hall, once the residence of a branch of the Savilles, are passed 1. The Hall, built in 1590, by Sir John Saville, first mayor of Leeds (the borough was incorp. in 1626) was one of the finest mansions in Yorkshire. 60 yds, square, with a central court. It was garrisoned for the Parliament by Sir John Saville, and battered and taken by storm by the Earl of Newcastle; who with the generosity of a cavalier gave every protection to the garrison and their leader. A large part of the house was pulled down, and the materials sold, in 1730 (wrought stone from the mansion appears in many houses in Morley, Birstal, and Batley); and the ancient park, of 900 acres, has been enclosed and cultivated. Near the hall is "Lady Anne's Well," whilst sitting at which, a certain "Lady Ann" was, says the tradition, worried and eaten by wolves. The well was formerly visited by the neighbours on Palm Sunday; and it is still believed that on the morning of that day it assumes all sorts of colours.

A small stone near Howley Farm (which was built from the materials of the Hall, and contains some 20,871) is the head-quarters of the

where Nevison, a noted highwayman, murdered one Fletcher, in 1684; and by the speed of his horse reached York so soon after the deed, that he was enabled to establish an alibi. At the back of the farmhouse are some remains of the mansion of the Mirfields, who were here long before the Savilles.

The rly. traverses the wooded valley of a stream descending to the Calder at Dewsbury, and (receiving rt. the branch rly, running to Birstall

see post) reaches

Batley Stat. The Church is seen on the hill rt. It is Perp., and contains the altar-tomb with effigies of a Mirfield and wife, one of the ancient owners of Howley; and at the foot is a brass for John, Lord Savile of Howley, buried here in 1630. There are some fragments of good old stained glass.

St. Thomas's Church, on the hill between Batley and Horley (Sheard, archit.), has a good tower and spire, and was built in 1868. ; Before the introduction of the factory system, with the vast influx of population which followed, all this country, full of low, wooded hills, must have been very pleasing. Mills and tall smoky chimneys, however, have spread and are spreading over it in all directions. A network of roads unites the many "streets" and hamlets in which the inhabitants are warmly housed; and the relics of more ancient life, lingering here and there, contrast strangely with the stir and bustle of unsightly factories. There is evidence of wealth and activity on every side; but this great clothing district of Yorkshire hardly carries on its operations with such picturesque associations or surroundings as the cloth-workers of old Flanders-once the centre of the woollen trade, as Yorkshire is now.

Batley (Pop. of township in 1871.

no special interest for the tourist. Old clothes are bought here from all parts of Europe; are torn to pieces by machinery; and at last reappear in the shape of various fabrics in which the presence of "shoddy" is not generally suspected. "From what I saw in the tenter-ground," says Mr. White, "I discovered that pilot cloth is shoddy; that glossy beavers and silky-looking mohairs are shoddy; that the Petershams, so largely exported to the United States. are shoddy; that the soft, delicate cloths in which ladies feel so comfortable and look so graceful, are shoddy; that the fabric Talmas, Ragians, and paletots is shoddy. And if Germany sends us abundance of rags, we send to Germany enormous quantities of shoddy in return. The best quality manufactured at Batley is worth 10s. a vard: the commonest not more than 1s."-Month in Yorkshire.

The shreds and fragments of cloth are first torn and ground to pieces by a "devil," a revolving cylinder full of blunt steel teeth, which fills the air with "devil's dust." and throws out the "flocks" in a heap before The "flocks," so produced, are carried to the mixing-house, where, "according to the quality required, the long fibre is mixed in certain proportions with the short." They are then passed under a series of rollers, and come forth from the last looking something like wool. passes through the "scribbling" and "carding" machines; is wound on spindles, spun, and then passes through a fulling process until the piece is finished and ready for the dver. From the dve-house the cloth is carried to the tenter-ground. The whole process of converting the short, frizzly flocks, "resembling negro hair," into something which if not true broadcloth is very nearly as serviceable, is curious and interest-

"shoddy" trade, but has otherwise | necessary for seeing the mills, here as elsewhere.

> (In the Church of Woodkirk (rebuilt except the tower), 2 m. N.E. of Batley, is the tomb-slab of Sir John Topcliff. Chief Justice of the King's Bench and Master of the Mint, temp. Hen. VII. and VIII. He died at his house at Topcliff, in this parish, in 1514. Some part of the old house remains.)

The Great Northern Bly., between Bradford and Halifax, here touches the present line, and the trains stop at Batley Stat. The short "Birstall branch" joins the L. and N.W. Rly. a little above the stat. Birstall, about 2 m. from Batley, contains numerous woollen and "shoddy" mills. The ch. is late Perp. (temp. Hen. VIII.) and fine. The parish abounds in stone and iron. and contains numerous stone-quarties. Near Birstall is Oakwell Hall, the original of "Shirley," in Miss Bronte's novel. "The enclosure in front, half court, half garden; the panelled hall, with the gallery opening into the bedchambers running round; the barbarous peach-coloured drawingroom; the bright look-out through the garden-door upon the grassy lawns and terraces behind, where the soft-hued pigeons still love to coo and strut in the sun, are described in 'Shirley.' In the great hall hangs a mighty pair of stag's horns, and dependent from them a printed card. recording the fact that on the 1st Sept. 1763, there was a great hunting match when this stag was alain: and that 14 gentlemen shared in the chase, and dined on the spoil in that hall, along with Fairfax Fearneley. Esq., the owner."—Mrs. Gaskell, 'Life of C. Brontë.' (There is an actual "Field Head" a little beyond Oakwell, at which Dr. Priestley was born.) Miss Brontë was for some time at school at Roe Head, a house ing. An introduction is generally standing rt. of the road from Leeds

to Huddersfield, not far above Kirk- that many neighbouring churches. Gildersome Street, a village about 2 m. N.W. of Birstall, is supposed to derive its name from a colony of "Guilderland" cloth-weavers, who settled here in 1571.7

Batley Stat. is only 3 or 4 minutes distant from

Dewsbury Stat. (Inns: Royal Hotel, indifferent; King's Arms, similar: both near stat. Pop. in 1851. 10,601; in 1861, 18,148; in 1881. 29.617. It was created a corporate borough in 1862, and, with Batley, returns one member to Parliament.) The town of Dewsbury, the centre of a great branch of the woollen manufacture, comprising cloths, blankets. druggets, and carpets, stands pleasantly on the N. bank of the Calder. In and about the town are numerous woollen-mills, some worsted-mills. and some shoddy factories. A weekly market is held in the Cloth-hall, built in 1837. New public buildings, banks, and schools have risen here, as in other Yorkshire manufacturing Some churches have been built, none calling for special notice. Observe the Co-operative Buildings in North Gate, erected at a cost of 120,000L, including stores, reading rooms, large music hall; also the handsome block of buildings of the Demobury Pioneer Industrial Society, consisting chiefly of artizans, who have laid out 50,000L of their savings upon it.

An ancient tradition (unsupported, however, by any statement in Bede, the only trustworthy authority) asserts that Paulinus, the first preacher of Christianity in Northumbria (see York, Rte. 1: and Goodmanham, Rte. 8), addressed the heathen Saxons on the spot where the Church of All Saints now stands; baptised many thousands in the Calder; and afterwards founded the ch. itself. It is at least certain that Dewsbury is the mother ch. of all this district, and | valley is very picturesque, in spite of

[Yorkshire.]

including those of Huddersfield and Bradford, still make an annual payment to it. (The original parish occupied an area of 400 m., extending quite to the Lancashire border. and for some distance along it.) The outer walls of the present building were rebuilt in 1767; and in 1823 the ch. was again altered and enlarged. It seems to have been originally an E. Eng. structure: and the existing nave arcades are of that period: the piers on the N. side having detached shafts, ringed. The nave roof (Perp.) is nearly flat, with bosses at the angles of the panels. The chancel arch is E. Eng. chancel itself has been much altered. and shows only flat-headed lights at present. The S. and N. windows are filled with fragments of fine old glass of various dates. The E. window is modern. The font (Trans.-Norm.) is worth notice.

Some tombstones in the ch.-yard. of the 17th and 18th cents., are worth attention. Built in the W. wall of the S. aisle are some fragments of ancient carving, representing our Lord in Majesty, the miracle of Cana, and that of the loaves and fishes. There are others in the vicarage garden. These remains have been called Saxon, but are more probably early Norman. There are also some fragments of a Saxon tomb, discovered when the ch. was repaired. and resembling remains of a similar character at Bedale. (See Rte. 23.)

Leaving Dewsbury, a viaduct carries the rly. over the river Calder, the valley of which is still pretty; and passing the stat. at Thornhill Junction, the line, as far as it proceeds through the Calder valley, is the same as that of the Lancashire and Yorkshire Rly. between Wakefield and Halifax (see Thornhill Ch. seen on the Rte. 39. hill I. is there described). The rlv. again crosses the river, where the

the smoky town and inky stream, | bourhood of Huddersfield, though th before reaching

Mirfield Junct. Stat. (Here & branch line runs across to Low Moor and Bradford. See Rtc. 35.)

Mirfield (rt. of the stat.) is a large manufacturing village (Pop. of parish in 1881, 11,512), with many cotton and woollen-mills. The Church of St. Mary, a fine building (archit. Sir G. G. Soott), was completed in 1874. The tower alone of the older church remains.

After again crossing the Calder. the rly. leaves the Lancashire and Yorkshire line; and crossing the Colne just above Cooper Bridge, where that river falls into the Calder, proceeds up the valley of the Colne to Huddersfield. (At

Bradley Junction a short branch turns off rt., and soon again falls in with the Lancashire and Yorkshire line, thus connecting Halifax with Huddersfield.)

Hudderefield Stat. (Buffet here), used jointly by London and N.W. and York. and Lancashire Rlys., in St. George's Square (Inns: The George, best; Imperial, good; The Queen; The Cherry Tree). The town (Pop. in 1861, 34,874, showing an increase of 3994 since 1851; in 1881, 81,825) from the rly. stat. is somewhat imposing. It is built of stone, has fine wide modern streets and many noble buildings of considerable architectural pretensions. Such are some of the banks, warehouses, and factories. stands partly in the valley of the Colne, and partly on a hill rising toward the N.W. (The river Holme, which rises on the same high ground, close on the Yorkshire border, as the Colne, joins that river just above combined Huddersfield, and the streams are thenceforth known as the Colne till the junction with the Calder.) There is some picturesque the centre. These are near the sta-

surrounding country is by no mean the most fertile district of Yorkshire The coal, which is found here n plenty, and the abundance of water power, are the real causes of the pro sperity of the town, which in 180 had only a population of 7268. staple trade of cloth-weaving is car ried on, not only in the town, but is all the surrounding valleys, village and hamlets: thus rendering it a is more domestic occupation than u Leeds, Bradford, or Halifax. condition of the workpeople also i better than in those towns, their employment being more constant their appearance more healthy. the children rosy-cheeked, the cottage comfortable, and often furnished with a piano. (Musical power and taste are not less noticeable among the workpeople of Huddersfield than it the other manufacturing towns.) The agriculture of the district has greatly improved since the early part of the century, when it produced little mon than a scanty crop of oats. older part of the town, in addition to the manor of Almondbury, is the parperty of Sir John Ramsden, Bart., and has been in the possession of his family since the days of Charles II. A story is told that an offer was once made to Mr. Firth, a wealthy Quaker, who owned two small patches of ground in one corner of the town. the only pieces not belonging to the Ramsdens, to purchase them by covering them with guineas; and that his answer was "Set them edgeways, and the ground is yours." present and preceding Baronets have been large purchasers of land, extending their property on the N. and W. side of the town.

The Estate Buildings, two splendid blocks of building, have been erected by Sir John Ramsden for warehouses and offices, the estate office forming and pleasing scenery in the neigh- tion, and in front of the station is a

ir Robert Peel, in his robes as Chan-this, and the Hall, having become

ellor of the Exchequer.

Huddersfield (Odersfelt in Domeslay) was, no doubt (unless, as has een asserted, the stream running hrough it was anciently called the Iother), so named from the Odere Othere who established himelf here in the "field" or woodlearing by the river-side. It is the nost westernly of the "fields," a ermination always indicating an pen space in the forest, which inrease in number as Sheffield is aproached.

The churches are all modern. est are St. John's, of Early Dec. haracter, built by Sir J. Ramsden, rom designs by Butterfield; St. Chomas's, also Early Dec., built by he brothers Starkey, Sir G. G. Scott, rchit.; and St. Andrew's, Early Dec.,

W. H. Crossland, archit.

The parish Church (St. Peter's) vas entirely rebuilt in 1836; and is aid to have been originally founded in 1703) by Walter de Laci, who and vowed to build a ch. at Huddersield when in peril of his life among he then dangerous morasses between his place and Halifax. It still pays I fee of recognition to the mother ch. of Dewsbury, but, until the Dissoluion, belonged to the Priory of Nostel, dso founded by the Lacys. It contains a monument to Rev. Henry Venn, vicar from 1750 to 1778.

The Public Hall and Borough Court in Prince's and Peel Streets, built 1878-82, at a cost of 50,000l. (Abbey, archit.), contains a hall 140 ft. long.

The Cloth Hall, a red-brick rotunda, built by Sir John Ramsden in 1768, was the emporium for the products of the domestic manufacturers called "clothiers," who exposed their goods in the bulk or unfinished state. Merchants from Leeds, Halifax, and of Huddersfield itself, were the purchasers, who dyed and dressed the cloths ready for the tailor and draper.

tatue, in white marble, by Theed, of | The factory system has changed all less used year by year, has been converted into an Exchange and News Room.

> There are in the town more than 100 woollen-mills, besides a few silk and cotton factories. Firms of German merchants have been increasing in all these towns of late years, and do business mainly with the Conti-

> The Town Hall (1881) is a handsome ornate Italian building in Princes St. (Abbey, of Huddersfield,

archit.).

The Market Hall (opened 1880, archit., Hughes, of Lord St.) is covered by a glass roof resting on arched iron girders. The façade is of

stone, with tower.

The Mechanics' Institution - a plain substantial building in Northumberland-street, with news, lecture, and class rooms—is worth a visit. The Institute is one of the most flourishing in the kingdom.

The Literary and Scientific Sohas purchased a building formerly used as a chapel. is a small museum, and lectures and conversaziones are given during the

winter.

The Yorkshire Archeological and Topographical Association, founded in 1864, has the nucleus of a library in a room allotted to it by the President, Col. Brook, in Burston Road.

A Bridge over the Colne, of one noble span, was erected (1873), replacing the old one of 2 arches with high pitch, for which Blind Jack of Knaresborough was the contractor.

At Dungeon Wood is a Public Park (1880), presented to the town by H. Beaumont, Esq., of Whitley.

In the neighbourhood of Huddersfield are Whitley Park, the old seat of the Beaumonts, and Fixby Hall (W. C. C. Thornhill, Esq.). Pleasant excursions may be made to Almondbury (camp and village) and Woodsome Hall; and to Slack, the probable

site of the ancient Cambodunum; and that, in the British period, the disthe short line of rlv. to Kirkburton opens some picturesque country.

(1) Almondbury Camp (Castle Hill as it is generally called) may be reached by Somerset Road, or from the Fenay Stat., on the Kirkburton Railway (see post). (In the garden of Dudmanstone, the villa of W. R. Haigh, Esq., overlooking what is called the "Big Valley," is a remarkable block of millstonegrit, the relic of an escarpment, having in it a cavern precisely like a sea-cave. The rock itself has all the marks of the action of the sea. It is on the edge of the coal-measures.) Castle Hill is about 900 ft. above the sea; and is crowned by an intrenchment (with a single mound and fosse) taking the form of the summit of the hill, but with a mound running across the enclosure a little distance from either end, thus making a central square division, with two rounded extremities. Roman remains have been found here, although the squared centre seems to indicate the work of that people, and it is far from improbable that a British camp on so commanding a position may have been occupied by the legionaries. (The house which stands within the camp is entirely modern.) The Lacys had a castle at Almondbury, granted to them by King Stephen, who is said to have built it.

The view from Castle Hill is very fine and extensive; and the character of the district is well seen. High bare hills and ridges, with wooded valleys piercing them, stretch away S. and W. Stanedge and Holm Moss, on the Lancashire border, are conspicuous. N. Huddersfield is visible; and N.E. it is said that York Minster is sometimes to be seen. The hills and moors on which we look from Castle Hill are dotted with many tumuli, houses, and stone monuments (rings and upright stones), indicating one somewhat similar on the road-

trict was well peopled. There s some picturesque scenery in the upper part of the Colne valley: but on the whole this high country has no very great attractions for the tourist.

The village of Almondbury lin N.E. under the Castle Hill. Church (rest. 1875), ded. to All Saints, is worth a visit. The chancel is E. Eng. (circ. 1220?); the nave Perp., with the date 1471. On either side of the chancel are chantries (Perp.), founded by the Kavs of Woodsome, and the Beaumonts of Whitley. In the chancel is an incised slab for one of the Kays, date There is a very fine font cover, of the same character as those at Halifax and Bradford: and in chest in the aisle (rude and early are preserved some ancient standard measures for wine and corn. The Perp. tower is lofty, with high windows, filled with Perp. tracery. in the uppermost story. Round the nave of the ch., close under the roof (within), runs the following inscription :-

"Thou man unkind Have in thy miss My blody facce My woundes wyde On every my blody face: my wouldes water on every side For thy trespas.—Thou synar had Turn hiderward Behold thy Savyor fre-Unkind thou art From me to depart As-mercy I would grant thee.—For love of the The Jywes smeared me With skourgoskyne and sharp With a crown of thorn My head al to torn With a spert they thirly my hart.—With nails tree They nailed me has both foyt and hand for the treet.—My pashon was To reed the from the feede.— Penne cannot write Nor man indyght Pair-that I had so. Those mad my body bloo Pe that I had so. I nose mad my body bloo by wounds both large and long.—Thou doys me more dyre When thou doth swyre By m-here of my body Tham the Jwyca did Thi-spiylt my blod On the Mount of Calvere.— Wherefore pray the Thy swearing lay by Dread God alteryn If thou will do so I hevyn shall thou go Among angels to sync-

Before the verses are the words "Gefer Dyson was the maker of the Anno Domini 1522." Gaffer Dyson's production may be compared with screen in Campsall Church.

Rtc. 2.)

Almondbury Ch. seems to have been one of the earliest offsets from Dewsbury, to which it still pays dues. A very large parish stretches away from it, in which many daughter churches have been built, twelve of which now pay dues to Almondbury.

About 1 m. from the village is Woodsome Hall (a seat of the Earl of Dartmouth), one of the most charming old places in Yorkshire. (Woodsome may be conveniently reached from Fenay Stat., on the Kirkburton Railway, see post.) house, refronted in 1600, and again somewhat altered in 1644, low, gabled, and with long stone windows, stands on a paved terrace, with a Tufts of autumbalustrade in front. nal crocus push upward between the chinks of the pavement; and masses old-fashioned "greenery" rise against the grey walls themselves. From the terrace there is a beautiful view down the valley, which is much There is an air about the wooded. whole place, not only of unbroken antiquity but of the most complete repose and quiet, contrasting most delightfully with the bustle of the surrounding district. The interior is as little changed as the outside. A gallery runs along one side of the hall: which, with its old portraits, armour, cabinets, and enormous fireplace (above which are the names Arthur Kay, Beatrix Kay), affords an admirable study for the artist. A daughter of Arthur and Beatrix Kay married Lord Lewisham, and thus brought Woodsome into the family of its present owners. Curious portraits of an earlier John Kay and his wife (temp. Hen. VIII., the builders of the house) hang on cranes in the hall, so that they can be turned on either On the reverse of John Kay's portrait are the arms of many Yorkby John Kay and his wife; and on the same place; and it is certainly

(See the reverse of his wife's portrait are the "portraitures" of the descendants of an earlier Arthur Kay. edifying verses are inscribed on either picture, including the "Vita uxoris honesta"-

> "To live at home in howswyverie To order wel my famylye To see they lyve not idyllye To bringe upe children vertuislye To relyeve poore foulk willinglye This is my care with modestye To leade my life in honestye.

The house is built round a square courtyard, into which the main There are entrance formerly led. many gables, and an external staircase of stone affords access to the upper chambers. Woodsome is altogether an admirable specimen of a good (though not large) Yorkshire house of the 16th cent.; and it is much to be hoped that it is destined to undergo no changes. At the back are some pleasant woods, with a space of green field (ham-woods-ham) between them and the house.

(The ch. of Farnley Tyas, seen from Woodsome, was built by Lord Dartmouth 1840.) A good view of Huddersfield is

obtained in returning to the town

from Almondbury.

(2) Slack, the ancient Cambodunum, is 41 m. from Huddersfield, W. There is a good road passing Trinity Ch. and leaving Lindley to the rt. (The pedestrian may walk to it along Longwood Edge, whence good views of the country S. are commanded. On the hill opposite, S. are the reservoirs from which Huddersfield is supplied with water.)

Cambodunum is mentioned in the. 2nd of the Antonine Itinera as a station on the road from York to Manchester (Mancunium); 20 m. from Tadcaster (Calcaria), and 18 m. from Manchester. The "Camounlodounon," inserted by Ptolemy among shire families, "kin to Woodsome," the cities of the Brigantes, is perhaps

l. ii. c. 14), a "villa regia" of Edwin, in which Paulinus built a ch .afterwards burnt by the heathen Penda of Mercia, together with the whole "villa." (The altar. "quia lapideum erat," continues Bede, escaped the fire and was preserved in a monastery in Elmete. After Cambodum was burnt, the Northumbrian kings "made for themselves a villa" The site in the region of Loidis.) of Cambodunum, the Roman town in which there is thus tolerable evidence that the Saxons established themselves, has been variously fixed at Doncaster, at Almondbury, at Greetland (between Slack and Halifax). and at Slack; but the discoveries which have been made at this last place render it tolerably certain that the station was there. The position is high, but is screened by a higher ridge W. and S. A sloping piece of ground of about 12 acres is divided into enclosures called the "eald" or "old "fields, on which, says the local tradition, there formerly stood a great town. An altar, ded. to Fortune, by C. Antonius Modestus, centurion of the 6th legion, was found here about the middle of the last cent.; and Whitaker (Hist. of Manchester) asserts that pieces of thick glass, urns, Roman bricks and tiles, &c., were turned up in great quantities among the crowded foundations of buildings, against which the farmers frequently broke their ploughs. (In the Halifax Museum is one perfect tile, bearing the inscription, "Coh. IIII. Bre" (Cohors quarta Brencorum) and many fragments; and a sepulchre composed of such tiles is preserved at Huddersfield.) A hypocaust and bath have been found and uncovered here (the remains are preserved at Greenhead Park); and a thorough examination of the "eald fields," made Yorkshire by the Archæological Assoc., has been rewarded by a full confirmation of the views of Whitaker and Watson on

the "Campodonum" of Bede (H. E., l. ii. c. 14), a "villa regia" of Edwin, in which Paulinus built a ch.—afterwards burnt by the heathen Penda of Mercia, together with the whole "villa." (The altar, "quia lapideum erat," continues Bede, escaped the fire and was preserved in a monastery in Elmete. After Cambodum was burnt, the Northumbrian kings "made for themselves a villa" in the region of Loidis.) The site of Cambodunum, the Roman town in which there is thus tolerable evidence that the Saxons established them-

In the village of Stainland, 11 m. from Slack, is an ancient cross or landmark.—a circ. shaft, supporting a square block, carved with a St. Andrew's Cross, and hollowed on the Across the moor, about 2 m. is Greetland, where in 1597 a remarkable Roman altar was found, and figured by Camden, who saw it at Bradley Hall (Sir John Saville's). The tongue of land where it was discovered, at the junction of the Blackbrook with the Calder, may have been the site of a villa; but Roman relics of more or less importance have been found at many places in the neighbourhood.

(3) [The short rlv. from Huddersfield to Kirkburton is a branch of the London and North-Western, and opens up a very pleasant country. There is a station at Deighton; and then one at Kirkheaton, where is a ch., prettily situated, interesting chiefly as the burial-place of the Beaumonts of Whitley. There is a mural monument, of the 17th cent., for Sir Richard Beaumont, commonly known as "Black Dick;" and a good brass, with effigies for a Beaumont and his wife. The next station is at Fenau: and from it Almondbury and Woodsome Hall (see ante) may be visited. Fenay Hall (John A. Brooke, Esq.) is an old timbered building of the 17th cent., restored. Latin aphorisms are painted in old English

letters round the walls of the diningroom. The line continues to Kirkbuston, where is a fine ch., E. E.
and Perp., restored under the care of
W. S. Barber, Esq. Storths Hall (W.
Horsfall-Bill, Esq.) is beautifully situated on one side of the valley. Footpaths, leading sometimes through
woods and fields, may be followed to
join the Huddersfield and Sheffield
Rly. at Denby Dale, Stocksmoor, or
Brockholes stations.

(For Holmfirth, and other places accessible from Huddersfield by the Manchester and Sheffield Rly. (running by Penistone), see Rts. 44.)

Huddersfield to Manchester.

Leaving Huddersfield, the rly. passes through a tunnel in the rock, 966 yds. long; in the middle of which occurs an open cutting, 80 ft. deep, to allow of the junction, l., of the branch rly. from Sheffield to Penistone. The tunnel runs through the coal-measures, part of which have been worked, and the workings have been built up to sustain the rly. At

Longwood Stat. the rly. is carried across the valley on a viaduct of 20 arches, 249 yds. long and 70 ft. high.

Golcar Stat. is a scattered village, with a ch., built 1829—the head of a populous township, actively emgaged in the woollen manufacture. The Golcar Brook viaduct (61 yds. long) and the Grimble viaduct of 19 arches, 233 yds. long, and 63 ft. high, are passed before

Slastheonite Stat. This village, on the Coine and the Huddersfield Canal, has a Spa and bathing-house, supplied from a mineral spring abounding in alkaline salts and carburetted hydrogen, the latter in such quantity that it may be collected and burned. The spring rises in the bed of the river, but is now received in a stone reservoir. The spa is frequented in summer by the clothiers of the vici-

letters round the walls of the dining- inity, and is useful in some diseases of room. The line continues to Kirk- the skin.

A noble viaduct of 14 arches, 75 ft. high in the centre, and 182 yds. long, is then traversed, and the rly., winding much, and encountering many abrupt curves, reaches

Marsden Stat. On the E. side of Stanedge, in a deep valley on one of the head-waters of the Colne (5 m. N. of Delph), lies Marsden, a populous village, whose inhabitants are chiefly occupied in the woollen manufactures, though there is also a silk-mill and large iron-foundry.

[A very delightful moorland walk may be taken from Marsden, past Wissenden, to a place known as the Isle of Sleye. There is a road part of the way, and a poorly-defined path for the rest. From the high ground on the E. side of the valley there is a wide and very fine view—long hill-ranges, broken by "cloughs," each with its streamlet; a perfect seclusion, to which the heather and bracken lend beautiful and varying colour.]

The natural streams not being large enough in dry weather to supply the mills here, large reservoirs have been formed on the hills S. of Marsden, containing a supply sufficient to work the mills for 2 or 3 weeks, at the rate of 8 hours a day. There are 2 such reservoirs of 12 and 40 acres respectively to supply

The Huddersfield Canal, which has accompanied us by the valley of the Coine all the way from Huddersfield, and about \$\frac{2}{3}\$ of a mile from Marsden, enters a tunnel which carries it through the Stanedge mountain; whence it extends by Staley-bridge and Moseley to the Ashton and Oldham Canal. The canal tunnel is driven through the solid rock (except about \$\frac{1}{2}\$ m. of solid masonry at each end) for \$\frac{1}{2}\$ m., and is in one place

222 yds. below the surface. The I tunnel is often obstructed by the falling in of fragments from the roof, on which account persons are placed to warn the boatmen at each end. It is only wide enough to admit one boat a time. Barges are admitted for 3 or 4 hours in succession, first at one end and then at the other. They are worked through the tunnel by labourers, called "leggers," because, lving on their backs, they push the boat through with their legs against the walls,-a hard service, performed in the dark, and not unattended with danger from the falling masses. It requires 2 hours to leg a boat through. and a man earns from 1s. to 1s. 6d. for the task. The Huddersfield Canal. commenced by James Brindley, but not finished for 20 years, is the highest in Britain, being 655 ft. above the sea-level. Its entire length is 194 m., and the cost is believed to have exceeded 300,0001. It is still constantly used to convey raw materials and manufactured goods between Leeds and Liverpool; a traffic which the rlys. have not much affected.

Every nook and corner among these wild, barren. and uninviting hills is occupied with villages and manufactories; every rill and torrent most carefully husbanded to turn a wheel; and in addition, a very great number of mills are set in motion by steam.

A Tunnel, more than 3 m. long, running parallel with the canal tunnel, in places more than 652 ft. below the surface, and so straight that in a clear day you may see through it—carries the L. and N. W. Rlv. through Stanedge. It emerges close to the Diggle Stat.; and a little beyond is

12 m. Saddleworth Stat. The hilly district of Saddleworth—stretching along one side of Stanedge—(itself a continuation of Blackstone Edge, and part of the backbone of England) is scattered over with no fewer than of the primæval 177 villages and hamlets, the chief

of these being Upper Mill, Delph. Dobcross, Greenfield, Roughtown, and Lydgate. Almost all are occupied in the woollen manufacture, sometimes in mills, sometimes by their own hearths,—in which latter casthe business of a dairy-farmer is often added to that of a manufacturer: and the same hands ply the shuttle and milk the cows.

Saddleworth (12 m. from Huddersfield) is famed for its fine cloths and kerseymeres, very little inferior to those of the W. of England: also flannels and shawls. (Messrs. Whitehead and Co. here Weave Bunting for flags, destined to " brave the battle and the breeze" all over the world. Though a large part of the district consists of high and sterile land, it has increased most rapidly in population, and is the seat of prosperous and extensive manufactures. The number of steamengines is very great, while the valleys of the Tame and Medlock. and every tributary running into them, are occupied by numerous mills. (Stanedge is the watershed -the streams descending on one side into Yorkshire, on the other into Lancashire.) The contrast between the ancient and present condition of this district, which, according to the tradition, obtained its name from having been "sold for a saddle," is not a little striking. Many of the weavers keep beagles, and harehunting is a common amusement. "the field" following the hounds on

This wild district, extending into Lancashire, was divided into four "meres," one of which, Friar-mere, was given by the Stapleton family, the ancient lords of Saddleworth. to Roche Abbey.

The rocks of Greenfield, near Saddleworth, are very picturesque: and near them are some stone relics of the primesval period, known as the prince and Pane.

A short distance from Saddleworth | year.) the rly. crosses the Yorkshire border,

and soon reaches

Staleybridge, in Cheshire, and, 1 m. further, Ashton-under-Lyne, in Lancashire. (For the route hence to MANCHESTER TERMINUS see Handbook for Lancashire.)

ROUTE 38.

LEEDS TO WAKEFIELD.

(Great Northern Rly.—15 trains daily. Time of transit 30 min.)

The rly., leaving Leeds from the Central Stat., passes through a country of no great interest till it reaches Wakefield. Its whole course is through the coal-measures, which are largely worked, especially in the neighbourhood of Wakefield. The small woods, which here and there vary the surface very pleasantly, are grown in order to find supports for the collieries.

Holbeck Junction Stat., Beeston, Ardsley Junction, Lofthouse Stat.

From Ardsley Junction a branch line runs rt. by Gildersome and Drightlington to Bradford (transit in 40 min.). Immediately rt. of the Drightlington Stat. is Advalton Moor, where, June 30th, 1643, the Fairfaxes (who in January had entered Bradford, and had afterwards taken Leeds by storm) were entirely

"The Earl of Newcastle," says Rushworth, " had the advantage in numbers, especially in horse; but Fairfax's foot at first got the ground, and had almost encompassed the Earl's train of artillery, and put his forces to the rout, when a stand of pikes gave some check to their success, and at the same time a body of horse fell upon their rear and routed them: so that, the fortunes of the field being changed in one instant, Fairfax's army was utterly defeated. several pieces of ordnance taken, four or five hundred men slain, and many prisoners taken. The village of Adwalton, as its names indicates, is on the line of a Roman vicinal way. called here "Tong Street"—the entire course of which has not been traced.

Wakefield-2 stations, 1 in Kirkgate, for the Lancashire and Yorkshire. Gt. Northern, and N.E. Rly.; and one in Westgate, for Manchester, Sheffield, and Lincolnshire, and Gt. Northern Rlys. (Inns: Royal, opposite Town Hall; Bull; Strafford Arms; George. Pop. of township in 1881, 30,573), well situated on the banks of the Calder, was, until the rise of Leeds within the present cent., the great capital of the clothing trade in Yorkshire. Henry VII. settled many foreign weavers of woollen cloth at Wakefield, where the manufacture had long been practised; and Leland, in the reign of Henry VIII., describes it as "a very quick market town, meately large, the whole profit of which standeth by coarse drapery.' Early in the last cent. the worsted branch of the manufacture was established here; and in 1752 the inhabitants were of note as makers of worsted yarn, camblets, and stuffs. A large "Piece Hall" was afterwards erected; but either from want of enterprise, or from the more fortunate positions of such towns as Leeds and defeated by the Earl of Newcastle. Bradford, the woollen trade of Wake-(He was created marquis in the same field declined as that of the neigh-

bouring towns increased. There are ! still some woollen factories here; and many mills employed in spinning hosiery varn for the Nottingham and Leicester trade, but the main business of the place is now agricultural, in corn, wool, and cattle. One result of the change is that Wakefield is a more agreeable place of residence than its more bustling, but blacker and gloomier neighbours. There are indeed many collieries about it. and some iron-factories have risen on its outskirts; but no such cloud of smoke hangs over the town as that which hides the sunlight from Leeds. The Calder is navigable hence to Salter Hebble, where it is joined by canals extending to the Mersey. Much coal is exported from the district by this means. The town is but poorly built in comparison with its vigorous manufacturing neighbours, but is an interesting specimen of an old English town, with many large brick houses, and a few of earlier date—belonging to the days of "Merry Wakefield," as it was formerly called; though, says Fuller, "what peculiar cause of mirth this town hath above others, I do not know, and dare not too curiously inquire, lest I turn their mirth among themselves into anger against me. Sure it is seated in a fruitful soil and cheap country; and where good cheer and company are the premisses, mirth (in common consequence) will be the conclusion." George-a Green, the jolly Pinder" (keeper of the town pound or "pinfold"), who lived "in Wakefield all on a green,"—and who, after fighting "Robin Hood, Scarlet, and John," for a long summer's day (see post—Stanley Hall), took service with the "gentle thief"—introduced him, after the fight, to the "good cheer" of Wakefield :--

"'I have both bread and beef,' said the Pinder,
'And good ale of the best.'

' For such unbidden guests.'"

Excellent cheer is still to be commanded here: though unfortunately not at such rates as in the days of Leland, who says that "a right honest man shal fare wel in Wakefield for 2 pens a meale."—It has been suggested that one cause of "merriment" at Wakefield was afthe "mysteries" forded by "miracle plays," which were performed here, at stated seasons, as at Coventry and Chester. The so-called "Towneley Mysteries" were those played at Wakefield, and they contain one or two local allusions.

The famous Battle of Wakefield. fought Dec. 31, 1460, will best be noticed after the town itself has been described. The chief places of interest are—the Parish Ch., the Corn Exchange, and the Chantry Chapel. on the bridge over the Calder.

The *Parish Church (All Saints). the lofty spire of which, rising grandly over the surrounding buildings, is the great feature of the town. was consecrated by Archbp. William de Melton in 1329. The tower and spire are of 15th centy. date. Great part of the walls of the ch. was rebuilt between 1724 and 1800; between 1860 and 1874 the church tower and spire and the porch were most carefully restored, under the direction of Sir G. G. Scott. at a cost of 23,000l., and a reredos added. The height of tower and spire is 237 ft. The Perp. interior of the ch. is fine, with wide chancel and aisles. New windows have been inserted, and those E. and W. have been filled with stained glass by Hardman. Some tall screen work, temp. Charles I., between the nave and chancel deserves attention. The organ and case. of the same character, was a gift from the great Earl of Strafford. The ch.-yd. is paved with tombstones.

The Corn Exchange, built in 1837, and enlarged in 1862, is the largest in England, except that in Mark

^{&#}x27;And that is meat good enough,' said Robin Hood,

Lane, London. It is worth a visit on market-days, when a considerable (July 10) at Northampton, arrived amount of business is transacted. Wakefield is the great corn market for all this part of Yorkshire, but its trade has greatly declined, owing to the railways, by means of which Manchester has taken from Wakefield most of its former Lancashire trade. In the Kirkgate, which runs down to the Calder, is a picturesque timber-framed house locally known as the "Six Chimblies." Ireland after the Yorkist victory (July 10) at Northampton, arrived in London, and, "after long argument," agreed to a compromise with the party of King Henry; arranging that Henry should retain the crown for his life, but that the Duke should be recognised as heir-apparent. Queen Margaret, however, who was then in the North, would not surtender her son's rights without a further struggle. The Earl of North-umberland, and the Lords Clifford.

The Town Hall in Wood St. is a handsome edifice, in the French Gothic style, erected 1880 at a cost of 70,000L, Callcott, archt. It is surmounted by a clock tower 196 ft. high.

The *Chantry, on the bridge over the Calder, S. of the town, may be regarded as a direct memorial of the battle of Wakefield, and (except that on the bridge at Rotherham) is the only example of the kind now remaining in England. The bridge itself dates from the reign of Edw. III.: and the Chantry, originally built by Sir Robert Knolles in the same reign, was refounded by Edw. IV. in order that prayer might constantly be made in it for the soul of his father, Richard Duke of York. and for those of the followers of the White Rose who fell in the battle. The little chapel is 30 ft. long and 24 wide, and, after having long served as a corn-factor's counting-house and lumber-room, was restored in 1847, at a cost of nearly 3000l., and service is occasionally performed in it. windows are filled with good Perp. tracery; and the W. front (facing the bridge) is divided by buttresses into recessed compartments, arched. Above is an entablature, between which and the battlements are five sculptured figures. The great flood of the 16th Nov. 1866 rose nearly to this chapel, and laid all the lower parts of Wakefield under water.

In the autumn of 1460 the Duke Sir John and Sir Hugh Mortimers, of York, who had returned from Sir Davy Halle, his chief councillor,

(July 10) at Northampton, arrived in London, and, "after long argument," agreed to a compromise with the party of King Henry; arranging that Henry should retain the crown for his life, but that the Duke should be recognised as heir-apparent. Queen Margaret, however, who was then in the North, would not surrender her son's rights without a further struggle. The Earl of Northumberland, and the Lords Clifford. Dacres, and Neville, at once armed in her cause; and the Dukes of Exeter and Somerset, and the Earls of Devon and Wiltshire joined her, with their followers, at York. The Duke of York, with a body of about 5000 men (the exact numbers are uncertain, but it is clear that they were very much below those of the queen's army, said to have been 18,000), set out from London to oppose Queen Margaret, and reached Sandal Castle. 2 m. from the centre of Wakefield (on the hill S. of the bridge), on Christmas Eve. Here he was advised to wait until the Earl of March (afterwards Edw. IV.) could join him; but he insisted on accepting the challenge of his enemies (who were at Wakefield), and descended (Dec. 30—so Fabyan and the Rot. Parl. 1 Edw. IV.—others make it the 31st Dec.) upon Wakefield Green, as the level ground on the S. bank of the Calder was called. (The "Pinder," it will be remembered, "dwelt on Wakefield Green.") "He was suffered to pass forward," says Hall, "towards the main battle: but when he was in the plain ground between his castle and the town of Wakefield, he was environed on every side, like a fish in a net, or a deer in a buckstall; so that he, manfully fighting. was within half an hour slain and dead, and his whole army discomfited; and with him died, of his trusty friends, his two bastard uncles, Sir John and Sir Hugh Mortimers,

Sir Hugh Hastings, Sir Nevel, William and Thomas Aparre, both brethren, and two thousand and eight hundred others, whereof many were young gentlemen and heirs of great parentage in the S. part, whose lineages revenged their deaths within 4 months next and immediately ensuing." Whether the well-known scene of the Duke of York's death, in the 'Third Part of Henry VI.' (act i. sc. 4), is historically true, is uncertain. It is founded on a passage in Holinshed, who says, "Some write, that the duke was taken alive, and by derision made to stand on a molehill on whose head they put a garland made of bullrushes instead of a crown," and then, after mocking him, struck off his head. It is more probable that his body was found on the field, and that it was then mutilated—the head being sent to York, where it was set over Micklegate Bar. Queen Margaret's order was-

"Off with his head, and set it on York gates; So York may overlook the town of York."

The details of another famous episode in this battle—the murder of the young Earl of Rutland, son of the Duke of York, by the "butcher Clifford" ('Hen. VI.,' Part III., act i. scene 3)—are not less doubtful. It is uncertain whether Rutland fell by the hand of Clifford, of whom Leland only says that "for slaughter of men at Wakefield he was called the boucher;" and it is tolerably certain that Rutland, when he fell, was far more than the "maidenlike person of 12 years" as Hall describes him: he was at least 17 or 18, capable therefore of having taken part in the battle. The bodies of the Duke of York and of the young Earl of Rutland were interred first at Pontefract and afterwards at Fotheringay, where the Duke's head was afterwards conveyed.

A spot close to Wakefield Bridge, on the rt. bank of the Calder, is Mills, whither, until the year 1853, a

Thomas | of York was killed; and was at one time enclosed by a wall. (It is on the rt. side of the old road, leading from Wakefield to Barnsley, very near Sandal Castle.) The place is marked by two willows, still called the "Duke of York's trees." The young Earl of Rutland is said to have been killed in the town, where, savs Leland, he would have entered "a poor woman's house for succour; and she, for fear, shut the door, and straight the Earl was killed." Sandal Ch. is seen rt.; and on a hill crowned with trees nearer the river are some scanty remains of Sandal Castlelittle more than rubbish mounds, but enough to show that the central mound was crowned by a shell keep. and that there were external ditches and ramparts. The position commands the Calder valley and the surrounding country. John, the last Earl, who died in 1347, lodged within its walls his mistress Maud de Nerford, who had been the wife of Thomas of Lancaster. On his death without issue it came to the Crown: and, with the manor of Wakefield. had descended to the Duke of York from his uncle, Edward Earl of Rutland. In the reign of Edw. III. it was assigned as a residence to John Baliol, the ex-King of Scotland. It was dismantled by order of the Parliament in 1645. Except for the view over the battle-field the site of the castle is not worth exploring; and Sandal Ch. (Perp.) is of little interest. There is a chantry, but without monuments, for the Watertons of Walton.

In digging the foundations for Portobello House, N.W. of the meadow-land between Sandal and Wakefield, human bones, broken swords, and other relics, were discovered, showing that the battle extended in that direction.

At the foot of the bridge, on the l bank of the Calder, are the huge Sokr pointed out as that where the Duke very ancient feudal law compelled the inhabitants of Wakefield and five adjoining townships to send all their corn to be ground. This compulsory "multure" gave the miller 1-16th of the corn, and 1-32nd part of all the malt ground, in payment; in return for which the owner was obliged to maintain means for grinding (within 24 hours) all the corn of the district which might be brought to him. These compulsory rights were, however, purchased by the inhabitants in the above year for 18,000l., and were then abolished by Act of Parliament. On the opposite side of the river are large basins and a wharf, round which are grouped many corn magazines, huge piles of building filled with supplies of grains from Lincolnshire, the North and East Ridings, &c., destined to feed the clothing district.

On the hill above St. John's Ch. in Wakefield is the Lunatic Asylum, a vast building with a very good modern ch., large grounds and gardens, and the Grammar School, rebuilt in 1829. It was founded by Queen Elizabeth; and many distinguished natives of Wakefield have been educated here. Among them are John Potter, Archbp. of Canterbury and author of the once wellknown 'Antiquities of Greece,'-born here in 1674, died 1747; John Radcliffe, born 1650, founder of the Radcliffe Library and Observatory at Oxford (partly educated at Northallerton, see Rte. 16); Richard Bentley the famous critic, born at Oulton, between Leeds and Wakefield, in 1661, died 1742; and Joseph Bingham, author of the 'Origines Ecclesiasticæ,' born here in 1658. Other "illustrations" of Wakefield are Dr. Robertson, Dean of Durham, one of the "notable learned men" associated with Cranmer about the order of Communion (1548); Hugh Cressy, author of the 'Church History of Brittany,' born 1605; Dr. Burton, author of the 'Monasticon Eboracense.'

Richard Fleming, Bishop of Lincoln (1420-1431), the founder of Lincoln College, Oxford.

N. of the town (rt. of the Leeds Rly.) is the West-Riding Prison, an enormous building, constructed on the radiating principle, so that from the governor's desk in the centre the various wards are commanded. It can contain 2000 prisoners; but a large number of cells are rented by Government, and most of the Scotch convicts are sent here for some portion of their imprisonment.

Love Hill, commanding very extensive views, is very near Wakefield, S.W. There are a mound and earthworks, enclosing about 3 acres, and the site may have been that of a Saxon stronghold.

The most interesting excursion to be made from Wakefield is to Nostel Priory. (Walton Hall may be seen on the way. Walton is about 3 m. S. of Wakefield, and Nostel 4 m. from Walton.)

The Sandal and Walton Station, on the Midland Rly., is 1 m. from Walton Hall.

[The village of *Heath*, about 2 m. S. of the town, is built round a pleasant common commanding wide views. Heath Old Hall is a portion of a good Elizabethan house, with some fine elms round it. The arms of Queen Elizabeth and the shield of Kaye (circ. 1584) are over the entrance. On a chimney-piece in the house are the arms of Witham Witham, who died in 1503, bewitched, as it was decided, by a certain Mary Paunall, who was executed at York accordingly. The ghost of a Lady Bolles, a "baronettess,' so created by Charles I., and a solitary instance of such a creation, haunts the galleries. She died in 1662, and has a monument in Ledsham Church.]

author of the Monasticon Eboracense, Walton Hall, long the residence of born here 1697, died 1771; and the late Charles Waterton, is a place

But after the death of Mr. C. Waterton, in 1865, Walton lost its special character as a preserve, in which a gun was never fired, and the Museum was removed to Ushaw College.

Walton Hall, although still the property of Edmund Waterton, Esq., is now the residence of Edward Hailstone, Esq., who has removed hither, from Horton Hall, near Bradford, his library and art collections. Under his care the place has acquired other The "preserves" here attractions. were so remarkable that some notice of them must be inserted in this place. Mr. Charles Waterton (born in 1782, succeeded to Walton Hall in 1806), author of the amusing and instructive 'Wanderings in S. America,' was the descendant and representative of a family established at Walton for some centuries, having emigrated there from Waterton in Axeholm, Lincolnshire. It was one of the many Yorkshire houses which did not accept the changes of the Reformation. On his return from Guiana in 1813, Mr. Waterton determined so to arrange his park and estate at Walton as to "offer a hearty welcome to every bird and beast that chose to avail itself of his hospitality, and by affording them abundant food and a quiet retreat to induce them to frequent a spot where they would feel themselves secure from enemies save those which have been appointed to preserve the balance of nature." Accordingly, "mead, hill, and dale were laid out to suit the idiosyncrasies of various species; and trees of different kinds were planted in clumps, rows, or in solitary state, to attract the birds that love such localities." The park, entered by a lodge gate a little beyond the village of Walton, contains about 260 acres of gently undulating ground rising from the centre, which is occupied by a large lake, studded with his hand."

well-known to every naturalist in the i islands, and surrounded by simple meadow-land, drooping willows, or thick woods. The house stands on an island in this lake; and the whole domain is enclosed by a high wall. completed in 1826. This wall cost 9000l.—a sum which Mr. Waterton said he saved in wine, which he No gun might be never drank. fired within the park. Mr. Waterton. in his own words, "waged war with none but poschers and Protestants." To defeat the poschers many hundred wooden figures of pheasants were disposed among the branches of the trees, and in the dusk could not be distinguished from real birds. The whole place," says a former visitor, "literally teems with life—sweep the meadows, the trees, and the waters with the telescope, at any season of the year, and each spot towards which the glass is directed is as busy as a disturbed anthill. On the lake may be seen Egyptian and Canadian geese, mallards (which come in great flocks, and take wing in the evening for the Lincolnshire fens, where they feed during the night), teal, wigeons, pochards, golden-eves, tufted ducks, geese, and shovellers. Waterhens and coots run about under the very windows of the house." Herons swarmed in the tree-tops round the lake; owls were carefully provided for in the gateway-tower and in hollow trees; and the "shyest birds were so well aware of their security that they cared no more for spectators than the London sparrows for passengers." In the "grotto," a most quiet and pleasant retreat, within a grove of fine spruce firs, and a garden-house surmounted by a cross, Waterton used to watch his birds at all hours Whenever the late owner appeared there was "a general rush in his direction, and great was the flapping of wings and welcome of eager voices Birds crowded round him on all sides to snatch the expected morsel from

The house, a handsome and comfortable modern mansion (with the Waterton motto over the entrance-"Better kinde fremde than fremde kyne"=Better a kind stranger than estranged kin), stands on a rocky island in the middle of the lake, and is approached by an iron bridge. Mr. Charles Waterton's grandfather unhappily removed the old castle with its drawbridge, which had endured a siege from Cromwell and his Iron-Only one small fragment remains—the original gateway, the oaken door of which still holds a bullet from the pistol fired in spite (so runs the story) by Cromwell as he rode off after 3 days' vain beleaguering and battering of the old This bullet has an manor-house. inscription round it, recording its history. Near it is a rough pillar of stone perforated with holes, each designed as a nestling-place for some feathered tenant, and proportioned to its size; while among the ivy an owl was lodged in the shade. Over the entrance-tower is a lofty crucifix. Within the house Mr. Waterton arranged his very interesting collection of natural history, which it is no exaggeration to say excelled in preservation, beauty of plumage and skin, and in the perfectly natural attitude in which the animals are set up, every other in this country. this fine collection has been removed to Ushaw College, near Durham.

Mr. Charles Waterton, the naturalist, was born here in June, 1782, and died here May, 26, 1865. He is buried in a vault built by himself near the end of the lake, between two large oak-trees, in a solitude as complete as if in the depths of S. American woods. The place is marked by a cross erected in his lifetime; and at the base are the words "Orate pro anima Caroli Waterton, cujus fessa juxta hanc crucem sepeliuntur ossa." Under a great elm near the bridge which crosses the lake reposes another Waterton, crand-

father of the naturalist, who suffered imprisonment and fine in the cause of the Stewarts.

The very important collections of Mr. Hailstone give a new interest to Walton Hall. The Library, distributed through several rooms at the top of the house, is rich in English and foreign archæology, and contains by far the most perfect assemblage of books and prints relating to Yorkshire that exists in or out of the county. Here are also curious collections of ancient cookery-books, books on dæmonology and witchcraft, broadsides and ballads. Armour and other antiquities are arranged in the hall; a large blue dish of Spanish faïence. and a Persian dish (date 1399) of brass, gilt, being conspicuous. the drawing and music rooms is much fine Venetian glass, including a large drinking goblet, with a silver bell attached to the end of the footstalk -which is probably unique. bell was no doubt tingled as a signal when the glass was passed on in its rounds.) Some 16th cent. German enamelled glass, old French, Dresden, and other porcelain, also form part of the treasures assembled here; besides much Rafaelle ware, and Grés de The house also contains Flandres. superb collection made by Mrs. Hailstone, of needlework, point and cushion Lace, of all ages and countries; British and Saxon relics from Yorkshire "howes" and barrows: and many objects of mediæval art.

Nostel Priory (Charles Winn, Esq.) stands pleasantly in a wooded and picturesque country, about 5 m. from Wakefield, on the road to Doncaster. The house (which is not generally shown, and a special introduction is desirable) contains a large and valuable collection of pictures—some of considerable importance.

peliuntur ossa." Under a great elm A Priory of Augustinian canons near the bridge which crosses the (the first house of that order founded lake reposes another Waterton, grand- in England) was settled here in the

well-known to every naturalist in the world. But after the death of Mr. C. Waterton, in 1865, Walton lost its special character as a preserve, in which a gun was never fired, and the Museum was removed to Ushaw College.

Walton Hall, although still the property of Edmund Waterton, Esq., is now the residence of Edward Hailstone, Esq., who has removed hither, from Horton Hall, near Bradford, his library and art collections. Under his care the place has acquired other attractions. The "preserves" here were so remarkable that some notice of them must be inserted in this place. Mr. Charles Waterton (born in 1782. succeeded to Walton Hall in 1806). author of the amusing and instructive 'Wanderings in S. America,' was the descendant and representative of a family established at Walton for some centuries, having emigrated there from Waterton in Axeholm. Lincolnshire. It was one of the many Yorkshire houses which did not accept the changes of the Reforma-On his return from Guiana in 1813, Mr. Waterton determined so to arrange his park and estate at Walton as to "offer a hearty welcome to every bird and beast that chose to avail itself of his hospitality, and by affording them abundant food and a quiet retreat to induce them to frequent a spot where they would themselves secure from enemies save those which have been appointed to preserve the balance of nature." Accordingly, "mead, hill, and dale were laid out to suit the idiosyncrasies of various species: and trees of different kinds were planted in clumps, rows, or in solitary state, to attract the birds that love such localities." The park, entered by a lodge gate a little beyond the village of Walton, contains about 260 acres of gently undulating ground rising from the centre, which is occupied by a large lake, studded with his hand."

islands, and surrounded by simple meadow-land, drooping willows, or thick woods. The house stands on an island in this lake; and the whole domain is enclosed by a high wall, completed in 1826. This wall cost 9000l.-a sum which Mr. Waterton said he saved in wine, which he No gun might be never drank. fired within the park. Mr. Waterton, in his own words, "waged war with none but poschers and Protestants." To defeat the poachers many hundred wooden figures of pheasants were disposed among the branches of the trees, and in the dusk could not be distinguished from real birds. The whole place," says a former visitor, "literally teems with life—sweep the meadows, the trees, and the waters with the telescope, at any season of the year, and each spot towards which the glass is directed is as busy as a disturbed anthill. On the lake may be seen Egyptian and Canadian geese, mallards (which come in great flocks, and take wing in the evening for the Lincolnshire fens, where they feed during the night), teal, wigeons, pochards. golden-eyes, tufted ducks, geese. and shovellers. Waterhens and coots run about under the very windows of the house." Herons swarmed in the tree-tops round the lake: owls were carefully provided for in the gateway-tower and in hollow trees: and the "shvest birds were so well aware of their security that they cared no more for spectators than the London sparrows for passengers." the "grotto," a most quiet and pleasant retreat, within a grove of fine spruce firs, and a garden-house surmounted by a cross, Waterton used to watch his birds at all hours Whenever the late owner appeared there was "a general rush in his direction, and great was the flapping of wings and welcome of eager voices Birds crowded round him on all sides to snatch the expected morsel from

fortable modern mansion (with the Waterton motto over the entrance-"Better kinde fremde than fremde kvne"=Better a kind stranger than estranged kin), stands on a rocky island in the middle of the lake, and is approached by an iron bridge. Mr. Charles Waterton's grandfather unhappily removed the old castle with its drawbridge, which had endured a siege from Cromwell and his Iron-Only one small fragment remains—the original gateway, the oaken door of which still holds a bullet from the pistol fired in spite (so runs the story) by Cromwell as he rode off after 3 days' vain beleaguering and battering of the old manor-house. This bullet has an inscription round it, recording its history. Near it is a rough pillar of stone perforated with holes, each designed as a nestling-place for some feathered tenant, and proportioned to its size; while among the ivy an owl was lodged in the shade. Over the entrance-tower is a lofty crucifix. Within the house Mr. Waterton arranged his very interesting collection of natural history, which it is no exaggeration to say excelled in preservation, beauty of plumage and skin, and in the perfectly natural attitude in which the animals are set up, every other in this country. this fine collection has been removed to Ushaw College, near Durham.

Mr. Charles Waterton, the naturalist, was born here in June, 1782, and died here May, 26, 1865. He is buried in a vault built by himself near the end of the lake, between two large oak-trees, in a solitude as complete as if in the depths of S. American woods. The place is marked by a cross erected in his lifetime; and at the base are the words "Orate pro anima Caroli Waterton, cujus fessa juxta hanc crucem sepeliuntur ossa." Under a great elm near the bridge which crosses the

The house, a handsome and comrtable modern mansion (with the aterton motto over the entrance— of the Stewarts.

> The very important collections of Mr. Hailstone give a new interest to The Library, dis-Walton Hall. tributed through several rooms at the top of the house, is rich in English and foreign archæology, and contains by far the most perfect assemblage of books and prints relating to Yorkshire that exists in or out of the county. Here are also curious collections of ancient cookery-books, books on demonology and witchcraft, broadsides and ballads. Armour and other antiquities are arranged in the hall; a large blue dish of Spanish faïence, and a Persian dish (date 1399) of brass, gilt, being conspicuous. the drawing and music rooms is much fine Venetian glass, including a large drinking goblet, with a silver bell attached to the end of the footstalk -which is probably unique. bell was no doubt tingled as a signal when the glass was passed on in its rounds.) Some 16th cent. German enamelled glass, old French, Dresden, and other porcelain, also form part of the treasures assembled here; besides much Rafaelle ware, and Grés de The house also contains Flandres. superb collection made by Mrs. Hailstone, of needlework, point and cushion Lace, of all ages and countries; British and Saxon relics from Yorkshire "howes" and barrows: and many objects of mediæval art.

Nostel Priory (Charles Winn, Esq.) stands pleasantly in a wooded and picturesque country, about 5 m. from Wakefield, on the road to Doncaster. The house (which is not generally shown, and a special introduction is desirable) contains a large and valuable collection of pictures—some of considerable importance.

peliuntur ossa." Under a great elm A Priory of Augustinian canons near the bridge which crosses the (the first house of that order founded lake reposes another Waterton, grand- in England) was settled here in the

well-known to every naturalist in the world. But after the death of Mr. C. Waterton, in 1865, Walton lost its special character as a preserve, in which a gun was never fired, and the whole domain is enclosed by a high wall, completed in 1826. This wall cost College.

Walton Hall, although still the property of Edmund Waterton, Esq., is now the residence of Edward Hailstone, Esq., who has removed hither, from Horton Hall, near Bradford, his library and art collections. Under his care the place has acquired other attractions. The "preserves" here were so remarkable that some notice of them must be inserted in this place. Mr. Charles Waterton (born in 1782, succeeded to Walton Hall in 1806). author of the amusing and instructive 'Wanderings in S. America,' was the descendant and representative of a family established at Walton for some centuries, having emigrated there from Waterton in Axeholm. Lincolnshire. It was one of the many Yorkshire houses which did not accept the changes of the Reforma-On his return from Guiana in 1813, Mr. Waterton determined so to arrange his park and estate at Walton as to "offer a hearty welcome to every bird and beast that chose to avail itself of his hospitality, and by affording them abundant food and a quiet retreat to induce them to frequent a spot where they would themselves secure from enemies save those which have been appointed to preserve the balance of nature." Accordingly, "mead, hill, and dale were laid out to suit the idiosyncrasies of various species; and trees of different kinds were planted in clumps, rows, or in solitary state, to attract the birds that love such localities." The park, entered by a lodge gate a little beyond the village of Walton, contains about 260 acres of gently undulating ground rising from the centre, which is occupied by a large lake, studded with his hand."

meadow-land, drooping willows, or thick woods. The house stands on an island in this lake; and the whole domain is enclosed by a high wall, completed in 1826. This wall cost 9000l.—a sum which Mr. Waterton said he saved in wine, which he never drank. No gun might be fired within the park. Mr. Waterton, in his own words, "waged war with none but poachers and Protestants." To defeat the poschers many hundred wooden figures of pheasants were disposed among the branches of the trees, and in the dusk could not be distinguished from real birds. The whole place," says a former visitor, "literally teems with life—sweep the meadows, the trees, and the waters with the telescope, at any season of the year, and each spot towards which the glass is directed is as busy as a disturbed anthill. On the lake may be seen Egyptian and Canadian geese, mallards (which come in great flocks, and take wing in the evening for the Lincolnshire fens, where they feed during the night), teal, wigeons, pochards, golden-eyes, tufted ducks, geese. Waterhens and and shovellers. coots run about under the very windows of the house." Herons swarmed in the tree-tops round the lake: owls were carefully provided for in the gateway-tower and in hollow trees: and the "shyest birds were so well aware of their security that they cared no more for spectators than the London sparrows for passengers." the "grotto," a most quiet and pleasant retreat, within a grove of fine spruce firs, and a garden-house surmounted by a cross, Waterton used to watch his birds at all hours Whenever the late owner appeared there was "a general rush in his direction, and great was the flapping of wings and welcome of eager voices Birds crowded round him on all sides to snatch the expected morsel from

fortable modern mansion (with the Waterton motto over the entrance-"Better kinde fremde than fremde kyne"=Better a kind stranger than estranged kin), stands on a rocky island in the middle of the lake, and is approached by an iron bridge. Mr. Charles Waterton's grandfather unhappily removed the old castle with its drawbridge, which had endured a siege from Cromwell and his Iron-Only one small fragment remains—the original gateway, the oaken door of which still holds a bullet from the pistol fired in spite (so runs the story) by Cromwell as he rode off after 3 days' vain beleaguering and battering of the old This bullet has an manor-house. inscription round it, recording its history. Near it is a rough pillar of stone perforated with holes, each designed as a nestling-place for some feathered tenant, and proportioned to its size; while among the ivy an owl was lodged in the shade. Over the entrance-tower is a lofty crucifix. Within the house Mr. Waterton arranged his very interesting collection of natural history, which it is no exaggeration to say excelled in preservation, beauty of plumage and skin, and in the perfectly natural attitude in which the animals are set up, every other in this country. this fine collection has been removed to Ushaw College, near Durham.

Mr. Charles Waterton, the naturalist, was born here in June, 1782, and died here May, 26, 1865. buried in a vault built by himself near the end of the lake, between two large oak-trees, in a solitude as complete as if in the depths of S. American woods. The place is marked by a cross erected in his lifetime; and at the base are the words "Orate pro anima Caroli Waterton, cujus fessa juxta hanc crucem sepeliuntur ossa." Under a great elm near the bridge which crosses the (the first house of that order founded

The house, a handsome and com- | father of the naturalist, who suffered imprisonment and fine in the cause of the Stewarts.

> The very important collections of Mr. Hailstone give a new interest to The Library, dis-Walton Hall. tributed through several rooms at the top of the house, is rich in English and foreign archæology, and contains by far the most perfect assemblage of books and prints relating to Yorkshire that exists in or out of the county. Here are also curious collections of ancient cookery-books, books on dæmonology and witchcraft, broadsides and ballads. Armour and other antiquities are arranged in the hall; a large blue dish of Spanish faïence, and a Persian dish (date 1399) of brass, gilt, being conspicuous. the drawing and music rooms is much fine Venetian glass, including a large drinking goblet, with a silver bell attached to the end of the footstalk —which is probably unique. bell was no doubt tingled as a signal when the glass was passed on in its rounds.) Some 16th cent. German enamelled glass, old French, Dresden. and other porcelain, also form part of the treasures assembled here; besides much Rafaelle ware, and Grés de Flandres. The house also contains superb collection made by Mrs. Hailstone, of needlework, point and cushion Lace, of all ages and countries; British and Saxon relics from Yorkshire "howes" and barrows: and many objects of mediæval art.

Nostel Priory (Charles Winn, Esq.) stands pleasantly in a wooded and picturesque country, about 5 m. from Wakefield, on the road to Don-The house (which is not generally shown, and a special introduction is desirable) contains a large and valuable collection of pictures—some of considerable importance.

A Priory of Augustinian canons lake reposes another Waterton, grand- in England) was settled here in the well-known to every naturalist in the world. But after the death of Mr. C. Waterton, in 1865, Walton lost its special character as a preserve, in which a gun was never fired, and the whole domain is enclosed by a high wall, completed in 1826. This wall cost College.

Walton Hall, although still the property of Edmund Waterton, Esq., is now the residence of Edward Hailstone, Esq., who has removed hither, from Horton Hall, near Bradford, his library and art collections. his care the place has acquired other attractions. The "preserves" here were so remarkable that some notice of them must be inserted in this place. Mr. Charles Waterton (born in 1782, succeeded to Walton Hall in 1806), author of the amusing and instructive 'Wanderings in S. America,' was the descendant and representative of a family established at Walton for some centuries, having emigrated there from Waterton in Axeholm, Lincolnshire. It was one of the many Yorkshire houses which did not accept the changes of the Reformation. On his return from Guiana in 1813, Mr. Waterton determined so to arrange his park and estate at Walton as to "offer a hearty welcome to every bird and beast that chose to avail itself of his hospitality, and by affording them abundant food and a quiet retreat to induce them to frequent a spot where they would themselves secure from all enemies save those which have been appointed to preserve the balance of nature." Accordingly, "mead, hill, and dale were laid out to suit the idiosyncrasies of various species; and trees of different kinds were planted in clumps, rows, or in solitary state, to attract the birds that love such localities." The park, entered by a lodge gate a little beyond the village of Walton, contains about 260 acres of gently undulating ground rising from the centre, which is occupied by a large lake, studded with his hand."

meadow-land, drooping willows, or thick woods. The house stands on an island in this lake; and the whole domain is enclosed by a high wall, completed in 1826. This wall cost 9000l.-a sum which Mr. Waterton said he saved in wine, which he never drank. No gun might be fired within the park. Mr. Waterton. in his own words, "waged war with none but poschers and Protestants." To defeat the poschers many hundred wooden figures of pheasants were disposed among the branches of the trees, and in the dusk could not be distinguished from real birds. The whole place," says a former visitor, "literally teems with life—sweep the meadows, the trees, and the waters with the telescope, at any season of the year, and each spot towards which the glass is directed is as busy as a disturbed anthill. On the lake may be seen Egyptian and Canadian geese, mallards (which come in great flocks, and take wing in the evening for the Lincolnshire fens. where they feed during the night), teal, wigeons, pochards, golden-eyes, tufted ducks, geese. and shovellers. Waterhens and coots run about under the very windows of the house." Herons swarmed in the tree-tops round the lake: owls were carefully provided for in the gateway-tower and in hollow trees: and the "shyest birds were so well aware of their security that they cared no more for spectators than the London sparrows for passengers." In the "grotto," a most quiet and pleasant retreat, within a grove of fine spruce firs, and a garden-house surmounted by a cross, Waterton used to watch his birds at all hours Whenever the late owner appeared there was "a general rush in his direction, and great was the flapping of wings and welcome of eager voices Birds crowded round him on all sides to snatch the expected morsel from

fortable modern mansion (with the Waterton motto over the entrance-"Better kinde fremde than fremde kyne"=Better a kind stranger than estranged kin), stands on a rocky island in the middle of the lake, and is approached by an iron bridge. Mr. Charles Waterton's grandfather unhappily removed the old castle with its drawbridge, which had endured a siege from Cromwell and his Iron-Only one small fragment remains—the original gateway, the oaken door of which still holds a bullet from the pistol fired in spite (so runs the story) by Cromwell as he rode off after 3 days' vain beleaguering and battering of the old This bullet has an manor-house. inscription round it, recording its Near it is a rough pillar history. of stone perforated with holes, each designed as a nestling-place for some feathered tenant, and proportioned to its size; while among the ivy an owl was lodged in the shade. Over the entrance-tower is a lofty crucifix. Within the house Mr. Waterton arranged his very interesting collection of natural history, which it is no exaggeration to say excelled in preservation, beauty of plumage and skin, and in the perfectly natural attitude in which the animals are set up, every other in this country. this fine collection has been removed to Ushaw College, near Durham.

Mr. Charles Waterton, the naturalist, was born here in June, 1782, and died here May, 26, 1865. He is buried in a vault built by himself near the end of the lake, between two large oak-trees, in a solitude as complete as if in the depths of S. American woods. The place is marked by a cross erected in his lifetime; and at the base are the words "Orate pro anima Caroli Waterton, cujus feesa juxta hanc crucem sepeliuntur ossa." Under a great elm near the bridge which crosses the

The house, a handsome and comrtable modern mansion (with the imprisonment and fine in the cause aterton motto over the entrance— of the Stewarts.

> The very important collections of Mr. Hailstone give a new interest to Walton Hall. The Library, distributed through several rooms at the top of the house, is rich in English and foreign archaeology, and contains by far the most perfect assemblage of books and prints relating to Yorkshire that exists in or out of the county. Here are also curious collections of ancient cookery-books, books on dæmonology and witchcraft, broadsides and ballads. Armour and other antiquities are arranged in the hall; a large blue dish of Spanish faïence. and a Persian dish (date 1399) of brass, gilt, being conspicuous. the drawing and music rooms is much fine Venetian glass, including a large drinking goblet, with a silver bell attached to the end of the footstalk —which is probably unique. bell was no doubt tingled as a signal when the glass was passed on in its rounds.) Some 16th cent. German enamelled glass, old French, Dresden, and other porcelain, also form part of the treasures assembled here; besides much Rafaelle ware, and Grés de Flandres. The house also contains a superb collection made by Mrs. Hailstone, of needlework, point and cushion Lace, of all ages and countries: British and Saxon relics from Yorkshire "howes" and barrows; and many objects of mediæval art.

Nostel Priory (Charles Winn, Esq.) stands pleasantly in a wooded and picturesque country, about 5 m. from Wakefield, on the road to Doncaster. The house (which is not generally shown, and a special introduction is desirable) contains a large and valuable collection of pictures—some of considerable importance.

peliuntur ossa." Under a great elm | A Priory of Augustinian canons near the bridge which crosses the (the first house of that order founded lake reposes another Waterton, grand- in England) was settled here in the

But after the death of Mr. C. Waterton, in 1865, Walton lost its special character as a preserve, in which a gun was never fired, and the Museum was removed to Ushaw College.

Walton Hall, although still the property of Edmund Waterton, Esq., is now the residence of Edward Hailstone, Esq., who has removed hither, from Horton Hall, near Bradford, his library and art collections. his care the place has acquired other attractions. The "preserves" here were so remarkable that some notice of them must be inserted in this place. Mr. Charles Waterton (born in 1782, succeeded to Walton Hall in 1806), author of the amusing and instructive 'Wanderings in S. America,' was the descendant and representative of a family established at Walton for some centuries, having emigrated there from Waterton in Axeholm, Lincolnshire. It was one of the many Yorkshire houses which did not accept the changes of the Reformation. On his return from Guiana in 1813, Mr. Waterton determined so to arrange his park and estate at Walton as to "offer a hearty welcome to every bird and beast that chose to avail itself of his hospitality, and by affording them abundant food and a quiet retreat to induce them to frequent a spot where they would feel themselves secure enemies save those which have been appointed to preserve the balance of nature." Accordingly, "mead, hill, and dale were laid out to suit the idiosyncrasies of various species; and trees of different kinds were planted in clumps, rows, or in solitary state, to attract the birds that love such localities." The park, entered by a lodge gate a little beyond the village of Walton, contains about 260 acres of gently undulating ground rising from the centre, which is occupied by a large lake, studded with his hand."

well-known to every naturalist in the islands, and surrounded by simple meadow-land, drooping willows, or thick woods. The house stands on an island in this lake; and the whole domain is enclosed by a high wall, completed in 1826. This wall cost 9000l.-a sum which Mr. Waterton said he saved in wine, which he never drank. No gun might be fired within the park. Mr. Waterton. in his own words, "waged war with none but poschers and Protestants." To defeat the poschers many hundred wooden figures of pheasants were disposed among the branches of the trees, and in the dusk could not be distinguished from real birds. The whole place," says a former visitor, "literally teems with life—sweep the meadows, the trees, and the waters with the telescope, at any sesson of the year, and each spot towards which the glass is directed is as busy as a disturbed anthill. On the lake may be seen Egyptian and Canadian geese, mallards (which come in great flocks, and take wing in the evening for the Lincolnshire fens. where they feed during the night), teal, wigeons, pochards, golden-eyes, tufted ducks, geese. and shovellers. Waterhens and coots run about under the very windows of the house." Herons swarmed in the tree-tops round the lake; owls were carefully provided for in the gateway-tower and in hollow trees; and the "shyest birds were so well aware of their security that they cared no more for spectators than the London sparrows for passengers." In the "grotto," a most quiet and pleasant retreat, within a grove of fine spruce firs, and a garden-house surmounted by a cross, Waterton used to watch his birds at all hours Whenever the late owner appeared there was "a general rush in his direction, and great was the flapping of wings and welcome of eager voices Birds crowded round him on all sides to snatch the expected morsel from

fortable modern mansion (with the Waterton motto over the entrance-"Better kinde fremde than fremde kyne"=Better a kind stranger than estranged kin), stands on a rocky island in the middle of the lake, and is approached by an iron bridge. Mr. Charles Waterton's grandfather unhappily removed the old castle with its drawbridge, which had endured a siege from Cromwell and his Iron-Only one small fragment remains—the original gateway, the oaken door of which still holds a bullet from the pistol fired in spite (so runs the story) by Cromwell as he rode off after 3 days' vain beleaguering and battering of the old This bullet has an manor-house. inscription round it, recording its history. Near it is a rough pillar of stone perforated with holes, each designed as a nestling-place for some feathered tenant, and proportioned to its size; while among the ivy an owl was lodged in the shade. Over the entrance-tower is a lofty crucifix. Within the house Mr. Waterton arranged his very interesting collection of natural history, which it is no exaggeration to say excelled in preservation, beauty of plumage and skin, and in the perfectly natural attitude in which the animals are set up, every other in this country. this fine collection has been removed to Ushaw College, near Durham.

Mr. Charles Waterton, the naturalist, was born here in June, 1782, and died here May, 26, 1865. He is buried in a vault built by himself near the end of the lake, between two large oak-trees, in a solitude as complete as if in the depths of S. American woods. The place is marked by a cross erected in his lifetime; and at the base are the words "Orate pro anima Caroli Waterton, cujus fessa juxta hanc crucem sepeliuntur ossa." Under a great elm near the bridge which crosses the

The house, a handsome and comrtable modern mansion (with the imprisonment and fine in the cause faterton motto over the entrance— of the Stewarts.

> The very important collections of Mr. Hailstone give a new interest to Walton Hall. The Library, distributed through several rooms at the top of the house, is rich in English and foreign archæology, and contains by far the most perfect assemblage of books and prints relating to Yorkshire that exists in or out of the county. Here are also curious collections of ancient cookery-books, books on demonology and witchcraft, broadsides and ballads. Armour and other antiquities are arranged in the hall; a large blue dish of Spanish faïence, and a Persian dish (date 1399) of brass, gilt, being conspicuous. the drawing and music rooms is much fine Venetian glass, including a large drinking goblet, with a silver bell attached to the end of the footstalk -which is probably unique. bell was no doubt tingled as a signal when the glass was passed on in its rounds.) Some 16th cent. German enamelled glass, old French, Dresden, and other porcelain, also form part of the treasures assembled here; besides much Rafaelle ware, and Grés de Flandres. The house also contains a superb collection made by Mrs. Hailstone, of needlework, point and cushion Lace, of all ages and countries; British and Saxon relics from Yorkshire "howes" and barrows: and many objects of mediæval art.

Nostel Priory (Charles Winn, Esq.) stands pleasantly in a wooded and picturesque country, about 5 m. from Wakefield, on the road to Doncaster. The house (which is not generally shown, and a special introduction is desirable) contains a large and valuable collection of pictures—some of considerable importance.

peliuntur ossa." Under a great elm | A Priory of Augustinian canons near the bridge which crosses the (the first house of that order founded lake reposes another Waterton, grand- in England) was settled here in the

well-known to every naturalist in the world. But after the death of Mr. C. Waterton, in 1865, Walton lost its special character as a preserve, in which a gun was never fired, and the Museum was removed to Ushaw College.

Walton Hall, although still the property of Edmund Waterton, Esq., is now the residence of Edward Hailstone, Esq., who has removed hither, from Horton Hall, near Bradford, his library and art collections. Under his care the place has acquired other attractions. The "preserves" here were so remarkable that some notice of them must be inserted in this place. Mr. Charles Waterton (born in 1782, succeeded to Walton Hall in 1806), author of the amusing and instructive 'Wanderings in S. America,' was the descendant and representative of a family established at Walton for some centuries, having emigrated there from Waterton in Axeholm, Lincolnshire. It was one of the many Yorkshire houses which did not accept the changes of the Reforma-On his return from Guiana in 1813, Mr. Waterton determined so to arrange his park and estate at Walton as to "offer a hearty welcome to every bird and beast that chose to avail itself of his hospitality, and by affording them abundant food and a quiet retreat to induce them to frequent a spot where they would themselves secure from enemies save those which have been appointed to preserve the balance of nature." Accordingly, "mead, hill, and dale were laid out to suit the idiosyncrasies of various species; and trees of different kinds were planted in clumps, rows, or in solitary state, to attract the birds that love such localities." The park, entered such localities." by a lodge gate a little beyond the village of Walton, contains about 260 acres of gently undulating ground rising from the centre, which is occupied by a large lake, studded with | his hand."

islands, and surrounded by simple meadow-land, drooping willows, or thick woods. The house stands on an island in this lake; and the whole domain is enclosed by a high wall, completed in 1826. This wall cost 90001.-a sum which Mr. Waterton said he saved in wine, which he never drank. No gun might be fired within the park. Mr. Waterton. in his own words, "waged war with none but poschers and Protestants. To defeat the poschers many hundred wooden figures of pheasants were disposed among the branches of the trees, and in the dusk could not be distinguished from real birds. The whole place," says a former visitor, "literally teems with life—sweep the meadows, the trees, and the waters with the telescope, at any season of the year, and each spot towards which the glass is directed is as busy as a disturbed anthill. On the lake may be seen Egyptian and Canadian geese, mallards (which come in great flocks, and take wing in the evening for the Lincolnshire fens, where they feed during the night), teal, wigeons, pochards-golden-eyes, tufted ducks, geese. and shovellers. Waterhens and coots run about under the very windows of the house." Herons swarmed in the tree-tops round the lake: owls were carefully provided for in the gateway-tower and in hollow trees: and the "shyest birds were so well aware of their security that they cared no more for spectators than the London sparrows for passengers." In the "grotto," a most quiet and pleasant retreat, within a grove of fine spruce firs, and a garden-house surmounted by a cross, Waterton used to watch his birds at all hours Whenever the late owner appeared there was "a general rush in his direction, and great was the flapping of wings and welcome of eager voices Birds crowded round him on all sides to snatch the expected morsel from

fortable modern mansion (with the Waterton motto over the entrance-"Better kinde fremde than fremde kyne"=Better a kind stranger than estranged kin), stands on a rocky island in the middle of the lake, and is approached by an iron bridge. Mr. Charles Waterton's grandfather unhappily removed the old castle with its drawbridge, which had endured a siege from Cromwell and his Iron-Only one small fragment remains-the original gateway, the oaken door of which still holds a bullet from the pistol fired in spite (so runs the story) by Cromwell as he rode off after 3 days' vain beleaguering and battering of the old This bullet has an manor-house. inscription round it, recording its history. Near it is a rough pillar of stone perforated with holes, each designed as a nestling-place for some feathered tenant, and proportioned to its size; while among the ivy an owl was lodged in the shade. Over the entrance-tower is a lofty crucifix. Within the house Mr. Waterton arranged his very interesting collection of natural history, which it is no exaggeration to say excelled in preservation, beauty of plumage and skin, and in the perfectly natural attitude in which the animals are set up, every other in this country. All this fine collection has been removed to Ushaw College, near Durham.

Mr. Charles Waterton, the naturalist, was born here in June, 1782, and died here May, 26, 1865. buried in a vault built by himself near the end of the lake, between two large oak-trees, in a solitude as complete as if in the depths of S. American woods. The place is marked by a cross erected in his lifetime; and at the base are the words "Orate pro anima Caroli Waterton, cuius fessa iuxta hanc crucem sepeliuntur ossa." Under a great elm near the bridge which crosses the (the first house of that order founded

The house, a handsome and com- | father of the naturalist, who suffered imprisonment and fine in the cause of the Stewarts.

> The very important collections of Mr. Hailstone give a new interest to The Library, dis-Walton Hall. tributed through several rooms at the top of the house, is rich in English and foreign archeology, and contains by far the most perfect assemblage of books and prints relating to Yorkshire that exists in or out of the county. Here are also curious collections of ancient cookery-books, books on dæmonology and witchcraft, broadsides and ballads. Armour and other antiquities are arranged in the hall; a large blue dish of Spanish faïence, and a Persian dish (date 1399) of brass, gilt, being conspicuous. the drawing and music rooms is much fine Venetian glass, including a large drinking goblet, with a silver bell attached to the end of the footstalk -which is probably unique. bell was no doubt tingled as a signal when the glass was passed on in its rounds.) Some 16th cent. German enamelled glass, old French, Dresden, and other porcelain, also form part of the treasures assembled here; besides much Rafaelle ware, and Grés de The house also contains Flandres. superb collection made by Mrs. Hailstone, of needlework, point and cushion Lace, of all ages and countries; British and Saxon relics from Yorkshire "howes" and barrows; and many objects of mediæval art.

Nostel Priory (Charles Winn, Esq.) stands pleasantly in a wooded and picturesque country, about 5 m. from Wakefield, on the road to Doncaster. The house (which is not generally shown, and a special introduction is desirable) contains a large and valuable collection of pictures—some of considerable importance.

A Priory of Augustinian canons lake reposes another Waterton, grand- in England) was settled here in the

reign of Henry I. by Ralph Adlave, its foundation here. Of the many the king's chaplain and confessor, on a spot where certain hermits had already established themselves. Ralph had been left sick at Pontefract during one of the northern expeditions of Henry I.; discovered the hermits whilst riding through the woods here; was struck "by their pious manner of living," and wished at first to join them, but afterwards established the priory of which he became the first superior. Grants were made to the new foundation by Henry and his nobles-especially by Robert de Laci-who gave the wood in which the priory was built. (It was within his honour of Bontefract: the name probably signifies "North stall," from a "stall" or hunter's lodge in the wood here-so Kirkstall, near Leeds.) The Lacys were accordingly regarded as the real founders by the canons of Nostel. The priory was dedicated to St. Oswald, whose name seems to have been connected with the place at an earlier period: and other churches dedicated to him were united to Nostel, among them the ch. of Macerfeld (the site is uncertain), on the battle-field where Oswald had fallen, and Bamborough, where one of the royal saint's arms was preserved. During the civil war Nostel belonged to Sir John Wolstenholme; and it was here, whilst Charles I. was at York, that Hyde lay concealed and penned the King's answers to the propositions of Parliament. ('Life of Clarendon,' i. 138.)

The existing house, on the site of the ancient priory, was built entirely by Sir Rowland Winn. It is large and stately, standing in a park well peopled with deer, and having in front and at the side (partly separated from the park by the high road) the "pool of Nostel," a considerable piece of water, frequently referred to in the charters of the priory, as the "stagnum S. Oswaldi," and one of

interesting pictures in the house the most remarkable is the celebrated representation of Sir Thomas More and his family, ascribed to Holbein, and exhibited at S. Kensington in 1866. This picture hangs in the hall, and deserves the most careful examination. In front, seated, are Sir Thomss More, aged 50, wearing the chancellor's collar; and his father. Sir John More, aged 76. On the rt. are Alice, wife of Sir Thos. More, aged 57, kneeling in prayer with a book: Margaret Roper, eldest daughter of Sir Thomas, and the most learned of the "Moricæ," as Erasmus, in his letters, calls the daughters of the chancellor,-she holds open in her hands Seneca's tragedy of 'Œdipus,' at a passage of the Chorus. act iv.; and Cecilia Heron, his third daughter. On the l. are Mrs. Clements, wife of Dr. John Clements (her maiden name was Gigey); and Elizabeth Dancy. 2nd daughter of Sir Thomas, aged 21, with a vol. of Seneca's epistles under her arm. Behind are Anne Crisacre, aged 15; John More, son of Sir Thomas, to whom she was betrothed, aged 19; and Henry Pattison, Sir Thomas's jester. Next is John Harris, with a roll of paper in his hand, secretary to Sir Thomas. On the wall behind hangs a curious Dutch clock-the original of which was long preserved at Walton Hall. In an inner room is a young man reading. Size of the picture, 11 ft. 6 by 8 ft. 3. The names and ages are inscribed over every figure.

This picture, painted according to the dates in 1530, has generally been supposed to be the same which is known to have been in the possession of Andreas Van Loo, a contemporary of Holbein, and to have been purchased at his death by Mr. Roper. of Well Hall, Eltham, the son-in-law of Sir Thomas More. Thence it came by marriage to Sir Rowland Winn. Horace Walpole first, howthe advantages of site which led to ever, and after him Dr. Waagen,

expressed grave doubts whether the good foreign sculpture and carving picture now at Nostel is more than an early copy; and its exhibition at S. Kensington has led the most competent critics to the same conclusion. Holbein's drawing for this picture remains at Basle, and was engraved in outline by Christian Von Mechel in 1781. It agrees in all essential respects with the Nostel picture; and since the original (if this be indeed a copy) no longer exists, the value of this at Nostel can hardly be overrated.

Among other pictures at Nostel are-Van de Velde, a very fine seapiece, with stormy sky; Jacob Ruysdael, a canal, with houses and trees; Robert Van der Hoeck, combat of horseman. "Of great delicacy. The pictures of this artist, well known to the connoisseur by his spirited etchings, are very rare."-Waagen. Jan Miel, a party of peasants in the open air: Carel Dujardin, landscape with cattle; Guercino, a sibyl (very fine); Dirk Van Delen, interior of a ch.; Vanduck, boys playing with leopards—a very remarkable picture, of unusual character for Vandyck. but no doubt by him; Orizzonte, a landscape; fine; Jan Wynants, a fine landscape, resembling Ruysdael; Van Aelst, dead game; Swaneveldt, landscape with the Flight into Egypt; A. Van Boom, landscape with ruins.

In the Library is preserved a history of the Prince of Nostel, written in the time of Prior Quixley (1393-1428). The Chartulary of Nostel is among the Cotton MSS. (Vesp. E. 19.)

Close to the entrance of the park is the Church of Wragby, in which parish Nostel is situated. It occupies, in all probability, the site of a chapel of St. Oswald, either first built by Ralph Adlave, or which he found already standing, and grouped his first temporary buildings around it. The ch. is for the most part plain Trans.-Norman; and can hardly be as ancient as the priorate of Ralph Adlave. The font is Norm. Some [Yorkshire.]

has been placed in the ch. by the Winns of Nostel. Over the altar is a "pietà," the Virgin supporting the Saviour,—with figures of the Apostles on either side. The panels of the pulpit are filled with carvings in Turkish box by Venetian artists, representing the Nativity: the Adoration of the Shepherds; the Wise Men the Saviour mocked by soldiers (finest, but painful in design); and the Descent from the Cross. Round the reading-desk are old Flemish figures. The E. window is filled with stained glass, the greater part of which seems German—but there is a tradition that some of the figures-including a portrait of Alured Comyn, the last prior but one, with St. Oswald and other saints, were brought from the refectory of the priory. The shield of Prior Comyn (a golden wheatsheaf on an az. ground) is at any rate conspicuous in the window.

At the end of the S. aisle is a mont. with figures by Chantrey, for John Winn of Nostel, died 1817, and his sister. In the N. aisle is a monument by Flaxman (Justice with her balance), for Sir Rowland Winn, died 1765.

In returning to Wakefield from Nostel, Sharlston Hall, an Elizabethan house (date 1574) of some character, containing a few ancient portraits, is passed rt. There is an inscription over the porch.

About 2 m. from Wakefield, near the village of Stanley, is "Pinder's Green," the traditional scene of the combat between the "Jolly Pinder of Wakefield" and "Robin Hood, Scarlet, and John."

"'Now turn again, turn again,' said the Pinder,

For a wrong way you have gone; For you have forsaken the king's highway, And made a path over the corn.

"'O that were a shame,' said jolly Robin, 'We being three, and thou but one.'
The Pinder leapt back then thirty good feet, Twas thirty good feet and one.

"He lean'd his back fast unto a thorn, And his foot against a stone,

And there he fought a long summer's day, A summer's day so long! Till that their swords on their broad bucklers

Were broke fast into their hands."

(See the whole ballad in Ingledew's 'Ballads and Songs of Yorkshire,' p. 46.) The fight ended in the Pinder's taking service with Robin Hood.*

ROUTE 39.

WAKEFIELD TO HALIFAX.

(Lane, and Yorksh. Rly.)

12 through-trains daily. Time of transit 1 hr.

The rly. runs through the valley of the Calder, still wooded in parts, and picturesque in spite of the never-ending mills and tall chimneys. The valley is one of the great manufacturing centres of Yorkshire, and indeed of the world. It is a great colony of mills and mill-hands; and is one of the most densely populated districts of England.

Before reaching Horbury Stat. (the first out of Wakefield) the rly, from Barnsley (see the next route) joins

the line l., at

Horbury Junction Stat. Horbury, rt. (Pop. of township in 1881, 5050),

* The history of "George-a-Green, Pinder of Wakefield," was long a popular chapbook, and is included among Thoms' 'Early English Romances.' "As good as George-a-Green" is still a local saying.

is a large manufacturing village. It was the birthplace of Carr the architect (died 1807), the builder of many important houses in Yorkshire, and both architect and founder of a chere, a most unsatisfactory building.

From the next station.

Thornhill Lees, Dewsbury (Rte. 37) is distant 1 m. rt. (A very good modern ch., Dec. in character, with schools and vicarage, is seen rt., close to the line, just before the train enters the stat. Lees Hall (Charles Wheatley, Esq.) is an Elizabethan house, partly of wood and plaster. There are many mills for woollens of various sorts, carpets, and "shoddy"

in this part of the valley.) Thornhill Lees, or Meadows (the termination is often found in this district, as at Kirklees), stretch along the Calder at the foot of the bare hill-side on which Thornhill Church (It is about a mile from is seen l. This ch, must not be left the stat.) unvisited by the antiquary. nave was rebuilt in 1777 (as appears from an inscription on the exterior); but the fine Perp. tower, and a Dec. chancel with its aisles, remain, and the latter contains some very interesting monuments, besides some of the finest ancient glass in Yorkshire. The tower arch at the W. end of the nave is Perp. like the tower itself. The Dec. chancel is of 3 bays, with small bosses of very good foliage at the intersections of the hood-mouldings. The clerestory lights above are insertions of later date. The E. window and the windows in the S. aisle are Perp., as are those in the N. aisle, forming the Savile Chantry. The E. window is filled with fragments of magnificent Perp. (portions of a tree of Jesse) singularly fine in both design and colour. This was probably inserted by Robert Frost, "chancellor to the redoubted prince Arthur, and late parson of this ch.," who, as an inscription formerly in one of the chancel

windows recorded, "made new this and the date 1529. The figures are window, and also clerestoried and arched this choir, finished the yere of grace, 1499." The inscription is preserved by Dugdale, but the window in which it was placed is not mentioned. It was probably, however, the E. window. Some glass of the same date, more fragmentary, but well worth notice, remains in the E. window of the N. aisle, with remains of an inscription running thus when entire, "Pray for the guide prosperity, mercy, and grace of Wm. Savile, one of the company of Grase In, and for the soules of Sir John Savile and Dame Alice, fadyr and modyr to the said William; and also for the guide prosperity, mercy, and grace of Sir John Savile and Dame . . ., which Wm. Savile enlarged this choir at his cost at the oversight of his nephew, wherewith pray we all that God be pleased, the which warke was finished in the yeare of our Lorde 1497." There is more glass (also very good) in the tower window at the back of the organ, where it cannot be seen. In the clerestory of the chancel are some scattered fragments (heads, All this glass is probably foreign.

The chantry on the N. side of the chancel is rich in Memorials of the Saviles, of whose ancient residence, Thornton Hall, some remains exist in the vicarage grounds. In the easternmost arch (between chancel and chantry) is a lofty canopied mont., with effigies of a knight and lady, Sir George Savile and his wife, sister of the great Earl of Strafford. is a good example of the time—early in the reign of Chas. I. The next arch contains a very large altar-tomb. with effigies of a knight and his two On the tomb is a curious wives. inscription-

" Bonys emong stonys lyes here ful styl Quilst the sawle wanders wher God wyl "- of oak, and represent a Sir John Savile, with his two wives. Alice Vernon and Eliz. Paston. armour is not well made out; and the ladies wear mantles, with chaplets on their long flowing hair. the third arch is a very fine alabaster tomb, with a knight and lady, temp. Edw. IV.; the knight wears a collar of suns and roses, the badge of Edw. IV., and is bareheaded. His armour is an excellent example, but the sword - scabbard, which has been elaborately ornamented, is broken. At the E. end of the chantry is the earliest effigy-that of a knight (no doubt a Thornhill—the family which was established here before the Saviles, who acquired the property with the Thornhill heiress), temp. Edw. I., cross-legged, with a surcoat over his chain-mail, and his head under a canopy. A helmet and gauntlets (Elizabethan?) are hung in this chapel.

A few ivv-covered walls of the Saviles' Hall here remain as has already been said, but are of no architectural value. The Saviles of Thornhill were the chief of their name in Yorkshire, and the many other families of Savile in the county were descended from them. had been settled here since the end of the reign of Edw. III., and long held the stewardship of the honour of Wakefield, which gave them the command of Sandal Castle, where they frequently resided. There is excellent letter from Lord Strafford to his young nephew Sir Wm. Savile, giving him instructions for his manner of life at Thornhill (Strafford Letters, i.); but the house was soon afterwards taken and burnt by the Parliamentarian forces, and was never rebuilt. William's son, Sir George Savile, a man of great wit and greater vice, was created by Chas. II. Baron of Elland, Earl and Marquis of Halifax.

Beyond the Thornhill Lees Stat.

2 H 2

^{*} See Whitaker's 'Loidia,' where the date is given 1897-an obvious error.

Dewsbury is seen lifting its tall | chimneys through the cloud of smoke that hangs densely above it. At Mirfield Junction the line is joined rt. by the branch rly, that runs hence to Low Moor, on the line between Bradford and Halifax, passing by Heckmondwike and Cleckheaton (see Rte. 35). Mirfield Church (Rte. 37) is seen on the hill rt. Great factories and warehouses rise on either side. The river, already once crossed by a viaduct, is recrossed; and

Cooper Bridge Junct. is reached, where the line to Huddersfield (Rte.

37) turns off 1.

On the l. bank of the Calder, a little above this stat., is Kirkless, the seat of Sir George Armytage, famous as the traditional scene of Robin Hood's death. A priory of Cistercian nuns was founded here in 1155 by Regner de Fleming, some remains of which exist, although the greater part of the materials were used for building the present Hall, in the reign of Jas. I. (The family of Armytage became possessed of the site 8th Eliz.) A buttress and two piers of the N. nave arcade mark the site of the priory church. W. is a Perp. building, 3 stories high, probably part of the prioress's lodgings; and on the S. side of the ch. is the cemetery, in which were discovered in 1706 (and are still to be seen) the tomb-slabs of the first prioress, Elizabeth de Stainton, and of her 2 sisters, who entered the house at the time of its foundation. The inscription on the tomb of the prioress runs: " Douce J.H.U. de Nazaret Filz Dieu Tez Mercy a Elizabeth Stainton Priores de cest maison." The most perfect relic of the priory, however, is the gatehouse, with very thick walls and narrow windows. A small closet here is pointed out as the scene of Robin Hood's death. According to a tradition of uncertain age, but which is certainly older than Camden's time (to whom it was commu- inscription-

nicated in a letter from Sir John Savile), "the gentlest of thieves" (whom Fuller places among his worthies "not for his thievery, but for his gentleness"), being "distem-pered with cold and age," applied to the prioress of Kirklees, "a woman very skilful in physic and surgery. to be let blood. The prioress, it is also said, was his aunt: but, knowing "how fell an enemy he was to religious persons," she took revenge by letting him bleed to death. ballad (of no great value—it will be found in Gutch's 'Robin Hood,' and in Ingledew's 'Yorkshire Ballads') gives the rest of the story. Robin, shut up in a narrow room by the prioress, was slowly bleeding to death, he "bethought him of his bugle horn," and "blew out weak blasts three."

"Then little John, when hearing him. As he sat under the tree,

'I fear my master is near dead. He blows so wearily."

Little John hastens to Kirklees. "breaks locks two or three," and prays that he may be allowed to burn

> " -fair Kirkley hall And all their nunnery.'

This Robin forbids—

"I never hurt fair maid in all my time. Nor at my end shall it be. But give me my bent bow in my hand, And a broad arrow l'il let flee; And where this arrow is taken up, There shall my grave digg'd be,"

So it was done; and across the park. at a distance giving sufficient proof that Robin had not lost his skill, notwithstanding his weakness, is his grave. It lies high, on a table-land commanding a very fine view across the valley. The spot on which the arrow fell, in the midst of thick trees, is enclosed by iron railing; and at the back is a block of stone. on the side of which is the well-known "Hear Underneath dis lait! Stean Las Robert earl of Huntington Neer arcir ver as hie as geud An pipl kauld him Robtn Heud Sick utlaus as he an is men Vil england nivr ei agen. Obit 24 kai Dekembris, 1247."

The stone has been broken, and the inscription is said to have been originally on the top. It is curious that nothing has been ascertained as to the history of these rhymes, which cannot be older than the last century, and are by no means so passably antique as the least careful of Chatterton's.

The park of Kirklees is large and well timbered, "full of sunny glades, speckled with black shadows of immemorial yew-trees." There are traces of an ancient camp near its S.E. corner. Close outside is an old gabled house, now a roadside inn, known as the 'Three Nuns;' and near it is the so-called "Dumb Steeple"—a monument which possibly marks the limit of sanctuary formerly belonging to the priory.

Leaving the Cooper's Bridge Stat., and crossing the river, the rly. has I. the sloping woods of *Bradley Park*, and soon reaches

Brighouse Stat. Here is another large and rapidly increasing assemblage of mills and warehouses, woolen, as usual in this district. Beyond the stat. a very pretty view occurs up a wooded valley rt., through which a considerable stream descends to join the Calder.

Elland Stat. Very near the rly. l. is the "old hall of Elland," once the home of a family of the same name, whose history affords an example of private feud to be paralleled perhaps on the Highland border, but hardly in England even during the middle ages. It forms the subject of a long and indifferent ballad (of uncertain date, but perhaps formed on some earlier poem) called 'The

History of Sir John Elland, and printed in Mr. Ingledew's volume. (There is also a prose narrative, which became a sort of popular drama, called 'Revenge upon Revenge,' acted by travelling companies in this part of Yorkshire, the dialogue being partly extempore, and partly supplied from the book. See Hunter's 8. Yorkshire, ii. 431.) In the 15th year of Edw. III. (1342) one Exley, a relation of the Beaumonts of Crossland Hall (about 5 m. direct S. of Elland, in the Meltham Valley), killed, it would appear accidentally or in a sudden fray, a sister's son of Sir John Elland, who in that year was sheriff of Yorkshire. Exley gave to the Ellands a piece of land, hoping by this means to pay his "blood fine," and to satisfy the powerful family whom he had offended: but Sir John, either discontented with the value of the land, or resolved on more complete revenge, sought to kill Exley, who fled for protection to Sir Robert Beaumont. the neighbouring families - Lockwood of Lockwood, and Quarmby of Quarmby—were bound to the Beaumonts either by ties of relationship, or by the feudal "bond of associa-They, too, seem to have supported Exley, and accordingly Sir John Elland led his men by night first to Lockwood, where they killed the head of the house-"that wilv wight," as the ballad calls him-and then to Quarmby, where Hugh of Quarmby shared the same fate. Neither of these houses (they stood at no great distance from Crossland, but no traces of them remain) was defended by a moat, and the assailants seem to have had little difficulty in breaking into them. But Crossland, to which they next went, was surrounded by a "wet ditch," the traces of which are still visible; and Elland and his men were stopped by it for some time, until, in the early morning, a servant, coming out of the house for water,

which they instantly rushed and entered the house. Sir Robert Beaumont, in spite of vigorous resistance. was overpowered, dragged from his bed, and beheaded in his own hall in the presence of his wife and two young sons. Elland then called for bread and meat, and insisted that the two boys should eat with him. The younger did so; but the elder, not more than 5 years old, flung back the meat at his father's murderer: and Sir John threatened that he "would speedily weed out the offspring of Beaumont's blood, as they weed out the weed from corn." He Crossland, however, without harming the boys, who with their mother fled at once into Lancashire. where they remained for 15 years in the households of the Townleys and the Breretons—relatives of Ladv Beaumont. The sons of Lockwood and of Quarmby had also sought refuge in Lancashire, and, being now of sufficient age, they agreed with the two Beaumonts to return and take an ample revenge. Assisted by friends who came with them from Lancashire, and by others from their own estates, they waylaid Sir John Elland on his return from holding his "turn" (court) at Brighouse; and as he passed through a wood called "Cromwell Bottom" (about 2 m. from Elland, and near Brighouse) they set on him and killed The Beaumonts then, according to the ballad, "fled in Furness fells," but after some time determined to complete their work. Palm Sunday "at e'en" they hid themselves in Elland mill, waited there through the night, and early on the following morning saw, as they expected, the young knight of Elland, with his wife and infant son, pass by the mill-dam toward Elland Adam Beaumont shot at him with an arrow from a window of the mill, but the arrow glanced

let down the drawbridge, across | wood, with surer aim, sent a second arrow through Elland's head. The child in arms was also wounded, and carried back to die in Elland Hall. The Beaumonts fled from the hue and cry that was instantly raised, toward Ainley Wood, making stand occasionally against their pursuers. In the wood, Quarmby, who had been severely wounded, was hidden by Lockwood "in an ivy tree." The others got safe to Crossland and the Elland men, as they turned back through Ainley Wood, found Quarmby and killed him. Lockwood afterwards escaped to a place called Camel Hall, where he was discovered by the sheriff, and killed after a desperate resistance. His family, a very ancient one, expired with him. The Beaumonts left the country. took service with the knights of Rhodes, and Adam Beaumont fell at last in battle with the Turks.

Elland Hall, although still retaining some old portions, has been so much of it has been rebuilt, that it has lost all architectural value. Above it, rt. of the rly., stretches Elland Park, thickly wooded; and on its western border is Exley, no doubt the place which gave name to the Beaumonts' follower. Elland mill still occupies its old position—near the bridge; and a small part of it is ancient. Of Crossland nothing remains but the most.

ing to the ballad, "fled in Furness fells," but after some time determined to complete their work. On Palm Sunday "at e'en" they hid themselves in Elland mill, waited there through the night, and early on the following morning saw, as they expected, the young knight of Elland, with his wife and infant son, pass by the mill-dam toward Elland church. Adam Beaumont shot at him with an arrow from a window of the mill, but the arrow glanced from his corselet; William Lock-

stone is 27 yards in thickness, and is | described in Rte. 39. Thence turnthe grand repository from which the greater part of England is supplied. Some ferns and calamites occur in it. but it is not rich in fossil remains. There is a good view from Elland Edge.

Beyond Elland the rly. again crosses the Calder, and at the

North Dean Junct. the Huddersfield line (which has run over the same ground as our own from Cooper Pridge Junct.) turns N. up the valley of the Hebble to Halifax. A very good new ch., with schools adjoining, crowns the cliff rt. At

Sowerby Bridge Stat. passengers for Halifax sometimes have to change carriages. (For Sowerby Bridge, and the line thence to Halifax, see Rte. 36.)

ROUTE 40.

WAKEFIELD DONCASTER, BARNSLEY AND MEXBOROUGH (CONINGSBOROUGH).

(Lancashire and Yorkshire Rly. from Wakefield to Barnsley. M., S., and L. (Manchester, Sheffield, and Leeds) from Barnsley to Doncaster.

From Wakefield to Barnsley 7 trains daily. Time of transit, 30 min.)

As far as Horbury Junct. the line

ing S. it proceeds to

Crigaleston Stat., close to the entrance of a long tunnel, which extends nearly the whole way between this and the next stat...

Haigh. From the tunnel the rly. emerges into the long valley of a feeder of the river Dearne. On the

high ground L is

Woolley Hall (Godfrey Wentworth, Esq.), with a Jacobsean house much modernised. In the park, wellstocked with deer, are some fine chestnuts. The house was painted by Aglio, about 1820, and has some enriched ceilings and Italian scenes on the walls of the music - room. It contains some valuable chinaamong other pieces, a turtle in Urbino ware, of which only one other example (at Narford Hall, in Norfolk) is known; and a sort of epergne, in Plymouth china, with shells and fish admirably moulded and coloured. In the Library are the cartularies of Monk Bretton Priory (see post), and of St. Leonards at Pontefract. Woolley Church, Perp., of two periods, with some interesting Norman portions, has been well restored. Some excellent figures in stained glass, of Perp. date, have been rearranged by Clayton and Bell, by whom there are 2 good modern windows in similar style. In the ch.-vd. are 2 remarkable coped tombs, with sides built up with ashlar, date and appropriation unknown. There is a very wide and fine view from Woolley Edge, as the high ground above the village is called. The vale of the Calder is seen on one side, and in another direction the long ridges of moorland about Penistone.

Rt. of the rly. are seen the extensive park and lake of West Bretton (W. B. Beaumont, Esq.). The house, large and fine, is of 3 periods, but all from Wakefield is the same which is comparatively modern. It contains

There is a some good portraits. wide view from the terrace over the Dearne valley. At the next stat.

Darton, is a fine Church (restd.), worth a visit. It is late Dec. or early Perp. (nave with clerestory, and a Perp. open roof), and Perp. chancel, on the wall-plate of which is the "Ad landem Dei inscription. omnium sanctorum istum cancellum de novo construxit Thomas Tykyll. prior monasterii Monk Britannise, et hujus ecclesise patronus; et eundem complete finivit anno Domini 1517." The ch. belonged to the Lacys and their descendants, until in the 1st Rich. III. it was given to Monk Bretton Priory, the arms of which, three covered cups, occur in the wood-work of the nave roof. John Heathfield, vicar of Darton during the civil war, has left a short notice of himself in the parish register, and adds a prayer for delivery from the Roundhead, more honourable to his loyalty than to his Latinity,-"A dolis rotundi capitis, libera me Domine, et Judæ suavium det Deus ut caveam." In the ch. is an elaborate monument, with a full-sized marble statue, for John Silvester (died 1722, aged 70), who, when a smith at the Tower of London, is said to have constructed a chain for stretching across the Thames, so as to prevent the Dutch fleet from sailing up the river. This was the foundation of his fortunes, and he became a large landowner in this part of Yorkshire.

An obelisk, about 70 ft. high, near the entrance of Darton village, is a memorial of Ann, wife of Thomas Beaumont, of Darton, d. 1778. modern church of High Hoyland is seen on the hill rt. There is a wide view from the ch.-vd.

A little beyond Darton the river

Dearne is crossed.

Barnsley Junct. Stat. for the Lancashire and Yorkshire, Midland, and Manchester, Sheffield and Lincoln Rlys.

Barnsley Stat. (Inns: King's Head. old-fashioned and comfortable: famous for the best mutton-chops in Yorkshire; Royal). Barnsley is a place of little interest for the ordinary tourist. It is without antiquities, and the extensive manufactories are very far from rendering the town agree-It is, however, a good point from which to explore the very interesting country lying between it and Sheffield. Wentworth Castle (see post) is easily accessible from Barnsley. Wortley and Wharncliffe (Rte. 44) are reached in a very short time by rly.; and the branch of the S. Yorkshire Rly. between Barnsley and Sheffield (Rte. 46) will take the tourist through much beautiful country, well worth exploring on foot. Wentworth House (described Rte. 45) may also be visited from the Chapel Town Stat. on this line. these places may be made the objects of days' excursions from Barnsley.

The town, from its exposed situation, was formerly known as "Bleak Barnsley," an epithet now changed to "Black Barnsley," from its smokestained houses, and narrow dirty streets. The population in 1861 was 17,885. In 1811 it was 5014. 1881 it was 29,781. Except Middlesbrough and Bradford, no town in Yorkshire is increasing at so rapid a rate. It is one of the chief seats of

the linen manufacture.

Damasks, drills, dowlas, ducks, broad sheetings, &c., are made here. There are bleaching, dyeing, and calendering works in and near the town, besides a flax-spinning mill: but most of the flax thread is brought from Leeds and other places at a distance. Barnsley was once exclusively celebrated for its iron wire. The surrounding country abounds in coal (there are more than 42 collieries in the district), iron, and freestone, and there are several iron foundries in the neighbourhood.

[The Oaks Colliery at Ardsley in

this district was the scene (Dec. 12,1 1866) of one of the most fatal accidents in a coal-mine ever recorded. More than 300 men and boys perished in the first explosion; and 20 or 30 volunteers engaged in searching for their missing comrades were killed by a second explosion on the following (The total number killed morning. was 358.) The two accidents which most nearly approached this in extent of destruction were at Lundhill Colliery, in this district, in 1857, when 189 were killed; and at Hartley, Durham, in 1862, when 209 were killed.]

St. Mary's Church, modern except the tower, was built in 1820, in the Gothic of that period, and in 1870 greatly improved and decorated. Near the stat. is the Independent Chapel, built in 1851, Gothic, with a good spire. The Park of Barnsley was given to the town in 1861 by Mrs. Locke, widow of Joseph Locke, Eq., M.P., who was educated at the Grammar School here.

'T' Bairnsla Foaks Annual, an Pogmoor Olmenack. Be Tom Treddlehoyle, Esq.,' is published here regularly, and very well illustrates the peculiar dialect of the district.

Old Barnsley, which gave rise to the town, is a small village on the summit of a hill, about 1 m. to the N.W.

Barnsley enjoys the advantages of inland navigation by means of the Barnsley Canal, which extends from the Dearne and Dove Canal, near the town, to the Calder near Wakefield.

A branch Rly. runs to Cudworth Stat., 31 m. E. on the Midland Line.

[About 2 m. N.E. of Barnsley, between the river Dearne and the Barnsley Canal, are the remains of Monk Bretton Priory. (The village of Monk Bretton is more than 1 m. N.) The priory was founded for Cluniac monks by Adam Fitz-Swain in 1157 (3rd Hen. II.). The site was granted to a certain William Blith-

man, whose descendant sold it to George, Earl of Shrewsbury.

The remains are scanty, but deserve a visit. The gatehouse (Perp.) is perfect, and the E. end of the ch., with some portions of the domestic buildings, are Dec. "A pigeonhouse," says Rickman, "seems of E. Eng. date; it is circular, and a curious building."

3 m. S.W. of Barnslev is Wentworth Castle (F. Vernon Wentworth. Esq.), to be carefully distinguished from Wentworth Woodhouse, the seat of Earl Fitzwilliam (Rte. 45), with which it is often confounded. township of Stainborough (so named most probably from Stainborough Low, a mound which may have been the ancient gathering-place of the district) had belonged to the families of Everingham and Cutler, until in the reign of Wm. III. it was bought by Thomas Wentworth, Baron Raby, 1st Earl of Strafford, of the 2nd creation. The old house, which had been known as Stainborough, was pulled down, and the new one received the name of Wentworth Castle. This house, a building of the Queen Anne period, was refronted, after a design of his own, by William. 2nd Earl of Strafford of the new creation; and the park in which it stands, highly ornamented with wood and water, is in truth, as Gray the poet says "he was told," as beautiful a scene of rich and cultivated country as Yorkshire affords. "This place," writes Walpole, " is one of the very few that I really like. The situation, woods, views . . . are perfect in their kinds. "Gramercy for your intention," he afterwards writes to the Miss Berrys (1789) "of seeing Wentworth Castle. It is my favourite of all great seats. Such a variety of ground, of wood and water, and almost all executed and disposed with so much taste by the present earl. Mr. Gilpin sillily could see nothing but faults there. The new front, in my opinion, is one

of the lightest and most beautiful buildings on earth; and pray like the little Gothic edifice, and its position in the menagerie. I recommended it, and had it drawn by Mr. Bentley from Chichester Cross."

In the quadrangle of the house is a statue by Rysbrach of the Lord Strafford who refronted the house. Of the pictures here (which are numerous, but among them are many copies) the most important and inter-

esting are-

Tintoretto (according to Waagen, but here called Holbein), portrait of a monk: Lorenzo Lotto, a half-length male portrait, very excellent, inscribed "An. xlii. 1537" (here said to be by Giorgione, who died in 1511); Lucas van Uden (called Rubens), large landscape with figures; Walker or Sir P. Lely, portrait of Cromwell: Bartholomew de Bruun (marked Unknown), "a good though rather late specimen of this Cologne master; " Holbein (marked Unknown), Ecolampadius the reformer; Lucas de Heere, portrait, said to be that of Lady Eleanor Brandon, dau. of Chas. Duke of Suffolk, and Mary, dowager of France and sister of Hen. VIII.—this picture is, however, dated 1565: Lady Eleanor died in 1547;-Albano, Flight into Egypt; Unknown, portrait of Thomas, 1st Lord Wentworth, served in France in Hen. VIII.'s expedition in 1523, created Lord Wentworth of Nettleden in 1529. Lord Chamberlain and Privy Councillor to Edw. VI.; Unknown, 2nd Lord Wentworth (eldest son of 1st lord), Governor of Calais under VI. and Mary, surrendered Calais to D. of Guise, 1588; Antonio More (?) Sir Philip Sydney, fulllength; Unknown, but signed H. E., Mary Queen of Scots, dated 1563, age 24 (but the queen, born in 1542, was then only 21); Vandyck, Henry Danvers, Earl of Danby, served in France and the Low Countries: made President of Munster and Governor of Guernsey by James I., created

Earl of Danby by Chas. I. 1625: Earl of Strafford in armour, fine: John, Count of Nassau, half-length (fine); Vandyck himself with broad hat and feather (Chas. I., Chas. and Henrietta Maria, family of Chas. L. Lord Strafford and his Secretary, are copies); Zucohero, Earl of Essex: Sir Peter Lely, Margaret Lucas, the eccentric Duchess of Newcastle: Rubens, portrait by himself,—a replica of that at Windsor.]

At Barnsley the Lancashire and Yorkshire Rly. ends. A branch of the Manchester, Sheffield, and Leeds Rly, proceeds thence through a not very interesting country (abounding. however, in coal and collieries) to Wombwell, where it falls in with the main line of the same rly. running between Doncaster and Sheffield. The Dearne and Dove Canal is crossed by the rly. near the Stairfoot and Ardsley Stat., and at Aldham Junct. a branch of the South Yorkshire Rly. falls in rt. short branch crosses the country to the Silkstone Stat. on the rlv. between Penistone and Barnsley (see Rte. 44), and is chiefly used for the conveyance of stone and iron. The whole of this country is one vast colliery, and this branch line, as far as Worsborough, where Alex. Pope's mother, Edith Turner, was born, is accompanied by a branch from the Dearne and Dove Canal, the banks of which are lined with wharfs, and with coal, lime, chemical, and flint-glass

works.

At Wombwell the ch. has been rebuilt, with the exception of the chancel, which is E. Kag. and in a state of utter disrepair. The ground about the ch. is disgracefully kept. (1½ m. N. across the River Dove, is Darfield, where is a fine ch.—see Rte. 41.)

The stats. at Wath-upon-Dearne ("wath," A.-S., signifies a ford, and occurs frequently in Yorkshire) and

Mexborough Junct. (where the Mid-1 a most romantic effect in the morning land Rly, between Doncaster and dawn." It is accurately described Sheffield falls into the line rt.) are now passed. At the east end of the village of Mexborough is the Castle Hill. a fortified hill of the same character as others at Wincobank (Rte. 45), Laughton (Rts. 47), Tickhill (Rte. 47), and perhaps Coningsborough (see post). All have a circular or elliptic enclosure, with a high mound closely adjoining the dyke, or in the actual ring of it. It is difficult to say whether these are British or Saxon works; though Mr. G. T. Clark regards them as decidedly Saxon, and as always indicating the stronghold of some Early possessor. English Mexborough seems to be connected with the line of intrenchment running by Winco-(See Rte. 45). bank from Sheffield. The "Chateaux a Mottes," common in Normandy, greatly resemble these Yorkshire strongholds, and should be compared with them. They are enclosures-elliptical, round, and irregular-defended by earthen dykes and remparts, and without any trace of walls or stone-work. All have a " motte," or elevated mound.

Mexborough ch. has E.E. por-Here the valley of the Don is entered, and the scenery becomes very pleasing as we approach

Coningsborough Stat. The Castle, the fame of which is widely spread from its having been made the home Athelstane the Unready 'Ivanhoe,' and the scene of his funeral feast, rises on a wooded hill rt., about ten min. walk from the stat. (The keys, however, are kept at the village, on the other side of the castle.) Sir Walter Scott, writing to Morritt in 1811, whilst 'Rokeby was in contemplation (he seems to have had some intention of introducing Coningsborough in that poem), says that he "once flew past Coningsborough on the mail-coach, when its round tower and flying buttresses had | present owner, the Duke of Leeds.

in 'Ivanhoe,' where it is said that "there are few more beautiful or striking scenes in England than are presented by the vicinity of this ancient fortress. The soft and gentle river Don sweeps through an amphitheatre in which cultivation is richly blended with woodland; and on a mount ascending from the river, well defined by walls and ditches, rises this ancient edifice, which, as its name implies, was, previous to the Conquest, a royal residence."

The name Coningsborough, King's hold or "borough," may perhaps indicate that a royal fortress of some kind (probably of wood) existed on this site during the Saxon period; and the outer walls of the castle are apparently raised on an earthwork of the same general character as Mexborough (see ants). But in spite of all that has been written on the subject by earlier antiquaries, such as Grose and King, and by Sir Walter himself (in the notes to 'Ivanhoe'), we now know positively that no part of the existing remains is earlier than the Norman Conquest. keep tower, to which the circular form and the projecting buttresses give an unusual appearance, was no doubt the work of one of the earls of Warrene, in (perhaps) the latter part of the 12th cent. (It has sometimes been assigned to Hamelyn, Earl of Warrene, who died in 1202.) honour of Coningsborough was given by the Conqueror to his son-in-law, the great Earl of Warene, whose remains were discovered at Lewes in Sussex in 1845. In the hands of his descendants it continued till the middle of the reign of Edw. III. then passed to Edmund of Langley, Duke of York, and to his descendants. Elizabeth granted the castle and demesne to her cousin Lord Hunsdon; and it has since passed through many hands to those of its

The Castle crowns a natural knoll! above the Don, the summit of which forms a platform of rather less than an acre, and is encircled by the outer wall of the place. The entrance is from the village or S.W. side, by a narrow winding way between walls, flanked by 2 round towers. whole was surrounded by a deep fosse, the sides of which, especially on the N.E., are steeply scarped. At the N.W. angle, and forming part of the circuit of the outer wall, is the keep-tower, 86 ft. high. The basement walls are 15 ft. thick. The tower is circular in plan, and within is a perfect cylinder, of about 22 ft. diameter. Outside, 6 buttresses of enormous projection ascend above the summit as turrets, and give to the building the appearance of a polygon (compare Orford Castle in Suffolk). The lower stage or basement of the tower slopes outwards for strength.

The entrance is by a modern and steep flight of steps (the original means of access was no doubt of wood, and removable) to a door about 14 ft. above the ground, from whence a stair in the wall leads to each of the upper stories. The keep altogether consists of 3 stories (besides the dungeon), the first of which is on a level with the door. this again, and underground, is the dungeon, a domed chamber, accessible only by a hole in the dome. In the centre of this chamber is a small well, about 2 ft. diameter, 105 ft. deep, and lined with stone. (It has, however, been filled up.) wooden floors of every story have long been wanting, and the immense cylinder is now open from turret to foundation.

The first floor, reached through the door of entrance, is a plain, circular room, unlighted even by a loophole. A flight of 25 steps in the thickness of the wall, rt. of the entry, leads to the level of the second floor, which contains a good chimney,

with carved initials. Here is also a garderobe formed in one of the buttresses, and beyond again a small apartment in the wall, with a stone bench running round 3 sides, and a window. The fireplace in it is an excellent example, and the flat arch above it is filled with curiously joggled masonry. Near the entrance is a stoup for holy water. The third floor seems to have contained the principal or "lord's" apartment, with a fireplace, holy-water stoup near the door, and garderobe in the thickness of the wall. From this room opens the chapel (described in 'Ivanhoe, where Athelstane reappears to preside at his own funeral feast). From a charter of Earl Hamelin, temp. John, it appears that this chapel was dedicated to SS. Philip and James, and endowed with 50s. a year. to be paid from Coningsborough mills. It is 12 ft. long, 8 ft. broad in the centre, and 6 at each end, and about 16 ft. high. It is divided into 2 bays by plain circular shafts, which carry the ribbed vaulting; and in the eastern bay is a narrow loopholed window (formed in one of the buttresses) with zigzag ornament. the side walls of this bay are 2 piscing, and 2 small circular openings for light, filled with a quatrefoil. Another small room (perhaps assigned to the castle priest) opens l. of the entrance of the chapel.

The staircase continues through the wall of this story to what is now the top of the keep, with the buttress turrets rising above it. In the thickness of one of the buttresses is a well-built oven in perfect condition (there is an oven in a similar situstion at Orford Castle in Suffolk); and in two others are small chambers. The flue-vents from the fireplaces, sepsrated at the top by a thin stone, should also be noticed. The view from the top of the castle is very striking: but although iron rods have been placed for protection between the different having at the sides triple shafts stories, the ascent requires a good

head and some nerve. The mouth of the dungeon, fringed with grass and fern, yawns below, and the passage from one stair to another must be made along a narrow ledge which calls for wary treading. The ashlar work, inside and out, is very good, and the whole ruin is hung with wild flowers, harebells, and ivy. Near the keep is a sallyport in the wall, of curious construction, but now blocked up on the inner side.

Outside the castle walls is a barrow called the tomb of Hengist. Neither the death nor the grave of Hengist is mentioned in the 'Sax. Chron.' or by Bede; but Geoffrey of Monmouth, either by pure invention or by the adoption of vague British traditions, made this neighbourhood the scene of a battle in which Hengist is taken by Ambrosius, brought a prisoner into his own castle, and afterwards beheaded outside the walls by a certain "prelate" named Eldol. "laid him in the earth after the heathen law," writes Layamon, who, like Wace in the original Brut, and many a later chronicler, has followed Geoffrey throughout. The Norm. castle of the Warrenes was perhaps newly finished when Geoffrey of Monmouth's "history" was published (about 1138), and that Geoffrey's work at once became well known in this neighbourhood is clear from the words of Alured of Beverley, who says that whoever was ignorant of it " notain rusticitatis incurrebat." The name of Hengist was then perhaps first connected with the ancient barrow outside the castle. It is found at one other place in the neighbourhood—at Hengest-rein—the name of a belt of wood N.W. of Sprotborough.

Coningsborough Church (restored) is principally Norm. (lower part of tower and chancel-arch) and Trans.-Norm., and deserves a visit. Norm. work is perhaps of the same date as the castle. There is an unusual piscina at the E. end of the N. aisle, a good Perp. font, and a remark- earlier than the 19th or 14th cent.

able tomb of the 12th cent. (?) curiously carved with rude bas-reliefs. The porch is E. Eng. There are some early tombstones in the church-The church was given by William, the 2nd Earl of Warrene (died 1138), to the Cluniac Priory of Lewes, in Sussex, which his father The Cluniacs poshad founded. sessed it until the Dissolution.

A Roman road, running N., and marked by the names "Street" and "Street Lane," crossed the Don a short distance W. of Coningsborough. and before the junction of the river Dearne with the Don. The angle of this junction is known as the " Strafford Sands," and it was from this place-"street-ford," the ford of the Roman "Street," which gives name to the wapentake—that the great Lord Strafford took the title by which he is best known, although the Earldom was only granted twelve months before his death.

Before passing through a short tunnel, immediately beyond the stat., there is a very picturesque view of the castle rt., with the river (here crossed by a weir) in the foreground. Don is then crossed, and through a richly wooded country the train reaches

Sprotborough (Stat. on the Midland Rly., between Doncaster and Sheffield; the South Yorkshire trains do not stop here). The ch. is seen rt. The stat. is in the midst of deep cuttings in the magnesian limestone, here extensively quarried. Cliffs of this rock here border the river, and are very picturesque.

To most persons Sprotborough will seem a place of no very great interest. The Church contains some ancient portions; monuments to the Fitzwilliam and Copley families, some old screenwork and tattered flags, said to have been carried by Charles I.'s army. and a singular stone chair, with grotesque sculpture, which is not

Near the village is Sprotborough Hall, | cel, and aisles all under one roof, and the seat of Sir Joseph Copley, Bart., a large house built in the reign of Charles II., commanding a wide prospect over the river, which runs near the house on its S. side. It contains some pictures-portraits of Sir W. Waller; of Denzil Hollis; Commissioner-General Copley in the reign of Chas. I.; Chas. I.; Lady Digby, Vandyck; portraits by Rembrandt: 2 interiors of churches, P. Neefs; 2 views in Venice. Canaletti. There is a library containing some curious MSS., chiefly collected by Sir Godfrey Copley, the 2nd baronet, an early member of the Royal Society, and the founder of the "Copley Medal," one of its greatest distinctions.

The Copleys inherited this estate through an heiress of the great Yorkshire house of Fitzwilliam, of whom the present earl is the male repre-

sentative.

The Church of Sprotborough contains some fine tombs of Fitzwilliams The earliest Fitzand Copleys. williams are a knight and lady, temp. Hen. III. In the chancel is a good brass for Wm. Fitzwilliam and his wife, 1474. The principal Copley memorial is the monument of Philip Copley, temp. Eliz. There are some fragments of old glass. The stone chair has been already noticed. the midst of the village once stood a cross which bore an inscription recording the bygone hospitality of the place:-

"Whose is hungry and lists well to eate, Let him come to Sprotburgh for his meate; And for a night and for a day His horse shall have both corne and hay, And none shall ask him when he goeth

This cross was pulled down in 1520. At Cadeby, in the parish of Sprotborough, a small but very decorated ch. has been built by Sir is Hickleton Hatt (1994) decorated ch. has been built by Sir Hickleton is 7 m. from Doncaster.]

near York (see Rte. 1), but of a later

a bell-gable in the middle. It will hold about 120 people, but is said to have cost 60007.

In the porch of Barnborough Ch. about 11 m. W. of Sprotborough, one of the Cresscres, former lords of Barnborough, is said to have killed. and to have been killed by, a wild cat, which attacked him in a wood at some distance from the ch. battle continued as far as the porch. where it ended fatally for both. red tinge of the stone paving the porch (magnesian limestone) is said to be owing to the blood of the combatants, which cannot be removed.

The church itself contains the curious monuments of Percival Cresacre (living in 1455), and of his wife Alicia, died 1450. gravestone 9 strings of beads are so arranged as to form a cross. tomb of Percival Cresacre is between the chancel and the N. chapel. effigy in oak lies on it; and the front and sides are covered with rosary, the favourite device of the Cresacres, and with short inscrip-This is the Cresacre said to tions. have been killed by the wild cat, and the lion at the feet of the effigy passes, in local opinion, for that A wild cat was the crest animal. of the Cresacres, whose interest in Barnborough passed by marriage to the family of the great Sir Thomas More. Anne Cresscre, who married John More, son of Sir Thomas (see the picture at Nostel, Rte. 38), was, with her husband, buried in this The old house of church. Cresacres and Mores still remains.

2 m. N. of Barnborough, on the high road between Barnsley and Doncaster, is *Hickleton*; adjoining which Hickleton Hall (Lord Halifax).

Rt. of the line is Warmenorth. architectural style; with nave, chan- where Fox, the founder of the Quakers, preached in a meeting- | poet, who held the living from 1755 house which still exists. A little beyond a good view opens of Doncaster Church, with a foreground of tree-dotted meadow and the winding Don, and the train soon reaches

Doncaster Stat. (see Rtc. 1).

ROUTE 41.

LONDON TO LEEDS.

(North Midland Railway).

(6 through trains daily. The ordinary trains perform the distance in about 61 hours; the express in 4 hours 45 min., about the same time taken by the express on the Great Northern Rly, from London to Leeds by Doncaster-see Rte. 28.)

Leaving London from the King's Cross Stat. (see Rte. 1A) to Chesterfield. Here the line divides, one branch proceeding vid Sheffield, as described (Rte. 1A), the other on rt. direct to Rotherham, by which the Yorkshire border is crossed close to the stat. at

Woodhouse Mill. Here the rly. from Sheffield to Great Grimsby passes over our line, on a viaduct of 30 arches.

12 m. rt. is Aston. Aston is the residence of William Mason the burn.

to his death in 1797. Here he amused himself by carrying into execution, so far as the size of his grounds would permit, the principles of art laid down in his English Garden,' which he wrote at Aston. The garden remains nearly as he laid it out, with walks winding between trees and broad spaces of greensward, and openings here and there toward the distant hills of Derbyshire. In a summer-house is an urn and medallion to the memory of Gray, who often visited Mason "Aston's secret shade" is duly celebrated in a sonnet addressed by Mason to the Earl of Holderness in 1763 :--

" Here, as the light-wing'd moments glide I weave the bower: around the tufted mead In careless flow the simple pathway lead, And strew with many a rose the shaven

Mason was a painter and musician as well as a poet. He was Precentor of York; and is said to have greatly improved the Cathedral choir, as well as that of his own village, which became a model for the neighbouring churches. In the church is a plain memorial tablet for the poet, with a medallion placed there by his successor, Mr. Alderson. The Church (partly Norm.) was probably re-built by the Melton family, and contains a monument with effigies of Lord Darcy and his 3 wives. is some curious grotesque carving on the S. side. Aston Hall, long the seat of the Earls of Holderness, now belongs to J. Nerelst, Esq. 1

On the rt., about 11 m. beyond Woodhouse Stat., is Treeton Church (13th cent.), in which tradition asserts that Bradshaw the regicide was buried. He was, however, buried in Westminster Abbey, and was disinterred with Cromwell and Ireton, chiefly noticeable as having been to be hanged and re-buried at Tythree times, and then the Don, before 1857. They were buried here. reaching Masborough Stat. (for Rotherham).

(For the line hence to Swinton Junct., see Rte. 45).

At Swinton the South Yorkshire Branch Rly. from Barnsley to Doncaster (Rte. 40) crosses the line. 3 m. beyond, through the Cathill tunnel, 149 yds. long, we reach

Darfield Stat. Here is a fine Church, worth a visit. The ch. and village stand on a ridge overlooking a great stretch of wooded country much broken into hill and valley, and abounding in coal and collieries. The ch. is for the most part very late Dec., but has some E. Eng. (?) portions in the choir. These are the chancel-arch (slightly stilted), and 1 bay on the S. side. The rest of the choir (which is of 3 bays) is late Dec. or early Perp. (The windows of the S. aisle in both nave and choir have flowing late Dec. tracery.) (The glass is modern.) In the pier between the choir-arch and the 1st bay N. there is a large square hagioscope. On the S. side the thickness of the pier is pierced by a rood-loft stair, now used as an access to the pulpit. At the E. end of the S. choir aisle is a good monument with effigies of a knight (probably one of the Bosviles of New Hall, in this parish) and The knight lady, temp. Rich. II. wears a collar of SS. There is some good carvings on the bench-ends in the N. aisle. The nave is very late Dec., with clerestory lights filled with flowing tracery. The old seating (17th cent.) exists throughout, and has some carving. font is Perp., and a very good and wide Perp. arch opens to the tower. which is massive Perp. There is a tradition that the bells were brought from Beauchief Abbey, near Sheffield.

In the churchyard an obelisk is raised to the memory of 189 men and

The rly, crosses the river Rother in the Lundhill Colliery, Feb. 19.

2 m. rt. of the rlv., between Darfield and the next station (Cudworth), lies the village and manor of Great Houghton, from which place Lord Houghton receives his title. The ancient manor-house of Rhodes family here, within whose walls the great Earl of Strafford wooed and won his bride, and which was afterwards defended against the Parliamentarians, has become a prosaic village alchouse.

From the next stat..

Cudworth, a branch line runs to Barnsley (see Rte. 40) 3 m. S.W. Part of the town is visible from this Hence for several miles the rly, runs by the side of the Barnsley Canal, and passes the Yorkshire summit level 202 ft. above the sea.

The next stat. is

Royston and Notton. Rougton Church (2 m. S.W. of the stat.) was given at the beginning of the 13th cent. to Monk Bretton Priory. ch. (restored), which is fine and worth notice, is late Dec., and much resembles that of Darton (Rte. 40). The open roof is Perp. There are chapels N. and S. of the choir, and parallel with it. In the tower is a priest's chamber. There is a monument for Sandford Neville of Chevet (died 1672)—a slab of black marble supported by 4 boys in white marble. whose streams of tears are sufficiently (When Dodsworth visited this ch. in 1621 he noticed in one of the windows a plough drawn by four oxen, driven and led by angels. Below was the inscription-

> " God speed the plough, And send us corne enough.")

The church of Felkirk, 11 m. S.E. of the station, has Norm. portions.

A little beyond the Royston and boys who were killed by an explosion | Notton Stat. the Chevet viaduct of 13 arches, and the Chevet tunnel 688 yards long, are passed.

Chevet Hall is a house, temp. Hen. VIII., with the inscription on a beam—"Thys hows was mad by John Nevyll, knyght, and dame Elizabeth, hys wyf, in the yere of ouar God 1529." In the park, from which good views are commanded, are some very fine beeches.

Rt. is Walton Hall, the seat of the late C. Waterton, Esq. (see Rte. 38), and the spire of Wakefield Ch. is

seen l. At

Oakenshaw Stat. the line from Wakefield to Pontefract (Rte. 28) is passed. (Rt., 2 m. is Nostel Priory, Rte. 38).

At the Oakenshaw Stat. the North Midland Rly. is not more than 1½ m. from the Leeds and Manchester Line (Rte. 38), which runs through Wakefield; but owing to an intervening ridge of high ground, the 2 lines do not meet until within a short distance of the Normanton Stat.

An excavation of considerable depth in the rock, which furnishes good building-stone, conducts to the

Normanton Junct. Stat. This is a large, important, and bustling stat. and point of junction belonging to the Midland, the N. Eastern, and the Lancashire and York. Rly. Companies. The stat. stands within the most of a Roman camp, only partly traceable on the river Calder.

All Saints' Church, Norm. and Perp., the tower 1629, contains the graves and monuments of many Yorkshire families—Torre, Favells, Mallet, Cockells, and an altar-tomb to John Treston.

At Normanton passengers for York, for Hull, and for Leeds are separated, and are forwarded in distinct trains. About & m. N. of this stat. the rly. to Leeds diverges l. from that to York. The river Calder is crossed, and at

[Yorkshire.]

Methley Junct. the branch line (Lancashire and Yorkshire) from Pontefract falls into the N. Midland. (For the line hence to

LEEDS JUNOT. see Rtc. 28.)

ROUTE 42.

LEEDS TO SELBY, BY MILFORD, JUNCTION.

(North Eastern Rly.—9 trains daily in 36 min.)

Leaving Leeds from the New Stat. the line soon crosses the little stream of Killingbeck, a feeder of the Aire. (Rt. is Killingbeck Hall, and near it, on the E. side of the beck, are some curious earthworks, consisting of a number of terraces cut in the hill-side one above another. They run out as they approach level ground, and one is now used as a road.)

Cross Gates Stat. () m rt is Whitkirk Church, in which Smeaton the engineer is buried; near it is his old home, Austhorpe Lodge, and another 1 m. S. Temple Newsam. For all these places see Rte. 28—Exc. from Leeds.)

1 m. beyond Cross Gates, and near the Manston Stat., the rly. crosses a well-defined line of Roman road, here called "the Street," and running N. in the direction of Pampocalia (see Rtc. 43).

2 1

2 m. S. is Swillington Church, early Dec. with a Perp. tower. The Rev. H. Robinson, the vicar of Leeds who was ejected in the days of the Commonwealth, is buried in the chancel. He was rector of Swillington after the Restoration. From

Garforth Stat.,

Church Garforth, the antiquary may visit the singular mounds of Barwick-in-Elmete, a village which The rly. from hes about 3 m. N. Leeds has been passing through the ancient district of Elmete, a name which seems to have been given in the earlier Saxon period to the great tract of wooded country which extended E. of Leeds as far as Sherburn and Tadcaster. The magnificent elm-trees (from which the name "Elmete" is said to have been derived), and the rich "greenwood" which still overshadow the roads and hill-sides of this district, are sufficient to prove that the ancient forest here must have been unusually thick and stately. The Roman road of the 5th and 8th Itinera ran through passing from Castleford (Legiolium) to Tadcaster (Calcaria). This road, still called the "Roman ridge," and very conspicuous, passed through the village of Aberford (it forms the main street of the village) about 2 m. E. of Barwick.

On the way from Garforth to Barwick, the woods and park of Parlington (Col. F. C. T. Gascoigne) are The little river Cock, passed rt. which rises on Whin Moor N.E. of Leeds, and at first takes a southerly course, here winds northward, and after many twistings passes the battlefield of Towton, and at last falls into the Wharfe near Tadcaster. The village of Barwick stands high. The ch. (which has been restored) has some Dec. portions, and in the W. front are 2 canopied niches, one containing a figure of Sir Henry Vavasour, a benefactor.

2 m. S. is Swillington Church, Perp. In the centre of the village rly Dec. with a Perp. tower. The stands a maypole.

The remarkable earthwork, however (opposite the ch. W.), is the great point of interest at Barwick. It consists of a conical mound, known as "Hall Tower Hill." It is about 30 ft. high, and covers a base of about 200 ft. diam. The summit is slightly hollow, and has a diam. of 40 ft. This mound stands in a circular ditch, from 6 to 12 ft. deep: and the circle is placed within a platform of irregular figure, surrounded by a bank of earth which. to the S., where the platform is 15 ft. wide, rises about 8 ft. above its level. Beyond the bank is a ditch. On the N. side was another large circular area, enclosed within a bank and ditch, and called Wendell Hill. This is now very obscure. Tradition asserts that this place was a residence of Edwin of Northumbria, who had certainly conquered Elmete (then held apparently by a British chieftain) before his conversion by Paulinus: and the earthworks here are so unlike British or Roman that there seems much reason for assigning them to this early Saxon period The larger enclosure (circ. 620). may have contained the buildings in which the chieftain and his household lived. The object of mound is not so evident. "It could hardly," says Mr. Wright, "be intended for defence, because it was cut off by strong entrenchments from the larger enclosure, which was sufficiently strong in itself. It has not the appearance of having ever supported buildings. It was not wanted as a place for watching the approach of enemies, for the position of this stronghold is so bold that you overlook the country as well from the entrenchments below as from the top of the mound." It is possible. he adds, that it may have served as the gathering-place of the "Thing" (like the Tynwald hill of Man. and The tower is the green mote-hills of Galloway), the

general assembly for administering to the clergyman of the parish a series iustice summoned by the king or the ealdorman. (Compare also the intrenchments and mounds at Mexborough (Rte. 40), Wincobank (Rte. 45), and Tickhill (Rte. 47). Some remarkable banks and ridges (called in one place "Becca banks") should be studied in connection with the Barwick mound, though they do not They follow immediately join it. the N. side of the Cock beck toward Aberford, and extend again on the S. side of the stream in the direction of Lotherton. The village of Aberford has a ch. dedicated to St. Richard, Bp. of Chichester, who died in 1258.

[1] m. N. of Barwick is Kiddal throughout the country east Hall, long the residence of the Ellis family. It is of the 15th cent. The hall has a canopied sideboard at the E. end, and a large bay window with much carving, and an inscription recording its construction by Thomas Elvs and Anne his wife in 1501. mysterious tramping is constantly heard through the passages of Kiddal Hall, and is laid to the account of the Cavalier John Ellis, who was killed here by a party of Parliamentary soldiers.]

[About 1] m. S. of Garforth Stat. is Ledstone Hall (T. Broadhead, Esq.), for 2 generations the seat of the Earls of Huntingdon; it is beautifully situated, overlooking the Vale of Aire. It is a large mansion of the time of James I., and once belonged to Thomas Wentworth, Earl of Strafford.

Ledeham Church, near Ledstone Hall, contains a monument-with marble effigies of all 3,-to Lady Eliz. Hastings, daughter of Theophilus Earl of Huntingdon, a pious and benevolent lady, who died in 1739, aged 58, and her 2 sisters. The inscription is by Barnard, master of the grammar-school at Leeds, who wrote the Life of Lady Elizabeth. She left

of instructions as to his conduct, still affixed to a pillar in the church, and which, in the words of Whitaker, "savour of a spirit of lay episcopacy, to which devout and honourable women are wont to addict themselves.

11 m. farther S. is Kippax Park, an Elizabethan mansion, the seat of J. Bland, Esq., representative of an ancient family here.]

Beyond Garforth the line crosses the Roman road running N. to Aberford and Tadcaster, and soon reaches

Micklefield Stat. Here. Garforth, the magnesian limestone is extensively quarried for building purposes; and beyond Micklefield, N. of the rly., adjoining Huddlestone Hall, is Huddlestone quarry, stone from which was used in building the choir and presbytery of York Minster. (In 1485 the chapter obtained a lease of this quarry for 80 years. See Rte. 1, the Minster, § xv.)

Teazles are much grown throughout "Elmete" for the use of the Leeds clothiers. By fields of them, and through a varied, pleasing country, the train reaches the stat. at

Milford Junct., on the line of the Great Northern Rly. (see Rtc. 2). Thence a branch line runs by

SELBY STAT. to

Hull Terminus (Rte. 5).

ROUTE 43.

LONDON TO HARROGATE, BY TAD-CASTER AND WETHERBY.

For this route, as far as the Church Fenton Junct., see Rtes. 1 and 2. From Church Fenton a branch line of the North Eastern Rly. runs to Harrogate by Tadcaster and Wetherby. There are 8 trains daily. The distance is performed in somewhat less than 1 hour.

From Church Fenton the Harrogate line diverges N.W., and, after crossing the Cock Beck, skirts Grim-

stone Park, and reaches

Stutton Stat. From this stat. (or from that of Church Fenton) the battle-field of Towton may be visited.

Grimston Park, between Stutton Stat. and the Wharfe, was bought from Lord Londesborough, in 1872, by John Fielden, Esq., of Dobroyd Castle, near Todmorden, at a price The Park is bounded of 240,000l. on the N.E. by the river Wharfe, and is pleasantly varied and wooded.

The village of Towton lies about 2 m. W. of Stutton, and the battlefield is again about 2 m. S. of the village, nearer the village of Saxton. For the battle of Wakefield and the events which preceded the battle of Towton, see Rte. 38. On the 28th of March, 1461, there had been a skirmish at Ferrybridge on the Aire (Rte. 2), and Lord Clifford had been (The enkilled a few hours later. gagement in which he fell occurred at Dintingdale, about 11 m. E. of Saxton village. According to the family tradition, his body was flung into a pit with many others.) The following day (March 29) the Lancastrians, whose main body had advanced through Tadcaster to Towton,

Edward's forces on the high land N. of Saxton, and the great battle of Towton was fought-the bloodiest and most fatal fought on English soil since Hastings. It was in fact a battle of extermination; and orders were given on either side to give no quarter and to take no prisoners. The fight began during a heavy fall of snow, which drove in the faces of the Lancastrians, who had drawn up their forces N. of a depression in the ground called " Towton Dale," which was thus made to form part of their defence. The Yorkists were opposite. The accounts of the engagement are very confused, but it appears that Edward at first ordered his archers to shoot a volley of flight arrows (those used for great distances) and to retire a little. The volley was returned by the Lancastrians, but the snow prevented them from calculating the distance, and their arrows fell short. Fauconbridge, who commanded Edward's archers in the van, then ordered them to throw back their bows and draw their The armies met. and the swords. battle became a furious conflict of personal strength and braverv-"sore fought," says Hall, "for hope of life was set on side on every part " until the Lancestrians finally fled in the direction of Tadcaster, and Edward remained victorious. generally said that the battle lasted for 10 hours, but one account (published by Hearne) asserts that it began at 4 o'clock on the evening of Saturday, March 29, was continued through the night, and was decided at noon on the following day (Palm Sunday) by the arrival of the Duke of Norfolk with reinforcements for Edward.) The loss of life was enormous, even allowing for the (no doubt) extreme exaggeration which makes the number of killed between 30,000 and 40,000. Nearly half the Lancastrians perished. The Earl of having failed to defend the passes Northumberland and 6 barons were of the Aire, were attacked by killed, and the Earls of Devon and

Wiltshire taken prisoners. castrian Lord Dacre was shot, says they reached the river, to which they tradition, in a field called the "Nor (north) Acres," by a boy out of a "bur-tree" (elder-tree). Hence the local rhyme :--

" The Lord of Dacres Was slain in the North Acres."

The Dukes of Somerset and Exeter escaped to York, where Henry and Margaret received the fatal tidings and retreated at once into Scotland. Edward himself advanced to York. where the Earls of Dover and Wiltshire were beheaded, and their heads placed above Micklegate Bar in place of those of Edward's father, the Duke of York, killed at Wakefield (Rte. 38), and of his supporters. (By far the most minute and accurate account of Towton Field will be found in Brooke's 'Visits to Fields of Battle in England of the 15th Century.' London, 1857.)

The field of battle is a tract of tolerably level ground, rising gently from the village of Saxton, and sloping (or rather terminating in broken ground) W. toward the river Cock, which winds round it. The fight no doubt extended over the whole ground between Saxton and Towton; but the main battle took place in what is now a large meadow near Towton Dale Quarry, about 1 m. S. of Towton village. The grave-mounds, toward the southern end, indicate the scene of the hardest and closest struggle. A thicket of wild roses, white and red, is growing in the meadow, perhaps planted as a memorial after the battle, but more probably the work of Nature herself -impartial alike to York and Lancaster. The meadow itself is sometimes called the Bloody Meadow, and is remarkable for producing rich i rank grass. A mound, possibly of British origin, crests the bank above the river, which, at the time of the battle, was swollen by wintry rains | teresting portion of it. The view and snow. The Lancastrians are from Hazelwood is very extensive.

The Lan-1 said to have retreated in order until descended by a very steep road bevond Towton Hall. The steepness of this road, and the consequent crush of men, disorganized them. They broke and fled on all sides. So many perished in the water, that the rest crossed on the bodies of their comrades. The scene of this battle in Shakspeare's 'Henry VI.' (Pt. II. act ii. sc. 3) is altogether unhistorical. Clifford was killed before the fight at Towton, and nearer Ferrybridge. Hen. VI. was at York.

> The village of Saxton partly occupies the site of a large square Roman camp. The ditch on the W. side is now a public road. A great number of those killed in the battle were buried in a large trench on the N. side of Saxton Church: and in 1848. during the construction of a vault, their remains were exposed. Outside the ch. (which has a Norm, portal and some E.E. portions, but is of small architectural interest) is the monument of Lord Dacre, who fell here, a plain altar-tomb, with muchdefaced inscription. Others of the leaders are said to have been buried here, but there are no memorials of them.

Many relics have been found from time to time on the battle-field. In the Duke of Northumberland's museum at Alnwick is a battle-axe with handle of black oak, found in the bed of the river, and long used by the wife of the miller who found it, for "breaking sugar."

(On high ground opposite Towton, 21 m. from Stutton, and nearly 4 from Tadcaster, is Hazelwood Hall, the ancient seat of the Vavasours. A part of the house is old, but the chapel, which was once the parish ch., and contains some monuments of the Vavasours, is the most inand both York and Lincoln cathedrals, i 60 m. apart, can (it is said) be seen from it. It was from their manor here that the Vavasours contributed the stone of which great part of York Minster is built (see Rte. 1, Minster, Their most ancient 68 9 and 29). quarry is that known as Jackdaw's Craq, or Thievesdale (the latter name is significant, and indicates that "broken men" may have often found good shelter within its recesses), about 1 m. W of the Stutton Stat. It was probably from this place, which is interesting and beautiful, and well deserves a visit, that the Romans procured the magnesian limestone for their buildings at Calcaria (Tadcaster) about 2 m. distant. mounds of various sizes, made by working the rock, give the whole quarry the appearance of mountain country in miniature

From Stutton a run of 3 m. brings

the train to

Tadcaster Stat. (Inn: Londesborough Arms). P. H. Tadcaster is now a small and uninteresting town of about 3000 Inhab. In posting days, when the main road from Leeds to York ran through it, it was a place of considerable bustle; and the Roman stat. Calcaria (on the site of which the existing town is built) here commanded the chief and lowest passage of the Wharfe. The tide flows to within a short distance below the town, and the Roman road of the 2nd, 5th, and 8th Itineraries crossed the river at Calcaria on its way to York. (Another road diverged from this line shortly before reaching Tadcaster, and, crossing the Wharfe at St. Helen's ford higher up, proceeded to Isurium (Aldborough). No Roman remains exist at present in Tadcaster, although numerous coins and other relics have been discovered here; but 1 m. below the town, a 3 m. N. of Tadcaster, is believed ! few yards above the confluence of the mark the site of St. Hein's foundation. little river Cock with the Wharfe, is and possibly preserves her namea small bridge (Kettleman's Bridge) | "Hein-læg"—"Hein's territor

of 1 arch (over the Cock), which has been considered Roman. "The arch is constructed without a keystone, and springs from square pier walls. blocks of stone are neatly squared. about twice as large as in the wall of Eboracum; on several are the mason marks. The parapets are modern. The arch has yielded a little upwards. so as to be rather elliptical."—Phillip. It seems very doubtful, however. whether such antiquity can be claimed for this bridge, and Mr. Brooke ('English Battle-fields of the 15th Century,' Towton) has pointed out that similar bridges are not uncommon in some parts of Yorkshire. and are not very ancient. A truck leading to this bridge from the S. is called the "Old Street."

The Roman Castrum gave its name to the "Kaelca caestir" of Bede, the Anglian or Danish "Tadcaster." There was a mediseval castle at Tadcaster, from the ruins of which the bridge over the Wharfe was built early in the last cent. During the Civil War, Fairfax, with only 900 men, was attacked here by the Marquis of Newcastle with 4000. The struggle lasted all day, and at nightfall Fairfax drew off toward Selby

The Perp. Church of St. Mary is the only building of interest in Tadcaster, and the tourist need hardly delay his journey to visit it. It is throughout of late character, with square-headed windows in the nave and clerestory. It was restored 1877.

A monastery was founded, according to Bede (H E., iv. 88). at "Kaelcacaestir" (no doubt Tadcaster), by a certain Heiu, who, he tells us, was the first woman who congcrated herself to a monastic life in Northumbria.

The village of Healaugh, shat

There are remains of ancient founda- ! tions N.W. of the cha and a very early tomb-slab, with a cross marked on it (the head formed by 5 circles), and a name, "Madug," was found The churches of Healaugh and of Wighill, 1 m. W., have Norm. portions. Healaugh Manor, 1 m. S. of the ch., occupies the site of a priory of Augustinian canons, founded in 1218 by Jordan de St. Maria and Alice his wife.

Leaving Tadcaster, the village of Newton Kume, with a picturesque old ch. and the remains of a castle, is passed rt. A fine avenue of trees leads to Newton Hall (W. Wickham Wickham, Esq., belonging to Col. Fairfax). The house, faced with a Corinthian colonnade, contains some interesting Fairfax portraits. The rly. then crosses the Wharfe. (A little above the rly. bridge is St. Helen's Ford. by which the Roman road, here called Rudgate (compare the Rudstone near Bridlington, Rtc. 13), crossed. Here, in Leland's time, stood St. Helen's Chapel. This has now disappeared, but its site is indicated by a range of rock, close to the river, in which, in a hollowed recess. St. Helen's Well still exists and is still venerated, as the shreds and scraps of linen hung on the surrounding sufficiently attest. This bushes "well-worship" was formerly common throughout the northern counties, and still flourishes in Ireland. (The St. Helen here commemorated is of course the Empress Helens, the mother of Constantine.)

At Thorp Arch, the next Stat., we reach a very picturesque part of the river, which here flows under steep limestone cliffs. The ch. of Thorpe Arch has Norm. portions. On the S. bank of the Wharfe, 1 m. from the stat. (an omnibus meets the trains), is the village of Boston, where is a Spa of some pretensions. (Spa Royal reached. Make direct for the house.

a great posting-house, and much frequented by foxhunters. are large gardens.) The neighbourhood is very pleasant, and contains many place of interest. Lodgings (in the long village street which lies on the high road between Wetherly and Tadcaster) are plenty, and the quiet and accommodation of the place make Boston a good centre for 2 or 3 days. It is about half an hour's distance by rail from Harrogate, and all the places mentioned in this route are readily accessible in the same manner.

Boston Spa (saline) was discovered There is a pump-room. in 1744. with hot and cold baths. The ch. here is modern. There is much wood round Boston, and very pleasant walks around the Wharfe. From Jackdaw Crag there is a very picturesque view across a bend of the river. Boats may be hired at the Spa house for excursions or fishing. fish, not very abundant, are trout, grayling, and pike. It is possible to take a boat about 1 m. down the stream.

About 2 m. from Boston is Bramham, passing by Clifford. The ch. at Clifford is modern, and there are here a Roman Catholic chapel (the architecture of which is far better than that of the Anglican ch.) and a nunnery. Outside the village are 2 large flax-mills. Bramham Church has a Norm. tower, but is of no very great interest.

Bramham Park (George Lane Fox, Esq.) lies 1 m. S. of the village. For seeing the gardens and grounds an order is required either from Mr. Lane Fox, or from his agent in the village of Bramham. Pedestrians may enter the park by the Lodge of the College - a large school, with modern Tudor buildings and then. keeping along the wall (not entering the College gates), the park is Hotel-large and scrambling-once which is not habitable. It was

large and important, and was built by Lord Bingley in the reign of Queen Anne, who shortly after its completion honoured the mansion with a visit. Bramham, however, was greatly injured by fire a few years ago, and since that time the house has not been restored; but the gardens and grounds are well kept up, and are very excellent examples of old French taste, with tall hedges, allees vertes, and cabinets de verdure. The park contains about 2000 acres: the gardens and dressed grounds, 120. The long vistas through avenues and allees are wonderfully fine and picturesque, and the place altogether is one of the grandest in Yorkshire. The park is well varied, and contains an avenue of enormous beeches, known as Lord Bingley's Walk, and leading to an enclosure of about 400 acres (within the park), called Blackfen. Here 12 avenues of noble trees diverge from an obelisk in the centre. In the park are the kennels of the Bramham Hunt. A branch Roman road crosses the park, but (as will be seen by a reference to the Ordnance map) all this country is full of ancient roads, of Roman adoption if not of Roman origin, which fall into the main "streets" passing through Tadcaster to York, or from Tadcaster to Ilkley (Olicana). of these roads, leaving the village of Bramham in a direction nearly due W., points towards Bardsey (3½ m. distant); a little S. of which (near Scarcroft Mill) is the probable site of a small Roman stat. mentioned only by the geographer of Ravenna as Pompocali. This very name, in the shape of "Pampycallo" is said to have been retained to the present day. At any rate, numerous Roman relics have been found in the neighbourhood. Near Scarcroft Old Hall is a small Roman camp, and at Scarcroft Mill are considerable earthworks on the summit of a steep, rocky bank, washed at the foot by a stream that flows northward towards the Wharfe.

Bardsey Church, chiefly Norm.. deserves a visit. There is an enriched Norm. portal, and the chancel arch and N. nave arcade are Norm. The S. arcade is Trans. Norm. The tower also is partly of this date. No of the village is a mound called Castle. Hill, with a large earthwork peculiar in form, and perhaps marking the site of the stronghold of the Saxon Lord of Bardsey. Soon after the Conquest, Bardsey passed to the Mowbrays, and was granted by them to the monks of Kirkstall.

At Bardsey Grange William Congrees the dramatist was born in 1672. The house was then the residence of his mother's uncle. His birth here is duly recorded in the register.

Harewood Park (Rte. 29) is rather more than 3 m. from Bardsey. The

walk is rather pleasant.

Wetherby Stat. Here is little to delay the tourist. It is an important agricultural market-town, with a good Bridge over the Wharfe, from which the view is very picturesque, and is one of the many places on the main northern roads which have lost their importance since the introduction of railways. The church was built 1840. and enlarged 1877-80. From Wetherby the famous Couthorpe Oak may best be visited; and the 3 miles' walk or drive between the Wharfe and the Nidd (near which the oak stands) is well worth undertaking for a sight of which is generally allowed to be the largest oak in England.

1. of the road to Cowthorpe, about 1 m. from Wetherby Station, is the village of Kirk Deighton, where the Church deserves a visit. It has Norm. (N. side of nave) and E. E. (S. of nave) portions, and a very fine Perp. tower. At the end of the N. nave-aisle is a wooden tablet, with the Ten Commandments in an earlier version than that of 1603. On one side are the arms of Roos; on the

other some elaborate marshallings. In 1772 a branch fell which was 80 Below each shield is a landscape. The date is 1576, and the tablet is supposed to have been given by the Lord Roos of that date as a thankoffering of his safe return from France, the landscapes representing scenes in which he took part during the Tournay and Therouenne expedition. The whole must, however, have been repainted. The rude woodwork of the S. porch-door deserves notice. In the vicarage garden is a very remarkable cherry-tree, the girth of which, at 1 ft. from the ground, is 14 ft.; the height of the tree is 76 ft. The growth is very graceful and regular, and in spring the tree is a perfect hill of snowy blossoms. It is a small black cherry, something like the Hamp-shire "merry." The tree is well shire "merry." seen from the ch.-yd.

Rt. of the road to Cowthorpe, Inquanthorps Hall (- Montague, Esq.) is passed. Mr. Montague is the proprietor of the venerable Cowthorpe Oak, the age of which has been estimated by Prof. Burnett at 1600 years. It stands on a croft adjoining a farmhouse near Cowthorpe Church, and its true measurements are—circumference at 5 ft. from the ground, 36 ft. 3 in.; close to the ground, 60 ft.; extent of the principal branch, 50 ft. 6 in.; girth close to the trunk, 10 ft.; height of tree, including decayed wood, 43 ft; height of vigorous wood, 33 ft. 6 in. The tree contained 73 tons of timber, and the diameter of its hollow close to the ground is 11 ft. The trunk is quite hollow, but the branches, the largest of which are supported by wooden props, still cover much ground and bear much foliage. top branch (leader?) fell about 180 vears since. In 1718 a branch fell which extended 90 ft. from the trunk, and contained 5 tons and 2 ft. of wood. Before this fall, the oak which lies about 1 m. E. extended its shade over half an acre.

ft. in length, and was found to contain upwards of 5 tons of timber. The height of the tree in 1776 was 85 ft. Mr. Montague possesses a table made from the wood of a fallen portion: and the box in which the freedom of the city of York was presented to Lord Brougham was made of Cowthorne The soil in which the tree stands is a deep, rich, light loam, resting on fine clay. The tree is engraved in Hunters edition of Evelyn's 'Sylva.' The circle occupied by the oak, where the bottom of its trunk meets the earth, exceeds the ground-plot of the Eddystone lighthouse, which was confessedly based on the growth and proportion of an oak-tree stem. There was a good brass in Cowthorps Church, the Perp. tower of which is built into the nave. and near the altar is a carved structure of oak, supposed to be an Easter sepulchre!

The pedestrian should cross the Nidd (which is here close at hand). and visit Hunsingore Ch., the spire of which will serve as a guide. On the l. bank of the river (close to the bridge by which he will cross), is a large earthwork called the "Castle." It consists of an oblong mound of some height and length, having one portion toward the E., higher than the rest, and on this is a squared enclosure. A deep hollow E. of the mound leads up to the village of Helsingore. The mound, like so many in Yorkshire, may very likely be of Saxon date, but some stone building seems to have been raised on it. Its history has yet to be traced. Hunsingore Church, beyond (Kirk. of Sleaford, architect), is of very good early Dec. character, with an apse, and a western tower and spire. The stained windows are by Ward and Hughes. Church and vicarage were built at the cost of J. D. Dent, Esq., of Ribston Hall. The stat. beyond Wetherby is

Spofforth, formerly one of the most ancient possessions of the Percys in Yorkshire. It was granted to William de Percy by the Conqueror, and the chief Percy residences in the county were here, at Topcliff, Wressel, and at Leconfield. There are considerable remains of Spofforth Castle, at the end of the village farthest from the stat. Henry de Percy obtained a licence to crenellate in 1309 (2nd Edw. II.). The plan is a parallelogram with the hall in the centre. The castle, with other Percy possessions, was forfeited to the Crown after the rising of the 1st Earl of Northumberland against Henry IV., and his defeat on Bramham Moor (1408).It soon, however, was restored to the Percys, but was defaced by the Earl of Warwick and Lord Montacute after the battle of Towton (1462), in which 2 of the Percys were killed. It was afterwards repaired, and was finally dismantled in the time of the Commonwealth. ruins are of 3 periods. The lower room under the hall is Trans.-Norm. of the end of the 12th cent. building opening from the S. end of this Norm. room, containing the kitchen, a vaulted chamber between it and the hall, and a solar over it, is of the 14th cent., as the hall itself evidently was originally. but this was destroyed and rebuilt in the 15th cent. The remaining buildings form one side of a quadrangle, the other sides of which may be traced by remaining fragments. It is now the property of Lord Leconfield, lord of the manor.

The Church of Spofforth, Perp., rebuilt except the Tower, 1855, possessed a chancel until it was pulled down by the rector (on whom the charge of repairing it fell), in spite of vigorous remonstrance. The rectory of Spofforth is in the gift of

a year. In the ch. is a memorial for "Blind Jack of Knaresborough" (see Rte. 20), who died in the parish.

There is nothing calling for notice between Spofforth and Harrogate Stat. (See Rte. 20.)

ROUTE 44.

HUDDERSFIELD TO SHEFFIELD, BY PENISTONE AND WORTLEY.

(Lancashire and Yorksh. Rly.-5 trains daily. The line between Huddersfield and Sheffield is traversed

in about 11 hour.) Passing through the long tunnel (see Rte. 37) which begins at the Huddersfield Stat., and crossing the Lockwood viaduct, the pretty valley of the Colne is seen rt. before the train reaches the

Lockwood Stat. From the next.

Berry Brow Stat., the camp or "Castle Hill" at Almondbury is easily reached (Rte. 37).

Honley Stat., Honley Ch. and village are seen rt. (Scotgate Head. in the parish of Honley, is pointed out by tradition as the furthest point reached by Charles Edward at the head of the Highlanders in 1745. It need hardly be said, however, that the Prince really advanced as far as Derby. But all this district was Lord Leconfield, and is worth 1500l | thrown into great confusion at that time, and it is possible that some wilder above the village, where the halt of the Scottish troops may have taken place here.) The tower on the hill in front is "Cook's Study," a modern building of no interest. Farnley spire rises above the wooded hill l., and soon the train reaches

Brockholes Funct. [Rt., up the very pretty wooded valley of the Holme, a short branch line runs to Holmfirth. with a stat. halfway at Thongsbridge. The valley is full of cloth-mills and "clothing" villages. (At Meltham, 2 m. W. of Thongsbridge, are the large linen and thread manufactories of Messrs, Brook. They are probably the most extensive thread factories in the world.)

Holmfirth, a large manufacturing village high up in the valley, is best known as the scene of the terrible catastrophe of the 5th of February, 1852. About 1 o'clock on the morning of that day the Bilberry reservoir, in the hills nearly 8 m. above the village, burst its embankments, and 86,248,000 gallons of water, amounting in weight to about 300,000 tons, rolled down the valley. carrying everything before it. The chimney of Digley mill was the only one left standing in the valley. 81 persons perished, property to the value of nearly 200,000l. was destroved, and 7000 hands were thrown out of employment. A subscription was at once opened for the relief of the sufferers, and 70,000l. was collected, the greater part from the immediate neighbourhood. Such great reservoirs are formed in the hills all along the S. border of Yorkshire, partly for the service of the mills in the valleys, and partly for the watersupply of the great towns. bursting of the Holmfirth reservoir is by no means a solitary accident; that which occurred in Sheffield in 1864 was far more serious. (See post.)

ley is very picturesque. It becomes ornaments inserted at intervals. It

stream descends from Holme Moss (1859 ft.), a continuation of Stanedge. The Yorkshire border is carried along its summit.

There is little to notice between Brockholes Junct. and Penistone. There are stats, at Stockmoor, at Shepley, and at Denby Dale. Shepley the country becomes barer and less interesting. At Denby Dale a high and long viaduct is crossed, commanding a rather pretty view up and down the dale. youd it, a wide view extends northward, over broken ground.

Enter the Manchester, Sheffield, and Linc. Rlv.

Penistone Junct. Stat. is a large village with steel-works of Cammell and Co; the cloth-mills and trade are gone. (The cattle market here is the most important in the district.) stands high and bleak, in a country of no great interest. It has, however. a Church (restored in 1863) which well deserves a visit. nave is Dec., with arches of which the deep mouldings descend on the caps of the piers in an unusual man-All is plain, owing to the ner. extreme hardness of the local gritstone of which the ch. is built, but a very striking effect is produced by these deeply cut mouldings. W. tower arch, of similar character. fine and lofty, was opened to the ch. during the restoration. roof is Perp., very good panelled oak, with richly carved bosses and The aisle windows are brackets. triangular - headed. with simple tracery. The E. window, early Dec., with plain intersecting tracery, descends unusually low, and is filled with modern stained glass. The W. tower is lofty, of Dec. character, and at once excites attention on entering the village. The W. door has a The scenery of the Holmfirth val- double hollow moulding, with leaf of Gunthwaite, and to Wm. Fenton,

murdered in Spain, 1855.

In the parish of Penistone (which is a very extensive one, reaching to the Derbyshire border) the ancestors of William Wordsworth resided (probably as small holders) from a very early period, until, in the last century, the poet's grandfather passed into Westmore-land. Various "Wordsworths" ap-Dear on different occasions in transactions personal and public connected with the parish of Penistone: and it was for one of them that the carved almery at Rydal Mount was made in 1525.

Among the bare hills, neither picturesque nor attractive, which extend S. of Penistone, are two remarkable intrenchments, marked "camps" on the Ordnance Survey. but of similar character with the earthworks at Thornborough near Ripon (Rte. 22). They are circular, with an external ditch, and with openings opposite each other N. and S. The circumference is about 900 ft. This range of high moorlandthe extreme eastern portion of the so - called "Pennine" chain—the "backbone of England," gives birth to the River Don (as it is usually named on modern maps. Camden calls it Dan and Dane; and Phillips ('Mountains and Sea Coast of Yorkshire') insists that Dun is the true form. It is at any rate so pronounced in the district through which it flows). The etymology is not clear, though Danube, Don, or Tanais, and Eridanus, or Po, are no uncertain cousins of the Yorkshire stream. "Ultimately we may probably refer Don to the conjectural Sanscrit word udan, water, which contains the root und, to wet. Hence the Latin unda."—Taylor. The Etherow, running through Cheshire, and the Wrongsley, a branch of the Derbyshire Derwent, rise on the same watershed, but take different courses.

contains monuments to the Bosvilles The Don itself has a double source. the Don and the little Don, both rising in Penistone parish, and uniting a little below Worsley. At Penistone the river is not very attractive. but its banks become striking as we descend.

> From Penistone Junct. the rlv. passes rt. to Manchester, and l. to Barnsley.

- (a) The Manchester line crosses the valley behind Penistone Ch. by a viaduct, and has stats. at Hazlehead Bridge and Dunford Bridge before it passes out of Yorkshire. On the moorland near Dunford Bridge (the "bridge" is thrown across the headwaters of the Don or Dun) Lord Fitzwilliam has a shooting-lodge. Immediately beyond the latter stat. the rly. passes into Lancashire through a funnel in the "Pennine" chain, said to be the longest in Great Britain. It measures 3 miles and 20 vards. The one side of it for a single line of rails took 7 years (1838-1845) to complete, and cost 200,000L It has 5 vertical shafts, the highest 579 ft. deep, and the whole length. excepting about 1000 yards, is lined with masonry. The rock through which it passes is hard millstonegrit. (For the rly, beyond, to Manchester, see Handbook for Lancashire.)
- (b) The short Barnsley line of 7? m. has stats, at Silkstone and Dodworth, and passes through one of the richest coal-fields in England. coal, which is raised in all directions about Silkstone, belongs to the "ironstone coal" of the "Middle Coal Section." (The ironstone coals belong to the lowest beds of Middle Coals, and rest on flagstone rock (such as that of Elland, Rte. 39), dividing the Middle from the Lower Coals. The last rest on millstone-grit.) The scenery throughout this district is of great beauty. Wide valleys, in which

between ranges of low hills, richly cultivated, contrasting sharply with the limestone districts of the W., and the sandstone of N.E. Yorkshire. Taking these as the 2 most picturesque districts of the county, this tract, lying between Barnsley and Sheffield, stands next to them, and offers a third, and very distinct, class of scenery. Turner represents the limestone cliffs of Swale and Wharfe. The beautiful moors and valleys of Cleveland have yet perhaps to find their artist; but this old forest country is the stronghold of Creswick. who was born at Sheffield, and whose pictures faithfully reproduce the oaks and beeches of his native district.

Silkstone Stat. is about 1 m. from the village, which is seen in the valley below. The ch. tower is a good guide, and the ch. itself is well worth visiting. There are large Collieries between the stat, and the village, which is mainly occupied by men who work in them. In spite of this, however, the country here is very pretty, and much wooded. In descending the hill from the stat. the woods of Cannon Hall (W. J. W. Spencer Stanhope, Esq.) are seen opposite. In the hall is kept a bow called "Little John's," which has been preserved at Cannon Hall for 170 years, and was formerly at Hathersage Hall in Derbyshire, one of the owners of which place succeeded to the estate at Cannon Hall. (There is a tradition that Little John was buried at Hathersage.) It requires a power of 160 lbs. to draw the bow to its full-only 60 lbs. is the power used by men at present at archery meetings. On the bow is the date 1715, and the name of Colonel Naylor, who in that year strung, and shot a deer with it. It has never been strung since.

Silkstone Church (All Saints) has

oaks grow to a considerable size, lie | work in the chancel, part of which was rebuilt by Salvin, under whose direction the whole ch. was restored. The nave piers and arches are late Dec., and have above them a clerestory of small square-headed lights. (Remark the bases of the piers, which vary.) The tower arch has been opened, and the capitals of its piers have ornaments like those on the W door of Penistone. The aisle windows are sharply pointed, with 3 lights in each: foliated, but without tracery. The timber roofs of nave and aisles are Perp. and very good, with bosses of carving. The piers of the chancel arch are perhaps Norm. (The arch they carry is Dec. like the others.) On the N. side of the chancel is a Norm, arch, under which the organ is now placed. On the S. side, with Perp. arches opening to it, is a chantry now belonging to the Beaumonts of Bretton, and formerly to the Wentworths of the same place. It contains a fine monument, with effigies in white marble, of Sir Thomas Wentworth and ladv. a faithful follower of Charles I., 1675. There is some good modern glass by O'Connor in the E. and W. windows. The ch. also contains a memorial tablet for Joseph Bramah, the wellknown mechanician, and the inventor of the famous lock, who was born on a farm of the Earl of Strafford's, in this parish, and died Dec. 1814. On the exterior of the ch. each bay is divided by a buttress pierced at the top by a gurgoyle (as in the E. transept of York Minster, Rte. 1), and having a small half-arch below. These mark the very late Dec., almost Perp., character of the work. Two gurgoyles on the N. side, representing a friar and a pilgrim, with a collar of shells, are The tower is Perp. and curious. The ch. of Silkstone, which fine. was originally of Saxon foundation. and is no doubt the mother ch. of all this district, was given soon a late Dec. nave, and some Norm. after the Conquest by Swein Fitzfract, in whose hands it continued until the Dissolution. Darton Ch. (between Barnslev and Wakefield) is of the same general character as the churches of Silkstone and Penistone. which resemble each other. The 3 form a very distinct group.

(A rly., only used for the conveyance of coal runs from Silkstone to the line between Barnsley and Wake-Another line, "the Darley field. Main and Old Silkstone Branch. connects Silkstone with the South Yorkshire Rly. between Barnsley and Mexborough,)

Passing the stat. at Dodworth (a large village rt.), the train soon reaches Barnsley (see Rte. 40).]

After leaving Penistone, the rly. crosses the main stream of the Don, the banks of which become rocky and picturesque as it makes a sweep rt. of the line, opposite Thurgoland, a village surrounded by collieries, and having a considerable manufacture of iron wire. Beyond is

Wortley Stat. On the hill, L, is the ch. and village of Wortley, where are collieries, iron and Steel works. 50 cottagers enjoy under Lord Wharncliffe about a rood of land, rent free, Small premiums are given each. annually to those whose houses are cleanest, and whose land is best cultivated. The Church contains a monument by Flaxman.

Wortley Hall (Earl of Wharncliffe), near the village, is a modern Italian mansion, containing a few family portraits, including those of Lady Mary Wortley Montagu, her husband, and son, in a Turkish dress: 4 pictures representing their reception by the Sultan: portraits of the 1st and 2nd Lord Sandwich, and of Lord Cardiff (a Bute title), by Reynolds. The house is charmingly situated in a fine park, and the pleasure grounds

Ailric to the Cluniac monks of Ponte-I condition. The lordship of Wortlet has been in the hands of a family of the same name from the period of the Conquest to the present time.

Beyond Wortley the line enters Lord Wharncliffe's picturesque woods. through which it is carried for about 4 m. (The woods, which contain Wharncliffe Crags and the "Dragon's Den" (see post) are open to the public on Mondays, Wednesdays, and Saturdays. They are accessible from either Wortley, Deep Car, or Oughtv Bridge stats. A long day may be spent in them with great delight, or they may be walked through (a distance of 4 or 5 miles) from Wortley to Oughty Bridge, or in the opposite direction. The most striking scenery (at the Lodge and the Dragon's Den) is near the Oughty Bridge end.)

The valley of the Don, seen rt. of the line, is here very picturesque. At

Deep Car Stat. are chemical works and numerous coke-ovens, which are supplied with a poor coal raised in the neighbourhood. The coke is sent to Sheffield for the use of the cutlers. Opposite Deep Car the noble woods of Wharncliffe sweep down to the margin of the river, which is here joined by the little Don (see ante).

Oughty Bridge Stat. is 11 m. from Wharncliffe Lodge, a pleasant walk. crossing the bridge and descending by a road through the wood.

Wharncliffe is a grand wild chase. extending along the steep rocky ridge that here rises from the L bank of the Don. It abounds in deer, and among its woods are a few venerable caks of great size and antiquity. On a high point toward the E. end, overlooking the valley of the Don. Wharncliffe Lodge was built in 1510 by Sir Thomas Wortley. as an inscription once to be read on a large stone close to the lodge (it is now illegible) testifies. This ran. " Pray for the saule of Thomas Wrytand gardens attached are in high telay Knight for the kyngys bode to Edward the forthe Rychard therd Hare the VII. and Hare VIII. hows saules God perdon wyche Thomas cawsyd a loge to be made hon this crag ne mydys of Wanclife for his plesor to her the hartes bel in the vere of our Lord a thousand cccc. x." Sir Thomas, according to an ancient account of the Wortleys, "was much given to showtinge in the longe bowe," and "had much delite in huntinge." His hounds were so famous that the "king of Scots" desired to have some of the breed. At the lodge he built in Wharncliffe Chase "he did lye for the most part of the grease tyme; and the worshipful of the country dyd ther resorte unto hime, havinge ther with hime pastime and good cheare." A curious local tradition asserts that Sir Thomas destroyed a village for the sake of improving his "chase" between Wharncliffe and Penistone; and that as a punishment he became distracted before he died, and "belled" (bellowed) like a stag. The lodge was considerably enlarged at a later period, and Lady Mary Wortley Montagu lived in it for some time after her marriage. (It is sometimes asserted that her eccentric son was born here; but this is incorrect. See Hunter's S. Yorkshire. ii. p. 321.) Many of her early letters are dated from this lodge; and long afterwards, when describing the magnificant view which stretches away from the Palace of the Popes at Avignon, she wrote of it as "the most beautiful land prospect I ever saw, except Wharncliffe." The best point of view is from a sort of natural terrace extending along the top of the hill. From the "table-rock" on this terrace, the eye ranges over an expanse of foliage and tree-tops (chiefly oaks, which grow here like weeds) across the vale of the Don-here little more than a mountain torrent, and not as yet the "gulphie Don" of Milton -backed by round, billowy mountains. Under special lights, when

"The sun o'er purple moorland wide Glids Wharncliffe's wood, while Don is dark below "—Eliot—

this scene is very fine and striking. Eastward the towers of York and Lincoln are said to be visible in clear weather.

The terrace extends along the rocks known as Wharncliffe Crags, and below it is the Den of the famous "Dragon of Wantley" (Wantley is a corruption of Wharncliffe), to whom

"Houses and churches
Were as geese and turkeys;
He ate all, and left none behind—
Save some stones, dear Jack, which he could
not crack,
Which on the hill you will find."

"Old Wortley Montagu," wrote Walpole, "lives on the very spot where the Dragon of Wantley did, only I believe the latter was much better lodged."

The Dragon's Den, as it is called, is a shallow recess in the rocks, beneath the terrace, about 2 yards deep and 4 long. Masses of broken rock rise above and round it, with yew and ash, and luxuriant fern springing from between the fissures. "The savageness of the scene," writes Walpole, "would please your Alpine taste: it is tumbled with fragments of mountains that look ready laid for the building of a world. . . . I am persuaded it furnished Pope with this line, so exactly it answers to the picture—

" 'On rifted rooks, the Dragon's late abode."

Taylor "the Water Poet" was entertained in this cave by Sir Francis Wortley in 1639. "Hither," he says, "the keeper brought a good red deere pye, cold roast mutton, and an excellent shooing hora of hanged Martimas biefe, which cheer no man living would think such a place could afford; so, after some merry passages and repast, we returned home." But he makes no allusion to the dragon; and indeed, it seems probable that the

cording to that, the dragon was destroved by More of More Hall, an old house on the opposite side of the river Don, conspicuous from Wharncliffe. More provided himself with a suit of armour at Sheffield-

"The spikes all about, not within but with-

Of steel so sharp and strong, Both behind and before, arms, legs, and all

Some five or six inches long."

The ballad is said to have been a burlesque, referring either to a contest between a wicked attorney who had stripped 3 orphans of their inheritance, but was ruined in a lawsuit which he had undertaken against More of More Hall: or to a most formidable drinker, who was at length fairly drunk dead by the chieftain of the opposite moors. But many stories resembling it are scattered over the N. of England, such as those of Sir John Conyers of Sockburne; the Worm of Spindleston Heugh; the worm of Lambton; Kempion in the 'Border Minstrelsy,' and many others. Whether all these record the destruction of real monsters, and whether, as Ellis suggested to Scott, the dragon here was "some wolf or other destructive animal, finally hunted down by More of More Hall," must remain uncertain.

Ellis's letter to Sir Walter Scott, in which the Dragon's Den is described, was written from Wortley Hall in October, 1803. The love of Sir Thomas Wortley for "hearing the hart's bell " greatly delighted Sir Walter, who makes frequent allusion to it. In the opening sentences of 'Ivanhoe' he refers to the den of the Dragon of Wantley as one of the relics and recollections that give a charm to "that pleasant district of merry England watered by the river Don:" and the magnificent forest scene in which Gurth and Wamba first appear, may serve as well for a description of the stately oaks of | town.

ballad is of more modern date. Ac- | Wharncliffe as of any other fragment of ancient Sherwood.

The visitor should wander along the edge of Wharncliffe (or "Holy Birch Edge," as it is called) at least as far as Deep Car Stat.

At the next stat..

Wadsley Bridge, the near approach to Sheffield begins to be seriously The din of falling hammers felt. and the smoke of tall chimneys extend as far as this village, which is chiefly inhabited by cutlers. short stage of not quite 3 m. brings the train to

(262 m. from Huddersfield, 177 m.

from London)

SHEFFIELD JUNCTION STAT.

RAILWAY STATIONS, VIADUCTS.

(a) Victoria Stat., Furnival Boad, Manchester, Sheffield and Lincolnshire Rly.; Great Northern Rly.; South Yorkshire Rly.

The Manchester, Sheffield and Lincolnshire Rly, crosses the Wicker on a viaduct of 1 large and 2 smaller arches, connected with piers and arches, by the side of the Don.

(b) Midland Stat., Old Haymarket and Sheaf Street.

The main line of Midland Rly. from Chesterfield passes under part of the town in a tunnel, and is carried across the Don valley on 5 arches Another Viaduct of 40 arches carries it across the Don valley to a junction with Rotherham Rly., near Brightside Stat.

Within the precincts of Sheffield and its suburbs, there are stations at Attercliffe, Beauchief and Abbeydale, Healey, Station Road, Broughton Lane, Grimesthorpe, and Tinsley Road.

Post and Telegraph Office, Old Haymarket, corner of Commercial St. Pillar-boxes in all parts of the

Sheffield (Pop. of township in 1881, | here were famous all over England 284,410; in 1801, it was 44,755).

Inns: Victoria, adjoining the stat. of the Manchester, Sheffield, and Lincolnshire Rly., best; large and comfortable. In the town are the Royal, the Angel, and the King's Head.

Sheffield, with the exception of Leeds, the largest and most important town in Yorkshire, is beyond all question the blackest, dirtiest, and least agreeable. It is indeed impossible to walk through the streets without suffering from the dense clouds of smoke constantly pouring from great open furnaces in and around the town. Yet Sheffield stands in a highly picturesque situation, at the confluence of the Don and the Sheaf (a river descending from the high moors of Derbyshire and giving name to the town); and 3 smaller streams—the Porter, the Loxley, and the Rivelin-join either the Don or the Sheaf within the precincts of the town, and are made to do "waterservice" by moving grindstones and tilt - hammers. Thus Elliott "Corn-law Rhymer," a native of Masborough, near Sheffield, writes of "Five rivers, like the fingers of a hand." Horace Walpole, writing to Montagu in 1760, describes Sheffield with great truth as "one of the foulest towns in England in the most charming situation." "One man there." he continues, amusingly enough in the presence of the enormous manufactures of the same class now carried on in the town, "has discovered the art of plating copper with silver. I bought a pair of candlesticks for two guineas that are quite pretty." The discovery was made by Thomas Balsover in 1742.

Sheffield, a great Railway Centre, is the great mart and manufacturing place of Cutlery in England. Iron the rude knives or "whittles" made the ironstone of the neighbourhood

in Chaucer's time-

" A Sheffeld thwytel bare he in his hose:" and these maintained their reputation till the days of Elizabeth, when the Earl of Shrewsbury (1575) prea case of "Hallamshire sented whittles" to Lord Burleigh. Arrows were also made here, and at the battle of Bosworth the Earl of Richmond's men were supplied with Sheffield arrows of a better form and make than had hitherto been manufactured. Toward the end of the 16th cent. certain refugees from Holland-

"They whom the rod of Alva bruised,"-

skilled in working iron and steel took refuge in Sheffield, and were protected by the Earl of Shrewsbury. But throughout all this period the trade, in Lord Macaulay's words. was "subject to such regulations as the lord and his court-leet thought fit to impose," and little advance was made. "The more delicate kinds of cutlery were either made in the capital, or brought from the Continent. It was not indeed until the reign of George I. that the English surgeons ceased to import from France those exquisitely fine blades which are required for operations on the human frame."-Hist. Eng., i. ch. 3. During the 19th cent., however, the advance in skill of workmanship, in enterprise, and consequently in population, has been enormous, and Sheffield now "sends forth its admirable knives, razors, and lancets to the farthest ends of the world."—Ib. The situation is especially favourable. Coal is abundant all around, and formerly the woods supplied charcoal, and the rivers the water-power for tilt-hammers, &c. It is often asserted that the water of Sheffield has special efficacy in tempering steel, but this is a fiction. It depends upon abounds in the neighbourhood, and the skill of the workmen. Neither is

suitable for steel making. Swedish | early as 1682, when many peers were charcoal-iron is the best, and it is imported accordingly. Next to this is the iron made from hæmatite ores of Cumberland, Westmoreland, Antrim, and Bilbao. Sheffield, however, does possess some natural facilities for steel making and working that are peculiar. The millstone-grit beneath and around it supplies the material for the grindstones so largely used in the manufacture of cutlery. and "ganister," a peculiarly refractory material admirably adapted for lining melting-pots, &c., is found so abundantly on the spot that it not only supplies all the local demand, but is

largely exported.

The Company of Cutlers was incorporated in the reign of James I. (1624) by an act "for the good order and government of the makers of knives, sickles, shears, scissors, and other cutlery wares in Hallamshire." and was under the control of a master. wardens, searchers, and assistants. Their duties consisted in maintaining the reputation of Sheffield wares by examining into the quality of goods made, and allowing their marks to be affixed only to such as were of approved excellence, to prevent their trade "falling into disrepute by making and selling unworkmanly and deceitful wares;" they also administered the laws respecting masters and apprentices. The company and Master Cutler, however, were stripped of the chief part of their authority by the Reform Bill, and their funds are considerably reduced since the cessation of apprentice fees and other branches of their monopoly. Their annual feast, however, it need hardly be said, is still, like a Lord Mayor's festival, one of those public occasions on which statesmen and politicians find an opportunity for discussing public events. Some of Mr. Roebuck's most remarkable speeches were made here. The "feast," which is given in Cutlers' Hall by the Master Cutler on his in-

present at it.

The manor of Hallam, which Sheffield now represents, belonged at the period of the Conquest to the great Earl Waltheof, beheaded in 1075 for his share in a rising against the Conqueror. It gave name to the surrounding district of "Hallamshire." which originally comprehended the parishes of Sheffield, Ecclesfield, and Handsworth, but which now represents a wider tract, embracing all the villages in which cutlery-work is (So " Howdenshire, carried on. "North Allertonshire," "Richmondshire," are the districts surrounding those towns over which the jurisdiction of their lords anciently extended. Yorkshire is in effect an agglomeration of smaller shires.)

Hallamshire was granted to Roger de Busli, who is recorded as its lord in 'Domesday.' It passed from him to the De Lovetots and the Furnivals. from whom, in 1406, the estates came by marriage to the Talbots, Earls of Shrewsbury. A castle was certainly existing here in the reign of Henry III., and had probably been built by the first Norman lords of Hallam. A stately manor-house was built, 2 m. from the castle, by the 4th Earl of Shrewsbury, and was completed early in the reign Hen. VIII. Of the castle, which stood at the angle formed by the junction of the Sheaf and the Don.

no fragment remains.

Of the Manor-House only a small portion, which is, however, interesting as having been occasionally occupied by Mary Queen of Scots during her long captivity in Sheffield. This fragment of the ancient manor-house was restored, 1873, by the owner, the Duke of Norfolk. contains a small apartment known as Queen Mary's Chamber," having a richly-decorated ceiling, embossed with rose, pomegranate, and fleur-delys ornament, of arabesque design, stallation, had become important so and with the heraldic charges of the

Talbots. A turret-staircase leads from it to a watch-tower and flat roof. which command an extensive view of the eastern part of the town and In the manor Wolsey was received by the Earl of Shrewsbury after his disgrace, and remained here 18 days. He died in the abbey at Leicester 5 days after he left Sheffield. In the Castle Queen Mary of Scotland passed 12 years of her captivity, strictly watched by the stern Earl and Countess, her keepers. "I have hur sur inoughe," he writes to Elizabeth, "and shal keepe hur for the comyng at your Majesty's commandment, ether quyke or ded, what soever she or anny for hur inventes for the contrary; and as I have no doute at all of hur stelynge away from me, so if any forsabull attempts be gyven for hur, the gretest perell is sure to be hurs." Mary was first sent to Sheffield in 1570, and finally left it for Winfield in 1584. During her stay here she was twice allowed to visit Buxton; and on one occasion the rooms she inhabited in the castle were so violently shaken by an earthquake that, wrote the Earl, "I douted more her faleing than ner goinge." She was allowed to ride forth in the neighbourhood under strict supervision.

During the Civil War Sheffield Castle was garrisoned for the king by the Earl of Newcastle, who left Sir William Saville in it as governor. It was attacked and taken by the Parliamentarians in August, 1644, and was afterwards slighted and dismantled. Before the war it had passed by marriage, with the Hallamshire estates of the Talbots, to the Howards; and in 1648 all this property, which had been confiscated by the Parliament, was restored to that family, and still belongs to the Duke

of Norfolk.

Except St. Peter's Church, the public buildings of Sheffield are of little interest, and the town has received less consideration and orna-

ment of late years than any other of the great manufacturing towns in Yorkshire; but the stranger who cares for such matters should not leave the town without visiting a steel furnace; a grinding-mill for scace as well as small articles; and one of the large depôts of outlery.

It should be said that the authorities of the town are careful in providing such open spaces for health and recreation as may be attainable. The large Weston Hall estate, on the N. of the town, was bought (1873) at a large price, to be converted into a public park. The Norfolk Park, in the neighbourhood of the Manor House, has been well laid out, and commands a fine view of Sheffield, when the wind carries the smoke in an opposite direction.

*St. Peter's, or the parish Church, stands in an open churchvard near the centre of the town. It is a cruciform building of 14th and 15th centuries, its chancel (late Dec.) and nave (Perp.), with a tower and crocketed spire rising at the intersection. After suffering several barbarous alterations in recent times, it underwent a thorough restoration, completed 1880, at a cost of 20,0001., of which one half was given by Mrs. Thornhill Gell : and 2500l. by Mrs. Parker, to raise a S. transept as a memorial to her husband, a physician of Sheffield. N. transept has been thrown out the nave extended 35 ft., and a new W. front erected, including a 6-light window and recessed porch beneath Plaster-roof, galleries, and high pews were swept away, and the result reflects credit on the liberality of the citizens of Sheffield. The nave has lofty Perp. piers, with battlemented The four piers supporting capitals. the central tower are earlier, and are remarkable for their small caps.

More interesting than the building itself, however, are the monuments in the Sirewebury Chapel, at the S.E. end of the chancel, founded by the

house) in the reign of Hen. VIII. His monument is placed under the arch which divides the chapel from It is an altar-tomb. the chancel. with effigies of the Earl and his 2 Countesses, the 2nd of whom, however (in spite of the inscription round the tomb), survived her husband, and was buried at Erith in Kent. Earl is in armour, with coronet, mantle of the Garter, and George. The Countesses wear heraldic dresses. All their figures are in alabaster, and are unusually good. Against the S. wall is the monument to the 6th Earl: erected during his lifetime. He was the "keeper" of Queen Mary, and was present at her execution. The long inscription was composed by Foxe, the compiler of the 'Book of Martyrs,' an honour which was perhaps thought due to the Earl for his services in the Protestant cause. The effigy, in armour, partly gilt, lies on a rolled mattrass, with the feet resting on a talbot-"the talbot ever true and faithful to the crowne." Below is a sarcophagus with bands and lions' heads. At the sides of the monument are talbots supporting banners. Much gold and colour remain throughout, and the whole work deserves special notice as one of the very finest examples in England of its period. The plain tomb in the centre of the chapel is probably a cenotaph, and is thought to have been the first design of the 6th Earl for his own monument.

In the chancel is a monumental bust of the Rev. Jas. Wilkinson. vicar, died 1805. It is by Chantrey, and is said to have been his first work. Another monument, also by Chantrey, is for Sir Thos. Harrison (died 1818) and his wife Elizabeth (1833). This is one of the later works of the sculptor, but is not very successful.

At the door of the chancel, in

4th Earl (the builder of the manor- | from Sheffield), who is supposed (with whatever truth) to have been the executioner of Charles I. Walker was a person of considerable standing in the neighbourhood, and was at all events a violent republican, and the author of a book entitled 'Vindicise contra Tyrannos.' said that at one time a warrant was issued for his apprehension, and that he was obliged to conceal himself in the village of Handsworth.

There are many other churches in Sheffield, owing their existence to munificent private subscribers. The town has increased so greatly since 1840, that additional church accommodation had become imperiously necessary, when, in 1863, the Abp. of York made a stirring appeal to the inhabitants. It was nobly responded to. Many thousands were subscribed at once. The sites of fresh churches were chosen, and in 1866 the first of these new churches at Brightside was built and endowed at the cost of Sir John Brown. IIt is dedicated to All Saints, but is commonly known as "John Brown's Church," and is finely situated, overlooking the Atlas works which he established, and for the employés in which the church was mainly erected. It was consecrated by the Abp.]

The Roman Catholic Church of St. Mary, in Norfolk Row, is a good modern building, completed in 1850 (architects, Weightman and Had-The chancel is richly ornafield). mented. The roodscreen and lof: were designed by Pugin.

The Cutlers' Hall. Church St. (built 1823, enlarged by a fine hall about 1865), is a Grecian building no very striking appearance externally. It contains a few portraits and busts; among the latter those of the Rt. Hon. J. Parker and J. S. Buckingham, the first members returned for Sheffield, which was 1700, was buried William Walker unrepresented in Parliament before of Darnall (a village about 3 m. the Reform Bill; besides one of

Montgomery the poet, by Theophilus | Pot Square (named from crucibles Smith of Sheffield. Of the portraits, the most interesting is that of the Rev. Joseph Hunter, the historian of Hallamshire. In the larger hall the annual banquets are held.

The Corn Exchange was built 1881. at the cost of the Duke of Norfolk. A Hotel forms part of the building.

The Market, opened in 1851 (cost, with site, about 40,000l.), is spacious and convenient: it deserves a visit. Fronting the Meat and Poultry Market (opposite High St.) is the "Elliott Monument," a sitting figure of the "Corn Law Rhymer" (see post), in bronze, by Burnand,

In Norfolk road, on a part of the Park of the old Manor-house, stands the Shrewebury Hospital, founded by Gilbert, 7th Earl, and completed 1673, in pursuance of his will, by the Duke of Norfolk. It was originally in the centre of the town, but removed hither 1827. The present edifice is a handsome Gothic struc-It forms 3 sides of a square, including a chapel, 36 dwellings for poor pensioners, and a chaplain's re-Near it, on an eminence sidence. planted with trees, is a monument to the memory of those (339) persons who died here of cholera in 1833.

In Barker Pool is the Albert Music Hall, a spacious modern building, erected at a cost of 40,000l., and containing a fine concert organ by a French builder.

In the Music Hall, Surrey St., is the Public Library of 7000 vols. The Free Library of 35,000 vols. is also in Surrey St.; and in the School of Art, in Arundel St., there is a small Museum of the Literary and Philosophical Society, who hold their meetings in the building. The Commercial Buildings, a Grecian edifice, in High Street, include a subscription News-гоот.

A good News-room exists in the Athenæum, George St.

or melting "pots"), in the centre of the town, is an open space.

The Frith College, a handsome building, corner of Bow St. and Leopold St., erected at a cost of 20,000%, endowed in great part by members of the Frith family aided by other citizens, is intended for the promotion of Scientific and Technical Education. It contains large Lecture Hall, laboratories, and class rooms.

The Botanical and Horticultural Garden, about 14 m. from the marketplace (1 hour's drive-fare 1s. 6d.), will well repay a visit. An order of admission must be obtained from a member. To reach it, the High St. and other thoroughfares stretching up the hill are traversed, and, leaving behind manufactories and warehouses, you emerge into a quarter composed of villas and country houses, in small gardens. At this elevation you have surmounted the smoke which envelopes the lower town, and look down upon the vale of the Porter, hereabouts still rural and pretty, though shrouded at its lower extremity, like that in the vision of Mirza, by a sea of thick vapour. Near the gardens stands the Wesleyan Proprietary School, a handsome Grecian building, with central portico, destined for the education of about 200 boys, children of Wesleyans, who are very numerous in Sheffield, having 12 chapels, of which several are somewhat imposing buildings.

Lower down, on the slope of the hill, is the Collegiate School (Church of England). It is a neat Gothic building.

The opposite slope of the valley beyond the river Porter is occupied by the General Cometery, partly formed in a quarry cut in the hillside. Montgomery the poet is buried here, and over his grave is a bronze Public Baths in Glossop Road. statue designed by Bell the sculptor.

The Barracks, on the outskirts of t the town (between the Penistone road and the Languett road), were completed in 1850, and contain accommodation for a regiment of cavalry and a regiment of infantry, besides drill and parade grounds,

The Firth Park, opened Aug. 16, 1875, by the Prince and Princess of Wales, is named after Mr. Mark Firth, the steel manufacturer, who presented 35 acres to the town. stands on the Sheffield and Wakefield road, between Grimesthorpe and Shire Green, 21 m. from the centre of the town. It is well laid-out onundulating ground, well-wooded on one side and commanding fine views of the valley, in which are the works of Sir J. Brown, Cammel, &c., and through which runs the Midland Rlv. Also of the wood and hill of Wincobank (Rte. 45), which may be conveniently visited from here. This park is well appreciated by the multitude of workers on this side of the town. and has supplied a want that was sorely felt in summer time.

There is another small park attached to the Western Museum, which contains the nucleus of a technological and general collection intended to illustrate the local industries and

natural productions.

St. George's Museum, founded by Mr. Ruskin, at Upper Walkley (take the Hillsbrough tramcar from bottom of Snig Hill to Greaves St., then walk or drive up a steep hill by the Walkley Road) is at present (1882) in a small house in a garden commanding magnificent views; but a large and more suitable building will be built for them. Mr. Ruskin's gift includes his fine collection of silicious minerals, drawings by himself, photos of Venice, and some rare books, devoted by their proprietor to public instruction. They are crowded in one room, and therefore ill displayed, He has placed them here on an emivisit them shall for the time be removed from the smoky town, and contemplate the natural beauties which the prospect displays.

Perhaps the most imposing distant view of Sheffield is obtained from

the village of Crookes.

Sanderson, Bishop of Lincoln. was buried here, 1587; and here Buchan practised, and wrote his 'Domestic Medicine.' Mrs. Hofland, author of 'The Son of a Genius:' the Rev. Jos Hunter, the able historian of Hallamshire and South Yorkshire: T. Creswick, R.A., the landscape artist (born here 1811); and W. S. Bennett, the musician (born 1816), are all natives of Sheffield. Like most of the wealthy manufacturing towns, Sheffield was a stronghold of Puritanism. Bagshaw of Hucklow, called the Apostle of the Peak. Daniel and Samuel Clark, Jollie and Wadsworth of Attercliffe, all connected with this district, are well-known names.

Closely connected with Sheffield was James Montgomery, the poet, born et Irvine in Ayrshire, Nov. 4, 1771. His father was a Moravian minister. In 1792 Montgomery came to Sheffield as assistant to Mr. Gales, proprietor of the 'Sheffield Register,' afterwards called the 'Iris,' and remained here till his death in 1854. His chief poems are 'The Wanderer of Switzerland,' 'The World before the Flood.' and 'The Pelican Island.' Elliott, the "Corn Law Rhymer." was born at Masborough in 1781. He afterwards settled in Sheffield. and embarked in the steel business. His Corn Law Rhymes' first made him known, but his most interesting poems are those in which he describes the scenery round Sheffield. Sir Francis Chantrey was born (April 7, 1781) at Norton in Derbyshire, about 4 m. from Sheffield. After some attempts at other occupation, he was apprenticed to a carver and gilder in Sheffield: but his innence, in order that the students who dentures were soon cancelled, and he

began here on his own account, first as a portrait-painter, and then (1804) as a sculptor. His first bust remains in St. Peter's Ch. (see ante). Chantrey died in 1841, and was buried in Norton charchyard.

The Steel Manufactures of Sheffield are of 3 distinct kinds. Cutlery-knives, razors, scissors, &c.; this is the old and staple trade of the place: (2) Larger forgings in steelsuch as steel rails for railways, steel bells, &c.: and (3) Workmen's and engineer's tools-files, saws, &c. Of the 1st. Messrs. Joseph Rodgers's Works and Show Rooms in Norfolk St. will supply the visitor with the best examples; and if he take an introduction, or can otherwise obtain permission, he may here see the whole process of manufacture. The largest iron and steel works in the town are those of Sir John Brown and Co. (Lim.), and Messrs. Cammell and Co. (Lim.), both celebrated the manufacture of armourfor and heavy castings forgings of every description. Messrs. Naulor and Vickers, of the "Don Works," are the best and largest makers of cast-steel and bells: Messrs. Turton, Messrs. Sanderson, and Messrs. Ward, are very extensive makers of steel files, &c. A list of the great steel manufacturers of Sheffield would, however, extend to no small length. Factories and works have rapidly extended, chiefly on the N. side of the Don, between the rly. stat. and Brightside. The works are not generally shown without an introduction. It should be added that, although those named above are very large and important, there are many of equal, or of hardly less extent: and in all, large or small. the process of manufacture may be well seen.

Steel is a peculiar combination of iron with carbon. "Without carbon edge-tools, saws, &c., but it is largely the manifold uses of iron would be exported to all parts of the world, and greatly restricted. . . When carbon Swedish and Russian iron is returned

small quantity, we have wrought iron, which is comparatively soft, malicable, ductile, weldable, easily forgeable, and very tenacious, but not fusible except at temperatures rarely attainable in furnaces, and not susceptible of tempering like steel: when present in certain proportions, the limits of which cannot exactly be prescribed, we have the various kinds of steel, which are highly elastic, malleable, ductile, forgeable, weldable, and capable of receiving very different degrees of hardness by tempering, even so as to cut wrought iron with facility, and fusible in furnaces; and lastly, when present in greater proportion than in steel. we have cast iron, which is hard, comparatively brittle, and readily fusible, but not forgeable or weld-The differences between these 3 well-known sorts of iron essentially depend upon differences in the proportion of carbon, though other elements may and often do concur in modifying in a striking degree the qualities of this wonderful metal."-Dr. Percy, 'Iron and Steel.'

No British iron (except the Ulverstone charcoal iron, of which the supply is very small) is adapted to make good steel, owing to the phosphorus and other impurities in the ore; consequently our manufacturers are compelled to import large quantities of iron or iron-ore from Sweden, Russia, and Germany. The best quality is that called, from the mark it boars (the letter L within a circle), "hoop-L." and is made with charcoal, at Dannemora, in Sweden; but there are many other good qualities of iron, each distinguished by its peculiar mark. Though British iron is not fitted for steel, yet British steel is of such superior excellence, that it is not only employed at Sheffield, and throughout England, for cutlery, edge-tools, saws, &c., but it is largely exported to all parts of the world, and

to the countries from which it came, shaped close crucible of Stourbridge in the shape of steel bars. To convert the iron bars into blistered steel. they are laid in a trough of firestone in layers side by side, bedded in a powder of charcoal mixed with 1-10th of ashes and common salt. called cement, and keeps the bars separate from one another. The whole is covered with damp sand, or the residue of sand and mud found at the bottom of the grinding-troughs, here This excludes called wheelswarf. the air and prevents combustion. A fire is lighted underneath, and kept up for 8, 10, or 12 days, at a temperature not exceeding 100° Wedgwood's pyrometer (for fear of melting the iron). At the end of that period the iron is converted into steel-that is, has imbibed a sufficient quantity of carbon from the charcoal (in the proportion of about 1 per cent.) to change its nature and give it the hardness belonging to steel. When the bars are drawn out, the surface found covered with blisters. whence its name. It is also considerably fissured in the process, and to render it fit for use it must be hammered and forged under a tilthammer.

Shear Steel is made by shearing or cutting the bars of blister steel into short lengths, binding them together into bundles or "faggots," which are raised to "welding heat" in a furnace. then beaten under a tilt-hammer till the bars combine into one mass or rod -thus gaining uniform density and tenacity throughout.

Cast Steel.— The art of melting steel and casting it in a mould, thus converting it into the best quality of the metal for fine cutlery, was invented at Sheffield, 1770, by Mr. Huntsman, of Attercliffe. It is made in greater quantity here than anywhere else in the world. For this into small pieces, is heated in a barrel- days; and 31 hours more are re-

clay in a furnace fed with coke, in which it is entirely imbedded. usually takes 4 hours to reduce the metal to a fluid state. The heat of the furnace used in this process is so intense that a stranger will find himself scorched on approaching it. workman who extracts the crucible with a pair of tongs, prepares himself for the operation by clothing arms. legs, and head with coarse sacking, and either subjects himself to a nump. or sprinkles his garments thoroughly with water beforehand, to prevent their catching fire. Simple as the duty of taking out the crucible and pouring the fluid metal into the mould may appear, it is one requiring great skill and care, only to be acquired by long experience, and paid by very high wages. The shower of bright green sparks issuing from the liquid metal as it is poured into the mould is very beautiful. The ingot of steel, when cold, rings with a pure, clear, and intense sound, like bell-metal. All the finest articles of cutlery, the best scissors, knives, razors, the chisels used by sculptors. and the steel plates employed by engravers, as well as surgical instruments, are made of cast steel.

These are the usual processes in steel-making. But the Bessemer process, the invention of Mr. Henry Bessemer, calls for especial notice, since for some purposes it promises to supplant all others. This was first made generally known in 1856, when Mr. Bessemer read a paper on the subject before the British Association at Cheltenham. He afterwards established a manufactory at Sheffield (it is near Brightside, adjoining the works of Sir J. Brown and Co.) for the preparation of steel on his own principle, and has succeeded completely.

The length of time necessary for converting iron into steel according purpose the blistered steel, broken to the usual method is from 15 to 20 quired for changing the bars into moved, and the melted steel pours By the Bessemer process iron is converted into steel in half an hour. The vessel used for the conversion is made of strong boiler - plate, and is lined with "ganister," a silicious stone found in the neighbourhood, and capable of resisting the action of heat and This vessel has an aperture at the top for pouring the metal in and out, and at the bottom are tuveres of fireclay, each with several holes in it. Through these a blast from the engine enters. The vessel is first thoroughly heated with coke, and a quantity of pig-iron, having been melted in an adjoining furnace, is poured into it. The blast is then turned on, and a most powerful combustion takes place, filling the place with a strong white light. At a certain time, 15 to 20 minutes, the huge dazzling flame contracts and loses its brilliancy: this is due to the cessation of the combustion of silicon and carbon, which are now burnt out. this signal the "converter," with its charge of 5 to 10 tons of molten metal, is turned over by means of hydraulic machinery, and as it turns, the blast cutting through the scoria on the surface throws up a magnificent arch of brilliant coruscations. Then the metal rests on the side of the converter, the blast is turned off, and the "spiegeleisen," or "ferromanganese," a compound of known percentages of iron, manganese, and carbon, is poured in. This supplies the proportion of carbon required to give the steel the requisite hardness, and the manganese assists in purifica-During the pouring of the "spiegel" a beautiful blue flame of burning carbonic oxide pours in vast volume from the mouth of the converter. The steel is now made; the hydraulic machinery, moved by a mere touch of the hand, pours the molten charge into a huge cauldron called the "ladle." This now swings over the ingot moulds, a plug is re- in fact cut out of a sheet of steel,

heavily into the moulds. The ingots thus formed are picked up by machinery while still red-hot, and carried away to the steam hammers to be condensed by heavy thumping, then re-heated and rolled into rails, plates, tires, or what else may be required.

Visitors should, if possible, witness the whole of a "blow," from the charge of the converter to the pouring into moulds, about & an hour. This is best seen at "The Atlas Works" (J. Brown and Co.), or "The Attercliffe Works" (Brown, Bayley and Dixon). Tramcars run continu-

ally to either.

From the manufacture of steel itself we come to that of the various articles made of it. Shear-steel is used for table-knives and edge-tools; cast steel for razors, penknives, and best scissors; and common steel for inferior articles. The workman called a forger is provided with a small furnace, an anvil, and a trough of water. He heats red-hot the end of a rod in the fire, places it on the anvil, and hammers it by hand into the shape of a penknife, razor-blade, or whatever is required. It is then cut off, heated again, and a piece of iron welded to it to form the tang by which it is held during grinding, and afterwards attached to the haft. It is again smartly hammered to give it density. The nail-hole is struck in it and the maker's name and mark stamped while hot. The blade is hardened by being plunged red-hot into water; it is afterwards tempered by being laid upon a flat plate over the fire until it assumes a certain blue or purple colour, according to the temper required. Oil is frequently used instead of water, and in some cases baths of melted metal, for tempering.

The processes of making other articles vary in the details. knives are partly made of iron, and in part shaped by a stamp or die, being and the shoulders, tangs, and backs welded on: these and razors require 2 workmen, a forger and a striker, to manage the forging process, the one holding the hot steel by a pair of tongs with his left hand and a small hammer in his right, while the other wields a heavy hammer with which he strikes alternate blows.

Scissors and forks are also made in a different manner. The blades after being tempered and hardened are sent to the

Grinding Mill to be ground, a curious operation well worth the notice of the traveller. There are at least 70 grinding-mills in and about Sheffield, more than 20 of which are moved by steam-engines of the aggrepower of 800 horses, and the rest turned by water.

The first steam-wheel was erected in 1787, and formed a very sensible improvement upon the old-fashioned rickety sheds of former times. entering one of these mills the first impression made on the stranger will be by the harsh and stunning noise. He will then remark that the apartment is occupied by a number of troughs, in which turn grindstones of various sizes; those for table-knives being 4 feet in diameter, and 9 or 10 inches broad, whilst some are employed even as large as 8 ft. in diameter. They are of soft gritstone, and are obtained from the quarries of Wykersley, near Roche Abbey. immense velocity with which they whirled round renders liable to split and fly, and the fragments not unfrequently burst through the roof and break holes in the walls; of course seriously injuring or even killing the grinder, who sits astride above the stone, on a wooden There are few mills whose walls and roofs do not exhibit the marks of such accidents. Such fractures of the stones arose either from some flaw in their mass, or they are cracked by too tight wedging round the hole formed for the axle to turn |

in. To avoid this, the axle is now usually fixed in stout iron discs acrewed against the stone so as to press its sides, and remove the torsion as far as possible from the centre.

Some articles are ground wet, and others require a dry stone. the latter is employed, a constant stream of sparks of the utmost brilliancy, rivalling fireworks, is emitted. to the great injury of the health of the workman, who inhales the fine angular particles and contracts what is called grinder's asthma. and needle-grinders are most exposed to this disease, as they use the drystone exclusively, and their heads are constantly enveloped in the deleterious atmosphere. The complaint was unknown until grinding became an exclusive business, and not performed. as previously, by the cutlers themselves. It has become much more prevalent since the introduction of steam-mills, and it has been proved that out of 2500 grinders in this town not 35 had reached the age of 50, while among 80 fork-grinders there was not one individual of the age of 35. It was proposed to prevent this by making the workmen wear a necklace of magnets to attract the steel dust, and a gauze or wire mask before the mouth; but a more effectual contrivance is a wooden chimney communicating with the open air, and with its lower end partly enclosing the wheel, the mere revolution of which produces a current of air sufficient to carry off the dust. In spite, however, of the certain fate which awaits the grinder, this invention is but little employed. The blade after being ground is subjected to the glazier, a wooden wheel formed of wedge-shaped pieces arranged crossgrained, to preserve a perfectly circular form in case of shrinking, and strongly glued together. The surface is covered either with a strip of leather coated with emery, or with a sheet of soft metal, an alloy of tin and lead

(for penknives and razors), on which mot to leave the alightest variation emery is also laid; this give smoothness and polish to the surface, while tween the lines, is wonderful. Before the finest articles are rubbed on another wooden wheel coated with buff leather and thence called a believe and salt, to preserve it from buffer.

The most extraordinary variety of grinding is that of saws, in which the grinder, holding the steel plate cut into the shape of a saw with both hands outstretched, and nearly prostrate, leans his whole weight upon the grinding-stone, balancing himself on the points of his toes, and pressing the plate against the stone with his knees. There is a risk of his being whirled over by the grindstone if he loses his balance. This process requires great muscular exertion as well as skill.

Saws are made of steel rolled out into plates. Very long practice will alone enable the cutler to hammer out the plate true, even, and of equal clasticity. The teeth are cut with a punch and then filed, and the tempering is effected by dipping the plate heated in a furnace to a cherry red, in a mixture of oil, tallow, and resin, the proportions and some of the ingredients being generally kept secret.

A File Manufactory is another of the sights of Sheffield. Here again great delicacy and skill are required to produce a good article, and the marks of certain houses, reputed for the wares they turn out, are often falsified. The steel bars out of which files are made, after careful forging with hammers of peculiar shape, are softened in order to be cut or grooved. This is effected by the hand: and though to all appearance just the sort of work which machinery might easily perform, yet it has never been so effectually executed as by hand. The precision and celerity with which the workman strikes the cuts or furrows by a heavy hammer and a short highly tempered chisel, so as

in depth, distance, or parallelism between the lines, is wonderful. Before hardening the file, its surface requires to be protected with a mixture of ale-lees and salt, to preserve it from scaling off and exfoliating in the fire: sometimes the charcoal of burnt leather is used. It is then heated in a coke fire as uniformly as possible in every part, and it is next hardened by dipping it in water as cold as possible. Unless care be used, the file will warp in this process, and skill is required and some strength to bring it straight. The files are lastly washed in lime-water "to kill the salt," which would rust and corrode them.

The casting of steel bells at Messrs. Naylor and Vickers' works is well worth seeing. Steel grates and stoves are made largely in Sheffield. Steel wire (some even finer than hair, used for watches) is another branch of manufacture which is rapidly increasing, as is the making of steel springs for railways. In some of the larger steel-works Bessemer-steel rails are made at a price but little above that of iron rails, which they are now rapidly superseding. Iron armour-plate for ships of war are also made at Brown's and Cammell's, who have practical monopoly of these.

Silver plating and the manufacture of Britannia metal (this is composed of block-tin, copper, and martial regulus of antimony) are carried on here by several large firms. In Portland St. are the very large confectionery works of Messrs, Bassett.

Broom Hall, on the southern outskirts of Sheffield, the house of R. N. Phillips, Esq., is a remarkable timbered mansion, the earliest portions of which seem to have been built by one Robert Swyft, in the reign of Edward IV. or Richard III. It has been added to and altered, but is still very interesting, and affords an excellent specimen of the timbered dwellings anciently constructed in this great forest district.

The great inundation on the night of the 11th of March, 1864, will long be remembered at Sheffield. Bradfield reservoir, 6 m. above Sheffield, covering an area of 76 acres, and holding 114,000,000 cubic feet of water, suddenly burst through its embankment—an enormous erection 300 yards long, with an average height of 85 ft., and 40 ft. in thick-The flood swept off everything before it, from the confluence of the Loxley and the Rivelin to Nearly 300 persons the Don. perished, and the property destroyed was estimated at more than one Large subscriptions were at once raised for the sufferers. vast reservoirs which are formed among all these hills for the watersupply of the great manufacturing towns demand constant watching and supervision: adding, as they do, a danger by no means to be despised to the many others to which such towns are specially exposed.

Sheffield has a water communicacation between the 2 seas by means of the river Don, which is made navigable from the confluence with the Humber to Tinsley, 3 m. off, whence the Sheffeld Canal, constructed 1817 along the rt. bank of the Don, conveys to the doors of the manufacturers the heavy raw materials for their wares, and distributes hence to all parts of the world the equally heavy manufactured articles. It terminates in a basin near the junction of the Don and Sheaf, passes through a deep cutting on the S. side of Attercliffe, and is carried over the Derwent road by a long massy aqueduct. There are 12 locks upon it in a course of little more than 3 m.

There is some pretty scenery on brook, which falls into it about 4 m.

(see the present route, anie) may easily be visited by rly. Wentworth House (Lord Fitzwilliam), with its noble Vandycks, is also accessible from the Rotherham Rly. (see Rtc. 45): Beauchief Abbey, 4 m. from Sheffield. on the Midland line to Chesterfield. is in Derbyshire (see Handbook for that county). There are few remains, but the site is very pleasing and picturesque.

ROUTE 45.

SHEFFIELD TO DONCASTER, BY MAS-BOROUGH (ROTHERHAM).

Midland Rly., 5 trains daily, in 1 This line has a stat. at Masborough only. The tourist wishing to go direct to Rotherham (which is a m. from Masborough) should take the Sheffield and Rotherham line, on which there are very frequent trains, performing the distance in 20 min. On this line there are stations at Brightside and Holmes. line as far as Masborough is the same as in the following route, but on this (the Sheffield and Doncaster branch of the Midland) the trains do not stop between Sheffield and Masborough.

The smoke and dirt of numberless forges and collieries accompany the rly. nearly as far as Masborough the Rivelin, and on the Wyming Its course is through the valley of the Don, which winds rt. from Sheffield. Wharncliffe Woods m. from Sheffield, across the river. is the village of Attercliff, with a modern ch., only remarkable for a sounding-board, invented by the Rev. J. Blackburn, and described in the 'Philos. Trans.' Beyond the village is the wooded hill of Tinsley Park, with large collieries, quarries, and iron-works. 2 m. from Sheffield, 1. of the rly., is the village of Brightside (stat. on the Sheffield and Rotherham Rly.), between which and Sheffield itself enormous iron and steel factories are rapidly extending.

On the hill of Wincobank, at the back of the village, is a large camp. nearly circular, with a deep ditch and vallum, attributed to the Romans, but probably constructed originally by the Brigantes, a numerous and warlike British tribe, who struggled fiercely against the Romans. wooded hill, commanding a wide view, on which this camp is placed, has been formed by a fault which here occurs in the coal formation. Connected with the camp, and running from it N.E. in the direction of Mexborough, is a bank called the " Roman Ridge," partly natural, and formed by the same "fault," but artificial wherever additional strength was required. On the S. side (towards the Don) is a deep ditch. For some distance this rampart forms the boundary between the parishes of Sheffield and Ecclesfield. It has been traced (and, spite of ploughs and collieries, is still traceable at intervals) as far as Mexborough, where it seems to terminate. At the period of its construction marshes extended from Mexborough to Conisborough Cliffs, and formed of themselves a sufficient On the W. side of Wincobank a similar intrenchment has been traced as far as Sheffield. probable that these lines formed the main defences of the Brigantes on this They may side of their territory. be compared with the strong camps and lines of defence in the neighbourhood of Catterick. posite Wincobank, across the river, were cast here during the revolu-

is the Roman permanent camp or stat. of Templeborough (Morbium or Ad Fines?), defending a ford where a Roman road, running N. from Chesterfield towards Castleford (Legiolium), crossed the Don. It was excavated 1877, and among the Roman remains discovered were a stone inscribed-"Cohors quarta Gallorum," traces of a Prætorium, columns, and a hypocanst.

[At Blackburn Junct., a little beyond Brightside, the S. Yorkshire Rly., between Sheffield and Barnsley, falls into the Midland. For this line see the following route. The stream Blackburn here joins the Don.

Rt. of the rly. is the village of Tinsley, with large collieries. canal running at some little distance from the Don unites Tinsley with Sheffield.

Passing through some deep cuttings, which well expose the coal strata, the Holme Collieries and the blazing furnaces of the Holmes Ironworks are seen l. (Stat. on the Sheffield and Rotherham Rly.) Boston Castle, a tewer built as a shooting-box by Thomas Earl of Effingham, is conspicuous on a hill rt.; and beyond it, the spire of Rotherham Ch. Hence the rly. curves round to

5 m. from Sheffield, Masborough (Inn: Prince of Wales). Masborough is in effect a suburb of Rotherham, from which it is separated by the Don (Pop. of municipal borough, including both places, in 1871, 25,087). It is famous for the *Iron-works* (about \(\frac{1}{2}\) m. from the stat.) established in 1746 by Samuel Walker, who, being left at the age of 12 an orphan, with 2 brothers and 4 sisters unprovided for, by his own talents and industry acquired a large fortune. establishment was at one time per-Nearly op- haps the largest in Europe.

of Sunderland, Staines, and part of Southwark came from the works. They are now divided among small proprietors, and are surpassed by others in different parts of the coun-Walker was a friend of the poet Mason, who wrote the inscription on his memorial tablet in the There is an In-Wesleyan chapel. dependent Church at Masborough. Ebenezer Elliott, the "Corn Law Rhymer," was born here in 1781.

Across the Don, ? m. from the Masborough Stat., is Rotherham Stat. (The Sheffield and Rotherham Rly. on the rt. bank of the Don. This rly. passes under the N. Midland Rly. shortly before it crosses the river.)

Rotherham (Inns: Crown: Royal: Ship; Prince of Wales) is a very thriving but murky town, trading in iron, coal, corn, horses, cattle, and sheep; and one of the chief Yorkshire markets for the latter. Pop. 24,782. It stands at the confluence of the Rother with the Don, which is navigable hence to the Humber. The chief point of interest at Rotherham

The Church of All Saints; "one of the finest Perp. churches in the north," says Rickman; and "of so great beauty that it gives interest even to the murky atmosphere of the town; with the tall black cones of the Masborough forges for a foreground." This ch. was restored by Sir G. G. Scott It is generally assigned (1873).entirely to Thomas Scott (or Rotherham), Abp. of York (1480-1501), who was born here; but a careful examination proves that, whilst the nave, the upper part of the tower, and the spire, may safely be attributed to him, the lower part of the tower and the whole of the chancel and transept arches are of earlier date. Windows (chancel and transepts) have been inserted of various dates. On the exterior remark the very

tionary war; and the iron bridges | beautiful W. front, with its panelled doorway (now closed), and the great Perp. window above it, the hoodmoulding of which runs up into a gable cross;—the S. porch—the S. aisle of the nave (much richer than the N.), the lofty clerestory of the nave, with pinnacled buttresses between each bay: the tower, which has windows resembling those in the nave aisles; and the lofty crocketed spire. The chancel or transepts are less worthy of attention than the nave: the clerestory windows are late and very indifferent insertions. The great Within the E. window is bad Perp. bold and lofty proportions of the nave at once strikes us. The piers "are of a very singular section, being, in general contour, of an elongated lozenge shape, the longer section running N. and S." The capitals are of very slight projection, and seem designed to "carry out the ideals of the piers - the greatest possible compression and lightness. The present roof of the central tower is covered with fan tracery: but this tower was originally a lantern, and the Dec. windows, once above the roof, now look into the ch. below them, since the roofs were raised in the Perp. period. In the chancel, the sedilia and piscina, and the niches on each side of the E window, deserve attention. There is a hagioscope from the S. aisle. At the end of the S. chancel aisle was the Lady-chapel, the roof of which was richly coloured, and retains many striking and unusual devices, all relating to the Blessed Virgin. In the N. aisle in the chapel of St. Anne is an altar-tomb with brasses of Robt. Swifte (1561), wife and children. The screen-work separating the chancel aisles from the transepte seems to have belonged originally to the rood-screen. The mont. of John Shaw, vicar (died 1672), "tam Barnabas quam Boanerges rite habitus. should also be noticed. He was an active Puritan, ejected under the

Act of Uniformity. In the chancel | of Strafford, born in 1593 (in London), is a mural tablet by Flazman; and in the nave a mont, to the memory of 50 persons who were drowned in 1841, at the launch of a boat in Masborough.

On the Bridge of 5 pointed arches over the Don is a plain wavside chapel, the dimensions of which (32 ft. by 14 ft.) are somewhat less than those of the chapel at Wakefield (40 ft. by 16 ft.). It is, however, of little architectural interest, though it does not deserve its present degradation. It was for many years used as a prison.

Bp. Sanderson, whose Life was written by Isasc Walton, was born at Gilfil Hall in the parish of Rother-

The Rother, a stream of some importance, descends from the Derbyshire highlands. Rotherwood—the hall of Cedric the Saxon-which may be supposed to have stood in this neighbourhood, has no real prototype. Coningsborough Castle, also scribed in 'Ivanhoe,' is 6 m. from Rotherham. (See Rte. 40.)

Roche Abbey (see Rte. 47) is 8 m. S.E. At Wickersley, 3 m. W., are some large quarries, whence are obtained most of the grindstones used by the Sheffield cutlers. The ch., ded. to S. Alban, is chiefly Norm.

Wentworth House and Park (Earl Fitswilliam) is 4 m. W. of Rotherham, and is perhaps most easily reached thence (unless the tourist chooses to drive from Sheffield). The house is always to be seen in the absence of the family. family-taking their name from the place—had been settled here from an early period, and becomes more conspicuous toward the beginning of the 14th cent. By the 16th the Wentworths had become of great importance in the county; and Sir Thomas Half the sum necessary for their

succeeded to a position only second (if it was second) to that of the powerful family of Savile. Before he became immersed in public life, Sir Thomas lived much at Wentworth, delighting in all country amusements. "Our objects and thoughts," he writes to Sir George Calvert in 1623, " are limited in looking upon a tulip, hearing a bird sing, a rivulet murmuring, or some petty yet innocent pastime." After the great Earl's execution the estates and honours were restored to his son by the King. The 2nd Earl, however, proved the last in the male succession of Wentworth Woodhouse. 3rd son of the great Earl's eldest daughter, Lady Rockingham, succeeded, and assumed the name of Wentworth. His son became Marquis of Rockingham; who was succeeded by his son, the 2nd and last Marquis -the statesman, who was first Lord of the Treasury from July, 1765, to August 1766; and again from March, 1782, to his death in July of the same year. He died without issue; and Wentworth passed to William Earl Fitzwilliam, the eldest son of the Marquis's eldest sister. The verv ancient family of Fitzwilliam had been settled at Sprotborough from a very early date (see Rte. 40); and the head of a branch from the main stock was created a peer of Ireland by James I. The 3rd Baron was created an Earl by George I.; and the 3rd Irish Earl was created a Baron of Great Britain, and, in 1746, Viscount Milton and Earl Fitzwilliam.

The Barnsley road, which leads to Wentworth, after crossing the bridge over the Don, passes under the rly. and proceeds by Carr House and Barbot Hall (Lord Howard-finely placed to command the view) to the The ch. village of Greasborough. and school-house here are modern. Wentworth, afterwards the great Earl | erection was contributed by the Fitz-

william family. Passing the "Roman ! ridge" (see the present route, ante, Wincobank), on entering the park of Wentworth Woodhouse a fine view opens over its lawns and woods, with a considerable sheet of water in the hollow. On the height. rt., stands the Mausoleum erected by the late Earl to the memory of his uncle, Charles Marquis of Rockingham, the minister. Within it is his statue by Nollekens, surrounded by busts of Burke (who wrote his epitaph), Fox, Admiral Keppel, and others. On the N. side of the park rises an Ionic column, erected by the Marquis of Rockingham on the acquittal of Keppel, who was his intimate friend.

The house itself was built by the 1st Marquis of Rockingham, who enclosed the older mansion, in which the great Lord Strafford had delighted, within the new. It lies somewhat low, but is a very stately edifice, having a façade of 600 ft. long, with a fine portico in the There is, wrote Walpole. centre. "a pompous front, screening an old house; it was built by the last lord on a design of the Prussian architect Both, and is not ugly. The one pair of stairs is entirely engrossed by a gallery of 180 ft., on the plan of that of the Colonna Palace at Rome. The hall is pretty, but low; the drawing - room handsome." The house contains some antique sculpture; but its great treasure is the Collection of Pictures, including perhaps the finest and most interesting Vandycks in England. The principal are as follows :-

First Room. Vandyck: 3 children of the great Lord Strafford-Wm. afterwards Earl of Strafford; Lady Anne, and Lady Arabella Wentworth. Sir J. Reynolds: Charles Marquis of Rockingham.

Library. Sir Peter Lely: Lady Anne and Lady Arabella Wentworth. Here, however, the great picture is of the Earl of Rockingham.

Vanduck's portrait of Lord Strafford dictating to his secretary, Sir Philip Mainwaring. The great Earl is in black, Sir Philip in red. picture," says Waagen, "far excels the usual work of the master. are distinctly shown a moment of that ominous period. In these serious features we read all the energy of a character devoted to the service of his sovereign; at the same time they have something tragical in expression." "Great he surely was." writes Hallam, no "reverer" of Lord Strafford's name, "since that epithet can never be denied without paradox to so much comprehension of mind, such ardour and energy, such courage and eloquence; those commanding qualities of soul, which, impressed upon his dark and stern countenance. struck his contemporaries with mingled awe and hate, and still live in the unfading colours of Vandyke. —Const. Hist., chap. viii.

Gallery. Lely: Portraits of 2 chil-Teniers: A rocky landscape. with peasants good. Rafaelle: (but attributed by Waagen to Innocenzo da Imola): Virgin and Child. Palms Vecchio: Virgin, with Child holding the globe; the Baptist pointing to the Child; and St. Catherine. beautiful picture, executed in his warmest tones."—Waagen. A. Van Ostade: A peasant wedding. Rosa: Jason giving the dragon the sleeping charm (this picture was etched by the artist); a rocky coast. Sir J. Reynolds: Portrait of the Countess Fitzwilliam. Vanduck: Henrietta Maria; Lord Strafford in armour; Rinaldo and Armida. Here is also a portrait of Shakespeare. copied from an earlier picture by Sir G. Kneller, and given by him to Dryden. He is in black, with moustache and beard, and an carring in the left ear.

Yellow Room. Hogarth: Family

Drawing Room. Sir. J. Reynolds: \ Portrait of the late Earl Fitzwilliam when 4 years of age Stubbs: Porttrait of Whistleiscket (size of life), a famous winner of the St. Leger.

Vandyck Room. Vandyck: Lord Strafford in armour - in his right hand is the baton, the left rests on the head of a white dog; a most noble picture; whole-length; lifesize. Henrietta Maria, in blue silk -she is patting a monkey, held by the dwarf Jeffery Hudson; wholelength; life-size; very excellent. Archbp. Laud; "of masterly execution in a clear reddish tone." -- Waagen. Arabella. 2nd Countess of Lord Strafford. (She was a daughter of the Earl of Clare and sister of Denzil Holles.) Mytens: Lord Baltimore (founder of the colony of Maryland). Lely: Duke of Gloucester, son of Chas. I. Janson (?): Villiers, Duke of Buckingham.

Ante-room. Lely: Prince Rupert. "One of the warm, carefully-treated pictures of his best time."-Waagen: Sir J. Reynolds: The Infant Hercules strangling the serpents. Studies for the window in New College Guido: Cupid sleeping. Chapel. A. Carracci: Christ crowned with thorns.

In another room are some works by modern sculptors, including a boy with a hare, and a fisher-boy, by Wyatt: and a bas-relief by Gibson.

The Cellars are by no means the least remarkable part of this most stately mansion, and give a good idea of the hospitality which is maintained here after the fashion of olden days. They extend under the building, arched and vaulted, like the crypt of some vast cathedral. That devoted to ale and beer contains at least 200 huge casks; and the butler rarely allows any visitor to quit the house until he has tested the quality of the contents. A glass of this ambercoloured nectar poured from a vener- smoking chimneys, with their glow-[Yorkshire.]

able black-jack is by no means to be despised.

Behind the house is a sort of wilderness filled with fine trees. The

gardens are not remarkable.

On some high ground E. of the house are Keppel's Column and Hoober Stand, a lofty building erected by the 1st Marquis to commemorate the peace of 1748. vast extent of country is commanded from it. The Mausoleum was built by the 2nd Earl in honour of the Marq. of Rockingham.

The *Churck of Holy Trinity is a beautiful Gothic edifice, erected 1877 by Earl Fitzwilliam, in memory of his parents, at a cost of 25.000L Attached to it is the chancel of the old ch.. rich in monuments, and here the great Lord Strafford is buried. His Monument, says Walpole, is "a little mural cabinet, with his figure, 8 ft. high, kneeling." There is also an altar-tomb, with effigies, for Thomas Wentworth and wife (1587); and a mont, with kneeling figures for Sir Wm. Wentworth (1614). An earlier altar-tomb, with effigies, belongs to a knight and lady of the Gascoigne family (see Harewood, Rte. 29), with which that of the Wentworths was connected.

Beyond Masborough the rly. continues through the valley of the Don, here broad and open. some distance a branch rly, belonging to Earl Fitzwilliam, and constructed to convey coals from his collieries near Greasborough to Sheffield, runs by the side of the main line. It terminates at the Greasborough Canal, where a wharf and basin have been constructed. canal communicates through river Don with the Humber. Birmingham tin-plate works are passed l., marked by a group of ing and smoking furnaces, and Lord Fitzwilliam's New Parkgate colliery.

At 2 m. from Masborough, Rawmarsh Stat., are the Rockingham china-works, where porcelain 4-post bedsteads have been made. Here

also are large iron-works.

Across the Don, nearly opposite Rawmarsh, are the picturesque woods and lawns of Thrybergh Park, once the seat of the Reresbys, now of John Fullerton, Esq. The house, which is modern, commands a very fine view. The Reresbys had been seated here from the 14th cent., until, in 1689, Sir William Reresby succeeded to the property and gambled it entirely He became a tapster in the AWSV. King's Bench prison. The Thrybergh tradition asserts that he staked and lost the estate of Dannaby on a In a lane near the single main. village of Thrybergh is the fragment of a remarkable cross, covered with foliage and ornaments of late Norm. It is known as St. character. Leonard's Cross, and tradition asserts that the heiress of the Normanvilles, who passed Thrybergh before the Reresbys, met the ancestor of the latter family at the cross, where they plighted their vows to each other. Reresby was on his way to the Holy Nothing was heard of him for many long years, and the lady was about to marry another lord, when she received a mysterious message, directing her to visit St. Leonard's Cross on a certain night. There she met a palmer, who proved to be her former lover. Of course she married him, and the Reresbys thus became lords of Thrybergh. The story is found in many forms and in many places,

Passing the stat, at

12 m. Kilnhurst, the train soon reaches

1½ m. Swinton Junct. (For the rest of the line to Doncaster see Rte. 40.)

ROUTE 46.

SHEFFIELD TO BARNSLEY.

(South Yorkshire Rly., 4 trains daily.)

Leaving Sheffield from the Victoria Stat., the train for a short distance follows the line of the Sheffield and Rotherham Rly. (see Rtc. 45), until it turns off N.W. at Blackburn Junct. From this point as far as Wombwell, where it joins the main line between Barnsley and Doncaster, this branch rly. passes through a country of hills and valleys, of woods and coppices, still, in spite of collieries and iron-works, retaining much of the forest character which it possessed in the days of Cedric the Saxon. The glades of Tankersley or of Wentworth afford many such scenes as are described in the opening pages of 'Ivanhoe; where "hundreds of broad-headed, short-stemmed, wide-branched caks fling their gnarled arms over a thick carpet of the most delicious greensward; in some places intermingled with beeches, hollies, and copsewood of various descriptions; in others receding from each other, and forming those long sweeping vistas, in the intricacy of which the eye delights to lose itself, while imagination considers them as the paths to yet wilder scenes of sylvan solitude.'

Passing the stat. at

21 m. Broughton Lane, we reach

5½ m. Grange Lane Stat. Rt. is The Grange (Earl of Effingham), built in 1777, and surrounded by woods. 1½ m. Ecological Stat. A village

with a fine Perp. Church worth a chimneys have sadly marred its visit. "This church." wrote Dodsworth, " is called, and that deservedly, by the vulgar, the Mynster of the Moores, being the fairest church for stone, wood, glass, and neat keeping that ever I came in of country church." The tower is central. The present building is almost entirely Perp.: but a ch. was founded here certainly as early as Henry I. (possibly before the Conquest), and gave name to the settlement—Ecclesfield. the church (ecclesia) in the "field" -a term which everywhere in this district, retaining its true signification, indicates a clearing in the midst of the woods The chancel and transepts of the ch. of Ecclesfield have been excellently restored by the Rev. Dr. Gatty. The old woodwork, including screen and stalls, has been carefully preserved, and there are some good modern windows of stained glass. The plaster and whitewash have been removed. In the churchyard is a memorial for the Rev. Joseph Hunter, the historian of Hallamshire, and of South Yorkshire, who is interred here.

The next stat. is

8 m. Chapeltown. Here are large collieries, ironstone pits, and (at Thorncliffe) extensive iron - works. All this country is rich in coal and iron; and the mines and quarries, which extend in all directions, have of course destroyed its ancient quiet and seclusion. But it is still beautiful. The line runs through woods

91 m. Westwood Stat., close to which is a large colliery. A very short distance rt. is Tankersley Park, with the fragment of its hall, an ancient seat of the Saviles, Talbots, and Wentworths. The park in De Foe's time was celebrated for some of the finest red deer and most venerable oaks in Yorkshire; but ironstone pits, coal-smoke, and furnace

beauties. The red deer have entirely disappeared (they were removed to Wentworth Park by Lord Fitz-william), and many of the oaks have also vanished. Here, in 1655, Sir Richard Fanshawe translated the 'Lusiad' of Camoens. He had been taken prisoner in 1651 after the battle of Worcester, and was afterwards allowed to choose his own residence, provided he did not go 5 miles from the place without leave of Parliament. Lady Fanshawe, in her curious Memoirs, says that the country was "plentiful and healthy, and very pleasant; but there was no fruit in it till we planted some, and my Lord Strafford says now that what we planted is the best fruit in the north." There were some enormous yew-trees in Tankersley Park, in the hollow of one of which, called Talbot's yew, a man on horseback might, it was said, turn about. In the midst of the park, on an eminence, is a tower called the Lady's Folly, commanding a very wide view. kersley now belongs to Earl Fitzwilliam.

(Wentworth House—see Rte 45 is about 3 m. E. of Chapeltown Stat. The walk is very pleasant, but no conveyance is to be had here. Wentworth is most easily visited from Sheffield or from Rotherham.)

The country retains the same general character to

102 m. Birdwell Stat., and thence

131 m. Dovecliffe Stat. The rly. winds round Dovecliffe, a steep wooded hill, with sandstone quarries. overhanging the river Dove (which joins the Dearne below Darfield). and thence proceeds by Aldham Junct. to Wombwell. (For Wombwell and the line thence to

Barnsley, see Rte. 40.)

ROUTE 47.

ROTHERHAM TO BAWTRY, BY TICK-HILL (ROCHE ABBEY).

No rly. traverses this the S.E. corner of Yorkshire." There are, however, coaches (as to which the tourist should inquire at Rotherham) which run to Tickhill, 12 m. The country is pleasant, without being unusually picturesque. The most interesting places on the route are Roche Abbey, the ch. of Laughton-en-le-Morthen, and Tickhill Ch. and Castle.

The country immediately round Rotherham has already been noticed (Rte. 45). At Maltby, 6 m. from Rotherham, a road branches S.E. to Sandbeck Park (2 m. further), adjoining which are the ruins of Roche Abbey. Sandbeck (Earl of Scarborough) is a modern house, standing in a very agreeable park. The ruins are at the W. end of the park, in a deep, narrow, and very picturesque valley, one side of which is overhung by a limestone rock, somewhat recalling the rocks that rise on the N. "I saw Roche side of Fountains. Abbey too," writes Walpole to Cole in 1772, "which is hid in such a venerable chasm that you might lie concealed there even from a squireparson of the parish. Lord Scarborough, to whom it belongs, and who lives at next door, neglects it as general character. The chancel conmuch as if he was afraid of ghosts, tains some later work, apparently I believe Montesinos' Cave lay in Dec. Little is known of the early

now so overgrown that, when one finds the spot, one can scarce find the ruins." It is almost to be desired that the ruins were still in this neglected state: but some time after they were visited by Walpole, Lard Scarborough called in "Capability Brown " to "improve" them. removed all those portions of the ruins which did not satisfy his ideas of the picturesque, and formed the lake which is now seen in connection with them. How much he destroyed it is impossible to determine.

Roche Abbey was founded about 1147, for Cistercian monks. Richard de Builli, in conjunction with 2 other proprietors - Richard de Buisli, and Richard son of Tur-It would seem that certain monks or hermits had (as in the cases of Nostel and Kirkstall, Rtes. 38 and already established themselves in the valley, where they professed to have discovered a natural crucifix in the face of the limestone rock. This was afterwards known as "Our Saviour of the Rock"—de Rupe and it was probably from this figure that the abbey received its name. It was colonised from Fountains.

The main gateway, and the ruins of the ch. (transepts and part of chancel—the nave has entirely disappeared), are the principal relics of Roche Abbey. The gateway is Dec., and the room above it probably served (as at Easby, Rte. 25) as the guest-chamber of the monastery. The ch. had a low central tower, and in each transept were 2 small chapels, repeating the usual Cistercian arrangement, as at Kirkstall and Foun-These portions are Trans.tains. Norm., no doubt of the date of the foundation, and should be compared with Abp. Roger's work at Ripon (Rte. 22), which they resemble in just such a solemn thicket, which is history of Roche, which was not one

of the wealthier Yorkshire houses, | and none of its abbots seem to have been men of note. Near the ruins are the limestone-quarries which have supplied so much stone (known as Roche Abbey stone) to Yorkshire church - builders. Sir Christopher Wren proposed to use it for building St. Paul's Cathedral.

The fine ch. of Laughton-en-le-Morthen—the name is corrupted into "Lighten in the Morning," and is locally connected with the great distance at which its spire is visibleis 2 m. across the country, S.W. from Roche. Le Morthing (perhaps " Moor-thing," the " Moor-portion is the ancient name of this district. extending S. and E. to the borders of the county, and for some distance The ch., which is for the most part early Perp., with a tower and very fine spire, rising to a height of 185 ft., has been restored by Sir G. G. Scott, and, out of the way as it is, well deserves a visit. It abounds in curious and grotesque carvings, and seems to have been mainly rebuilt in the latter half of the 14th But the northern arcade is Norm.; there is one Norm. window; and a portal on the N. side is so rude and peculiar that it may have been part of a church built here before the Conquest. At that time the place belonged to the great Earl Edwin, the brother of Morcar, and brother-in-law of Harold; and near the village is the Castle Hill, with strongly resembling foundations those at Wincobank (Rte. 45), at Mexborough (Rte. 40), and at Tickhill (post). There is a high conical mound, in the ring of a circular embankment, with an enclosed area, defended by a bank and ditch, appended to one side of it. bank is cut through and the ditch traversed, toward the E.N.E., by a narrow causeway, no doubt representing the original entrance, which little later, and the rest of the 15th may have been over a timber bridge. | cent.

It seems very probable that this is the site of the Saxon stronghold, and that Laughton, as the chief "aula" of Earl Edwin here, may signify the "Lagh'-" law-town "-of the dis-

[The Ch. of Thorpe Salvin. 5 m. S. of Laughton, and anciently a chapel in that parish, is remarkable for a fine late Norm. portal, much enriched: and for a large and singular font of the same date. The font is circular: and, besides a representation of the secrement of baptism, has figures apparently emblematical of the four seasons. In the village are the ruins of a large Elizabethan house, once the residence of the Sandfords.]

A road of about 4 m. will bring the tourist from Roche to Tickhill, a small town with a large Perp. ch. and the fragments of a castle, founded apparently by Roger de Buisli soon after the Conquest, but afterwards enlarged and strengthened. Like Coningsborough, Tickhill Castle had a circular keep, placed on a mound, with an outer ballium to which there was but a single entrance, strongly defended. Of this keep only foundations and some fragments of walls remain. The mound and the line of the outer walls probably represent the foundations of an earlier fortress, and resemble the works at Laughton, and elsewhere.

The Church is fine, in Perp. style, founded 1360 by Wm. de Estfield. Seneschal of Holderness to Queen Philippa. In an elegant chantry, lighted by a flamboyant window, are the efficies of him and his wife. The nave has a lofty clerestory, and there is some old glass in windows of S. aisle. There is a very fine altartomb, with effigies of a Fitzwilliam and his wife, brought here, according to Leland, from the ch. of the Austin Friars. The tower is of the early part of the 14th cent.; the S. side a

only castles that held out for John on the return of Richard I. from his Austrian captivity. Tickhill, during the civil war, was held for the King. but surrendered after Marston Moor. The keep was then "slighted" by order of Parliament. The gatewaytower remains, and is apparently of earlier date than the rest of the castle. It is, in Mr. G. T. Clark's judgment, an original and early Norm. structure, the upper part of which is unaltered, while the lower has been Rte. 1).

Nottingham and Tickhill were the marked by a Dec. gateway, witingly castles that held out for John portcullis-groove and pointed and. In the court, besides other buildings, was a chapel. An old oak door outside the gatehouse, with the inscription. "Peace and grace be to this place," may have belonged to it. The N. side of the castle has been converted into a modern dwelling-house.

The Yorkshire border is crossed close beyond Tickhill. A road of 4 m. runs across the projecting corner of Nottinghamshire to Bawtry (see

INDEX.

ARBOT'S HOUSE.

ABBOT'S HOUSE, 194. Aberford, 482. Acklam Wold, 128. Ackworth, school, church, Park, residence of Mr.

Peel, 360. Addingham, 385. Addleborough, 318. Adel, church, Roman re-

mains, 370. Adlave, Ralph, founds an Augustinian priory, 464. Adlingfleet, 90 Adoration of the Kings,"

the, by Mabuse, 163. Adwalton, 457.
— Moor, battle of, 457. Adwick-le-Street, 8, 352.

Ailcy Hill, 284. Ainderby Steeple, 301. Aire river and valley, 9, 360,

402, 424. Aire and Goole canal, 9. Airedale College, 437.

Aitkin, Dr., Birthplace, 76 Alan the Red, first Earl of Richmond, his manors in Yorkshire, 326.

Albemarie, lords of, 121. Albert, Abp., his basilica at York, 20.

Alcock, John, Bishop of Ely. 135. Alcuin at York, 69

(Holderness), Aidborough church, fine monument, 118.

- (the Roman Isurium), plan and position, ancient importance, 254; Roman remains, "Museum Isu-rianum," representatives

in parliament, church, 255.

Hall, 256.

Aldby Park, 126. Aidham junction, 474. Aldrow, 154. Alfred, king of Northumbria supposed tomb of, 148. Alfred's Hole, 168.

ARTHUR.

Allerton, effigles and brass in the church, 259. Great and Almes Cliffs.

Almes tums,
Little, 267, 378.
Almondbury Camp, 452;
village,

church, 452; remarkable inscription round the nave, 452.

Aln, 218. Alpaca fabrics, 426.

Alum-working first practised in England, 217. Alum-works at Sandsend,

202; fossils found in the

QUATTY, 202. Alured, 135.

Alvin, murderer, scene at his condemned sermon, 117. Amotherby, 242.

Ampleforth, church, Rom. Cath. college, 239. Angler's Arms inn, 39

Anglians, incursions of, xiv. Angram, 273.

Anley, 407. Antiquities of Yorkshire, XXÍV.

Apperley Bridge, 424. Appleby stat., 413.

Appleton-le-Moors, 252. - Roebuck, 84.

— le-Street, 242. Aram, Eugene, story of, 264 his birthplace, sketch of his career, 272.

Ardsley, scene of colliery accident, Dec. 1866, 472; stat., 474 ; junction, 457. Arkengarthdale, lead-mines

in hills bordering, 334.

Arkle beck, 333.

Arksey, church, hospital, 8.

—— Pool, 8.

Armley, 424. —— House, 424. Aracliffe, 203, 215, 399. Arram, 147.

Arres, 131. Arthington Hall, 376.

— junct. stat., 375. Arthur and his Knights, legend concerning, 329.

BARF.

Ascham, Roger, his birthplace, 224. Aake Hall, and family, 335.

, Cristofer, his adventure at Skipton Castle, 393.

Robert, leader in the "Pigrimage of Grace,"
xviii. 7; his home, 132.
Askerne Spa, 78.
Askrigg, 318.
Aston, living of Mason the

poet, 479. Athelstane at the tomb of St. John of Beverley, 133.

Attercliff, 509 Attermyre Cliffs, cavern in.

409. Atwick, 125.

Auburn, 151.

Aughton, 132.

Augustine, St., Pulpit, 91. Austerfeid, 3.
Austhorpe Lodge, Smeaton's
birthplace, 372.

Ayagarth, view from the ridge, 316; church, 317. - Force, 316.

Ayton, 179, 213, 216.

BASSHAW, the Apostle of the

Peak, 502. Bein, river, 317.

Bainbridge, 317.

Bainton, 145. Baker, J. G., on the trapdyke of Yorkshire, xi.

Balder, river, 348. Baiderdale, 348.

Baldersby, church, 299.
—— Park, 300.

Balaover, Thos., his discovery of the art of silver-

plating, 497. Bankfield, 441. Barbot Hall, 511.

Barden Tower, 390. Bardsey, 488.

Barr, animal remains found in the, 151.

BARFORD.

Barford, 336. Barmston, church, monuments, remains of manorbouse, 151.

Barnard Castle, 337; situation, church ruins of castle, 337; view from Brackenbury's Tower, excursions

from, 339. — to Middleton-in-Teesdale, 348.

Barnborough, church with curious monuments, 478.

Barnby-on-Don. 85. Barnoldswick, Cisterdan ab-

bey at, 395. Barnsdale, district of, 79. Barnsley, 472; manufactures, 472; church, park, 473; canal, 473.

Barton, 92. — Hill, 158.

- le-Street, 242. Barwick-in-Kimete, remark-

able earthworks at, 482. Bashall, 424.

Bastides, plan of, 93. Batley, the shoddy - trade,

Battersby junct. stat., 212. Battles

Adwalton Moor, 457. Boroughbridge, 253 Ferrybridge, 15, 81. Flamborough Head, 186. Hatfield Chase, 86. Marston Moor, 256. Myton (the White Battle), 256. Sherburn, 82. Stamford Bridge, 125.

the Standard, 225. Towton, 484. Wakefield, 459, 460. Bough Fell, 321. Bawtry, 2.

Bay Town, 203. Beamsley Beacon, 385 Beckholes, 195. Beckwith, Dr., his tomb, 28.

Bedale, 301; interesting stained glass church. monuments, efficies of the Fitzalans, 301, 301,

- Hall, 302. Bedford, 76. Beeford, 151.

Beeston, 457. Beggar's Bridge, 203. Bell Busk, 403.

Bempton, 184. Beningbrough Hall, 74. Benedict, a monk of Autun.

monastery at Selby founded by, II.

BOLTON HALL.

Bennett, W. S., musician, 402. Ben Rhydding, 383. Bentley, Richard, critic, his

birthplace, 362, 461.

Berry Brow, 490.
Bessemer, Mr. Henry, his process of steel-making described, 504-506.

Beswick, 147. Bethel, "blameless Bethel"

of Pope, 147.

Beverley: stat., 133; derivation of the name, 133; college, 134; history, 134; worthies, 135; Minster, 135 – 141; St. Mary's church, 141; North Bar,

Minster: site, 135; burning of former church, 134: architectural details. 135; choir, 136; stalls, 136: Percy shrine, 137; Lady-chapel, Percy chantry, 138; sanctuary, nave, 138, 139; exterior, 140;

dimensions, 141. St. John of sketch of his life, 133; his shrine,

to Bridlington, 150. Bewerley, 271. Bierley Hall, 436.

Bilberry reservoir, bursting of, 491.

Bilborough church, 84. Billinge, 425. Blisdale, 212, 247,

Bingham, Joseph, his birthplace, 461.

Bingley, 427. Birdsall Hall, 154. Birdwell, 515. Birkby, 229.

Birk Crag, 267. Birkdale, 351. Birkin church, 82. Birstall, 448.

Birstwith, 269. Bishopdale, 313. Bishop's Wilton, 124.

Blahopthorpe, 73. Black Beck Vale, 180. Blackburn function, 509. Black Fors, 385. Blackstone Edge, 443.

Blakey House, 210. Blakey-topping, 194. Biayshaw Bents, 273.

GIII, 272. Bolland, forest of, 423.

Bolton, brasses in the church, 421. — Hall, Henry VI. at, 420; relics of the king, 421.

BRADLEY.

Bolton-on-Swale, 226.

Castle, great castle of the Scropes, its history, 314; description, 315; tradition of Mary Queen of Scots connected with, arc.

Bolton Hall Scrope portraits. Percy, church, stained giass, monuments, 83.

Priory: situation, history, tradition connected with, 385: the church with, 385; the church the chief relic, 387; re-mains of the conventual buildings, 388; churchyard

and priory barn, 388.

Hall, woods and walks. 388; park, 389.

Bolton-upon-Deane, 77. Bone-cavern of Kirkdale, 248. Bonner, Bishop, his rectory.

133. Booth Ferry, 108.

Boroughbridge, 252; ancient stone relics, 253; its parliamentary representatives, 254.

Boston, 487.

—— Spa, 487.
Bosvile, Charles, chief of the northern gipsies, his grave,

3. Boulby, 208. Boulder-stones, 346. Bowes (the "Lavatres" of

the Romana, the " delightful village of Dotheboys"), 344; church and church-yard, 344; castle, 344, 345; Roman remains, 345

Bowet, Abp., his tomb, 42. Bowfell, 320. Bowling Hall, 436.

Ironworks, 436.

Boy of Egremond tradition of, 386

Boyle, Richard, his birthplace, 189. Boynton, Sir Henry, 140

Bracchium, supposed site of, 317.

Bracewell, 396. Bradford, 430; situation, history, trade, 431; the old town, church, 432; public buildings, 432, 433; ceme-tery, Peel Park, 433.

Bradley junction, 450. Marmaduke, last abbot of Fountains, 288.

- Park, 469. William, the "York-shire Giant," 131.

BRADSHAW.

Bradshaw, regicide, tradition as to his burial - place. 479. Brafferton, 252.

Braithwaite, Richard (* Dap-per Dick." or * Drunken Barnaby"), his monument,

Bramah, Joseph, tablet to, 493. Bramhall, Abp., his birth-

place, 359. Brambam, 487.

—— Park, 487, 488. Brambope Tunnel, 375.

Bramley stat., 430 Brandon, Lady Eleanor, her escape from Skipton, 193. Bransdale, 212, 249.

Brandsburton, church, brass-C& 151.

Brayton Barf, 15; Church, 15. Bridestones, 194, 248.

Bridlington, 186; Priory, history of, 187; church, 188, 189; celebrities, 189. Brigantes, the, xiii.

Brighouse, 469.
Briggs, Henry, mathematician, his birthplace, 443.

Brightside, 508, 509. Brignall Banks, 341. Brimham Crage, 269.

—— Hall, 270. Brocksdale, 81. Brockholes junction, 491. Brompton, 181, 229.

- John of, 181, 305. Bronte family, notice of, 428.

Broom Hall, 507. Brotherton, 82. Brotton, 236. Brough, or

Hall stained glass, pictures, antiquities, 324, 325. Broughton Hall, 396.

- Lane, 514. Browsholme, 424

Bruce family, memorials of, 217.

Bubwith, church, 132. Buchan, author of Domestic Medicine,' 502.

Buckden, 401.

Birks, 401.

Pike, 401.
Buckingham, Geo. Villiers, duke of scene of his death-Pope's account of, incorrect, 249. Buckinghamshire, Sheffield,

duke of, 375.

Bugthorpe, 128.

CARTHUSIAN.

Bulmer, Sir John and Lady. executed, 234. - Hill. 148. Burdale, 154 Burgh Wallis, 80. Burley, 382.

Burnby, 129. Burnet, Thos., his birthplace, 225. Burneall, 191.

Burstwick, 111. Burton Agnes, Hall and

church, 149. — Constable stat., 122. – mansion and park, 123.

--- Head, 212. — Park, 306.

- Pidses, 111. - Salmon, 82.

-, West, 314. Dr., his birthplace, 461.

Burythorpe, 128. Busby Hall, pictures, 214.

Buttertube Pass, 322, 334 Byland Abbey, foundation

and history, 237; situa-tion, 238, church, 238.

CADEBY, 478. Credmon, tradition of the origin of his paraphrase of the Scriptures, 201. Calcaria, site of, 482. Calder, river, 360, 444, 449, 457; vale of the, 445, 449, 466.

Caldron Snout, 350. Calverley, 425. scene of the

'Yorkshire Tragedy,' 425. Walter, pressed

death, 425. Cam Fell, 401.

Cambodunum, site of, 452. Camps Mount, fine cedars, 79.

Campeall, church, library, and vicarage, 78, 79. Cannon Hall, 493. Cargo Fleet stat., 232.

Carlisle, Earl of, 160.

Carlton Hall, 103. Carlyle, Thos., his account of the battle of Marston Moor, 258. Carnaby, 150.

Carr, architect, his birthplace, House, residence of the

Childers family, 8, 511 Carthusian Order in England, 227.

CLAPHAM.

Castleford, 360. Castle Howard: Walpole's description of, 160; pictures, 161-165; museum, gardens, 165; mausoleum, 164.

- stat... 160. - Hill, 452, 475. Levington, 215.

Castlestead, 271, 272. Castleton, 210; walks from, 210.

Cataractonium, site of, 324. Cathcart, Earl, 223. Catrigg Force, 335.

Cattal, 259 Catterick, bridge, 323; bap-tisms in the Swale at, by Paulinus, 324; church, stained glass, brasses, 225;

earthworks, 325.

Cautley Spout, 321.
Cave Castle, 91.
Cawood, Archbishop's palace,

Cawthorne, Roman camps at, 19}.

Cayton Bay, 177. - stat., 182.

Ceadda (St. Chad of Lichfield). 250.

Cedd, monastery at Lastingham founded by, 250. Cedds Well, 251.

Chaloner, Sir Thos., the working of alum in England begun by, 217; excommu-nicated by the pope, 217. bambers, marine artist, Chambers, marine his birthplace, 198.

Chantrey, Sir Francis, notice of, 502.

Charel House, 399 Chapel-le-Dale, 417. Chapeltown, 515.

Charles I., lays siege to Hull, 100; at Red Hall, Leeds. 166. Chatburn, 423.

Cherry Burton, 133. Chevet Hall, 481.

Cholmley, Sir Hugh, his defence of Scarborough castle, 172.

- Sir Richard effigy of 190.

Chop Gate, 213. Christianity, its introduction into Yorkshire, xiv.

Church Fenton, 83. - Garforth, 482.

Clapham, 414. – Cave, 414.

- junction, 413.

family, tradition as to their interment, 387.

CLARKE. Clarke, Daniel, scene of his murder, 264 Clavereux Castle, 220. Clayton stat., 77. Cleckheaton, 436 Cleveland, district of 200. Port. 222. Cliffe, 104. Clifford, family, possessors of Londesborough, 120; of Skipton, 393-395. Lord, slain at Dintingdale, 81, 484 — Henry (the "Shepherd Lord"), his life at Barden, 300.

— Lady Anne, Counters of Pembroke, restores Barden, 300; sketch of her life, 393-395. village, 487. Cloth-trade of Leeds, 362; manufacture, 367. Cloughton Wyke, 177. Coal and collieries, xxxii. xxxiii. Coatham, East, 233. Cobden, Richard, his school, Cock, river, 482, 483, 485. Cockhill mines, 274. Cockshot Mill, 202 Coifi, heathen priest, conversion of, 130. Coleridge, Hartley, at Sedbergh, 321. Colne, river, 450, 455; valley, 490. Colvile of the Dale, Sir John, 238. Commondale, 212. Congreve, dramatist. birthplace, 488. Coningsborough Castle. described in 'Ivanhoe,' date and history, 475; description, 475-477; tomb of Hengist, so called, 477; tomb of church, 477. Conistone, 399. Cononley, 430. Constable, family of, 123. —, Burton, 305. Constantine the Great, proclaimed emperor at York, Constantius Chlorus, his residence and death at York, Cook, Captain, circumnavigator, at Whitby, 198; at Staithes, 208; his column, 212; his birthplace, me-morials of, 232.

Cookridge Hall, 375.

CURWORTH.

Cooper Bridge junction, 468. Copley tombs at Sprotborough, 478. Commanthorpe, 84. Cornelian Bay, 177. cheese, Cotherstone 348; 348; ruins of castle, 348. Cotter, river, 320. Cottingham, 146. Council of the North, xx. Cover, river, 309. Coverbridge, 305. Coverdale, 310. Miles, Bishop of Exeter, his birthplace, 310. Coverham, 309.; — Abbey, ruins of, 309; effigies, 300. Cow and Calf rocks, 384. Cowick Hall, 102. Cowthorpe, venerable oak at 260, 480, Cowton, 229 Coxwold (Sterne's vicarage), 236; church, monuments, 237. Cracoe, 398. Crakehall, 304. Crathorne, 215. Craven, Sir William, Lord Mayor, 391; his son the first Earl of Craven, 391. -, deanery of, 392. - Fault, the, xiil, 406. Crayke, ruins of castle, tradition of St. Cuthbert, 218. Cresacre, Percival, and wife curious monuments of, 478. Cressy, Hugh, church his-torian, 461. Creswick, J., artist, 493; his birthplace, 502. Criscleston, 471. Crimble viaduct, 454. Croft, 229. Croston, 360 Cromwell, Oliver, relies of, tradition concerning his remains, 237; at Marston Moor, 258; at Ripley Castle, 269; story of, at Norton Conyers, 295; his letter to the Council concerning the siege of Pontefract Castle, 357; memorials of, at Farnley Hall, 381; porat Farnley Hall, 381; por-trait at Weston Hall, 382. Cronkley Fell, 350. - Scars, 350. Cropton, 194. Cross Gates, 481. Crow Garth, 151.

Cudworth, 480.

Cusworth House, 8.

DEWSBURY.

Cutler, Sir John, notice of, by Pope, 378. Cutlers, Company of, 498. Cutlery, great mart of, 498.

DACES Banks, 269. - Lord, slain at Towton. 485; his monument, 485. Daiby Beck, 194. Dale, the valley and hamlet, 238. beck, 416. - End, 411. Dalton junction, 229. - Hall, 144. - Holme, 144 Danby Beacon, 200. - Castle, 209. - church, 211. Danes, their settlements in Northumbria, xv. Danes' Dyke, 184. Danthorpe Hall, 118. Danum, ancient, site of, 3. Darfield, church, efficies, obelisk in churchyard, 480. Darley, 269. Darlington, 229. —— to Barnard Castle, 336. Darnley, Henry, his birthplace, 371. Dartmouth, Earl of, 473. Darton, church, 472, 493. Dawnay family, the, 103. Dearne, river, 472, 477, 515. Dearne and Dove canal, 474. Dee, river, 321 Deep Car, 494. Deepdale, 346.
Defoe, Daniel, at Halifax,
442; his passage of Blackstone Edge, 444; description of the country near Halifax, 445. Deighton stat., 454. De la Pole, family of, of Denby Dale, 401. Dent, 413.
Dentdale, 321.
Denton Park, 382.
De Quincy, Peter, 304. Derwent, river, 105, 126; val-ley, 160; tributaries, 160. 180; source and course, 168 Devil's Arrows, 253. Devonshire Arms botel, 185, Devonabire, Duke of, 188. Dewsbury, 449; church, 449; sculptures, Sexon tomb

449

DIALECTS.

Dialects of Yorkshire, xlvii. Diderston Hill. 226. Diggle, 456. Dimlington Hill, 115. Dodworth, 494.

, Roger, antiquary, his birthplace, 242. " Dog of Alciblades," at Dun-

combe Park, 245. Dolben, Abp., his tomb, 42. Dolman, Thomas, monument to, 127.

Don river and valley, 77, 89 475, 477, 492, 495, 496, 508,

513; rise of, 492.

Doncaster; hotels and railways, 3; situation and history, 3; St. George's ch., painted glass, organ, comparative cost, 4, 5; St. James's Church, 5; Christ church, 5; races and racecourse, 6; history, 7; railway factories, 6; ancient cross, buildings, 6; excur-

sion, 7. to York, 78. "Dotheboys," 344.

Dove, river, 474, 515; valley. 250

Dovecliffe, 515.

Dowkabottom Cave, animal and human remains, 400. Downe, Lord, 200, 295, 300. Dragon, legend of a, 208. "Dragon of Wantley," 495,

Dragon's Den, 495. Drax priory, site of, 105. Driffield, Great, its antiquities, 148; church, basrelief, 148.

. Little, 148.

Drightlington, 457.
Dropping Well at Knaresborough, 262. "Drunken Barnaby," monu-

ment of, 325. Dudmanstone, 452. Duncombe Park, sculpture,

pictures, park, fine view, 244. Dunford Bridge, 492.

Dunsley, 202. Dunstan's stat., 430. Dutch River, the, 103.

E

EAGLESCLIFFE junct, 215. Kesby, abbey and church, 331; parish church, 332; the Abbot's Elm, 332. - Moor, 212. Eccgill, 419.

ERMYN STREET.

Easgill Kirk, 410. Easington, 115. Easingwold, 218. East Coatham, 233. Easter controversy, synod to determine the, 200. Eastrington, 108. East Witton, 310. Eastwood, 446 Ebberston, 168. Eboracum, ancient, 19. Ecclesfield, church, 514. Eden, river, 323. Edstone, 248. Edward L, plan of his towns,

94 IV., story of his imprisonment in Middleham Castle, and escape, 308; gains the battle of lowton.

Edwin, first Christian king of Northumbria, his conversion, 19; his death, 86; his conferences with Paulinns, and conversion, 130,

Edwin and Emma, grave of the lovers in the poem,

344. Effingham, Earl of, 514. Eggleston Abbey, ruius of,

346. Eglin's Hole, 273. Egliston Hall, 349. Egton Bridge, 203; church,

Eldwick, Roman remains at, 383.

Elfieda, Princess, abbess of Whitby, 201.

Elland family, story of an extraordinary feud in the,

469, 470. — Edge, 470. — Hall, 469, 470. — New Hall, 470.

Ellerbeck, stream and glen, 195.

Ellerker, 91. Kilerton Priory, ruins of,

Elliott, Ebenezer, "Corn-Law Rhymer," notice of, 502,

Elloughton, 91. Eimete, ancient district of,

368, 482. Elsternwick, 118.

Embsay, priory founded at, removed to Bolton, 386, 391.

Emsell, South, 352. Erewash Valley, 77. Ermyn Street, 9, 79.

FENAY.

Escrick, church, 16.

Esholt Hall, 425. Eshton Hall, extensive library, pictures, 403. Esk river, geology of hill country near, 193; at Whitby, 197; in Westerdale, 211. valley, iron blast furnaces, 196. Eston, stat, and quarries, 232. — Nab, 234. Etton, 144. Ettv. William, Etty, William, his ourse-place, 71; his description of Hull, 96. Exley, 470.

FACEBY HILL 214 Fairfax family, 84.
——, Edward, translator of

Tasso, his birthplace, 182, -, Ferdinando, Lord, his monument, 83; his defence of Hull, 101; his birthplace, 382. —, Thos., Lord, his monu-

ment, 379; his residence. ₹82.

of him and his wife, 240; 356; takes Leeds, 369; memorials of, at Farnley Hall, 381, 382; his birthplace, 182; his grave, 84. Fairy Dell, 385.

Falcon Clints, 241. Falling Force, 197. Fangioss, 127.

Fanshawe, Sir Rich., translator of Camoens, 515. Farfield Hall, 385.

Farndale, 211.
Farnley Hall, collection of

pictures, landscapes and drawings by Turner, in-teresting memorials, 380, 38 L - Tyes, 453.

Fauconberg tombs in Cox-wold church, 237. Faux, Guy, his birthplace and

CATCET, 71. Featherstone, 360.

Feliskirk, church, effigies, stained glass, 221. Felkirk, 480. Felon Sowe of Rokeby, 342.

Fenay, 454.

FERBYBRIDGE. Ferrybridge, battle at, 14, 81. Ferriby, 92. Feversham, Earl of, 244. Fielden, John, his mammoth cotton-mill, 446. Files, manufacture of, 507. Filey, 182; its ancient importance, fisheries, church, i82. Brig, 183. Fimber, 129, 146, 154. Finghall Lane stat., 305. Fisher, John, Bishop of Rochester, 135. Fishlake, village and church. Fitzalan, Sir Brian, his monument at Bedale, 301 Fitzroy, Henry, son of Henry VIII., first Duke of Richmond, 327. Fitswalter, Lord, slain, 8r. Fitswilliam, Earl, 511. tombs at Sprotborough, 478. Fixby Hall, 451. Flamborough, church, caves, ligh thouse, 184. - Head, 185. Flasby Fell, 397. Hall, 403. Flatt Wood, 339. Flaxman, John, his birthplace, 71. Flaxton, 156. Fleming, Bishop of Lincoln, 461. "Flying Childers," 8. Formathorpe, 132. Folkton, 182. Fordun, the first writer who mentions Robin Hood, 79. Forest Kirk, 350. Forge Valley and British camp, 179. Foes, river, 156. - Gill, 313. Fossard family, 3. Foston - le - Clay, Sydney Smith's living, 158. Abbey, Fountains ground-plan, 287; founda-tion and history, 288; beauty of the site, 188; venerable yews, 289; gatehouse, 289; conventual church, 289-291; chapterhouse, 291; Hall of Pleas, kitchen, refectory, 291; Abbot's House, 292; great cloister, dormitory, guesthouse, infirmary, 292; dissolution and subsequent fortunes, 202.

— Hall, 293.

GILLING.

Fox, George, imprisoned at Scarborough, 172; his preaching at Sedbergh, :21; and at Warmsworth, 478. Freebrough Hill 211. Fremington, 333.
Frewen, Archbishop, his tomb, 41. Friar's Wood, 403. Fridaythorpe, 128. Frith-stol, in Beverley Minster, 138. Fryston Hall, 81. Fryup Dale, 209. Fuller, his character of Yorkshire, vii Fulneck, Moravian actilement at, 430. GAIMFORD, 336. Galtres, forest of, 72. Ganton, 168. Garforth stat., 482. Gargrave, tradition of its churches, 402. - House, 403. Garadale, 320. — beck, 321. Garside Valley, 413. Garton, 118. on-the-Wolds, 155. Gascoigne, Sir William, tomb and effigies, scene in Shak-

spears concerning, 377.
Gaskell, Mrs., her notice of

Gaveston, Piers, beheaded,

172, 354. Gawthorpe Hall, seat of the

Gent, Thos., his residence,

George-a-Green, 458, 466. Gheast, Edmund, Bishop of Salisbury, 225. Gibbet-law, 438, 441, 442.

Gilling (near Byland) stat.

scholars, 408;

bours, 428, 429.

Gastrills, 399. Gatekirk Cave, 418.

Gascoignes, 377.

Gearstones, 319, 418.

Geology of Yorkshire, ix.

– Inn, 418.

guished

well, 408.

Gill beck, 391.

Gillamoor, 211.

- Scar, 408.

Gildersome Street, 449.

and church, 230.

Haworth and its neigh-

Gilling to Pickering, 242

GREETLAND. Gisburne, ham, 158. Goxhill, 123. Grantley 291. at, 259 I 35.

28.

273.

454-

Greenhow Hill lead - mines.

Greetland, Roman remains,

- Castle, seat of the Fairfaxes, 240; stained glass, portraits, 240. — (near Richmond), its antiquity, church, 335. church. 419; stained glass, 420.

— Park, pictures, 420;
white cattle, ancient drinking-horn, 420. Glaisdale, 204. Glanville, Ranulph de, justiclary, his birthplace, 210. Gledstone House, 397. Goathland Mill stat., 195. -, Vale of, 195. God's Bridge, 345. Golcar, 455. —— Viaduct, 454. Goldsborough, 20 efficies in the church. discovery of old 259. — Hall, 260.' Goodmanham, scene of the conversion of Edwin of Northumbria, 130, 131; church, 131. Goole docks, 90. Gordale Scar, rare plants, 404, 405. Gormire, 222. Gower, Sir John, the poet, his birthplace, 158; the family settled at Sitten-Gowthwaite Hall, 272. Goydon Pot, 272 Graham, Sir Richard, legend concerning, 295; monument to, 296. Grange, the, 514. Grange Lane, 514. Hall, pictures, Grassington, lead-mines on the moor, 398. Gray, Archb., his tomb, 25. Great Driffield, 148 Houghton, 480. - Smeaton, 229 Green Hamerton, Henry IV. Green, John, Bishop of Ely, Greenfield, 456. , Archbishop, his tomb,

GRETA BRIDGE.

Greta Bridge, 336; river,
340, 342, 343, 417.
Greweithorpe, 294.
Grey, Sir Ralph, executed, 7.
Griffiths family, monuments
of, 150.
Grimston Garth, 118.
Grimstone, North, 154.

Hall, 118.

----- Park, 484. Grinder's asthma, fatality of, 506.

506.
Grinton, earthworks at, 333.
Gristhorpe Bay, 177.
Grosmont, 196; Priory, 196.
Guisborough, Priory and
church, 216; the modern
church, memorials of the
Bruces, 217; the Hall,
ironatone quarries, spa,

217. Guiseley, 379. Gully, Mr., his residence, 360. Gunnergate, 232.

H

HACKFALL, 204. Hackness, monastery, history of, 179; church, 180; village, 179. — Park, 180. Haiburn Wyke, 177. Haigh, 471. Halfpenny House, 210. Halifax: situation, 437. 438; rise and progres trade, explanations of the name, 438; parish church, 439; Cloth-hall, Town-hall, 440; All Souls church, 440, 441; Worsted and carpet manufactories, 441; museum, 441; the "Hali-fax gibbet," 441, 442; 441, 442; People's Court - house, Park, old houses, 442; celebrities, 443. Hallam, manor of, 498. Hallamshire, 498. Hainaby Hall, 229. Halsham, 111. Hambleton, 104. - Hills, 221. Hamerton, 259. Hampole, 9, 352. Harald Hardrada, Scarborough burnt by, 171. Harden Grange, 427. Hard Flask, 401. Hardraw Force, 319. Harewood, manor and castle, 375; church, tombs, and

effigies, 376, 377-

HELMBLEY. Harewood House, pictures, collection of antique china. fine view, vineries, 377, 378. Harlow Car, 267. Tower, 267. Harpham church, fine monuments and brasses, 149. Harrison, John, builds St. John's church, Leeds, his monument, 363; his hospital, 364 Harrogate: hotels, lodgings, railways, 265; situation and climate, 265; way of life described by Smollett, 265; the first spa discovered, growth of the place, 266; character and uses of the waters, 266; walks, 267; excursions. 267. to Pateley Bridge, 268. to Northallerton, 274. Harswell Gate, 132. Hartburn, 151. Hartleap Well, 310. Hatfield, 85, 123. Thomas of, 85. - Chase, 85. Hauxwell church, 106. - Park, 306. Hawes, 319, 320. —— to Kirkby Stephen, 322. - to Muker, 322. Haworth (home of the Brontes), 428; church, 429; character and manners of the people, 429. Hawsker, 203. Haxby, 156. Hayton, 129. Hazelwood Hall, 485. Hazlehead Bridge, 492. Headingley, 370, 372. Healaugh, 486. Heath, 461.
— Old Hall, 461. Hebble river, 438; valley of the, 443. Hebden Bridge, 444.

Heck, 9.

Heckmondwike, 436.

487. Helena, Empress, 69.

Kettles, 229.

Hell-becks, 323.

- GW, 323.

Hedon, its decay, 109; church, ancient cross, 110.

Hein, St., her monestery, 487. Helen's (St.) Ford and Well,

Hellifield, 407.
Helmsley, history, 243; ruins
of the castle, 243; church,
brass, Canon Garth, 244.

HOLMES.
Helperthorpe, 155.
Helsingore, 480.
Hemingborough, church, 104.
Hemsworth, 353.
Hengist, so-called tomb of,
477.
Hengist-rein, 477.
Henrietta Maria, Queen, at
Bridlington, 187.
Henry I, tradition of his
birth, 10.

— IV. struck with leprosy,
259.

V., his asserted rein-

statement of Judge Gascoigne not true, 377.

VI. at Bolton Hall, and Waddington Hall, 421.

VIII., his visit to Yorkshire, 3.

Hensall, 102.

ahire, 3.
Hensall, 102.
Heptonstall, 445.
Hereford, Bohun, Earl of, killed at Boroughbridge, 258.
Healerton, 168.
Healerton, 168.
Hesslengton Hall, 72.
Hessay, 256.
Hessle, 02.
Hickes, 620., antiquary, 225.

John, sheltered by
Alice Lisle, executed, 225.
Hickleton, 478.
High Cup Nick, 351.
— Force, 349.

— Hoyland, 472.
— Whitby, 202.
Hilda, abbess, her monastery at Whitby, 198, 200.
Hildyard family, 112.
Hilston, 118.
Hilton, monuments of the family, 122.
Hinderwell, 207.

Hipswell, 330.
History of Yorkshire, xiii.
liob Hole, 207.
— Thrush, a woodland

spirit, legend of, 250. Hodder, river, 424. Hodgebeck, river, 248, 249. Hofland, Mrs., 502. Holbeck junction, 372, 457. Holderness, district of, description and history, 120.

Holgate, Robert, his school and hospital, 352. Hollin Hall, 384. Holme, river, 450; valley of

the, 491.
— on Spalding Moor, 132;

beacon at, 132.

on-the-Wolds, 145.

Holmes, 508.

HOLMES. Holmes, antiquary, his birthplace, 395. Holmfield, 437 Holmfirth, inundation 491. Holwick Scars, 349. Honley, 490. Hood Grange, 223. Hill, 222 Hook, Dr., Vicar of Leeds, 363. Horbury, 466, 471. Horcum, Hole of, 194. Horn of Ulphus, 46. Hornby Castle, 302; pictures, 303, 304; church, 304. Hornsea, 123. - Mere, contest as to right of fishing in, geological changes now in progress, 124; character of coast near, 124. Horses of Jervaulx, 305. Horsforth, 375. Horton, 410. — Moor, 412. — Hall, library and collections, 434. Hotham, 91. Sir John, governor of Hull, 100; he and his son beheaded, 100. —, Lord, 144. Houghton Hall, 92. Hoveden, Roger de, his birthplace and annals, 107. Hovingham, spa, church, 241. - Park, 241. Howden, stat., church, 105; manor - house, celebrities, great horse fair, 107, 108. Howgill Fells, 321. How Hill, 293. Howley Hall, 447. Howsham, 158. - Hall, 158 How Stean Beck, 273. Hubberholme, 402 Huddersfield, trade, condition of the people, 450; name, churches, museum, 451. - Canal, 455. to Manchester, 455. - to Sheffield, 490. Huggate, 146. Hull, 92: hotels, steamers, situation, various names, 93; whale-fishery, 92; the original Kingstown, 93; founded by Edward I., 93; docks, 94; trade, 95; quay, Trinity-house, 96; Charter-house, Wilberforce monu-ment, 97; Holy Trinity church, 97, 98; St. Mary's

IRON.

church, 98; Town-hall, Museum of Literary and Philosophical Society, 99, 100; citadel, 100; history, " 101; 100; the "bore," commerce, 101; excursions, 102 Hull to Bridlington, 147, - to Hornsea, 120. - to Withernsea, 108. Humber, river, 92; dock, 94; estuary, 101. King, 101. Humbleton, 118. Hunmauby, 183. Hunsingore, 260, – Hall, 184. Huntcliff Nab. 208. Hunter, Rev. Joseph, historian, 502; his grave, 515. Hunslet, 362. Huntsman, Mr., the art of melting and casting steel invented by, 504. Husthwaite, 236. Hutchinson, John, his special doctrines, birthplace, 306. Hutcliffe, 235. Hutton, 166. , family of, its eminent

members, 333.

—, Archbishop, his tomb,
42.

— Bonville Hall, 229.

— Buscel, 181.

— Cranswick, 148.

T

ILELEY: hotels, hydropathic stablishments, situation, Roman remains, water-cure system, 382; church, 383; effigy, ancient curious crosses, 384; walks in the neighbourhood, 384. Illingworth, 443 Ingetlingum, 335. Ingilby, Sir Wm., 269. Ingleberd, Philip de, 111. ingleborough, 415. - Cave, 414. - Hall, 414. Ingleby, 212 Ingleton, 416. Ingmanthorpe Hall, 489. Ingram, Mrs. Meynell, 371. Ingthorpe Grange, 397. Inundation at Sheffield, 508. irchester stat., 76. ireton, sword of, 381. Iron, conversion of, into steel,

KILNWICK.

Iron manufacture described,

231, 434.

and ironstones, xxxi.

Ise river, 76.
Isurium, site of, 254.

Ivelet beck, 314.

1

JAMES I, of Scotland, capture of. 186. Jenkins, Henry ("Old Jenkins"), notice of, 326. Jervaulx Abbey, ruins of, 304; founded originally at Fora, 304; church, chapterhouse, 305; tombs of the abbots, 305; its cheese and breed of horses, 305; its last abbot hanged, celebrities of, 305. Jet found and worked near Whitby, 200. Jews, massacre of, at York in 1190, 64 John of Bridlington, reputed saint, 188.

of Gaunt Inn, 362.

Jones, Paul, 119; sea-fight with, off Flamborough Head, 186.

July Park, 195.

•

Krasdon, 334. - Force, 334. Kegworth, 77. Keighley, 428. Keld, 334. Keldgate, 147. Kellington, 102, Kent, Wm., landscape gar-dener, his birthplace, 189. Kettleness, 207. Kettlewell, 401; hills round, , John, nonjuror, 225. Keyingham, 111. Kiddal Hall, 483. Kilburn, 219. Kildale, 212. Kildwick, 429. - Grange, 430.

— Grange, 430.

— Hall, 430.

Kilham, 130.

Killingbeck, stream, 481.

Killingrobe Scar, 194.

Killing Pita, 195.

Kilnhurst, 514.

Kilnsea, 115.

Kilnsey Grag, 399.

Kilnwick, Percy, 127.

— on the Wolds, 147.

KIL/FON CASTLE.

Kilton Castle, ruins of, 208, Kilvington, 220. Kingsdale, 418. Kingston Hall, 77.

Kingston-upon-Hull, 93; see

Kingstown, its resemblance to Edward L's "Bastides."

Kiplingcotes, 132. - Racecourse, 145. Kippax Park, 483. Kirby Grindalythe, 155.

Malzeard, 294 Underdale, 128.

Wharfe, 82, Kirk Bramwith, 85. Kirkburn, Norman church,

145. Kirkburton, 455.

Kirkby, 214.
— Malham, 404. - Moorside, 249

- Ravensworth, 336. Stephen junct. stat.

323, 413. --- Wiske, church, stained

glass, 224. Kirkdale church, ancient sun-dial 248; famous bone-CAVETO 248

Kirkham, 158; Priory (remains) story of its foundstion, 159; Gatehouse, bird-fair, church, 159.

Kirk Deighton, 488. - Hamerton, 259.

Kirkheaton, 454. Kirkleatham, hospital, fine stained glass in the chapel, museum, library, 233; church, brass, 234.

— Hall, 234. Kirkleen, traditional scene of Robin Hood's death, 468;

the park, 469. Kirklington, church, brass, stained glass, 299. Kirk Smeaton, 80.

Kirkstall village, 372; abbey, history and description. 372-374; antiquities found in the ruins, iron-works, church, 375.

- Forge, 375.

Knapton, 168. Knaresborough, 260; situation and trade, church, 260; castle, 261; besieged by Liburne, 262; Dropping-Well, 262; limestone quarry, 262; St. Robert's Chapel, the Priory, notice of St. Robert, 263; cave of St. Giles (scene of the

LIKEDA.

murder of Daniel Clarke), story of Eugene Aram, John Metcalf (Blind Jack), 264.

Knottingley, 81.

- to Goole, 102. - and Goole Canal, 9. Knowles, Herbert, his lines on Richmond churchyard,

L

LACY, family of, 354. - libert de founds Pontefract castle, 354. Laister Dyke, 430.

Lambert, Gen., at Pontefract, Lamplush, Abo., his tomb.

42. Lamwith, river, 123.

Lancaster, Thos. Earl of, notice of his rebellion against Edward II., defeat and execution, 253, 354, 355; miracles wrought at his tomb, question of his canonization, discovery of his supposed remains, 355; site of his tomb, 355.

Landon inn, at the junction of three counties, 350, Langbargh Ridge, 211. Langstrothdale, 401, 402. Langton Hall, 128, 154. Lartington, 343.

Hall, 343. Lastingham, ancient monastery at, 250; church and crypt, 251; Codd's Well,

Latimer, last Lord, his monument and effigy at Well,

Laughton - en - le - Morthen,

Lavatra, site of, 345; situation and plan, Rossan remains, 345.

Laver, stream, 34%. Lawson, Sir John, 128. Leake church, 220.

Lealholme Bridge, 209. Leaserigg, 196. Leathley, 381. Leavening Brow, 153.

Leconfield Castle, 144. Ledsham, 483. Ledstone Hall, 483.

Leeds: stations, hotels, railcomparative importance, 302; history,

LITTLE RUDSTONE.

368; cloth trade, 362; St. Peter's church, stained giass and monuments, 363; Saviour's, 363; John's, founder's tomb. 363; hospital, 364; town-hall, Philosophical Hall, 364; museum, library, 365; Cloth-halls, bridge, grammar-school, 766; hospital, Medical School, 366; manufactories, 366, 367.

Leeds to Bradford, 410, 437, - to Harrogate, 372.

- to Manchester, 446. — to Selby, 481.

to Skipton, 378, 424.
to Wakefield, 457.
and Liverpool Canal,

402, 424. Leeming Lane, 301.

Lees Hall, 466. Legeolium, site of, 160.

Le Gros, Wm., Earl of Albemarie, castle of Scarbo-rough built by, 17x.

Leicester, 76. Leonards (St.), Lord, his birthplace, 195.

L'Espec, Walter, founder of Kirkham Priory and other religious houses, 150,

Levels, the, 85. Leven, church, fragment of ancient cross, 150.

Leventhorpe Hall, 437. Levisham, 193.

Leyburn, 305. — to Sedbergh, 312. Libraries at

Escrick Park, 17. Kirkleatham, 233.

Leeds, 365. Sheffleld, 501. Whitby, 199. York Minster, 50.

Lighthouse on Spurn Head, Lilburne, siege of Knares-

borough Castle by, 262. Lilla Cross, 197.

Limestone quarries near Womersley, 81; caverna near Horton, 412.

Lindholme, 87. -, William of, 87.

Linen manufacture at Leeds, 367. Linton, 398.

Liquorice, its cultivation and manufacture at Pontefract. 359.

T.Iseett, 151 Little Driffield, 148. - Rudstone, 100.

LITTLE STAINFORTH.

Little Stainforth, 410. Littondale, 399. Liversedge, 436. Lockington, 147. Lockwood, 490. Lofthouse, 208, 272, 457. Loidis, 368. Londesborough, stat., 129; the former mansion, descent of the estate, 129; probable Roman villa at, 130; tumuli near. 131 London to Harrogate, 484. – to Hull, 85. - to Leeds, 352, 479. -- to York, 2, 76. Long Hull, 217. Marston, 256. - Preston, 407. - Riston, 123. Longwood, 45 3, 454. Loughborough, 77. Lovely Seat, 322. Low Moor ironworks, 414, 435. Lowthorpe, 149 Luddenden Foot, 444. Lund, 145. Lune, river, 349. Lunedale, 149. Luton, 76. Lythe, 207.

.

MAGIS, site of, 336. Magnus, Thos., legend concerning, 219. Malham, 404 - Cove, 405 Water, 406. Mallyan's Spout, 196. Maitby, 516. Malton (junct. stat.), its ancient importance and position, 166; history, 166; churches, site of Roman castrum, Roman remains. 167; British camp, 167. - to Driffleld, 152. Manchester Hole, 273. Manningham Mills, 433. Manston, 481. Manufactures of Yorkshire, xxxi Mappleton, 110. Martieet, 109 Marishes Road stat., 190. Markenfield Hall, 293. Market Harborough, 76. Weighton, 131. Markham, Abp., his tomb,

METHILEY. Marmion family, their lord-ship, 296; their tombs at Tanfield, 297; their extinction, 297.
Marrick Priory, ruins of, 333. Marsden, 455. Marshall, Wm., agriculturist, his grave, 191. Marske, 234, 333.

—, seat of the Huttons. pictures, 333. Marston, 256. - Moor, battle of, 256-259. Martin's, St., Priory, ruins of, 332. Marton (near Flamborough), (birthplace of Captain Cook, near Middlesbrough), 232. —, East and West, 396. - Hall, 232. Marvell, Andrew, at Nun Appleton, 84; portrait of, 96; his birthplace, 112. Mary Queen of Scots at Bolton Castle, 314; tradition concerning, 315; her cap-tivity at Sheffield, 499, Masborough, 509. Masham, 290, 297. Mason, Wm., his residence at Aston, memorial tablet, 479. Matthew, Abp., his tomb, 42. Mande, Thos., the poet of Wensleydale, 313 Mauleverers, tradition as to their interment, 387. Mauley family, 206. Mase beck, 351. Maser-bowl in York Minster, Meaux Abbey, remains of, 121. Meldrum, Sir John, takes Scarborough, killed in the siege of the castle, 172. Melmerby junction, 296. Meltham, 491. Melton, 92. -, Abp., his burial-place, ZI. Mercer, Andrew, and his sons, Scottish pirates, 172. Metcalf, John (Blind Jack), notice of, 264 Metcalfe, clan of, 317. Metham family, 91. Methley, 360; stained glass and monuments in the church, 361. - Park, 360.

- lunction, 481.

MULTANGULAR TOWER. Mexborough function, earthworks, 475. — Earl of, 260. Meynill, tombs of the family at Whorlton, 214. Micklefell, 351 Micklefield, 483. Mickleton, 349. Mickley, 294. Middleham, 307; castle, 307; church, stained glass, \$06; moor, 309. Middlesbrough, rise and rapid growth of the town, 230; its iron-manufacture, 230. Middlesmoor, 272. 349. Midelton, family of, effigy of Sir Adam de, 184. — Lord, 154. Milford junction, 82. - to Hull, 104. Military memorials in York Minster, 42. Milleill Force, 318. Mirfield, 450. - junction, 468 Monckton, Sir Philip, tablet to, 91. Monk Bretton, remains of priory, 473. Montgomery, the poet, his birthplace and grave, 502. Moorthorpe stat., 77.
More Sir Thos. and family. Holbein's picture of, de-scription and history, 464. Morley, 446. Morris, Col., regains Pontefract castle by stratagem, 356; excepted from mercy, taken, and executed, 357. - Rev. F. O., 129. Mortham Tower, 340. Morthing, le, district of, 517. Morton, Roman coins found at, 427. Moss, 9. Moulton, 323. Mount Grace Priory, history and description of, 227, 228 St. John, remains of Preceptory, 22r.
Mowbray, vale of, 294.
—, Roger de, founds Byland Abbey, 237; tradition concerning, 238.

Muker, 334. Mulgrave Castle, 205.

55.

Multangular Tower, York,

MUNCASTER.

Muncaster, Lord, 120. Murdae, Henry, Abbot of Fountains, 288; raised to the see of York, 288. Murray, Lindley, his residence, 71. Museums: Aldborough, 254. Castle Howard, 165. Giggleswick, 408. Halifax, 441. Hudderstield, 451. Kirkleatham, 212. Leeds, 364, 365. Literary and Philosophi-cal Society, Hull, 99. Scarborough, 176. Sheffield, 501. Whitby, 199.

Whithy, 199.

Philosophical Society, 55. Musgrave, Abp., his tomb, 42. Mytholmroyd, 444. Myton, "Chapter of Myton," stained glass in the church.

N

NABURN, 18.

Nafferton, 148.

Nappa Hall, 317. Nelly Ayre Fore, 196. Neswick Hall, 145. Netherside, 399. Neville, family of, 156. Nevison, a famous free-booter, his supposed residence, 222, 447. Newbiggin, 349. New Building, 222. Newburgh Park, Cromwellian relics at, 237. Newby Hall, collection of sculpture, 294. - Wiske, 299. Newcastle, Marquis of, siege of Hull by, 100. New Hall, 353. New Hertford river, 182. Newlay, 425. Newton, 194. —— Dale Well, 195. Hall, 487. House, 19 – Kyme, 487. – ·upon-Ouse, 74. -le-Willows, 302 Nidd, river, 74, 260, 262, 272, 289. Nidderdale, 271. Nine Standards, 335. Normanby, Marq., 205. Yorkshire.

OTLEY.

Normans in Yorkshire, xvi. Normanton, 481. Allerton. North Sydney Smith's "Black Swan" inn. 224; its ale, history, 224; church, 225; grammar-school, celebrities, moes, scene of the battle of the Standard, 225. to Leyburn, 301.

North Burton, 190.

- Cave, 91. - Dean junction, 471. - Grimstone, 154.

Newbald, 91. Northumberland, Duke of, 336.

Norton, 80, 168. family of their activity in rebellions, 295; brauces of, at Wath, 296; their attainder, 397.

Conyers, ancient home of the Nortons, afterwards

of the Grahams, 295. Nostel Priory, history of the Augustinian establishment, 463; the modern house, its collection of pictures, 464; library, 465. Notton, 480. Nun Appleton Hall, seat of the Fairfaxes, 84.

Nunburnholme, 120. Nunkeeling, 151. Nun Monkton church, 74. Nunnington, 240. Nunthorpe junct. stat., 216. Nutwith Camp, 294.

OAKEMBRAW, 481. Oaks Colliery, accident at. 472. Oakwell Hall, 448. Obtrush Roque, 250. Old Malton, Priery, 167; remains of church, 167. Olicana, site of, 383. Oliver's Mount, 178. Ormesley, 218. Ormsby, 232. Gemotherley, 226. Oswaldkirk, 242 Oswi, King of Northumbria. 200; at the synod at Whitby, 200; his grave, 201. Oswin, King of Deira, murder of, 335. Otley, 268; church, monuments, 379; manor-house,

PICKERING.

Otley Chevin, magnificent view from, 380. Otterington, 224. Ottringham, 111. Oughty Bridge, 494. Oulton, 361. Ouse river, 10, 74, 90, 101. Overton church, 74. Owston, 78; Hall, 78. Owthorne, disappearance of church and churchyard, murder in the vicarage. 117.

PACHILL, or Paul. 120. Palet Hill, 325. Paley, Archdeacon, his birthplace, 408; his school, 408. Rev. Wm., brass plate to his memory, 408. Palliser, Wm., Abp. Cashel, 225. Pannal, 378. Park Foss, 273. Parke, Baron (Lord Wensleydale), his birthplace, 312. Parlington, 482.

Pateley Bridge, 272. Patrick Brompton, 302. Patrington, 112; church, one of the glories of Yorkshire, its antiquity, 112; Lady chapel and Kaster sepul-

chre, 114. Paulinus, with, and conversion of, Edwin of Northumbria, 130; tradition of, at Brafferton, 252; tradition of, at Dewsbury, 449.

Penhill, 313. Penistone, junct. stat. church. entrenchments near, 401.

Penyghent, 410. Pepper Hall, 229. Family, 83, ercy family, 83, 404; their state at Wressel, 105;

shrine in Beverley Minster, 137; chantry, 138; tombs, 137, 138.
Phillips on the geology of
Yorkshire, ix-xi.

Philpot, Alderman, fleet equipped by, 272; impeached and acquitted, 172. Pickering junet. stat., an-

tiquity, derivation of name, church, 191; castle, 191. - Lythe of, 191.

2 M

PICKERING.

Pickering, Vale of, 191. Pickhill, 299. Picton junct, stat., 215. Piercebridge, 336. "Pilgrimage of Grace," history of the rising so called, and its suppression, zviti-XX, 7, 393 Pilmoor, 216. Pinchingthorpe stat., 216. Pinder's Green, 465. Plumpton Park, 264, 267. Pocklington stat., good monuments in church, 127. Pompocali, site of, 488. Pontefract, situation, 353; castle, history and description of, 353-359; remains of church of All Saints, 359; cultivation of liquorice, 359. Pope, Alex., lines on the Duke of Buckingham, 240; on Str J. Cutler, 378. Poppleton, 256. Population of Yorkshire, vii. Port Clarence, 232. Potter, John, Abp. of Canterbury, 461. Pottery Carr, 8. Preston, 170. Priestley, Dr., his birthplace, 448. Proctor, Str Stephen, 201. Pudsey, 430.

QUEEKSBURY, 437. Quintin, St., family of, 140.

R RACECOURSE, near Richmond. fine view from, 312, Radeliffe, John, founder of the Radchiffe Library, 225, 461. Radiett, 76. Railways: Great Northern, 2, 352, 430, 438, 457 Hull and Witherness. Lancashire and Yorkshire. 466, 471, 490. Manchester, Sheffield, and Lincolnshire, 496 Midland, 419, 424, 508. North - Eastern, 104, 120, 147, 152, 156, 218, 230, 230, 252, 256, 268, 274, 701, 323, 336, 372, 481.

RIPLEY CARTLE.

Railways: North Midland, 479 North-Western, 446. North Yorkshire and Gleveland, 208, Filey, Scarborough to

Flamborough Head and Bridlington, 181. South Yorkshire, 514. Rainsborough, Gen., slain. 7. Raisegill Hag, 401. Ralph Cross, 210. Ramegill, 272.

Raskelf, 219. Ravensor (Shakspeare's Ravenspurg), 116.

Rawcliff, 103. Rawden, 425. Rawmarsh, 514. Raydale, 318. Redcar, 232.

Red Hill Tunnel, 77 Red House, 75. Redmire, 310, 314.

Reeth, 333. Reighton, 184. Religious houses in York-

shire, xvk. Rere Cross, camp of, 345. Reresby family, traditions

concerning, 514. Ribble, river, 407, 412, 419,

420. Ribblehe**ad, 413.** Ribblesdale, 410,

— Lord, 420. Ribston Hall, original " pippin " tree, ruins of preceptory of Knights Templars, 260.

Riccall, 15. Richard II., notice of his death, 355. Richard III., favourite resid-

ence of, his great popularity in Yorkshire, 308. Richardson, Dr., naturalist, his grave, 436. Richmond: history,

3261 castle, 327; parish church, grammar - school Trinity church, tower of the Grey Friam, 330.

Riddingsgill, 272. Riddlesden Hall, 428.

Rievaulz Abbey, first sight of, foundation and history of, 245; description of the ruins, 246. Rillington, 168; janct. stat.

190. Ripley, town - hall, church, 268.

- Castle, seat of the Ingelbys, 269.

BOLLE.

Ripon, 274; situation and history, 275; trade, 275; cathedral, 276-284; hospitals, 284; remarkable tumulus, 284; episcopal Dalace, excursions, 284.

Cathedral : history, 276; ground-plan, 276; front, 277; nave 278; mouruments, 278; stained glass in S. aisle, 279; central tower, 179; transepts, 279; choir-screen, 280; choir. stained glass, 260; choir-aisles, shrine of St. Wilfrid, 281; chapter - house, vestry, Lady Loft, crypt, 282.

Rise Bush, 123. Hell 121.

"Rising in the North." history of the, axi; crucities practised on its suppresklpon, sion, xxii ; at

275. Rivelin, river, 508. Rivers, Earl, his imprisonment and execution, 356. Rivet Hall, 197.

Robert, St., motice of his life, 263.

Robertson, Dr., Dean of Dur-

ham, 461. Robin of Redesdale, 112. Robin Hood, a favourite haunt of, researches concerning, perhaps a mythical personage, 79 ; an actual ersonage in Barnedale. bellads on, his Well, 80; tradition concerning, 20; his encounter with the "curtall friar of Foun-tains," 226; traditional scene and story of his death, his grave, 468. Robin Hood's Bay, 203.

- Butts, 203 Robin Lyth's Hole, 185. "Robinson Crusoe," 72.

Roche Abbey, rains of, 516. Rocking-stones on Brambana Crags, 269; Bear Atter-

myre, 410. Rockliffe, 215. Rogan's Seat, 33

Roger, Abp., his supposed tomb, 30.

Rokeby, 359; Roman camp, park, Sir W. Scott's visit and description, 319; Mortham Tower, the house,

340; church, 341. Rolle, Richard, the "Hermit of Hampole," Q.

BOLLESTON HALL.

Rolleston Hall, 110. Romaldkirk, effigy and brass in the church, 148. Roos. 118. - Carra, 118. Ros or Roos, family of, 243. Rosebery Topping, 213. Rosedale, 205; village, 205; iron-works, 205. Rossington, 3. Rother, river, 480. 410. Rotherham, 510; church, - to Bawtry, 516. -, Abp., his tomb, 41. Rougemont, 372. Routh, church, brasses, 140. Royal Marriage Act occasion of its possing, 16. "Royd," meaning of, 444. Royston, 480. Rudby, 215. Rudland Moor, 250 Rudstone-on-the-Wolds, 189; the "stone" which gives name to the parish, 190. - Walk, 190. -, Little, 190. -- Moor, Rumbald's earth-Works, 384. Runswick Bay, 207. Rupert, Prince, instance of his forbearance, 182. Ruskin, Mr., on Turner's Works, 380. Ruswarp, 197. Rye, river, 248. Ryclosf, 400. Rutland, Earl of, his death at Wakefield, 460.

Rylatone, the Nortons, 397; tower and mounds on Ryl-

Rymer, Thos., editor of the

stone Fell, 398.

Forders, 225.

Saddleworth, 456. Saltaire, great woollen factory, 425; church and schools, 427. Saltergate brow, 194. Sultburn-by-the-Sea, 234. Saltmarshe Hall, 90. Sancton, 92. Sanctuary, at Beverley, 138, Sandal, ruins of castle, 400. and Walton Stat., 461. Sandbeck, 516. Sanderson, Bishop of Lincoln, his grave, 502

SEDGEWICK. Sand Hutton, 158. Sandley Mere, 117. Sandsend, alum-works, 202. Savage, Archbishop, his tomb, Savile family, monuments to, Selside, 412. at Methley, 36c; memorials and tombs of at Thornhill, 466, 467.

—. Sir Henry, editor of Chrysostom, 443. Park, 443. foundation history, and description of, 421-423. Saws, manufacture of, 507. Saxton, 485. Scalby, 180. Scaleber Force, 409 Scampston Park, 168. Scarborough: stat., 169; hotels, railways, steam-434ers, situation, 169; history, 170; castle, history, and description of, 171-174; church of St. Mary, 174; spa, 175; museum, 176; St. Martin's church, 177; environs, 177; drives and excursions, 178. - to Bridlington, 181. -, Earl of, 516. Scarth Nick, magnificent views from, 255, 307, 310. Scawton, 239. Scorborough, 147. Scoresby, Dr. Wm., his birthplace, 198. Scorton, 323. Scott, Sir Walter, his visit to Rokeby, 339. Scriven Hall, 264. Scrope, Archbishop, his tomb, 41; his " Indulgence Cup, 47; place of his execution, 73; his version of Richard IL's death, his execution,

356. Scrope and Grosvenor controversy, 332. Scropes of Bolton, family of,

314; portraits, 313; their burial-place, 332. Scruton, 301.

Scugdale, 215. Seamer, 169, 181. - Mere, 178.

Seamerdale, 318. Seamer water, 318; tradition concerning, 318. Sedbergh, 321.

Sedburgh, Adam, last abbot of Jervaulx, executed, 305. Sedgewick, Adam, geologist, his birthplace, 321, 413.

SHERIPP VILLAGE.

Selby, 9; bridge over the Ouse, 10; tradition of the birth of Henry I., to; history of the Benedictine monastery, II: church, II-I4.

Sessay, brass in church, 210. Settle, old houses, 407. to Chatburn, 419. Settrington Beacon, 154. Seven-dales, 320.

Severus' Hills, 68. Sewerby, 189. Sexbow, 215

Shandy Hall (Sterne's residence), 237; meaning of "Shandy," 237. Shariston Hall, ancient por-

traits, 465. Sharp, Thos. and Abraham.

Sharpe, Archbishop, his tomb, 41.

Shaw, John, puritan vicar, his monument, 510. Shawl, the, view from, 306.

Sheaf, river, 497. Sheffield: hotels, 496; position, five rivers, cutlery trade, 497; the Cutlers' Company, 498; history, 498-500; St. Peter's ch., Shrewsbury Chapel and monuments, 499; Roman Cath. church, Cutlers Hall, oo; market, Shrewsbury Hospital, library, museum, 501; Botanical Garden, Wesleyan School, ceme-tery, 501; barracks, cele-brities, 502; steel manufactures, 503-507; mode of converting iron into steel, 503; shear and cast steel, 504; the Bessemer process, 504, 505; articles made of shear steel, 505; grinding, 506, 507; grinder's asthma, 506 saws, 507; file-making, 507; other manufactures. 507; great inundation of 1564, 508; canal, 508. — to Barnsley, 514.

- to Doncaster, 508. Shepherd, Joseph, memorial church to, 252.

Shepley stat., 491. Sherburn, church, skirmish at, 82; stat., 168. Sheriff Hutton Park, 156.

- Castle, 156; compared with Bolton, 157

village and church, 157.

SHIPLEY.

Shipley junct. stat., 425. Shipton, 129, 218. Mother, her reputed birthplace, 262. Shoddy trade and manufacture, 448. Shrewsbury, sixth Earl of, his letter to Queen Elizabeth, 499 - monuments at Sheffield. 499, 500. Shunnor Fell, 322, 335. - Howe, 204. Sigglesthorne, 124 Silkstone, collieries, church, 49 7. Silton. interesting church, 22 I. Shmon Howe, 195. Simon Seat, 389. Simon's Hall, 320. Sinclair, Rev. Enoch, murdered, 117. Sinderby, 299. Sinnington, 191, 252. Sittenham, home of the Gowers, 158. Skeffling, 115. Skelbrook, &c. Skeleton tours, xlfx. Skell, river, 288. Skelton church, 73, 254, 295. Castle, curious tenure, history, 235. Skerne church, 148; river, Skinningrove, 208. Skipsea Castle, remains of, 125. - Brough, 125. Skipton, 392; castle, the Cliffords, 394; church, gram-mar-school, celebrities, 395. - to Clapham, 523. --- to Ingleton, 402. - to Kettlewell, 397. Skipwith, church and common, 17; tumuli, 17. Skircoat Moor Orphanage, 443. Skirfare, river, 399. Skirlaugh stat., 122. - Beck, 122 -. Walter, Bishop of Durham, 122. Skirlington Hill, 124. Skye, Lale of, 455. Skyrack oak at Headingley. 370. Slack, Roman remains, ancient camp, 453. Slaithwaite, 455.

Sleddale, 212

Sledmere, 154. Sleightholmedale, 249.

Sleights Chapel, 196.

STAINED GLASS. Sleights stat, 197. Slingsby, 247; castle, church, 24I. monuments at Knaresborough, 260. —, Sir Henry, 79. Str Wm., discovers a spa at Harrogate, 266. Smeaton, Great, 229... —, John, his birthplace and residence, mural tablet, Smith, Sydney, his living and residence, 158. Smollett, his notice of the way of life at Harrogate, 265. Snaith, church, 102. Snape Castle, 299. Soar, valley of, 77. South Cave, residence of the Washingtons, 91.

Emsall, 352.

Frothingham Hall, 117. - Skirlaugh, 122. Southbank stat., 232. Southey's Doctor, scene of, 204. Sowerby Bridge, 443, 471. Spas, English, attention first attracted to, 170. Specton, 183. Spennithorne, 306. Spofforth, remains of castle, church, 490. Sprotborough, 477; church with stained glass, 477. — Hall, pictures, 478. Spurn Head, 114, 115. Spurs, Ripon famous for, 276. Staddlethorpe, 90, 108. Stafford, Thos., takes Scar-borough, beheaded, 172. Stainborough, 473. Stainburn, 381. Stained glass: at Doncaster, 4; at Bolton Percy, 83; in York Minster, 25, 27, 31, 74, 43, 44; in St. Denis, York, 51; in St. Martin's, York, 53; in All Saints', York, 54; in the Guitdhall York, 54; in the Gulidhall, York, 66; at Nun Monkton. 74; in Selby abbey-church, 12; in Holy Trinity ch., Hull, 98; at Hayton, 129; in Beverley Minster, 140; at Thirsk, 220; at Feliskirk, 221; at Kirkby Wiske, 224; at Kirkleatham, 233; in Gilling Castle, 240; at Myton, 256; in Ripon Cathedral, 279, 280; at Well, 298; at Tanfield, 297; at Wath, 206; at Kirklington, 209;

SWARTHOUS.

at Bedale, 30x; at Middlebeine, 308; at Brough Hall, 324; at Richmond, 330; at Methley, 361; at Leeda, 363; at Hallfax, 430, 440; at Wragby, 465; at Thornhill, 466. Stainforth, 85, 410. Stainland. angient CTOSS. 454 Staintondale cliff, 177. Stairfoot, 474. Staithes, 207. Staleybridge, 457. Stamford Bridge, battle of, Stanedge, 455. Stanley, 465. Stanningley stat., 430. Stansfield Hall, 446. Stanwick earthworks, 726 Park carthworks, 336. Stapleton Park. 81. Starbeck, baths, 265. Starbottom, 401. Stean beck, 277. Steel manufactures of Sheffield, 502-507. method of conversion. 503. Steeton, 420. —— Hall, 82. Stepney, 121. Sterne, Archbishop, his tomb. Lawrence, at Skelton, 235; his vicarage, 236. Stevenson, John Hall, Sterme's " Eugenius," 235. Stockmoor, 491. Stockton to Saltburn, 230. Stokesley, 212. Stoneraise, 318. Stonegrave church, 240. Storch Hall, 454. Stoupe Brow, 203. Stourton Castle, 250. Strafford, the Great Lord, at York, 58; his grave, 513. Strensall, 156. Strid, the, 389. Studiey Royal, 285; pleasuregrounds, fine view, 285. Stump Cross, stalactite caverns at 274. Stutton, 484. Sun-dials, ancient, 248. Sunk Island, 114. Sutton, 121. Sutton-en-the-Forest, 216. Swale, river, 19, 252, 256, 201 300, 311, 326, 334. Swaledale, 333. Swarcliffe Hall, 260

Swarthone Cross, 204

SWILLINGTON.

Swillington, 362, 482. Swine, church, monuments, 122 Swinefleet, 90. Swinemunde, 122 Swinithwaite Hall, 214. Swinton junction, 514. - Park, pictures, 298. Sydney Smith, 158. Sykes, Sir Tatton, notice of.

154, 155. TADCASTER, ancient bridge, derivation of name, church, 486; monastery of St. Heiu, 487. Tallgarth Hill, 194. Tancred Christopher, curious mode of interment of, 250. Tanfield, 206; Marmion tombs and other monuin the church. stained glass, 297-Tankersley Park, 515. Tansbelf stat., 360. Tate, James, master of Richmond Grammar - school, memorial of his labours. 330. Taylor, the water-poet, in the "Dragon's Den," 495. Tees, river, 220, 230, 336, 342, 349. Templeborough, permanent Roman camp, 509. Templehurst, 9. Temple Newsam, history, collection of pictures, 371; park, 371. Thieves' litany, 94, 442. Thievesdale, 486. Thirkleby, 220. Thirlwall, Bp., 128. Thirsk, interesting church, stained glass, 219 — to Malton, 230 William, Abbot of Fountains, bis resigns office, executed at Tyburn, Thixendale, 128, 154. Thomas of Brotherton, 82. Thomason Foss, 195. Thougsbridge, 401. Thoresby, Archbishop, his great services, 30.

Ralph, his birthplace, 368. Thornborough, earthworks

at, 297.

Thorne, 89 Thorngumbald, 111.

TURNER_

Thornhill, church, Perp. glas memorials and tombs of the Saviles, remains of their Hall, 466, 467. - junction, 449.

--- Lees, 466. Thornton (Charlotte Bronts's birthplace), 437.

- church, 190. - -le-Dale, 192.

- Force, 418 - in Lonsdale, 419.

Rust, 317. - -le-Street, 221.

- Hall, 223. Thornthorps, British came at, 168.

Thorpe Arch, 487.
—— Hall, 91, 190, 371.

- Perrow, 299.

— Salvin, 517. — -in-the-Street, 129.

Thorsgill, 347. "Three Marys," the, by Annibale Carracci, 162. Threshfield, 398.

Thrybergh, remarkable cross,

514. Park, 514. Thurgoland, 494. Thwaite, 334 Tibthorpe, 146. Tickhill, 3; ruins of castle,

with important church monumenta, 517. Tiliotson, Archbishop, birth-

place, 443. Tinsley, 509. Todmorden, cotton - works.

446. , vale of, 44%.

Tollerton, 218. Topcliffe, brass in the church,

a lordship of the Percys. 300. Tosside, 421.

Towton, 484; the battle, 484; the battle-field, 485. Trafford, Wm., Abbot of Saw-

ley, hanged, 422. Traveller's view, xxxviiixlviii.

Treeton church, 479. Trenholme, 214. Trent junct. stat., 77.

Troutedale, 180. Trowler's Gill, 391. Tunstall, 118.

Bishop of Durham, his birthplace, 304.

Turner family, 233.

_____ J. M. W., his works

at Farnley Hall, 180.

WALPOLE.

T

ULP. Danish Jarl of Deirs. 119. Ulleskelf, 83. Ulrome, 125. Undercliffe, 437. Upleatham Hall and church, 226. Upsall Castle, 222. Ure, river, 19, 253, 294, 295, 307, 312.

VAVASOUR family, ancient, seat and monuments of, 485. Vermuyden, Cornelius, drainage of Hatfield Chase by. 86; "Dutch River" cut

by, 103. Vernon-Harcourt, Abp., his tomb, 28.

Victoria Cavern, animal remains and Roman relics found in, 408, 409. Villiers, George, Dryden's Duke of Buckingham, 84.

Vyner, Lady Mary, 204.

WADDINGTON HAM. Henry VI. at, 420. Wade's Causeway, 206. Wadaley Bridge, 496. Wadworth, remarkable effigy in the church, 3.

in the cnurca, 3.

Waghen, 121.

Wakefield: trade, 457; the

"pinder," 458; parish ch.,

Corn - Exchange, 458;

Chantref, 459; the battle,

459, 460; 50ke mills, 460;

lunatic asylum, grammar
chael 451; celebrities. school, 461; celebrities, 461; prison, 461. — to Doncaster, 471.

to Halifax, 466.

Walburn Hall, 311. Waldendale, 313.

Walker, Samuel, his celebrated fron-works at Mas-

borough, 509, 510.

— William, supposed executioner of Charles L, Em

Walpole, Horace, his description of Sheffleld, 497; of Roche Abbey, 516.

WALTON HALL

Walton Hall, 461-463. Wandesford, Sir Christopher, 299. --- Hall, 299.

Wansford, 140

Wantley, the Dragon of, 405, 496.

Ward, Baron, minister of the Duke of Parma, his birthplace and remarkable career, 108.

Warmsworth, 478. Warter Priory, 129.

Washington tamily, 9, 91. Wassand Hall, 124 Watering places, xl.

Waterton, Chas, naturalist, his preserves and collections at Walton, 461-463; his mausoleum, 46;

- Sir Bobert and wife. tomb and efficies at Mechley, 361.

Wath, 296; monuments, brases, and stained glass

in the church, 296. unon-Dearne, 474. Watling Street, 79, 335, 353.

Watton Priory, 147. Weaponness, 178. Weathercote Cave, 417.

Weaverthorpe, 155. Webster, John, author of Discovery of supposed

Witchcraft, 237, Weeton, 178.

Weibury, 229. Well, church, monuments,

208. Welles, Lionel Lord, and wife, tomb and efficies at Methley, 361.

Sir Robert, executed, 7.

Wellingborough, 76. Welwick, church, remark-

able monument, 114. Wensley, 312; interesting church, fine brass, early Saxon fragments, 313.

Wensleydale, 112. Went, valley of the, 80.

- bridge, 8o. Wentworth Castle, collection of pictures, 473, 474.

Woodhouse, seat of the Earl Fitzwilliam, 511; collection of pictures, 512, 513; cellars, 513; church tombs with effigies, 513.

- family of, 511. . monuments, 42.

West Bretton, 471.

– Burton, 314. - Lutton, 155.

- Newton Grange, 242.

WILRER PORK

West Witton, 313. Whale-fishery, 95. Westerdale Moor and village, 211.

Weston Hall, 382. Westwood, 515.

Wetherby, 488. Wetwang, 146, 155. Wharfe, river, 372, 375, 379, 391, 398, 488; vale of, 382;

source of, 402, 412. Wharncliffe, 494. Wharram-le-Street, 154.

Wheeldale stream, 196.

— gien, 195.
Whernside, 418.
Whithy: hotels,conveyances,

situation, trade, 197; sea-views, promenades, 198; the Abbey, 198, 199; history, 200, 201; churches, museum, 199; jet found near, 200; Walks and excursions from, 202.

to Guisborough and Middlesbrough, 216.

- to Stockton-upon-Tees, 208.

Whitcliffe Wood, 316. Whitecross, 204. Whitedale, 123.

White Force, 15t. - Hall, 112. - Horse, figure of, on the

Hambleton Hills, 219. - Mear, 223. Whitestone Cliff, 221, 222. Whitewall training establish-

ment, 168. Whitfell Force, 318. Whitgift, 90.

Whitkirk, 372, 481. Whitley Bridge, 102.

– Hall, 259. - Park, 451.

Whitwell, 158. Whixley Hall, residence of the Tancreds, 259.

Whordale, 382. Whorlton, church, Meynill monuments, 214; remains

of the castle, 214. - Bridge, 343.

Wickersley, 511. Wickliffe, John, his supposed birthplace, 330, 342; portrait of, 343.

Widdale, 120. Wighill, 487.

Wilberforce, notice of, by Boswell, 66; his birthplace and monument, 97. -, derivation of the name.

Wilberfoss, 127.

WRESKEI.

Wilfrid, Abp., repairs King Edwin's church at York, 20.

St., monastery erected by, at Ripon, 275; his shrine in Rinon cathedral, 261. Willance's Leep, 311. Willey-houe, legend of, 190. William do Hatfield, h `hle

tomb, 40. St., Abp. of York, his burial-place, 31; his chrine and history, 37.

Wilmington, 121. Wilton Castle, 234. Winch Bridge, 349. Wincobank, earthworks on,

Winestead, 112. Winston, 336. Wiske, river, 220. Wissenden, 455. Withernsea, 116.

Witton, East, 310. - West, 313.

Wode, Wm., prior, executed, r 88. Woden Croft, 348. Wold Newton, 190.

Wolds, the, 152. Wolf, the last slain in Yorkahire, 362.

Wolsey, Card., at Cawood, 15: his last days, 499. Wombwell, 474. - Sir G. O., 237.

Womersley, 81. Woodhouse Mill, 479. - Moor, 366.

Woodlesford, 361. Woodsome Hall, 453. Woollen trade and manufac-

ture xxxiii-xxxviii Woolley Hall, 471; church,

— Edge, 471. Wordsworth family, 492. Wormald Green, 274. Worsborough, 474.
Worsted manufacture, xxxiii-

xxxviii., 438. Worth, river, 428.

Wortley, 494.

Hall, 494.
Sir Thos., his hounds, legend concerning him,

Montagu, Lady Mary, her residence at Wharncliffe, 495. church, painted

Wragby, c Wreke, river, 77.

Wressel, stat. and custle 105.

WRIGHT.

Wright Mr., his suggestion concerning Robin Hood,

John and Christopher (of the Gunnowder Plot). their residence, 114. Wycliffe, village, 142; church,

343. — Hall, 343. Wyke, Scandinavian name of Hull, 93.

Wykeham, 181. Wyming brook, 508.

Ŧ

Yarm, 215. Yew-trees, ancient, of Fountains, 288.

Yordas Cave, 419.

York: station, hotels, railways, 18; situation and derivation of the name, 18, genvation of the name, 10, 139 history, 65-71; Minster, 19-50; Rom. Cath. Procathedral, 50; Churche, 50; St. Michael-le-Beilry, Holy Trinity (Goodramgate), site of St. Helen's on the Walls, Christ church, 51; St. Saviour's, St. Cuthbert's, St. Denis, 51; St. Marga-ret's, St. Lawrence, All Saints' (Pavement), Sampson, St. Helen's, 52; St. Martin's, St. Michael's, St. Mary's, St. John's, All Saints' (North-street), 53; St. Mary (the Elder and the Younger), 54, 55; St. Mar-tin's cum Gregory, Holy Trinity (Micklegate), 55; St. Mary's Abbey, 55;

YORK.

grounds of the Yorkshire Philosophical Society, 55-61 : City walls, 61 : gates and bars, 61, 62; the castle, Mansion - house, 6:-66: 6j-66; Mansion-house, Guildhall, 66; St. An-thony's Hospital (Blue-coat School), St. William's College, old houses, 67; the Retreat (asylum for the insane), 67; Severus' Hills, races, 68; cele-bettes under the control of the better of the control of the college was a control of the college of the colle brities, 71; excursions.

York Minster: materials for its history, 19; ground-plan, 21; churches preceding it, 20; dates and architectural character of its different portions, 22; its great reputation and general character, 22; S. transept, exterior, 23; view on entering, 24; S. transept, interior, stained glass, monuments, 25, 26; narrow arches in transepts, 26; N. transept, stained glass, monuments, 27, 28; nave, 28-31; great W. window, 30; monuments and stained glass in the nave, 31; chapter-house, stained glass, 32-34; choir and presbytery, 35; shrine of St. William, 37; choir aisles, 38; E. window, 39; monuments in N. choir aisle, 40; in presbytery, 40; in S. choir aisle, 42; stained glass in choir aisles and E. window, 43, 44; crypt, 44; central tower, 45; choirscreen, 46; organ, 46; re-

ZETLAND.

treasury, 46; exterior, 47-49; W. front, 47; N. side of nave, N. transept, 48; chapter-house, 49; E. end of choir, 49; library, 50.

York to Boroughbridge and Aldborough, 252.

to Beverley and Hull, 124.

- to Darlington, 218.

to Knaresborough and Harrogate, 256. - to Market Weighton,

125. - to Richmond, 323.

- to Scarborough, 156.

- to Whitby, 190. -. Archbishops of, their struggle for supremacy.

- Richard Duke of his death at Wakefield, 450,

Yorkshire: extent and gene-ral character, vii; geology, ix; history, xili; antiquities, xxiv; resources and manufactures, xxxi; tra-veller's view and scenery, xxxviii; skeleton tours. xlix.

Philosophical Society. grounds of the, 55; Multangular Tower, 55; St. Leonard's Hospital, 56; ruins of St. Mary's Abbey, 56; remains of the abber church, 57; St. Olave's church, 57; museums, 50.

cord - room, vestry, and Zetland, Rari of, 236, 226.

LONDON:

PRINTED BY WILLIAM CLOWES AND SONS, LIMITED, STANFORD STREET AND CHARING CHOSS.

HANDDOOK ADVEDTICED 1000 09

HANDBOOK	ADVERTIS	ER, 1882–83.	
CONTENTS. FOREIGN AGENTS:—J. & B. McGRACKEN			
FOREIGN AGENTS:-J. & B. McGRACKER			
RAILWAY AND STEAMBO		PAGE 9	
BARROW BOUTE TO TE			
CALEDONIAN BAILWAY	STEAM PACKET COMPANY		
GENERAL STEAM NAVI	GATION COMPANY		
OT ASSOCIATE AND THE HIS	GHYANDS—BOYAL BOUTE	· · · • •	
GLASGOW AND SOUTE-	WESTERN RAILWAY	A 9	
GLASGOW, BELFAST, B. GREAT EASTERN RAUL	RISTOL, CARDIFF, AND SWANLE		
LONDON AND SOUTH-W	BOTERN BAILWAY	•	
MIDLAND RAILWAY .		7	
HOTELS AND MISCELLANEOUS ADVERTISEMENTS.			
PAGE	PAGE		
ARERYSTWITH 9	EGGISCHHORN 28	ODESSA	
AIX-LES-BAINS 10	EMS ,	OSTORD 51	
AIX LA CHAPELLE 11	ENGELBERG	PARIS	
ALEXANDRIA (BANK OF) 40 AMIENS	FRANKFORT 28	PAU	
ANTWERP	GENEVA	PERTANCE . 55, 56	
AVIGNON 19	GENOA	PEGLI	
AVRANCHES 12	GMUNDEN 29	PEGLI 86 PIBA 87 PLYMOUTH 87, 88	
BADEN-BADEN 12, 18	GOTHA	PRAGUE 86	
BAGNÈRES DE BIGORRE . 13 BAGNÈRES DE LUCHON . 13	GRASSE	RAGATZ 57	
BÂLE	HAMBURG 80	RIGI	
BAMBERG 14	HANOVER 81	ROME 60, 61 ROTTERDAM 61	
BARCELONA 14	HARROGATE 81	BOME 60, 61 BOTTERDAM 61 BOUEN 61, 62	
BELFART 14	HAVRE	BOYAT-LES-BAINS . 62	
BELLAGIO 14 BERLIN 14, 15	HEIDRIBERG . 32, 38 HOMBURG 32	BALISBURY 62	
BERLIN 14, 15 BIARRITZ . 16	HYRRES	SAN REMO 68	
BOLOGNA . 18, 16	ILFRACOMBE 84	SAN SERASTIAN 63	
BONOR . 16	INNSBRUCK 84	SALZBURG 62 SCHAFFBAUSEN 50	
BORDEAUX . 16 BOULOGNE-SUR-MER . 16	INTERLAKEN	SOHWALBACH 63, 66	
	EILLARNET 87	SEVILLE 64	
BOTZEN 15 BREMEN 17	K1881NGEN	SHANKLIN	
PRIORE 17	LAUSANNE 87,88	SHEFFIELD 66	
BRUSSELS 17-19	LEAMINGTON	SOUTHPORT 66 STUTTGART 66	
BRUSSELS . 17-19 BUXTON 19 CAEN 19	LISBON	SPA 64	
CAEN	LOCH LOMOND	STOCKHOLM 65	
CAIRO	LONDON 39-44, 76	STRASBURG 66	
CASPET.LAMARE . 31	LUCERNE 44-45	THUN	
CHAMONIX 21	LYNTON . 45	TOTNES 67	
CHAUMONT 21	LYONS 48	TOURS 66	
00201201	MARIENBAD	TURIN 67,68	
	MAYENCE 46	VARIESE 68	
COBLENTZ	MENTONE 46, 47	VENICE 68	
COMMITANTINOPLE . 94	METZ	VEBONA 68 VEVEY 70	
COPENHAGEN 94	MILAN 47, 48 MOFFAT 48	VICHY 70, 71 VIENKA 69, 70	
	MULHOUSE 48		
ONWES 26	MUNICH 48, 49	WIESBADEN . 70, 71, 72	
DIEPPE 26	NAPLES 49	WILDBAD 73 WURZBURG 73	
DLTON 25, 26	NERVI	ZARAGOZA	
DINABD 96	NEUCHATEL 49, 80, 51	ZUBICH 78, 74	
DOVER	NURMINEBO 51		
Caracter Care			

MESSRS. J. & R. MCRACKEN.

38. OUEEN STREET, CANNON STREET, E.C.,

AGENTS. BY APPOINTMENT. TO THE BOYAL ACADEMY, MATIONAL GALLEBY. AND GOVERNMENT DEPARTMENT OF SCIENCE AND ART.

GENERAL AND PORTIGN AGENTS.

WINE MERCHANTS. Agents for Bouvier's Neuchatel Champagne,

FOR THE RECEPTION AND SHIPMENT OF WORKS OF ART, RAGGAGE, &C., FROM AND TO ALL PARTS OF THE WORLD.

Avail themselves of this opportunity to return their sincere thanks to the Nobility and Gentry for the patronage hitherto conferred on them, and hope to be honoured with a continnance of their favours. Their charges are framed with a due regard to economy, and the same care and attention will be bestowed as heretofore upon all packages passing through their bands.

DRY AND SPACIOUS WAREHOUSES.

Where Works of Art and all descriptions of Property can be kept during the Owner's

absence works on Arts and an descriptions of reoperty can be kept during the Owner's absence, at most moderate rates of rent.

Parties favouring J. and B. McC. with their Consignments are requested to be particular in having the Bills of Lading sent to them DIRROT by Post, and also to forward their Keys with the Packages, as, although the contents may be free of Duty, all Packages are still EXAMPIRED by the Customs immediately on arrival. Packages sent by Steamers or otherwise to Southampton and Liverpool also attended to; but all Letters of Advice and Bills of Lading to be addressed to 88, QUEEN STREET, as above.

> AGENTS IN ENGLAND OF MR. J. M. FARINA, GEGENÜBER DEM JULICH'S PLATE, COLOGNE,

CELEBRATED EAU DE COLOGNE.

MESSRS. J. AND R. MCCRACKEN'S

PRINCIPAL CORRESPONDENTS. ALGIERS Mr. P. DESSEIGNE. ALEXANDRIA.... Mr. A. MONFERRATO. Mr. P. B. Dahlander ANCONA destra. Moore, Money, LET. & Co. Messya, F. Monerin & Co. Mr. H. W. Thing. Mr. Che, De J. Perriswere, Mr. J. J. Frey. Mr. Lion M. Coem, Comm^{ro}, Expéditeut. ANTWERP BAD EMS..... BASLEBERLIN BERNE Meesrs. A. BAUER & Co. BEYROUT Mesers. HENRY HEALD & CO. BOLOGNA Messrs. Renoll, Buggio, & Co.

BOMBAY Mesers. King, King, & Co. Mesers. Albuncht & Fils. BORDEAUX BOULOGNE s. M Messrs. Mony & Co. BRUSSELS Mossys. Verstraften De Meurs & Fila.

CALAIS..... Mousts. L. J. Voque & Co.

CALCUTTA..... Messrs. King, Hamilton & Co. CAIRO Mr. A. MONFERRATO. CANNES..... Mesers. J. TAYLOR & RIDDETT.

CARLSBAD. Mr. THOMAS WOLP, Glass Manufacturer. CARRARA. Sig. F. BIRNAIM &, Scalptor,

CHRISTIANIA Mr. H. HEITMANN. OOLOGNE

Mr. J. M. Farma, gegenübzs tiem Jülicha Platz. CONSTANTINOPLE Mr. ALPRED C. LAUGHTON.

MCCRACKEN'S LIST OF CORRESPONDENTS—continued.

MORVOTEM & PIRI, OL SORETRIONITEM IS—communer		
OPENHAGEN	Messrs. H. J. Brmg & Sou.	
CORFU	Mr. J. W. Taylor.	
DRESDEN	Messrs. Schlobsmeane & Schlpfler. Messrs. H. W. Bassenge & Co. The Director of the Royal Poscelain Manufactory Depôt.	
DIEDEL	The Director of the Royal Poscelain Manufactory Depôt.	
4	Mesers, France & Co. Sig. Luiei Ramagol. Mesers, Emma, Frazzi & Co. Sig. Tito Gagliardi, Dealer in Antiquities, Mesers, Maquay, Hooker, & Co. Mr. E. Goodran, Printseller, Mr. T.	
FLORENCE	MANUAL HOUSE & CO. Mr. C. Conner Drintelles, Messis.	
PLADE BANCE	BLANCHIMI, Mosaic Worker. Mesers. P. BAZZARTI & Fig.	
	Sculptors, Lungo l'Arno.	
FRANKFORT o. M.	Massrs River Inn & Co. Mr G Knyne	
GENEVA	MM, LEVRIER & PELISARE.	
GENOA	MM, LEVERR & PÉLIMER. MESETS, G. & E. BARGHI BROTHERS. Mr. C. A. WILSON. Mr. H. A. Mossa, Grande Albergo d'Italia.	
GENOM:	Mr. C. A. Wilson. Mr. H. A. Mossa, Grande Albergo d'Italia.	
GIBRALTAR	Messis, John Pracock & Co.	
HAMBURG	Messys. J. P. Jenski & Co. Messys. Sohörmer & Triohmann. Mr. Ph. Zimmermann.	
HELSING FORS	Mours. Luters & Rudolph.	
INTERLACKEN	Mr. J. Grossmann.	
JERUSALEM	Meegra, E. F. SPITTLER & Co. Mr. M BERGHEIM, Jun.	
KISSINGEN	Mr. DAVID KEGELMANN. Mr. H. F. KUGELMANN.	
LAUSANNE	Mr. Dunous Ramou & File.	
LEGHORN	Mesers. Alex. Maghan & Co. Mesers. Maghay, Hoosen, & Co.	
LUCERNE	Messes. F. Knorn & Fils.	
MADRAS MALAGA	Меаяга. Винит & Co. Мг. Свовек Норскоп.	
MAILAGA	Mesars. Josh. Darmanin & Sons, 45, Strada Levante, Mosaic	
MALTA	Workers Mr Roservano Testa 92 Strade Sta Lords. Mosern	
	Workers. Mr. Fortunato Testa, 92, Strade Sta Lucia. Messis. Turnbull Jun. & Somreville.	
MARIHNBAD	Mr. J. T. Adlen. Gless Manufacturer.	
Marskilles	Mesecs. E. Calleot and H. Samtterne.	
MENTONE	Mt. Palmano. Mt. Jran Orengo Fils.	
MESSINA	Mesers, Callers, Walkers, & Co. Mr. G. B. BUFFET, Plasse di S. Sepolero, No. 1. Macore, Physics C. Macore III.	
MIT AN	Mr. G. B. BUFFET, Plassa di S. Sepoloro, No. 1.	
MILLAND	Mr. G. E. BUFFF, Plana di S. Sepokro, No. 1. Messrs. Fratzlii Branzilla. Messrs. Ulrich & Co Messrs. G. Boso & Co MessrsWinners & Co., Printsellers. Brienner-Strasse.	
MITNICH	Mesers. Winners & Co., Printsellers, Briemer Strasse.	
WARE THE	Mosers. W. J. Turnes & Co. Mr. G. Scala, Wine Merchant. Mesers. G. Oursta & Co. Mesers. Certuil & Co.	
NAPLES	Montra, G. Quinta & Co. Montra, Curtilli & Co.	
NEUCHATEL		
(SULASE)	Messrs. Bouvren Friens, Wine Merchants.	
NEW YORK		
NICE NUREMBERG	Madame V** ADOLPHE LAGROIX & Co.	
OSTEND	Mr. A. Picker, Dealer in Antiquities.	
PALERMO	Mosers. B. St. Amour & Son. Mosers. Ingham, Whitaker, & Co.	
PARIS	Mr. L. CHEMUE, Packer, Rue Croix des Petits Champs, No. 24.	
PATT	Mr Minoraus Clay.	
PIRA	Mesers. Husver & Van Lier, Sculpton in Alabaster and Marble.	
DD 4 CITT	Mesers. HUGUER & VAN LERR, Sculptors in Alabaster and Marble. Mr. G. ANDREONI, Sculptor in Alabaster. Mr. W. Hownaws, Glass Manufacturer, Bismers Stern. Mr. W. Hownaws, Glass Manufacturer, Bismers Stern. Manufacturer, Manufact	
PRAGUE	Mr. W. Hormann, Glass Manuscurer, Bianers Stern.	
ROME	Mossers. Plowden & Co. Mossers. A. MacBran & Co. Mossers. Maquay, Hooken, & Co. Mossers. Spada & Flamini. Mr. J. P. Shira. Mr. A. Tombini.	
COMMITTED TO STATE OF THE STATE	J. P. Sima. Mr. A. Tomrini.	
ROTTERDAM	Massey Present & Co.	
SAN REMO ST. PRTERSBURG.	Mesers. Fratelli Asquasciati.	
ST. PRTERSBURG.	Messys. Frayelli Asquasciate. Messys. Thomson, Bohar, & Co. Mr. C. Krugke. Messys. Olsson & Wright.	
STOCKHOLM	Meesrs. Oleson & Wright.	
THOUNE	Mp. Jean Behrli-Seerchi.	
TURIN	Mesers, Fill, Chiesa. Mesers, Rochas, Père & Fils.	
TOBLE	(Mr. I. Rovarni, Ponte alie Ballotte.	
VENICE	Mr. L. Bovardi, Ponte alle Ballotte. Messys. S. & A. Blumesthal & Co. Mr. Carlo Posel.	
VEVEY	Mr. Jules Gétaz Fila.	
	Mr. Jules Gétaz File. Mr. H. Ullenus, Glass Manufacturer, 16 Kärnthner Stresse. Meesra, J. & L. Losekster, Glass Manufacturers, 13, Karnthner Stresse. Mr. Peres Commones.	
VIENNA	Messra J. & L. Lobinsvin, Glass Manufacturers, 13, Karnthner	
.,	Strame. Mr. Perza Compacter.	
ZURICH	Mr. Orbil Hess.	

TOURS IN SCOTLAND.

THE CALEDONIAN BAHWAY COMPANY have arranged a system of Tours—about 78 in number—by Rail, Steamer, and Coach, comprehending almost every place of interest either for scenery or historical associations throughout Scotland, including—

EDINBURGH, GLASGOW, ABERDEEN, DUNDEE, INVERNESS, GREENOCK, PAISLEY, DUMFRIES, PEEBLES, STIRLING.

PERTH, CRIEFF, DUNKELD, OBAN, INVERARY,

The Tresachs, Lech-Katrine, Lech-Lomend, Lech-Earn, Lech-Tay, Lech-Awe, Caledonian Canal, Glencoe, Iona, Staffa, Skyc, Balmeral, Braemar, Arran, Bute, The Firth of Clyde, The Falls of Clyde, &c., &c.

TOURISTS are recommended to procure a copy of the Caledonian Railway Company's "Tourist Guide," which can be had at any of the Company's Stations, and also at the chief Stations on the London and North-Western Railway, and which contains descriptive notices of the districts embraced in the Tours, Maps, Plans, Bird's-eye View, &c.

Ticksts for these Tours are issued at the Company's Booking Offices at all the large Stations.

The Tourist Season generally extends from Junz to September inclusive.

The Caledonian Co. also issue Tourist Tickets to the Lake District of England, The Isle of Man, Connemara, The Lakes of Killarney, &c.

The Caledonian Railway, in conjunction with the London and North-Western Railway, forms what is known as the

WEST COAST ROUTE

BETWEEN SCOTLAND & ENGLAND.

DIRECT TRAINS BUN FROM AND TO

Glasgow, Edinburgh, Greenock, Paisley, Stirling, Oban, Perth, Dundee, Aberdeen, Inverness, and other places in Scotland.

TO AND FROM

London (Euston), Birmingham, Liverpool, Manchester, Leeds, Bradford, and other places in England.

SLEEPING & DAY SALOON CARRIAGES. THROUGH GUARDS & CONDUCTORS.

The Caledonian Company's Trains, from and to Edinburgh, Giasgow, Carlisle, &c., consect on the Clyde with the "Columbia," "Iona," "Lord of the Islea," "Ivanboe," "Geel," and other steamers to and from Duncon, Innellan, Botheray, Larga, Millport, the Kyles of Bute, Arran, Campbeltown, Ardrisbalg, Inversary, Loch-Coll, Loch-Long, &c.

A full service of Trains is also run from and to Glasgow, to and from Edinburgh. Stirling, Ohn, Perth, Duadee, Aberdeen, and the North; and from and to kidinburgh, to and from these places.

For particulars of Trains, Fares, &c., see the Caledonian Railway Company's Time Tubles.

It is expected that the Caledonian Company's large and magnificent
NEW CENTRAL STATION HOTEL, GLASGOW,

will be opened during the Season of 1882, under the Company's own Management.

GENERAL MANAGER'S OFFICE, GLASGOW, 1882. JAMES THOMPSON, General Manager.

GLASGOW AND SOUTH-WESTERN RAILWAY.

DIRECT ROUTE BETWEEN

SCOTLAND & ENGLAND.

THROUGH TRAINS ARE RUN BETWEEN

GLASGOW (St. Enoch) and LONDON (St. Pancras),

Fig the GLASGOW & SOUTH-WESTERN and MIDLAND RAILWAYS,

Giving a Direct and Expeditious Service between

GLASGOW, GREENOCK, PAISLEY, AYR, ARDROSSAN, KILMARNOCK, DUMFRIES, &c., AND

LIVERPOOL, MANCHESTER, BRADFORD, LEEDS, SHEFFIELD, BRISTOL, BATH, BIRMINGHAM, LONDON, &c.

PULLMAN DRAWING-ROOM AND SLEEPING CARS
Are run by the Morning and Evening Express Trains between GLASGOW and LONDON.

FIRTH OF CLYDE and WEST HIGHLANDS, via GREENOCK.

EXPRESS and FAST TRAINS are run at convenient hours between

GLASGOW & GREENOCK

(St. Enoch Station) (Lynedoch St. and Princes Pier Stations)
IN DIRECT CONNECTION WITH THE

"COLUMBA," "IONA," "LORD OF THE ISLES,"

Kirn, Duncon, Innellan, Rothesay, Kyles of Bute, Ardrishaig, Oban, Inverary, Largs, Milliport, Kilereggan, Kilmun, Lochgoilhead, Garelochhead, &c.

Through Carriages are run by certain Trans between GREEROCK (Princes Pier), and EDIRBURGH (Waverley), and by the Morning and Evening Express Trains between GREENOCK (Princes Pier) and London (St. Pancras).

RETURN TICKETS issued to COAST TOWNS are available for RETURN AT ANY TIME.

Passengers are landed at Princee Pier Station, from whence there is a Covered Way to the Pier where the Statemers call; and Passengers' Luggage is conveyed FREN OF OHARDE between the Stations and the Statemers.

ARRAN AND AYRSHIRE COAST.

An Express and Fast Train Service is given between GLASGOW (St. Enoch), PAISLEY, and TROON, PRESTWICK, AYR, ARDROSSAN, FAIRLIE, &c.

From ARDROSSAN the Spiended Saloon Steamer "BRODICK CASTLE" sails daily to and from the ISLAND OF ARRAN, in connection with the Express Train Service.

Fast Trains provided with Through Carriages are run between AYR, &c., and GLASGOW, (St. Enoch), and EDINBURGH (Waverley).

IRELAND.

A NIGHTLY SERVICE is given by the Royal Mail Steamers via GREENOCK, and also by the ARDROSSAN SHIPPING COMPANY'S Full-Powered Steamers via ARDROSSAN.

For Particulars as to Trains and Steamers see the Company's Time Tables.

GLASOOW, May 1882.

W. J. WAINWRIGHT, General Manager.

LONDON AND SOUTH - WESTERN RAILWAY.

LONDON STATION, WATERLOO BRIDGE.

The Cheap and Picturesque Route to Paris, Havre, Rouen. Honfieur, Trouville, and Caen, via Southampton and Havre, every Monday, Wednesday, and Friday, The last Train from London at 9 p.m. goes into Southampton Docks alongside the Steamer. Farms throughout (London to Paris, Single Journey, First Class, 33s.; Second Class, 24s. Double Journey (available for One Month), First Class, 55s.; Second Class, 39s.

Jersey, Guernsey, Granville, and St. Malo. Daily Mail Service to Channel Isles, via Southampton (the favourite route), every Week-day. The last Train from London goes into Southampton Docks, alongside the Steamer, leaving Waterloo each Week-day at 9 p.m. (except on Saturdays, on which day the last Train leaves at 5.20 p.m., and the Steamer goes to Jersey only). FARES throughout (London and Jersey or Guernsey), Single Journey, First Class, 33a; Second Class, 23s.; Third Class, 20s. Double Journey (available for One Month), First Class, 48s.; Second Class, 38s.; Third Class, 30s. Direct Service, Southampton to St. Malo, every Monday, Wednesday, and Friday, according to Tide. The best Route for Dinard. Dinan, Bennes, Brest, Nantes, Laval, Le Mans, Angers, Avranches, &c.

Southampton to Cherbourg every Monday and Thursday. Last Train from the Waterloo Station, London, at 9.0 A.M. The best Route for

Valognes, Carentan, St. Lo, Bayeaux, and Coutsness.

steamers run between Jersey and St. Malo, and Jersey and Granville,

twice Weekly each way.

For further information apply to Mr. BENNETT, 3, Place Vendôme, Paris; Mr. LANG-STAFF, 67, Grand Qual, Havre; Mr. RNAULT, Honfieur; Mr. R. SPURRIER, Jersey; Mr. SPENCER, Guernsey; Mr. E. D. LE COUTEUR, 8t. Malo; Messa. MAHIEU, Cherbourg; or to Mr. E. K. CORKE, Steam Packet Superintendent, Southampion.

GREAT EASTERN RAILWAY.

THE TOURIST'S ROUTE TO THE CONTINENT IS viå HARWICH.

THE Continental Express Train leaves Liverpool Street Station, London, for Rotterdam every evening (Sundays excepted), and for Antwerp on Mondays, Tuesdays, Thursdays, and Saturdays, in direct connection with the Fast and elegantly fitted up Passenger Steamers of the Company.

It is expected that a Daily Service to Antwerp will be commenced on

July 1st, 1882 (Sundays excepted).

The Steamers are large powerful vessels, ranging from 800 to 1200 tons burden, with ample sleeping accommodation; and consequently Passengers suffer less from mal de mer than by any of the shorter Sea Routes.

The Provisions on Board are supplied from the Company's own Hotel at Harwich, and are unequalled in quality. Luggage can be registered through to all principal Towns on the Continent from Liverpool Street Station. Through Tickets are issued at-44, Regent Street; 48, Lime Street; and Blossom's Inn, Lawrence Lane, Cheapside, E.C.

Cook and Son's Tourist Office, Ludgate Circus, London, E.C. GAZE and Son's Tourist Office, 142, Strand, London, E.O.

O. CATGILL'S Tourist Office, 371, Strand, London, E.C.

And the Continental Booking Office, Liverpool St. Station, London, E.C. For further particulars and Time Books apply to the Continental Traffic Manager, Liverpool Street Station, London, E.C.

MIDLAND RAILWAY.

DIRECT ROUTE TO

EDINBURGH AND GLASGOW,

Vid SETTLE AND CARLISLE.

EXPRESS TRAINS, WITH PULLMAN PARLOURS CARS BY DAY. AND SLEEPING CARS BY NIGHT.

The Picturesque Route between London and Manchester and Liverpool, through Matlock and the Peak of Derbyshire.

Improved Express Service between London and Nottingham, Sheffield, Leeds, and Bradford.

The Midland Railway System (one of the largest in the United Kingdom), extending from LONDON in the SOUTH to LIVERPOOL in the NORTH-WEST, and from BOURNE-MOUTH and BRISTOL in the WEST to CARLISLE in the NORTH affords direct communication with all the manufacturing and business centres, including—

LONDON, LIVERPOOL, MANCHESTHR, NOTTINGHAM, GLASGOW, EDINBURGH, SWANSEA. PLYMOUTH,
BRISTOL,
BIRMINGHAM,
WOLVERHAMPTON,
LEICESTER,
DERBY,
DERBY.

SHEFFIELD, HUDDERSFIELD, YORK. SCARBOROUGH, LEMDS, BRADFORD,

The Trains of the Midland Company run to and from the St. Pancras Station in London, the Cantral Station, Hanelagh Street, Liverpool, the New Street Station in Birmingham, the Central and London Road Stations in Manchester, and the Wellington Station in Leeds.

The official Time-tables of the Company, and every information respecting their Trains and arrangements, may be obtained at any of the above-mentioned Stations, and the other Stations on the Line.

TOURIST TICKETS

are issued by the Midland Company during the Summer Mouths from all principal Stations on their system to principal places of Tourist resort and interest in England, Scotland, Ireland, and Wales; and special arrangements are made for Pleasure Parties.

Third-Class Passengers conveyed by all Trains at Penny per Mile Fares.

The Company are General Carriers to and from all parts of ENGLAND, SOOTLAND, IRELAND, and WALES.

JOHN NOBLE, General Manager.

DERBY, 1882.

DUBLIN AND GLASGOW STEAM PACKET COMPANY. The Company's First Class Saloon Paddle Steamers,

OR OTHER STEAMERS,

Are intended to Sail as per Monthly Sailing bills, unless prevented by any unforeseen occurrence, from

Duke of Argyll, Duke of Leinster, Lord Clyde, Lord Gough,

GLASGOW DUBLIN ${f TO}$

Every MONDAY. WEDNESDAY and FRIDAY, and every alternate TUESDAY. THURSDAY and SATURDAY, From

GLASGOW TODUBLIN

Every MONDAY, WEDNESDAY and FRIDAY, and every alternate TUESDAY, THURSDAY and SATURDAY, calling at Greenock both ways, except Saturday Boat from Dublin, which proceeds direct to Glasgow.

£ s. d. Return Ticket to Edinburgh Cabin Fare, (including Steward's (2 Months) . 10 0 Edinburgh Fees) Return Tickets (6 Months). 0 15 0 Single Ticket to (3rd Class and Deck) . 2 6 8 Ω B Õ Return Ticket to Edinburgh Steerage Return Tickets (6 Months) . 2 Months) (3rd Class and 10 0 Deck) Single Ticket to Edinburgh Ω

Passengers can travel between Greenock and Edinburgh Direct, without change of carriage, by either Caledonian or North British Railway, according to the Ticket they hold. The Caledonian Railway Stations are Catheart Street, Greenock; and Prince's Street, Edinburgh. North British Company's-Lyndoch Street, Greenock; and Haymarket and Waverly Stations, Edinburgh.

2 Passengers are also Booked Through between Dublin and the principal Railway Stations in Scotland.

AGENTS .- HENRY LAMOST, 93, Hope Street, Glasgow. James Little & Co., Excise Buildings, Greenock.

DUBLIN OFFICES .- Booking Office for Passengers -1 Eden Quay; where Berths can be secured up to 2 o'clock, p.m., on day of Sailing.

CHIEF OFFICE AND STORES .- 71, NORTH WALL.

Further particulars, Monthly Bills, &c., on application to A. TAYLOR, Secretary.

B. MANN, General Manager.

GENERAL STEAM NAVIGATION COMPANY

From and to Irongate and St. Katherine's Wharf, near the Treer.

LONDON AND BOULOGNE, -The Dolphin, Rhine, Cologne, Moselle, or Concordia. -For departures see Daily Papers. FARES-London to Boulogne, 18e, or 8e, 6d.; Return 18e, 6d. or 18e.

LONDON TO PARIS direct from London, via Boulogue. FARES Surella (available for Three Days), Saloos, 1st Class Ball, 18-2; Sare Cabin, 2nd Class Ball, 18-2; Fore Cabin, 2nd Class Ball, 18-2; Fore Cabin, 2nd Class Ball, 18-2; Sare Cabin, 2nd Class Ball, 18-2; March 18-2;

LONDON AND HAVRE —Swift or Seculos—From London—Every Thursday. From Hawre—Every Sunday. FARES—Chief Cabin, 18c.; Fore Cabin, 9c.; Return Tickets, 20c. 6d. and 14c.

LONDON AND OSTEND,—The Seris and Sealous—From London—Wednesday and Sunder.
From Ostend—Tuesday and Friday. FARES (Steward's Fee incinded), Chief Cabin, 15e.; Fore Cabin.
10e. Return, 5th. and 15e. 5d.

LONDON AND ANTWERP,—The Houle, Teel, Folcos, or Copelet. From London—Every Cables and Saintein. From Antwerp—Every Tuesday and Friday. FARES, Chief Cables, Ste.; Fore Cables, 18 & Return, 18 and 18 & See

LONDON AND HAMBURG.—The Libra, Capray, Iris, Baisboss, Martin, Granton, Widgeon, Nantiles, or PARS*, Chird Date County of Coun

LONDON AND BORDEAUX.—Fastrel, Bittern, Lopering and Gennel. From London—Every Thursday. From Bordeaux.—Every Friday. FABES, Chief Cabin, M.; Fore Cabin, M. Retern Tickets. Ohlef Cabin, 61; Fore Cabin, 51. 6: 46:

W. LONDON AND EDINBURGH (GRAWTOW PIER).—The Virgo and Stork. From London—Every Wednesday and Saturday. From Edinburgh (Granton Piery—Every Wednesday and Saturday. FARES, Chief Cable, 22s.; Fore Cablen, 18s. Settlems, 84s. and 28s. del. Deck (Soldiers and Sallors only).

LONDON AND HULL,—The *Heron, Ostrich*, or *Hambury*. From London—Every Wednesday and Saturday, at morn. From Hull—Every Wednesday and Saturday. FAREs, Saloon, Sc.; Fore Cabeta. Sc. Return Tickste, 12a. 6d. and 8c.

ONDON AND YARMOUTH,—From London Bridge Wharf, During the summer there is a speeds passenger savites. FARM, Saloon, St.; Fore Cakin, St. Return Tickets, Ist. and St. Steward's Fuen are included in above Fares and Statur Tickets by the Company's vessels are available for one measth.

For further particulars apply to the Secretary, 71, Lombard Street, London, E.C.

162.

BARROW ROUTE TO THE ISLE OF MAN.

Express Service. Shortest Sea Passage (reduced to 3 hours) by the Picturesque Route, via Grange, Furness Abbey, and Barrow.

The Barrow Steam Navigation Company's First-Class New and Swift Paddle Steamer "Monaman," or other First Class Paddle Steamer, will sail (weather and unforescen circumstances permitting) between BARBOW (Ramsden Dock Station) and DOUGLAS (Isle of Man) as follows:—

May 3rd to May 26th.
DOUGLAS TO BARROW every Monday,

May 2nd to May 25th. BARROW TO DOUGLAS every Tuesday, Thursday and Saturday, at 2:50 p.m.

Wednesday, and Friday, at 9: 30 a.m. May 27th to September 30th.
BARROW TO DOUGLAS DAILY (Sundays May 29th to September 30th, DOUGLAS TO BARROW DAILY (Sundays excepted), at 1:45 p.m. excepted) at 8:0 a.m.

In connection with Trains to and from all parts of the United Kingdom. Particulars of additional Sailings during July and Aveysy will be announced in Time Tables and Sailing Bills for those respective months.

SUMMER TOURS IN SCOTLAND. GLASGOW HIGHLANDS.

(Royal Route will Criman and Caledonian Canals.)
CLAYMORE NEW SCREW STEAM SHIP. The Royal Mail Steamers-Columba, Iona, Mountaineer, Clausman, Glencoe.

The Boyal Mail Steamers—Columba, Iona, Mountainer, Clauman, Glencoe, Chevalier, Pioneer, Clydesdale, Glengarry, Gondolier, Cygnet, Staffa, Linnet, Plover, Fingal, Lochiel, Islay, Queen of the Lake, and Inverange Castle, Sall during the Sesson for ISLAY, LOCHAWE, OBAN, FORT-WILLIAM, INVERNESS, STAFFA, IONA, GLENCOE, TOBERMORY, PORTREE, STROME-FERRY, GAIRLOCH, ULLAPOOL, LOCHINYER, & STUENOWAY; affording Tourists an opportunity of visiting the magnificent Scenery of Lochawe, Glencoe, the Cuchulin Hills, Loch Scawaig, Loch Corust, Loch Marce, and the famed Islands of Staffa and Iona. Official Guide Book, 3d. Illustrated, 8d.; cloth gilt, 1s. Time-Bills, with Map and Tourist Fares, free, of Messrs. Ceatro and Windus, Publishers, 214 Piccadilly, London; or by post from the owner.

DAVID MACBEAYNE, 118, Hope Street, Glasgow.

GLASCOW, BELFAST, BRISTOL, CARDIFF, AND SWANSEA

Oarrying goods for Newport (Mon.) Easter, Glomoster, Cheltanham, &c., &c.

The Screw Steamships "Solway," "Avon," "Severn," Princess Alexandra," or other
Steamers are intended to sail (unless prevented by circumstances) from Glasgow, calling at Greenock.

To Bristol vid Belfast every Monday and Thursday at 2 p.m. To Swansea every Friday " 2 p.m. To Cardiff .

Bristol to Glasgow vid Belfast every Monday and Thursday. Swansea to Glasgow " " Wednesday.

Cardiff to Giasgow , Swansea and Belfast every Monday.

Cardiff to Giasgow , Swansea and Belfast every Monday.

See Steamers have very superior accommodation for pessengers, and affird a favourable opportunity for making exoursions from West of England to Irsland and Scotland.

Parest from Ghaggow:—Cabin, 30s. Steerage, 13s. 6d. Soldiers and Saliors, 10s.

Parest from Belfast:— 17s. 6d. 10s.

Beturns:—Cabin and Steerage, Pare and Half, available for Two Months.

For rates of freight and further particulars, apply to

WILLIAM SLOAN & Co. 10s. Hone Street Glasgow.

WILLIAM SLOAN & Co., 140, Hope Street, Glasgow.

JAMES LITTLE & Co., Barrow-in-Purness.

UEEN' ABERYSTWITH.

THIS Hotel is situate on the Marine Terrace, facing the sea, and contains several Private Sitting Rooms, Coffee Rooms, Ladies' Drawing Room, Library, and all its Bedrooms are pleasantly situated.

TABLE D'HÔTE AT 6 O'CLOCK DURING THE SEASON. ARRANGEMENTS MADE FOR FAMILIES.

TARIFF ON APPLICATION.

W. H. PALMER, Proprietor.

AIX-LES-BAINS.

GRAND HOTEL DE L'EUROPE.

Proprietor, J. BERNASCON.

FIRST-CLASS House, admirably situated near the Casino, the Baths, and the English Church. This Hotel is strongly recommended to Travellers for the comfort of its arrangements. Good Gardens, with a beautiful view of the Lake and Mountains. Large and small Apartments for Families at moderate prices, and a Châlet in the Garden for Families who may prefer being out of the Hotel. Excellent Tablel'Hôte. Open all the Year. LAWN TENNIS.

Carriages for hire, and an Omnibus belonging to the Hotel to meet every Train.

AIX - LES - BAINS.

HÔTEL VENAT ET BRISTOL.

OPEN ALL THE YEAR ROUND.

European Reputation.

Re-furnished, with extensive Garden.

THE SPLENDID HOTEL.

150 Rooms, situated up Hill, with Lift, will be OPEN the 1st of March, 1884.

ROSSIGNOLI, Proprietor.

AIX-LES-BAINS.

GRAND HÔTEL DE L'UNIVERS.

First-Class Establishment, Open all the Year.

SPLENDID Situation; immense Garden; South aspect well shaded; a very extended view of Lake Bourget and the Mountains. Belvedere, with fine prospect of the principal points of view, and Excursions. Small and large Apartments; Salons for Families; Drawing Room, Reading Room, and Smoking Room, with every comfort that can be desired.

Premch and Porcipa Papers.

Arrangements made for Pension. Private Carriages. Stable and Oach-house.

Omnibus of the Hotel meets every Train.

CLUE. RENAUD, Proprietor.

ASCENT OF THE MATTERHORN, MONT PELVOUX. &c., &c.

By EDWARD WHYMPER.

With Maps and Illustrations. Medium 8vo. 10s. 6d.

JOHN MURRAY, ALBEMARLE STREET.

AIX - LA - CHAPELLE.

GRAND MONARQUE HOTEL. Close by the Railway Stations and the Baths.

KAISERBAD HOTEL (built in 1865). The principal Spring rises in the Hotel itself.

NEURAN HOTEL.

Opposite the Fountain "Eliea."

Mr. G. F. DREMEL is the Preprietor of these four hotels of European reputation. The combination in one hand of Four Intalkishments of such magnitude, enables Mr. Dremel to afford suitable accommodation to all conserve to whether to whom money is no object, as well as to parties desirous of living at a moderate rate of expense. "Excellent Hotels," wide Murray.

AIX - LA - CHAPELLE HOYER'S IMPERIAL CHOWN HOTEL, near the Kurbaus and Bath-houses, with large Garden. Very comfortable Apart-ments. Single Rooms. Excellent Cooking, and attentive attendance. Very Moderate Charges, and advantageous arrangements for Winter. OTTO HOYER.

AIX - LA - CHAPELLE.
HOYER'S UNION HOTEL. First-Class Hotel, immediately opposite the Rhenich Railway Station, and admirably situated in the best part of the city. Well-known for its clearly ess, comportable apertments, excellent cooking, and Moderate Charges. CHARLES HOYER.

AMIENS.

GRAND HÖTEL DU RHIN.

PLACE ST. DENIS.

FIRST-CLASS HOTEL, highly recommended, near to the Affords every accommodation. Cathedral and Railway Station. Spacious Apartments and siry Bed Booms. Private and Public Saloons. Warm Baths. Large Garden. Stabling and Coach Houses. Omnibus to and from each Train. English Interpreter. The house is newly furnished.

CH. FICHEUX. Proprietor.

AMIENS.

OTEL DE L'UNIVERS.—First-Class Hotel, facing St. Denis' Square, near the Railway Station. Three minutes' walk to the Cathedral. Drawing and Bath Rooms. English Interpreter.

Omnibus of the Hotel at every Train.

AMIENS.

OTEL DE FRANCE, D'ANGLETERRE, and DE L'EUROPE BRULÉ, Proprietor.—First-Class Hotel, one of the oldest on the Continent. Situated in the centre and the finest part of the town. Having recently been newly furnished, it offers great comfort. Families and Single Gentlemen accommodated with convenient Suites of Apartments and Single Rooms.

> OMNIBUS AT STATION. ENGLISH SPOKEN.

ANTWERP.

HOTEL ST. ANTOINE.

PLACE VERTE, Opposite the Cathedral.

THIS excellent FIRST-CLASS HOTEL, which enjoys the wellmerited favour of Families and Tourists, has been re-purchased by its old and well-known Proprietor, Mr. SCHMITT SPAENHOVEN, who, with his Partner, will do everything in their power to render the visit of all persons who may honour them with their patronage as agreeable and comfortable as possible.

BATHS IN THE HOTEL.

MODERATE PRICES.

ANTWERP.

HÔTEL DU GRAND LABOUREUR.

THIS Hotel occupies the first rank in Antwerp, and its position is most delightful. The testimonials given by Families is the best assurance of its

COMFORT AND MODERATE CHARGES.

AVIGNON.

HÔTEL D'EUROPE,

HIGHLY recommended to English Travellers on their journey to Nice, italy, &c. First-Class and Moderate Prices. The Proprietor and his Wife having lived in England, are aware of the wants of English Travellers; and he assures them that their controls shall be studied. Omnibus at all Trains.

AVRANCHES.

Grand Hôtel de Londres.

FAUVEL, Proprietor.

The best in the Town. Spacious Garden. English spoken, and English Newspapers.

BADEN - BADEN.

Grand Hôtel Belle - Vne.

First-class and large establishment, most delightful situation of all, in the Alli-Lichtesthal in the centre of a fine park. Really well-kept. Arrangements for a sijour.

RIOTTE, Proprietor.

BADEN - BADEN.

VICTORIA HOTEL.

Proprietor, Mr. FRANZ GROSHOLZ.

THIS is one of the finest-built and best-furnished First-class Hotels, situated on the new Promenade, near the Kursaal and Theatre; it commands the most charming views in Baden. It is reputed to be one of the best Hotels in Germany. The Table and Wines are excellent, with prompt attendance and great civility. Prices very moderate. English and other Journals.

BADEN-BADEN.

HÔTEL DE HOLLANDE and Dependance.

A U BEAU SEJOUR,—A. ROESSLER, Proprietor. This favourite and first-class A. Hotel, situated near the Kursaal, Promenade, and Theatre, commands one of the most charming views in Baden. The Hotel and Dependance consist of One Humdred and Elaty Sleeping Apartments, elegant Sitting-rooms, and a Garden for the use of visitors. Extensive and airy Dining-room, and a comfortable Public Sitting-room, with Plane and Library. It is conducted under the immediate superintendence of the Proprietor, who endeavours, by the most strict attention and exceedingly Moderate Prices, to merit the continued patronage of Engitsh and American visitors. English and American Newspapers. The Table d'Hôte and Wines of this Hotel are reputed of the best quality in Baden. Fixed moderate charges for everything. Rooms from 2s. and upwards.

PENSION Prices for a longer stay.

BADEN-BADEN.

HÔTEL DE LA COUR DE BADE.

Badischer Hof.

(Not to be confounded with the Hitel de la Ville de Bade, opposite the Railway Station.)

A FIRST-RATE and large Establishment near the Promenade and the Conversation House, with extensive Gardens, Warm, Mineral, and other Baths, enjoying a well-merited reputation for its great comfort and attention. It is patronised by the most distinguished Families.

Manager, Mr. Fr. ZIEGLER.

BADEN - BADEN.

HÔTEL STADT BADEN.

On the right hand side and nearest the Station.

COMMANDING a delicious view of the Old Castle and high rocks. Known for its Cleanliness, excellent Cooking, good Attendance, and fixed Moderate Charges. E. ROESSLER, Landlord.

BADEN-BADEN.

HÔTEL DE FRANCE.

FIRST-GLASS HOTEL. Best Situation.

Excellent Cooking, and Moderate Charges.

PENSION.

CARL ULRICH, Proprietor.

BADEN-BADEN.

MURRAY'S HANDBOOK FOR NORTH GERMANY.

Post 8vo. 10s.

JOHN MURRAY, Albemarle Street.

BAGNÈRES DE LUCHON PYRÉNÉES.

Hôtel Bonnemaison et de Londres,
Opposits the Springs.

First-Class Hotel. Recommended to Families.

HTE. VIDAL Fils, Proprietor.

BAGNÈRES DE LUCHON PYRÉNÉES.

GRAND HÔTEL RICHELIEU.

(Hotel de S. M. le roi de Hollande.)

200 Rooms, 10 Salons. Splendid view.

LOUIS ESTRADE, Proprietor.

BAGNÈRES DE BIGORRE.

Grand Hôtel Beau-Séjour.

FIRST-CLASS.

The most comfortable and the best situated-

BOLOGNA.

HÔTEL PELLEGRINO.

The most central position, and unsurpassed for its home comforts and extremely Moderate Charges.

F. RAVALDONI, Proprietor.

BÂLE, SWITZERLAND.

HOTEL SCHWEIZERHOF.

Opposite the Swiss French Railway Station, the healthiest part of the Town.

Moderate Charges. Well Recommended.

L. MERIAN, Proprietor.

BAMBERG (GERMANY).

HÔTEL ZU DEN DREI KRONEN.

I RECOMMEND my newly-furnished and arranged Hotel, situated in the middle of the Town, to all Travellers and Families. First-Class Board. Pure Wines, and excellent Service. Moderate Prices. Omnibus at the Station on the arrival of every Train. Carriages. Also Warm and Cold Baths in the Hotel.

I. A. BERNREUTHER, late Proprietor of the Hotel "Zum Hirsch" at Mergentheim.

BARCELONA.

GRAND HÔTEL DES QUATRE NATIONS.

IN THE RAMBLA.

THE largest and finest Hotel in Barcelona; most advantageously situated in the best position in the Rambla, facing the Teatro Principal, and close to the Post and Telegraph Offices. Full Southern Aspect. Enlarged and newly decorated. Table d'Hôte. Private Service. Large and small Apartments. Many Fis-places. Bath. Reading Room, with Piano. Smoking Room and Parlour. Foreign Newspapers. Carriages of every description. Great Comfort and Chailiness. French Custons. Omnibus at Railway Stations. Interpreters. Moderate Terms. English and German Spoken. Arrangements for Pension during the Winter Season.

BELFAST.

THE IMPERIAL HOTEL.

Just Re-decorated and Enlarged. First-Class. Best Situation.
Omnibuses meet all Trains and Steamers.

W. J. JURY, Proprietor.

BELLAGIO (Lago di Como).

GRAND HÔTEL BELLAGIO.

ONE of the finest in Europe, containing 200 Rooms, 30 Sitting Rooms, and surrounded by a splendid Park and Garden. Full view of all three Lakes and the Mountains. Hot and Cold Baths. Douches. Equipages and Boats attached to the Hotel. English Service. Moderate Charges. Daily arrangements. Highly recommended. Open all the Year.

L. BREITSCHMID, Proprietor.

BERLIN.

HÔTEL D'ANGLETERRE,

2, SCHINKEL-PLACE, 2.

SITUATED IN THE FINEST AND MOST ELEGANT PART OF THE TOWN.

Near to the Royal Palaces, Museums, and Theatres.

OlingLE Travellers and large Families can be accommodated with entire Suites of Apartments, consisting of splendid Salcons, airy Bedrooms, &c., all furnished and carpeted in the best English style. First-rate Table d'Hôte, Baths, Equipages, Guides. Times and Gallgmant's Messenger taken in. Residence of Her British Majesty's Messengers.

R. SIEBELIST, Proprietor.

BERLIN.

HÔTEL DU NORD.

UNDER THE LIME TREES.

FIRST-CLASS HOUSE, CLOSE TO THE IMPERIAL PALACE AND THE THEATRES.

Beautiful Dining Room, freshly Decorated.

EXCELLENT CUISINE. MODERATE PRICES.

ENGLISH NEWSPAPERS.

FEBD. SCHMIDT, PROPRIETOR.

BERLIN.

HÔTEL DE RUSSIE.

THIS well-known FIRST-CLASS HOTEL, newly restored and handsomely decorated, and situated in the most attracting part of the City, facing the Imperial Castle,

NEAR UNTER DEN LINDEN, recommends itself for the comfort it offers to its Visitors.

CARL FRIEDRICH KÜHRT.

BERLIN.

THE KAISERHOF.

Wilhelmsplatz. Zietenplatz.

THE largest and most commodious First-Class Hotel in Berlin. Situated in an elegant, quiet, and magnificent part of the city.

ST. PETERSBURG HOTEL.

Unter den Linden 31.

The Table d'Hôte and Wines of this Hotel are reputed of the best quality in Berlin. Fixed Moderate Charges.

JULES HEUDTLASS, Proprietor.

BOTZEN, SOUTH TYROL.

HÔTEL VICTORIA.

Opposite the Railway Station. First Class.

H. SCHMID.

BIARRITZ.

HÔTEL DES PRINCES.

A LARGE and beautiful Hotel with a fine view of the Sea. This Hotel will be found most suitable for English Families and Gentlemen. Excellent cooking. Exceptional arrangements can be made for pension. English spoken.

E. COUZAIN, Proprietor.

BOLOGNA.

Murray's Handbook for North Italy.

Post 8vo. 10s.

JOHN MURRAY, Albemarle Street,

CROWE AND CAVALCASELLE.

History of Painting in

North Italy.

From 14th to 16th Century. With Illustrations. 2 vols. 8vo. 42s.

JOHN MURRAY, Albemarle Street.

BONN.

THE GOLDEN STAR HOTEL.

THIS First-rate and unrivalled Hotel, patronised by the English Royal Family, Nobility, and Gentry, is the nearest Hotel to the Railway Station, and to the Landing-places of the Rhine Steamers. The Proprietor, Mr. J. SCHMITZ, begs leave to recommend his Hotel to Tourists. The Apartments are comfortably furnished and carpeted in the best style, and the charges are moderate. Arrangements for the Winter may be made, on the most moderate terms.

BORDEAUX.

HÔTEL DE PARIS.

FIRST-CLASS HOTEL

Much frequented by English and American Travellers. BORDEAUX.

MURRAYS HANDBOOK FOR FRANCE

Part I. Post 8vo. 7s. 6d. New Edition. Revised to date. JOHN MURRAY. Albemarle Street.

BOULOGNE-SUR-MER.

GRAND HÔTEL CHRISTOL & BRISTOL.

First-class Hotel.

Best Situation in the Town. Highly recommended for Families and Gentlemen.

Carriage in Attendance on Arrival of all Trains and Boats. F. CHRISTOL, Proprietor and Manager.

BOULOGNE-SUR-MER.

FAMILY HOTEL AND BOARDING HOUSE, 87 & 89, RUE DE THIERS.

Established 1845. Near the Port. Very comfortable. Moderate Charges.

Proprietor, L. BOUTOILLE.

BREMEN.

HÔTEL DE L'EUROPE.

First-Class English Hotel. Entirely Renovated. Highly Recommended.

LUSCHE-BAUR, Proprietor.

Formerly of { HUTEL BAUR AU LAC, ZURICH. HOTEL DE RUSSIE, BERLIN.

BRUGES.

GRAND HÔTEL DU COMMERCE.

FIRST-CLASS HOTEL.—Proprietor, C. VANDEN BERGHE. The largest and oldest Hotel of the Town. Comfort. Moderate Charges.

Special Omnibus.

BRUSSELS.

HÔTEL MENGELLE (RUE ROYALE).

B. MENGELLE, PROPRIETOR.

most healthy part of the Town, near to the Promenades the most frequented, and is supplied with every modern accommodation and comfort. Table d'Hôte at 6 and 7.15, five france. Restaurant à is carte, and at fixed prices, at any hour. Excellent "Culsine" and Choice Wines. THIS large and beautiful First-Class Hotel is situated in the finest and

Baths, Smoking Room, Reading Room, Billiard Room, Arrangements made with Families during the Winter Season.

BRUSSELS.

HÔTEL DE L'EUROPE, PLACE ROYALE.

The Best Situation in Brussels, near the Park, Royal Palace. Boulevards, Museum, and Picture Galleries.

Table d'Hôte.

ENGLISH SPOKEN.

BRUSSELS.

DE L'EMPEREUI

63. RUE NEUVE. Patronised by Prince Teck.

THIS old-established First-Class Family Hotel is very conveniently situated near the Station du Nord. Post and Telegraph Offices and Theatre de la Monnale. The new Proprietor, who speaks English, has repleted it with every modern comfort. Se Bed Rooms, private Dining and Sitting Rooms. Excellent Table d'Hôte. Choice Wines. Terms Moderate. English Newspapers. Attendants speak English. Baths in the Hotel. Arrangements made for a protracted stay. Rooms from 3 francs. N.B.—A speciality is the beautiful Garden adjoining the Hotel.

Proprietor, HENRY DORGELOH.

BRUSSELS.

HÔTEL DE LA POSTE,

RUE FOSSÉ-AUX-LOUPS.

NEAR THE PLACE DE LA MONNAIE.

This Hotel, specially frequented by English and Americans, is situated in the centre of the Town, and near the principal Theatres.

BEST TABLE D'HÔTE. MODERATE CHARGES. ENGLISH SPOKEN. OMNIBUS AT THE STATION.

BRUSSELS.

CARAND HÖTEL DE SAXE, 77 and 79 RUE NEUVE. Admirably GRAND HOTEL DE SAXE, 77 and 79 BUE NEUVE. Admirably situated near the Boulevards. Theatres, and two minutes' walk from the North Rallway Stations. This Establishment, which has been considerably enlarged, possesses now a most splendid liming-room, and offers to Families and Single Travellers *pactons, comfortable, airy Apartments. Twifs in every 800m.—Fixed Prices:—Plain Breakfact, 1fr. 250. Two chops or steaks, or ham and eggs, 1fr. 50c. Table d'Hôte at five o'clock, 3fr. 50c. Private Dinners from 8fr. Bed-rooms, including light, 4fr. 25c.; 3fr. 15c.; 6fr.—for the first night: and for the following night, 3fr. 56c.; 8fr.; 5fr.; and 4fr. Steing-rooms from 3fr. to 12fr. Attendance ifr. per night. London "Times" and "illustrated London News' taken in. Travellers baying only a few hours to spend in Brussels between the departure of the trains, can have refreshments or dinner at any hour. The Waterloo 28fr., every expense included. Table d'Hôte at 6.30 p.m., 5fr.

HENRY KERVAND, Proprietor.

BRUSSELS.

HÔTEL DE FRANCE.

RUE ROYALE AND MONTAGNE DU PARC.

Proprietor, JOHN JAMES BARBER.

THE beautiful situation of this Hotel (adjoining the Park), the Moderate Charges, excellent Cuisine, and greatly improved arrangements for the comfort of Visitors, renders it especially deserving the paironage of Travellers. Reading and Smoking Rooms. English, French, and German Papers taken. English and other principal Languages spoken. Rooms from 8 francs upwards. Table d'Hôte (at half-past five o'clock in Winter, six in Summer), 8 francs.

Arrangements made with Families during the Winter Months.

BRUSSELS.

HOTEL DE SUEDE.

FIRST-OLASS HOTBL, in a thoroughly central position near the New Boulevards.

EXCELLENT TABLE D'HÔTE.

CHOICE WINES.

VAN CUTSEM, Proprietor.

BRUSSELS.

CULLIFORD'S HOTEL.—No. 20, opposite the Sablon Church, près la Place Royale.

The rooms are well adapted and carefully arranged to meet the requirements of Families and single travellers. Ladics' brawing Room. Rooms from 2 francs and pawards. Breakfasts, Tea or Coffee with Steak, Chops, or Ham and Eggs. 2 francs; with Eggs. 1 francs 50 cents. Table d'Hête, 6 p.m. 3 francs 50 cents. Refreshments to order at any hour. Wines, Spirits, Beer, &c., of the best quality.

BRUSSELS.

HÔTEL DE L'UNIVERS,

RUE NEUVE.

Has a Wide Entrance from the New Boulevards, which places it in one of the best and most advantageous positions in the city. A First-class House for Families, to be recommended for its Comfort and Moderate Prices. Table d'Hôte, Restaurant, Smoking-room, Reading-room.

Arrangements made for the Winter Season, or for a prolonged residence.

SCHOËFFTER-WIERTZ, Proprietor.

BRUSSELS.

GRAND HÔTEL GERNAY.

Moderate Charges. Ancien Propriétaire de l'Hôtel de Portugal à Spa.

This Hotel is close to the Railway Station for Ostend, Germany, Holland, Antwerp, and Spa, forming the Corner of the Boulevards Botanique et du Nord.

BUXTON. CRESCENT HOTEL, DERBYSHIRE,

THIS First-Class Hotel is close to the Railway Stations. Connected by a Covered Colonnad- with the Hot and Natural Baths, Drinking Wells, and New Pavilion and Gardens. Public Dining, Drawing, Smoking, and Billiard Rooms. Suites of Apartments for Private Families. Table d'Hôte et Six p.m. Terms strictly moderate.

JOHN SMILTER, Proprietor.

CAEN.

HÔTEL



d'ANGLETERRE,

Rue St. Jean, Nos. 77, 79, 81.

Situated in the Centre of the Town. Rendezvous of the best Society.

100 Elegantly Furnished and Comfortable Bed Rooms and Sitting Rooms.

BREAKFASTS À LA CARTE.

DINNER AT TABLE D'HÔTE, 4 FRANCS.

SUITES OF APARTMENTS FOR FAMILIES.

ENGLISH AND SPANISH SPOKEN.

L. MANCEL, Proprietor.

CAIRO, EGYPT.

HÔTEL ROYAL.

THIS First-Class Hotel, newly built, is situate on the BOULEVARD DE L'ESBEKIEH, in the centre of the finest part of Cairo. Newly furnished throughout. This Hotel is recommended to travellers for its comfort and moderate charges. There are also

READING, CONVERSATION, AND BILLIARD ROOMS.

BATHS AND HYDROPATHIC DOUGHES.

FINE GARDEN LEADING UP TO THE HOTEL.

AN OMNIBUS TO MEET ALL TRAINS.

PRICES FROM 10 TO 12 SHILLINGS A DAY.

ISIDORE ROMAND, Proprietor.

CANNES.

HÔTEL BEAU SITE.

SITUATED at the West end of Cannes, adjoining Lord Brougham's property; the finest part of the Town. Newly enlarged. 200 Rooms. 20 private Sitting-rooms. Reading and Smoking-rooms, and English Billiard-table.

Sheltored Situation, commanding an unequalled view of the Sea, the Iles Lérins, and the Esterel Mountain. Large beautiful Gardens. Promenades, and Lawn Tennis belonging to the estate. Arrangements made for the Season for Families. Moderate Charges. Bath-rooms and Lift.

Omnibuses at the Station.

OPENED THE 1st OF OCTOBER.

GEORGES GOUGOLTZ, Proprietor.

CANNES.

WINDSOR HOTEL.

THIS First-Class Family Hotel is beautifully situated, not too far from the Town and the Sea, of which, however, it enjoys an extensive view. Baths. Smoking and Billiard Room. Large and sheltered garden.

Most Comfortable Apartments and Careful Attendance.

ED. SCHMID, Proprietor.

CANNES.

HÔTEL DES PINS.

FIRST-CLASS Hotel. Highly recommended by Physicians for its salubrity and its sanitary situation.

L. GRENET, Proprietor.

CASTELLAMARE (Near Waples.)

GRAND HÔTEL ROYAL

THE only first-class Establishment in the town, Sphendid House, with a large Garden. Healthy position, orposite the sea. View of the Vesuvius and Fompeli. Carriages for Excursions. A. RUGGIERI, Proprietor.

CANNES.

MURRAY'S HANDBOOK TO FRANCE.

Part II. Post 8vo. 7s. 6d.

JOHN MURRAY, Albemarle Street.

CHAMONIX.

GRAND HÔTEL D'ANGLETERRE.

First-Class Hotel, with splendid view of Mont Blanc.

J. CRÉPAUX, Proprietor.

CHAUMONT-NEUCHATEL.

HÔTEL DU CHAUMONT, near Neuchatel, Switzerland. 3,500 feet high. Open from the 18th June till end of September. Kept by C. RITZMANN. Proprietor of the Hôtel Suisse, Cannes. Post and Telegraph Office. Billiards.

Carriages in the Hotel.

CHRISTIANIA (Morway).

GRAND HÔTEL.

J. FRITZNER, Proprietor.

THIS First-Class Hôtel, delightfully situated in the best part of the Town, opposite the Public Parks, the House of Parliament, and close to the Royal Palace, commands a charming view of the Christiania Fjord, and the surrounding mountains. Table d'Hôte. Warm and Cold Baths in the Hôtel. English Newspapers taken in. Omnibus at the Railway and Steam-boat Stations. Moderate Charges.



CHESTER. THE GROSVENOR HOTEL.

FIRST-CLASS, situated in the centre of the City, close to the Cathedral, The Rows, City Walls, and other objects of interest.

A Large Ceffee-Room and Ladies' Drawing-Room for the convenience of Ladies and Families The Bedrooms are large and handsomely furnished.

Open and close carriages, and Posting in all its Branches.

Omnibuses attend the Trains for the use of Visitors to the Hotel. Tariff to be had on application. A Night Porter in attendance.

DAVID FOSTER, Manager.

CHRISTIANIA, NORWAY.

HÔTEL ROYAL.

W. WELGE, PROPRIETOR.

FIRST-CLASS HOTEL,

OPPOSITE THE

RAILWAY STATION AND HARBOUR.

JOHANN MARIA FARINA, GEGENÜBER DEM JÜLICH'S PLATZ

(Opposite the Jülich's Place),

PURVEYOR TO H.M. QUEEN VICTORIA;

TO H. R. H. THE PRINCE OF WALES;

TO H. M. WILLIAM KING OF PRUSSIA; THE EMPEROR OF RUSSIA;

THE EMPEROR OF AUSTRIA;

THE KING OF DRYMARK FTO. FTC.

OF THE

ONLY GENUINE EAU DE COLOGNE,

Which obtained the only Prize Medal quarted to Eau de Cologne at the Paris Exhibition of 1867.

THE frequency of mistakes, which are sometimes accidental, but for the most part the result of deception practised by interested individuals, induces me to request the attention of English travellers to the following statement:—

The favourable reputation which my Eau de Cologne has acquired, since its invention by my ancestor in the year 1709, has induced many people to imitate it; and in order to be abl to sell their spurious article more easily, and under pretext that it was genuine, they procured themselves a firm of Forius, by entering into partnership with persons of my name, which is a very common one in Italy.

Persons who wish to purchase the genuine and original Ban de Colegne cught to be particular to see that the labels and the bottles have not only my name, Johann Maria Parine, but also the additional words, gegentiber dem Jülich's Plats (that is, opposite the Julich's Place), without addition of any number.

Travellers visiting Cologne, and intending to buy my genuine article, are cautioned against being led astray by cabmen, guides, commissioners, and other parties, who offer their services to them. I therefore beg to state that my manufacture and shop are in the same house, situated opposite the Julich's Place, and nowhere else. It happens too, frequently, that the raid persons conduct the uninstructed strangers to shops of one of the fictitious firms, where, not withstanding assertion to the contrary, they are remunerated with nearly the half part of the price paid by the purchaser, who, of course, must pay indirectly this remuneration by a high price and a bad article.

Another kind of imposition is practised in almost every hotel in Cologne, where waiters, commissioners, &n., offer to strangers Eau de Cologne, pretending that it is the gamine one, and that I delivered it to them for the purpose of selling it for my account.

The only certain way to get in Cologne my genuine article is to buy it personally at my house, egyotic the Jilifoh's Piece, ferming the corner of the two streets, Unter Goldschmidt and Oben Marspferten, No. 22, and having in the front six balconies, of which the three bear my name and firm, Johann Maria Farina, Gegenüber dem Jillich's Plats.

The excellence of my manufacture has been put beyond all doubt by the fact that the Jureus of the Great Exhibitions in London, 1851 and 1862, awarded to me the Prise Medal; that I obtained honourable mention at the Great Exhibition in Paris, 1855; and received the only Prise Medal awarded to Eau de Cologne at the Paris Exhibition of 1867, and in Oporto 1865.

COLOGNE, January, 1882.

JOHANN MARIA FARINA, GEGENÜBER DEM JÜLICH'S PLATZ.

* * MESSES. J. & R. M'CRACKEN, 38, Queen Street, Cannon Street, E.C., are my Sole Agents for Great Britain and Ireland.

COBLENTZ.

GIANT HOTEL—HÔTEL DU GEANT.

THE best situated First-Class Hotel, just opposite the landing-place of the Steam-boats and Fortress Ehrenbreitstein. Excellent Cuisine and Cellar. Moderate Charges. Reduction for a long residence.

PROPRIETORS, EISEN MANN BROS.

COLOGNE.

HÔTEL DISCH.

First-Class Hôtel newly refitted; near the Cathedral and Central Station. Omnibuses meet every Train. Large stock of Choice Wines for wholesale.

F. CHRISTOPH, Proprietor.

COLOGNE.

HÔTEL DU DÔME.

TR. MERS.—This old and excellent House, advantageously situated in the centre of the City, near the Cathedral and the Central Railway Station, hes undergone important improvements that make it very comfortable. Table d'Ette 1 o'clock. Café du Dome adjoining the Hotel. Recommended to Registrations. Terms Moderate.

CONSTANTINOPLE.

THE PROPRIETOR of the

HÔTEL D'ANGLETERRE

(MISSIRIE),

In view of the great number of Families and Gentlemen travelling in this Capital, has thought it expedient to fit up a Branch for the accommodation of the same, consisting of the

HÔTEL ROYAL,

For some time the residence of H.B.M.'s Ambassador, Sir H. Elliot, His Majesty the Emperor of the Brazils, and lately, for two months, of His Excellency the Marquis of Salisbury. It is needless to say anything in praise of the fine position and splendid view on the Golden Horn. The Arrangements are thoroughly comfortable, and the Furniture first-class. The Hotel is within two minutes' walk of the British Embassy; and the Arrangements have given the greatest satisfaction to the above high personages. The Proprietor begs to inform Gentlemen travelling, that both Establishments are provided with every desirable comfort, Guides, and Attendants; and at Prices calculated to suit passing Travellers, as well as those making a prolonged stay.

F. LOGOTHETTI.

COPENHAGEN.

HOTEL KONGEN OF DENMARK.

THIS First-Class Hotel, much frequented by the highest class of English and American Travellers, affords first-rate accommodation for Families and Single Gentlemen. Splendid situation, close to the Royal Palace, overlooking the King's Square. Excellent Table d'Hôte. Private Dinners. Best attendance. Reading Room. Hot Baths. Lift. English, French, German, and American Newspapers. All Languages spoken.

Very Moderate Charges. The only Vienna Coffee House.

R. KLÜM, Proprietor.

CORFU. HÔTEL ST. GEORGE.

THIS FIRST-CLASS HOTEL, very well situated on the best side of the Esplanade, dose to the Royal Palace, is fitted up after the English style, affording first-rate accommodation for Families and Single Gentlemen. Excellent Pension, and prices very moderate. A large addition to the Hotel just now finished makes it one of the meet comfortable of the Continent, with splendid Apartments, Conversation Salcon, Reading Salcon and Library, Smoking and Billiard Rooms, and Bath Room. Magnificent Carriages and Horeae, the whole new, neat, and elegant. All Languages spoken. Ladies travelling alone will find here the greatest comfort and best attendance. The Hotel is under the patronage of King George L, the Emperor of Austria, and the Grand Duke of Mecklenburgh.

Madame Vva S. P. MAZZUCHY & FILS, Proprietors.

COWES. Isle of Wight.

DROVER'S MARINE HOTEL.

PARADE, ISLE OF WIGHT.

FIRST-CLASS FAMILY HOTEL.

The Comfort of Visitors carefully studied. Board on Low Terms during the Winter Months.

> CREUZNACH. HÔTEL DE HOLLANDE.

THIS FIRST-CLASS HOTEL offers superior accommodation at very Moderate Charges.

I to Families and Single Gentlemen. It is situated in the finest and bealthlest part of the town, and is surrounded by a beautiful Garden. It is fitted up after the English and American style. Splendid large Dining Rooms, and newly fitted-up Conversation Salcom. Comfortable and well-furnished Apartments (with many Balconies). Good Baths. Excellent Board. Arrangements can be made for a protracted stay. Pension in Winter.

FOLTYNSKI & WOOG, Proprietors.

CREUZNACH (BAD). PRIVATE HOTEL BAUM.

PIRST-CLASS Family Hotel, best situated. Great cleanliness. Comfortable Baths. Beautiful Garden. Excellent Cooking, Choice Wines. Pension moderate charges. Recommended.

JEAN BAPTISTE BAUM, Proprietor.

CREUZNACH (BAD).

HÖTEL KAUTZENBERG.

THIS First-Class Hotel is beautifully situated, close to the Kurhans, adjoining the Promenade. Large Garden. Baths in the Hotel. The Table d'Hôte and Wines of this Hotel are reputed the best in Creunach. Moderate Charges.

F. EISENBEICH, Proprietor.

DIJON.

GRAND HÔTEL DE BOURGOGNE. Near the Station. Well situated in an open Square. Enlarged in 1880. Apartments for Families. Table d'Hôte. Carrieges. English Newspapers. Omnibuses to meet all Trains.

Wines Exported by the Proprietor.

DIEPPE. HÔTEL ROYAL,

Facing the Beach, close to the Bathing Establishment and the Parade.

IT IS ONE OF THE MOST PLEASANTLY SITUATED HOTELS
IN DEEPE, commanding a beautiful and extensive View of the Sea. Families and
Gentlemen visiting Dieppe will find at this Establishment elegant Large and Small Apartments, and the best of accommodation, at very reasonable prices. Large Reeding Roses,
with French and English Newspapers. The Refreshments, &c., are of the best quality. In
fact, this Hotel fully bears out and deserves the favourable opinion expressed of it in
Murray's and other Guide Books.

LARSONNEUX, Proprietor.

Table & Hote and Private Dinners.

* * This Batel is open all the Year.

DIJON.

HÔTEL DE LA CLOCHE.

Mr. GOISSET. PROPRIETOR.

OUITE near the Railway Station, at the entrance of the Town. First-Class House of old reputation. Enlarged in 1870. Apartments for Families. Carriages for drives. Table d'Hôte and Service in private. Reading Room. Smoking Room. English spoken. Exportation of Burgundy Wines.

GRAND HÔTEL GOISSET will be Open in 1888.

DIJON.

HÔTEL DU JURA.

M. LOUIS MERCIER, Proprietor.

THIS Hotel is the nearest to the Railway Station, the Cathedral, and the Public Garden Saloons. Apartments and Rooms for Families. Table d'Hôte. Private Carriages for hire by the hour. English Newspapers. Omnibus to carry passengers to and from each train. English spoken. The greatest attention is paid to English visitors. Burean de Change in the Hotel. Considerably enlarged and newly furnished, 1875. The best Bargundy Wines shipped at wholesale prices.

DINARD, ILLE ET VILAINE (Brittany).

GRAND HÔTEL DU CASINO.

THIS First-Class Hotel is the nearest to the Casino and Bathing Establishment. Splendid View from the Terrace adjoining the Garden of the Hotel. Private Dining Saloons and Smoking Rooms. Table d'Hôte at 11 o'clock a.m. and 6 o'clock p.m. Terms from 12 to 15 francs per day. Excellent Cooking. Choice Wines. English Newspapers. Stabling.

L. BIARDOT, PROPRIETOR. BOUDIN FILS, SUCCESSEUR.

DRESDEN.

VICTORIA HOTEL.

THIS First-rate Establishment, situated near the great public Promenade, and five minutes from the Central Station for Prague, Vienna, Berlin, Munich, Frankfort, combines comfort with elegance, and has the advantage of possessing a spacious and beautiful Garden.

TWO SUPERIOR TABLES D'HÔTE DAILY.

PRIVATE DINNERS AT ANY HOUR.

During the Winter, Board and Lodging at very moderate rates.

Mr. Whise has an extensive Stock of the best Bhenish, Bordeaux, Burgundy, and Spanish Wines, and will be most happy to execute Orders at Wholesale Prices.

DRESDEN.

HÔTEL BELLEVUE.

Situated on the river Elbe, facing the new Opera, the Galleries, the Green Vaults, Cathedral, and Brühl's Terrace. Well-known First-Class Establishment, with 150 Rooms. Families desirous of taking Apartments for the Winter can make arrangements at very moderate prices.

LOUIS FEISTEL, Manager.

DRESDEN.

WEBER'S HOTEL.

INGLISH and American visitors desiring a comfortable residence are respectfully invited to give this Hotel a trial. It is situated in a delightful part of the city, overlooking the Promenades, Gardens, and Galleries. Handsome Dining Room. Reading Room well furnished with American, French, and English Newspapers. During the Winter, pension at very advantageous terms.

BERNHARD WEBER, Proprietor.

DOVER.

ESPLANADE HOTEL.

Pleasantly situated on the Marine Promenade, and near the Railway Stations and Steam-Packets. Well-appointed General Coffee Rooms. W. CESSFORD. EGGISCHHORN, VALAIS.

HÔTEL JUNGFRAU.

Open 1st June. Beautiful Climate. Splendid view. Pension.

CATHREIN, Proprietor.

EMS.

DARMSTADT HÔTEL AND PENSION.

THIS FIRST-CLASS HOUSE, of an old reputation, is the nearest to the Mineral Springs and Baths and the Imperial residence. Splendid situation, with every comfort and Moderate Charges. The Milk used in the Hotel is supplied from the Proprietor's own farm, where there are also good stables.

TH. BIEGEN, Proprieter.

ENGELBERG.

THE VALLEY OF ENGELBERG (3200 ft. high) with its

KURHAUS AND HÔTEL SONNENBERG,

THE properly of Mr. H. HUG. Summer stay unrivalled by its grand Alpine somery, as well as by the curative efficacy of the climate against lung and chest diseases, coughs, nervous aliments, &c., &c. Clear bracing air, equable temperature. Recommended by the highest medical authorities. The HOTEL SONNENBERG in the finest and best managed hotele in Switserland. Lawn Tennis Ground. Excellent and central place for akeeching, botanising, and the most varied and interesting excursions. The ascent of the Titlis is best made from here. Shady Woods. Vapour and Ghower Beths. Waterspring 5° R.; 200 Rooms; Pension from 7 fr. a day upwards. Because of its so sheltered situation specially adapted for a stay in May and June. Resident English Physician. English Divine Service.

ENGELBERG, SWITZERLAND.

KURHAUS HÔTEL ET PENSION TITLIS.

LIRST-CLASS HOTEL in the best situation of the valley, in the middle of an extensive garden. It possesses the best recommendations of English Families.

ENGLISH AND AMERICAN NEWSPAPERS.

New English Chapel in the Garden of the Hotel.

ED. CATTANI, Proprietor.

EXE

ROYAL CLARENCE HOTEL.

WITH FULL VIEW OF THE GRAND OLD CATHEDRAL.

Patronised by the best Families.

BILLIARD RUOM. MODERN TARIFF.

J. H. STANBURY, Proprietor.

FRANKFORT O.M.

P. A. TACCHI'S SUCCESSORS,

BOHEMIAN FANCY GLASS AND CRYSTAL WAREHOUSE.

Chandeliers for Gas and Candles in Glass and Brass.

Correspondent in England, Mr. LOUIS HENLE, 8, Budge Row, Cannon St., London, E.C.

GENEVA.

HÔTEL PENSION BELLEVUE.

Well-kept Establishment, in the midst of a large well-shaded Garden.
50 Bed Rooms. Pension 5 f. a day.

J. SUTTERLIN, Proprietor.

HÔTEL DES BERGUES.

Mme. Vve. FREDERIC WACHTER, Proprietress.

The Hotel, one of the largest in Geneva, is in a delightful situation—near the English Church and the General Rallway Station; it has an uninterrupted view of Mont Blanc and the Alps. A Litt of superior construction; large Conservatory. Families or Single Gentlemen will find every accommodation and comfort which a first-class Hotel can afford. Table d'Hôte at 8 o'clock. Excellent Baths in the Hotel.

GENEVA.

GRAND HÔTEL BEAU RIVAGE.

THE LARGEST AND BEST IN GENEVA.

MAYER & KUNZ, Proprietors.

GENOA.

GRAND HÔTEL DE GÊNES.

Messra, L. BONERA AND BROTHERS.

PLACE CARLO FELICE, the most beautiful situation in the City.
(FULL SOUTH.)

This Hotel, formerly the Palazzo Marchese Spinola, was newly opened and entirely re-furnished about two years ago. Its situation, opposite the celebrated Theatre Carlo Felice, on the Piazza de Ferrari, the healthiest part of the town, in the vicinity of the English Church, the Telegraph, the Post Office, the principal Public Bulldings, and near all the curiosities in the town; free from the noise of the Railway and the Harbour. Large and small Apartments. Table d'Hôte. Restaurant. Reading and Smoking Saloon. Bath Rooms. Omnibus from the Hotel meets every Train. Moderate Charges.

GENOA.

HÔTEL LONDRES

ET PENSION ANGLAISE.

The nearest to the Central Station.

First Class. Full South.

Moderate Prices.

NERVI.

WINTER RENDEZVOUS, SHELTEBED FROM THE N., N.E., AND N.W. WINDS BY MOUNTAINS.

HÔTEL and PENSION VICTORIA.

GOOD, WITH LARGE GARDEN.

GMUNDEN, AUSTRIA. HÔTEL BELLE VUE.

TACING the Steamboat landing-place. Comfortable First - Class Hotel. Highly recommended. Mr. BRACHER, the Proprietor, has been in England and America, and knows the wants of English and American Travellers. Charges moderate. Omnibus at the Station. Baths in the Hotel.

GOTHA.

HÔTEL DEUTSCHER HOF.

Proprietor, L. STAEBLER.

**IRST-RATE HOTEL, situated close to the Promenades and near the Railway Station; combines comfort with elegance. Baths in the House.

Carriages.

GRASSE.

GRASSE. AM. GRAND HÔTEL DE

TAMILY HOTEL, 88 minutes from Cannes. First-Class Hotel, situated on the Boulevard Thiers, full South. Large Garden. Splendid view of the Ses. Large and small Apartments, combritably furnished. Table d'Hee, Reading, Billiard, Smoking, and Bath Rooms. Omnibus meets every train.—M. TOURNAIRE, Manager, Formerly Proprietor of the Hotel Helvetique, Nice.

GRENOBLE.

HÔTEL MONNET.

THIS splendidly-situated First-Class Hotel, which is the largest in the Town, and enjoys the well-merited favour of Families and Tourists. has been enlarged and Newly Furnished. The Apartments, large and small, combine elegance and comfort, and every attention has been paid to make this one of the best Provincial Hotels. Public and Private Drawing-rooms; English and French Papers. Table d'Hôte at 11 and 6. Private Dinners at any hour. Excellent Cuisine. Mederate Charges. The Omnibuses of the Hotel meet all Trains.

L. TRILLAT, Proprietor.

First-Class Carriages can be had at the Hotel for Excursions to the Grande Chartreuse, Uriage, and all places of interest amongst the Alne of Dauphine.

URIAGE - LES - BAINS.

HOTEL RESTAURANT, MONNET.

Founded in 1846. English Visitors will find every comfort and luxury in this First-Class Establishment. Private Rooms for Families. Excellent Cuisine and Wines. Table d'Hôte, 11 and 6. Carriages and Horses can be had in the Hotel for Excursions and Promenades.

HAMBURG.

L'EUROPE.

)LD - RENOWNED FIRST-CLASS HOUSE, patronised by the imperial and Royal Families. Delightful situation, overlooking the Alater. 180 elegantly furnished Rooms and Apartments. Bath, Reading, and Smoking Rooms. Table d'Hôte. Hydraniic Lifts. Special arrangements made at a longer stay.

BRETTSCHNEIDER AND BANDLI, Proprietors.

HAMBURG.

HÔTEL ST. PETERSBURG.

OLD-BENOWNED FIRST-CLASS FAMILY HOTEL, situated on the Alster Bassin, the most fashionable quarter of the town U the most fashionable quarter of the town. Superior comfort and accommodation.

Table d Hôte and Restaurant à la carte. Resplendent Electric Light throughout. Near Safety Lift. Telephone. G. REUTER, Proprietor.

2 vols., royal 4to. 42s. each.

ETCHINGS FROM THE LOIRE AND THE MOSEL.

A Series of Forty Plates, with Descriptive Letterpress. BY ERNEST GEORGE.

JOHN MURRAY, ALBEMARLE STREET.

HANOVER.

HÔTEL ROYAL.

(FIRST-CLASS HOTHL.)
CITUATED in the best part of the City, and opposite the General Railway Station.
Large and small Apartments and Single Bed-rooms for Gentlemen. Every comfort.
Baths in the Hotel.

MODERATE CHARGES.

CHRIST BROS., Proprietors.

HANOVER.

HÛTEL DE RUSSIE.

THIS FIRST-CLASS HOTEL is beautifully situated opposite the Railway Station and Post Office, and in the healthtest part of the City, and in the centre of large gardens. The Proprietor and Proprietors have been for several years in England and France, and make the comfort of English and American Families their special study. The prices are very moderate, and the servants are trained to be cityl and obliging to visitors, and not to accept fees.

C. FREIBERG, Proprietor.

HANOVER.

CONTINENTAL HÔTEL.

NEW FIRST-CLASS HOTEL, 150 Rooms, with every modern comfort. Lifts, &c. Moderate Charges.

F. RIECHELMANN, Proprietor.

"THE GRANBY."

IRST-CLASS Family Hotel, facing the Stray. Every accommodation for Visitors and Tourists. Carriages to Wells and Baths every morning free of charge. Good Stabling. Carriages on Hire.

W. H. MILNER. Proprietor.

HAVRE.

HÔTEL D'ANGLETERRE. RUE DE PARIS. 124-126.

EXCEEDINGLY well-situated in the best quarter of the Town, is recommended for its Comfort and Moderate Charges. Apartments for Families; Music and Conversation Saloons. Restaurant a la Carte. Rooms from 2 to 5 francs. Breakfast, 2 francs. Dinners at Table d'Hôte, 3 francs. Board and Lodging from 8 to 10 francs per day. Wine and Service included. English and German spoken.

GRELLÉ, Proprietor.

HAVRE.

HÔTEL CONTINENTAL.

Quai des Etats Unis et Boulevard François I^{er.}
Facing the Sea. Opening 1st June.

TIRST-CLASS HOTEL, beautifully situated; newly-built and furnished, with every modern comfort. Large and small Apartments. Rooms from 3 francs. Table d'Hôte. Restaurant "à la Carte." Saloon. Smoking Room. Charges mederate. English spoken. Open all the year.

LÉON SOUCHARD, Proprietor.

HAVRE.

GRAND HÔTEL DE NORMANDIE.

RUE DE PARIS.

FIRST-CLASS HOTEL, exceedingly well situated in the centre of the Town. Apartments for Families. Moderate prices. Music and Conversation Salcons. "Table d'Hôte." Restaurant à la Carte. English and German spoken.

M. DESCLOS, Proprietor.

HEIDELBERG.

NECKAR HÔTEL.

Opposite the Buins of the Castle. Open May 1st.

CITUATED close to the Necker, fifteen minutes from the Castle and D ten minutes from the Ballway, near the fine old Necker Bridge, it is a new and elegant First-Class Establishment, one of the most beautifully-situated Hotels in Germany. The only Hotel from which a full view of the Ruins and the Panorams of the City and Valley can be had. A Large Garden and Terrace close to the House. Baths. Table of Hôte. Restaurant à la carte. Pension the whole year. Omnibus at the Station. Under the management of the Proprietor of the old-renowned Hotel de Hollands.

HÔTEL DE HOLLANDE.

An Old-Established Hotel, beautifully situated. Excellent Cooking.

L. SPITZ, Proprietor.

HÔTEL EUROPE.

THE finest and best situated Hotel in Heldelberg; kept in the very superior and elegant style
of a First-class Family Hotel. The beautiful extensive Gardens are for the exclusive use
of the Visitors. Hot and Cold Baths fitted up in a superior manner in the Hotel. Ournibus
at the Station. Terms strictly moderate. Railway Tlokets are issued in the Hotel.

HARFELI-GUJER, Proprietor.

HOMBURG.

HÖTEL BELLE VUE.—First-Class Hotel, exceedingly well situated, opposite the Park of the Kursaal, and close to the Springs. Families, and Single Gentlemen, will find this Hotel one of the most comfortable, combining excellent accommodation with cleanliness and moderate Charges. Best French and English Cooking. Excellent Wines. Hare and Partridge Shooting free.

H. ELLENBERGER, Proprietor.

HOMBURG.

POYAL VICTORIA HÔTEL.—Patronised by H.R.H. the Prince of Wales and several other Royal Personages. Highest Position. First-Class Hotel, close to the Springs and the Kursal, with fine view of the Tamus Mountains. Quiet Apartments. At the early and later part of the 8-ason arrangements are made on very reasonable torms. Best Stag and Roebuck Shooting, as well as Trout Fishing, free for the guests of the Hotel.

GUSTAVE WEIGAND, Proprietor.

HYÈRES (VAR).

GRAND HÔTEL D'ORIENT.

THIS Hotel is situated in the most salubrious and sheltered part of Hyères, and is the Resort of the étite of English and French Society. Drawing Room full South. Billiards.

ENGLISH NEWSPAPERS.

HEIDELBERG. - Hôtel Prince Charles. A FIRST-CLASS HOTEL



(UNormanable emerged by a New Bulliang Contents a spiendid Dioling Recoil, 6 reastless Borlin, a ... a ... a ... a ... a ... in a Reading Room. Ten Balconies. This Hotel, patronised by their Highnesses the Prince of Wales and Frince Alfred, is the largest in the Town, and thoroughly Benovated and Newly Farnished. Bost Cookery, Good Wines. Charges Reasonable. Moderate Arrangements made by the Week. The Hotel is situated in an open Square, eight mininter walk from the colebrated Costle, with the finest riew of the rains from all the balconies and hearly all the windows; two minutes walk to the Necker Bridge. Close to the Nurnburg and Wursburg Ballway Station. Omnibus and Roiel Porter meet the Train. From this Hotel there are three different roads leading to the Castle. Firstly, footpath ever the Kursen Buckel; steps, five minutes; sunny. Secondly, by the Burgweg: eight minutes walk; shady; the finest. Thirdly, Noner Schlossweg: by carriage; gentle ascent. The Proprietors report Wines to Ringland.

G Ballway Tickets can be obtained at the Burcan of the Hotel, and Luggage booked to all Stations.

SOMMER & ELLMER, Proprietors.

HYÈRES. HÔTEL DE L'ERMITAGE.

BEAUTIFULLY situated in the Pine Forest, well sheltered, and commanding magnificent view of the Mediterranean and the Hes of Hyères. Drawing and Dining Rooms, full South. Billiards. Full-sized Lawn Tennis Grounds. English management. Divine Service in the Hotel.

OMNIBUS TO AND FROM ALL TRAINS. A. PEYRON, Proprietor.

HYERES-LES-PALMIERS.

GRAND HÔTEL DES ILES D'OR.

THIS FIRST-CLASS HOTEL, the largest in the Town is situated in the middle of a most beautiful Garden. Lawn Tennis Ground in front of the Hotel. Dining and Drawing Rooms full South containing a Collection of Pictures by a celebrated French artist.

Smoking Room, Billiards, and Baths.

Pension from 10 france a day and upwards.

E. WEBER, Proprietor.

ROYAL CLARENCE

FAMILY AND COMMERCIAL HOTEL.

(Old Established.)

HAS recently been rebuilt with extra Bed Room accommodation and Ladies' Drawing Room. Commodious Coffee Room. Handsome Commercial Room and Good Stock Room. Billiards.

Omnibus meets every Train.

TARIFF ON APPLICATION. SPECIAL TERMS FOR BOARDING.
RICHARD LAKE. Proprietor.


I LFRACOMBE HOTEL. "A Model of Senitary Excellence."—The lifracombe Hotel is on the verge of the Atlantic, in its own picturesque Grounds of Five Acres, with Tennis Lawn, &c. it contains 250 Rooms. The Charges are fixed and moderate, and there is a Table d'iblée Daily. Every information will be afforded by the Manager, lifracombe, North Devon. Tourist Tickets to Hiracombe for Two Months are issued at all principal Stations. There is attached to the Hotel one of the largest Sea Water Swimming Baths in England; also Hot and Cold Sea Water Frivate Baths.

THE ROYAL BRITANNIA HOTEL, ILFRACOMBE, — Good Public Rooms.

Moderate Terms.

Address—THE MANAGES.

IINNSBRUCK.



HOTEL DU TYROL.—First-Class Hôtel, in a beautiful position near the Station and the new Steam Baths, with magnificent Views of the Valley of the inn and the Mountains. Comfortable Apartments, Reading, Smoking, Bath Rooms, &c., with every modern convenience. Arrangement for prepared stay. Special terms for solound in winter. Climate exceedingly healthy; air brasing.) In Wister Stairs and Passages warmed. From the top of the hotel a fine birds-eye view of the Town and Valley. Motel chiarget. Splendid Garden lately acquired. CARL LANDS FIE.

INNSBRUCK.

HÔTEL DE L'EUROPE.

EPT by Mr. J. REINHART.—A new and well-furnished First-Class Hotel, conveniently situated, just facing the splendid valley of the lim, opposite the Railway Station Excellent Table d'Hôte and private Dimers. Arrangements made at very resconable prices Well-furnished Apartments. English Newpapers taken in. Splendid situation, commanding a fine Viaw of the Mountains. English spoken.

INTERLAKEN.

HOTEL-PENSION.

JUNGFRAU.

F. SEILER-STERCHI. Proprietor.

THIS Establishment, with two Branch Houses, is situated in the centre of the Höheweg, and enjoys a splendid view of the Jungfrau and the entire range of the Alps. It recommends itself for its delightful position, as well as for its comfortable accommodation.

TABLE D'HÔTE AT 2 AND 6.30 O'CLOCK. DINNERS À LA CARTE.

CARRIAGES, GUIDES, AND HORSES FOR MOUNTAIN EXCURSIONS.

OMNIBUS WAITING AT ALL THE STATIONS.

INTERLACKEN.

J. GROSSMANN.

Sculptor in Wood, and Manufacturer of Swiss Wood Models and Ornaments.

Carved and Inlaid Furniture Manufactured to any Design,

AT INTERLACKEN.

IS WAREHOUSE is situated between the Belvedere Hotel and Schweiserhof, where 1. be keeps the largest and best assortment of the above objects to be found in Switzer-land. He undertakes to forward Goods to England and elsewhere. Correspondents in Esgland, Messra. J. & R. MOCRACHEN, 39, Queen Street, Cannon Street, E.O., London.

INTERLAKEN.

GRAND HÖTEL BEAU RIVAGE.

in a Splendid Position. Recently built EVERY LUXURY AND COMFORT. H. REGLI. Proprietor.

INTERLAKEN.

SCHWEIZERHOF-HÔTEL SUISSE.

J. & E. STRUBIN & WIRTH, Proprietors.

THIS First-Class Family Hotel of old reputation is situated in the best position of the Köheweg, near the Kursaal Gardens. Every modern comfort.

INTERLAKEN.

RAND HÔTEL DES ALPES

Is surrounded by large shady Gardens and Grounds, contains large Dining and Drawing-Rooms, fine Reading, Billiard and Smoking-Rooms, commanding a full view of the Glaciers.

Warm and Cold Baths. Lawn Tennis. Moderate Prices.

MAURER-KNECHTENEOFER, Proprietor.

KARLSRUHE.

HÔTEL GERMANIA.

CITUATED a few minutes from the Railway Station, on the Public Gardena. This First-Class Hotel is furnished with every modern comfort. 100 Rooms and Sultes of Apartments. Bed an a attendance from 2 Marks. The whole of the house heated so as to ensure comfort to Winter Visitors, for whom also Special Arrangements are made. Baths. Lift. Omnibuses at the Station.

KISSINGEN.

HÔTEL SANNER.

FIRST-CLASS Family Hotel, of good reputation for its comfort, cleanliness, and good Cuisine. Beautiful situation with open views. Well furnished large and small Apartments. Three Minutes from the Kurhaus, Springs, and Garden. The only Hotel in Kissingen fitted up with the latest improved Sanitary Water appliances.

CHARGES STRICTLY MODERATE.

SCHMIDT, Proprietor.

KISSINGEN.

ROYAL CURHAUS HÔTEL.

ARGEST and best situated First-Class Hotel in town. 160 Bed Rooms with 30 Sitting Rooms, all with a fine open view. Pension in the early and later part of the Season. The only Hotel with Mineral Bath in the House.

F. JOS. MULLER, Manager.

KISSINGEN.

HÔTEL D'ANGLETERRE.

THIS First-Class Hotel is situated three minutes from the Springs and the Kurgarden. Excellent Table d'Hôte. Pension from 7 Marks each Person. Omnibus at every Train.

L. MISMER, Proprietor.

Second Edition, with Portrait and Illustrations. 2 vols. 8vo. 21s.

THE LIFE AND TIMES OF TITIAN. With some Account of his Family, chiefly from new and unpublished Records

"No such gap has existed in the history of art as that which is filled by the present volumes. Everything on the subject is now superseded. We cannot make an abstract of nine hundred pages; suffice it to repeat that the book is by far the most important compation made in our time to the history of art."—Atheneuse.

By J. A. Crowe and G. B. CAVALCASELLE.

JOHN MURRAY, ALBEMARLE STREET.

KILLARNEY.

LAKES OF KILLARNEY.

By Her Most Gracious Majesty's Special Permission.

THE ROYAL VICTORIA HOTEL.

Patronised by H.E.H. THE PRINCE OF WALES; by H.R.H. PRINCE ARTHUR, and by the Royal Families of France and Belgium, &c.

THIS HOTEL is situated on the Lower Lake, close to the water's edge, within ten minutes' drive of the Railway Station, and a short distance from the far-famed Gap of Dunice. It is lighted with gas made on the premises; and is the Largest Hotel in the district. A magnificent Coffee-room, a public Drawing-room for Ladies and Families, Billiard and Smoking-rooms, and several suites of Private Apartments facing the Lake, have been recently added

TABLE D'HÔTE DURING THE SEASON.

Cars, Carriages, Boats, Ponies, and Guides at fixed moderate charges.

Drivers, Boatmen, and Guides are paid by the Proprietor, and are not allowed to solicit
gratulties. The Hotel Omnibus and Porters attend the Trains.

THERE IS A POSTAL TELEGRAPH OFFICE IN THE HOUSE.

Boarding Terms from October to June, inclusive.

It is necessary to inform Tourists that the Railway Company, Proprietors of the Railway Hotel in the Town, send upon the platform, as Touters for their Hotel, the Porters, Car-drivers, Boatmen, and Guides in their employment, and exclude the servants of the Hotels on the Lake, who will, however, be found in waiting at the Station-door.

JOHN O'LEARY, Proprietor.

LAUSANNE - OUCHY.

HÔTEL BEAU RIVAGE.

DIRECTOR, A. MARTIN-RUFENACHT.

THIS splendid Establishment, constructed on a grand scale, is situated on one of the most beautiful spots on the shore of the Lake of Geneva, surrounded by an English Park and Garden. It is near the Steamboat Landing and the English Church.

WINTER PENSION

FROM OCTOBER UNTIL MARCH, AT VERY MODERATE PRICES.

Constant communication with the City and Railway Station by Omnibus.

Baths, Telegraph, and Post Office in the Hotel.

LAUSANNE.

HÔTEL GIBBON.

FIRST-CLASS Hotel, situated in the finest part of the town, and most highly recommended. Splendid view of the Lake. Large Terrace and Garden. Pension during Winter. RITTER-BOCHAT, Proprietor.

LAUSANNE.

HÔTEL PENSION VICTORIA.

BEAUTIFUL situation, large garden. Most excellent house and reasonable terms. LS. DESPLAND, Proprietor.

A COMPANION TO BRADSHAW. Handbook for England and Wales.

Describing the History and Objects of Interest of each Locality, as well as the Means of Access, Hotels, Lodgings, &c. Alphabetically arranged for the use of Travellers. With an Outline Map. Post 8vo. 108.

"An admirably arranged epitome of useful information, giving not merely all necessary details of hotels, trade, &c., but a condensed history of remarkable places in the neighbourhood of each town, and suggestive skeleton tours,"—The World.

JOHN MURRAY, Albemarle Street.

LAUSANNE. GRAND HOTEL DE RIGHEMONT.

TINEST and best situated quiet First-Class
Hotel of Lausanne. Amongst large
gardens. In an exceedingly beautiful and
healthy position. Hishly recommended.
Moderate Charges. Pension.

RITTER-WOLBOLD

LEAMINGTON.

The Clarendon Family and Private Hotel.

SITUATED in the highest part of the Town. Highly recommended by the best English and American Families, for Comfort and Moderate Charges. Carriages.

LISBON.

BRAGANZA HOTEL.

THIS First-Class well-known Family Hotel, lately renovated by the Royal House of Bragansa, and fitted up by the new Proprietor, Victor C. Sassett, highly recommendable for its large, siry, and comfortable Apartments commanding the most extensive and picturesque views of the River Tagus, as well as of Lisbon. Superior Culsine, and carefully-selected Wines. Under the same Management, within 2½ hours' drive, VICTOR'S ROYEL, CINTRA.

RAMBLES AMONG THE HILLS IN THE PEAK of DERBYSHIRE and the SOUTH DOWNS.

By LOUIS J. JENNINGS, Author of "Field Paths and Green Lanes."
With Illustrations. Post 8vo. 12s.

JOHN MURRAY, ALBEMARLE STREET.

Crown 8vo., cloth, 6s.

THE COPTIC MORNING SERVICE FOR THE LORD'S DAY.

Translated into English by JOHN, MARQUESS OF BUTE, K.T. With the Original Coptic of those parts said aloud.

London: J. MASIERS & CO., 78, New Bond Street,

MURRAY'S HANDBOOK FOR PORTUGAL:

LISBON, OPORTO, CINTRA, MAFRA, &c. Map and Plan. Post 8vo. 12a
JOHN MURRAY, ALBEMARLE STREET.

LAKE MAGGIORE LOCARNO LAKE MAGGIORE (Switzerland)

(Switzerland)
Beginning of the St. Gothard Railway and Landing Stage.

the italian Lakes.

Best intermediate Station on

GRAND HOTEL LOCARNO

Magnificent Establishment, one of the finest in Switzerland. Two Hundred Rooms. Pension from 74 francs, including Room. English Church. Baths. Billards. Large Garden. G. SEVOHAB & Co.

LOCH LOMOND.

INVERSNAID HOTEL.

THE LANDING PLACE FOR LOCH KATRINE, THE TROSACHS, ABERFOYLE, &c.

Parties Boarded by the Week or Month.

ROBT. BLAIR, Proprietor.

LONDON.

PHOTOS FOR PRESENTS LETTS.

A LARGE Collection of Views of this Neighbourhood, from 1s. each; also of Views of other parts of the United Kingdom, France, Italy, Spain and Portugal, Norway, Switzerland, Egypt, Palestine, India, United States, English Cathedrals, Abbeys and Castles, on approval, to double amount of cash sent. Lists on receipt of stamped addressed envelope to

LETTS, SON, & CO., LIMITED,
72. QUEEN VICTORIA STREET, LONDON, E.C.

TRAVELLERS' REQUISITES.

MAPS OF EVERY COUNTRY OR PART OF THE WORLD.

Knapsacks and Bags, Passports and Visas, Colour Boxes, Drawing Blocks, Guide Books, and Time Tables,

New Books of Roads, describing their Character.

Send Stamp for Tourist Catalogue.

LETTS, LIMITED, LONDON BRIDGE, S.E.

DINNEFORD'S MAGNESIA.

A Pare S lution.
For Acidity of the Stomach.
For Heartburn and Headache.
For Gout and Indigestion.
Safest Aprient fr Delicate
Constitutions, Ladies, Children, and Infants.

DINNEFORD & CO., 180, New Bond Street, London.
Sold by Chemists throughout the World.

MURRAY'S HANDBOOK-LONDON AS IT IS.

Maps and Plans, 16mo. 3s. 6d.

THE

COMMERCIAL BANK OF ALEXANDRIA, LIMITED.

CAPITAL, £480,000, in Shares of £6 each.

Paid-up £3 per Share, say £240.000. RESERVE FUND, £25,000.

Directors.

THOMAS S. RICHARDSON, Esq., Chairman.

EMMANUEL A. BENACHI, Esq. JACOB BRIGHT, Esq., M.P. JOHN COW, Esq.

JOHN CONSTANTINE CHOREMI, Esq. JOSEPH MELLON, Esq. CONSTANTINE GEORGIO ZERVUDACHI, Esq. Auditors-W. W. DELOTTE, Esq., and JOHN ELIN. Esq.

HEAD OFFICE-2, MOORGATE STREET, LONDON, E.C. WILLIAM ROBERT LA THANGUE, Manager. JOHN BROOKS, Secretary,

ALEXANDRIA OFFICE .- DUKE BAKER, MORAGOR.

Bankers.

BANK OF ENGLAND.

LONDON AND COUNTY BANK.

Letters of Credit granted on Alexandria, and payments made in Cairo and Sues, Bills for collection encashed in any part of Egypt, and the purchase and sale of Egyptian and all kinds of Securities undertaken.

interest allowed at the rate of 5 per cent, per annum on money deposited for not less than twelve months.

LONDON.

THE LONDON AND WESTMINSTER BANK, Limited, issues Chroular Notes of £10, £25, and £50 each, for the use of Travellers payable in the principal Towns on the Continent of Europe, also in Asia, Africa, and North and South America. No expense whatever is incurred, and when cashed no charge is made for commission. Letters of Credit are also granted on the same places. They may be obtained at the City Office in Lothbury, or at any of the Branches, viz .: -

Westminster Branch . 1, St. James's Square. | Marylebone Branch . 4, Stratford Place. Bloomsbury . 214, High Holborn. Southwark

Eastern


May, 1882.

. 6, High St., Borough. . 130, High St., Whitechapel,

Oxford Street. Temple Bar

. 217, Strand. Lambeth . 89 & 91, Westmineter Bridge Road.

South Kensington Branch, 192, Brompton Rd.



THE

GRAND HOTEL,

TRAFALGAR SQUARE,

LONDON.

This Magnificent Hotel occupies the Finest Site in the

CENTRE OF THE METROPOLIS,

And combines the Elegance and Luxury of the most important and attractive Hotels in Europe and America, with the Repose and Domestic Comfort which are essentially English.

THE RECENT EXTENSIONS OF THE BUILDING

HAVE ADDED TO

THE GRAND HOTEL

UPWARDS OF A HUNDRED BED AND SITTING ROOMS.

For Apartments, address THE SECRETARY.

One of the Sights and one of the Comforts of London.

THE

HOLBORN RESTAURANT,

218, HIGH. HOLBORN.

THE FAMOUS TABLE D'HÔTE DINNER, served at separate Tables, accompanied with Selection of High-class Music by complete Orchestra. 5.30 to 8.30 every Evening, 3s. 6d.

TOURISTS AND TRAVELLERS.



Ladies visiting the Seaside, Rinking, Driving, or otherwise exposed to the sconching rays. the Sun, or heated particles of dust, will find

ROWLAND'S KALYDOR

Most cooling and refreshing to the face, hands, and arms: it eradicates all Sunburn, Freckles, Tan. Stings of Insects. &c.

Sizes, 4s. 6d. and 8s. 6d. per Bottle.

ROWLAND'S ODONTO

has been proved, by its unparalleled success of 50 years, to be the best, purest, and most

fragrant Dentifrice for procuring White and Sound Teeth, Healthy Gums, and Fragrant Breath, being perfectly free from all deleterious and acid compounds, which give a temporary whiteness to the Teeth, but ultimately ruin the enamel.

Sold by Chemists and Perfumers.

FOREIGN BOOKS AT FOREIGN

TRAVELLERS may save expense and trouble by purchasing Foreign Books in England at the same Prices at which they are published in Germany or France.

have published the following CATALOGUES of their Stock :--

- 2 THEOLOGICAL CATA-LOGUE.
- 3. FRENCH CATALOGUE.
- 4. GERMAN CATALOGUE. 5. EUROPEAN LINGUISTIC CATALOGUE.
- 6. ORIENTAL CATALOGUE.
- 7. ITALIAN CATALOGUE.
- 8. SPANISH CATALOGUE. 9. ART-CATALOGUE, Art, Archi-
- tecture, Painting, Illustrated Books. 10. NATURAL HISTORY
 - tany, Geology, Chemistry, Mathe matics. &c.

- 1. CLASSICAL CATALOGUE. | 11. NATURAL SCIENCE CATALOGUE. Mathematics. Astronomy, Physics, Chemistry, Technology.
 - 12. MEDICAL CATALOGUE. Medicine, Surgery, and the Depet.dent Sciences.
 - 18. SCHOOL CATALOGUE. Elementary Books, Maps, &c.
 - 14. FOREIGN BOOK CIRCU-New Books, and New LARS. Purchases.
 - CATALOGUE. Zoplogy, Bo- 15. SCIENTIFIC-BOOK OTROU-LARS. New Books and Recent Purchases. .

ANY CATALOGUE SENT POST-FREE FOR ONE STAMP.

WILLIAMS & NORGATE, Importers of Foreign Books.

14, HENRIETTA STREET, COVERT GARDEN, LONDON, and 20. SOUTH FREDERICK STREET, RONBURGH.

NEW AND CHOICE BOOKS.

More than One Hundred and Fifty Thousand Volumes of the Best Books of the Past and Present Seasons are in Circulation at

MUDIE'S SELECT LIBRARY.

The Collection exceeds One Million Volumes, comprising all the Best Modern Works of every shade of opinion on all subjects of general interest. Fresh Copies are added as the demand increases; and an ample supply is provided of all the Best Forthcoming Works as they appear.

SUBSCRIPTION, ONE GUINEA PER ANNUM

AND UPWARDS, according to the Number of Volumes required.

LONDON BOOK SOCIETY SUBSCRIPTION, TWO GUINEAS
PER ANNUM. For the Free Delivery of Books in every part of London.

Thousands of Families in London and the Suburbs already subscribe to this Department of the Library, and obtain a constant succession of the Best Books of the Season.

BOOK SOCIETIES SUPPLIED ON LIBERAL TERMS.

Prospectuses postage free on application.

MUDIE'S SELECT LIBRARY (Limited), 30 to 34. New Oxford Street, London. CITY OFFICE—2, KING STREET, CHEAPSIDE.

TO CONTINENTAL TRAVELLERS.

DORRELL AND SON'S PASSPORT AGENCY,

15, OHARING CROSS, S.W.

A PASSPORT is a ready means of identification, and although it
may not be asked for in some countries, in others it is absolutely necessary, and the want of

it may cause great inconvenience.

BETTISH SUBJECTS visiting the Continent will save trouble and expense by obtaining their Passports through the above Agency. No personal attendance is required, and country residents may have their Passports forwarded through the post. A Form of Application forwarded by Post. Passports Mounted and enclosed in Cases with the name of the bearer impressed in gold on the outside; thus affording security against injury or loss, and preventing delay in the frequent examination of the Passport when travelling.

Fee, Oblaining Pussport, 1s. 6d.; Visas, 1s. each. Cases, 1s. 6d. to 5s. each.

HANDBOOK TO THE ENVIRONS OF LONDON.— An Account, from personal visits, of every Town and Village within a circle of twenty miles round the Metropolis, and the more important

An Account, from personal visits, of every flown and vising within a circle of twenty miles round the Metropolis, and the more important places lying four or five miles beyond that boundary. Alphabetically arranged. By James Thorne, F.S.A. With Index of Names. 2 vols. Crown 8vo. 21s.

This Work comprises the whole of Middlesex, part of Surrey, Kent, Essex, and Herts, and smaller portions of Berks and Bucks.

"Such a work as Mr. Thorne's Handbook was called for. The 'call' has been admirably responded to. Mr. Thorne's book, although a work of reference and a guide, is full of pleasant goestp. We find Mr. Thorne's book an excellent performance of a work which was required."—The Times.

JOHN MURRAY, ALBEMARLE STREET.

Gold Medal, Paris, 1878. Medals, Sydney, 1880; Melbourne, 1881.

FRY'S COCOA EXTRACT

GUARANTEED PERFECTLY PURE COCOA ONLY, deprived of the Superfluous Oil.

"Strictly pure."—W. W. Stoddart, City and County Analyst, Bristol.
"Pure Cocoa."—Charles A. Cameron, Analyst for Dublin.

Try also FRY'S CARACAS COCOA,
"A DELICIOUS PREPARATION."

15 PRIZE MEDALS awarded to J. S. FRY & SONS.

LUCERNE.

SCHWEIZERHOF. LUZERNERHOF.

First-Class Hotels.

HAUSER BROTHERS, PROPRIETORS.

BEST SITUATION ON THE QUAY.

With splendid View of the Celebrated Panorama of the LAKE AND MOUNTAINS.

LUCERNE.

GRAND HÔTEL NATIONAL.

SEGESSER BROTHERS and CIE., Proprietors.

THIS large and splendid HOTEL is one of the most comfortable in Europe. Situated in front of the Lake, with the finest Views. Every attention paid to Tourists.

A LIFT FOR THE USE OF VISITORS.

LYNTON (NORTH DEVON).

THE VALLEY OF ROCKS HOTEL.

THIS favourite and beautifully situate First-Class Hotel is built on one of the finest sites in the neighbourhood, and largely patronised by the best Families. It has been considerably enlarged, remodelled, and inspectly patronised by the best Families. It has been considerably enlarged, remodelled, and improved; and combines, with Moderate Charges, all necessary means for the accommodation and comfort of Families and Tourists. The splendid Table d'Hôte and Coffee Room, Reading Rooms, Ladies' Drawing Room, and several Private Sixting Rooms, replete with every comfort, range in a long iront, overlooking the Séa, and looking into the extensive Private Grounds of the Hotel. It is most conveniently situate as a centre for visiting all the places of interest in the district. Handsomely-fitted Billiard Room open during the Season for Residents in the Hotel only.

Post-Horses and Carriages: also the very best kind of Modern Stabling.

JOHN CROOK, PROPRIETOR.

LYONS.

GRAND HÔTEL DE L'UNIVERS.

FACING PERRACHE STATION.

FIRST-CLASS FAMILY HOTEL. FULL SOUTH.

GROUND FLOOR APARTMENTS.

Railway Tickets Office.

MADRID.

GRAND HÖTEL DE LA PAIX.

THE ONLY FRENCH HOTEL IN MADRID.

FIRST-OLASS Hôtel, Boarding-House, in the finest part of the Puerta del Sol, with magnificent views and full southern aspect. Table d'Hôte. Private service. Large and small apartments. Bath. Reading-room, with Plano. Foreign Newspapers. Great comfort and cleanliness. French Cuisine. Omnibus at Railway Stations. Interpreters.

Grand Hôtel de Londres. Family Hotel. Annex of the Hôtel de la Paia, under the same management. Moderate Prices.

T. CAPDEVIELLE & Co.,

Proprietors of both Houses.

MARIENBAD (BOHEMIA).

'HOTEL KLINGER.

Proprietor, J. D. HALBMAYR.

Preferred on account of its charming situation at the corner of the Promenade and Park, and has a beautiful View. Newly and elegantly furnished with every comfort and in noble style, containing, with the Dépendance, 270 Rooms, Saloons, &c. English spoken in the Hotel.

Carriages in the Hotel. Omnibus to the Railway Station.

MAYENCE.

First-Clase Hotels.

HÔTEL DU RHIN. HÔTEL DE HOLLANDE. HÔTEL D'ANGLETERRE.

Best Second-Class Hotel.

HÔTEL DE LA CARPE.

MENTONE. (Alpes Maritimes.)

HÔTEL DES ANGLAIS.

THIS well-known Establishment has been newly improved, and combines every modern comfort with moderate and fixed prices. Situated in the East Bay, near the favourite residence of Her Majesty Queen Victoria.

Messrs. CLERICY BROTHERS.

MENTONE.

ISNARD'S

HÔTEL DE BELLE VUE.

THIS well-known ESTABLISHMENT is beautifully situated in the best quarter of the Town, with a vast Garden, and affords every English comfort.

MENTONE.

GRAND HÔTEL WESTMINSTER.

Central First-Class Establishment.

BUILT and furnished with taste and according to the latest improvements. In a Southern aspect overlooking the Sea, and a beautiful Garden giving access to the public "Promenade du Midi." Fine Public Salcon and Reading Room. Billiard and Smoking Rooms. Patronised especially by English. Moderate Prices.

ENGLISH AND SEVERAL FOREIGN LANGUAGES SPOKEN.
ONNIBUS TO AND FROM THE BAILWAL STATION.

.....

GRAND HÔTEL DE L'EUROPE.

THE largest and most beautiful Hotel in Lorraine, patronised by the most Aristocratic Families. This splendid Establishment is recommended for its comfort and Moderate Charges. English Newspapers.

MILAN.

GRAND HÔTEL DE MILAN.

200 Rooms and Saloons, with every comfort and requirements of the present day.

Pension in the Winter Months.

. THE ONLY HOUSE AT MILAN WHICH HAS A HYDRAULIC LIFT.

J. SPATZ-WÜRMS.

MILAN.

GRAND HOTEL, CONTINENTAL.

7, VIA MANZONI.

FIRST-CLASS HOTEL, containing 200 Rooms, and Salons. The nearest to the Cathedral, Post Office, and Theatre de la Scala. Full South aspect.

Hydraulic Lift, with Safety Apparatus.

MARINI, LEGNANI, & CO.

MILAN.

HÔTEL BISCIONE.

A HIGHLY recommended Hotel and Pension, warmed and conveniently stinated, overlooking the Square and Cathedral. First-rate Restaurant. Table d Hôte. Plano. Telephone. Omnibus to and from all Trains. Fixed inderste prices. BORRLLO, Propr. The same Proprietor as Hotel Aigle Noit and Pair at Bologna.

MILAN.

HÔTEL DE LA GRANDE BRETAGNE

E REICHMANN. Proprietor. J. LEGNANI.

THE House is situated in the centre of the Town, near the Cathedral and all other Places of interest. Good Table d'Hôte. The Times, &c. Several Languages spoken. The House is only two Storeys high. minutes' walk from the English Church.

Omnibus at the Station to meet all Trains.

MOFFAT HYDROPATHIC ESTABLISHMENT AND SANATORIUM, DUMFRIESSHIRE, N.B.

Resident Physician, Dr. R. THOMSON FORBES.

77HIS Establishment, which occupies a beautiful situation on the western slope of the beautifully wooded Gallowhill, and within a short distance of the far-famed "Moffat Well." is replete with every comfort for visitors and patients. The public rooms, halls, and corridors are universally recognized as unsurpassed by any similar Establishment, and the baths are of the most varied and perfect construction. Moffat has long been a favourite resort for those seeking health and pleasure, and in the Establishment, here is the additional attraction of good society and varied amusements. For full particulars apply to

THE MANAGER.

MULHOUSE (ALSACE).

HÔTEL CENTRAL.

(Formerly HÔTEL ROMANN.)

IN Town the only First-Class Establishment for Merchants and Families. This House has been entirely redecorated. Baths, Grand Café, Smoking, and Billiard Rooms. The Hôtel is in Telephonic connection with the Merchants' Offices in Town and Neighbeurhood.

Mulhouse is the best resting-place between France, Belgium, Holland, North Germany, and Switzerland.

E. GRAEUB, Proprietor.

MUNICH. WIMMER & CO.,

GALLERY FINE

3. BRIENNER STREET,

Invite the Nobility and Gentry to visit their GALLERY OF FIVE ARTS, containing an Extensive Collection of

> MODERN PAINTINGS by the best Munich Artists.

PAINTINGS ON PORCELAIN AND ON GLASS.

Correspondents in England, Mesers. J. & R. MCHACKEN, 38, Queen Street, Cannon Street, E.C., London, Correspondents in the United States, Mesers. BALDWIN BROS. & Co. 72, Broadway, New York.

MUNICH.



BAVARIAN HOTEL. HOTEL DE BAVIÈRF.

OSCAR SEIF, Proprietor. Excellent First-class Hotel. Finest and healthlest situation and Carriages in the Hotel. Best Cooking and Wines. Moderate Charges. Personal management by the Proprietor.

NAPLES.

HÔTEL DE ROME.

Incomparable situation facing the Sea and overlooking the Bay and Mount Vesuvius.

Great Bath Establishment.

A. BRUSCHETTI, MANAGER.

NICE-(CARABACEL).
JULLIEN'S HOTEL.

Highly Recommended.

CHARGES VERY MODERATE.

JULLIEN, Proprietor.

HÔTEL DE BELLE VUE

Mr. ALBERT ELSKES, Proprietor.

FIRST-CLASS HOTEL, magnificently situated on the border of the Lake, commanding splendid views of the Panorama of the Alps. MODERATE CHARGES.

N.B.—Besides the Evening Train (direct) a Day Train is newly organised between Neuchatel and Paris, and vice vered.

NICE.

HÔTEL DE FRANCE—Quai Masséna.

M^{me} S. ZUNDEL, Proprietress.

FIRST-CLASS FAMILY HOTEL of universal reputation, commanding a fine View of the Sea, and in best central position, close to the Public Garden and the Promenade. House Patronised especially by English and American Families.

Table d'Hôte, having the Reputation of being the best in Nice. Charges very moderate.

NICE.

SOCIÉTÉ ANONYME DE LA GRANDE BRETAGNE.

HÔTEL DE LA GRANDE BRETAGNE.

Best Position of the Town, facing the Public Gardens, where Concerts are given Daily, and overlooking the

PROMENADE DES ANGLAIS AND THE SEA.

New Reading and Smoking Rooms. South.

COSMOPOLITAN HOTEL

(late Chauvain's).

Enlarged, Restored, and entirely Refurnished by the New Manager.

Reading, Ladies' Drawing, Billiard, and Smoking Rooms.

SPLENDID GALLERIE PROMENOIR.

FOUR LIFTS.

HÔTEL DE L'ELYSÈE,

PROMENADE DES ANGLAIS.

Admirably Situated in a Vast Garden.

Splendid View of the Promenade and the Sea.

Reading, Ladies' Drawing, Billiard, and Smoking Rooms.

Full South. Arrangements made for a Protracted Stay.

N.B.—These three well-known First-Class Establishments are situated full South, and heated by "Calorifères." Bath Rooms on every Floor. Excellent Cuisine. Choice Wines. Moderate Charges.

J. LAVIT, Directeur-Gérant.

NUREMBERG.

HÔTEL DE BAVIÈRE.

PROPRIETRESS. MRS. G. P. AUINGER.

THIS First-Class Hotel is situated in the middle of the Town, close to the River. It is highly patronized by English and American Families. Every comfort and Moderate Charges. Hot and Cold Baths in the Hotel.

Omnibuses to and from each Train. Carriages in the Hotel.

ENGLISH CHURCH SERVICE HELD EVERY SUNDAY IN THE HOTEL.

ODESSA.

HÔTEL EUROPA.

OPPOSITE the Bourse, commanding a view on the Sea, on the Promenade, on the Sea Shores. Beautiful Rooms. Baths in the House. Omnibus on the arrival of all Trains. Restaurant à la Carte. German, French, English, and Russian spoken.

GOOD ATTENDANCE.

PRICES MODERATE.

F. H. KÖHL (a Swiss) Proprietor.

NICE.

HÔTEL DES PRINCES.
FIRST-CLASS Family Hotel,
situated on the Quat du Midi. Sheltered
stuation, with a line view of the Sea.
Charges Moderate. J. B. ISNARD.

OSTEND.

Murray's Handbook for Holland and Belgium. Map and Plans. Post 8vo. 6a

JOHN MURRAY, Albemarle Street.

OSTEND. MERTIAN'S

FAMILY HOTEL AND PENSION.

Olose to the Kursaal.

OSTEND.

GRAND HOTEL MARION.

FIRST-CLASS HOTEL, open all the year. Much frequented by English.

JOHN MARION & CO.

E 9

OXFORD.

RANDOLPH HOTEL.

THE ONLY MODERN HOTEL. FIRST-CLASS.

Every Comfort. Close to the Colleges. Prices Moderate.

MISS I'ANSON, Manageress.

FIELD PATHS AND GREEN LANES.

Being Country Walks, chiefly in Surrey and Sussex. Third Edition, with Illustrations from Sketches made on the Spot.

By LOUIS J. JENNINGS. Post 8vo. 10s. 6d.

JOHN MURRAY, ALBEMARLE STREET.

OXFORD.

OXFORD.

THE CLABENDON HOTEL. (Patronised by H.B.H. The Prince of Wales, H.R.H. Prince Leopold, Their Imperial Majesties the Emperor and Empress of Brazil, the Princess Frederick Charles of Prussia, and Prince Louis Lucien Bosaparte.) Situate in the most central part of the City, and near to the principal Colleges, and places of Therest to visitors. Families and Gentlemen will find this Hotel replete with every comfort. Sparious Coffee and Billiard Rooms. Private Sitting and Bed rooms en suits. Ladies' Coff. e Room. Guides always in att-undance. Fashionable Upen and Close Carriages. Job and Cost Herrest. Good Stabling and Commodious Coach Houses.—JOHN F. ATTWOOD, Proprietor.

PARIS.

HÔTEL MIRABEAU,

8. Rue de la Paix.

Patronised by the Royal Families of several Courts of Europe.

DEAUTIFULLY situated between the Place Vendome and D the New Opers, this Hotel possesses the prettlest Court-Yard in Paris. Table d'Hote at separate Tables. All languages spoken. Lift to each Floor. Arrangements made during the Winter.

PETIT (Uncle and Nephew), Proprietors.

PARIS.

HÔTEL DES DEUX MONDES ET D'ANGLETERRE.

22. AVENUE DE L'OPERA.

Founded in 1854, formerly 8, Rue d'Antin.

Mr. LEQUEU, Proprietor.

Splendid Situation between the Tuileries and the New Grand Opera.

The most comfortable Family Hotel, being built specially. Patronized by the English Aristocracy.

EXCELLENT TABLE D'HÔTE.

READING, SMOKING, AND BILLIARD ROOMS: BATHS.

LIFT. MODERATE CHARGES.

SPECIAL ARBANGEMENTS MADE

PARIS.

OPTICAL INSTRUMENTS.

THE Establishment of the late celebrated Civil Engineer, CHEVALLIER, 15, Place du Pont Neuf (Founded in 1740), Sole Sucoscsor DUCKAY CHEVALLIER, Manufacturer of Microscopes, of improved double Opera Glasses, Military Telescopes, Telescopes of all kinds, Mathematical, Meteorological Instruments for Natural Philosophy, the Navy, &c., Author of the "Conservateur de la vue" de "l'Essai sur l'art del'ingénieur." En Inventor of the Jumelles centrées (improved Opera Glasses). Patented Photo Field Glass.

FIRST-CLASS HOTEL.

FARIS.
MEURICE. HÔTEL

RUE DE RIVOLI.

PARIS.

TOBACCO IN PARIS.

W. D. & H. O. WILLS'

BEST BIRD'S-EYE TOBACCO

Is now (by the courtesy of the French Government) sold at the Bureau of the Régie, Grand Hotel, Boulevard des Capucines, Paris, at the rate of

12 Francs the Pound, in 8 oz. and 2 oz. Packets.

WILLS' "BEST BIRD'S-EYE,"

WILLS' "THREE CASTLES,"

AND

WILLS' "WESTWARD-HO,"

SMOKING MIXTURE,

(All specially prepared for export) may be obtained in Brussels, St. Petersburg, Berlin, Stockholm, Gothenburg, in most towns in Switzerland, and in the principal cities of the German Empire.

Purchasers should beware of imitations, and see that every packet bears the name of

W. D. & H. O. WILLS.

BRISTOL & LONDON.

PAU.

PAU.

A WINTER RESORT, renowned for the numerous essres which a residence has effected, particularly in cases of Affections of

the Chest, Heart, Larynx, and Throat.

PAU possesses a mild and salubrious climate, lying in the midst of scenery of great grandeur; on three days in each week Fox-hunting and Polo Matches take place, and during the winter and spring there are Horse Races twice every month.

In addition to these attractions, there are Good Clubs, a Theatre, Opera, two Casinos, Balls, Pigeon Shooting Matches, Cricket Matches, Skating

Rinks, &c., &c.

FIRST-CLASS HOTEL AND GOOD BOARDING HOUSES.

Villas, Houses, and Furnished Apartments to Let,

AT VARIOUS PRICES.

All particulars sent gratuitously, address Mr. FREDERIC DANIEL,

Directour Gérant de l'Union Syndicale, 7, Eus des Cordeliers, Pau.

PENZANCE.

QUEEN'S HOTEL.. (On the Esplanade,)
Patronised by Her Majesty the Queen of Holland:



TTHIS magnificent Hotel has a frontage of over 170 lest, all the Rooms of which overlook the Roa. It is the only Hotel that commands a full and uninterrupted view of Mount's Bay. Apartments or suite. Pensance stands univalled for the variety and quiet beauty of its sensery, whilst the midness of its climate is admirably adapted to invalide. Ladies' Coffee and Drawing Rooms. Billiard Room. Hot and Cold Maks. Table d'Hôte at 7 o'clock. An Omnibus meets every Train. Posting in all its Branches. Yachts, &c.

A. H. HORA, Proprietor.

PENZANCE.

MOUNTS BAY HOTEL, ESPLANADE.



MIS First-Class Hotel was built and furnished by the present owner nearly twenty your ago. It has Fifty-five Rooms, having an uninterrupted and unsurpassed View of St. Michael's Mount and all the Ray. It is heated in Winter with Hot Water. Porting in all its Branches. Choice Wines, &c. Table d'Hôte. Ladies' Drawing Room. Hot and Cold Eaths. Terms Moderate. Porter meets each Train.

Mrs. E. LAVIN, Proprietress.

Winter Resort.

PEGLI.

Sea Bathing.

GRAND HOTEL.

DISTANT FROM GENOA: AN HOUR BY TRAMWAY, AND THIRTY MINUTES BY RAILWAY.

SAME CLIMATE AS MENTONE AND SAN REMO. Stay of Their Imperial and Royal Highnesses the CROWN PRINCE and CROWN PRINCESS of Germany.

AGNIFICENT First-Class Establishment, of 100 Rooms, with Southern aspect, in the middle of a large Park and Garden of Exotic Plants. English Service in the Chapel, on the grounds of the Hotel. Resident English Physician. Warm Sea Water Baths. Splendid Bathing Establishment on the shore. Excellent place for Excursions, Sketching, and Botanising. First-rate Cooking. Very moderate prices.

LANDRY & BUCHEN, Proprieto t.

FOR TRAVELLERS AND SPORTSMEN.

Fifth Edition, with Woodcute, small 8vo.

THE ART OF TRAVEL; or, Hints on the Shifts and Contrivances available in Wild Countries. By FRANCIS GALTON, F.R.G.S., Author of "The Explorer in South Africa."

".... The soldier should be taught all such practical expedients and their philosophy, as laid down in Mr. GALTON'S USEFUL LITTLE BOOK."—Minute by the late Su JAMES OUTRAM.

"Mr. Galton publishes this little volume for the use of tourists who travel far and ' rough it.' It would also put some useful ideas into the heads of men who stay at home." - caminer.

" A handbook such as this might prove a friend in need even to an old traveller, while to a joung one who intends to venture beyond railways it must be invaluable."-Athenau...

JOHN MURRAY, ALBEMARLE STREET.

PISA.

HÔTEL ROYAL GRANDE BRETAGNE ET D'ANGLETERRE.

THE BEST HOTEL IN PISA (see Murray's Handbook of Central Italy), opposite the New Bridge, "Pont Solferino," leading direct to the Leaning Tower. Patronised by Henry Wadsworth Longfellow, Silvio Pellico, and Manimo d'Azeglio, whose recommen ation is written in the Visitors' Book of the Hotel.

Fifty years established, and known for its great comfort. Splendid Terrace, with view of the Surrounding Country and Cathedral. Full South on the Arno, with a nice Garden.

Next to the English Church.

CAPOCCHI ET MENESINI.

Special Terms at Moderate Prices for the Winter Season.

PISA.

ROYAL VICTORIA HOTEL.

Clean. Great attention. Recommended.

Messrs. MAQUAY HOOKER'S Banking Office is in the Hotel.

RAGATZ.

SCHWEIZERHOF HOTEL & PENSION.

BEST situation, next to the Baths, affords every convenience to English and American Travellers. English Papers. Garden. Moderate G JÄKLE, Proprietor.

PLYMOUTH.

THE ROYAL HOTEL.

FIRST-CLASS FAMILY AND POSTING HOUSE.

S. PEARSE, Proprietor.

PLYMOUTH .:

Only Hotel with Sea View.

GRAND HOTEL.

(ON THE HOE.)

Facing Sound, Breakwater, &c. Mail Steamers anchor in sight. Public Rooms, and Sitting Rooms, with Balconies.

JAMES BOHN, Proprietor.

PLYMOUTH.

MURRAY'S HANDBOOK FOR DEVON AND CORNWALL.

2 vols. Post 8vo.

JOHN MURRAY, ALBEMARLE STREET.

PLYMOUTH. DUKE OF CORNWALL HOTEL.



Railway Terminus -- Plymouth, Devon (Postai Telegraph Office). Oriental Steam Navigation C mpany's Office. First-Class Family Hotel. Table d'Hôte daily.

Apply to the Manager.

PRAGUE.

"ENGLISCHER HOF."

(HÔTEL D'ANGLETERRE.)

FIRST-CLASS. The next to the Vienna, Dreaden, and Karlsbad Station. Patronised by English and Americans. English, American, and French Papers. Reading Room. Ladies' Coffee Room. Excellent Board. Reasonable Charges.

GUSTAV HÜTTIG, Proprietor.

PRAGUE.

HÔTEL GOLDEN ANGEL.

Zûm Goldenen Engel. Hôtel de l'Ange D'Or. Zeltner Street, Old Town.

SITUATED at an easy distance from the Terminus of the Bailway to Dresden and Vienna, Post and Telegraph Offices, the Custom House, the Theatre, and other Public Buildings. English and French Newspapers. Cold and Warm Baths.

F. STICKEL. Proprietor.

RHEINFALL, NEUHAUSEN, SCHAFFHAUSEN,



HOTEL SCHWEIZERHOF. PROPRIETOR, MR. WEGENSTEIN.

THE HOTEL SCHWEIZERHOF, known to English visitors as one of the best Hotels in Switzerland, has been greatly enlarged, and is now a splendid first-rate establishment.

The SCHWEIZERHOF is situate opposite the celebrated Falls of the Rhine, and surrounded by a fine park and garden. The position is unsurpassed, the eye ranging a distance of above 180 miles—a panoramic view including the whole range of the Swiss Alps and the Mont Blanc. Healthy climats. Church Service. Preserved Trout Flahing. Prices moderate. Pension. Hotel Omnibuses at Menhausen and Schaffhausen.

RIGI.

HOTEL AND PENSION RIGHT-SCHEIDECK.

Terminus Station of the Rigi Kaltbad-Scheideck Railway.

Excellently suited for Tourists and Pensioners. View on the Alps as beautiful as at Rigi-Kulm.

MODERATE CHARGES.

LIBERAL TREATMENT.

By a stay of not less than four days, arrangement by pension can be made at 8 to 12 francs per day per person. For further information apply to the

Proprietors, HAUSER & STIERLIN.

N.B.—Tourists having Tikets from Vitznau to Bigi-Kulm can interrupt the journey at Rigi Kaltbad, take advantage of the beautiful Excursion to Scheideck and back, and then continue the journey to Kulm by a following Train.

RIGI-KALTBAD.

A LPINE CLIMATE. 1500 metres above the sea. Opened from June to October. First-Class Hotel, with 300 Rooms comfortably furnished. Finest situation. The only Establishment on the Rigi sheltered from the cold winds. Large Park and Gardens, Terrases, Verandaha, especially for the use of Visitors. Level Walks and facilities for Excursions.

Railway Station. Post and Telegraph Office. Physician. Baths. Divine Service. Good

Orchestral Band.

NEWSPAPERS, BILLIARDS, &c., IN THE HOUSE.

Pension Arrangements.

Further information will be given by

X. SEGESSER FAADEU, Proprietor.

ROME.

HÔTEL MINERVA.

THIS large Establishment, whose direction has lately been taken up again by the Proprietor, M. Joseph Sauve, has been considerably ameliorated both as regards the perfect service and the most elaborate comfort. Large Apartments as well as small, and Rooms for Parties with more modest tastes, both very carefully furnished, are to be found here.

Its position is one of the most advantageous. It is situated in the very centre of the Town, and close to the most remarkable Monuments. the Post and Telegraph Offices, the House of Parliament, and the Senate.

The Ladies' Drawing Room, the Smoking Room, and Reading Rooms, where the principal Newspapers of every country are to be found, and the Bathing Rooms, are always carefully warmed.

TWO OMNIBUSES BELONGING TO THE HOTEL MEET EVERY TRAIN.

THE WAITERS AND CHAMBERMAIDS SPEAK ALL THE PRINCIPAL LANGUAGES.

VERY MODERATE TERMS.

ROME.

CONTINENTAL HÔTEL

ONE OF THE LARGEST AND MOST COMFORTABLE HOTELS IN ITALY.

Facing the Railw y Station, in the most elevated part of the Town, and the nearest to all the Antiquities and Attractions.

PROPRIETOR OF THE WELL-KNOWN
HÔTEL D'ALLEMAGNE.

SITUATED IN THE CENTRE OF THE CITY OF ROME.

HEATED WITH HOT-AIR STOVES.

ELEVATOR WITH SAFETY BRAKE.

P. L. LUGANI, Proprietor.

ROME.

GRAND HOTEL DE RUSSIE, ET DES ILES BRITANNIQUES.
This First-Clara Establishment possesses the advantage of a beautiful Garden, and is situated near the English and American Churches; the principal Apartments face the South, the entire Hotel being warmed by two calorifères, and the whole arrangements and moderate prices give universal satisfaction.

MAZZERI, Proprietor.

ROME.

HÔTEL ANGLO-AMERICAIN, Via Frattina, 128. Between the Corso and Plazza d'Spagna. The nearest Hotel to the Post and Telegraph Offices. Situated full South, in the most healthy part of the Town. Large and small Apartments. Table d'Hôte. Restaurant. Salon. Residing Room, with Newspapers in four languages. Smoking and Billiard Room. Bath Room. Pension, and arrangements for Families. Moderate Charges. Omnibus at the Station to meet every Train. The principal languages are spoken.

VISCIOTTI & MERLI, Proprietors.

ROTTERDAM.

H. A. KRAMERS & SON, IMPORTARS OF FOREIGN BOOKS.

Mr. MURRAY'S 'Handbooks for Travellers,' Branchaw's Monthly Railway Guides, BARDERRS'S 'Reisehandbücher,' and HENDGORRL'S 'Telegraph,' always in Stock. Books in all Languages imported every day, and a great variety of New Books kept in Store.

26. GELDERSCHE KADE, 26.

ROUEN.

CRAND HÔTEL DE FRANCE, 97-99, Rue des Carmes. Entirely and carefully reorganised by the new Proprietor. This First-Class Hotel is now a curiosity more in the Town, and situated in central position near the Public Bullding and Theatres, specially recommended to Families visiting the Normandy Coasts. Large Courtyard and Garden, where Breakfast, Luncheons, and Dinners are served in the Summer. Ladies' Room, Smoking Room, Table d'hôte at 6 o'clock. First-Class Restaurant.

E. BARBIER, Proprietor.

ROUEN.

GRAND HÔTEL DE PARIS. FIRST-CLASS HÔTEL

SPLENDIDLY SITUATED ON

THE QUAI DE PARIS,

VIEWS OF THE SEINE AND MOUNTAINS

SPECIALLY RECOMMENDED TO

FAMILIES AND SINGLE TRAVELLERS.

Conversation Saloon.

Smoking Room.

MODERATE PRICES.

TABLE D'HÔTE.

SERVICE À LÀ CARTE RECOMMENDED.

GUÉNARD BATAILLARD, Proprietor.

ROUEN.

GRAND HÔTEL D'ANGLETERRE (On the Ousy).

Mr. AUGUSTE MONNIER, Proprietor, Successor of Mr. LEON SOUCHARD.

THIS HOTEL is distinguished for the salubrity of its situation, &c.; and the new Proprietor has entirely re-fitted it, and added a very comfortable Smoking-Room. It is situated on the Quay facing the Bridges, and commands the finest view of the Seine, and the magnificent Scenery encircling Rouen, that it is possible to imagine. Travellers will find at this first-rate ketablishment every comfort—siry Rooms, good Beds, Refreshment and Wines of the best quality at moderate Prices. An excellent Table d'Hôte at Six o'clock. Restaurant à la carte.

Mr. Monnier speaks English, and has English Servants.

An excellent Descriptive Guide of Rouen can be had of Mr. MONEYER.

ROYAT-LES-BAINS.

HOTEL. GRAND

L. SERVANT, Proprietor.

FIRST-CLASS HOUSE. ENGLISH SPOKEN.

Opened from the First of May till the end of October.

SALISBURY.

THE WHITE HART HOTEL. Nearly Opposite the Cathedral. The largest And principal Hotel in the City.—This iod-entails between Hotel contains every accommode Families and Tourists. A Ladies' Coffee Room, Billiard and Smalting Rooms, and spacings Orders Edwinders. Table d'Hôte deily during the season from 6 to 8.00 p.m. at reglisate failuis. Cardin Brome on hits for Boussburgs and other places of interest, Escalines Stabling, Loos Ence, Sc. 1 application to H. T. BOWES, MANAGER, Postiniz Master to Her Majesty.

SALZBURG.

HÖTEL DE L'EUROPE.

PPOSITE the Station. First-Class Hotel, surrounded by a large Park, and offering the best view on the Mountains.

PENSION.

Moderate Charges.

G. JUNG, Proprietor.

SAN SEBASTIAN. HOTEL INGLES Y DE INGLATERRA.

Facing the Sea.

English Spoken. English Papers.

SAN SEBASTIAN.

Murray's Handbook for Spain. -

Maps and Plans. Post 8vo.

JOHN MURRAY, Albemarle Street.

SAN REMO, ITALY.

WEST-END HOTEL.

A LARGE Building, expressly built for an Hotel, with all the latest appliances to insure perfection in sanitary arrangements—its Closets being on the most approved English principle. Beautifully situated at the West End of the Town, a good distance from the Sea, commanding an extensive View of the Bay.

LIFT. READING, BILLIARD, and SMOKING SALOONS.

LADIES' DRAWING ROOM.

ENGLISH AND FOREIGN NEWSPAPERS.

Excellent Cuisine and Choice Wines.

GREAT CLEANLINESS

Omnibus of the Hotel meets all Trains.

Special arrangements for a lengthened sojourn.

ONLY HOUSE WITH LIFT.
All Languages spoken.

Proprietor, ROBERT WULFING.

SCHWALBACH.

THE DUKE OF NASSAU HOTEL.

This First-Class Hotel, with private Hotel adjoining, is beautifully situated in the healthest and best part of the town, facing the Public Promenades, and in close proxin-lity to the Royal Bahs, the New Curhouse, the Drinking Hail, and the English Church. It contains a good number of eleganity-turnished apartments and Salcons for families and single gentlemen, and combines comfort with Moderate Charges. This Hotel is patronized by many disting-isbed families of England and the Continent. Favourable "Pension" arrangements are made at the end of the Season. A comfortable Omnibus belonging to the Hotel starts from Schwalbach to Wiesbaden at eight o'clock in the morning, and leaves Wiesbaden at five o'clock in the afternoon, opposite the Hailway Station, from the Taunus Hotel. Café Restaurant, Paulinenberg, Whey and Milk Establishment, ten minutes' walk from the Nassau Hotel, with which there is communication by Telephone, delightfully situated, amidst a beautiful park with splendid view.

J. C. WILHELMY, Proprietor.

SCHWALBACH.

HÔTEL ALLÉE-SAAL

(HOTEL DE LA PROMENADE.) Dépendance: VILLA GREBERT.

TIRST-CLASS HOTEL. Under the Patronage of T.R.H. the Prince and Princes of Wales. FERD. GREBERT, SONS, Proprietors.

SHANKLIN, ISLE OF WIGHT. Shanklin for Sunshine.

II INTON'S ROYAL SPA HOTEL. Facing the Sea and under the Cliffs in the Isle of Of Wight, a Sheltered and Sequestered nook. Drawing-room, Conservatory, Flowers and Birds. Table-d'hôte at ?, separate Tables; 50 Bed and Sitting Rooms; Billiards and Lawn Tennis free of charge, and constant amusements. Tarifi, on application, for Families residing in the Hotel. Pension, 23 3s. per week in winter; 23 13s. 6d in Summer.

SEVILLE.

GRAND HÔTEL DE MADRID.

LIRST-CLASS Family Hotel, the largest in Seville. Well situated. Apartments for Families. Table d'Hôte. Reading and Smoking Rooms. Foreign Newspapers. Baths, Tropical Gardens, Carriages, Interpreters. Arrangements for Winter.

Moderate Prices.

JULIO MEAZZA, Manager.

SPA.

GRAND HÔTEL BRITANNIQUE.

F. LEYH, Proprietor.

PATRONISED BY THE ROYAL FAMILY OF BELGIUM,

And maintains a high reputation among the Aristocracy of Europe.

SITUATED IN THE HEALTHIEST PART OF THE TOWN.

LARGE GARDEN AND SWIMMING BATHS.

Adjoining the Boulevard des Anglais and the English Church.

ENGLISH SPOKEN.

OMNIBUS AT EACH ARRIVAL.

SPA.

HÔTEL DES PAYS-BAS.

Vve. I. DE COCK, Proprietress.

FIRST-CLASS. Exceptional situation at the top of the Town. Large Garden opposite the Pouhon, close to the Casino and Baths. Omnibus at the Staths. Much recommended.


SPA.

GRAND HÔTEL DE L'EUROPE.

TIRST-CLASS HOTEL. Splendid Situation. Fine Apartments. Drawing and Reading Room. Every Comfort. Spacious and handsome alterations have been lately made.

Countless of the Hotel at the Arrival of every Train.

STOCKHOLM, SWEDEN.



GRAND HÔTEL.

THIS Handsome Building is situated in the finest part of the City, between Charles the XHth's Square and the National Museum, on one of the Principal Quays, just at the confluence of the Lake Mälar and the Baltic.

The Boyal Palace, one of the stateliest in Europe, faces the Hatel on the opposite side of the Harbour. The Royal Opera and the Principal Theatres are in close proximity.

The belconies and roof of the Hotel command the most extensive Views

of the City.

The House is replete with every modern improvement and convenience, and no expense has been spared to render it one of the first and most confortable Motels on the Continent.

The Building contains Four Hundred Sleeping Apartments, besides Dining Rooms, Sitting Rooms, Coffee and Reading Rooms, a Billiard Room, a Telegraph and Post Office, Baths, Retiring Rooms, a Laundry, and other accommodations. The several flats can be reached by Steam Lifts.

All Hunepean Languages spoken. Guides and Conveyances supplied to all places of interest in the City and Neighbourhood. Terms will be found

to compare favourably with those of other first-class Hotels.

The Hôtel Rydberg.

GUSTAF ADOLF'S TORG.

THIS Old-established House has long been favourably known to Travellers. It contains One Hundred and Fifty Sleeping Apartments.

The Proprieter of these Two First-Class Hotels is in a position to offer every advantage to strangers visiting the Swedish Capital.

R. CADIER.

Proprietor of the Grand Hôtel and the Hôtel Rydberg.

SCHWALBACH.

Métropole Dépendance Hotel Villa Métropole.

First-Class Hotel. Fine situation. In the most airy and healthiest part.

G. HERBSTER, Proprietor.

SHEFFIELD.

MIDI.AND STATION HOTEL.

A First-Class Hotel, within one minute's walk of the Station. Telephone, Hutel Porters attend the Trains.

GEORGE WOOD, Proprietor.

SOUTHPORT.

ROYAL HOTEL.

(ON THE PROMENADE.)

Facing the Sea. Adjoining the Winter Gardens. Charges Moderate. Boarding Terms, Three Guineas per Week. J. C. SEIDENSTRICKER, Proprietor.

STRASBURG.

HÔTEL D'ANGLETERRE.

NEWLY RESTORED, and Furnished with every modern comfort by its new Proprietor, CH. MATHIS. Opposite the Railway Station. Adjoining the Post and Telegraph Office. Near the Cathedral.

Large Dining, Reading, and Smoking Rooms.

80 Sitting and Bed Rooms.

E STUTTGART.

HÔTEL MARQUARDT

IS situated in the finest part of the Town, in the beautiful Place Royal, Is situated in the linest part of the Lowi, in the destining risco boyst,

near the Railway Station, the Pest Office, the Theatre, the Royal Gardens, opposite the
Palace, and facing the new Odeon. This Hotel will be found most comfortable in every
respect; the Apartments are elegantly furnished, and suitable for Families or Single
Geutlemen. Table d'Hôte at 1 and 5 o'clock. French and English Newspapers.

GME. MARQUARDT, Proprietor.

THUN (Switzerland).

GRAND HOTEL DE THOUNE

(THUNERHOF).

Proprietor, Ch. STARHLE, formerly Manager at the Hôtel Bauer au Lac, Zurich.

FIRST-CLASS HOTEL, the largest and most comfortable in the place, beentifully situated at the Lake, with a splendid view of the Aips, and surrounded by a large Garden. A Terrace found the whole length of the House; no equal in Switzerland. There is also a Lift.

PRICES ARE FIXED UP IN EACH ROOM.

Pension, the whole Season by staying Five Days.

THUN, SWITZERLAND. FALCON HOTEL.

CENTRAL ON THE AAR.

GOOD SITUATION. COMMERCIAL AND FAMILY HOTEL. OPEN ALL THE YEAR.

TOURS. HÔTEL DE L'UNIVERS.

Pleasantly Situated. Has a Europes Reputation.

> Specially arranged for Families. ENGLISH SPORES.

TOTNES.

THE SEYMOUR FAMILY HOTEL, on the banks of the DART, TOTNES. Patronised by B.B.H. the Prince of Wales. Tourists and Families visiting the unrivalled accessy of the Biver Davi and South Devon, will find the above Hotel most convenient. The Hotel is formissed with every requisite, seen room commanding an extensive and beautifully varied landecape. The return of Totnes. Berry Fromeroy, and Compton Castles, are within eavy distance. Hotel cases, the formed Succitand Drives, Ray Tor and Davinsow, which posting distance. Force van be hered from the Hotel Cases Steps. Bunding and Fishing in the faminediate Seigh, Bunding and Fishing in the faminediate Seigh, Bunding and Fishing in the faminediate Seigh Bunding and Fishing in the faminediate Seigh Bunding and Fishing in the faminediate Seighbourhood.

Post Horses and Carriages.

G. & F. MITCHELL, Proprietors,

TOULOUSE.

Patronised by the Duke of Norfolk and Duc d'Aumale. BEAUTIFULLY SITUATED ON THE PLACE DU CAPITOLE.

FIRST-CLASS ESTABLISHMENT.

Offering the same comforts as the largest Hotels in France. Frequented by the highest Class of English and American Travellers.

English spoken. Restaurant and Table d'Hôte. Rich Reading Room and Conversation Salon.

EUG. POURQUIER, Proprietor.

TOULOUSE.

GRAND HÔTEL SOUVILLE (Place du Capitole).

LEPT by M. DARDIGNAC, Restaurateur. A First-class House, one of the best-situated in the Town, close to the Grand Theatre, Post and Telegraph Office. Is to be recommended from its good Attendance. Most comfortable Apartments, Salons, and Bedrooms. Restaurant at fixed-Prices, or & accept. Private Service for Families. Baths and Private Carriages in the Hotel. Carriages and Omnibus enter the Courtyard of the Hotel.

TURIN.

EL DE L'EUROPE. GRAND HOT

PROPRIETORS-

Messrs. BORGO and GAGLIARDI.

Situated Place de Château, opposite the King's Palace.

(Five minutes from the Railway Station.)

THIS unrivalled and admirably-conducted Hotel recommends itself to the notice of English travellers.

EXCELLENT TABLE D'HÔTE AT 6 O'CLOCK.

BATHS IN THE HOTEL.

Interpreters speaking all the European Languages.

Charges Moderate. The Times Newspaper. An Omnibus from the Hotel will be found at every Train.

TURIN.

GRAND HÔTEL LIGURIE,

Bodoni Square, and Andrea Doria and Charles Albert Streets.

MAGNIFICENT, very good and comfortable. Removed to a large and sumptuous Palace, expressly built. First-Class Family Hotel. The only one of Turin isolated in a large beautiful square, splendidly exposed to the south. Highly patronised by the best English and American Families.

ALBINO GUIDI, Proprietor.

VARESE. (Lombardy.)

GRAND HÔTEL VARESE.

In direct communication by Rail with

MILAN, LAKE MAGGIORE, COMO, and LUGANO.

PIRST-CLASS HOTEL, surrounded with an extensive GARDEN and PARK, situated in the best and healthiest part of Lombardy, 1319 feet above the Sea, commanding a most extensive view of the Alps, Monte Ross Chains, and containing

PENSION. Baths on each floor. English Church. English Physician attached to the Hotel.

E. MARINI, Manager.

VENICE.

GRAND HOTEL D'ITALIE, BAUER TRÜNWALD.

PIRST-CLASS HOTEL, near St. Mark's Square, on the Grand Canal, facing the Church of St. Maria della Salute. Fresh and Salt Water Baths ready at all hours.

Colditated for its " Grand Restaurant" and Vienna Bear.

INLES TRUMWALD, Proprietor.

VENICE.

GRAND HÔTEL DE L'EUROPE.

OLD-ESTABLISHED FIRST-CLASS HOTEL, situated on the Grand Canal. Large and small Apartments for Families and Gentlemen. Visitors will find this Hotel very comfortable, well-situated. and reasonable in its Charges.

MARSEILLE BROS Proprietors.

VERONA.

GRAND HOTEL DE LONDRES.

FORMERLY HOTEL DE LA TOUR DE LONDRES. A. CERESA, New Proprietor.
THER largest and finest Hotel in Verona, near the Roman Amphitheatre. English Church Services in the
Zetti. Sett contral position. Great comfort. All Languages spoken. Omnibus to and fives the
Stations. Highly recommended.

G. CAVESTRI, Manager.

· VIENNA.

GRAND HÔTEL.

KÄRNTHNERRING No. 9,

SITUATED on the most elegant and frequented Square of the City. Three hundred Rooms, from 1 florin upwards. Apartments, from 6 florins upwards. Beautiful Dining Saloon, Restaurant Saloons, Conversation, Smoking, and Reading Rooms.

BATHS & TELEGRAPH OFFICE IN THE HOUSE.

Lifts for Communication with each Storey.

DINNERS & SUPPERS À LA CARTE. TABLE D'HÔTE.

OMNIBUSES AT THE RAILWAY STATIONS.

VIENNA.

J. & L. LOBMEYR,

GLASS MANUFACTURERS,

Appointed Purveyors to the Imperial Court of Austria, No. 13, KÄRNTHNERSTRASSE.

The most extensive Establishment for Bohemian Crystal, Fancy Glass, and Chandeliers.

Every variety of Glass for Household use, Ornament, and in Art Workmanship Specialities in Engraved Glass and Looking-Glasses. Chandeliers, Candelabras, in Orystal and Bronze.

LARGE SHOW-ROOMS UPSTAIRS.

The prices are fixed, and are very moderate.—English is spoken.

Their Correspondents in England, Messrs. J. & R. M'CRACKEN, No. 38, Queen Street, Cannon Street, E.C., London, will transmit all orders with the greatest care and attention.

VEVEY.

HÔTEL MONNET AND TROIS COURONNES.

F. SCHOTT.

GRAND HÔTEL DE VEVEY,

THESE two First-Class Houses are beautifully situated on the Lake of Geneva, with a magnificent view from the Gardens in front of the Hotel.

GREAT COMFORT AND CLEANLINESS.

ARRANGEMENTS MADE DURING THE WINTER

"EN PENSION."

VICHY.

GRAND HÔTEL DU PARC.

THE LARGEST AND MOST COMFORTABLE IN VICHY.

A FIRST-CLASS HOTEL, situated in the Park, facing the Baths, Springs, and Casino.

PRIVATE PAVILION FOR FAMILIES.

GERMOT, Proprietor.

VIENNA.

HÔTEL DE LA COUR D'AUTRICHE.

TIRST-CLASS Hotel. Moderate Charges.

Bath. English Newspapers. English

J. HANISCH, Proprietor.

VIENNA.

Murray's Handbook for

South Germany.
Post 8vo. 10s.

JOHN MURRAY, Albemarle Street.

WIESBADEN.—ROSE HOTEL AND BATH HOUSE.

QPLENDID First-Class Establishment close to the Cursaal, opposite the

Trinkballe, and adjoining the Promenade. No other Hotel except this is surrounded by a Garden of its own, or supplied with Baths direct from the hot springs (Kochbrunnen). Quiet and airy situation, with English comfort and reasonable Charges. Drawing, Reading, and Smoking Rossns, and Silliard Rosm, containing a full-sized Billiard Table. 'Table d'Hôte at One and Five o'clock.

HAEFFNER FRERES, Proprietors.

VICHY.

View of the Grand Hotel des Ambassadeurs at Vichy-les-Rains.



CRAND HOTEL DES AMBASSADEURS, Situated on the Park.—
This magnificent Hotel is now one of the first in the town. It is managed in the same style as the largest and best hotels on the Continent. By its exceptional situation, the hones presents from the first which the most beautiful visys are to be had; and from its halconies is heard the excellent Band of the Casino. The Betel consistes \$50 Recome, 30 Reloses, a falcon for Banquets, expable of holding 600 persons, and a large and fine Dining Room, 200 Covers, a Smoking Room, and 3 Billiard Tables. Restaurant et service à la Carte. Large and small apartments for families. Raglish spoken. The Omnibus of the Hotel awaits all the Trains at the Station.

ROUBEAU-PLACE, Proprietor.

WIESBADEN.

HÔTEL ET BAINS DE NASSAU.

Messrs. GOETZ BROTHERS, Proprietors,

FIBST-CLASS HOTEL of old and good reputation, opposite the Curbaua, Colonnades, Paras, and next the Theatre. Splendid Dining and Reading Rooms. Table d'Hôte at One and Five o'clock. Mineral Baths of Own Hot Spring.

HÔTEL VILLA NASSAU.

Annexe of the HOTEL DE NASSAU. Proprietors also Messrs. Goetz Brothers.

FINEST FAMILY HOTEL in Town, with all Modern Comfort, in beautiful situation next the Hot Springs, Theatre, Curhaus, Colonnades, etc.

WIESBADEN.

GRAND HÔTEL DU RHIN AND BATH.

FIRST-CLASS New House, exceedingly well situated, just opposite the Railway Station, the Post and Telegraphic direction, on the Promenades, combining comfort with Moderate Charges. Music and Reading Saloons. Rooms from 2 mks. 50 pf. per day, inclusive of Candles and Service. In Winter the whole Building and Winter Gardens are well warmed. The Omnibus for Schwalbach and Schlangenbed starts from near the Hotel.

Large stock of the best Rhine and Moselle Wines for wholesale.

Railway Tickets for all the Towns on the Continent are issued in the Hotel.

W. ZAIR

WIESBADEN.

Proprietor.

"FOUR SEASONS" (Vier Jahreszeiten) HOTEL

THIS First-Class House enjoys the finest position in the Great Square, facing the Kursaal, the Park, and being close to the Springs. Numerous Salcons with Balconies and comfortable sleeping Rooms. Fine Uning and Assembly Rooms. Large Mineral Bathing Establishment. Charges Moderate.

WIESBADEN.

HÔTEL VICTORIA AND BATH.

TIRST-CLASS HOTKL, with real English sumfort, situate opposite the Rallway and the T Promensele; sphendidly fitted up for Vagour, Russian, and all Medical Baths; own Spring. Magnificently Furnished Apartments. Moderate Charges. Good Attendance. Petision: Rosum from 2 marts and upwards.

WILDRAD.

HÔTEL KLUMPP,

Formerly HOTEL DE L'OURS.

Mr. W. KLUMPP, PROPRIETOR.

"NHIS First-Class Hotel, containing 45 Saloons and 285 Bed Rooms, with a separate Breakfast and new Reading and Conversation Rooms, as well as a Smoking Saloon, and a very extensive and elegant Dining Room; an artificial Garden ever the river; is beautifully situated in connection with the old and new Bath Buildings and Conversation House, and in the immediate vicinity of the Promenade and the New Colonnade. It is celebrated for its elegant and comfortable spartments, good Chaine and Cellar, and deserves its wide-spread reputation as an excellent Hetel. Table d'Hôte at One and Five o'clock. Breakfasts and Suppers à la carte. Exchange Office. Correspondent of the principal Banking-houses of London for the payment of Circular Notes and Letters of Credit. Omnibuses of the Hotel to and from each Train. Elevators to every floor. Fine Private Carriages when requested. Warm and Cold Baths in the Hotel.

EXCELLENT ACCOMMODATION.

WURZBURG.

HÔTEL. KRONPRINZ

DONOURED by the presence of His Imperial Majesty the Emperor of Germany, on the occasion of his recent visit to this Town. This First-Class Hotel is particularly recommended for its Large and Airy Amstructs, having the florest situation near the Station, facing the Palace, and adjoining a fine Garden. Reading Moona. Cold and Warm Baths, &c. Moderate Charges. No extra charges for Service and Camélies.

J. AMMON.

ZARAGOZA, SPAIN.

Grand Hôtel de l'Europe. Exalient Cooking and Moderate

Charges. VIUDA DE ZUPPETTI Y HIJOS

Preprietora.

SPAIN.

Duncan's English in Spain: or, The Story of the War of Succession, 1834 and 1846. Commiled from the Boports of the British Commissioners. With lilustrations. 8vo. 16s.

JOHN MURRAY, Albemarie Street.

· ZURICH.

Railway Station. HÔTEL HABIS, Railway Station,

MOST Comfortable. 50 Rooms, with 80 Beds. Winter Garden. Telephone. Moderate Prices.

Tourists are hereby invited on their arrival at the Station to ask for the Hall Porter to attend to their Luggage.

ED. HABISREUTINGER, Proprietor.

ZURICH.

WANNER'S HOTEL GARNI, on the Railway Terminus, Bahnhofstrasse. The most beautiful and open situation in the Town. Rooms, beautifully furnished, from frs. 1'50 to frs. 2'50. Apartments for Families. The comforts as in a First-Class Hotel.

Restaurant on Ground Floor. Garman Beer on draught. Pester at the Station.

H. WATER, Proprietor.

EVERY TRAVELLER'S COMPANION.

Sixteenth Edition. Fcap. 3s. 6d.

MURRAY'S

HANDBOOK OF TRAVEL TALK.

DIALOGUES - QUESTIONS - VOCABULARIES.

IN ENGLISH, GERMAN, FRENCH, AND ITALIAN.

Prepared expressly for English Travellers Abroad, and Foreigners Weiting England.

A NEW EDITION, THOROUGHLY REVISED.

The "Handbook of Travel Talk" is not a reprint of old manuals of conversation "drawn up towards the end of the last century," but a modern traveller's phrase book, compiled expressly to meet the wants of the present day. Ample space is given to such matters as Railway (Taking Tickets—In the Train—The Station, &c.), Post Office, Telegraph, Luggage Office, and to the multitude of technical words and phrases which the progress of modern travel has developed.

During the Fifteen Editions which it has passed through, it has undergone constant improvement; the consequence is, that it contains many words of modern invention not to be found in dictionaries.

"The appearance of a new and carefully revised edition of Mr. Murray's excellent 'Handbook of Travel Talk' is one of many severe aymptoms of the return of the Tourist Season.

"The compilers of the 'Handbook of Traval Talk' appear to have kept steadily in view the actual needs of travellers; for it is absurd to put a manual of polite conversation on literature, art, science, philosophy, and the musical glasses into the hands of an honest but uncultivated tourist, who can only ejaculate his simple wants in inarticulate theory."—Saturday Review.

JOHN MURRAY, ALBEMARLE STREET.

Switzerland.)

ZURICH. (Switzerland.)



URICH is the Central Point of Eastern Switzerland for Traffic, Commerce, Industry, and for its Social Life.

Most beautifully situated on the Lake and the River Limmat, with extended Panorama of the Alps from the Uetliberg Railway, the Zurichberg and the "Waid." Celebrated Town Library. Scientific Collections in the Polytechnic.

University, Observatory. Well-known Reading-Boom in the

Museum. Summer Theatre. Daily Concerts in the Concert Hall.

HÔTELS. Central Part of Town.

· Fam BRUKKER.

On the Lake and in the Vicinity. Baur au Lac. TH. BAUR. Baur en Ville. Bellevue au Lac. POEL

Du Lac, MOOSER.

Zurcherhof, Laxe. Falken, WESS.

Kreuz, Seefeld, MEYER.

Schweizerhof, MEISTER. Hecht, WALDMEIRR-BOLLER. Schwanen, BRUNGGER.

Rothhaus, BRUNNER. Schiff, SCHATTI.

Near the Bailway Station. National, MICHEL

St. Gotthard, Zolliker. Wanner's Garni, WARRER.

Limmathof, Purrer.

Sieberz STEBERS.

Boarding Houses and Curative Establishments:-

HOTEL and PENSION "UETLIBERG," on the Uetliberg, J. BOLLER and SONS.

HOTEL and PENSION SCHWANEN, on the Muhlebach, J. BOLLER and Sons.

PENSION NEPTUN, Seefeld. VVE. METTLER.

Gastwirth-Verein-Societé des Hôteliers - United Hotel-keeper's Society.

HOW TO LEARN MODERN LANGUAGES.

The success attending Dr. WM. SMITH'S "PRINCIPIA LATINA" and "INITIA GRECA," which practical teachers have found the easiest books for learning Latin and Greek, has led to the application of the same method to the French, German, and Italian Languages. There is an obvious advantage in a beginner learning a new language on the plan with which he is already familiar. These books combine the advantage of the older and more modern methods of instruction.

FRENCH COURSE.

Edited by Dr. WM. SMITH.

- FRENCH PRINCIPIA, Part I. A First French Course, containing Grammar, Delectus, Exercises, Vocabularies, &c. 12mo. 31, 64,
- APPENDIX TO FRENCH PRINCIPIA, Part I.
 Containing Additional Exercises, with Examination Papers. 12mo. 24.64.
- FRENCH PRINCIPIA, Part II. A Reading Book, containing Fables, Stories, and Anecdotes, Natural History, and Scenes from the History of France. With Grammatical Questions, Notes, and Copioss Etymological Dictionary. 120m. 44.
- THE STUDENT'S FRENCH GRAMMAR: a Practical and Historical Grammar of the French Language. By C. HERON-WALL. With Introduction by M. Littré, Post 8vo. 7s. 6d.
- A SMALLER GRAMMAR OF THE FRENCH LANGUAGE Abridged from the above. 12mo. Sa 6d.

GERMAN COURSE.

Edited by Dr. Wm. SMITH.

- GERMAN PRINCIPIA, Part I. A First German Course, containing a Grammar, Delectus, Exercises, Vocabularies, &c. 12mo. 3s.6d.
- GEBMAN PRINCIPIA, Part II. A Reading Book, containing Fables, Stories, and Anecdotes, Natural History, and Scenes from the History of Germany. With Grammatical Questions, Notes, and Dictionary. 12mo. 3s. 6d.
- PRACTICAL GERMAN GRAMMAR. With a Sketch of the Historical Development of the Language and its Principal Dislocts. Post 8vo. 3s. 6d.

ITALIAN COURSE.

Belited by Dr. Wm. Shirts.

- ITALIAN PRINCIPIA, Part I. A First Italian Course, containing a Grammar, Delectus, Exercise Book, with Vocabularies, and Materials for Italian Conversation. By Signor RECO. 12mo. 32. 6d.
- ITALIAN PRINCIPIA, Part II. A First Italian Reading Book, containing Fables, Ancodotes, History, and Passages from the best Italian Authors, with Grammatical Questions, Notes, and a copious Etymological Dictionary. 12mo. 3s. 6d.

JOHN MURRAY, ALBEMARLE STREET.

ESTABLISHED 1882.


THE ORIGINAL QUIDE & TRAVELLERS' DEPÔT.

Passport and Couriers' Agency,

LEE & CARTER,

440, WEST STRAND, LONDON
(Nearly opposite the Charing Cross Hotel).







KNAPSAGKS

PORTMANTEAUX

BAGS OF ALL KINDS.

Intending Tourists are respectfully invited to visit this Establishmen before making purchases for their journey.

AN EXTENSIVE STOCK OF TRAVELLERS REQUISITES TO SELECT FROM.

LISTS GRATIS.

COURIERS, DRAGOMEN,

ANI

TRAVELLING SERVANTS

of good character and experience, speaking European and Eastern Languages, can be engaged at the above Establishment.

Also Passports and Visas obtained. Passports mounted on Linen and put in Genes, with Name printed outside.

440, WEST STRAND.



•		
	!	





